



## Overview

This report is proposing an upgrade to the existing public toilets at Maherabeg beach.

The P.E. has been advised to us as 30.

In this proposal the local authority is proposing to upgrade and improve the on-site system.

The amenity is currently served by an old style septic tank and soak-pit.

This system should be replaced and improved. The E.P.A advice allows existing systems to upgrade and improve unsuitable systems with results outside the conditions set out for new amenities.

It would be in the best interest of all parties, their neighbor's and the local authority to improve the in-situ system.

Please find attached the S.C.R. form and supporting paperwork with drawings to apply for the upgrade of the in situ septic tank system.

# APPENDIX A: SITE CHARACTERISATION FORM

1

File Reference:

## 1.0 GENERAL DETAILS (From planning application)

Prefix:  First Name:  Surname:

Address:   
Site Location and Townland:

Number of Bedrooms:  Maximum Number of Residents:

Comments on population equivalent **As per loading information supplied by the client & their agent.**

Proposed Water Supply:  
Mains  Private Well/Borehole  Group Well/Borehole

## 2.0 GENERAL DETAILS (From planning application)

Soil Type, (Specify Type):

Subsoil, (Specify Type):

Bedrock Type:

Aquifer Category: Regionally Important  Locally Important  Poor

Vulnerability: Extreme  High  Moderate  Low

Groundwater Body:  Status:

Name of Public/Group Scheme Water Supply within 1 km:

~~Source Protection Area: ZOC  SI  SO~~  Groundwater Protection Response:

Presence of Significant Sites (Archaeological, Natural & Historical):

Past experience in the area:   
Comments:

(Integrate the information above in order to comment on: the potential suitability of the site, potential targets at risk, and/or any potential site restrictions).

Note: Only information available at the desk study stage should be used in this section.

## System Loading Sheet

### Maherabeg Beach

Load information for toilet and shower block supplied by M.W.P      Total Hydraulic Load  
3,480 Litres

Total      3480 litres

**3480 litres      divided by 150 litres (load per person) = 23.2 P.E. Say (24 P.E.)**

150 litres

The client has decided to propose a 30pe unit so in order to have extra capacity.

**These figures are supplied by the client based on their good research and allow for a situation where the visitor numbers may increase over time and allow for slightly extra busy periods.**

**Figures sheet supplied by client and their agent.**

HOUR	NO. OF PERSONS (wc & shower)	LITRES USED			TOTAL (litres)
		WC	WHB	SHOWER	
08:00-09:00	5 & 0	25	5	0	30
09:00-10:00	15 & 2	75	15	90	180
10:00-11:00	25 & 3	125	25	135	285
12:00-13:00	35 & 5	175	35	225	435
13:00-14:00	45 & 6	225	45	270	540
14:00-15:00	35 & 4	175	35	180	390
15:00-16:00	25 & 2	125	25	90	240
16:00-17:00	25 & 3	125	25	135	345
17:00-18:00	25 & 6	125	25	270	420
18:00-19:00	20 & 6	100	20	270	390
19:00-20:00	10 & 2	50	10	90	150
20:00-21:00	5 & 1	25	5	45	75
<b>TOTAL DAILY LOADING ON SYSTEM</b>					

N.B. - Sizing of effluent system is based on usage figures supplied by the client and their agent .



Brandon Bay

Tralee Bay

Cloghadhu

Lough  
NORRICO

MAGHERABEG


Brandon Bay

Tralee Bay


Tralee Bay

4

# Maherbeg




Source Protection Area : SI – n/a, SO – n/a.




Groundwater Body Name : Brandon Head

5




Vulnerability : High




Aquifer : Locally Important (LI)






Bedrock : Dinantian Pure Unbedded Limestones (DPUL)



O.S. Map

G.P.R. is R2<sup>1</sup>

8



Groundwater Quality Map : Not at Risk

### 3.0 ON-SITE ASSESSMENT

#### 3.1 Visual Assessment

Landscape Position:

Slope: Steep (>1:5)  Shallow (1:5-1:20)  Relatively Flat (<1:20)

Slope Comment

Surface Features within a minimum of 250m (Distance To Features Should Be Noted In Metres)

Houses:

Existing Land Use:

Vegetation Indicators:

Groundwater Flow Direction:

Ground Condition:

Site Boundaries:

**3.0 ON-SITE ASSESSMENT**

**3.1 Visual Assessment (contd.)**

Roads:

By road to front of site

Outcrops (Bedrock And/Or Subsoil):

None evident during testing

Surface Water Ponding:

None visible during testing in test zone (wet weather)

Lakes:

None within 150m

Beaches/Shellfish Areas:

Magherbeg beach is adjacent to site (see layout)

Wetlands:

None within 250m

Karst Features:

None within 250m

Watercourses/Streams:\*

None within 250m

\*Note and record water level

### 3.0 ON-SITE ASSESSMENT

#### 3.1 Visual Assessment (contd.)

Drainage Ditches:\*

Existing storm water drain 22.8m to the South (see layout)

Springs:\*

None evident within 100m (confirmed by client / agent)

Wells:\*

None evident within 100m (confirmed by client / agent)

Comments:

(Integrate the information above in order to comment on: the potential suitability of the site, potential targets at risk, the suitability of the site to treat the wastewater and the location of the proposed system within the site).

Magherbeg Beach is adjacent to site  
Existing storm water drain 22.8m to the South (see layout)  
E.P.A set back distances will be achieved with our proposal

\*Note and record water level

**3.2 Trial Hole** (should be a minimum of 2.1m deep (3m for regionally important aquifers))

To avoid any accidental damage, a trial hole assessment or percolation tests should not be undertaken in areas which are at or adjacent to significant sites, (e.g. NHAs, SACs, SPAs, and/or Archaeological etc.), without prior advice from National Parks and Wildlife Service or the Heritage Service.

Depth of trial hole (m):

Depth from ground surface to bedrock (m) (if present):

Depth from ground surface to water table (m) (if present):

Depth of water ingress:  Rock type (if present):

Date and time of excavation:   Date and time of examination:

Depth of Surface and Subsurface Percolation Tests

Soil/Subsoil Texture & Classification\*\*

Plasticity and dilatancy\*\*\*

Soil Structure

Density/ Compactness

Colour\*\*\*\*

Preferential flowpaths

0.1 m	<input type="checkbox"/>	SAND	0 Threads 5 mm Ribbons Dilatant	Granular	Low (uncompact)	Brown	Roots and Small stones
0.2 m	<input type="checkbox"/>						
0.3 m	<input type="checkbox"/>						
0.4 m	<input type="checkbox" value="P"/>						
0.5 m	<input type="checkbox"/>						
0.6 m	<input type="checkbox"/>						
0.7 m	<input type="checkbox"/>						
0.8 m	<input type="checkbox" value="t"/>						
0.9 m	<input type="checkbox"/>						
1.0 m	<input type="checkbox"/>						
1.1 m	<input type="checkbox"/>						
1.2 m	<input type="checkbox"/>						
1.3 m	<input type="checkbox"/>						
1.4 m	<input type="checkbox"/>						
1.5 m	<input type="checkbox"/>						
1.6 m	<input type="checkbox" value="WT"/> Water Table 1.6m						
1.7 m	<input type="checkbox"/>						
1.8 m	<input type="checkbox"/>						
1.9 m	<input type="checkbox"/>						
2.0 m	<input type="checkbox"/>						
2.1 m	<input type="checkbox"/>						
2.2 m	<input type="checkbox"/>						
2.3 m	<input type="checkbox"/>						
2.4 m	<input type="checkbox"/>						
2.5 m	<input type="checkbox"/>						
2.6 m	<input type="checkbox"/>						
2.7 m	<input type="checkbox"/>						
2.8 m	<input type="checkbox"/> Bedrock 2.85m						
2.9 m	<input type="checkbox" value="BR"/>						
3.0 m	<input type="checkbox"/>						
3.1 m	<input type="checkbox"/>						
3.2 m	<input type="checkbox"/>						
3.3 m	<input type="checkbox"/>						
3.4 m	<input type="checkbox"/>						
3.5 m	<input type="checkbox"/>						

Likely Subsurface Percolation Value:

Likely Surface Percolation Value:

**Note:** \*Depth of percolation test holes should be indicated on log above. (\*Enter Surface or Subsurface at depths as appropriate).  
 \*\* See Appendix E for BS 5930 classification.  
 \*\*\* 3 samples to be tested for each horizon and results should be entered above for each horizon.  
 \*\*\*\* All signs of mottling should be recorded.

BS5930 Tests (TH )

13

SAND

0 threads

6mm ribbons

Dilatant

0 threads

5mm ribbons

dilatant

0 threads

4mm ribbons

dilatant

**3.2 Trial Hole** (should be a minimum of 2.1m deep (3m for regionally important aquifers))

To avoid any accidental damage, a trial hole assessment or percolation tests should not be undertaken in areas which are at or adjacent to significant sites, (e.g. NHAs, SACs, SPAs, and/or Archaeological etc.), without prior advice from National Parks and Wildlife Service or the Heritage Service.

Depth of trial hole (m):

Depth from ground surface to bedrock (m) (if present):

Depth from ground surface to water table (m) (if present):

Depth of water ingress:  Rock type (if present):

Date and time of excavation:   Date and time of examination:

Depth of Surface and Subsurface Percolation Tests	Soil/Subsoil Texture & Classification**	Plasticity and dilatancy***	Soil Structure	Density/ Compactness	Colour****	Preferential flowpaths	
0.1 m	SAND	0 Threads 6 mm Ribbons Dilatant	Granular	Low (uncompact)	Brown	Roots and Small stones	
0.2 m							
0.3 m							
0.4 m							P
0.5 m							
0.6 m							
0.7 m							
0.8 m							t
0.9 m							
1.0 m							
1.1 m							
1.2 m							
1.3 m							
1.4 m	WT	Water Table 1.4m					
1.5 m							
1.6 m							
1.7 m							
1.8 m							
1.9 m							
2.0 m							
2.1 m							
2.2 m							
2.3 m							
2.4 m							
2.5 m							
2.6 m							
2.7 m							
2.8 m	BR	Bedrock 2.8m					
2.9 m							
3.0 m							
3.1 m							
3.2 m							
3.3 m							
3.4 m							
3.5 m							

Likely Subsurface Percolation Value:

Likely Surface Percolation Value:

**Note:** \*Depth of percolation test holes should be indicated on log above. (\*Enter Surface or Subsurface at depths as appropriate).  
 \*\* See Appendix E for BS 5930 classification.  
 \*\*\* 3 samples to be tested for each horizon and results should be entered above for each horizon.  
 \*\*\*\* All signs of mottling should be recorded.

BS5930 Tests (TH )

SAND

0 threads

7mm ribbons

Dilatant

0 threads

6mm ribbons

dilatant

0 threads

5mm ribbons

dilatant

# T & P Tests

## Set 1

**3.2 Trial Hole (contd.) Evaluation:**

This type of soil should be able to treat wastewater

**3.3(a) Subsurface Percolation Test for Subsoil**

**Step 1: Test Hole Preparation**

**Percolation Test Hole**

	1	2	3
Depth from ground surface to top of hole (mm) (A)	320	320	320
Depth from ground surface to base of hole (mm) (B)	720	720	720
Depth of hole (mm) [B - A]	400	400	400
Dimensions of hole [length x breadth (mm)]	300 x 300	300 x 300	300 x 300

**Step 2: Pre-Soaking Test Holes**

Pre-soak start	Date	25-Mar-2024	25-Mar-2024	25-Mar-2024
	Time	10:20	10:21	10:22
2nd pre-soak start	Date	25-Mar-2024	25-Mar-2024	25-Mar-2024
	Time	16:07	16:08	16:09

Each hole should be pre-soaked twice before the test is carried out.

**Step 3: Measuring  $T_{100}$**

**Percolation Test Hole No.**

	1	2	3
Date of test	26-03-2024	26-03-2024	26-03-2024
Time filled to 400 mm	09:30	09:31	09:32
Time water level at 300 mm	10:02	10:03	10:04
Time (min.) to drop 100 mm ( $T_{100}$ )	32.00	32.00	32.00
Average $T_{100}$			32.00

If  $T_{100} > 480$  minutes then Subsurface Percolation value  $>120$  – site unsuitable for discharge to ground

If  $T_{100} \leq 210$  minutes then go to Step 4;

If  $T_{100} > 210$  minutes then go to Step 5;

**Step 4: Standard Method** (where  $T_{100} \leq 210$  minutes)

18

Percolation Test Hole	1			2			3		
Fill no.	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta t$ (min)	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta t$ (min)	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta t$ (min)
1	10:02	10:43	41.00	10:03	10:45	42.00	10:04	10:47	43.00
2	10:44	11:29	45.00	10:46	11:31	45.00	10:48	11:33	45.00
3	11:30	12:25	55.00	11:32	12:27	55.00	11:34	12:29	55.00
Average $\Delta t$ Value	47.00			47.33			47.67		
	Average $\Delta t/4 =$ [Hole No.1] <b>11.75</b> ( $t_1$ )			Average $\Delta t/4 =$ [Hole No.2] <b>11.83</b> ( $t_2$ )			Average $\Delta t/4 =$ [Hole No.3] <b>11.92</b> ( $t_3$ )		

Result of Test: Subsurface Percolation Value = **11.83** (min/25 mm)

Comments:

This is an acceptable T value in the subsoil layer.

**Step 5: Modified Method** (where  $T_{100} > 210$  minutes)

Percolation Test Hole No.	1					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 1 = ( $T_1$ )				<b>0.00</b>

Percolation Test Hole No.	2					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 2 = ( $T_2$ )				<b>0.00</b>

Result of Test: Subsurface Percolation Value = **0.00** (min/25 mm)

Percolation Test Hole No.	3					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 3 = ( $T_3$ )				<b>0.00</b>

Comments:

### 3.3(b) Surface Percolation Test for Soil

19

#### Step 1: Test Hole Preparation

Percolation Test Hole	1	2	3
Depth from ground surface to top of hole (mm)	0	0	0
Depth from ground surface to base of hole (mm)	400	400	400
Depth of hole (mm)	400	400	400
Dimensions of hole [length x breadth (mm)]	300 x 300	300 x 300	300 x 300

#### Step 2: Pre-Soaking Test Holes

Pre-soak start	Date	25-Mar-2024	25-Mar-2024	25-Mar-2024
	Time	10:26	10:27	10:28
2nd pre-soak start	Date	25-Mar-2024	25-Mar-2024	25-Mar-2024
	Time	16:10	16:11	16:12

Each hole should be pre-soaked twice before the test is carried out.

#### Step 3: Measuring $T_{100}$

Percolation Test Hole No.	1	2	3
Date of test	26-Mar-24	26-Mar-24	26-Mar-2024
Time filled to 400 mm	09:36	09:37	09:38
Time water level at 300 mm	10:08	10:09	10:10
Time to drop 100 mm ( $T_{100}$ )	32.00	32.00	32.00
Average $T_{100}$			32.00

If  $T_{100} > 480$  minutes then Surface Percolation value  $>90$  – site unsuitable for discharge to ground

If  $T_{100} \leq 210$  minutes then go to Step 4;

If  $T_{100} > 210$  minutes then go to Step 5;

**Step 4: Standard Method** (where  $T_{100} \leq 210$  minutes)

Percolation Test Hole	1			2			3				
Fill no.	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta T$ (min)	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta T$ (min)	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta T$ (min)		
1	10:08	10:55	47.00	10:09	10:57	48.00	10:10	10:59	49.00		
2	10:56	11:45	49.00	10:58	11:47	49.00	11:00	11:49	49.00		
3	11:46	12:36	50.00	11:48	12:38	50.00	11:50	12:40	50.00		
Average $\Delta T$ Value	48.67			49.00			49.33				
Average $\Delta T/4 =$ [Hole No.1]			12.17 ( $T_1$ )	Average $\Delta T/4 =$ [Hole No.2]			12.25 ( $T_2$ )	Average $\Delta T/4 =$ [Hole No.3]			12.33 ( $T_3$ )

Result of Test: Surface Percolation Value = 12.25 (min/25 mm)

Comments:

This is an acceptable P value in this layer

**Step 5: Modified Method** (where  $T_{100} > 210$  minutes)

Percolation Test Hole No.	1					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 1 = ( $T_1$ )				0.00

Percolation Test Hole No.	2					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 2 = ( $T_2$ )				0.00

Result of Test: Surface Percolation Value =

0.00 (min/25 mm)

Percolation Test Hole No.	3					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 3 = ( $T_3$ )				0.00

Comments:

21

# T & P Tests

## Set 2

**3.2 Trial Hole (contd.) Evaluation:**

Uphill / Downhill  
 This type of soil should be able to treat wastewater

**3.3(a) Subsurface Percolation Test for Subsoil**

**Step 1: Test Hole Preparation**

Percolation Test Hole	1	2	3
Depth from ground surface to top of hole (mm) (A)	320	320	320
Depth from ground surface to base of hole (mm) (B)	720	720	720
Depth of hole (mm) [B - A]	400	400	400
Dimensions of hole [length x breadth (mm)]	300 x 300	300 x 300	300 x 300

**Step 2: Pre-Soaking Test Holes**

Pre-soak start	Date	25-Mar-2024	25-Mar-2024	25-Mar-2024
	Time	10:29	10:30	10:31
2nd pre-soak start	Date	25-Mar-2024	25-Mar-2024	25-Mar-2024
	Time	16:13	16:14	16:15

Each hole should be pre-soaked twice before the test is carried out.

**Step 3: Measuring  $T_{100}$**

Percolation Test Hole No.	1	2	3
Date of test	26-03-2024	26-03-2024	26-03-2024
Time filled to 400 mm	09:33	09:34	09:35
Time water level at 300 mm	10:05	10:06	10:07
Time (min.) to drop 100 mm ( $T_{100}$ )	32.00	32.00	32.00
Average $T_{100}$			32.00

If  $T_{100} > 480$  minutes then Subsurface Percolation value  $>120$  – site unsuitable for discharge to ground  
 If  $T_{100} \leq 210$  minutes then go to Step 4;  
 If  $T_{100} > 210$  minutes then go to Step 5;

**Step 4: Standard Method (where  $T_{100} \leq 210$  minutes)**

23

Percolation Test Hole	1			2			3		
Fill no.	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta t$ (min)	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta t$ (min)	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta t$ (min)
1	10:05	10:49	44.00	10:06	10:51	45.00	10:07	10:53	46.00
2	10:50	11:35	45.00	10:52	11:37	45.00	10:54	11:40	46.00
3	11:36	12:30	54.00	11:38	12:33	55.00	11:40	12:35	55.00
Average $\Delta t$ Value	47.67			48.33			49.00		
	Average $\Delta t/4 =$ [Hole No.1] 11.92 ( $t_1$ )			Average $\Delta t/4 =$ [Hole No.2] 12.08 ( $t_2$ )			Average $\Delta t/4 =$ [Hole No.3] 12.25 ( $t_3$ )		

Result of Test: Subsurface Percolation Value = 12.08 (min/25 mm)

Comments:

This is an acceptable T value in the subsoil layer.

**Step 5: Modified Method (where  $T_{100} > 210$  minutes)**

Percolation Test Hole No.	1					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 1 = ( $T_1$ )				0.00

Percolation Test Hole No.	2					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 2 = ( $T_2$ )				0.00

Result of Test: Subsurface Percolation Value =

0.00 (min/25 mm)

Percolation Test Hole No.	3					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 3 = ( $T_3$ )				0.00

Comments:

This is an acceptable T value in the subsoil layer.

### 3.3(b) Surface Percolation Test for Soil

24

#### Step 1: Test Hole Preparation

Percolation Test Hole	1	2	3
Depth from ground surface to top of hole (mm)	0	0	0
Depth from ground surface to base of hole (mm)	400	400	400
Depth of hole (mm)	400	400	400
Dimensions of hole [length x breadth (mm)]	300 x 300	300 x 300	300 x 300

#### Step 2: Pre-Soaking Test Holes

Pre-soak start	Date	25-Mar-2024	25-Mar-2024	25-Mar-2024
	Time	10:32	10:33	10:34
2nd pre-soak start	Date	25-Mar-2024	25-Mar-2024	25-Mar-2024
	Time	16:17	16:18	16:19

Each hole should be pre-soaked twice before the test is carried out.

#### Step 3: Measuring $T_{100}$

Percolation Test Hole No.	1	2	3
Date of test	26-Mar-24	26-Mar-24	26-Mar-2024
Time filled to 400 mm	09:39	09:40	09:41
Time water level at 300 mm	10:11	10:12	10:13
Time to drop 100 mm ( $T_{100}$ )	32.00	32.00	32.00
Average $T_{100}$			32.00

If  $T_{100} > 480$  minutes then Surface Percolation value  $>90$  – site unsuitable for discharge to ground

If  $T_{100} \leq 210$  minutes then go to Step 4;

If  $T_{100} > 210$  minutes then go to Step 5;

25

**Step 4: Standard Method (where  $T_{100} \leq 210$  minutes)**

Percolation Test Hole	1			2			3		
Fill no.	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta T$ (min)	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta T$ (min)	Start Time (at 300 mm)	Finish Time (at 200 mm)	$\Delta T$ (min)
1	10:11	11:01	50.00	10:12	11:03	51.00	10:13	11:05	52.00
2	11:02	11:52	50.00	11:04	11:55	51.00	11:06	11:58	52.00
3	11:52	12:43	51.00	11:55	12:47	52.00	11:58	12:51	53.00
Average $\Delta T$ Value	50.33			51.33			52.33		
	Average $\Delta T/4 =$ [Hole No.1] 12.58 ( $T_1$ )			Average $\Delta T/4 =$ [Hole No.2] 12.83 ( $T_2$ )			Average $\Delta T/4 =$ [Hole No.3] 13.08 ( $T_3$ )		

Result of Test: Surface Percolation Value = 12.83 (min/25 mm)

Comments:

This is an acceptable P value in this layer

**Step 5: Modified Method (where  $T_{100} > 210$  minutes)**

Percolation Test Hole No.	1					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 1 = ( $T_1$ )				0.00

Percolation Test Hole No.	2					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 2 = ( $T_2$ )				0.00

Result of Test: Surface Percolation Value =

0.00 (min/25 mm)

Percolation Test Hole No.	3					
Fall of water in hole (mm)	Time Factor = $T_f$	Start Time hh:mm	Finish Time hh:mm	Time of fall (mins) = $T_m$	$K_{fs} = T_f / T_m$	T-Value = $4.45 / K_{fs}$
300 - 250	8.1			0.00		
250 - 200	9.7			0.00		
200 - 150	11.9			0.00		
150 - 100	14.1			0.00		
Average	T-Value	T-Value Hole 3 = ( $T_3$ )				0.00

Comments:

**3.4 The following associated Maps, Drawings and Photographs should be appended to this site characterisation form.**

26

1. Discovery Series 1:50,000 Map indicating overall drainage, groundwater flow direction and housing density in the area.
2. Supporting maps for vulnerability, aquifer classification, soil, subsoil, bedrock.
3. North point should always be included.
4. (a) Scaled sketch of site showing measurements to Trial Hole location and
  - (b) Percolation Test Hole locations,
  - (c) wells and
  - (d) direction of groundwater flow (if known),
  - (e) proposed house (incl. distances from boundaries)
  - (f) adjacent houses,
  - (g) watercourses,
  - (h) significant sites
  - (i) and other relevant features.
5. Site specific cross sectional drawing of the site and the proposed layout<sup>1</sup> should be submitted.
6. Photographs of the trial hole, test holes and site including landmarks (date and time referenced).
7. Pumped design must be designed by a suitably qualified person.

<sup>1</sup> The calculated percolation area or polishing filter area should be set out accurately on the site layout drawing in accordance with the code of practice's requirements.

### 4.0 CONCLUSION of SITE CHARACTERISATION

Integrate the information from the desk study and on-site assessment (i.e. visual assessment, trial hole and percolation tests) above and conclude the type of system(s) that is (are) appropriate. This information is also used to choose the optimum final disposal route of the treated wastewater.

Slope of proposed infiltration / treatment area:

Are all minimum separation distances met? (Upgrade)

Depth of unsaturated soil and/or subsoil beneath invert of gravel (or drip tubing in the case of drip dispersal system)

Percolation test result: Surface:  Sub-surface:

Not Suitable for Development

Suitable for Development   
NB - as upgrade.

- Identify all suitable options**
1. Septic tank system (septic tank and percolation area) (Chapter 7)
  2. Secondary Treatment System (Chapters 8 and 9) and soil polishing filter (Section 10.1)
  3. Tertiary Treatment System and Infiltration / treatment area (Section 10.2)

**Discharge Route <sup>1</sup>**

Discharge to Groundwater

### 5.0 SELECTED DWWTS

Propose to install:

and discharge to:

Invert level of the trench/bed gravel or drip tubing (m)

Site Specific Conditions (e.g. special works, site improvement works testing etc.)

This system should be built and located as shown on the attached planning drawings: **Key Levels:**  
 Inlet into Malloy Chieftan M.A.U. is 3.350m (approx) Inlet into Ecoflo modules is 4.633m (approx)  
 Top of distribution stone is 3.953m (approx) Trench invert level is 3.653m (approx)  
 Contact OSC prior to construction. all relevant issues must be re-verified prior to installation. All works must be in strict compliance with E.P.A C.O.P guidelines and K.C.C. conditions. Layout & levels supplied by client & agent. Prior to commencement of installation a qualified engineer must determine and instruct the installer regarding issues such as if a retaining wall is required for the polishing filter. etc. We are not liable for any issues that arise with upgrades of old in situ systems being done to improve the situation while not fully E.P.A. compliant. Responsibility for this rests with the client. Clients and their agents are responsible for information supplied to us such as flood plain verification, well location, drains, local features identification etc. We asked about these issues during testing. All pipework and equipment being used in this system is the responsibility of the client and their installer to ensure that they are fit for purpose and not carrying roof water and surface water. Clients must ensure that all products used in this system are properly certified and correctly sized. Suppliers instructions should be read and followed.

<sup>1</sup> A discharge of sewage effluent to "waters" (definition includes any or any part of any river, stream, lake, canal, reservoir, aquifer, pond, watercourse or other inland waters, whether natural or artificial) will require a licence under the Water Pollution Acts 1977-90. Refer to Section 2.4.

## 6.0 TREATMENT SYSTEM DETAILS

### SYSTEM TYPE: Septic Tank Systems (Chapter 7)

Tank Capacity (m <sup>3</sup> )	<input type="text"/>	Percolation Area	Mounded Percolation Area
		No. of Trenches	No. of Trenches
		Length of Trenches (m)	Length of Trenches (m)
		Invert Level (m)	Invert Level (m)

### SYSTEM TYPE: Secondary Treatment System (Chapters 8 and 9) and polishing filter (Section 10.1)

#### Secondary Treatment Systems receiving septic tank effluent (Chapter 8)

Media Type	Area (m <sup>2</sup> )*	Depth of Filter	Invert Level
Sand/Soil	<input type="text"/>	<input type="text"/>	<input type="text"/>
Soil	<input type="text"/>	<input type="text"/>	<input type="text"/>
Constructed Wetland	<input type="text"/>	<input type="text"/>	<input type="text"/>
Other	5.6	1.3	4.633

#### Packaged Secondary Treatment Systems receiving raw wastewater (Chapter 9)

Type	<input type="text" value="Malloy Chieftan"/>
Capacity PE	30
Sizing of Primary Compartment	<input type="text"/> m <sup>3</sup>

#### Polishing Filter\*: (Section 10.1)

Surface Area (m <sup>2</sup> )*	120.01	Option 3 - Gravity Discharge Trench length (m)	<input type="text"/>
Option 1 - Direct Discharge Surface area (m <sup>2</sup> )	<input type="text"/>	Option 4 - Low Pressure Pipe Distribution Trench length (m)	<input type="text"/>
Option 2 - Pumped Discharge Surface area (m <sup>2</sup> )	<input type="text"/>	Option 5 - Drip Dispersal Surface area (m <sup>2</sup> )	<input type="text"/>

### SYSTEM TYPE: Tertiary Treatment System and infiltration / treatment area (Section 10.2)

Identify purpose of tertiary treatment

Provide performance information demonstrating system will provide required treatment levels

Provide design information

To treat the effluent from the facility to a better standard.

As per suppliers P.I.A cert (attached)

As per table 10.1 in E.P.A. manual 2021 .

#### DISCHARGE ROUTE:

Groundwater	<input checked="" type="checkbox"/>	Hydraulic Loading Rate * (l/m <sup>2</sup> .d)	<input type="text"/>	Surface area (m <sup>2</sup> )	120.01
Surface Water **	<input type="checkbox"/>	Discharge Rate (m <sup>3</sup> /hr)	<input type="text"/>		

\* Hydraulic loading rate is determined by the percolation rate of subsoil

\*\* Water Pollution Act discharge licence required

### 6.0 TREATMENT SYSTEM DETAILS

#### QUALITY ASSURANCE:

##### Installation & Commissioning

System install to be overseen and certified as correct by a qualified and insured engineer. E.P.A guidelines to be adhered to. Equipment must be commissioned. Kerry County Council and E.P.A. conditions to be complied with.

##### On-going Maintenance

Service contract to be taken out for the equipment. Regular clean out of unit, as per supplier advice.

### 7.0 SITE ASSESSOR DETAILS

Company: O.S.C

Prefix: Mr      First Name: Tim      Surname: O'Sullivan

Address: Rossanean, Currow, Killarney. Co. Kerry

Qualifications/Experience: F.E.T.A.C. S.S.A.C

Date of Report: 01-Apr-2024

Phone: 0876858993      E-mail: tim@osullivanconsulting.ie

Indemnity Insurance Number: PSL0739668459

Signature: T.O'Sullivan

30



31





26/03/2024  
10.05

26/03/2024  
10.06

26/03/2024  
10.07

26/03/2024  
13.09

26/03/2024  
13.10

26/03/2024  
13.11

26/03/2024  
13.12



26/03/2024  
13.15

26/03/2024  
13.16

26/03/2024  
09.01

26/03/2024  
09.02

26/03/2024  
09.03

26/03/2024  
09.04

26/03/2024  
09.05



26/03/2024  
09.06

26/03/2024  
09.07

26/03/2024  
09.08

26/03/2024  
09.09

26/03/2024  
09.10

26/03/2024  
09.11

26/03/2024  
09.12



26/03/2024  
09.13

26/03/2024  
09.14

26/03/2024  
09.15

26/03/2024  
09.16

26/03/2024  
09.17

26/03/2024  
09.18

26/03/2024  
09.19



26/03/2024  
09.20

26/03/2024  
09.21

26/03/2024  
09.22

26/03/2024  
09.23

26/03/2024  
09.24

26/03/2024  
09.30

26/03/2024  
09.31



26/03/2024  
09.32



26/03/2024  
09.36



26/03/2024  
09.37



26/03/2024  
09.38



26/03/2024  
09.39



26/03/2024  
09.33



26/03/2024  
09.34



26/03/2024  
09.35



26/03/2024  
09.40



26/03/2024  
09.41



26/03/2024  
10.02



26/03/2024  
10.03



26/03/2024  
10.04



26/03/2024  
10.08



26/03/2024  
10.09



26/03/2024  
10.10



26/03/2024  
10.43



26/03/2024  
10.44



26/03/2024  
10.45



26/03/2024  
10.46



26/03/2024  
10.47



26/03/2024  
10.48



26/03/2024  
10.55



26/03/2024  
10.56



26/03/2024  
10.57



26/03/2024  
10.58



26/03/2024  
10.59



26/03/2024  
11.00



26/03/2024  
11.29



26/03/2024  
11.30



26/03/2024  
11.31



26/03/2024  
11.32



26/03/2024  
11.33



26/03/2024  
11.34



26/03/2024  
11.45

34



26/03/2024  
11.46



26/03/2024  
11.47



26/03/2024  
11.48



26/03/2024  
11.49



26/03/2024  
11.50



26/03/2024  
12.25



26/03/2024  
12.27



26/03/2024  
12.29



26/03/2024  
12.36



26/03/2024  
12.38



26/03/2024  
12.40



26/03/2024  
10.11



26/03/2024  
10.12



26/03/2024  
10.13



26/03/2024  
10.49



26/03/2024  
10.50



26/03/2024  
10.51



26/03/2024  
10.52



26/03/2024  
10.53



26/03/2024  
10.54



26/03/2024  
11.01



26/03/2024  
11.02



26/03/2024  
11.03



26/03/2024  
11.04



26/03/2024  
11.05



26/03/2024  
11.06



26/03/2024  
13.19



26/03/2024  
13.20



26/03/2024  
11.35



26/03/2024  
11.36



26/03/2024  
11.37



26/03/2024  
11.38



26/03/2024  
11.40



26/03/2024  
11.40



26/03/2024  
11.52



26/03/2024  
11.52



26/03/2024  
11.55



26/03/2024  
11.55



26/03/2024  
12.30



26/03/2024  
12.33



26/03/2024  
12.35



26/03/2024  
11.58



26/03/2024  
12.43



26/03/2024  
11.58



26/03/2024  
12.47



26/03/2024  
13.22



26/03/2024  
13.27



26/03/2024  
12.51




26/03/2024  
13.29



26/03/2024  
13.30


# Notes:

- 1) Please contact O'Sullivan Consulting prior to the construction of this waste-water treatment system.
- 2) Levels and Site Layout Map provided by the clients Planning Agent.
- 3) These drawings have been prepared for the purposes of making a planning application only.
- 4) All work to be carried out in accordance with EPA Code of Practice Guidelines.
- 5) All plant operators should check for and locate any existing on-site services prior to work commencing.
- 6) OSC is not responsible for ground conditions or existing pipe work (which should be checked) on already developed sites.
- 7) On sloped sites it is necessary for the client to consult an engineer to determine if a Retaining Wall is required.
- 8) It is vital that the supervising engineer ensures that the trench invert level is below the iron pan (if present).
- 9) This office has not been advised of any issues resulting or relating to a flood plain.
- 10) OSC is not liable for upgraded systems on existing unsuitable sites, such as this one.




**Site Layout Map** Scale: 1 in 500

Client(s): Kerry County Council		Proposed upgrade of Wastewater Treatment System for Public Toilet/Showers at Maherabeg, Castlegregory, Co. Kerry	O'Sullivan Consulting Rossaneen, Currow, Killarney, Co. Kerry Telephone/Fax: (066) 9793931 Email: <a href="mailto:info@osullivanconsulting.ie">info@osullivanconsulting.ie</a> Website: <a href="http://www.osullivanconsulting.ie">www.osullivanconsulting.ie</a>	Notes: 1) Please contact O'Sullivan Consulting prior to the construction of this waste-water treatment system. 2) Levels and Site Layout Map provided by the clients Planning Agent. 3) These drawings have been prepared for the purposes of making a planning application only. 4) All work to be carried out in accordance with EPA Code of Practice Guidelines. 5) All plant operators should check for and locate any existing on-site services prior to work commencing. 6) OSC is not responsible for ground conditions or existing pipe work (which should be checked) on already developed sites. 7) On sloped sites it is necessary for the client to consult an engineer to determine if a Retaining Wall is required. 8) It is vital that the supervising engineer ensures that the trench invert level is below the iron pan (if present). 9) This office has not been advised of any issues resulting or relating to a flood plain. 10) OSC is not liable for upgraded systems on existing unsuitable sites, such as this one.
Date: April 2024	Scale: As Indicated			
Drawing No: OSC/KCC - PS/03/2024	Rev. A			



### PLAN VIEW - WASTEWATER TREATMENT SYSTEM

SCALE: 1:20



### SECTION - WASTEWATER TREATMENT SYSTEM

SCALE: 1:20

NOTES:

1. ALL DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL RELEVANT SPECIFICATIONS, BILLS OF QUANTITIES, ARCHITECTURAL, SERVICES AND ENGINEERING DRAWINGS.
2. ALL LEVELS ARE IN METRES RELATED TO ORDNANCE DATUM MALIN HEAD.
3. ANY DISCREPANCIES BETWEEN THESE DOCUMENTS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.
4. DRAWINGS ARE NOT TO BE SCALED.
5. ALL DIMENSIONS ARE IN MILLIMETRES, UNLESS NOTED OTHERWISE.

P01	05/10/23	ISSUED FOR PLANNING	S.S.	I.B.
REV	DATE	DESCRIPTION	BY	APP

PROJECT: **MAGHERABEG BEACH FACILITIES**


TITLE: **SBR TREATMENT SYSTEM DETAILS**




DRAWN: S.S.	CHECKED: A.G.	APPROVED: I.B.
PROJECT NUMBER: 23173	DATE: OCT '23	SCALE @ A1: 1:75

STATUS DESCRIPTION: **FOR INFORMATION** STATUS: **S2**

DRAWING NUMBER: 23173 - MWP - 00 - 00 - DR - A - 0420	REV: P01
---	----------



**Cross Section A - A** Scale: 1 in 100



**Cross Section B - B** Scale: 1 in 100

Client(s): Kerry County Council

Date: April 2024

Scale: As Indicated


Drawing No: OSC/KCC - PS/01/2024

Rev. A

Proposed upgrade of Wastewater Treatment System for Public Toilet/Showers at Maherabeg, Castlegregory, Co. Kerry

O'Sullivan Consulting  
Rossaneen, Currow,  
Killarney, Co. Kerry  
Telephone/Fax: (066) 9793931  
Email: [info@osullivanconsulting.ie](mailto:info@osullivanconsulting.ie)  
Website: [www.osullivanconsulting.ie](http://www.osullivanconsulting.ie)

- Notes:
- 1) Please contact O'Sullivan Consulting prior to the construction of this wastewater treatment system.
  - 2) Levels and Site Layout Map provided by the clients Planning Agent.
  - 3) These drawings have been prepared for the purposes of making a planning application only.
  - 4) All work to be carried out in accordance with EPA Code of Practice Guidelines.
  - 5) All plant operators should check for and locate any existing on-site services prior to work commencing.
  - 6) OSC is not responsible for ground conditions or existing pipe work (which should be checked) on already developed sites.
  - 7) On sloped sites it is necessary for the client to consult an engineer to determine if a Retaining Wall is required.
  - 8) It is vital that the supervising engineer ensures that the trench invert level is below the iron pan (if present).
  - 9) This office has not been advised of any issues resulting or relating to a flood plain.
  - 10) OSC is not liable for upgraded systems on existing unsuitable sites, such as this one.



# Plan of Proposed System Scale: 1 in 200

Usage confirmed by the Local Authority & their Agent

I.L. of Pipe into Molloy Chieftan M.A.U. =  
3.350m or thereabouts

I.L. of pipe into Commercial Eco Modules =  
4.633m or thereabouts

Client(s): Kerry County Council		Proposed upgrade of Wastewater Treatment System for Public Toilet/Showers at Maherabeg, Castlegregory, Co. Kerry	O'Sullivan Consulting Rossaneen, Currow, Killarney, Co. Kerry Telephone/Fax: (066) 9793931 Email: <a href="mailto:info@osullivanconsulting.ie">info@osullivanconsulting.ie</a> Website: <a href="http://www.osullivanconsulting.ie">www.osullivanconsulting.ie</a>	<small>Notes:</small> <ol style="list-style-type: none"> <li>1) Please contact O'Sullivan Consulting prior to the construction of this waste-water treatment system.</li> <li>2) Levels and Site Layout Map provided by the clients Planning Agent.</li> <li>3) These drawings have been prepared for the purposes of making a planning application only.</li> <li>4) All work to be carried out in accordance with EPA Code of Practice Guidelines.</li> <li>5) All plant operators should check for and locate any existing on-site services prior to work commencing.</li> <li>6) OSC is not responsible for ground conditions or existing pipe work (which should be checked) on already developed sites.</li> <li>7) On sloped sites it is necessary for the client to consult an engineer to determine if a Retaining Wall is required.</li> <li>8) It is vital that the supervising engineer ensures that the trench invert level is below the iron pan (if present).</li> <li>9) This office has not been advised of any issues resulting or relating to a flood plain.</li> <li>10) OSC is not liable for upgraded systems on existing unsuitable sites, such as this one.</li> </ol>
Date: April 2024	Scale: As Indicated			
Drawing No: OSC/KCC - PS/02/2024	Rev. A			