

AtkinsRéalis



# Stage 2 Structural Assessment Report

Mayo County Council

January 2025

# N58 STRADE RIVER BRIDGE REHABILITATION WORKS

# Notice

This document and its contents have been prepared and are intended solely as information for Mayo County Council and use in relation to TO315 Mayo Bridges Assessments & Strengthening 2023.

WS Atkins Ireland Limited assumes no responsibility to any other party in respect of or arising out of or in connection with this document and/or its contents.

## Document history

Document title: MO-N58-001.00 Strade River Bridge Stage 2 Assessment


Document reference: 0088572DG0018

Revision	Purpose description	Originated	Checked	Reviewed	Authorised	Date
0.0	Draft for Comment	POS	VP	MG	MJ	22/10/2024
1.0	Final Issue	POS	MG	MJ	MJ	31/01/2025

## Client signoff

Client	Mayo County Council
Project	TASK ORDER NO.315 MAYO BRIDGE ASSESSMENTS & STRENGTHENING 2023
Job number	0088572
Client signature/date	





# Contents

<b>1.</b>	<b>Introduction.....</b>	<b>1</b>
1.1	Background information covering the origins for the need for the structural assessment .....	1
1.2	Previous reports and their recommendations .....	1
<b>2.</b>	<b>Executive Summary .....</b>	<b>2</b>
<b>3.</b>	<b>Structure Description .....</b>	<b>3</b>
3.1	General description of structure .....	3
3.2	Span arrangements.....	3
3.3	Foundation Type .....	3
3.4	Substructure .....	3
3.5	Superstructure.....	3
3.6	Articulation arrangements, joints and bearings.....	3
3.7	Parapet.....	3
3.8	Materials.....	4
3.9	Changes to Material Properties .....	4
<b>4.</b>	<b>Stage 1 Structural Assessment Summary .....</b>	<b>4</b>
4.1	Date of assessment .....	4
4.2	Assessing organisation .....	4
4.3	Review of testing undertaken as part of Stage 1 Assessment .....	4
4.4	Review of the results of the Stage 1 Structural Assessment .....	4
4.5	Extent to which the structure failed the assessment.....	5
4.6	Detailed commentary on the significance of all of the original assumptions made during the stage 1 assessment in terms of the assessed capacity of the structure.....	5
4.7	Mode of failure .....	5
4.8	Details of any strengthening works undertaken as a result of the assessment.....	5
4.9	Description of any changes to the load effects or assessment resistance since the original assessment .....	6
4.10	Results of any monitoring or inspections undertaken .....	6
4.11	The assessed capacity.....	6
<b>5.</b>	<b>Stage 2 Structural Assessment Inspection Summary.....</b>	<b>6</b>
5.1	Detailed description of the findings of the visual inspection .....	6
5.2	Identification and justification of the condition factor used in the assessment calculations for each structural element .....	8
5.3	Detailed description of the testing undertaken.....	8
5.4	Results of all testing undertaken .....	9



5.5	Summary of safety partial factors used in the assessment .....	9
5.6	Summary of all material properties used in the assessment .....	9
<b>6.</b>	<b>Assessment Method.....</b>	<b>10</b>
6.1	Summary of analysis methodology undertaken as part of Stage 1 Structural Assessment .....	10
6.2	Detailed description of method of analysis undertaken for Stage 2 analysis including justification as to how this has led to an increase in the assessed capacity for the superstructure, substructure and foundations .....	10
6.3	Description of the model and software used for the analysis .....	10
6.4	Assessment live loading.....	11
6.5	Abnormal loading .....	11
6.6	Additional loading requirements.....	11
<b>7.</b>	<b>Assessment Commentary .....</b>	<b>11</b>
7.1	Assumptions made during the Stage 2 Structural Assessment.....	11
7.2	Significance of these assumptions in relation to the overall capacity of the structure or element.....	11
<b>8.</b>	<b>Assessment Results .....</b>	<b>12</b>
<b>9.</b>	<b>Recommendations .....</b>	<b>13</b>
<b>Appendix A.</b>	<b>Archive Information about the Structure .....</b>	
<b>Appendix B.</b>	<b>Results of Additional Literature Search.....</b>	
<b>Appendix C.</b>	<b>General Arrangement Drawings .....</b>	
<b>Appendix D.</b>	<b>Structural Condition Drawing .....</b>	
<b>Appendix E.</b>	<b>Copy of Materials Testing Report .....</b>	
<b>Appendix F.</b>	<b>Structure Idealisation Model and Model Inputs .....</b>	
<b>Appendix G.</b>	<b>Calculations .....</b>	
<b>Appendix H.</b>	<b>Photographs .....</b>	



# 1. Introduction

AtkinsRéalis were appointed by Mayo County Council for Eirspan Task Order 315 – Mayo Bridge Assessments and Strengthening 2023, comprising the assessment and rehabilitation of 10no. bridges on the national road network throughout County Mayo. 7no. structures required structural assessment to determine the condition of the structures and their load-carrying capacity for HA, HB and SV loading. The assessment of the structures was undertaken in accordance with TII Publications *AM-STR-06056 Stage 1 Structural Assessment of Road Structures* and *AM-STR-06057 Stage 2 Structural Assessment of Sub-Standard Road Structures*.

The assessment of MO-N58-001.00 Strade River Bridge comprised the Stage 2 assessment of the 2no. span filler beam slab structure.

## 1.1 Background information covering the origins for the need for the structural assessment

The need for the Stage 2 structural assessment was outlined in the recommendations of the 2012 Stage 1 assessment report, refer to Appendix A of this report for the Stage 1 Assessment Report. The Stage 1 Assessment determined a bending capacity of 18t and a shear capacity of 40t for the structure but less than 3t capacity for bond with the low concrete strength and area of steel found to be the cause of low structural capacity.

## 1.2 Previous reports and their recommendations

The following table outlines the previous reports, with the 2012 Stage 1 assessment report recommending that a Stage 2 assessment be undertaken to the structure. The 2024 Principal Inspection report found the structure to be in poor condition due to the spalling and delamination to the deck slab soffit.

**Table 1-1 Previous Reports**

Document Reference	Document Title
-	Strade River Bridge Stage 1 Assessment Report (May 2012)
-	MO-N58-001.00 Strade River Bridge PI Report (May 2024)



## 2. Executive Summary

MO-N58-001.00 Strade River Bridge carries the N58 National Secondary Road over the Strade River in Co. Mayo. The structure comprises a two span filler beam deck structure with the filler beam deck slab comprising railway girders encased in concrete and supported on a mass concrete pier and abutments. The structure has skew span lengths of 3.82m and 3.79m for the south and north spans respectively with an overall structure length of 8.6m. The structure has a skew of 26 degrees. The overall width out-to-out of the structure is 10.3m.

The assessment of the structure comprised the Stage 2 assessment of the 2no. span filler beam slab structure. The need for the Stage 2 structural assessment was outlined in the recommendations of the Stage 1 assessment report completed by Atkins in May 2012. The Stage 1 Assessment determined a bending capacity of 18t and a shear capacity of 40t for the structure but less than 3t capacity for bond with the low concrete strength and area of steel found to be the cause of low structural capacity.

A visual inspection for the Stage 2 assessment was undertaken by Atkins in July 2024 with the structure in poor overall condition due to the extensive spalling and delamination noted to the deck soffit. Structural investigations were also undertaken to the structure by Triur Construction Ltd. in July 2024 to confirm the parameters for the Stage 2 assessment.

The initial assessment of the filler beam deck slab was carried out using the strip analysis method as per *AM-STR-06026* and *AM-STR-06037* followed by a grillage analysis as per *AM-STR-06057*. The assessment live loading comprised 40t HA loading in accordance with TII Publication *AM-STR-06026*. Abnormal loading considered as part of the assessment comprised SV196 loading in accordance with TII Publication *AM-STR-06048 The Assessment of Road Bridges and Structures for the Effects of Abnormal and Exceptional Abnormal Load Vehicles using SV and SOV Load Models* and 45 Units HB loading in accordance with *AM-STR-06030 Loads for Highway Bridges*.

The initial strip analysis showed a bending capacity of 3t HA loading alone, with no capacity for HB and SV loading. The filler beam was found unsuitable for composite action as it failed under the bond stress check, resulting in a bond capacity of less than 3t GVW.

The grillage analysis determined a reduction in the assessment load effects due to the transverse distributions of loads, which resulted in a bending capacity of 40t GVW for the structure when considering composite action. The bond capacity of the section limits the slab capacity to 7.5t however.

Structure ID	Structure Name	Structure Type	No. of Spans	Span Length	Assessed Capacity (ALL)	HB Capacity	SV Capacity
MO-N58-001.00	Strade Bridge	Filler Beam	2	3.79m(north) 3.82m(south)	7.5t	Fails HB30 units	Fails SV80

Based on the findings of the assessment the structure is determined to have a reduced load capacity due to bond failure between the concrete and steel beams with the significant delamination and spalling visible to the deck slab soffit providing evidence of the issue. As a result no further assessment measures are deemed required for the structure as they are not likely to increase the bond capacity to 40t loading due to the low compressive strength values found for the concrete in the soffit of the structure.

The deck slab is therefore recommended to be removed and a new deck installed across the structure, in either a single or two span structural arrangement.

Although there are extensive defects to the deck soffit as there is no evidence of failure or excess deformation of the slab a load restriction is not recommended at this time. Monitoring of the structure should be taken annually however to check for any further evidence of deformation or failure of the deck. Regular term maintenance should also be undertaken to the structure to maintain its condition in the interim.



## 3. Structure Description

### 3.1 General description of structure

MO-N58-001.00 Strade River Bridge carries the N58 National Secondary Road over the Strade River in Co. Mayo. The structure comprises a two span filler beam deck structure with the filler beam deck slab comprising railway girders encased in concrete and supported on mass concrete piers and abutments.

The structure has square spans of 3.44m and 3.42m and skew spans of 3.82m and 3.79m for the south and north spans respectively. The overall square length of the structure is 7.59m with a skew length of 8.6m. The structure has a skew of 26 degrees.

The overall kerb-to-kerb width on the bridge is 6.90m with the carriageway measuring 5.70m wide. Concrete verges are provided across the structure measuring 1.1m and 1.7m wide respectively with concrete parapets also provided measuring 900mm and 750mm high respectively. The overall width out-to-out of the structure is 10.3m square to the carriageway with a skewed width of 11.4m.

### 3.2 Span arrangements

The structure comprises 2no. spans measuring as follows:

South Span = 3.82m (square 3.42m)

North Span = 3.79m (square 3.44m)

### 3.3 Foundation Type

Unknown.

### 3.4 Substructure

The substructure comprises mass concrete abutments, pier and wing walls.

### 3.5 Superstructure

The superstructure comprises a filler beam deck slab formed by railway girders. The average thickness of the filler beam deck slab is 310mm.

### 3.6 Articulation arrangements, joints and bearings

The spans are separated by a transverse joint across the central pier with the support conditions considered as simply supported for the purpose of assessment.

### 3.7 Parapet

The parapets are of mass concrete construction with heights of 750mm and 900mm. The parapets have a thickness of 290mm.



## 3.8 Materials

The superstructure is comprised of steel railway girders and secondary reinforcement encased in concrete and the substructure comprises mass concrete.

## 3.9 Changes to Material Properties

The Stage 1 investigation report found the estimated worst credible concrete strength of the deck slab to be 13.3 N/mm<sup>2</sup>. Further concrete strength testing undertaken as part of the Stage 2 assessment determined an increased concrete strength of 18.9 N/mm<sup>2</sup>, accredited to a lower void % found in the core samples.

# 4. Stage 1 Structural Assessment Summary

## 4.1 Date of assessment

31<sup>st</sup> May 2012.

## 4.2 Assessing organisation

Atkins.

## 4.3 Review of testing undertaken as part of Stage 1 Assessment

The testing undertaken as part of the Stage 1 assessment comprised the following:

- 1no. trial pit was excavated over the filler beam deck to establish the internal thickness of the slab and the depth of the fill.
- Covermeter survey at 4 different locations at the soffit of the RC beam and slab to identify the reinforcing bar spacing, arrangement and orientation.
- 2no. concrete breakouts at the base of the slab to determine articulation details
- 3no. concrete cores drilled from the deck soffit of each span for the compressive strength testing of the concrete.

## 4.4 Review of the results of the Stage 1 Structural Assessment

Stage 1 assessment was carried out for filler beam structure in accordance with UK Highways Agency Design Manual for Roads and Bridges (BD21/01, BD44/95 & BD44/96). The structure was assessed using the strip method for HA loading, single axle and single wheel loads in accordance with BD21/01 and the methods outlined in BD44/95. Each span was assessed separately.



The live load capacity of both spans was 7.5 tonnes Gross Vehicle Weight (GVW) for bending and 40 tonnes for shear. An additional check carried out on the bond also indicated the capacity of the structure of less than 3 tonnes assessment loading for both spans.

As the adequacy of the structures in bending for 40t live loading was 60% for span 1 and 73% for span 2 using the strip method, a grillage analysis was carried out, which increased the load capacity of the structure in bending to 18 tonnes assessment loading for Span 1 and to 40 tonnes for Span 2. The variation in capacity was due to the variation in concrete strengths found in both spans.

The structure was also assessed for 45 units of HB live loading as per BD37/01. The results indicated that the structure had a HB rating of 30HB units for bending and 45HB units for shear, while for bond the structure had less than 30HB units capacity.

## **4.5 Extent to which the structure failed the assessment**

The filler beam deck was found to have a sufficient capacity of 40t for span 2 and have a reduced capacity of 18t in bending for span 1 due to the decreased concrete strength found. Both spans had sufficient capacity of 40t in shear but had less than 3t capacity in bond.

## **4.6 Detailed commentary on the significance of all of the original assumptions made during the stage 1 assessment in terms of the assessed capacity of the structure**

A condition factor of 0.9 was assumed for both spans of the structure based on the condition of the structure at the time of assessment with water seepage and calcite staining evident. The shear at supports was assumed to be carried by the steel sections only with a 40t capacity in shear determined for the structure. The loadings on the slab were assumed to be dispersed in both the longitudinal and transverse direction, increasing the capacity of the slab in the grillage analysis. A varying concrete strength was assumed for both spans which resulted in different assessment capacities.

## **4.7 Mode of failure**

The mode of failure for the filler beam slab was identified as bond failure and bending for the south span.

## **4.8 Details of any strengthening works undertaken as a result of the assessment**

There were no known structural strengthening works undertaken as a result of the Stage 1 assessment.



## 4.9 Description of any changes to the load effects or assessment resistance since the original assessment

An increased worst credible concrete strength of 18.9 N/mm<sup>2</sup> has been determined by the Stage 2 structural investigations.

## 4.10 Results of any monitoring or inspections undertaken

Regular Principal Inspections have been undertaken on the structure since the Stage 1 assessment with the condition of the deck further deteriorating since the assessment. The most recent Principal Inspection found the deck to be in poor condition. See the most recent inspection report dated May 2024 in Appendix A of this report.

Crack pips were installed to the north abutment and the north span deck soffit as part of the 2023 Principal Inspection to the structure. No change has occurred to the pip measurements since installation. Refer to Section 5.1 for further details.

## 4.11 The assessed capacity

The Stage 1 Assessment of the structure determined a capacity of 18t assessment loading for bending, 40t assessment loading for shear and less than 3 tonnes assessment loading for bond.

# 5. Stage 2 Structural Assessment Inspection Summary

## 5.1 Detailed description of the findings of the visual inspection

The Inspection of the structure was undertaken in June 2024. Photographs from the inspection are provided in Appendix H of this report. The condition of the structure is outlined below.

### Bridge Surface

The bridge surface is in good condition apart cracking evident to the carriageway on the northwest approach. See Photograph H-1 to view the surface looking south and see Photograph H-2 to view the cracking to the northwest approach.

### Expansion Joints

Not applicable.



## Footways

The footways are in good condition apart from vegetation debris. See Photograph H-3 for the east footway and see Photograph H-4 for the west footway.

## Parapets

The parapets are in good overall condition. See Photograph H-5 and H-6 for views of the east and west parapets, respectively.

## Embankments

The embankments are in good condition apart from vegetation growth at both elevations to be cut back during routine maintenance. See Photograph H-7 to view the northwest embankment and Photograph H-8 for the southeast embankment.

## Wing/Spandrel walls

The wing walls are in good condition apart from vegetation growth. See Photograph H-9 for a view of the southwest wing wall.

## Abutments

The abutments are in good condition apart from algae and calcite staining evident. A 0.6mm crack is evident to the west side of the north abutment with previously installed (2023) crack pips measuring 25.91mm. The cause of the crack is unconfirmed with no signs of differential settlement to the structure and may be a shrinkage crack from the construction stage linked to the mass concrete nature of the abutments. The crack was reported in the 2012 PI with no significant deterioration since.

See Photograph H-10 for the south abutment and see Photograph H-11 for the north abutment.

## Pier

The pier is in good condition apart from algae and calcite staining evident. Minor honeycombing evident to the east side upstream of the pier. Cracking sealed with calcite is evident to the north face of the pier. See Photograph H-12 and H-13 for a view of the northeast and south faces. See Photograph H-14 to view the cracking to the north face of the pier sealed with calcite.

## Bearings

Not applicable.

## Deck

The deck is in poor condition with multiple areas of spalling noted with exposed filler beams evident. Extensive delamination is noted throughout both spans which is concentrated below each beam location, with water seepage and calcite staining evident. Refer to the defect plan in Appendix C.

Previously installed crack pips (2023 PI) are located on a 0.5mm wide longitudinal crack in the north span, approximately 5m from the west elevation and measured 25.56mm at the time of inspection. The widespread cracking is attributed to the low bond capacity between the concrete and steel girders found by the assessment, resulting in the cracking and delamination of the concrete at each girder bottom flange.

See Photograph H-15 and H-16 for a general view of the north and south spans. See Photograph H-17 and H-18 for a view of cracking sealed with calcite and the exposed filler beam to the south span. See Photograph H-19 for a view



of cracking sealed with calcite, water staining and spalling to the north span and Photograph H-20 for a view of the exposed filler beam at the north span.

## Beams

Included in deck component above.

## Riverbed

The riverbed is in good condition with a 600mm high raised concrete apron provided under the south span of the structure to direct flow through the north span. See Photograph H-21.

## Overall Structure

The structure is in poor condition due to the defects to the deck slab soffit. See Photograph H-22 for the west elevation of the structure and Photograph H-23 for the east elevation of the structure.

## 5.2 Identification and justification of the condition factor used in the assessment calculations for each structural element

The condition factor for the reinforced concrete slab was taken as 0.8 for assessment purposes due to the delamination to the concrete soffit and areas of spalling with exposed filler beams. The condition factor decreased from 0.9 used in the previous Stage 1 assessment due to deterioration in the deck soffit with additional cracking, delamination and spalling noted.

## 5.3 Detailed description of the testing undertaken

The testing undertaken to the structure for the Stage 2 assessment by Triur Construction Ltd. in July 2024 comprised the following:

- 2no. concrete cores and strength testing to both spans(4no. total)
- 4no. pilot holes to confirm deck thickness
- 4no. areas of breakout to areas of the steel beams for condition survey (2no. internal 2no. external beams)
- Delamination survey to both spans
- Durability testing to 6no. areas (2no. top, 2no. fascias, 2no. soffits)
- Waterproofing pull off testing
- Covermeter & GPR survey to 1no. areas of abutments and pier with breakouts (3no. areas total)
- 2no. pilot holes to confirm abutment thickness
- Durability testing to 2no. areas of each substructure element (6no. total)

For further information on the structural investigations undertaken refer to Appendix E of this report.



## 5.4 Results of all testing undertaken

The trial pit to the concrete verge found a total depth of fill of 420mm with no waterproofing present on the deck slab. The pilot hole cores drilled through the deck varied from 300mm and 320 mm in depth. The steel beams encased in the deck slab comprised a 125mm high railway girder at 600mm spacing with 23x13mm transverse bars at 600mm spacing between the girders. The concrete strength of the slab varied between 18.9 N/mm<sup>2</sup> and 57.10 N/mm<sup>2</sup>.

For further information on the structural investigations results refer to Appendix E of this report.

## 5.5 Summary of safety partial factors used in the assessment

For the concrete, the values of  $\gamma_m$  is taken as 1.2 considering worst credible strengths which is taken from Table 4A (4.3.3.3.) of AM-STR-06031. For structural steel the  $\gamma_m$  is taken as 1.05.

The partial safety factors taken from *AM-STR-06030 Appendix A* are represented below in Table 5-1. Refer to Appendix G calculations for more details.

**Table 5-1 - Partial Safety Factors for Assessment**

Loading	$\gamma_{f3}$ for ULS	$\gamma_{fL}$ for ULS
Dead Load	1.1	1.15
Super Imposed Dead Load	1.1	1.75
Soil Fill	1.1	1.2
Type HA Loading	1.1	1.5
Type HB Loading	1.1	1.3
SV Loading	1.1	1.1

## 5.6 Summary of all material properties used in the assessment

Fill Material: (Structural fill)

Unit weight of fill = 22kN/m<sup>3</sup>

Angle of Friction,  $\phi = 30^\circ$

Road Surfacing:

Unit Weight = 24kN/m<sup>3</sup>

Filler beam concrete slab:

The estimated worst credible concrete strength of the concrete deck slab is taken as 18.9 N/mm<sup>2</sup>. This is based on compression testing data of concrete core samples and is derived in accordance with *AM-STR-06031*. In the absence of test data on the characteristic yield strength of the structural steel sections, it was assumed as 230 N/mm<sup>2</sup> as per AM-STR-06026 CI 4.3.



## 6. Assessment Method

### 6.1 Summary of analysis methodology undertaken as part of Stage 1 Structural Assessment

Assessment of the Filler Beam deck was carried out in accordance with the NRA Stage 1 Assessment Methodology Report (Revision C) and the methods outlined in the UK Highways Agency Design Manual for Roads and Bridges (BD21/01, BD44/95 & BA44/96). The structure was assessed using the strip method for HA loading, single axle and single wheel loads in accordance with BD21/01 and the methods outlined in BD44/95. A grillage analysis was also subsequently undertaken as part of the Stage 1 Assessment.

### 6.2 Detailed description of method of analysis undertaken for Stage 2 analysis including justification as to how this has led to an increase in the assessed capacity for the superstructure, substructure and foundations

The initial assessment of the filler beam deck slab was carried out using the strip analysis method as per *AM-STR-06026* and *AM-STR-06037* followed by a grillage analysis as per *AM-STR-06057*. A refined grillage analysis including transverse distribution and enhanced material properties from the structural investigations was used for the Stage 2 analysis. Using Midas Civil the main longitudinal members were defined as line elements and assigned composite section properties, which produced improved results compared to the stage 1 analysis.

The assessment live loading comprised 40t HA loading in accordance with TII Publication *AM-STR-06026*. Abnormal loading considered as part of the assessment comprised SV196 loading in accordance with TII Publication *AM-STR-06048 The Assessment of Road Bridges and Structures for the Effects of Abnormal and Exceptional Abnormal Load Vehicles using SV and SOV Load Models* and 45 Units HB loading in accordance with *AM-STR-06030 Loads for Highway Bridges*.

An increase in the bending capacity of the structure from the Stage 1 assessment when considering composite action was found due to the increase in the worst credible concrete strength as determined by the structural investigations. However, the check on the bond between the beams and the concrete slab to enable composite action found a reduced capacity for the structure of 7.5t.

### 6.3 Description of the model and software used for the analysis

The filler beam concrete slab was analysed with a grillage model using MIDAS Civil software. The grillage model was created with main longitudinal beams modelled as composite steel sections and transverse dummy elements for transverse distribution.

The diagram of the model and the model inputs are shown in Appendix F of this report.

## 6.4 Assessment live loading

Assessment live loading comprised 40t HA loading in accordance with TII Publication *AM-STR-06026*.

## 6.5 Abnormal loading

Abnormal loading considered as part of the assessment comprised SV196 loading in accordance with TII Publication *AM-STR-06048 The Assessment of Road Bridges and Structures for the Effects of Abnormal and Exceptional Abnormal Load Vehicles using SV and SOV Load Models* and 45 Units HB loading in accordance with *AM-STR-06030 Loads for Highway Bridges*.

## 6.6 Additional loading requirements

Dead and superimposed dead loads were applied to the structure based on the information gathered during the site investigation works and the inspection for assessment.

# 7. Assessment Commentary

## 7.1 Assumptions made during the Stage 2 Structural Assessment

The section property and capacity calculations of the composite steel beams were calculated in accordance with *BS 5400 Part 3:2000*. A condition factor of 0.8 was applied due to the delamination and spalling of the concrete deck soffit in both spans. As the year of construction and yield strength of the steel beams is unknown, a minimum yield strength of  $230\text{N/mm}^2$  was assumed for structural steel as per *AM-STR-06026 Cl 4.3*. The worst credible strength of concrete for the superstructure was taken as  $18.9\text{ N/mm}^2$  based on the findings of the structural investigations. Transverse distribution has been assumed across the deck based on structural investigations confirming the presence of transverse reinforcement in the slab. The dispersion of traffic loading through the fill was not considered due to the shallow depth of fill over the structure.

## 7.2 Significance of these assumptions in relation to the overall capacity of the structure or element

The filler beam structure is found to have sufficient loading for 40t HA loading when considering full composite action however the capacity is reduced due to bond failure in the section which prevents full composite action from occurring.



## 8. Assessment Results

The initial strip analysis undertaken for the Stage 2 assessment showed a bending capacity of 3t HA loading, with no capacity for HB and SV loading. The filler beam was found unsuitable for composite action as it failed under the bond stress check, resulting in a bond capacity of less than 3t GVW.

The bridge was also assessed using grillage analysis for live load capacity of 40t HA, combined HA+HB45, HB45, and SV196 loading with the results shown in Table 8-1 below as per the guidance from *AM-STR-06057*. The detailed calculations for each load case are provided in Appendix G of this report.

**Table 8-1 – Grillage Assessment results for Filler beam slab**

Element	Load Effect	$R_A^*$	$S_D^*$	$S_{HA40t}^*$	$S_{HA+HB45}^*$	$S_{HB45}^*$	$S_{SV196}^*$	$R_A^*/S_A^*$
Filler beam concrete slab	Moment near Support (Sagging) (kNm)	73	5	12	20	14	18	3.64
	Max. Sagging Moment (kNm)	73	17	56	84	75	66	0.87
	Max. Shear (kN)	101	53	85	146	121	110	0.69
	Bond Capacity	7.5t			< HB 30 units		< SV 80	

Where

- $R_A^*$  = Assessment Resistance (flexure, shear etc.)
- $S_D^*$  = Assessment load effects due to dead and superimposed dead loads
- $S_{HA}^*$  = Assessment load effect due to the associated Type HA loading and Permanent loads (ULS)
- $S_{HA+HB}^*$  = Assessment load effect due to the Combined Type HA+HB loading and Permanent loads (ULS)
- $S_{HB}^*$  = Load effect due to HB loading and Permanent loads (ULS)
- $S_{SV}^*$  = Load effect due to Special Vehicle loading and Permanent loads (ULS)
- $S_A^*$  = Assessment load effects (Maximum of ULS Combination)
- $R_A^*/S_A^*$  = Structural Assessment Factor (shown for the critical case from the ULS cases)

The grillage analysis determined a reduction in the assessment load effects due to the transverse distributions of loads, which resulted in a bending capacity of 40t GVW for the structure when considering composite action. The bond capacity of the section limits the slab capacity to 7.5t however.

The assessment summary is provided in the Table 8-2 below.

**Table 8-2 - Assessment summary for Structure**

Structure ID	Structure Name	Structure Type	No. of Spans	Span Length	Assessed Capacity (ALL)	HB Capacity	SV Capacity
MO-N58-001.00	Strade Bridge	Filler Beam	2	3.82m / 3.79m	7.5t	Fails HB30 units	Fails SV80



## 9. Recommendations

Based on the findings of the assessment the structure is determined to have a reduced load capacity due to bond failure between the concrete and steel beams with the significant delamination and spalling visible to the deck slab soffit providing evidence of the issue. As a result no further assessment measures are deemed required for the structure as they are not likely to increase the bond capacity to 40t loading due to the low compressive strength values found for the concrete in the soffit of the structure. The deck slab is therefore recommended to be either strengthened or replaced.

Due to the extensive defects to the soffit of the structure and the presence of railway girders acting as primary structural members the strengthening of the structure is not recommended. A full deck replacement is instead recommended with the existing deck slab removed and a new deck installed across the structure, in either a single or two span arrangement.

Although there are extensive defects to the deck soffit as there is no evidence of failure or excess deformation of the slab a load restriction is not recommended at this time. Monitoring of the structure should be taken annually however to check for any further evidence of deformation or failure of the deck. Regular term maintenance should also be undertaken to the structure to maintain its condition in the interim.



# Appendices

# Appendix A. Archive Information about the Structure



## MO-N58-001.00 Strade River Bridge

Maintaining Agent.....: 23 MO - Mayo  
Road.....: Bellavary - Foxford, County Mayo  
Side of road.....: 0  
Region.....: 1 Connacht\Ulster  
Struct. reg. no.....: 1155  
  
Year of construction.....:  
Year of reconstruction.....:  
Primary passage Overbridge/Underbridge: U  
Dir. of chainage on primary road.....: N  
Access equipment needed.....: 0 Nothing  
  
Data collected: Date .....: 15 May 2024  
Inspector Initials.....: CS  
Checker Initials.....: CP

**MO-N58-001.00 Strade River Bridge****Geographical position (ITM):**

Easting: 525752.652

Northing: 797496.734

**Geometry:**

Number of spans.....:	2
Min span length.....(m):	3.79
Max span length.....(m):	3.79
Overall length.....(m):	8.70
Width out-to-out.....(m):	10.30
Width of median.....(m):	0.00
Width of footway left.....(m):	1.67
Width of footway right.....(m):	1.09
Width of carriageway.....(m):	5.70
Width kerb-to-kerb.....(m):	6.90
Width of approach.....(m):	5.70
Area.....(m2):	89.61
Minimum Parapet Height....(m):	0.88
Width of Soft Verge Left..(m):	0.00
Width of Soft Verge Right.(m):	0
Approach Skew 1.....(deg):	15.00
Approach Skew 2.....(deg):	15.00
Bridge curved.....(Y/N):	N
Skew.....(deg):	30

**Span Lengths:**

Span 1...(m): 3.79	Span 6...(m):	Span 11...(m):
Span 2...(m): 3.79	Span 7...(m):	Span 12...(m):
Span 3...(m):	Span 8...(m):	Span 13...(m):
Span 4...(m):	Span 9...(m):	Span 14...(m):
Span 5...(m):	Span 10...(m):	

**MO-N58-001.00 Strade River Bridge****Superstructure, principal type:**

Standard design .....(Y/N):	Y	
Design of cross section.....:	10	Slab
Design of elevation.....:	40	Frame, constant cross section
Material of primary members.....:	42	Composite steel & concrete

**Superstructure, secondary type (if applicable):**

Standard design .....(Y/N):	N	
Design of cross section.....:	91	Not applicable
Design of elevation.....:	91	Not applicable
Material of primary members.....:	91	Not applicable

**Superstructure, tertiary type (if applicable):**

Standard design .....(Y/N):	N	
Design of cross section.....:	91	Not applicable
Design of elevation.....:	91	Not applicable
Material of primary members.....:	91	Not applicable

**Substructure:**

Abutment: Type.....:	10	Abutm. wall, integ. wing walls
Material.....:	21	Reinforced concrete
Foundation.....:	92	Unknown
Pier: Type.....:	10	Solid wall
Material.....:	21	Reinforced concrete
Foundation.....:	92	Unknown

**MO-N58-001.00 Strade River Bridge****Details:**

Type of parapet.....:	30	Concrete cast in situ
Type of safety barrier.....:	0	No guard rail
Type of wearing surface.....:	23	Hot rolled asphalt
Type of expansion joint.....:	91	Not applicable
Type of fixed bearings on support...:	91	Not applicable
Type of free bearings on support...:	91	Not applicable
Type of fixed bearings on girders...:	91	Not applicable
Type of free bearings on girders...:	91	Not applicable

**Obstacle:**

Type of passage.....:	31	River
Passage id.....:		RIVER
Passage name.....:		Strade River
Road side.....:		

**Vertical Clearance:**

Primary passage.....(m):	L:	LM:	RM:	R:
Secondary passage.....(m):	L: 2.33	LM: 2.33	RM: 2.33	R: 2.33

**Miscellaneous:**

Design Load.....:		
Load Distribution.....:	2	Distribution in 1 direction
Technical Standards.....:	0	Unknown standard
Assessed Capacity Normal.....:	7	18T GVW
Assessed Capacity Abnormal.....:	32	30 Units HB
Weight Restriction.....:	1	N/A
Owner:	23	Mayo County Council
Maintaining Agent.....:	23	Mayo County Council
Inspection Consultant.....:	96	Atkins
Designer/Consultant.....:	92	Unknown
Technical installations.....:	2	Other electrical installation
	4	Water supply pipeline

MO-N58-001.00 Strade River Bridge

Remarks:

The deck slab comprises a composite filler beam slab construction.

The vertical clearance at the north span is 2.33m and the south span is 1.65m.

The skew span is 3.79m and the square span is 3.44m for both spans.

Technical installations over the structure include a water main and overhead ESB.

The 2012 Stage 1 Report gives a capacity of 18 tonnes in bending however this reduces to less than 3 tonnes when bond stress is considered.

Chronological Overview		1	2	3	4	5	6	7	8	9	10	11	12	13	14
Date	Activity	Br	Ex	Fo	Pa	Em	Wi	Ab	Pi	Be	De	Be	Ri	Ot	St
Remarks															
01 Jan 2012	Assessment	Stage 1 / 18T GVW / Y													
Bending Mid-Span															
14 Aug 2012	Principal inspection	0	-	2	1	0	0	1	1	-	2	-	0	-	2
18 Aug 2017	Principal inspection	2	-	-	1	0	0	1	1	-	1	-	1	-	1
09 Mar 2022	Principal inspection	1	-	0	0	1	0	1	1	-	2	-	1	-	2
29 May 2023	Principal inspection	1	-	1	1	1	1	2	1	-	3	1	1	-	3
15 May 2024	Principal inspection	1	-	0	0	1	1	2	1	-	3	-	0	-	3

MO-N58-001.00 Strade River Bridge

**Principal Inspection:**

Date.....:	15 May 2024
Team Leader Name.....:	Curtis Swanepoel
Initials.....:	CS
Weather.....:	Sunny
Temperature.....(deg. C):	14
Traffic:Annual Average Daily Traffic.:	6274
Percentage, light vehicles...:	96
Percentage, heavy vehicles...:	4
Year for next Principal Inspection...:	2025

**Remark:**

AADT Information sourced from TII Traffic Counter Data from  
'TMU N58 010.0 N' in year 2023, based on 100% coverage.

## MO-N58-001.00 Strade River Bridge

No	Component  Repair work Damage description Type of damage				Repair Work				
		Con rtg	Mtn req	Spe Ins	T P	Qty	Year	Cost	Pho tos
1	<b>Bridge surface</b>  The bridge surface is in good condition overall, see Pl.1 for a view north. There is cracking evident to the carriageway at the northwest corner to be sealed during routine maintenance, see Pl.2.	1	Y	N					2
2	<b>Expansion joints</b>	-		N					0
3	<b>Footways/median</b>  The rubbing strips are both in good condition, see P3.1 for a view of the eastern rubbing strip.	0	N	N					1
4	<b>Parapets/Safety barrier</b>  The parapets are in good condition, see P4.1 for a view of the western parapet.	0	N	N					1
5	<b>Embankments/Revetments</b>  The embankments are in a good condition apart from vegetation growth that should be cut back from all the embankments during RM, see P5.1 for a view of the southeast embankment.	1	Y	N					1
6	<b>Wing/Spandrel/Retaining Walls</b>  The wing walls are in good condition, see P6.1 for a view of the northeast wing wall. There is a previous repair evident to the northwest wing wall, see P6.2.	1	N	N					2
7	<b>Abutments</b>	2	N	N					2

**MO-N58-001.00 Strade River Bridge**

No	Component				Repair Work				
		Con rtg	Mtn req	Spe Ins	T P	Qty	Year	Cost	Pho tos
	<p>E : Injection of cracks</p> <p>Both abutments are in a fair condition, see P7.1 for view of the southern abutment. The previously reported crack to the west side of the northern abutment remains 0.6mm wide, see P7.2. The previously installed crack pips have a measurement of 25.91mm (The previous base reading 23.1mm is confirmed to be incorrect with 25.91mm the new base reading). The crack should be injection repaired.</p> <p>Cracking of concrete</p>				E	1	2026	500	
	<p><b>8 Piers</b></p> <p>The pier is in a good overall condition, see P8.1 for view of the south face of the pier looking east. There is minor honeycombing to the east side upstream of the pier which requires no action, see P8.2. There is a crack sealed with calcite on the concrete protection to the north face of the pier, see P8.3.</p>	1	N	N					3

MO-N58-001.00 Strade River Bridge

No	Component  Repair work Damage description Type of damage				Repair Work				
		Con rtg	Mtn req	Spe Ins	T P	Qty	Year	Cost	Pho tos
9	Bearings	-		N					0
10	Deck/slab/arch barrel	3	N	N					6
	A : Concrete repair (without reinforcement)				A	6	2025	3210	

## MO-N58-001.00 Strade River Bridge

The deck is in a poor condition, see P10.1 for view of the southern span deck looking east with areas of spalling evident below the filler beams. There is spalling with exposed beams in the northern span also, see P10.2. See P10.3 for closer view of large spalling to the south span deck. All areas of spalling should be repaired. There are longitudinal cracks that are self healed with calcite on the east and west side of the deck under the headwalls of the northern span. There are also longitudinal cracks that are self healed with calcite on the east side of the southern span, see P10.4.

There is a 0.5mm wide longitudinal crack in the northern span located 5.35m from the western elevation. Previously installed crack pips have a reading of 25.56mm (The previous base reading of 23.4mm is confirmed to be incorrect, with 25.56mm the new base reading), see P10.5. All cracks appear to be replicating the behaviour of spalling of the exposed beams with widespread delamination identified.

The 2012 Stage 1 Assessment report indicated that the structure is substandard due to failure of bond stress checks in the deck. The spalling and delamination of concrete noted above is consistent with debonding of the concrete to the soffit of the steel beams. Otherwise there was no deformation or transverse cracking in the deck that would suggest failure in bending/shear. The condition of the deck does not appear to have deteriorated further since the last PI.



MO-N58-001.00 Strade River Bridge

Component No.	1	Bridge surface
---------------	---	----------------

The bridge surface is in good condition overall, see P1.1 for a view north. There is cracking evident to the carriageway at the northwest corner to be sealed during routine maintenance, see P1.2.

Condition/Mainten. 1 / Y



MO-N58-001.00 Strade River Bridge

Component No.	1	Bridge surface
The bridge surface is in good condition overall, see P1.1 for a view north. There is cracking evident to the carriageway at the northwest corner to be sealed during routine maintenance, see P1.2.		
Condition/Mainten.	1	/ Y



MO-N58-001.00 Strade River Bridge

Component No.	3	Footways/median
---------------	---	-----------------

The rubbing strips are both in good condition, see P3.1 for a view of the eastern rubbing strip.

Condition/Mainten. 0 / N



MO-N58-001.00 Strade River Bridge


Component No.	4	Parapets/Safety barrier
The parapets are in good condition, see P4.1 for a view of the western parapet.		
Condition/Mainten.	0	/ N
<div><div>P4.1</div></div>		

MO-N58-001.00 Strade River Bridge

Component No.	5	Embankments/Revetments
The embankments are in a good condition apart from vegetation growth that should be cut back from all the embankments during RM, see P5.1 for a view of the southeast embankment.		
Condition/Mainten.	1	/ Y



MO-N58-001.00 Strade River Bridge

Component No.	6	Wing/Spandrel/Retaining Walls
The wing walls are in good condition, see P6.1 for a view of the northeast wing wall. There is a previous repair evident to the northwest wing wall, see P6.2.		
Condition/Mainten.	1	/ N
<div><div>P6.1</div><div></div></div>		

15/05/2024

MO-N58-001.00 Strade River Bridge

Component No.	6	Wing/Spandrel/Retaining Walls
The wing walls are in good condition, see P6.1 for a view of the northeast wing wall. There is a previous repair evident to the northwest wing wall, see P6.2.		
Condition/Mainten.	1	/ N




MO-N58-001.00 Strade River Bridge

Component No.	7	Abutments
Both abutments are in a fair condition, see P7.1 for view of the southern abutment. The previously reported crack to the west side of the northern abutment remains 0.6mm wide, see P7.2. The previously installed crack pips have a measurement of 25.91mm (The previous base reading 23.1mm is confirmed to be incorrect with 25.91mm the new base reading). The crack should be injection repaired.		
Condition/Mainten.	2	/ N



MO-N58-001.00 Strade River Bridge

Component No.	7	Abutments
<p>Both abutments are in a fair condition, see P7.1 for view of the southern abutment. The previously reported crack to the west side of the northern abutment remains 0.6mm wide, see P7.2. The previously installed crack pips have a measurement of 25.91mm (The previous base reading 23.1mm is confirmed to be incorrect with 25.91mm the new base reading). The crack should be injection repaired.</p> <p>Condition/Mainten.                      2   /   N</p>		
<div><div>P7.2</div></div>		
15/05/2024		

MO-N58-001.00 Strade River Bridge

Component No.	8	Piers
The pier is in a good overall condition, see P8.1 for view of the south face of the pier looking east. There is minor honeycombing to the east side upstream of the pier which requires no action, see P8.2. There is a crack sealed with calcite on the concrete protection to the north face of the pier, see P8.3.		
Condition/Mainten.	1	/ N



MO-N58-001.00 Strade River Bridge

Component No.	8	Piers
---------------	---	-------

The pier is in a good overall condition, see P8.1 for view of the south face of the pier looking east. There is minor honeycombing to the east side upstream of the pier which requires no action, see P8.2. There is a crack sealed with calcite on the concrete protection to the north face of the pier, see P8.3.

Condition/Mainten. 1 / N



MO-N58-001.00 Strade River Bridge

Component No.	8	Piers
---------------	---	-------

The pier is in a good overall condition, see P8.1 for view of the south face of the pier looking east. There is minor honeycombing to the east side upstream of the pier which requires no action, see P8.2. There is a crack sealed with calcite on the concrete protection to the north face of the pier, see P8.3.

Condition/Mainten. 1 / N



## MO-N58-001.00 Strade River Bridge

Component No.	10	Deck/slab/arch barrel
<p>The deck is in a poor condition, see P10.1 for view of the southern span deck looking east with areas of spalling evident below the filler beams. There is spalling with exposed beams in the northern span also, see P10.2. See P10.3 for closer view of large spalling to the south span deck. All areas of spalling should be repaired. There are longitudinal cracks that are self healed with calcite on the east and west side of the deck under the headwalls of the northern span. There are also longitudinal cracks that are self healed with calcite on the east side of the southern span, see P10.4.</p> <p>There is a 0.5mm wide longitudinal crack in the northern span located 5.35m from the western elevation. Previously installed crack pips have a reading of 25.56mm (The previous base reading of 23.4mm is confirmed to be incorrect, with 25.56mm the new base reading), see P10.5. All cracks appear to be replicating the behaviour of spalling of the exposed beams with widespread delamination identified.</p> <p>The 2012 Stage 1 Assessment report indicated that the structure is substandard due to failure of bond stress checks in the deck. The spalling and delamination of concrete noted above is consistent with debonding of the concrete to the soffit of the steel beams. Otherwise there was no deformation or transverse cracking in the deck that would suggest failure in bending/shear. The condition of the deck does not appear to have deteriorated further since the last PI.</p> <p>Condition/Mainten.                    3   /   N</p>		

MO-N58-001.00 Strade River Bridge

**P10.1**



## MO-N58-001.00 Strade River Bridge

Component No.	10	Deck/slab/arch barrel
<p>The deck is in a poor condition, see P10.1 for view of the southern span deck looking east with areas of spalling evident below the filler beams. There is spalling with exposed beams in the northern span also, see P10.2. See P10.3 for closer view of large spalling to the south span deck. All areas of spalling should be repaired. There are longitudinal cracks that are self healed with calcite on the east and west side of the deck under the headwalls of the northern span. There are also longitudinal cracks that are self healed with calcite on the east side of the southern span, see P10.4.</p> <p>There is a 0.5mm wide longitudinal crack in the northern span located 5.35m from the western elevation. Previously installed crack pips have a reading of 25.56mm (The previous base reading of 23.4mm is confirmed to be incorrect, with 25.56mm the new base reading), see P10.5. All cracks appear to be replicating the behaviour of spalling of the exposed beams with widespread delamination identified.</p> <p>The 2012 Stage 1 Assessment report indicated that the structure is substandard due to failure of bond stress checks in the deck. The spalling and delamination of concrete noted above is consistent with debonding of the concrete to the soffit of the steel beams. Otherwise there was no deformation or transverse cracking in the deck that would suggest failure in bending/shear. The condition of the deck does not appear to have deteriorated further since the last PI.</p> <p>Condition/Mainten.                    3   /   N</p>		

MO-N58-001.00 Strade River Bridge

**P10.2**

## MO-N58-001.00 Strade River Bridge

Component No.	10	Deck/slab/arch barrel
<p>The deck is in a poor condition, see P10.1 for view of the southern span deck looking east with areas of spalling evident below the filler beams. There is spalling with exposed beams in the northern span also, see P10.2. See P10.3 for closer view of large spalling to the south span deck. All areas of spalling should be repaired. There are longitudinal cracks that are self healed with calcite on the east and west side of the deck under the headwalls of the northern span. There are also longitudinal cracks that are self healed with calcite on the east side of the southern span, see P10.4.</p> <p>There is a 0.5mm wide longitudinal crack in the northern span located 5.35m from the western elevation. Previously installed crack pips have a reading of 25.56mm (The previous base reading of 23.4mm is confirmed to be incorrect, with 25.56mm the new base reading), see P10.5. All cracks appear to be replicating the behaviour of spalling of the exposed beams with widespread delamination identified.</p> <p>The 2012 Stage 1 Assessment report indicated that the structure is substandard due to failure of bond stress checks in the deck. The spalling and delamination of concrete noted above is consistent with debonding of the concrete to the soffit of the steel beams. Otherwise there was no deformation or transverse cracking in the deck that would suggest failure in bending/shear. The condition of the deck does not appear to have deteriorated further since the last PI.</p> <p>Condition/Mainten.                    3   /   N</p>		

MO-N58-001.00 Strade River Bridge



## MO-N58-001.00 Strade River Bridge

Component No.	10	Deck/slab/arch barrel
<p>The deck is in a poor condition, see P10.1 for view of the southern span deck looking east with areas of spalling evident below the filler beams. There is spalling with exposed beams in the northern span also, see P10.2. See P10.3 for closer view of large spalling to the south span deck. All areas of spalling should be repaired. There are longitudinal cracks that are self healed with calcite on the east and west side of the deck under the headwalls of the northern span. There are also longitudinal cracks that are self healed with calcite on the east side of the southern span, see P10.4.</p> <p>There is a 0.5mm wide longitudinal crack in the northern span located 5.35m from the western elevation. Previously installed crack pips have a reading of 25.56mm (The previous base reading of 23.4mm is confirmed to be incorrect, with 25.56mm the new base reading), see P10.5. All cracks appear to be replicating the behaviour of spalling of the exposed beams with widespread delamination identified.</p> <p>The 2012 Stage 1 Assessment report indicated that the structure is substandard due to failure of bond stress checks in the deck. The spalling and delamination of concrete noted above is consistent with debonding of the concrete to the soffit of the steel beams. Otherwise there was no deformation or transverse cracking in the deck that would suggest failure in bending/shear. The condition of the deck does not appear to have deteriorated further since the last PI.</p> <p>Condition/Mainten.                      3   /   N</p>		

MO-N58-001.00 Strade River Bridge

**P10.4**



## MO-N58-001.00 Strade River Bridge

Component No.	10	Deck/slab/arch barrel
<p>The deck is in a poor condition, see P10.1 for view of the southern span deck looking east with areas of spalling evident below the filler beams. There is spalling with exposed beams in the northern span also, see P10.2. See P10.3 for closer view of large spalling to the south span deck. All areas of spalling should be repaired. There are longitudinal cracks that are self healed with calcite on the east and west side of the deck under the headwalls of the northern span. There are also longitudinal cracks that are self healed with calcite on the east side of the southern span, see P10.4.</p> <p>There is a 0.5mm wide longitudinal crack in the northern span located 5.35m from the western elevation. Previously installed crack pips have a reading of 25.56mm (The previous base reading of 23.4mm is confirmed to be incorrect, with 25.56mm the new base reading), see P10.5. All cracks appear to be replicating the behaviour of spalling of the exposed beams with widespread delamination identified.</p> <p>The 2012 Stage 1 Assessment report indicated that the structure is substandard due to failure of bond stress checks in the deck. The spalling and delamination of concrete noted above is consistent with debonding of the concrete to the soffit of the steel beams. Otherwise there was no deformation or transverse cracking in the deck that would suggest failure in bending/shear. The condition of the deck does not appear to have deteriorated further since the last PI.</p> <p>Condition/Mainten.                    3   /   N</p>		

MO-N58-001.00 Strade River Bridge

**P10.5**



15/05/2024

## MO-N58-001.00 Strade River Bridge

Component No.	10	Deck/slab/arch barrel
<p>The deck is in a poor condition, see P10.1 for view of the southern span deck looking east with areas of spalling evident below the filler beams. There is spalling with exposed beams in the northern span also, see P10.2. See P10.3 for closer view of large spalling to the south span deck. All areas of spalling should be repaired. There are longitudinal cracks that are self healed with calcite on the east and west side of the deck under the headwalls of the northern span. There are also longitudinal cracks that are self healed with calcite on the east side of the southern span, see P10.4.</p> <p>There is a 0.5mm wide longitudinal crack in the northern span located 5.35m from the western elevation. Previously installed crack pips have a reading of 25.56mm (The previous base reading of 23.4mm is confirmed to be incorrect, with 25.56mm the new base reading), see P10.5. All cracks appear to be replicating the behaviour of spalling of the exposed beams with widespread delamination identified.</p> <p>The 2012 Stage 1 Assessment report indicated that the structure is substandard due to failure of bond stress checks in the deck. The spalling and delamination of concrete noted above is consistent with debonding of the concrete to the soffit of the steel beams. Otherwise there was no deformation or transverse cracking in the deck that would suggest failure in bending/shear. The condition of the deck does not appear to have deteriorated further since the last PI.</p> <p>Condition/Mainten.                      3   /   N</p>		

MO-N58-001.00 Strade River Bridge

**P10.6**

MO-N58-001.00 Strade River Bridge

Component No.	12	Riverbed
The riverbed is in good condition, see P12.1 for a view downstream east.		
Condition/Mainten.	0	/ N



## MO-N58-001.00 Strade River Bridge

Component No.	14	Structure in general
<p>The structure is in a fair condition with cracking to the northern abutment and spalling and delamination to the southern and northern deck slabs with exposed beams evident. Routine Maintenance is also required. See P14.1 and P14.2 for views of the western and eastern elevations respectively.</p> <p>The inspection of the structure has been undertaken in accordance with the requirements of TII AM-STR-06039 (BD 79) outside of the normal PI schedule due to the 2012 Stage 1 Assessment Report finding the structure to have a reduced load capacity due to failure of the bond stress checks between the filler beams and surrounding concrete.</p> <p>Condition/Mainten.                      3   /   Y</p>		

**P14.1**

15/05/2024

## MO-N58-001.00 Strade River Bridge

Component No.	14	Structure in general
<p>The structure is in a fair condition with cracking to the northern abutment and spalling and delamination to the southern and northern deck slabs with exposed beams evident. Routine Maintenance is also required. See P14.1 and P14.2 for views of the western and eastern elevations respectively.</p> <p>The inspection of the structure has been undertaken in accordance with the requirements of TII AM-STR-06039 (BD 79) outside of the normal PI schedule due to the 2012 Stage 1 Assessment Report finding the structure to have a reduced load capacity due to failure of the bond stress checks between the filler beams and surrounding concrete.</p> <p>Condition/Mainten.                      3   /   Y</p>		

**P14.2**

**STRADE RIVER BRIDGE**  
**STRUCTURE ID: MO-N58-001.00**  
**STAGE I ASSESSMENT REPORT**



**Revision 0**  
**May 2012**

## EIRSPAN BRIDGE MANAGEMENT SYSTEM

### TASK ORDER NO. 213 : STAGE 1 STRUCTURAL ASSESSMENTS OF BRIDGES IN DONEGAL, SLIGO, MAYO AND GALWAY

#### STRADE RIVER BRIDGE

STRUCTURE ID: MO-N58-001.00

#### STAGE 1 ASSESSMENT REPORT

#### Notice

This document has been produced by ATKINS solely for the purpose of the Eirspan Bridge Management System. It may not be used by any person for any other purpose other than that specified without the express written permission of ATKINS. Any liability arising out of use by a third party of this document for purposes not wholly connected with the above shall be the responsibility of that party who shall indemnify ATKINS against all claims costs damages and losses arising out of such use.

#### Document History

PROJECT NO.: 3044			DOCUMENT REF: DG-TO213-69 Local Reference: 3044/30/32/321			
Revision	Purpose and Description	Originated	Checked	Reviewed	Authorised	Date
0	NRA Approval	S. Counihan	C. Maunsell	P. Garg	M. Jennings	31.05.12

## **CONTENTS**

<b>Executive Summary</b>	<b>1</b>
<b>Location Map</b>	<b>2</b>
<b>1.0 Introduction</b>	<b>3</b>
<b>2.0 Description of Structure</b>	<b>3</b>
<b>3.0 Visual Inspection of structure</b>	<b>3</b>
<b>4.0 Site Investigation Results</b>	<b>4</b>
<b>5.0 Assessment of Structure</b>	<b>5</b>
<b>6.0 Conclusions</b>	<b>7</b>
<b>7.0 Recommendations</b>	<b>8</b>

## **APPENDICES**

<b>Appendix A: Sketches</b>
<b>Appendix B: Photographs</b>
<b>Appendix C: Site Investigation Results</b>
<b>Appendix D: Calculations</b>
<b>Appendix E: Sub-Standard Structure Summary</b>
<b>Appendix F: Interim Measures Feasibility Assessment</b>

## Executive Summary

Strade River Bridge, MO-N58-001.00 carries the N58 national secondary road across the Strade River in County Mayo. This bridge is a two span Filler Beam deck structure with skew spans of 3.81m and 3.79m, and square spans of 3.56m and 3.34m.

Assessment of this structure was carried out in accordance with the NRA Stage 1 Assessment Methodology Report (Revision C) and the methods outlined in the UK Highways Agency Design Manual for Roads and Bridges (BD21/01, BD44/95 & BA44/96 for the RC Slab). A summary of Stage 1 Assessment Results is presented in the following table.

Structure ID	Structure Name	Structure Type	No of Spans	Skew Span Lengths (m)	Assessed Capacity	HB Rating
MO-N58-001.00	Strade River Bridge	Filler Beam	2	Span 1: 3.81	18t Bending 40t Shear <3t Bond	30HB Bending 45HB Shear <30HB Bond
				Span 2: 3.79	40t Bending 40t Shear <3t Bond	30HB Bending 45HB Shear <30HB Bond

**Table 1.0: Structure Assessment Summary Results**

A site investigation was carried out by Stanger Testing Services Limited for this structure to establish the concrete slab thickness, concrete strength and layout and cover to the filler beams.


The Stage 1 Assessment of the filler beam deck structure indicated that both spans could withstand 7.5 tonnes assessment in bending and 40 tonnes in shear, however the bond load capacity was less than 3 tonnes for both spans. As the adequacy of the structures in bending for 40t live loading was 60% for span 1 and 73% for span 2 using the strip method, a grillage analysis was carried out, which increased the load capacity of the structures in bending to 18 tonnes assessment loading for Span 1 and to 40 tonnes for Span 2.

A low concrete strength and low area of steel components are the main causes of the low carrying capacity of the structure.

The following works are recommended for the structure:

- (i) Stage 2 Assessment of the filler beam deck in the form of Plastic Analysis or Finite Element Method and subsequent strengthening using FRP plates or similar;
- (ii) The grass verges on both sides of the carriageway should be replaced with paved/raised verges and the entire structure should be waterproofed (such as impermeable layer should be placed under the pavement);
- (iii) Both parapets should be upgraded to meet current standards.

It is recommended that the structure be inspected in year 2012, as per the Principal Inspection Report dated 1<sup>st</sup> October, 2008.



ORDNANCE SURVEY IRELAND LICENCE No. AR 0082511  
© ORDNANCE SURVEY IRELAND / GOVERNMENT OF IRELAND

## 1.0 Introduction

Atkins was appointed by the National Roads Authority in August 2011 to carry out the structural assessment of 136 bridges in Donegal, Sligo, Mayo and Galway as part of Task Order 213.

Strade River Bridge MO-N58-001.00, which is located in County Mayo and carries the N58 across the Strade River, is a part of this Task Order. The co-ordinates of the structure are:

Latitude Y: 297482.729

Longitude X: 125785.401

The most recent Principal Inspection of this structure was carried out on 1<sup>st</sup> October, 2008. An Inspection for Assessment was carried out by Atkins on 18<sup>th</sup> December, 2011.

The layout of the Assessment Report follows the layout as described in Section 7 of the NRA Stage 1 Assessment Methodology Report, Rev C.

## 2.0 Description of Structure

Strade River Bridge is a two span Filler Beam deck structure with skew spans of 3.81m and 3.79m, and square spans of 3.56m and 3.34m.

The structure carries the N58 national secondary route across the Strade River. The overall width of the structure from outside of the west parapet to the outside of the east parapet is 10.17m (skew length 11.54m).

## 3.0 Visual Inspection of structure

### General:

The visual inspection was carried out in dry weather from the river, inside the structure and from the carriageway over the bridge. Photos are given in Appendix B. Eastern and western elevations of the structure are shown in photos 1 & 2. The structure was on a straight alignment.

### Surfacing:

The surfacing of the 5.62m wide carriageway was noted to be in good condition, apart from minor wear. There were no obvious signs of rutting or ponding over the main carriageway. Road markings were showing signs of wear (Ref. photo 3, 4 & 5).

### Footways/verges:

There were no footways on this structure. There were 0.42m wide hard strips on both sides of the carriageway. Additionally, there was a 1.80m wide grassed verge on the west side of the structure and a 1.45m wide grassed verge on the east side (Ref. photo 6 & 7).

#### **Parapet walls / Headwalls:**

There were concrete parapets and spandrel walls on both sides of the structure.

The western parapet was 980mm high and the eastern parapet was 930mm high. Both parapets were 230mm thick. Both parapets were in good condition. Cracks to both parapets as outlined in the previous Principal Inspection Report have been repaired and the ivy growth removed (Ref. photo 6 & 7).

Both head walls were in good condition and there was no defects recorded (Ref. photo 8 & 9).

#### **Deck:**

The thickness of the Filler Beam deck was 340mm. The deck slab was noted to be in good condition, apart from some minor water seepage, calcite staining and stalactites in span 1 at the eastern end. There was also water seepage noted under span 2 at the western end (Ref. photo 10 & 11). The cracks identified in the previous principal inspection have been repaired and were not detected at the time of inspection.

#### **Abutments / Pier:**

There were concrete abutments on both sides of the structure. The abutments were noted to be in good condition, apart from honeycombing noted to both components (Ref. photo 12 & 13). There was 210mm wide x 230mm high scour protection on the southern abutment and the south face of the pier. There was also 210mm wide x 770mm high scour protection on the abutment and north face of the pier. The pier was in good condition apart from honeycombing to the east cut water as outlined in the previous inspection. The ivy growth has been removed from the west face of the pier (Ref. photo 14).

#### **River Bed:**

The riverbed was in good condition. The river bed in span 1 had a raised 540mm thick concrete apron and was dry at the time of inspection (Ref. photo 15 to 18).

## **4.0 Site Investigation Results**

Stanger Testing Services Limited carried out the intrusive site investigations at this structure.

As part of the site investigations, a trial pit was excavated over the Filler Beam deck to establish the internal thickness of the slab and the depth of the fill. The site investigation also showed that the deck was waterproofed.

Four covermeter scans were carried out to the soffit of the RC beam and slab deck to establish the beam spacing, arrangement and orientation. Additionally, 2 no. breakouts were performed at the base of the slab to determine the articulation.

3 no. cores were extracted from the deck soffit of each span. The cores were then sent for laboratory compression testing.

For full details and results of the site investigation, refer to Appendix C for Site Investigation Report.

## 5.0 Assessment of Structure

### Assessment of Filler Beam Deck Structure:

Assessment of this Filler Beam Deck structure was carried out in accordance with the NRA Stage 1 Assessment Methodology Report (Revision C) and the methods outlined in the UK Highways Agency Design Manual for Roads and Bridges (BD21/01, BD44/95 & BA44/96). The structure was assessed using the strip method for HA loading, single axle and single wheel loads in accordance with BD21/01 and the methods outlined in BD44/95. Due to water seepage, a condition factor of 0.9 was assumed for both spans of the Filler Beam Deck. Both spans were assessed separately.

As per the Stage 1 assessment, the live load capacity of both spans was 7.5 tonnes Gross Vehicle Weight (GVW) for bending and 40 tonnes for shear. An additional check carried out on the bond also indicated the capacity of the structure of less than 3 tonnes assessment loading for both spans. The results are summarised in Table 5.1a & 5.1b.

Assessment Live Load Capacity			
	HA UDL & KEL	Single Axle Load	Single Wheel Load
<b>Bending</b>	40t	7.5t	7.5t
<b>Shear</b>	40t	40t	40t
<b>Bond</b>	<3t	-	-
Hence Overall Rating of <3t			

**Table 5.1a Assessed RC Slab Load Capacity – Span 1**

Assessment Live Load Capacity			
	HA UDL & KEL	Single Axle Load	Single Wheel Load
<b>Bending</b>	40t	7.5t	7.5t
<b>Shear</b>	40t	40t	40t
<b>Bond</b>	<3t	-	-
Hence Overall Rating of <3t			

**Table 5.1b Assessed RC Slab Load Capacity – Span 2**

Using strip method analysis, the adequacy of the structure in bending was only 60% for span 1 and 73% for span 2 for 40t single wheel loading. Hence, a grillage analysis was carried out for the structure, which increased the bending load capacity of the structure to 18 tonnes assessment loading for span 1 and to 40 tonnes assessment loading for span 2. The results are summarised in Table 5.2a & 5.2b.

Live Load Capacity – Grillage Analysis	
Bending	18 t
Shear	40 t
Bond	<3 t
Hence Overall Rating of <b>&lt;3 t</b>	

**Table 5.2a Assessed Grillage Analysis Load Capacity – Span 1**

Live Load Capacity – Grillage Analysis	
Bending	40 t
Shear	40 t
Bond	<3 t
Hence Overall Rating of <b>&lt;3 t</b>	

**Table 5.2b Assessed Grillage Analysis Load Capacity – Span 2**

The structure was also assessed for 45 units of HB live loading in accordance with NRA Design Manual for Roads and Bridges BD37/01. As per Stage 1 Assessment, the HB rating of both spans was found to be 30HB units for bending, 45HB units for shear and less than 30HB units for bond. The results are summarised in Table 5.3a & 5.3b.

HB Live Load Capacity	
Bending	30 HB
Shear	45 HB
Bond	<30 HB
Hence Overall Rating of <b>&lt;30 HB</b>	

**Table 5.3a Assessed HB Load Capacity – Span 1**

HB Live Load Capacity	
Bending	30 HB
Shear	45 HB
Bond	<30 HB
Hence Overall Rating of <b>&lt;30 HB</b>	

**Table 5.3b Assessed HB Load Capacity – Span 2**

### **Abutments and Pier:**

A qualitative assessment was carried out for the substructure. The abutments and pier were in good condition and not showing any signs of distress apart from those mentioned in Section 3 of the report, which however were not considered to be structurally significant. Hence, the components were considered satisfactory in accordance with BD21/01 & BA 16/97.

### **Headwalls**

The headwalls were assessed qualitatively. Both headwalls were found to be in good condition with no signs of structural defects. Hence, the headwalls were considered satisfactory.

### **Parapets**

The western parapet was 980mm high and the eastern parapet was 930mm high. Both parapets were 230mm thick.

These parapets heights are substandard for a National Road as per clause 4.5 of NRA BD52/07.

Additionally, both parapets are inadequate for normal containment level with an impact speed of 80kph as per figure 4 of BS6779: Part 4.

Hence, it is advised that both parapets should be upgraded to meet current standards.

## **6.0 Conclusions**

The Stage 1 Assessment of the structure in its present condition indicates that both spans of the Filler Beam Deck structure have a live load capacity of 7.5 tonnes assessment loading for bending, 40 tonnes assessment loading for shear and less than 3 tonnes assessment loading for bond. As the adequacy of the structures in bending for 40t live loading was 60% for span 1 and 73% for span 2 using the strip method, a grillage analysis was carried out, which increased the load capacity of the structure in bending to 18 tonnes assessment loading for Span 1 and to 40 tonnes for Span 2.

The Stage 1 Assessment also indicated that the structure had a HB rating of 30HB units for bending and 45HB units for shear, while for bond the structure could not achieve even 30HB units.

The structure was noted to be in good condition and not showing any signs of structural defects. The main causes of low carrying capacity of the structure were low concrete strength and low area of steel components.

It is considered likely that Stage 2 Assessment of the Filler Beam Deck would increase the assessment load capacity of the structure, but may not increase it to 40 tonnes assessment loading.

## **7.0 Recommendations**

The following works are recommended for the structure:


- (i) Stage 2 Assessment of the filler beam deck in the form of Plastic Analysis or Finite Element Method and subsequent strengthening using FRP plates or similar;
- (ii) The grass verges on both sides of the carriageway should be replaced with paved/raised verges and the entire structure should be waterproofed (such as an impermeable layer should be placed under the pavement);
- (iii) Both parapets should be upgraded to meet current standards.

It is recommended that the structure be inspected in year 2012, as per the Principal Inspection Report dated 1<sup>st</sup> October, 2008.

# **Appendix A**

## **Sketches**

DO NOT SCALE



# **Appendix B**

# **Photographs**



**Photo 1. General view - Eastern elevation**



**Photo 2. General view - Western elevation**



**Photo 3. Northern Departure (Increasing Chainage)**



**Photo 4. Southern Departure (Decreasing Chainage)**



**Photo 5. Road surface**



**Photo 6. Western parapet**



**Photo 7. Eastern parapet**



**Photo 8. Eastern Headwall**



**Photo 9. Western Headwall**



**Photo 10. Span 1 soffit – water seepage & calcite staining**



**Photo 11. Span 2 soffit – water seepage**



**Photo 12. Southern abutment**



**Photo 13. Northern abutment**



**Photo 14. North face of pier**



**Photo 15. View through span 1**



**Photo 16. View through span 2**



**Photo 17. Upstream channel view**



**Photo 18. Downstream Channel View**

# **Appendix C**

## **Site Investigation Results**



**Stanger**

**WS ATKINS IRELAND  
LTD.**

**STRADE RIVER BRIDGE  
MO-N58-001.00**

**ISSUE DATE:  
24<sup>TH</sup> JANUARY 2012**

**REVISION No. 1**

*LMS/8623 – Strade River Bridge  
WS Atkins Ireland Limited  
Unit 2B 2200 Cork Airport Business Park, Cork, Ireland*

**Revision No. :** 1  
**Our Ref :** LMS/8623  
**Issue Date :** 24<sup>th</sup> January 2012

# Stanger

Stanger Testing Services Limited  
Cambuslang Laboratory  
Bogleshole Road Cambuslang  
Glasgow G72 7DD  
Telephone (0141) 641 3623  
Fax (0141) 641 927

WS Atkins Ireland Limited  
Atkins House  
150-155 Airside Business Park  
Swords  
Co. Dublin

**REPORT ON THE INVESTIGATION OF  
BRIDGE: STRADE RIVER BRIDGE  
MAP REF 69 STRUCTURE I.D: MO-N58-001.00  
STRUCTURE FORM: SLAB, SLAB**



**Prepared by :** James Maddison B.Eng (Hons)  
**Engineer**

**Approved by :**  Billy Johnstone B.Eng (Hons)  
**Manager/Engineer**

*LMS/8623 – Strade River Bridge  
WS Atkins Ireland Limited  
Unit 2B 2200 Cork Airport Business Park, Cork, Ireland*

## **CONTENTS**

- 1. INTRODUCTION**
- 2. SITE WORKS**
- 3. RESULTS**
- 4. QUALITY STATEMENT**

**APPENDIX A – LOCATION PLAN**

**APPENDIX B – CORE LOGS AND COMPRESSIVE STRENGTH CERTIFICATES**

**APPENDIX C – FERROSCANS**

**APPENDIX D – PLATE PAGES**

## 1. INTRODUCTION

Stanger Testing Services Ltd. were instructed by WS Atkins Ireland Ltd. on behalf of The National Roads Authority to carry out an investigation under task order 213 stage of Strade River bridge.

The object of the investigation was to determine the following;

- 1). Core strength of various elements
- 2). Typical reinforcement and cover to concrete elements
- 3). Articulation of the slab
- 4). Type and presence of water proofing
- 5). Depth of slab
- 6). Beam dimensions
- 7). Depth of fill over slab

## 2. SITE WORKS

Stanger Testing Services carried out the investigation on the 1<sup>ST</sup> December 2011.

All traffic management was in accordance with Chapter 8 of the Traffic Signs Manual 2009. Prior to hand excavating trial pits, the area was scanned for services using a cat scan. Wet drilling techniques were used to extract core samples. Each core was logged, photographed and individually numbered prior to being sealed in a sample bag for return to the laboratory for testing. A Hilti Ferroscan was used to determine the cover and the reinforcement layout a small breakout was performed at main and secondary steel to confirm the results of the Ferroscan. A breakout was performed at the base of the slab to determine the articulation. All core holes and breakout were repaired using a fast setting concrete repair material. Trial pits were reinstated and compacted in layers not exceeding 100mm and stabilized with cement.

## 3. RESULTS

### A) Concrete Cores

Core No.	Location	Compressive Strength (N/mm <sup>2</sup> )	As Received Density (kg/m <sup>3</sup> )
C1	Soffit span 1	30.9	2380
C2	Soffit span 1	27.4	2360
C3	Soffit span 1	32.1	2390
C4	Soffit span 2	32.6	2430
C5	Soffit span 2	38.1	2420
C6A	Soffit span 2	28.5	2380
C6B	Soffit span 2	13.5	2320

B) Cover Meter

Location: Soffit Span 1, Mid Span 1.8x1.8m (See Scan FB 011622)

Horizontal: Steel Beams Running From Abutment To Abutment (Slight Skew)

Beam Size: 125x125mm

Spacing: 600mm


Cover: 70mm

Vertical: Secondary Steel Running Parallel To Abutment (Slight Skew) Between Beams

Bar Size: 28x14mm Rectangular Bar

Spacing: 140mm

Cover: 60mm



Location: Soffit Span 1, Near Abutment 1.0x1.0m (See Scan FB 011626)

Horizontal: Steel Beams Running From Abutment To Abutment (Slight Skew)

Beam Size: 125x125mm

Spacing: 600mm

Cover: 70mm

Vertical: Secondary Steel Running Parallel To Abutment (Slight Skew) Between Beams

Bar Size: 28x14mm Rectangular Bar

Spacing: 140mm

Cover: 60mm



*LMS/8623 – Strade River Bridge  
WS Atkins Ireland Limited  
Unit 2B 2200 Cork Airport Business Park, Cork, Ireland*

Location: Soffit Span 2, Mid Span 1.8x1.8m (See Scan FB 011621)

Horizontal: Steel Beams Running From Abutment To Abutment (Slight Skew)

Beam Size: 125x125mm

Spacing: 600mm


Cover: 60mm

Vertical: Secondary Steel Running Parallel To Abutment (Slight Skew) Between Beams

Bar Size: 28x14mm Rectangular Bar

Spacing: 140mm

Cover: 70mm



Location: Soffit Span 2, Near Abutment 1.0x1.0m (See Scan FB 011620)

Horizontal: Steel Beams Running From Abutment To Abutment (Slight Skew)

Beam Size: 125x125mm

Spacing: 600mm

Cover: 60mm

Vertical: Secondary Steel Running Parallel To Abutment (Slight Skew) Between Beams


Bar Size: 28x14mm Rectangular Bar

Spacing: 140mm

Cover: 70mm




# Strade River Bridge




C) Articulation –

Location: Span No 1 (See Scan FB 11624)  
None Found



Location: Span No 2 (See Scan FB 11619)  
None Found



D) Trial Pit –

Location: Above Middle Pier In Verge 500mm From Parapet.  
Note: Slab Is Not Continuous Over The Pier.

0.0 – 0.10 Topsoil  
0.10 – 0.21 Granular Fill  
0.21 – 0.23 Blacktop 10mm  
0.23 – 0.57 Concrete



**4. QUALITY STATEMENT**


We can confirm that in preparing this report we have exercised all reasonable skill and care.

*LMS/8623 – Strade River Bridge*  
*WS Atkins Ireland Limited*  
*Unit 2B 2200 Cork Airport Business Park, Cork, Ireland*

# **APPENDIX A**

## **LOCATION PLAN**

Strade River Bridge



*LMS/8623 – Strade River Bridge  
WS Atkins Ireland Limited  
Unit 2B 2200 Cork Airport Business Park, Cork, Ireland*

# **APPENDIX B**

## **CORE LOGS & COMP STRENGTH CERTIFICATES**

**Your Ref** :  
**Our Ref** : LMS/8623  
**Date** : 21 December 2011

W.S Atkins Ireland Limited  
 Atkins House  
 150-155 Airside Business Park  
 Swords  
 Co.Dublin

## CERTIFICATE OF TEST FOR COMPRESSIVE STRENGTH OF CONCRETE CORES TO BS EN 12504-1 : 2009

Contract	:	Strade River Bridge
Designation	:	C1
Core Location	:	Soffit Span 1
Date Cored	:	01/12/2011
Date Cast	:	Not Stated
Date Received	:	12/12/2011
Sample Ref.	:	C1
GRN	:	23960
Cored By	:	Stanger Testing Services Ltd.
Estimated Maximum Aggregate Size	:	40mm
Max & Min Length as Received (mm)	:	160/150
Coring Direction	:	Vertical Up
Mean Diameter (mm)	:	92
Mean Length before End Preparation (mm)	:	90
Length/Diameter Ratio of Prepared Specimen (mm)	:	1.033
Position Relative to Total Length (mm)	:	20mm from top of core
Average Length after End Preparation (mm)	:	95
Method of End Preparation	:	Sulphur Sand
Density as Received (kg/m <sup>3</sup> )	:	2380
Method	:	Water Displacement
Date of Test	:	16/12/2011
Age at Test Date	:	N/A
Time Stored in Water before Test (days)	:	1 Day
Surface Moisture at Test	:	Moist
Maximum Load at Failure (kN)	:	205.7
Appearance at Failure	:	Normal
Size, Position and Spacing of Reinforcement Bars	:	Not Applicable
Compressive Strength (N/mm <sup>2</sup> )	:	30.9
Estimated In-Situ Cube Strength (N/mm <sup>2</sup> )	:	31.3

### Remarks:

Compaction	:	Good
Voids (%)	:	1
Honeycombing	:	None
Cracks	:	None
Aggregate Distribution	:	Even

**N.B.:** Please be advised that all samples (if not destroyed during the testing process) will be disposed of 7 days from the date of issue of this report unless we received written instruction to retain them, in which case charges may apply.

  
**Laurie Murphy**  
**Technical Director**


**Allan Reid**  
**Laboratory Supervisor**

**Billy Johnstone**  
**Manager/Engineer**

**James Maddison**  
**Engineer**

# CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
 STRUCTURE: Strade River Bridge LOCATION: Soffit Span 1  
 DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
 CORE MARK/No: C1 PHOTOGRAPH: Yes GRN: 23960



Aggregate Distribution : Even

Nominal Maximum Size : 40mm

Compaction Remarks:

Compaction : Good

Excess Voidage : 1.0%

Honeycombing : None

Cracks : None

No of pieces : 1

Type of Aggregate : Crushed Rock

Shape of Aggregate : Angular

Presence of Microcracking: N/A

Max/Min Length (mm) : 150/160

Diameter (mm) : 92mm

Depth of Carbonation : <1mm

Render : None

Repairs : None

Reinforcing Bars : None

No: N/A Diameter: N/A

Orientation of core

With respect to structure : Vertical Up

Checked by : S.Lilley

Date : 16/12/2011

### CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
STRUCTURE: Strade River Bridge LOCATION: Soffit Span 1  
DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
CORE MARK/No: C1 PHOTOGRAPH: Yes GRN: 23960



**Your Ref** :  
**Our Ref** : LMS/8623  
**Date** : 21 December 2011

W.S Atkins Ireland Limited  
 Atkins House  
 150-155 Airside Business Park  
 Swords  
 Co.Dublin

## CERTIFICATE OF TEST FOR COMPRESSIVE STRENGTH OF CONCRETE CORES TO BS EN 12504-1 : 2009

Contract	:	Strade River Bridge
Designation	:	C2
Core Location	:	Soffit Span 1
Date Cored	:	01/12/2011
Date Cast	:	Not Stated
Date Received	:	12/12/2011
Sample Ref.	:	C2
GRN	:	23960
Cored By	:	Stanger Testing Services Ltd.
Estimated Maximum Aggregate Size	:	40mm
Max & Min Length as Received (mm)	:	140/120
Coring Direction	:	Vertical Up
Mean Diameter (mm)	:	92
Mean Length before End Preparation (mm)	:	92
Length/Diameter Ratio of Prepared Specimen (mm)	:	1.054
Position Relative to Total Length (mm)	:	20mm from top of core
Average Length after End Preparation (mm)	:	97
Method of End Preparation	:	Sulphur Sand
Density as Received (kg/m <sup>3</sup> )	:	2360
Method	:	Water Displacement
Date of Test	:	16/12/2011
Age at Test Date	:	N/A
Time Stored in Water before Test (days)	:	1 Day
Surface Moisture at Test	:	Moist
Maximum Load at Failure (kN)	:	185.0
Appearance at Failure	:	Normal
Size, Position and Spacing of Reinforcement Bars	:	Not Applicable
Compressive Strength (N/mm <sup>2</sup> )	:	27.4
Estimated In-Situ Cube Strength (N/mm <sup>2</sup> )	:	28.0

### Remarks:

Compaction	:	Fair
Voids (%)	:	1.0
Honeycombing	:	None
Cracks	:	None
Aggregate Distribution	:	Even

**N.B.:** Please be advised that all samples (if not destroyed during the testing process) will be disposed of 7 days from the date of issue of this report unless we received written instruction to retain them, in which case charges may apply.

  
**Laurie Murphy**  
**Technical Director**

**Allan Reid**  
**Laboratory Supervisor**

**Billy Johnstone**  
**Manager/Engineer**

**James Maddison**  
**Engineer**

### Stanger Testing Services Limited

Cambuslang Laboratory Bogleshole Road Cambuslang Glasgow G72 7DD

Telephone (0141) 641 3623

Fax (0141) 641 9279

Email: stangertesting@aol.com

Stanger Testing Services Limited Registered in Scotland No. SC219023

'Stanger' is a trademark VAT Registration No. 774 7634 86


Dundee Telephone (01382) 535272

Fax (01382) 530899



# CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
 STRUCTURE: Strade River Bridge LOCATION: Soffit Span 1  
 DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
 CORE MARK/No: C2 PHOTOGRAPH: Yes GRN: 23960



Aggregate Distribution : Even  
 Nominal Maximum Size : 20mm  
 Compaction Remarks:  
 Compaction : Fair  
 Excess Voidage : 1.5%  
 Honeycombing : None  
 Cracks : None  
 No of pieces : 1  
 Type of Aggregate : Crushed Rock  
 Shape of Aggregate : Angular  
 Presence of Microcracking: N/A  
 Max/Min Length (mm) : 140/120  
 Diameter (mm) : 92mm  
 Depth of Carbonation : <1mm  
 Render : None  
 Repairs : None  
 Reinforcing Bars : None  
 No: N/A Diameter: N/A  
 Orientation of core  
 With respect to structure : Vertical Up

Checked by : S.Lilley  
 Date : 16/12/2011

# CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
STRUCTURE: Strade River Bridge LOCATION: Soffit Span 1  
DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
CORE MARK/No: C2 PHOTOGRAPH: Yes GRN: 23960



**Your Ref** :  
**Our Ref** : LMS/8623  
**Date** : 21 December 2011

W.S Atkins Ireland Limited  
 Atkins House  
 150-155 Airside Business Park  
 Swords  
 Co.Dublin

## CERTIFICATE OF TEST FOR COMPRESSIVE STRENGTH OF CONCRETE CORES TO BS EN 12504-1 : 2009

Contract	:	Strade River Bridge
Designation	:	C3
Core Location	:	Soffit Span 1
Date Cored	:	01/12/2011
Date Cast	:	Not Stated
Date Received	:	12/12/2011
Sample Ref.	:	C3
GRN	:	23960
Cored By	:	Stanger Testing Services Ltd.
Estimated Maximum Aggregate Size	:	40mm
Max & Min Length as Received (mm)	:	180/170
Coring Direction	:	Vertical Up
Mean Diameter (mm)	:	92
Mean Length before End Preparation (mm)	:	85
Length/Diameter Ratio of Prepared Specimen (mm)	:	0.99
Position Relative to Total Length (mm)	:	20mm from top of core
Average Length after End Preparation (mm)	:	91
Method of End Preparation	:	Sulphur Sand
Density as Received (kg/m <sup>3</sup> )	:	2390
Method	:	Water Displacement
Date of Test	:	16/12/2011
Age at Test Date	:	N/A
Time Stored in Water before Test (days)	:	1 Day
Surface Moisture at Test	:	Moist
Maximum Load at Failure (kN)	:	213.3
Appearance at Failure	:	Normal
Size, Position and Spacing of Reinforcement Bars	:	Not Applicable
Compressive Strength (N/mm <sup>2</sup> )	:	32.1
Estimated In-Situ Cube Strength (N/mm <sup>2</sup> )	:	31.7

### Remarks:

Compaction	:	Fair
Voids (%)	:	1.5
Honeycombing	:	None
Cracks	:	None
Aggregate Distribution	:	Even

**N.B.:** Please be advised that all samples (if not destroyed during the testing process) will be disposed of 7 days from the date of issue of this report unless we received written instruction to retain them, in which case charges may apply.

  
**Laurie Murphy**  
**Technical Director**

**Allan Reid**  
**Laboratory Supervisor**

**Billy Johnstone**  
**Manager/Engineer**

**James Maddison**  
**Engineer**

### Stanger Testing Services Limited

Cambuslang Laboratory Bogleshole Road Cambuslang Glasgow G72 7DD

Telephone (0141) 641 3623 Fax (0141) 641 9279

Email: stangertesting@aol.com

Stanger Testing Services Limited Registered in Scotland No. SC219023

'Stanger' is a trademark VAT Registration No. 774 7634 86


Dundee Telephone (01382) 535272

Fax (01382) 530899



# CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
 STRUCTURE: Strade River Bridge LOCATION: Soffit Span 1  
 DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
 CORE MARK/No: C3 PHOTOGRAPH: Yes GRN: 23960



Aggregate Distribution : Even  
 Nominal Maximum Size : 20mm  
 Compaction Remarks:  
 Compaction : Fair  
 Excess Voidage : 1.5%  
 Honeycombing : None  
 Cracks : None  
 No of pieces : 1  
 Type of Aggregate : Crushed Rock  
 Shape of Aggregate : Angular  
 Presence of Microcracking: N/A  
 Max/Min Length (mm) : 180/170  
 Diameter (mm) : 92mm  
 Depth of Carbonation : <1mm  
 Render : None  
 Repairs : None  
 Reinforcing Bars : None  
 No: N/A Diameter: N/A  
 Orientation of core  
 With respect to structure : Vertical Up

Checked by : S.Lilley  
 Date : 16/12/2011

# CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
STRUCTURE: Strade River Bridge LOCATION: Soffit Span 1  
DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
CORE MARK/No: C3 PHOTOGRAPH: Yes GRN: 23960



Your Ref :  
Our Ref : LMS/8623  
Date : 21 December 2011

W.S Atkins Ireland Limited  
Atkins House  
150-155 Airside Business Park  
Swords  
Co.Dublin

**CERTIFICATE OF TEST FOR COMPRESSIVE STRENGTH OF CONCRETE CORES  
TO BS EN 12504-1 : 2009**

Contract	:	Strade River Bridge
Designation	:	C4
Core Location	:	Soffit Span 2
Date Cored	:	01/12/2011
Date Cast	:	Not Stated
Date Received	:	12/12/2011
Sample Ref.	:	C4
GRN	:	23960
Cored By	:	Stanger Testing Services Ltd.
Estimated Maximum Aggregate Size	:	20mm
Max & Min Length as Received (mm)	:	225/225
Coring Direction	:	Vertical Up
Mean Diameter (mm)	:	92
Mean Length before End Preparation (mm)	:	93
Length/Diameter Ratio of Prepared Specimen (mm)	:	1.065
Position Relative to Total Length (mm)	:	30mm from top of core
Average Length after End Preparation (mm)	:	98
Method of End Preparation	:	Sulphur Sand
Density as Received (kg/m <sup>3</sup> )	:	2430
Method	:	Water Displacement
Date of Test	:	16/12/2011
Age at Test Date	:	N/A
Time Stored in Water before Test (days)	:	1 Day
Surface Moisture at Test	:	Moist
Maximum Load at Failure (kN)	:	217.0
Appearance at Failure	:	Normal
Size, Position and Spacing of Reinforcement Bars	:	Not Applicable
Compressive Strength (N/mm <sup>2</sup> )	:	32.6
Estimated In-Situ Cube Strength (N/mm <sup>2</sup> )	:	33.5

**Remarks:**

Compaction	:	Good
Voids (%)	:	1
Honeycombing	:	None
Cracks	:	None
Aggregate Distribution	:	Even

**N.B.:** Please be advised that all samples (if not destroyed during the testing process) will be disposed of 7 days from the date of issue of this report unless we received written instruction to retain them, in which case charges may apply.

  
Laurie Murphy  
Technical Director


Allan Reid  
Laboratory Supervisor

Billy Johnstone  
Manager/Engineer

James Maddison  
Engineer

# CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
 STRUCTURE: Strade River Bridge LOCATION: Soffit Span 2  
 DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
 CORE MARK/No: C4 PHOTOGRAPH: Yes GRN: 23960



Aggregate Distribution : Even  
 Nominal Maximum Size : 20mm  
 Compaction Remarks:  
 Compaction : Good  
 Excess Voidage : 1.0%  
 Honeycombing : None  
 Cracks : None  
 No of pieces : 1  
 Type of Aggregate : Crushed Rock  
 Shape of Aggregate : Angular  
 Presence of Microcracking: N/A  
 Max/Min Length (mm) : 225/225  
 Diameter (mm) : 92mm  
 Depth of Carbonation : <1mm  
 Render : None  
 Repairs : None  
 Reinforcing Bars : None  
 No: N/A Diameter: N/A  
 Orientation of core  
 With respect to structure : Vertical Up

Checked by : S.Lilley  
 Date : 16/12/2011

# CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
STRUCTURE: Strade River Bridge LOCATION: Soffit Span 2  
DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
CORE MARK/No: C4 PHOTOGRAPH: Yes GRN: 23960



**Your Ref** :  
**Our Ref** : LMS/8623  
**Date** : 21 December 2011

W.S Atkins Ireland Limited  
 Atkins House  
 150-155 Airside Business Park  
 Swords  
 Co.Dublin


## CERTIFICATE OF TEST FOR COMPRESSIVE STRENGTH OF CONCRETE CORES TO BS EN 12504-1 : 2009

Contract	:	Strade River Bridge
Designation	:	C5
Core Location	:	Soffit Span 2
Date Cored	:	01/12/2011
Date Cast	:	Not Stated
Date Received	:	12/12/2011
Sample Ref.	:	C5
GRN	:	23960
Cored By	:	Stanger Testing Services Ltd.
Estimated Maximum Aggregate Size	:	40mm
Max & Min Length as Received (mm)	:	135/125
Coring Direction	:	Vertical Up
Mean Diameter (mm)	:	92
Mean Length before End Preparation (mm)	:	94
Length/Diameter Ratio of Prepared Specimen (mm)	:	1.076
Position Relative to Total Length (mm)	:	20mm from top of core
Average Length after End Preparation (mm)	:	99
Method of End Preparation	:	Sulphur Sand
Density as Received (kg/m <sup>3</sup> )	:	2420
Method	:	Water Displacement
Date of Test	:	16/12/2011
Age at Test Date	:	N/A
Time Stored in Water before Test (days)	:	1 Day
Surface Moisture at Test	:	Moist
Maximum Load at Failure (kN)	:	253.0
Appearance at Failure	:	Normal
Size, Position and Spacing of Reinforcement Bars	:	Not Applicable
Compressive Strength (N/mm <sup>2</sup> )	:	38.1
Estimated In-Situ Cube Strength (N/mm <sup>2</sup> )	:	39.2

### Remarks:

Compaction	:	Good
Voids (%)	:	1
Honeycombing	:	None
Cracks	:	None
Aggregate Distribution	:	Even

**N.B.:** Please be advised that all samples (if not destroyed during the testing process) will be disposed of 7 days from the date of issue of this report unless we received written instruction to retain them, in which case charges may apply.

  
 Laurie Murphy  
 Technical Director

Allan Reid  
 Laboratory Supervisor

Billy Johnstone  
 Manager/Engineer

James Maddison  
 Engineer

### Stanger Testing Services Limited

Cambuslang Laboratory Bogleshole Road Cambuslang Glasgow G72 7DD  
 Telephone (0141) 641 3623 Fax (0141) 641 9279

Email: stangertesting@aol.com

Stanger Testing Services Limited Registered in Scotland No. SC219023


'Stanger' is a trademark VAT Registration No. 774 7634 86

Dundee Telephone (01382) 535272  
 Fax (01382) 530899



# CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
 STRUCTURE: Strade River Bridge LOCATION: Soffit Span 2  
 DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
 CORE MARK/No: C5 PHOTOGRAPH: Yes GRN: 23960



Aggregate Distribution : Even  
 Nominal Maximum Size : 40mm  
 Compaction Remarks:  
 Compaction : Good  
 Excess Voidage : 1.0%  
 Honeycombing : None  
 Cracks : None  
 No of pieces : 1  
 Type of Aggregate : Crushed Rock  
 Shape of Aggregate : Angular  
 Presence of Microcracking: N/A  
 Max/Min Length (mm) : 125/135  
 Diameter (mm) : 92mm  
 Depth of Carbonation : <1mm  
 Render : None  
 Repairs : None  
 Reinforcing Bars : None  
 No: N/A Diameter: N/A  
 Orientation of core  
 With respect to structure : Vertical Up

Checked by : S.Lilley  
 Date : 16/12/2011

### CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
STRUCTURE: Strade River Bridge LOCATION: Soffit Span 2  
DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
CORE MARK/No: C5 PHOTOGRAPH: Yes GRN: 23960



**Your Ref** :  
**Our Ref** : LMS/8623  
**Date** : 21 December 2011

W.S Atkins Ireland Limited  
 Atkins House  
 150-155 Airside Business Park  
 Swords  
 Co.Dublin

## CERTIFICATE OF TEST FOR COMPRESSIVE STRENGTH OF CONCRETE CORES TO BS EN 12504-1 : 2009

Contract	:	Strade River Bridge
Designation	:	C6A
Core Location	:	Soffit Span 2
Date Cored	:	01/12/2011
Date Cast	:	Not Stated
Date Received	:	12/12/2011
Sample Ref.	:	C6A
GRN	:	23960
Cored By	:	Stanger Testing Services Ltd.
Estimated Maximum Aggregate Size	:	20mm
Max & Min Length as Received (mm)	:	340/340
Coring Direction	:	Vertical Down
Mean Diameter (mm)	:	92
Mean Length before End Preparation (mm)	:	85
Length/Diameter Ratio of Prepared Specimen (mm)	:	0.98
Position Relative to Total Length (mm)	:	20mm from top of core
Average Length after End Preparation (mm)	:	90
Method of End Preparation	:	Sulphur Sand
Density as Received (kg/m <sup>3</sup> )	:	2440
Method	:	Water Displacement
Date of Test	:	16/12/2011
Age at Test Date	:	N/A
Time Stored in Water before Test (days)	:	1 Day
Surface Moisture at Test	:	Moist
Maximum Load at Failure (kN)	:	189.6
Appearance at Failure	:	Normal
Size, Position and Spacing of Reinforcement Bars	:	Not Applicable
Compressive Strength (N/mm <sup>2</sup> )	:	28.5
Estimated In-Situ Cube Strength (N/mm <sup>2</sup> )	:	28.3

### Remarks:

Compaction	:	Good
Voids (%)	:	1.5
Honeycombing	:	None
Cracks	:	None
Aggregate Distribution	:	Even

**N.B.:** Please be advised that all samples (if not destroyed during the testing process) will be disposed of 7 days from the date of issue of this report unless we received written instruction to retain them, in which case charges may apply.

  
 Laurie Murphy  
 Technical Director

Allan Reid  
 Laboratory Supervisor

Billy Johnstone  
 Manager/Engineer

James Maddison  
 Engineer

### Stanger Testing Services Limited

Cambuslang Laboratory Bogleshole Road Cambuslang Glasgow G72 7DD  
 Telephone (0141) 641 3623 Fax (0141) 641 9279

Email: stangertesting@aol.com

Stanger Testing Services Limited Registered in Scotland No. SC219023

'Stanger' is a trademark VAT Registration No. 774 7634 86

Dundee Telephone (01382) 535272  
 Fax (01382) 530899



**Your Ref** :  
**Our Ref** : LMS/8623  
**Date** : 21 December 2011

W.S Atkins Ireland Limited  
 Atkins House  
 150-155 Airside Business Park  
 Swords  
 Co.Dublin

## CERTIFICATE OF TEST FOR COMPRESSIVE STRENGTH OF CONCRETE CORES TO BS EN 12504-1 : 2009

Contract	:	Strade River Bridge
Designation	:	C6B
Core Location	:	Soffit Span 2
Date Cored	:	01/12/2011
Date Cast	:	Not Stated
Date Received	:	12/12/2011
Sample Ref.	:	C6B
GRN	:	23960
Cored By	:	Stanger Testing Services Ltd.
Estimated Maximum Aggregate Size	:	20mm
Max & Min Length as Received (mm)	:	340
Coring Direction	:	Vertical Up
Mean Diameter (mm)	:	92
Mean Length before End Preparation (mm)	:	85
Length/Diameter Ratio of Prepared Specimen (mm)	:	0.99
Position Relative to Total Length (mm)	:	220mm from top of core
Average Length after End Preparation (mm)	:	91
Method of End Preparation	:	Sulphur Sand
Density as Received (kg/m <sup>3</sup> )	:	2320
Method	:	Water Displacement
Date of Test	:	16/12/2011
Age at Test Date	:	N/A
Time Stored in Water before Test (days)	:	1 Day
Surface Moisture at Test	:	Moist
Maximum Load at Failure (kN)	:	89.8
Appearance at Failure	:	Normal
Size, Position and Spacing of Reinforcement Bars	:	Not Applicable
Compressive Strength (N/mm <sup>2</sup> )	:	13.5
Estimated In-Situ Cube Strength (N/mm <sup>2</sup> )	:	13.3

### Remarks:

Compaction	:	Good
Voids (%)	:	2.0
Honeycombing	:	None
Cracks	:	None
Aggregate Distribution	:	Even

**N.B.:** Please be advised that all samples (if not destroyed during the testing process) will be disposed of 7 days from the date of issue of this report unless we received written instruction to retain them, in which case charges may apply.

  
 Laurie Murphy  
 Technical Director


Allan Reid  
 Laboratory Supervisor

Billy Johnstone  
 Manager/Engineer

James Maddison  
 Engineer

# CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
 STRUCTURE: Strade River Bridge LOCATION: Soffit Span 2  
 DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
 CORE MARK/No: C6 PHOTOGRAPH: Yes GRN: 23960



Aggregate Distribution : Even  
 Nominal Maximum Size : 20mm  
 Compaction Remarks:  
 Compaction : Good  
 Excess Voidage : 1.5%  
 Honeycombing : None  
 Cracks : None  
 No of pieces : 3  
 Type of Aggregate : Crushed Rock  
 Shape of Aggregate : Angular  
 Presence of Microcracking: N/A  
 Max/Min Length (mm) : 340/340  
 Diameter (mm) : 92mm  
 Depth of Carbonation : <1mm  
 Render : None  
 Repairs : None  
 Reinforcing Bars : None  
 No: N/A Diameter: N/A  
 Orientation of core  
 With respect to structure : Vertical Up

Checked by : S.Lilley  
 Date : 16/12/2011

# CONCRETE CORE LOG

CLIENT: W.S Atkins Ireland Limited FILE REF: 8623  
STRUCTURE: Strade River Bridge LOCATION: Soffit Span 2  
DATE CORED: 01/12/2011 CORED BY: Stanger DATE REC'D: 12/12/2011  
CORE MARK/No: C6 PHOTOGRAPH: Yes GRN: 23960



*LMS/8623 – Strade River Bridge  
WS Atkins Ireland Limited  
Unit 2B 2200 Cork Airport Business Park, Cork, Ireland*


# APPENDIX C

## FERROSCANS

Date / Time: 2011-11-30 13:14:45

SSN: 04310005

[mm]




Customer: W.S Atkins

Location: Soffit Span No 1, Mid Span 1.8x1.8m Operator: B.Johnstone

Comment:

Horizontal: Steel Beams Running From Abutment To Abutment (Slight Skew)  
Beam Size: 125x125mm  
Spacing: 600mm  
Cover: 70mm

Vertical: Secondary Steel Running Parallel To Abutment (Slight Skew) Between Beams  
Bar Size: 28x14mm Rectangular Bar  
Spacing: 140mm  
Cover: 60mm



Customer: W.S Atkins

Location: Soffit Span No 1 Near Abutment 1.0x1.0m Inspector: B.Johnstone


Comment:

Horizontal: Steel Beams Running From Abutment To Abutment (Slight Skew)  
Beam Size: 125x125mm  
Spacing: 600mm  
Cover: 70mm

Vertical: Secondary Steel Running Parallel To Abutment (Slight Skew) Between Beams  
Bar Size: 28x14mm Rectangular Bar  
Spacing: 140mm  
Cover: 60mm

Date / Time: 2011-11-30 12:27:51

SSN: 04310005 [mm]



Customer: W.S Atkins

Location: Soffit Span No 2, Mid Span 1.8x1.8m Operator: B.Johnstone

Comment:


Horizontal: Steel Beams Running From Abutment To Abutment (Slight Skew)  
Beam Size: 125x125mm  
Spacing: 600mm  
Cover: 60mm

Vertical: Secondary Steel Running Parallel To Abutment (Slight Skew) Between Beams  
Bar Size: 28x14mm Rectangular Bar  
Spacing: 140mm  
Cover: 70mm

**Blockscan:** FB011620.XFF

Date / Time: 2011-11-30 12:13:15

SSN: 04310005 [mm]



Customer: W.S Atkins

Location: Soffit Span No 2 Near Abutment 1.0x1.0m Operator: B.Johnstone


Comment:

Horizontal: Steel Beams Running From Abutment To Abutment (Slight Skew)  
Beam Size: 125x125mm  
Spacing: 600mm  
Cover: 60mm

Vertical: Secondary Steel Running Parallel To Abutment (Slight Skew) Between Beams  
Bar Size: 28x14mm Rectangular Bar  
Spacing: 140mm  
Cover: 70mm

Date / Time: 2011-11-30 14:17:29

SSN: 04310005 [mm]



Customer: W.S Atkins

Location: Span No 1


Operator: B.Johnstone

Comment:

None Found

Date / Time: 2011-11-30 11:29:52

SSN: 04310005 [mm]



Customer: W.S Atkins

Location: Span No 2

Operator: B.Johnstone

Comment:

None Found

*LMS/8623 – Stade River Bridge*  
*WS Atkins Ireland Limited*  
*Unit 2B 2200 Cork Airport Business Park, Cork, Ireland*

# **APPENDIX D**

## **PLATE PAGES**

*LMS/8623 –Strade River Bridge  
WS Atkins Ireland Limited  
Unit 2B 2200 Cork Airport Business Park, Cork, Ireland*



**Beam**



**Beam**

*LMS/8623 –Strade River Bridge  
WS Atkins Ireland Limited  
Unit 2B 2200 Cork Airport Business Park, Cork, Ireland*




**Beam**




**Beam**

*LMS/8623 –Strade River Bridge  
WS Atkins Ireland Limited  
Unit 2B 2200 Cork Airport Business Park, Cork, Ireland*



**Beam**



**Scan Location**

# **Appendix D**

## **Calculations**

ATKINS	Project NRA Eirspan Task Order 213			Job ref 3044																							
	Part of Structure MO-N58-001.00			Calc sheet no. rev 1 0																							
	Drawing Ref MO-N58-001.00	Calc By CP	Date 13-Feb-12	Check by PG	Date 14-Feb-12																						
Ref	Calculations				Output																						
App. C1 /SI Report	<b>ASSESSMENT SUMMARY:</b> Filler Beam - Span 1 (South)																										
	<table><tr><td></td><td>HA UDL &amp; KEL</td><td>Single Axle</td><td>Single Wheel</td><td>HB</td><td>Punching Shear</td></tr><tr><td>Moment</td><td>40t</td><td>18t</td><td>18t</td><td>&lt;30HB</td><td>-</td></tr><tr><td>Shear</td><td>40t</td><td>&lt;40t</td><td>&lt;40t</td><td>&lt;45HB</td><td>0</td></tr><tr><td>Bond</td><td>&lt;3t</td><td>-</td><td>-</td><td>&lt;30HB</td><td>-</td></tr></table>						HA UDL & KEL	Single Axle	Single Wheel	HB	Punching Shear	Moment	40t	18t	18t	<30HB	-	Shear	40t	<40t	<40t	<45HB	0	Bond	<3t	-	-
	HA UDL & KEL	Single Axle	Single Wheel	HB	Punching Shear																						
Moment	40t	18t	18t	<30HB	-																						
Shear	40t	<40t	<40t	<45HB	0																						
Bond	<3t	-	-	<30HB	-																						
App. C1 /SI Report	<b>CALCULATION OF REBAR SPACING</b>																										
	<b>MID SPAN</b> <div><div>Spacing (mm)</div><div>MAIN BEAM 600</div></div> <div>Average beam spacing600</div> <div>Depth of beam125 mm</div> <div>Bottom Cover60 mm</div>																										
App. C1 /SI Report	<b>NEAR SUPPORT</b> <div><div>Spacing (mm)</div><div>MAIN BEAM 600</div></div> <div>Average rebar spacing600</div> <div>Depth of beam125 mm</div> <div>Bottom Cover60 mm</div>																										

**CALCULATION OF WORST CREDIBLE STRENGTH**

Input a maximum of 11 Core samples

LOCATION	CORE REFERENCE	ESTIMATED IN-SITU CUBE STRENGTH N/mm <sup>2</sup> (f <sub>c</sub> )	(f <sub>c</sub> - MEAN) <sup>2</sup>
	C4	33.5	23.36
	C5	39.2	110.95
	C6b	13.3	236.13
			-
			-
			-
			-
			-
			-
			-
TOTAL		86	370.44667
No of cores		3	
MEAN		28.67	
Standard Deviation		13.61	

WCS will be calculated using 2 different methods:

**1) LOCATION :** Using equation from BA 44/96 with n = total number of core samples

**Note** - only use this for cores taken at the location of interest

n = 3


From BA 44/90,  $WCS = (Total\ f_c * (100 - (20/n^{0.5}))) / 100n$ 

WCS = **25.4 N/mm<sup>2</sup>**
**2) LOWEST CORE STRENGTH :**

Lowest core strength = 13.3 N/mm<sup>2</sup>

WCS = **13.3 N/mm<sup>2</sup>**

Using the above results and engineering judgement,  
the proposed WCS = **13.3 N/mm<sup>2</sup>**



Ref

Calculations

SAGGING - SECTION PROPERTIES (Using BS 5400 Part 3:2000) for composite section

Slab

Width (mm)

Depth (mm)

f<sub>cu</sub> (MPa)

E(short Term)

Slab

600

340

13.3

23.6

Haunch

Width (mm)

Depth (mm)

f<sub>cu</sub> (MPa)

E(short Term)

Haunch

0

0

0

0

Girder

Width (mm)

Depth (mm)

f<sub>y</sub> (MPa)

E (GPa)

Top Flange

50

30

230

205.0

Web

10

85

230

205.0

Bottom Flange

125

10

230

205.0

Bottom Cover

60

mm

Panel Length (mm)

Section depth mm

125

m

8.69

e) Plastic Section Properties

nb if NA lies below the web this doesn't work

Stress in concrete = 0.4\*f<sub>cu</sub>

Stress in steel = σ<sub>y</sub>/γ<sub>m</sub>

γ<sub>m</sub> = 1.05

Condition factor for RC Filler

-

0.9

Depth (mm)

Width (mm)

Area (mm<sup>2</sup>)

Stress (Nmm<sup>-2</sup>)

Force (kN)

Force above NA (kN)

Force below NA (kN)

y above NA (mm)

y below NA (mm)

Slab\*

155

600

93000

5

495

495

-

91

-

Haunch

0

0

0

0

0

0

-

0

-

Top Flange

30

50

1500

219

329

147

182

7

8

Web

85

10

850

219

186

0

186

-17

59

Bottom Flange

10

125

1250

219

274

-

274

-

107

NA lies in

Top Flange

Depth of Neutral Axis From Top Slab

Depth (mm)

Slab

0.0

Haunch

0.0

Top Flange

168.4

Web

0.0

m=

0.0

Depth of Plastic NA =

168.4

171.6

\*Concrete above beam only taken in properties

Concrete M<sub>plastic</sub> =

45

kNm

Single Beam M<sub>plastic</sub> =

38

kNm

f) Compactness Check

9.3.7.2

If m < 0.5

Check web depth is less than

(34t<sub>w</sub>/m)\*(355/σ<sub>yw</sub>)^0.5

n/a

mm

(Compact?)

n/a

If m > 0.5

Check web depth is less than

(374t<sub>w</sub>/(13m-1))\*(355/σ<sub>yw</sub>)^0.5

n/a

mm

n/a

If web fully in tension section is compact

yes

Section is Compact

SAGGING - PLASTIC CHECKS (Using BS 5400 Part 3:2000)

2. ULS Bending Capacity of Section

M<sub>plastic</sub> =

88

kNm

M<sub>pe</sub> (unfactored) =

92

kNm

M<sub>D</sub> = M<sub>pe</sub> / 1.05 x 1.1 =

72

kNm

(Also Adjusted by condition factor)

3. ULS Pure Shear Capacity of Section

Depth of panel = d<sub>we</sub>

=

85

mm

Aspect Ratio = φ = a/d<sub>we</sub>

=

1.000

b<sub>fe</sub> (top flange)

=

0

b<sub>fb</sub> (bottom flange)

=

0

m<sub>fw</sub> (top flange) = σ<sub>yf</sub>b<sub>fc</sub>t<sub>f</sub><sup>2</sup>/(2d<sub>we</sub><sup>2</sup>t<sub>w</sub>σ<sub>yw</sub>)

=

0.1557

m<sub>fb</sub>(bot) = σ<sub>yf</sub>b<sub>fc</sub>t<sub>f</sub><sup>2</sup>/(2d<sub>we</sub><sup>2</sup>t<sub>w</sub>σ<sub>yw</sub>)

=

0.0433

Minimum value of m<sub>fw</sub> for use in shear calcs.

=

0.0433

λ = (d<sub>we</sub>/t<sub>w</sub>)x(σ<sub>yw</sub>/355)<sup>1/2</sup>

=

6.8

τ<sub>y</sub> = σ<sub>yw</sub>/√3

=

132.79

3/9.9.2.2

τ<sub>f</sub>/τ<sub>y</sub> for m<sub>fw</sub> of

0.0433

=

1.300

τ<sub>I</sub> =

172.58

τ<sub>f</sub>/τ<sub>y</sub> for m<sub>fb</sub> of

0.000

=

1.300

τ<sub>I</sub> =

172.58

3/9.9.2.2

V<sub>D</sub> = (d<sub>w</sub>t<sub>w</sub>xτ<sub>I</sub>) / (γ<sub>m</sub>γ<sub>I</sub>s)

=

114.3

kN

When m<sub>fw</sub> =

0.1557

(Adjusted by condition factor)

V<sub>R</sub> = ""

=


114.3

kN

When m<sub>fb</sub> =

0.0000

(Adjusted by condition factor)




Ref

Calculations




ATKINS	Project				NRA Eirspan Task Order 213		Job ref 3044	
	Part of Structure MO-N58-001.00			Assessment using BD21/01 RC Slabs		Calc sheet no. rev 6 0		
	Drawing Ref MO-N58-001.00			Calc By CP		Date 13-Feb-12	Check by PG	Date 14-Feb-12
Ref	Calculations						Output	
Table 3.1/ BD21 Cl.3. 1/ BD21 & Cl. 4.2.3/ BD 44  Table 3.1/ BD21 Cl.3. 1/ BD21 & Cl. 4.2.3/ BD 44  Table 3.1/ BD21 Cl.3. 1/ BD21 & Cl. 4.2.3/ BD 44	Filler Beam - Span 1 (South)						Available Capacity for LL  Moment 54.9 kNm          Shear At 2d 102.9 kN/m At d 100.1 kN/m          Bridge Category Mg  <	

ATKINS		Project					Job ref 3044				
		NRA Eirspan Task Order 213									
		Part of Structure MO-N58-001.00		Assessment using BD21/01 RC Slabs		Calc sheet no. rev 7 0					
		Drawing Ref MO-N58-001.00		Calc By CP		Date 13-Feb-12					
						Check by PG					
						Date 14-Feb-12					
Ref		Calculations					Output				
Table 5.3.1 of BD21		<b>Single Axle Load</b>			Filler Beam - Span 1 (South)		Moment	Shear	Adequacy		
							Check	Check	for 40t		
		Assessment Loading			(Tonne)	7.5	40.0	40.0			
		Nominal Single Axle Load			(kN)	86	170	170			
		Wheel Contact Area			(m)	0.198	0.278	0.278			
		Minimum Distance Possible from edge of slab to centre line of first wheel in width direction			on left side	(m)	0.58	0.58	0.58		
					on right side	(m)	10.96	10.96	10.96		
		Dispersion for one axle, in transverse direction			b <sub>eff</sub>	1.53	1.69	1.69			
		Dispersion for two axle, in transverse direction			b' <sub>eff</sub>	2.99	3.23	3.23			
		Dispersion in longitudinal direction			b <sub>L</sub>	0.43	0.51	0.51			
		=> Load for one axle (P)			kN	86.0	170.0	170.0			
		Load for two axle (P')			kN	172	340	340			
		w = P/b <sub>eff</sub> b <sub>L</sub> assuming load dispersed long. & transversely			kN/m <sup>2</sup>	131.5	198.1	198.1			
		w' = P'/b' <sub>eff</sub> b <sub>L</sub> assuming load dispersed long. & transversely			kN/m <sup>2</sup>	134.3	206.9	206.9			
					Y <sub>fl</sub>	1.50	1.50	1.50			
					Y <sub>f3</sub>	1.0	1.0	1.0			
		Moment due to one axle			M <sub>LL</sub>	(kNm)	72	-	128		
		Moment due to two axles			M <sub>LL</sub>	(kNm)	74	-	133		
		Adequacy Factor				74%	-	41%			
		=>Loading Capacity (Moment)				<7.5t	-	-			
		Shear Due due to one axle at support					140.4	140.4			
		Shear Due due to two axles at support					146.7	146.7			
		Shear due to one axle at av = d			V <sub>LLav = d</sub>	(kN/m)	-	129	129		
		Shear due to two axle at av = d			V <sub>LLav = d</sub>	(kN/m)	-	135	135		
		Adequacy Factor				-	74%	74%			
		=>Loading Capacity (Shear) (av = d)				-	<40t	-			
		Shear due to one axle at av = 2d			V <sub>av = 2d</sub>	(kN/m)	-	117	117		
		Shear due to two axles av = 2d			V <sub>av = 2d</sub>	(kN/m)	-	122	122		
		Adequacy Factor					84%	84%			
		=>Loading Capacity (Shear)(av = 2d)				-	<40t	-			
		Table 5.3.1 of BD21		<b>Single Wheel Load</b>					Moment	Shear	Adequacy
									Check	Check	for 40t
Assessment Loading				(Tonne)	7.5	40.0	40.0				
Nominal Single Wheel Load				(kN)	43	86	86				
Wheel Contact Area				(m)	0.198	0.280	0.280				
Minimum Distance Possible from edge of slab to centre line of first wheel				on left side	(m)	0.58	0.58	0.58			
				on right side	(m)	10.96	10.96	10.96			
Dispersion for Wheel Load				b <sub>eff</sub>	0.76	0.85	0.85				
w = P/b <sub>eff</sub> <sup>2</sup> assuming load dispersed long. & transversely				kN/m <sup>2</sup>	73.6	120.0	120.0				
				Y <sub>fl</sub>	1.50	1.50	1.50				
				Y <sub>f3</sub>	1.0	1.0	1.0				
Moment Due Single Wheel Load				M <sub>LL</sub>	(kNm)	68.7	-	122.6			
Adequacy Factor					80%	-	45%				
=>Loading Capacity (Moment)					<7.5t	-	-				
Shear Due Single Wheel Load				V <sub>LL</sub>	(kN)	-	134.7	134.7			
Shear due to 40t av = d				V <sub>LLav = d</sub>	(kN)	-	123.0	123.0			
Adequacy Factor						81%	81%				
=>Loading Capacity (Shear) (av = d)						<40t	-				
Shear due to 40t av = 2d				V <sub>av = 2d</sub>	(kN)	-	111.2	111.2			
Adequacy Factor						93%	93%				
=>Loading Capacity (Shear)(av = 2d)						<40t	-				
Refer page 4 of Grillage O/p				Grillage Required		Y/N	Y				
				As Adequacy factor is only 41% for 40 tonnes loading, a grillage analysis was carried out.							
				<b>Grillage Analysis Output due to 40t load</b>							
						Moment (kNm/m)					
				Applied 40 t (factored for ULS)		56.8	Moment of 94.7 kNm is for 1m, 56.8kNm moment is for 0.6m				
				'LL Capacity of the section		54.9					
				Live Load Capacity Factor, C		0.76					
				Hence, Live Load Capacity		18t					
				Adequacy Factor for 40t:		97%					

Project		NRA Eirspan Task Order 213				Job ref 3044	
Part of Structure MO-N58-001.00		Assessment using BD21/01 RC Slabs				Calc sheet no. rev 8 0	
Drawing Ref MO-N58-001.00		Calc By CP		Date 13-Feb-12		Check by PG	Date 14-Feb-12
Ref	Calculations					Output	
Table 5.3.1 of BD21	<b>HB Load</b>						
							
				Moment	Shear		
	Assessment Loading		HB	30.0	45.0		
	Nominal Single Axle Load		(kN)	300	450		
	Wheel Contact Area		(m)	0.261	0.320		
	Minimum Distance Possible from edge of slab to centre line of first wheel						
		on left side	(m)	0.58	0.58		
		on right side	(m)	10.96	10.96		
	Dispersion for HB Axle		beff	0.83	0.89		
	=> Load for HB axle		kN	75.0	112.5		
			kN/m	90.6	126.9		
		Yf1		1.50	Moment Factor as per Influence Line ↓ 0.5 0.4 0.0 0.0		
		Yf3		1.0			
	Moment Capacity Check						
	Position of first axle from left support centre line		x1	1.07			
	Hence, distance of other axle from left support		x2	2.9			
			x3	0.0			
			x4	0.0			
	Moment Due to HB Load	M <sub>LL</sub>	(kNm)	75			
	Adequacy Factor			73%			
	=>Loading Capacity (Moment)			<30HB			
	Shear Capacity Check			for shear at d	for shear at 2d	Shear Factor at d	Shear Factor at 2d
	Position of first axle from left support centre line		x1	0.42	0.70	0.88	0.8
	Hence, distance of other axle from left support		x2	2.2	2.5	0.07	0.1
			x3	0.000	0.0	0.00	0.0
	Shear Due HB Loading		x4	0.000	0.0	0.00	0.0
	Shear at av = d	V <sub>LLav = d</sub>	(kN/m)	109			HB Load
	Adequacy Factor			91%			
	=>Loading Capacity (Shear) (av = d)			<45HB			
	Shear at av = 2d	V <sub>av = 2d</sub>	(kN/m)	109			Moment Capacity <30HB
	Adequacy Factor			94%			
	=>Loading Capacity (Shear)(av = 2d)			<45HB			Shear Capacity <45HB
Ref Page 13&14	<b>Check Bond Stress</b>						Bond Capacity <30HB
	Moment Capacity for non composite section		=	<30HB	Assuming no contribution from Concrete		
	Adequacy Factor for 45HB			26%			



ATKINS		Project			NRA Eirspan Task Order 213			Job ref																																																																																						
		Part of Structure			Section Properties MO-N58-001.00			3044																																																																																						
								Calc sheet no. rev																																																																																						
Drawing Ref			Calc By			Date			Check by			Date																																																																																		
MO-N58-001.00			CP			13-02-12			PG			13-02-12																																																																																		
Ref		Calculations								Output																																																																																				
Top Flange Web Bot Flange		<div>Section Properties</div> <div>Cracked Section properties</div> <div></div> <div><div>Idealised Section Short Term</div><div><div>fcu = 13.3</div><div>Ec = (20 + 0.27fcu) = 24</div><div>Es = 205    m = Es / Ec = 8.69</div></div></div>																																																																																												
		<table><tr><th>Sr No.</th><th>b</th><th>h</th><th>No.</th><th>Es/Ec</th><th>Area b x h</th><th>CG y-y (y)</th><th>Ay</th><th>Ay²</th><th>Iself</th><th></th></tr><tr><td>1</td><td>600</td><td>184.63</td><td>1</td><td>1.00</td><td>110778</td><td>247.685</td><td>27438064</td><td>6.796E+09</td><td>314686364</td><td>Concrete</td></tr><tr><td>2</td><td>50</td><td>30</td><td>1</td><td>8.69</td><td>13034.6</td><td>170</td><td>2215887.4</td><td>376700860</td><td>112500</td><td>Steel</td></tr><tr><td>3</td><td>10</td><td>85</td><td>1</td><td>8.69</td><td>7386.29</td><td>112.5</td><td>830957.78</td><td>93482750</td><td>511770.83</td><td>Steel</td></tr><tr><td>4</td><td>125</td><td>10</td><td>1</td><td>8.69</td><td>10862.2</td><td>65</td><td>706042.56</td><td>45892766</td><td>10416.667</td><td>Steel</td></tr><tr><td colspan="5"></td><td>Σ A</td><td>Σ y</td><td>Σ Ay</td><td>Σ Ay²</td><td>Σ Iself</td><td></td></tr><tr><td colspan="5">Sum</td><td>142061</td><td>595.185</td><td>31190951</td><td>7.312E+09</td><td>315321051</td><td></td></tr></table>											Sr No.	b	h	No.	Es/Ec	Area b x h	CG y-y (y)	Ay	Ay²	Iself		1	600	184.63	1	1.00	110778	247.685	27438064	6.796E+09	314686364	Concrete	2	50	30	1	8.69	13034.6	170	2215887.4	376700860	112500	Steel	3	10	85	1	8.69	7386.29	112.5	830957.78	93482750	511770.83	Steel	4	125	10	1	8.69	10862.2	65	706042.56	45892766	10416.667	Steel						Σ A	Σ y	Σ Ay	Σ Ay²	Σ Iself		Sum					142061	595.185	31190951	7.312E+09	315321051						
		Sr No.	b	h	No.	Es/Ec	Area b x h	CG y-y (y)	Ay	Ay²	Iself																																																																																			
		1	600	184.63	1	1.00	110778	247.685	27438064	6.796E+09	314686364	Concrete																																																																																		
		2	50	30	1	8.69	13034.6	170	2215887.4	376700860	112500	Steel																																																																																		
		3	10	85	1	8.69	7386.29	112.5	830957.78	93482750	511770.83	Steel																																																																																		
		4	125	10	1	8.69	10862.2	65	706042.56	45892766	10416.667	Steel																																																																																		
							Σ A	Σ y	Σ Ay	Σ Ay²	Σ Iself																																																																																			
		Sum					142061	595.185	31190951	7.312E+09	315321051																																																																																			
		<div><div><div>YCG = Σ Ay / Σ A    for bottom</div><div>= 31190951.4 / 142061.211</div><div>= 219.56    mm</div></div><div><div>IcG = Iyy - ( Σ A x yCG² )</div><div>Iyy = ( Σ Iself + Σ Ay² )</div><div>IcG = ( Σ Iself + Σ Ay² ) - ( Σ A x yCG² )</div><div>= ( 3.2E+08 + 7.3E+09 ) - ( 142061 ) x ( 219.56² )</div><div>= 7.79E+08    mm4</div></div></div>																																																																																												
<div><div>Idealised Section Long Term</div><div><div>Es = 205    m = Es / Ec = 17.38</div></div></div>																																																																																														
<table><tr><th>Sr No.</th><th>b</th><th>h</th><th>No.</th><th>Es/Ec</th><th>Area b x h</th><th>CG y-y (y)</th><th>Ay</th><th>Ay²</th><th>Iself</th><th></th></tr><tr><td>1</td><td>600</td><td>184.63</td><td>1</td><td>1.00</td><td>110778</td><td>247.685</td><td>27438064</td><td>6.796E+09</td><td>314686364</td><td>Concrete</td></tr><tr><td>2</td><td>50</td><td>30</td><td>1</td><td>17.38</td><td>26069.3</td><td>170</td><td>4431774.8</td><td>753401721</td><td>112500</td><td>Steel</td></tr><tr><td>3</td><td>10</td><td>85</td><td>1</td><td>17.38</td><td>14772.6</td><td>112.5</td><td>1661915.6</td><td>186965501</td><td>511770.83</td><td>Steel</td></tr><tr><td>4</td><td>125</td><td>10</td><td>1</td><td>17.38</td><td>21724.4</td><td>65</td><td>1412085.1</td><td>91785533</td><td>10416.667</td><td>Steel</td></tr><tr><td colspan="5"></td><td>Σ A</td><td>Σ y</td><td>Σ Ay</td><td>Σ Ay²</td><td>Σ Iself</td><td></td></tr><tr><td colspan="5">Sum</td><td>173344</td><td>595.185</td><td>34943839</td><td>7.828E+09</td><td>315321051</td><td></td></tr></table>											Sr No.	b	h	No.	Es/Ec	Area b x h	CG y-y (y)	Ay	Ay²	Iself		1	600	184.63	1	1.00	110778	247.685	27438064	6.796E+09	314686364	Concrete	2	50	30	1	17.38	26069.3	170	4431774.8	753401721	112500	Steel	3	10	85	1	17.38	14772.6	112.5	1661915.6	186965501	511770.83	Steel	4	125	10	1	17.38	21724.4	65	1412085.1	91785533	10416.667	Steel						Σ A	Σ y	Σ Ay	Σ Ay²	Σ Iself		Sum					173344	595.185	34943839	7.828E+09	315321051								
Sr No.	b	h	No.	Es/Ec	Area b x h	CG y-y (y)	Ay	Ay²	Iself																																																																																					
1	600	184.63	1	1.00	110778	247.685	27438064	6.796E+09	314686364	Concrete																																																																																				
2	50	30	1	17.38	26069.3	170	4431774.8	753401721	112500	Steel																																																																																				
3	10	85	1	17.38	14772.6	112.5	1661915.6	186965501	511770.83	Steel																																																																																				
4	125	10	1	17.38	21724.4	65	1412085.1	91785533	10416.667	Steel																																																																																				
					Σ A	Σ y	Σ Ay	Σ Ay²	Σ Iself																																																																																					
Sum					173344	595.185	34943839	7.828E+09	315321051																																																																																					
<div><div><div>YCG = Σ Ay / Σ A    for bottom</div><div>= 34943839.1 / 173344.327</div><div>= 201.59    mm</div></div><div><div>IcG = Iyy - ( Σ A x yCG² )</div><div>Iyy = ( Σ Iself + Σ Ay² )</div><div>IcG = ( Σ Iself + Σ Ay² ) - ( Σ A x yCG² )</div><div>= ( 3.2E+08 + 7.8E+09 ) - ( 173344 ) x ( 201.586² )</div><div>= 1.10E+09    mm4</div></div></div>																																																																																														

Ref

Calculations

Ouput

## Check bond stress of section

Dimensions in mm

Allowable $f_{cu}$	13.3
$\gamma_{mc}$	1.05
Allowable $f_{st}$	230
$\gamma_{ms}$	1.05
$\gamma_{f3}$	1.1
Bottom Cover	60

b	600
$d_c$	340
$d_s$	125
$A_{st}$	1500
$t_{ft}$	30
$t_{fb}$	10
$A_{sb}$	1250
$t_w$	10

### Short Term Ec (BD 44/95 cl. 4.3.2.1)

$$E_c = (20 + 0.27f_{cu}) = 24$$


$$E_s = 205 \quad m = E_s / E_c = 8.69$$

### Long Term Ec (BD 44/95 cl. 4.3.2.1)

$$\text{Twice Short Term } m = 17.38$$

$$\text{Allowable Conc stress} = 0.75f_{cu}/\gamma_{mc}\gamma_{f3} = 8.636$$

$$\text{Allowable steel stress} = f_{st}/\gamma_{ms}\gamma_{f3} = 199.134$$



### Uncracked Section for Grillage Analysis

#### Short Term Long Term Ec

$$m = 8.69 \quad 17.38$$

$$x = 184.63 \quad 195.83 \quad \text{mm}$$

$$\text{Area of section (concrete units)} = 235283.12 \quad 266566.23 \quad \text{mm}^2$$

$$\text{Area of section (steel units)} = 27075.92 \quad 15337.96 \quad \text{mm}^2$$

$$I_{NA} \text{ (concrete units)} = 2.10\text{E}+09 \quad 2.22\text{E}+09 \quad \text{mm}^4$$

$$I_{NA} \text{ (steel units)} = 2.72\text{E}+08 \quad 1.55\text{E}+08 \quad \text{mm}^4$$

### Cracked Section

#### Short Term Long Term Ec

$$m = 8.69 \quad 17.38$$

$$x = 153.27 \quad 161.20 \quad \text{mm}$$

$$\text{Area of concrete in compression} = 91962.82 \quad 96717.02 \quad \text{mm}^2$$

$$\text{Centroid of conc. in comp. (from NA)} = 76.64 \quad 80.60 \quad \text{mm}$$

$$I_{NA} \text{ (cracked section)} = 7.79\text{E}+08 \quad 1.10\text{E}+09 \quad \text{mm}^4$$

$$A * y / I_{NA} = 0.00905 \quad 0.00709 \quad /\text{mm}$$

BD61/10 Cl 8.5.1: "The bond may be assumed to be developed uniformly only over both sides of the web and the upper surface of the top and bottom flanges of the steel beam where there is complete encasement and over both sides of the web and the upper surface of the top flange of the steel beam where the beam soffit is exposed."

Hence, as cover to soffit of bottom flange is 60mm,  $L_s = 335 \quad \text{mm}$

Ref

Calculations

Ouptut

## Check for Max Shear (at support) 40t

Serviceability Loads (F)

Shear at support	kN
Dead Load	14.66
Live Load	49.00

$$\text{Shear Force} = Fy/I_{NA} \quad \text{Live Load} \quad 443.24 \quad \text{Dead Load} \quad 103.99 \quad \text{N/mm}$$

$$\text{Bond stress} = 1.323 \quad 0.310 \quad \text{N/mm}^2$$


$$\text{Total bond stress} = 1.634 \quad \text{N/mm}^2$$

$$\text{Allowable bond stress at SLS} = 0.700 \quad \text{N/mm}^2$$

**Result:** Section is unsuitable for composite action (see BD 61/10 Clause 8.5.1)

## Check capacity of section unsuitable for composite action

Find distance x such that bond stress due to combined Dead Load and Live Load = 0.7N/mm<sup>2</sup>



**Legend:**

bond stress < 0.7N/mm<sup>2</sup>  
suitable for composite action

bond stress > 0.7N/mm<sup>2</sup>  
unsuitable for composite action

Vary x until bond stress = allowable bond stress

Try x = **1.75** m (Max x = L/2 = 1.82 m)

Okay Hint: Use Goalseek

Serviceability Loads (F)

Shear at location x	kN
Dead Load	<b>0.60</b>
Live Load	<b>9.49</b>

$$\text{Long'l Shear Force} = Fy/I_{NA} \quad \text{Live Load} \quad 85.82 \quad \text{Dead Load} \quad 4.28 \quad \text{N/mm}$$

$$\text{Bond stress using} = 0.256 \quad 0.013 \quad \text{N/mm}^2$$

$$\text{Total bond stress} = \mathbf{0.269} \quad \text{N/mm}^2$$

$$\text{Allowable bond stress at SLS} = \mathbf{0.700} \quad \text{N/mm}^2$$

**Result:** Bond stress okay

## Check corresponding moment capacity at x

Factor K for 40 tonne loading 0.79

Moment Capacity of steel section 25.58 kNm

Moment Capacity of composite section 38.41 kNm

ULS Moment at x	kNm
Dead Load	16.82

Available capacity for live load 8.76

Live Load	66.77
-----------	-------

Factor C for Moment 0.10

Loading Capacity Moment **<3t**

Adequacy Factor 0.13


as per Figure 5.6

(HA + KEL Eqv.)

Moment Capacity


<3t

## Dead Load



q	8.06	kN/m	unfactored
L	3.64	m	
x	<b>1.75</b>	m	

RA=RB =	14.66 kN
Vx	0.60 kN
Vmax	14.66 kN
Mx	13.32 kNm
Mmax	13.35 kNm




Ref

Calculations


Ouput

## HA UDL Live Load




q	18.36	kN/section
L	3.64	m
x	1.75	m

$R_A = R_B = 33.42 \text{ kN}$   
 $V_x = 1.38 \text{ kN}$   
 $V_{max} = 33.42 \text{ kN}$   
 $M_x = 30.36 \text{ kNm}$   
 $M_{max} = 30.41 \text{ kNm}$




## HA KEL Live Load



P	15.58	kN
L	3.64	m
a	1.75	
b	1.89	
x	1.75	m

$R_A = 8.11 \text{ kN}$   
 $R_B = 7.47 \text{ kN}$   
 $V_x = 8.11 \text{ kN}$   
 $V_{max} = 15.58 \text{ kN}$   
 $M_x = 14.16 \text{ kNm}$   
 $M_{max} = 14.16 \text{ kNm}$   
 $M_{max} \text{ P at centre} = 14.18 \text{ kNm}$



## Combined Continuos + Point Load

per m width  
 Combined Moment  $M_x = 44.51 \text{ kNm}$   
 Combined Shear  $V_x = 9.49 \text{ kN}$

ULS ( $\gamma_f=1.5$ )  
 66.77  
 14.23

Max M 44.59 kNm  
 Max V 49.00 kN

ULS ( $\gamma_f=1.5$ )  
 66.88 kNm  
 73.50 kN

Ref	<div>ATKINS</div>	Project NRA Eirspan Task Order 213			Job ref 3044.00																																																	
		Part of Structure MO-N58-001.00		Filler Beam Capacity		Calc sheet 14	Rev 0.00																																															
		Drawing ref.	Calc by CP	Date 2012-02-13	Check by PG	Date 2012-02-14																																																
Ref	Calculations					Ouput																																																
<div><div>HB Live Load</div><div><div>Check for Max Shear (at support) 45HB</div><div>Serviceability Loads (F)</div><table><tr><td>Shear at support</td><td>kN</td></tr><tr><td>Dead Load</td><td>14.66</td></tr><tr><td>Live Load</td><td>72.98</td></tr></table><div><div><div><div></div><div>Live Load</div></div><div><div></div><div>Dead Load</div></div></div><div><div>Longt'l Shear Force = <math>F_{Ay}/I_{NA}</math></div><div>660.13</div><div>103.99</div><div>N/mm</div></div><div><div>Bond stress using=</div><div>1.971</div><div>0.310</div><div>N/mm<sup>2</sup></div></div><div><div>Total bond stress using =</div><div>2.281</div><div>N/mm<sup>2</sup></div></div><div><div>Allowable bond stress at SLS =</div><div>0.700</div><div>N/mm<sup>2</sup></div></div><div><div>Result:</div><div>Bond Stress (2.28) greater or equal than Permissible Bond Stress (0.7) hence section is unsuitable for composite action (see BD 61/10 Clause 8.5.1)</div></div><div><div>Check section at x</div><div><div>45HB Loading</div><div>Try x = 1.55 m</div><div>Load 45.00 HB</div><div>reduce x Hint:Use Goalseek</div><div>Serviceability Loads (F)</div><table><tr><td>Shear at location x</td><td>kN</td></tr><tr><td>Dead Load</td><td>2.14</td></tr><tr><td>Live Load</td><td>8.22</td></tr></table></div></div><div><div>Check for Shear at x - 45HB</div><div><div>Note: If bottom flange is exposed use <math>L_{S1}</math> otherwise use <math>L_{S2}</math></div><div><div><div><div></div><div>Live Load</div></div><div><div></div><div>Dead Load</div></div></div><div><div>Longt'l Shear Force = <math>F_{Ay}/I_{NA}</math></div><div>74</div><div>15.19</div><div>N/mm</div></div><div><div>Bond stress=</div><div>0.222</div><div>0.045</div><div>N/mm<sup>2</sup></div></div><div><div>Total bond stress=</div><div>0.267</div><div>N/mm<sup>2</sup></div></div><div><div>Allowable bond stress at SLS =</div><div>0.7</div><div>0.700</div><div>N/mm<sup>2</sup></div></div><div><div>Result:</div><div>Bond stress okay using <math>L_{S2}</math></div></div><div><div><div><div><div><div></div><div>q</div></div><div><div><div><div>A</div><div>B</div></div><div><div><div><div><div></div><div><math>R_A</math></div></div><div><div><div><div></div><div><math>R_B</math></div></div></div></div><div><div><div><div><div></div><div>x</div></div><div><div><div><div>a</div><div>b</div><div>c</div></div><div><div><div><div>L</div></div></div></div></div></div></div></div></div></div><div><div>beff = 0.83 m</div><div>(beff/2)</div><div>Suggested values for x 0.41 m</div></div></div><div><div>Live Load at x</div><table><tr><td>q</td><td>90.59</td><td>kN/section</td></tr><tr><td>a</td><td>1.14</td><td>m</td></tr><tr><td>b</td><td>0.83</td><td>m</td></tr><tr><td>c</td><td>1.67</td><td>m</td></tr><tr><td>L</td><td>3.64</td><td>m</td></tr><tr><td>x</td><td>1.55</td><td>m</td></tr></table><div><div><div>RA</div><div>42.98 kN</div></div><div><div>RB</div><div>32.02 kN</div></div><div><div>Vx</div><div>5.48 kN</div></div><div><div>Vmax</div><div>42.98 kN</div></div><div><div>Mx</div><div>59.03 kNm</div></div><div><div>Mmax</div><div>59.20 kNm</div></div><div><div>ULS</div><div>8.22 kN</div></div><div><div></div><div>64.47 kN</div></div><div><div></div><div>88.55 kNm</div></div><div><div></div><div>88.80 kNm</div></div></div></div><div><div>Dead Load at x</div><table><tr><td>q</td><td>8.06</td><td>kN/m</td></tr><tr><td>L</td><td>3.64</td><td>m</td></tr><tr><td>x</td><td>1.55</td><td>m</td></tr></table><div><div>unfactored</div><div><div>RA=RB = 14.66 kN</div><div>Vx 2.14 kN</div><div>Vmax 14.66 kN</div><div>Mx 13.06 kNm</div><div>Mmax 13.35 kNm</div></div></div></div><div><div>Check corresponding moment capacity at x</div><table><tr><td>ULS Moment at x</td><td>kNm</td></tr><tr><td>Dead Load</td><td>15.02</td></tr><tr><td>Available capacity for live load</td><td>23.39</td></tr><tr><td>45HB Live Load</td><td>88.80</td></tr></table><div><div>Adequacy</div><div>0.26</div><div>Fail</div></div></div></div><div><div>Moment Capacity &lt;45HB</div></div></div></div></div></div></div></div></div></div></div></div></div></div>								Shear at support	kN	Dead Load	14.66	Live Load	72.98	Shear at location x	kN	Dead Load	2.14	Live Load	8.22	q	90.59	kN/section	a	1.14	m	b	0.83	m	c	1.67	m	L	3.64	m	x	1.55	m	q	8.06	kN/m	L	3.64	m	x	1.55	m	ULS Moment at x	kNm	Dead Load	15.02	Available capacity for live load	23.39	45HB Live Load	88.80
Shear at support	kN																																																					
Dead Load	14.66																																																					
Live Load	72.98																																																					
Shear at location x	kN																																																					
Dead Load	2.14																																																					
Live Load	8.22																																																					
q	90.59	kN/section																																																				
a	1.14	m																																																				
b	0.83	m																																																				
c	1.67	m																																																				
L	3.64	m																																																				
x	1.55	m																																																				
q	8.06	kN/m																																																				
L	3.64	m																																																				
x	1.55	m																																																				
ULS Moment at x	kNm																																																					
Dead Load	15.02																																																					
Available capacity for live load	23.39																																																					
45HB Live Load	88.80																																																					

**Check for Max Shear (at support) 30HB**

## Serviceability Loads (F)

Serviceability Loads (kN)	
Shear at support	kN
Dead Load	14.66
Live Load	48.65

**Note: If bottom flange is exposed use  $L_{S1}$  otherwise use  $L_{S2}$**

	<u>Live Load</u>	<u>Dead Load</u>	
Longt'l Shear Force = $F_{Ay}/I_{NA}$	440.08	103.99	N/mm
Bond stress=	1.314	0.310	N/mm <sup>2</sup>
Total bond stress=	1.624		N/mm <sup>2</sup>
Allowable bond stress at SLS =	0.700		N/mm <sup>2</sup>

**Result:** Bond Stress (1.62) greater or equal than Permissible Bond Stress (0.7) hence section is unsuitable for composite action (see BD 61/10 Clause 8.5.1)

**Check section at x 30HB**

Vary  $x$  until bond stress = allowable bond stress

**Loading** Try x =  m Load  HB  
reduce x Hint: Use Goalseek

## Serviceability Loads (F)


Shear at location x	kN
Dead Load	<b>2.14</b>
Live Load	<b>8.22</b>

	<u>Live Load</u>	<u>Dead Load</u>	
Longitud Shear Force = $F_{Ay}/I_{NA}$	74	15.19	N/mm
Bond stress=	0.222	0.045	N/mm <sup>2</sup>
Total bond stress=	<b>0.267</b>		N/mm <sup>2</sup>
Allowable bond stress at SLS = 0.7	<b>0.700</b>		N/mm <sup>2</sup>

**Result:** Bond stress okay using Ls2

### Use Composite Section

**Live Load at x**


$$b_{eff} = 0.83 \text{ m}$$

q	90.59	kN/section
a	1.14	m
b	0.83	m
c	1.67	m
L	3.64	m
x	1.55	m

RA	42.98 kN		
RB	32.02 kN	ULS	
Vx	5.48 kN	8.22	kN
Vmax	42.98 kN	64.47	kN
Mx	59.03 kNm	88.55	kNm
Mmax	59.20 kNm	88.80	kNm

## Dead Load at x

q	8.06	kN/m	unfactored
L	3.64	m	
x	1.55	m	

RA=RB =	14.66 kN
Vx	2.14 kN
Vmax	14.66 kN
Mx	13.06 kNm
Mmax	13.35 kNm

ULS Moment at x	kNm
Dead Load	15.02
Available capacity for live load	23.39
30HB Live Load	88.80

Adequacy	0.26	Fail
----------	------	------

**Moment Capacity**  
**<30HB**

ATKINS	Project NRA Eirspan Task Order 213			Job ref 3044																							
	Part of Structure MO-N58-001.00			Calc sheet no. rev 1 0																							
	Drawing Ref MO-N58-001.00	Calc By CP	Date 13-Feb-12	Check by PG	Date 14-Feb-12																						
Ref	Calculations				Output																						
App. C1 /SI Report	<b>ASSESSMENT SUMMARY:</b> Filler Beam Span 2 (North)																										
	<table><tr><td></td><td>HA UDL &amp; KEL</td><td>Single Axle</td><td>Single Wheel</td><td>HB</td><td>Punching Shear</td></tr><tr><td>Moment</td><td>40t</td><td>40t</td><td>40t</td><td>30HB</td><td>-</td></tr><tr><td>Shear</td><td>40t</td><td>40t</td><td>40t</td><td>45HB</td><td>0</td></tr><tr><td>Bond</td><td>&lt;3t</td><td>-</td><td>-</td><td>&lt;30HB</td><td>-</td></tr></table>						HA UDL & KEL	Single Axle	Single Wheel	HB	Punching Shear	Moment	40t	40t	40t	30HB	-	Shear	40t	40t	40t	45HB	0	Bond	<3t	-	-
	HA UDL & KEL	Single Axle	Single Wheel	HB	Punching Shear																						
Moment	40t	40t	40t	30HB	-																						
Shear	40t	40t	40t	45HB	0																						
Bond	<3t	-	-	<30HB	-																						
App. C1 /SI Report	<b>CALCULATION OF REBAR SPACING</b>																										
	<b>MID SPAN</b> <div><div>Spacing (mm)</div><div>MAIN BEAM 600</div></div> <div>Average beam spacing 600</div> <div>Depth of beam 125 mm</div> <div>Bottom Cover 70 mm</div>																										
App. C1 /SI Report	<b>NEAR SUPPORT</b> <div><div>Spacing (mm)</div><div>MAIN BEAM 600</div></div> <div>Average rebar spacing 600</div> <div>Depth of beam 125 mm</div> <div>Bottom Cover 70 mm</div>																										

**CALCULATION OF WORST CREDIBLE STRENGTH**

Input a maximum of 11 Core samples

LOCATION	CORE REFERENCE	ESTIMATED IN-SITU CUBE STRENGTH N/mm <sup>2</sup> (f <sub>c</sub> )	(f <sub>c</sub> - MEAN) <sup>2</sup>
	<b>C1</b>	<b>31.3</b>	0.93
	<b>C2</b>	<b>28.0</b>	5.44
	<b>C3</b>	<b>31.7</b>	1.87
			-
			-
			-
			-
			-
			-
			-
<b>TOTAL</b>		91	8.2466667
<b>No of cores</b>		3	
<b>MEAN</b>		30.33	
<b>Standard Deviation</b>		2.03	

WCS will be calculated using 2 different methods:

**1) LOCATION :** Using equation from BA 44/96 with n = total number of core samples

**Note** - only use this for cores taken at the location of interest

n = 3

From BA 44/90,  $WCS = (Total\ f_c \cdot (100 - (20/n^{0.5}))) / 100n$ 


WCS = **26.8 N/mm<sup>2</sup>**
**2) LOWEST CORE STRENGTH :**

Lowest core strength = 28.0 N/mm<sup>2</sup>

WCS = **28.0 N/mm<sup>2</sup>**

Using the above results and engineering judgement,  
the proposed WCS = **26.8 N/mm<sup>2</sup>**

Ref	Calculations									
	<b><u>SAGGING - SECTION PROPERTIES (Using BS 5400 Part 3:2000) for composite section</u></b>									
	<b>Slab</b>		Width (mm)	Depth (mm)		f <sub>cu</sub> (MPa)	E(short Term)	Panel Length (mm)	Section depth mm	
		Slab	600	340		26.8	27.2		50	
	<b>Haunch</b>		Width (mm)	Depth (mm)		f <sub>cu</sub> (MPa)	E(short Term)	NA		
		Haunch	0	0		0	0	NA		
	<b>Girder</b>		Width (mm)	Depth (mm)		f <sub>y</sub> (MPa)	E (GPa)		m	7.52
		Top Flange	50	30		230	205.0			
		Web	85	10		230	205.0			
		Bottom Flange	125	10		230	205.0			
	Bottom Cover			70	mm					
	<b>e) Plastic Section Properties</b>									
	nb if NA lies below the web this doesn't work									
	Stress in concrete = 0.4*f <sub>cu</sub>									
	Stress in steel = σ <sub>y</sub> /γ <sub>m</sub>									



Ref

Calculations

SAGGING - SECTION PROPERTIES (Using BS 5400 Part 3:2000) for Steel Section (IGNORING CONCRETE)

Slab		Width (mm)	Depth (mm)		fcu (MPa)	E(short Term)	Panel Length (mm)	Section depth mm 50	
	Slab	600	50		26.8307417	27.24430026			
Haunch		Width (mm)	Depth (mm)		fcu (MPa)	E(short Term)	NA		
	Haunch	0	0		0	0	NA		
Girder		Width (mm)	Depth (mm)		f <sub>y</sub> (MPa)	E (GPa)			
	Top Flange	50	30		230	205			
	Web	85	10		230	205			
	Bottom Flange	125	10		230	205			
Bottom Cover			70	mm					

e) Plastic Section Properties

nb if NA lies below the web this doesn't work

Stress in concrete = 0.4\*f<sub>cu</sub>

Stress in steel = σ<sub>y</sub>/γ<sub>m</sub>γ<sub>m</sub> = 1.05

Condition factor for RC Filler-0.9

	Depth (mm)	Width (mm)	Area (mm <sup>2</sup> )	Stress (Nmm <sup>-2</sup> )	Force (kN)	Force above NA (kN)	Force below NA (kN)	y above NA (mm)	y below NA (mm)
Slab*	-70	600	-42000	11	-451	-451	-	35	-
Haunch	0	0	0	0	0	0	-	0	-
Top Flange	30	50	1500	219	329	329	0	55	-40
Web	10	85	850	219	186	186	0	35	-30
Bottom Flange	10	125	1250	219	274	-	274	-	-25

NA lies in

Below Web

\*Concrete above beam only taken in properties

Depth of Neutral Axis From Top Slab

Depth (mm)	
Slab	0.0
Haunch	0.0
Top Flange	0.0
Web	0.0

m=

4.0

Concrete M<sub>plastic</sub> =

-16

kNm

Single Beam M<sub>plastic</sub> =

16

kNm

Depth of Plastic NA =

0.0

f) Compactness Check

9.3.7.2

If m < 0.5

Check web depth is less than

(34t<sub>w</sub>/m)\*(355/σ<sub>yw</sub>)^0.5

n/a

mm

(Compact?)

n/a

If m > 0.5

Check web depth is less than

(374t<sub>w</sub>/(13m-1))\*(355/σ<sub>yw</sub>)^0.5

774.40939

mm

yes

If web fully in tension section is compact

n/a

Section is Compact

SAGGING - PLASTIC CHECKS (Using BS 5400 Part 3:2000)


2. ULS Bending Capacity of Section


M <sub>plastic</sub> =	2	kNm	
M <sub>pe</sub> (unfactored) =	2	kNm	
M <sub>D</sub> = M <sub>pe</sub> / 1.05 x 1.1 =	2	kNm	(Also Adjusted by condition factor)



ATKINS	Project				NRA Eirspan Task Order 213		Job ref 3044	
	Part of Structure MO-N58-001.00			Assessment using BD21/01 RC Slabs		Calc sheet no. rev 6 0		
	Drawing Ref MO-N58-001.00			Calc By CP		Date 13-Feb-12	Check by PG	Date 14-Feb-12
Ref	Calculations						Output	
Table 3.1/ BD21 Cl.3. 1/ BD21 & Cl. 4.2.3/ BD 44	Filler Beam Span 2 (North)							
	<b>Calculation of Moment due to Permanent Loads at Mid Span &amp;</b>							
	<b>Calculation of Shear due to Permanent Loads near supports:</b>							
	Self weight	Load	(kN/m2)	5.1	SLS Shear (kN)	9.2		
		Yfl		1.15				
		Yf3		1.0				
		M <sub>sw</sub>	(kNm/m)	9.5				
		V <sub>sw</sub>	(kN/m)	10.6				
	Surfacing	Load	(kN/m2)	1.4	2.5			
		Yfl		1.75				
		Yf3		1.0				
		M <sub>s</sub>	(kNm/m)	3.9				
		V <sub>s</sub>	(kN/m)	4.4				
	Fill	Load	(kN/m2)	1.6	2.8			
		Yfl		1.20				
		Yf3		1.0				
		M <sub>fill</sub>	(kNm/m)	3.0				
		V <sub>fill1</sub>	(kN/m)	3				
	Hence, Capacity Available for LL, M <sub>CLL</sub>		(kNm/m)	105	14.5 kN			
	Distance (x) from support to face of support		(mm)	135				
	Shear at support		V <sub>LLsup</sub>	(kN/m)	18			
	Shear at av <sub>1</sub> = 2d		V <sub>LLav1 = 2d</sub>	(kN/m)	11			
	Shear at av <sub>2</sub> = d		V <sub>LLav2 = d</sub>	(kN/m)	14			
	Hence, Capacity Available for LL, V <sub>CLL= 2d</sub>		(kNm/m)	301	At 2d	300.5 kN/m		
	Hence, Capacity Available for LL, V <sub>CLL= d</sub>		(kNm/m)	298	At d	297.8 kN/m		
<b>Traffic Flows &amp; Surface Condition</b>								
Cl. 5.21/ BD 21	Annual Average Daily Traffic (Ref P I Report)			4147				
	Percentage of heavy vehicles			5%				
	Annual average hourly HGV flow (AAHHGVF)			9				
	Traffic Flow Cl.5.2.2 of BD 21		L/M/H	Medium				
	Condition of road surfacing (Good/ Poor)			Good				
	Therefore Bridge Category			Mg				
	Factor K for 40 tonne loading			0.79				
<b>HA + KEL and Equiv. 40 t Assessment Loading</b>								
Cl. 5.18/ BD21	HA Loading	UDL	(kN/m)	142.2				
		KEL	(kN)	120.0				
Cl. 5.23/ BD 21	Lane Factor			1.0				
	Adjustment Factor	AF		1.46				
Cl. 5.27/ BD 21	Therefore, Equivalent 40 t loading	UDL	(kN/m2)	30.77	SLS shear			
		KEL	(kN/m)	25.97				
		Yfl		1.50	49 kN			
		Yf3		1.0				
	Moment Due 40 tonne loading	M <sub>LL</sub>	(kNm)	66				
	Shear due to 40t at support	V <sub>LLsup</sub>	(kN/m)	73				
	Shear due to 40t av = 2d	V <sub>av = 2d</sub>	(kN/m)	51				
	Shear due to 40t av = d	V <sub>LLav = d</sub>	(kN/m)	60				
	Factor C for Moment at midspan			1.26	(HA + KEL Eqv.) Moment Capacity 40t			
	Loading Capacity Moment at midspan		40t	as per Figure 5.6				
Factor C for Shear at 3*d			3.24	Shear Capacity 40t				
Factor C for Shear at d			4.60					
Loading Capacity Shear		40t	as per Figure 5.6					
<b>Check bond stress at support where shear is maximum</b>								
Ref page 11	SLS Shear at support Dead Load		kN	14.50	Bond Stress (N/mm2)	Permissible Stress (N/mm2)		
	SLS Shear at support Live Load		kN	48.91	4.71	0.7		
	Is bond stress okay? Y/N			N				
	Load Capacity where bond stress exceeded			<3t	Assuming no contribution from Concrete			
	Adequacy Factor for Bond Stress			0%				
Adequacy Factor for Moment at Midspan			159%	40 t Adequacy				
Adequacy Factor for Shear			410%	159%				

ATKINS		Project					NRA Eirspan Task Order 213		Job ref 3044							
		Part of Structure MO-N58-001.00			Assessment using BD21/01			RC Slabs		Calc sheet no. rev 7 0						
		Drawing Ref MO-N58-001.00			Calc By CP			Date 13-Feb-12		Check by PG		Date 14-Feb-12				
Ref		Calculations									Output					
Table 5.3.1 of BD21		<b>Single Axle Load</b>			Filler Beam Span 2 (North)		Moment		Shear		Adequacy					
							Check		Check		for 40t					
		Assessment Loading			(Tonne)		7.5		40.0		40.0					
		Nominal Single Axle Load			(kN)		86		170		170					
		Wheel Contact Area			(m)		0.198		0.278		0.278					
		Minimum Distance Possible from edge of slab to centre line of first wheel in width direction			on left side		(m)		0.58		0.58		0.58			
					on right side		(m)		10.96		10.96		10.96			
		Dispersion for one axle, in transverse direction			beff		1.35		1.51		1.51					
		Dispersion for two axle, in transverse direction			b'eff		2.69		2.96		2.96					
		Dispersion in longitudinal direction			bL		0.43		0.51		0.51					
		=> Load for one axle (P)			kN		86.0		170.0		170.0					
		Load for two axle (P')			kN		172		340		340					
		w = P/b <sub>eff</sub> b <sub>L</sub> assuming load dispersed long. & transversely			kN/m <sup>2</sup>		149.5		222.2		222.2					
		w' = P'/b' <sub>eff</sub> b <sub>L</sub> assuming load dispersed long. & transversely			kN/m <sup>2</sup>		149.5		226.2		226.2					
					Yfl		1.50		1.50		1.50					
					Yf3		1.0		1.0		1.0					
		Moment due to one axle			M <sub>LL</sub>		(kNm)		81		-		142			
		Moment due to two axles			M <sub>LL</sub>		(kNm)		81		-		145			
		Adequacy Factor							129%		-		73%			
		=>Loading Capacity (Moment)							7.5t		-		-			
		Shear Due due to one axle at support									157.4		157.4			
		Shear Due due to two axles at support									160.2		160.2			
		Shear due to one axle at av = d			V <sub>LLav = d</sub>		(kN/m)		-		145		145			
		Shear due to two axle at av = d			V <sub>LLav = d</sub>		(kN/m)		-		147		147			
		Adequacy Factor							-		202%		202%			
		=>Loading Capacity (Shear) (av = d)							-		40t		-			
		Shear due to one axle at av = 2d			V <sub>av = 2d</sub>		(kN/m)		-		132		132			
		Shear due to two axles av = 2d			V <sub>av = 2d</sub>		(kN/m)		-		134		134			
		Adequacy Factor									223%		223%			
		=>Loading Capacity (Shear)(av = 2d)							-		40t		-			
		Table 5.3.1 of BD21		<b>Single Wheel Load</b>					Moment		Shear		Adequacy			
						Check		Check		for 40t						
Assessment Loading				(Tonne)		7.5		40.0		40.0						
Nominal Single Wheel Load				(kN)		43		86		86						
Wheel Contact Area				(m)		0.198		0.280		0.280						
Minimum Distance Possible from edge of slab to centre line of first wheel				on left side		(m)		0.58		0.58		0.58				
				on right side		(m)		10.96		10.96		10.96				
Dispersion for Wheel Load				beff		0.67		0.75		0.75						
w = P/b <sub>eff</sub> <sup>2</sup> assuming load dispersed long. & transversely				kN/m <sup>2</sup>		95.0		151.1		151.1						
				Yfl		1.50		1.50		1.50						
				Yf3		1.0		1.0		1.0						
Moment Due Single Wheel Load				M <sub>LL</sub>		(kNm)		78.5		-		138.2				
Adequacy Factor								134%		-		76%				
=>Loading Capacity (Moment)								7.5t		-		-				
Refer page 4 of Grillage O/p																
				Shear Due Single Wheel Load			V <sub>LL</sub>		(kN)		-		153.1		153.1	
				Shear due to 40t av = d			V <sub>LLav = d</sub>		(kN)		-		140.3		140.3	
				Adequacy Factor									212%		212%	
				=>Loading Capacity (Shear) (av = d)									40t		-	
				Shear due to 40t av = 2d			V <sub>av = 2d</sub>		(kN)		-		127.5		127.5	
				Adequacy Factor									236%		236%	
				=>Loading Capacity (Shear)(av = 2d)									40t		-	
				Grillage Required			Y/N		Y							
				As Adequacy factor is only 73% for 40 tonnes loading, a grillage analysis was carried out.												
				<b>Grillage Analysis Output due to HA loading &amp; Single Axle load</b>												
							Moment (kNm/m)									
				Applied 40 t (factored for ULS)			56.8									
				'LL Capacity of the section			105.4									
				Live Load Capacity Factor, C			1.46									
				Hence, Live Load Capacity			40t									
		Adequacy Factor for 40t:			185%											

ATKINS		Project					NRA Eirspan Task Order 213		Job ref 3044																																																																																																																																																																																				
Ref		Part of Structure MO-N58-001.00		Assessment using BD21/01 RC Slabs				Calc sheet no. rev 8 0																																																																																																																																																																																					
		Drawing Ref MO-N58-001.00		Calc By CP		Date 13-Feb-12	Check by PG	Date 14-Feb-12																																																																																																																																																																																					
Table 5.3.1 of BD21		<div>Calculations</div> <div><div><div>HB Load</div><div></div></div><table><thead><tr><th></th><th></th><th></th><th>Moment</th><th>Shear</th></tr></thead><tbody><tr><td>Assessment Loading</td><td></td><td>HB</td><td>30.0</td><td>45.0</td></tr><tr><td>Nominal Single Axle Load</td><td></td><td>(kN)</td><td>300</td><td>450</td></tr><tr><td>Wheel Contact Area</td><td></td><td>(m)</td><td>0.261</td><td>0.320</td></tr><tr><td rowspan="2">Minimum Distance Possible from edge of slab to centre line of first wheel</td><td>on left side</td><td>(m)</td><td>0.58</td><td>0.58</td></tr><tr><td>on right side</td><td>(m)</td><td>10.96</td><td>10.96</td></tr><tr><td>Dispersion for HB Axle</td><td></td><td>beff</td><td>0.74</td><td>0.79</td></tr><tr><td>=&gt; Load for HB axle</td><td></td><td>kN</td><td>75.0</td><td>112.5</td></tr><tr><td></td><td></td><td>kN/m</td><td>101.9</td><td>141.6</td></tr><tr><td></td><td>Yf1</td><td></td><td>1.50</td><td rowspan="7">Moment Factor as per Influence Line ↓ 0.5 0.4 0.0 0.0</td></tr><tr><td></td><td>Yf3</td><td></td><td>1.0</td></tr><tr><td>Moment Capacity Check</td><td></td><td></td><td></td></tr><tr><td>Position of first axle from left support centre line</td><td>x1</td><td></td><td>1.07</td></tr><tr><td>Hence, distance of other axle from left support</td><td>x2</td><td></td><td>2.9</td></tr><tr><td></td><td>x3</td><td></td><td>0.0</td></tr><tr><td></td><td>x4</td><td></td><td>0.0</td></tr><tr><td>Moment Due to HB Load</td><td>M<sub>LL</sub></td><td>(kNm)</td><td>83</td><td></td></tr><tr><td>Adequacy Factor</td><td></td><td></td><td>127%</td><td></td></tr><tr><td>=&gt;Loading Capacity (Moment)</td><td></td><td></td><td>30HB</td><td></td></tr><tr><td colspan="3">Shear Capacity Check</td><td>for shear at d</td><td>for shear at 2d</td><td>Shear Factor at d</td><td>Shear Factor at 2d</td></tr><tr><td>Position of first axle from left support centre line</td><td>x1</td><td></td><td>0.41</td><td>0.68</td><td>0.89</td><td>0.8</td></tr><tr><td>Hence, distance of other axle from left support</td><td>x2</td><td></td><td>2.2</td><td>2.5</td><td>0.07</td><td>0.1</td></tr><tr><td></td><td>x3</td><td></td><td>0.000</td><td>0.0</td><td>0.00</td><td>0.0</td></tr><tr><td>Shear Due HB Loading</td><td>x4</td><td></td><td>0.000</td><td>0.0</td><td>0.00</td><td>0.0</td></tr><tr><td>Shear at av = d</td><td>V<sub>LLav = d</sub></td><td>(kN/m)</td><td>123</td><td></td><td></td><td></td></tr><tr><td>Adequacy Factor</td><td></td><td></td><td>243%</td><td></td><td></td><td></td></tr><tr><td>=&gt;Loading Capacity (Shear) (av = d)</td><td></td><td></td><td>45HB</td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>Shear at av = 2d</td><td>V<sub>av = 2d</sub></td><td>(kN/m)</td><td>123</td><td></td><td></td><td></td></tr><tr><td>Adequacy Factor</td><td></td><td></td><td>245%</td><td></td><td></td><td></td></tr><tr><td>=&gt;Loading Capacity (Shear)(av = 2d)</td><td></td><td></td><td>45HB</td><td></td><td></td><td></td></tr></tbody></table></div> <div><div>Output</div><div><div>HB Load</div><div>Moment Capacity 30HB</div><div>Shear Capacity 45HB</div><div>Bond Capacity &lt;30HB</div></div></div> <tr><td colspan="2">Ref Page 14&amp;15</td><td colspan="7"><div>Check Bond Stress</div><div>Moment Capacity for non composite section = &lt;30HB Assuming no contribution from Concrete</div><div>Adequacy Factor for 45HB -14%</div></td></tr>										Moment	Shear	Assessment Loading		HB	30.0	45.0	Nominal Single Axle Load		(kN)	300	450	Wheel Contact Area		(m)	0.261	0.320	Minimum Distance Possible from edge of slab to centre line of first wheel	on left side	(m)	0.58	0.58	on right side	(m)	10.96	10.96	Dispersion for HB Axle		beff	0.74	0.79	=> Load for HB axle		kN	75.0	112.5			kN/m	101.9	141.6		Yf1		1.50	Moment Factor as per Influence Line ↓ 0.5 0.4 0.0 0.0		Yf3		1.0	Moment Capacity Check				Position of first axle from left support centre line	x1		1.07	Hence, distance of other axle from left support	x2		2.9		x3		0.0		x4		0.0	Moment Due to HB Load	M <sub>LL</sub>	(kNm)	83		Adequacy Factor			127%		=>Loading Capacity (Moment)			30HB		Shear Capacity Check			for shear at d	for shear at 2d	Shear Factor at d	Shear Factor at 2d	Position of first axle from left support centre line	x1		0.41	0.68	0.89	0.8	Hence, distance of other axle from left support	x2		2.2	2.5	0.07	0.1		x3		0.000	0.0	0.00	0.0	Shear Due HB Loading	x4		0.000	0.0	0.00	0.0	Shear at av = d	V <sub>LLav = d</sub>	(kN/m)	123				Adequacy Factor			243%				=>Loading Capacity (Shear) (av = d)			45HB											Shear at av = 2d	V <sub>av = 2d</sub>	(kN/m)	123				Adequacy Factor			245%				=>Loading Capacity (Shear)(av = 2d)			45HB				Ref Page 14&15		<div>Check Bond Stress</div> <div>Moment Capacity for non composite section = &lt;30HB Assuming no contribution from Concrete</div> <div>Adequacy Factor for 45HB -14%</div>						
			Moment	Shear																																																																																																																																																																																									
Assessment Loading		HB	30.0	45.0																																																																																																																																																																																									
Nominal Single Axle Load		(kN)	300	450																																																																																																																																																																																									
Wheel Contact Area		(m)	0.261	0.320																																																																																																																																																																																									
Minimum Distance Possible from edge of slab to centre line of first wheel	on left side	(m)	0.58	0.58																																																																																																																																																																																									
	on right side	(m)	10.96	10.96																																																																																																																																																																																									
Dispersion for HB Axle		beff	0.74	0.79																																																																																																																																																																																									
=> Load for HB axle		kN	75.0	112.5																																																																																																																																																																																									
		kN/m	101.9	141.6																																																																																																																																																																																									
	Yf1		1.50	Moment Factor as per Influence Line ↓ 0.5 0.4 0.0 0.0																																																																																																																																																																																									
	Yf3		1.0																																																																																																																																																																																										
Moment Capacity Check																																																																																																																																																																																													
Position of first axle from left support centre line	x1		1.07																																																																																																																																																																																										
Hence, distance of other axle from left support	x2		2.9																																																																																																																																																																																										
	x3		0.0																																																																																																																																																																																										
	x4		0.0																																																																																																																																																																																										
Moment Due to HB Load	M <sub>LL</sub>	(kNm)	83																																																																																																																																																																																										
Adequacy Factor			127%																																																																																																																																																																																										
=>Loading Capacity (Moment)			30HB																																																																																																																																																																																										
Shear Capacity Check			for shear at d	for shear at 2d	Shear Factor at d	Shear Factor at 2d																																																																																																																																																																																							
Position of first axle from left support centre line	x1		0.41	0.68	0.89	0.8																																																																																																																																																																																							
Hence, distance of other axle from left support	x2		2.2	2.5	0.07	0.1																																																																																																																																																																																							
	x3		0.000	0.0	0.00	0.0																																																																																																																																																																																							
Shear Due HB Loading	x4		0.000	0.0	0.00	0.0																																																																																																																																																																																							
Shear at av = d	V <sub>LLav = d</sub>	(kN/m)	123																																																																																																																																																																																										
Adequacy Factor			243%																																																																																																																																																																																										
=>Loading Capacity (Shear) (av = d)			45HB																																																																																																																																																																																										
Shear at av = 2d	V <sub>av = 2d</sub>	(kN/m)	123																																																																																																																																																																																										
Adequacy Factor			245%																																																																																																																																																																																										
=>Loading Capacity (Shear)(av = 2d)			45HB																																																																																																																																																																																										
Ref Page 14&15		<div>Check Bond Stress</div> <div>Moment Capacity for non composite section = &lt;30HB Assuming no contribution from Concrete</div> <div>Adequacy Factor for 45HB -14%</div>																																																																																																																																																																																											

ATKINS	Project				NRA Eirspan Task Order 213				Job ref																																																																														
	Part of Structure				Section Properties				3044																																																																														
	MO-N58-001.00								Calc sheet no. rev																																																																														
Drawing Ref				Calc By		Date		Check by		Date																																																																													
MO-N58-001.00				CP		13-02-12		PG		13-02-12																																																																													
Ref	Calculations								Output																																																																														
	<u>Section Properties</u>																																																																																						
	<u>Composite Section Properties</u>																																																																																						
																																																																																							
	Idealised Section Short Term																																																																																						
	f <sub>cu</sub> = 26.8307																																																																																						
	E <sub>c</sub> = (20 + 0.27f <sub>cu</sub> ) = 27																																																																																						
	E <sub>s</sub> = 205 m = E <sub>s</sub> / E <sub>c</sub> = 7.52																																																																																						
<table><tr><th>Sr No.</th><th>b</th><th>h</th><th>No.</th><th>E<sub>s</sub>/E<sub>c</sub></th><th>Area b x h</th><th>CG y-y (y)</th><th>A<sub>y</sub></th><th>A<sub>y</sub><sup>2</sup></th><th>I<sub>self</sub></th><th></th></tr><tr><td>1</td><td>600</td><td>340</td><td>1</td><td>1.00</td><td>204000</td><td>170</td><td>34680000</td><td>5.896E+09</td><td>1.965E+09</td><td>Concrete</td></tr><tr><td>2</td><td>50</td><td>30</td><td>1</td><td>7.52</td><td>11286.8</td><td>105</td><td>1185110.3</td><td>124436578</td><td>112500</td><td>Steel</td></tr><tr><td>3</td><td>85</td><td>10</td><td>1</td><td>7.52</td><td>6395.83</td><td>85</td><td>543645.82</td><td>46209895</td><td>7083.3333</td><td>Steel</td></tr><tr><td>4</td><td>125</td><td>10</td><td>1</td><td>7.52</td><td>9405.64</td><td>75</td><td>705422.78</td><td>52906708</td><td>10416.667</td><td>Steel</td></tr><tr><td></td><td></td><td></td><td></td><td></td><td>Σ A</td><td>Σ y</td><td>Σ A<sub>y</sub></td><td>Σ A<sub>y</sub><sup>2</sup></td><td>Σ I<sub>self</sub></td><td></td></tr><tr><td>Sum</td><td></td><td></td><td></td><td></td><td>231088</td><td>435</td><td>37114179</td><td>6.119E+09</td><td>1.965E+09</td><td></td></tr></table>											Sr No.	b	h	No.	E <sub>s</sub> /E <sub>c</sub>	Area b x h	CG y-y (y)	A <sub>y</sub>	A <sub>y</sub> <sup>2</sup>	I <sub>self</sub>		1	600	340	1	1.00	204000	170	34680000	5.896E+09	1.965E+09	Concrete	2	50	30	1	7.52	11286.8	105	1185110.3	124436578	112500	Steel	3	85	10	1	7.52	6395.83	85	543645.82	46209895	7083.3333	Steel	4	125	10	1	7.52	9405.64	75	705422.78	52906708	10416.667	Steel						Σ A	Σ y	Σ A <sub>y</sub>	Σ A <sub>y</sub> <sup>2</sup>	Σ I <sub>self</sub>		Sum					231088	435	37114179	6.119E+09	1.965E+09	
Sr No.	b	h	No.	E <sub>s</sub> /E <sub>c</sub>	Area b x h	CG y-y (y)	A <sub>y</sub>	A <sub>y</sub> <sup>2</sup>	I <sub>self</sub>																																																																														
1	600	340	1	1.00	204000	170	34680000	5.896E+09	1.965E+09	Concrete																																																																													
2	50	30	1	7.52	11286.8	105	1185110.3	124436578	112500	Steel																																																																													
3	85	10	1	7.52	6395.83	85	543645.82	46209895	7083.3333	Steel																																																																													
4	125	10	1	7.52	9405.64	75	705422.78	52906708	10416.667	Steel																																																																													
					Σ A	Σ y	Σ A <sub>y</sub>	Σ A <sub>y</sub> <sup>2</sup>	Σ I <sub>self</sub>																																																																														
Sum					231088	435	37114179	6.119E+09	1.965E+09																																																																														
<div>Top Flange</div> <div>Web</div> <div>Bot Flange</div>																																																																																							
<div>Y<sub>CG</sub> = Σ A<sub>y</sub> / Σ A for bottom = 37114178.9 / 231088.235 = 160.61 mm</div> <div>I<sub>CG</sub> = I<sub>yy</sub> - ( Σ A x y<sub>CG</sub><sup>2</sup> )</div> <div>I<sub>yy</sub> = ( Σ I<sub>self</sub> + Σ A<sub>y</sub><sup>2</sup> )</div> <div>I<sub>CG</sub> = ( Σ I<sub>self</sub> + Σ A<sub>y</sub><sup>2</sup> ) - ( Σ A x y<sub>CG</sub><sup>2</sup> )</div> <div>= ( 2E+09 + 6.1E+09 ) - ( 231088 ) x ( 160.606<sup>2</sup> )</div> <div>= 2.124E+09 mm4</div> <div>Idealised Section Long Term</div> <div>E<sub>s</sub> = 205 m = E<sub>s</sub> / E<sub>c</sub> = 15.05</div>																																																																																							
<table><tr><th>Sr No.</th><th>b</th><th>h</th><th>No.</th><th>E<sub>s</sub>/E<sub>c</sub></th><th>Area b x h</th><th>CG y-y (y)</th><th>A<sub>y</sub></th><th>A<sub>y</sub><sup>2</sup></th><th>I<sub>self</sub></th><th></th></tr><tr><td>1</td><td>600</td><td>340</td><td>1</td><td>1.00</td><td>204000</td><td>170</td><td>34680000</td><td>5.896E+09</td><td>1.965E+09</td><td>Concrete</td></tr><tr><td>2</td><td>50</td><td>30</td><td>1</td><td>15.05</td><td>22573.5</td><td>105</td><td>2370220.5</td><td>248873156</td><td>112500</td><td>Steel</td></tr><tr><td>3</td><td>85</td><td>10</td><td>1</td><td>15.05</td><td>12791.7</td><td>85</td><td>1087291.6</td><td>92419790</td><td>7083.3333</td><td>Steel</td></tr><tr><td>4</td><td>125</td><td>10</td><td>1</td><td>15.05</td><td>18811.3</td><td>75</td><td>1410845.6</td><td>105813417</td><td>10416.667</td><td>Steel</td></tr><tr><td></td><td></td><td></td><td></td><td></td><td>Σ A</td><td>Σ y</td><td>Σ A<sub>y</sub></td><td>Σ A<sub>y</sub><sup>2</sup></td><td>Σ I<sub>self</sub></td><td></td></tr><tr><td>Sum</td><td></td><td></td><td></td><td></td><td>258176</td><td>435</td><td>39548358</td><td>6.343E+09</td><td>1.965E+09</td><td></td></tr></table>											Sr No.	b	h	No.	E <sub>s</sub> /E <sub>c</sub>	Area b x h	CG y-y (y)	A <sub>y</sub>	A <sub>y</sub> <sup>2</sup>	I <sub>self</sub>		1	600	340	1	1.00	204000	170	34680000	5.896E+09	1.965E+09	Concrete	2	50	30	1	15.05	22573.5	105	2370220.5	248873156	112500	Steel	3	85	10	1	15.05	12791.7	85	1087291.6	92419790	7083.3333	Steel	4	125	10	1	15.05	18811.3	75	1410845.6	105813417	10416.667	Steel						Σ A	Σ y	Σ A <sub>y</sub>	Σ A <sub>y</sub> <sup>2</sup>	Σ I <sub>self</sub>		Sum					258176	435	39548358	6.343E+09	1.965E+09	
Sr No.	b	h	No.	E <sub>s</sub> /E <sub>c</sub>	Area b x h	CG y-y (y)	A <sub>y</sub>	A <sub>y</sub> <sup>2</sup>	I <sub>self</sub>																																																																														
1	600	340	1	1.00	204000	170	34680000	5.896E+09	1.965E+09	Concrete																																																																													
2	50	30	1	15.05	22573.5	105	2370220.5	248873156	112500	Steel																																																																													
3	85	10	1	15.05	12791.7	85	1087291.6	92419790	7083.3333	Steel																																																																													
4	125	10	1	15.05	18811.3	75	1410845.6	105813417	10416.667	Steel																																																																													
					Σ A	Σ y	Σ A <sub>y</sub>	Σ A <sub>y</sub> <sup>2</sup>	Σ I <sub>self</sub>																																																																														
Sum					258176	435	39548358	6.343E+09	1.965E+09																																																																														
<div>Top Flange</div> <div>Web</div> <div>Bot Flange</div>																																																																																							
<div>Y<sub>CG</sub> = Σ A<sub>y</sub> / Σ A for bottom = 39548357.7 / 258176.469 = 153.18 mm</div> <div>I<sub>CG</sub> = I<sub>yy</sub> - ( Σ A x y<sub>CG</sub><sup>2</sup> )</div> <div>I<sub>yy</sub> = ( Σ I<sub>self</sub> + Σ A<sub>y</sub><sup>2</sup> )</div> <div>I<sub>CG</sub> = ( Σ I<sub>self</sub> + Σ A<sub>y</sub><sup>2</sup> ) - ( Σ A x y<sub>CG</sub><sup>2</sup> )</div> <div>= ( 2E+09 + 6.3E+09 ) - ( 258176 ) x ( 153.183<sup>2</sup> )</div> <div>= 2.25E+09 mm4</div>																																																																																							



Ref

Calculations

Ouput

## Check bond stress of section

Dimensions in mm

Allowable $f_{cu}$ =	26.83074
$\gamma_{mc}$ =	1.05
Allowable $f_{st}$ =	230
$\gamma_{ms}$ =	1.05
$\gamma_{f3}$ =	1.1
Bottom Cover=	70

b=	600
$d_c$ =	340
$d_s$ =	50
$A_{st}$ =	1500
$t_{ft}$ =	30
$t_{fb}$ =	10
$A_{sb}$ =	1250
$t_w$ =	85

### Short Term Ec (BD 44/95 cl. 4.3.2.1)

$$E_c = (20 + 0.27f_{cu}) = 27$$


$$E_s = 205 \quad m = E_s / E_c = 7.52$$

### Long Term Ec (BD 44/95 cl. 4.3.2.1)

$$\text{Twice Short Term } m = 15.05$$

$$\text{Allowable Conc stress} = 0.75f_{cu} / \gamma_{mc} \gamma_{f3} = 17.423$$

$$\text{Allowable steel stress} = f_{st} / \gamma_{ms} \gamma_{f3} = 199.134$$



### Uncracked Section for Grillage Analysis

#### Short Term Long Term Ec

$$m = 7.52 \quad 15.05$$

$$x = 187.60 \quad 201.51 \quad \text{mm}$$

$$\text{Area of section (concrete units)} = 231088.23 \quad 258176.47 \quad \text{mm}^2$$

$$\text{Area of section (steel units)} = 30711.40 \quad 17155.70 \quad \text{mm}^2$$

$$I_{NA} \text{ (concrete units)} = 2.12\text{E}+09 \quad 2.25\text{E}+09 \quad \text{mm}^4$$

$$I_{NA} \text{ (steel units)} = 3.34\text{E}+08 \quad 1.95\text{E}+08 \quad \text{mm}^4$$

### Cracked Section

#### Short Term Long Term Ec

$$m = 7.52 \quad 15.05$$

$$x = 157.33 \quad 168.64 \quad \text{mm}$$

$$\text{Area of concrete in compression} = 94399.88 \quad 101183.60 \quad \text{mm}^2$$

$$\text{Centroid of conc. in comp. (from NA)} = 78.67 \quad 84.32 \quad \text{mm}$$

$$I_{NA} \text{ (cracked section)} = 8.69\text{E}+08 \quad 1.23\text{E}+09 \quad \text{mm}^4$$

$$A * y / I_{NA} = 0.00855 \quad 0.00692 \quad /\text{mm}$$

BD61/10 Cl 8.5.1: "The bond may be assumed to be developed uniformly only over both sides of the web and the upper surface of the top and bottom flanges of the steel beam where there is complete encasement and over both sides of the web and the upper surface of the top flange of the steel beam where the beam soffit is exposed."

Hence, as cover to soffit of bottom flange is 70mm,  $L_s = 110 \quad \text{mm}$

Ref

Calculations

Ouput

## Check for Max Shear (at support) 40t

Serviceability Loads (F)

Shear at support	kN
Dead Load	14.50
Live Load	48.91

$$l \text{ Shear Force} = Fy/I_{NA} \quad \text{Live Load} \quad 418.09 \quad \text{Dead Load} \quad 100.24 \quad \text{N/mm}$$

$$\text{Bond stress} = 3.801 \quad 0.911 \quad \text{N/mm}^2$$


$$\text{Total bond stress} = 4.712 \quad \text{N/mm}^2$$

$$\text{Allowable bond stress at SLS} = 0.700 \quad \text{N/mm}^2$$

**Result:** Section is unsuitable for composite action (see BD 61/10 Clause 8.5.1)

## Check capacity of section unsuitable for composite action

Find distance x such that bond stress due to combined Dead Load and Live Load = 0.7N/mm<sup>2</sup>



**Legend:**

bond stress < 0.7N/mm<sup>2</sup>  
suitable for composite action

bond stress > 0.7N/mm<sup>2</sup>  
unsuitable for composite action

Vary x until bond stress = allowable bond stress

Try x = **1.76** m (Max x = L/2 = 1.805 m)

Okay Hint: Use Goalseek

Serviceability Loads (F)

Shear at location x	kN
Dead Load	<b>0.33</b>
Live Load	<b>8.74</b>

$$\text{Long'l Shear Force} = Fy/I_{NA} \quad \text{Live Load} \quad 74.69 \quad \text{Dead Load} \quad 2.31 \quad \text{N/mm}$$

$$\text{Bond stress using} = 0.679 \quad 0.021 \quad \text{N/mm}^2$$

$$\text{Total bond stress} = \mathbf{0.700} \quad \text{N/mm}^2$$

$$\text{Allowable bond stress at SLS} = \mathbf{0.700} \quad \text{N/mm}^2$$

**Result:** Bond stress okay

## Check corresponding moment capacity at x

Factor K for 40 tonne loading 0.79

Moment Capacity of steel section 1.97 kNm

Moment Capacity of composite section 90.61 kNm

ULS Moment at x	kNm
Dead Load	16.51
Available capacity for live load	-14.55
Live Load	66.18

Factor C for Moment -0.17


Loading Capacity Moment **<3t**

Adequacy Factor -0.22

as per Figure 5.6


**(HA + KEL Eqv.)**  
**Moment Capacity**  
**<3t**

## Dead Load



q	8.03	kN/m	unfactored
L	3.61	m	
x	<b>1.76</b>	m	

RA=RB =	14.50 kN
Vx	0.33 kN
Vmax	14.50 kN
Mx	13.08 kNm
Mmax	13.08 kNm




Ref

Calculations


Ouput

## HA UDL Live Load




q	18.46	kN/section
L	3.61	m
x	1.76	m

$R_A = R_B = 33.33 \text{ kN}$   
 $V_x = 0.77 \text{ kN}$   
 $V_{\max} = 33.33 \text{ kN}$   
 $M_x = 30.06 \text{ kNm}$   
 $M_{\max} = 30.08 \text{ kNm}$




## HA KEL Live Load



P	15.58	kN
L	3.61	m
a	1.76	
b	1.85	
x	1.76	m

$R_A = 7.97 \text{ kN}$   
 $R_B = 7.61 \text{ kN}$   
 $V_x = 7.97 \text{ kN}$   
 $V_{\max} = 15.58 \text{ kN}$   
 $M_x = 14.06 \text{ kNm}$   
 $M_{\max} = 14.06 \text{ kNm}$  (P at support)  
 $M_{\max} \text{ P at centre} = 14.06 \text{ kNm}$



## Combined Continuos + Point Load

per m width  
 Combined Moment  $M_x = 44.12 \text{ kNm}$   
 Combined Shear  $V_x = 8.74 \text{ kN}$

ULS ( $\gamma_f = 1.5$ )  
 66.18  
 13.11

Max M = 44.14 kNm  
 Max V = 48.91 kN

ULS ( $\gamma_f = 1.5$ )  
 66.21 kNm  
 73.36 kN



Ref

Calculations

Oupput

## Check for Max Shear (at support) 30HB

### Serviceability Loads (F)

Shear at support	kN
Dead Load	14.50
Live Load	54.49

**Note: If bottom flange is exposed use  $L_{S1}$  otherwise use  $L_{S2}$**

	Live Load	Dead Load	
Longt'l Shear Force = $F_{Ay}/I_{NA}$	465.79	100.24	N/mm
Bond stress=	4.234	0.911	N/mm <sup>2</sup>
Total bond stress=	5.146		N/mm <sup>2</sup>
Allowable bond stress at SLS =	0.700		N/mm <sup>2</sup>

**Result:** Bond Stress (5.15) greater or equal than Permissible Bond Stress (0.7) hence section is unsuitable for composite action (see BD 61/10 Clause 8.5.1)

## Check section at x 30HB

Vary x until bond stress = allowable bond stress

**Loading** Try x = **1.57** m Load **30** HB  
reduce x Hint: Use Goalseek


### Serviceability Loads (F)

Shear at location x	kN
Dead Load	1.92
Live Load	7.45

	Live Load	Dead Load	
Longt'l Shear Force = $F_{Ay}/I_{NA}$	64	13.28	N/mm
Bond stress=	0.579	0.121	N/mm <sup>2</sup>
Total bond stress=	0.700		N/mm <sup>2</sup>
Allowable bond stress at SLS =	0.7	0.700	N/mm <sup>2</sup>

**Result:** Bond Stress (0.7) greater or equal than Permissible Bond Stress (0.7) hence section is unsuitable for composite action (see BD 61/10 Clause 8.5.1)

## Live Load at x



beff = 0.74 m

q	101.90	kN/section
a	1.20	m
b	0.74	m
c	1.68	m
L	3.61	m
x	1.57	m

RA	42.47	kN
RB	32.53	kN
Vx	4.97	kN
Vmax	42.47	kN
Mx	59.60	kNm
Mmax	59.72	kNm

ULS	7.45	kN
	63.70	kN
	89.40	kNm
	89.58	kNm

## Dead Load at x

q	8.03	kN/m	unfactored
L	3.61	m	
x	1.57	m	

RA=RB =	14.50	kN
Vx	1.92	kN
Vmax	14.50	kN
Mx	12.85	kNm
Mmax	13.08	kNm

ULS Moment at x	kNm
Dead Load	14.78
Available capacity for live load	-12.81
30HB Live Load	89.58

Adequacy  
-0.14 Fail

**Moment Capacity  
<30HB**

## Job Name :Eirspan TO213

Structure Type = Grillage  
No of joints = 60  
No of members = 103

## Analysis Settings

Analysis method = Linear Elastic

## Material Types

Data last edited at 15:38 on 9/5/12

Units : E(kN/mm<sup>2</sup>) G(kN/mm<sup>2</sup>) CTE(/deg C) Density(kN/m<sup>3</sup>)

Type no	E CTE	G Density	Name
1	31.0 1.2e-5	11.6 24.0	Concrete

## Supports

Data last edited at 15:45 on 9/5/12

Joint No	DZ (kN/m)	RX (kN.m/deg)	RY (kN.m/deg)
1	Rigid	Rigid	Free
6	Rigid	Rigid	Free
7	Rigid	Rigid	Free
12	Rigid	Rigid	Free
13	Rigid	Rigid	Free
18	Rigid	Rigid	Free
19	Rigid	Rigid	Free
24	Rigid	Rigid	Free
25	Rigid	Rigid	Free
30	Rigid	Rigid	Free
31	Rigid	Rigid	Free
36	Rigid	Rigid	Free
37	Rigid	Rigid	Free
42	Rigid	Rigid	Free
43	Rigid	Rigid	Free
48	Rigid	Rigid	Free
49	Rigid	Rigid	Free
54	Rigid	Rigid	Free
55	Rigid	Rigid	Free
60	Rigid	Rigid	Free
61	Rigid	Rigid	Free
66	Rigid	Rigid	Free
67	Rigid	Rigid	Free
72	Rigid	Rigid	Free

## Sections

Data last edited at 15:43 on 9/5/12

### **Section 1 : 1000mm slab : Rectangle**

	Dy = 1000.0 mm	Dz = 340.0 mm
	Tz = 0.0 mm	Ty = 0.0 mm
	Cy = n/a	Cz = 0.0 mm
Ax = 3400.00 cm <sup>2</sup>	Ay = n/a	Az = 2833.33 cm <sup>2</sup>
Ix = 1029815.29 cm <sup>4</sup>	Iy = 327533.33 cm <sup>4</sup>	Iz = n/a

## Section 2 : Support : Rectangle

	Dy = 640.0 mm	Dz = 340.0 mm
	Tz = 0.0 mm	Ty = 0.0 mm
	Cy = n/a	Cz = 0.0 mm
Ax = 2176.00 cm <sup>2</sup>	Ay = n/a	Az = 1813.33 cm <sup>2</sup>
Ix = 559717.50 cm <sup>4</sup>	Iy = 209621.33 cm <sup>4</sup>	Iz = n/a

### Loadcase titles

Data last edited at 10:32 on 10/5/12

Loadcase No	Reference	Title
1	B1	HL:ALP: My at End2 : Member 69: LV 40t

### CURRENT : Minimum Member end forces

Loadcases : B1

Analysed at 10:32 hrs on 10/5/12

Member	Joint	Torque (kN.m)	Bending Moment (kN.m)	Shear Force (kN)
38	61	<b>-5.361 B1</b>	-2.092h	80.654
126	66	5.946	<b>-2.312 B1</b>	-93.367
126	66	5.946	-2.312h	<b>-93.367 B1</b>

### CURRENT : Maximum Member end forces

Loadcases : B1

Analysed at 10:32 hrs on 10/5/12



Member	Joint	Torque (kN.m)	Bending Moment (kN.m)	Shear Force (kN)
126	66	<b>5.946 B1</b>	-2.312h	-93.367
69	64	-1.644	<b>95.101 B1</b>	20.637
38	61	-5.361	-2.092h	<b>80.654 B1</b>

10:34 : 10/5/12

V:\3044 Eirspan Task Order 213\30 Documents\32 Reports\321 Working Assessment Reports\69. MO-N58-001.00\MO-N58-001.00 Grillage.X00

## SCALES

Structure 1:74



Structure Set : ALL


10:34 : 10/5/12

V:\3044 Eirspan Task Order 213\30 Documents\32 Reports\321 Working Assessment Reports\69. MO-N58-001.00\MO-N58-001.00 Grillage.X00

## SCALES

Structure 1:74

Moments 1 mm = 1.500 kN.m



Results : Moment My  
Structure Set : ALL  
Loadcases : B1

# **Appendix E**

## **Sub-Standard Structure Summary**

## APPENDIX E: SUB-STANDARD STRUCTURE SUMMARY

Structure Name: **Strade River Bridge**

Structure Ref. No.: **MO-N58-001.00**

Assessment/Stage Review	Stage 1 Assessment	Stage 2 Assessment		
Date:	21/05/2012			
Report Reference:	DG-TO213-69			
Assessed Capacity:	Span 1: Bending 18t, Shear 40t, Bond <3t Span 2: Bending 40t, Shear 40t, Bond <3t			
Sub-Standard Status:	Provisionally Sub-Standard			
Interim Measures Date:	21/05/2012			
Feasibility Assessment				
Is the Structure an Immediate Structure or a Low Risk	Low Risk			
Provisionally Sub-Standard Structure?	Provisionally Sub-Standard			
Is the Structure Monitoring appropriate?	Monitoring of the substructure is not appropriate.			
Interim Measures Date:	21/05/2012			
Proposal:	Stage 2 Assessment of the structure and subsequent strengthening of the structure, if required.			
Recommendation:				
Interim Measures Date:				
Approval:				
Approval/Rejection:				
Actions Implementation Date :				
Details/Ref :				
Provisional finish date for monitoring :				
Removal Date :				
<b>Additional Notes</b>				

# **Appendix F**

## **Interim Measures Feasibility Assessment**

## APPENDIX F: INTERIM MEASURES FEASIBILITY ASSESSMENT FOR BRIDGES

### 1. GENERAL DETAILS

1.1 Structure name and assessment reference:

Structure Ref No: MO-N58-001.00

1.2 Location, route and county/area:

Strade River Bridge, N58, County Mayo

Latitude Y: 297482.729

Longitude X: 125785.401

1.3 Assessing Organisation:

ATKINS

Assessed by: CM

Checked by: PG

Assessment date: 21/05/2012

1.4 Structure type, form, span, skew:

Two Span Filler Beam Deck Structure, Skew Spans 3.81m & 3.79, Skew 28°.

1.5 Obstacle crossed and facility carried:

Carries the N58 National Secondary Route across the Strade River.

1.6 Estimated cost of permanent strengthening/replacement works:

Not applicable.

### 2. ASSESSMENT PROGRESS

2.1 Level of assessment reached:

Stage 1 Assessment

2.2 Assessed capacity:

Span 1: 18 t (Bending), 40t (Shear) & <3t (Bond)

Span 2: 40 t (Bending), 40t (Shear) & <3t (Bond)

2.3 Date of assessment:

21/05/2012

2.4 Assessment Report reference:

3044/30/32/DG-TO-213-69

2.5 Provisionally Sub-standard or Sub-standard?

Provisionally Sub-standard

2.6 Description of anticipated mode of failure, including its progressions from local overstress to global collapse mechanism.

Failure mode of the RC slab structure is likely to be due to bond stress between the steel components and the concrete.

2.7 Description of distress (if present):

No structural defects present.

### 3. CONSIDERATION OF RISK POSED BY STRUCTURE IN CURRENT STATE

#### 3.1 Discussion

The Stage 1 Assessment indicated that both spans of the structure had a capacity of 7.5 tonnes assessment loading for bending, 40 tonnes for shear and less than 3 tonnes for bond. As the adequacy of the structures in bending for 40t live loading was 60% for span 1 and 73% for span 2 using the strip method, a grillage analysis was carried out, which increased the load capacity of the structures in bending to 18 tonnes assessment loading for Span 1 and to 40 tonnes for Span 2. The Stage 1 Assessment also indicated that the structure failed for 30 Units of HB loading in bond.

The structure was noted to be in good condition and not showing any signs of structural defects. The main causes of low carrying capacity of the structure were low concrete strength and low area of steel reinforcement components.

It is considered likely that Stage 2 Assessment of the structure would increase the assessment load capacity of the structure, but may not increase it to 40 tonnes assessment loading. Hence, based on the results of Stage 2 Assessment, the structure should be strengthened, if necessary.

#### 3.2 Is the structure an Immediate Risk Structure?

No, the structure is not an immediate risk structure.

#### 3.3 Is the structure a Low Risk Provisionally Sub-standard Structure?

Yes, the structure is a Low Risk Provisionally Sub-standard Structure.

### 4. APPROPRIATENESS OF MONITORING

#### 4.1 Discussion

The structure was not showing any signs of structural defects. Hence, it is considered that the monitoring of the substructure is not appropriate.

#### 4.2 Is the structure monitoring appropriate?

No, the structure is not monitoring appropriate.

### 5. OPTIONS FOR LOAD MITIGATION INTERIM MEASURES

Load mitigation measures are not required at this stage

### 6. OPTIONS FOR MONITORING INTERIM MEASURES

Monitoring interim measures are not required at this stage.

### 7. RECOMMENDED OPTIONS FOR INTERIM MEASURES

#### 7.1 Recommended Load Mitigation Interim Measures:

Load mitigation measures are not required at this stage.

#### 7.2 Recommended Monitoring Interim Measures:

Monitoring interim measures are not required at this stage.


# Appendix B. Results of Additional Literature Search

No additional material found.




# Appendix C. General Arrangement Drawings





PLAN  
Scale at A1 1:75  
Scale at A3 1:150



SECTION A  
Scale at A1 1:25  
Scale at A3 1:50

- GENERAL NOTES
1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE
  2. ONLY WRITTEN DIMENSIONS SHALL BE USED. NO DIMENSIONS SHALL BE SCALED FROM THE DRAWINGS
  3. ALL LEVELS ARE IN METRES AND ARE TO MALIN HEAD DATUM
  4. ALL COORDINATES ARE IN METRES AND ARE TO IRISH TRANSVERSE MERCATOR
  5. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE SPECIFICATION

© ORDNANCE SURVEY IRELAND LICENSE NR. AR 0082524. ORDNANCE SURVEY IRELAND & GOVERNMENT OF IRELAND  
ATKINS WILL NOT TO BE HELD LIABLE FOR THE USE OF THIS DATA ON ANY PROJECT OTHER THAN TO015 - MAYO BRIDGE ASSESSMENTS AND STRENGTHENING 2023



Risk Level	Atkins Base Line - Low Risk
	Atkins Sensitive - Medium Risk
	Atkins Private - High Risk
	Client Critical - Already Marked

Rev	Description	By	Date	Chk'd	Rev'd	Auth
P0	ISSUED FOR REVIEW	SOC	08.24	POS	MG	MJ



Atkins House, 150-155 Ainslie Business Park, Swords, Co. Dublin  
Tel (+353) 01 810 8000  
Fax (+353) 01 810 8001

Unit 2B, 2200 Cork Airport Business Park, Cork  
Tel (+353) 021 429 0300  
Fax (+353) 021 429 0360

1st Floor Technology House Parkmore Technology Park, Galway  
Tel (+353) 091 786 050  
Fax (+353) 091 779 830





TO315 - MAYO BRIDGE ASSESSMENTS AND STRENGTHENING 2023

Purpose		PRELIMINARY ISSUE							
Title		Strade River Bridge MO-N58-001.00 PLAN AND CROSS SECTION							
Original Scale		As Shown		Drawn	Checked	Reviewed	Authorised		
				SOC	POS	MG	MJ		
		Date	30.08.24	Date	30.08.24	Date	30.08.24	Date	30.08.24
Status		Drawing Number						Rev	
S0		0088572-ATK-02-XX-DR-CE-900201						P0	


A1

DO NOT SCALE


File: 0088572-ATK-02-XX-DR-CE-900201 to 0202.dwg  
Date: Oct 22, 2024 - 2:19pm  
Plotted by: SDComor



DEFECT PLAN  
Scale at A1 1:50  
Scale at A3 1:100



EAST ELEVATION  
Scale at A1 1:50  
Scale at A3 1:100



WEST ELEVATION  
Scale at A1 1:50  
Scale at A3 1:100

- GENERAL NOTES
1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE
  2. ONLY WRITTEN DIMENSIONS SHALL BE USED. NO DIMENSIONS SHALL BE SCALED FROM THE DRAWINGS
  3. ALL LEVELS ARE IN METRES AND ARE TO MALIN HEAD DATUM
  4. ALL COORDINATES ARE IN METRES AND ARE TO IRISH TRANSVERSE MERCATOR
  5. DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE SPECIFICATION

Purpose PRELIMINARY ISSUE

Title Strade River Bridge  
MO-N58-001.00  
ELEVATIONS AND DEFECT LAYOUT PLAN

Original Scale	Drawn	Checked	POS	Reviewed	MG	Authorised	MJ
1:50	SOC	POS	POS	MG	MG	MJ	MJ
Date	30.08.24	Date	30.08.24	Date	30.08.24	Date	30.08.24

Status	Drawing Number	Rev
S0	0088572-ATK-02-XX-DR-CE-900202	P0

© ORDNANCE SURVEY IRELAND LICENSE NR. AR 0082524. ORDNANCE SURVEY IRELAND & GOVERNMENT OF IRELAND  
ATKINS WILL NOT TO BE HELD LIABLE FOR THE USE OF THIS DATA ON ANY PROJECT OTHER THAN TO015 - MAYO BRIDGE ASSESSMENTS AND STRENGTHENING 2023

Risk Level	Atkins Base Line - Low Risk
	Atkins Sensitive - Medium Risk
	Atkins Private - High Risk
	Client Critical - Already Marked



Rev	Description	By	Date	Chk'd	Rev'd	Auth
P0	ISSUED FOR REVIEW	SOC	08.24	POS	MG	MJ



Atkins House, 150-155 Ainslie Business Park, Swords, Co. Dublin  
Tel (+353) 01 810 8000 Fax (+353) 01 810 8001  
Unit 2B, 2200 Cork Airport Business Park, Cork  
Tel (+353) 021 429 0300 Fax (+353) 021 429 0360  
1st Floor Technology House Parkmore Technology Park, Galway  
Tel (+353) 091 786 050 Fax (+353) 091 779 830



TO315 - MAYO BRIDGE ASSESSMENTS AND STRENGTHENING 2023

# Appendix D. Structural Condition Drawing

Refer to Appendix C for General Arrangement Drawings with the defect locations sketch included.



# Appendix E. Copy of Materials Testing Report





# Structural Investigation Report

**MO-N58-001.00 - STRUCTURAL INVESTIGATION REPORT**  
**– [REV 1]**

**12<sup>TH</sup> December 2024**

PREPARED FOR



Comhairle Contae Mhaigh Eo  
Mayo County Council





## SITE INVESTIGATION REPORT

### CONTENTS

1.	INTRODUCTION.....	1
2.	GENERAL DESCRIPTION OF STRUCTURE .....	2
3.	INVESTIGATION WORKS.....	2
4.	INVESTIGATION RESULTS .....	4
5	.DETAILED SKETCHES .....	6
6	REINSTATEMENT WORKS	
7.	PHOTO REPORT .....	18
7.	APPENDIX 1 – BRIDGE LAYOUT DRAWING	
8.	APPENDIX 2 - LAB TEST REPORT	

## 1. INTRODUCTION

TRIUR Construction LTD carried out structural investigation works on Strade River Bridge (MO-N58-001.00) from the 8<sup>th</sup> to the 12<sup>th</sup> of July 2024

The Scope of the work included the following:

The site works were to consist of the following:

- Mobilization and site set up
- Installation of traffic management measures (traffic lights)
- Excavation of 2no. trial pits in the concrete verges for depth of fill and deck exposure. One trial pit was excavated above the Northeastern abutment support while the second trial pit was excavated above the western pier support.
- Coring of 4x samples for strength testing of deck soffit ( 2no. in each span ).
- The drilling of pilot holes in both the deck and the abutments, as required.
- Expose the deck slab and cleaning of the deck surface in adhesion test area.
- Carry out waterproofing adhesion test in Test Area 1
- Delamination survey to both spans
- Ferroskan and Concrete breakout of Test area 1-7.
- Chloride, cement content and carbonation samples obtained for BHP to lab test.
- Half-cell potential and Resistivity testing conducted by BHP.
- Detailed sketches made of breakout areas to include reinforcement sizing, location, spacing and cover.
- Reinstatement of the breakout and coring areas using PLANITOP RASA AND RIPARA R4 cementitious mortar.
- Reinstatement of any road openings as per *Guidelines for Managing Openings in Public Roads (Guidelines on the Opening, Backfilling and Reinstatement of Openings in Public Roads) Second Edition Rev 1 (2017)*.
- Preparation of a detailed factual report on the investigation work undertaken at each bridge, i.e. one no. report required per bridge
- Removal of traffic management measures
- Demobilization
- The Bridge was reinstated on the 15<sup>th</sup> July 2024
- A detailed sketch was prepared, see below.
- A digital photographic record was carried out throughout the investigation works, see below.

## 2. GENERAL DESCRIPTION OF STRUCTURE

The Strade River Bridge is a 2 span filler beam bridge. Each span is approx. 3.8m in length with a width of 11m. The Strade River predominantly flows in the northern span while the southern span consists of an elevated concrete floor which at the time of testing was above the river water level and completely dry. It carries the N58 national secondary road over the Strade River which flows from east to west.

### Location

Strade River Bridge

Co-ordinates: 53.921444, -9.130361

MO-N58-001.00, Strade



## 3. INVESTIGATION WORKS

- The excavation of the Trial pits above the deck comprised of the breakout and removal of 2no. concrete rubbing strip located on the eastern and western verges. A layer of mesh and fill was also removed from each trial pit until the deck was exposed. Test area 1 (TA1) was located over the northeastern abutment while Test area 2 (TA2) was located over the western pier. No waterproofing layer was found above the concrete deck. No services or ducting were located in each respective trial pit.
- The excavation of a Trial pit (Test Area 01), located above the northeastern abutment to expose the RC slab for depth of fill and deck exposure. In this Trial Pit, a Covermeter and GPR survey was conducted to an area of the deck surface followed by concrete breakout to confirm cover and sizing of reinforcement members. The material covering this RC slab was observed to be 804 over layed with a concrete rubbing strip. A concrete core (C1) was also extracted for strength testing along with a pilot hole to obtain deck thickness. Durability testing was carried out by BHP.

- The excavation of a Trial pit (Test Area 02), located above the western end of the bridge pier to expose the RC slab for depth of fill and deck exposure. In this Trial Pit, a Covermeter and GPR survey was conducted to an area of the deck surface. No Steel was found on the deck side of the slab. A concrete core (C2) was also extracted for strength testing. A 25mm diameter pilot hole was drilled through the deck to obtain a value for the depth of the slab in this location. Durability testing was carried out by BHP.
- The investigation of Test Area 03, located in the the centre of the southern span on the western fascia. The area was scanned for reinforcement, samples acquired for testing and broken out to expose reinforcement.
- The investigation of Test area 3.1 located on the southeastern corner of the soffit of the southern span. In this area, a Concrete core (C3) was extracted for strength testing. A pilot hole was drilled to obtain measurements for deck thickness. A scan and breakout of the soffit in this area was undertaken to expose internal reinforcement.
- The investigation of Test Area 04, was located at the centre of the northern span on the western fascia. The area was scanned for reinforcement, samples acquired for testing and broken out to expose reinforcement.
- The investigation of Test area 4.1 located on the northwestern corner of the soffit on the Northern span. In this area, a Concrete core (C4) was extracted for strength testing. A pilot hole was drilled to obtain measurements for deck thickness. A scan and breakout of the soffit in this area was undertaken to expose internal reinforcement.
- The investigation of Test Area 05 located in the southern abutment approx. 3 meters from the the western edge. In this area, a Covermeter and GPR survey was conducted. 2no. durability tests were also conducted. This was followed by the drilling of a pilot hole to obtain the abutment thickness.
- The investigation of Test Area 06 located on the southern face of the pier at the midpoint. In this area, a Covermeter and GPR survey was conducted. 2no. durability tests were also conducted.
- The investigation of Test Area 07 located in the northern abutment approx. 3 meters from the eastern edge. In this area, a Covermeter and GPR survey was conducted. 2no. durability tests were also conducted. This was followed by the drilling of a pilot hole to obtain the abutment thickness.
- Adhesion pull off test on the deck top surface in Test Area 1 to determine the suitability of deck to a spray applied deck waterproofing system.
- Reinforcement was found via breakouts in both the deck and in the soffit. Both longitudinal and transverse members were located and exposed on the deck and the soffit. The longitudinal reinforcement consisted of asymmetrical I-beams wherein the top flange was found to be narrower and thicker than the bottom flange. The transverse support consisted of smaller rectangular length of steel located close to the soffit. No connection observed between the traverse reinforcement and the beams. Placed rebar detail.
- A delamination survey of both the southern and northern soffits was conducted. In the southern span, significant delamination was found across the whole width of the bridge. The areas where delamination had occurred were generally in the area covering each section of longitudinal reinforcement. The delamination ran in the direction of the longitudinal reinforcement while being consistent with the longitudinal reinforcement spacing.  
In the northern span, delamination was present in the midsection of the bridge between 5m and 7.5m in from the eastern fascia. There was evidence to suggest that this northern span had previously experienced delamination and been repaired.

## 4. INVESTIGATION RESULTS

TEST AREA 1	mm
DeckTrial hole (east)	
cover of fill	420
cover on longitudinal bars	148
cover on transverse bars	124
Longitudinal bar sizing	125mm high rail
Transverse bar sizing	23x13mm bar
pilot hole 1	300
pilot hole 2	315
pilot hole 3	320
pilot hole 4	300
Core 1 – Area 1 – Deck	18.9 N/mm2
Core 2 – Area 1 – Deck	21.1 N/mm2

TEST AREA 2	mm
DeckTrial hole (west)	
cover of fill	315
cover on longitudinal bars	n/a
cover on transverse bars	n/a
Longitudinal bar sizing	n/a
Transverse bar sizing	n/a
<i>No reinforcement found above rail girders</i>	

TEST AREA 3	mm
FACIA (south west)	
side cover on Web	129
cover on bottom flange	32
side cover bottom flange	68
side cover on top flange	105

TEST AREA 3.1	mm
soffit (south east)	
cover of fill	n/a
cover on longitudinal bars	34
cover on transverse bars	59
Longitudinal bar sizing	125 high rail
Transverse bar sizing	23x13mm bar
Core 3 – Area 3.1 – Soffit 1	49.6 N/mm <sup>2</sup>

TEST AREA 4	mm
FACIA (north west)	
side cover on Web	132
cover on bottom flange	37
side cover bottom flange	80
side cover on top flange	104
Core 4 – Area 4.1 – Soffit 2	57.1 N/mm <sup>2</sup>

TEST AREA 4.1	mm
soffit (north west)	
cover of fill	n/a
cover on longitudinal bars	47
cover on transverse bars	51
Longitudinal bar sizing	125 high rail
Transverse bar sizing	23x13mm bar

TEST AREA 5	mm
Southern Abutment	
pilot hole	740
cover on longitudinal bars	n/a
cover on transverse bars	n/a
Longitudinal bar sizing	n/a
Transverse bar sizing	n/a
<i>No reinforcement found</i>	

TEST AREA 6	mm
Pier mid support (south west side )	
pilot hole	n/a
cover on longitudinal bars	n/a
cover on transverse bars	n/a
Longitudinal bar sizing	n/a
Transverse bar sizing	n/a
<i>No reinforcement found</i>	

TEST AREA 7	mm
Northern Abutment	
pilot hole	890
cover on longitudinal bars	n/a
cover on transverse bars	n/a
Longitudinal bar sizing	n/a
Transverse bar sizing	n/a
<i>No reinforcement found</i>	

## 5.DETAILED SKETCHES

Plan of works area – Test Area locations – see Appendix 1 for more details.




Figure 1: Strade Bridge Plan

## Test area 1





Figure 2: Test area 1 drawing

Test area 2

### Test Area 2- Plan View



### Test Area 2- Section




Figure 3: Test area 2 drawing

Test area 3

## TA3 Facia - SIDE SECTION




Figure 4: Facia side section

## TA3 Facia - CROSS SECTION




Figure 5: TP3 Facia cross section

# TA3 Beam dimensions (mm)




Figure 6 : External Beam Dimensions

Test area 3.1

TA3.1 Soffit  
(south east corner)




Figure 7: Test area 3.1 Soffit

Test area 4

TA4 Facia - SIDE SECTION




Figure 8:TA4 Facia - Side Section

TA3 Facia - CROSS SECTION




Figure 9 : TA4 Facia - Cross Section

# TA4 Beam dimensions (mm)




Figure 10: TA4 Beam Dimensions

## Test area 4.1

### T4.1 Soffit (south east corner)





Figure 11: Test Area 4.1

Delamination – shown in Red



## 6. REINSTATEMENT DETAIL

- Rubbing strip cutouts were backfilled with UGM A and infilled with 35N 10mm agg



- Fosroc Renderoc HB45 was used to carry out concrete repairs to breakouts.



7. PHOTO REPORT

**General bridge overview**






**TEST AREA 1**



Figure 12: Test area 1 containing pilot hole, core sample hole and breakout.



*Figure 13: Trial Pit layers*



*Figure 14: Deck cover on longitudinal steel*



*Figure 15: Concrete core hole (C1)*



*Figure 16: Adhesion testing*

**Test Area 2**



*Figure 17: Trial pit on western edge*



Figure 18: Trial pit layers



*Figure 19: 90mm cutout in deck surface*

**Test area 3**



*Figure 20: Breakout of external beam*



*Figure 21: Wide angle view of test area including drill holes for dust samples*



*Figure 22: Half cell potential testing*



*Figure 23: Carbonation test sample extracted to the left of breakout*

**Test Area 3.1**



*Figure 24: Core hole from C3*



*Figure 25: Measurement of longitudinal beam flange*



*Figure 26: Transverse steel members running perpendicular to longitudinal members at 160mm spacing*



*Figure 27: Longitudinal cover was 39mm, Transverse cover was 54mm*



*Figure 28: Delamination survey showed significant delamination underneath longitudinal sections on south arch*



*Figure 29: Further delamination on south arch*



*Figure 30: Exposed beams due to delamination of concrete cover*



*Figure 31: Delamination denoted by white x chalk marks*

**Test Area 4**



*Figure 32: Half cell potential testing of TP04*




*Figure 33: Resistivity testing of TP04*



*Figure 34: Breakout at test area 4 exposing external beam*

**Test Area 4.1**



*Figure 35: Breakout of internal beam showing transverse spacing marked via GPR*



*Figure 36: Half cell potential testing*



*Figure 37: Delamination found in northern arch*



*Figure 38: Delamination survey in Northern arch wide angle view*



*Figure 39: Core hole C4*



*Figure 40: Longitudinal bottom flange thickness*



*Figure 41: Cover of Transverse steel*



*Figure 42: 125mm wide bottom flange of internal beam*



*Figure 43: Wide angle view of breakout area*


**Test Area 5**



*Figure 44: Pilot hole reinstatement along with dust sample holes*



*Figure 45: Pilot hole depth measurement*



*Figure 46: Outline of scanned area*

# Test Area 6



*Figure 47: Outline of scanned area with carbonation sample removed*



*Figure 48: Carbonation sample consisted of 100mm x 100mm x 80mm cuboid*



*Figure 49: TA6 carbonation sample depth into pier*


**Test Area 7**



*Figure 50: Wide angle view of test area*




*Figure 51: Pilot hole reinstatement*



*Figure 52: Drill holes used for dust collection located on the northesatern end of the abutment*

# Appendix 1 – Bridge Layout

# Strade River Bridge Plan




# Appendix 2 – Lab Test report

# **Mayo Bridges Inspection – Strade River Bridge**

## **Concrete Testing Report**

**2024**

## Document Issue Register

Distribution	Report Status	Revision	Date of Issue	Prepared by	Approved by
Lurcan Donnellan Triur Construction	Final	A	27 <sup>th</sup> August 2024	Anton Hajek	James Purcell 

## Contents

<b>1.0</b>	<b>Project Overview</b>	<b>Page 4</b>
<b>2.0</b>	<b>Project Requirements</b>	<b>Page 4</b>
<b>3.0</b>	<b>Location of Works</b>	<b>Page 4</b>
<b>4.0</b>	<b>Summary of Results</b>	<b>Page 5 – 15</b>

<b>Concrete Strength Test Report</b>	<b>Appendix A</b>
<b>Pull Off Test Report</b>	<b>Appendix B</b>
<b>Carbonation Test Report</b>	<b>Appendix C</b>
<b>Reinforcement Test Report</b>	<b>Appendix D</b>
<b>Chloride Ion Test Report</b>	<b>Appendix E</b>
<b>Cement Content Test Report</b>	<b>Appendix F</b>
<b>Half Cell and Resistivity Test Report</b>	<b>Appendix G</b>

## 1.0 Project Overview

BHP was contracted by Lurcan Donnellan of Triur Construction to provide a survey of the concrete bridge.

The investigation is intended to provide information for the employer in respect of the structural condition of the concrete deck and parapets and to assess the existing condition to enable evaluation of the proposed need for strengthening/rehabilitation works.


## 2.0 Project Requirements

As directed by the project specification the requirements of the works included:



- Drill 4No. 100 diameter cores.
- Test for Density, Compressive strength and Visual examination.
- Chemical testing includes chloride content, cement content and depth of carbonation.
- Pull off testing on the concrete deck.
- Reinforcement scanning of concrete deck and parapets.
- Half-cell potential and concrete resistivity.

## 3.0 Location of Works

Site Location /  
Works Area



#### 4.0 Summary of Results



- \*Key**
- ✕ Cores
  - ✕ Half-cell
  - ✕ Pull test
  - ✕ Chloride
  - ✕ Carbonation
  - ✕ Cement

#### 4.1 Concrete Cores – Compressive Strength

In line with the project specification, BHP removed several cores from the reinforced concrete elements. These were cored using a water-cooled diamond drill. The cores were individually marked and placed in sealed plastic bags for transportation to the laboratory.

The concrete cores were visually assessed by BHP's technical manager Seamus O'Connell.

A summary of the results with photographs is contained below:

BHP Ref:	Core Ref.	Details	Density kg/m <sup>3</sup>	Compressive Strength N/mm <sup>2</sup>
24/07/072-1	Core 1 – Area 1 – Deck	20mm Crushed Rock, 1.5% Voids	2280	18.9
24/07/072-2	Core 2 – Area 1 – Deck	20mm Crushed Rock, 2.5% Voids	2300	21.1
24/07/072-3	Core 3 – Area 3.1 – Soffit 1	20mm Crushed Rock, 0.5% Voids	2610	49.6
24/07/072-4	Core 4 – Area 4.1 – Soffit 2	20mm Crushed Rock, 0.5% Voids	2380	57.1

The mean result for compressive strength for the deck cores is 20.0N/mm<sup>2</sup> with a standard deviation of 1.56. The mean density of the test specimens is 2290kg/m<sup>3</sup>.

The mean result for compressive strength for all the cores is 53.4N/mm<sup>2</sup> with a standard deviation of 5.3. The mean density of the test specimens is 2500kg/m<sup>3</sup>.

## 4.2 Pull Off Test

In accordance with the project specification, the pull off test was to be performed at one location in the concrete deck.

A summary of the results is contained below with full reports contained in Appendix B of this report.

Test Reference	Max Applied Load (MPa)	Depth of failure (mm)	Failure occurred in
Area 1 top deck	1.4	3	Below adhesive in concrete substrate (cohesion failure)
Area 1 top deck	1.7	4	Below adhesive in concrete substrate (cohesion failure)
Area 1 top deck	2.3	5.0	Below adhesive in concrete substrate (cohesion failure)
Area 1 top deck	0.9	0	Below adhesive on top of concrete surface (adhesion failure)
Area 1 top deck	2.6	4.0	Below adhesive in concrete substrate (cohesion failure)
<b>Mean</b>	<b>1.78</b>		

### 4.3 Carbonation

In accordance with the project specification, the carbonation testing was to be performed at seven locations.

Carbonation testing is carried out to determine the depth of concrete affected due to a combined attack of atmospheric carbon dioxide and moisture causing a reduction in the level of alkalinity in concrete. Cement paste has a pH of approximately 13 which provides a protective layer (passive coating) to the steel reinforcement against corrosion. Loss of passivity occurs at about pH 9.

A 3% phenolphthalein indicator is used for the test. This is applied to freshly exposed concrete surface as detailed above.

Once the indicator is applied to the concrete surface, the change of colour of concrete to pink indicates that the concrete is in good health/condition. Where no change in colour takes place, it is suggestive of carbonation-affected concrete.

The results of the tests performed at Knockavrony Bridge, Co. Mayo are contained in Appendix C of this report.

A summary of the results is contained below:

Location	Depth of Carbonation (mm)
Carbonation Test 1 – Area 1 Top Deck	<1
Carbonation Test 2 – Area 2 Top Deck	<1
Carbonation Test 3 – Area 3 Face deck	<1
Carbonation Test – Area 3.1 Soffit	16
Carbonation Test 5 – Area 4 Face deck	<1
Carbonation Test 6 – Area 4.1 Soffit	<1
Carbonation Test 7 – Area 5 Abutment	>20
Carbonation Test 8 – Area 5 abutment	<1
Carbonation Test 9 – Area 6 abutment	<1
Carbonation Test 10 – Area 6 abutment	<1
Carbonation Test 11 – Area 7 abutment	<1
Carbonation Test 12 – Area 7 abutment	<1

There was no obvious reason for the differing levels of carbonation other than different locations. The two locations of high carbonation can be viewed as isolated instances of carbonation. All other results had negligible carbonation. At both soffit locations (3.1 and 4.1), there was clear visual spalling of concrete. However, the carbonation at 4.1 did not show high carbonation like at location 3.1. To understand a full assessment of carbonation, further samples would have to be taken at a number of locations throughout to ascertain the consistency. It must be noted that the chloride ingress into the concrete is very low, so refurbishment works including the application of protection paint/similar material should limit any increase in carbonation and reduce long-term risks of corrosion occurring.

#### 4.4 Reinforcement Details

In following page, a summary of reinforcement investigation on deck, parapet sections and information on the reinforcement found in breakouts have been compiled from the survey conducted in Strade River Bridge, Co. Mayo

Full details are in Appendix D of this report.

Scan Location	Rebar direction	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)	Minimum Spacing (mm)	Maximum Spacing (mm)
Area 1 top deck longitudinal scan 001	T	153	n/a	n/a	n/a	n/a	n/a
Area 1 top deck transverse scan 001	L	164	158	170	180	n/a	n/a
Area 2 top of deck longitudinal scan 001	T	160	137	183	640	n/a	n/a
Area 2 top of deck longitudinal scan 002	T	156	150	162	620	n/a	n/a
Area 2 top of deck transverse scan 001	L	204	144	238	405	130	680
Area 3 deck face vertical scan 001	L	142	136	148	60	n/a	n/a
Area 3 deck face horizontal scan 001	T	135	n/a	n/a	n/a	n/a	n/a
Area 3.1 soffit longitudinal scan 001	T	38	28	48	684	560	710
Area 3.1 soffit longitudinal scan 002	T	42	37	48	657	620	690
Area 3.1 soffit transverse scan 001	L	46	42	55	166	140	198
Area 3.1 soffit transverse scan 002	L	62	54	68	165	140	196
Area 4 Deck Face Vertical scan 001	L	106	92	120	120	n/a	n/a

Area 4 Deck Face Horizontal scan 001	T	n/a	n/a	n/a	n/a	n/a	n/a
Area 4.1 Soffit longitudinal scan 001	T	48	42	51	666	640	700
Area 4.1 Soffit longitudinal scan 002	T	51	42	56	707	640	750
Area 4.1 Soffit transverse scan 001	L	60	44	69	227	120	330
Area 4.1 Soffit transverse scan 002	L	65	55	76	216	120	319
Area 5 Abutment vertical scan 001	L	n/a	n/a	n/a	n/a	n/a	n/a
Area 5 Abutment horizontal scan 001	T	n/a	n/a	n/a	n/a	n/a	n/a
Area 6 Pier horizontal scan 001	T	n/a	n/a	n/a	n/a	n/a	n/a
Area 6 Pier Vertical scan 001	L	n/a	n/a	n/a	n/a	n/a	n/a
Area 7 Abutment Vertical scan 001	L	n/a	n/a	n/a	n/a	n/a	n/a
Area 7 Abutment Horizontal scan 001	T	n/a	n/a	n/a	n/a	n/a	n/a

Rebar directions: L- longitudinal, T- transverse

\* In Area 1 (TP1), Area 2 (TP2) were not enough space to get more reinforcement readings due to lack of access for GPR as the Trail hole area only allowed for coring and breakouts

\* In Area 5 – Area 7 GPR did not find any reinforcement

Reinforcement found by completing a breakout	Actual cover (mm)	Diameter (mm)	Width(mm)
Area 1 top of deck top flange	150	N/A	N/A
Area 1 top of deck transverse rebar square	109	14.3 / 25.7	N/A
Area 3 face deck web	129	N/A	N/A
Area 3 face deck bottom flange	32	10.89	123
Area 3 face deck bottom side flange	68	N/A	N/A
Area 3 face deck top flange	104	N/A	N/A
Area 3 face deck distance top-bottom flange	117	N/A	N/A
Area 3.1 soffit bottom flange	34	N/A	N/A
Area 3.1 soffit transverse rebar square	59	15.3 / 28.9	N/A
Area 4 face deck top side flange	104	31.39	N/A
Area 4 face deck web	132	N/A	N/A
Area 4 face deck bottom flange	80	N/A	N/A
Area 4 face deck bottom flange	37	8.86	N/A
Area 4.1 soffit bottom flange	47	N/A	N/A
Area 4.1 soffit transverse rebar square	51	13.5 / 23.6	N/A

## 4.5 Chloride Ion Testing

Corrosion of reinforcing steel and other embedded metals is the leading cause of deterioration in concrete. When steel corrodes, the resulting rust occupies a greater volume than the steel. This expansion creates tensile stresses in the concrete, which can eventually cause cracking, delamination and spalling.

Steel corrodes because it is not a naturally occurring material. Rather, iron ore is smelted and refined to produce steel. The production steps that transform iron ore into steel add energy to the metal. Steel, like most metals except gold and platinum, is thermodynamically unstable under normal atmospheric conditions and will release energy and revert back to its natural state – iron oxide, or rust. This process is called corrosion.

Corrosion is an electrochemical process involving the flow of charges (electrons and ions). At active sites on the reinforcement bar, called anodes, iron atoms lose electrons and move into the surrounding concrete as ferrous ions. This process is called a half-cell oxidation reaction, or anodic reaction.

Corrosion of embedded metals in concrete can be greatly reduced by placing crack-free concrete with low permeability and sufficient concrete cover. Additional measures to mitigate corrosion of steel reinforcement in concrete include the use of corrosion inhibiting admixtures, coating of reinforcement, and the use of sealers and membranes on the concrete surface.

As noted in section 4.3 carbonation, the breakdown in the protection of reinforcement bars leads to concrete spalling. The depth of carbonation provides a guide as to the risk of corrosion on a particular bar. Concrete that is not carbonated (or has very low levels of carbonation) protects the embedded steel reinforcement.

Exposure of reinforced concrete to chloride ions is the primary cause of premature corrosion of steel reinforcement. The intrusion of chloride ions present in deicing salts, seawater and other associated sources, into reinforced concrete can cause steel corrosion if oxygen and moisture are available to sustain the reaction. Chlorides dissolved in water can penetrate through sound concrete or reach the steel through cracks.

No other contaminant is documented as extensively in the literature as a cause of corrosion of metals in concrete than chloride ions. The risk of corrosion increases as the chloride content of concrete increases. For Strade River bridge, Co. Mayo, the major concern is the extent of any existing chloride within the various concrete structural elements. While the levels are assessed during this survey, as the concrete is continually exposed to the natural environments and weathering, the level of chloride in the concrete could increase with time.

To assess potentially chloride-contaminated concrete, it is necessary to determine the concentration of chloride ions at various depths in order to determine the likelihood of corrosion of the reinforcement steel. To do this dust samples are taken from incremental depths. As specified, this was to be carried out in four depths (5-30mm, 30-55mm, 55-80mm & 80-105mm). Note the first 5mm drilling are normally discarded as being non-representative. Care was taken to ensure all drilling dust was collected. This is important as studies have shown that more chloride is contained in the finer component of the dust.

In line with the Irish concrete standard (EN 206), the chloride content as a percentage of cement is to be below the maximum allowable of 0.4% for concrete mixes containing embedded steel. At all twelve locations, the chloride content as a percentage of cement is below this value.

A summary table of the results is found below:

Location Reference	Sample Reference	Depth (mm)	Chloride Content % by mass of	
			Sample	Cement
Area 1 - Car 1	24/07/072-1	5-30	0.01	0.08
		30-55	0.01	0.08
		55-80	0.02	0.15
		80-105	0.01	0.08
Area 2 - Car 2	24/07/072-2	5-30	0.04	0.20
		30-55	0.03	0.15
		55-80	0.03	0.15
		80-105	0.01	0.05
Area 3 - Car 3	24/07/072-3	5-30	0.02	0.13
		30-55	0.02	0.13
		55-80	0.02	0.13
		80-105	0.02	0.13
Area 3.1 - Car 4	24/07/072-4	5-30	0.03	0.20
		30-55	0.02	0.13
		55-80	0.03	0.20
		80-105	0.03	0.20
Area 4 - Car 5	24/07/072-5	5-30	0.04	0.19
		30-55	0.02	0.10
		55-80	0.02	0.10
		80-105	0.02	0.10
Area 4.1 - Car 6	24/07/072-6	5-30	0.04	0.33
		30-55	0.03	0.25
		55-80	0.03	0.25
		80-105	0.04	0.33

Location Reference	Sample Reference	Depth (mm)	Chloride Content % by mass of	
			Sample	Cement
Area 5 - Car 7	24/07/072-7	5-30	0.02	0.20
		30-55	0.01	0.10
		55-80	0.01	0.10
		80-105	0.01	0.10
Area 5 - Car 8	24/07/072-8	5-30	0.02	0.25
		30-55	0.01	0.13
		55-80	0.01	0.13
		80-105	0.01	0.13
Area 6 - Car 9	24/07/072-9	5-30	0.01	0.07
		30-55	0.01	0.07
		55-80	0.01	0.07
		80-105	0.01	0.07
Area 6 - Car 10	24/07/072-10	5-30	0.03	0.21
		30-55	0.03	0.21
		55-80	0.03	0.21
		80-105	0.03	0.21
Area 7 - Car 11	24/07/072-11	5-30	0.01	0.08
		30-55	0.01	0.08
		55-80	0.01	0.08
		80-105	0.01	0.08
Area 7 - Car 12	24/07/072-12	5-30	0.03	0.17
		30-55	0.03	0.17
		55-80	0.02	0.11
		80-105	0.02	0.11

## 4.6 Cement Content

The determination of the cement content (mix proportions) is undertaken largely for two reasons. The first is in the cases of problems to identify the reason for concrete failure or lack of quality. The second is to investigate old structural concrete for redevelopment and improvement works. This is the case in this project. The cement content analysis will also allow BHP to provide chloride and sulphate results as a percentage of cement for clear comparison with standard allowances.

We start by describing the raw materials that go into mortar and concrete and by defining some terms. Cement is a generic term meaning “glue.” Portland cement is a gray powder that when mixed with water forms a paste that hardens and gains strength with time. This is the glue that holds mortar and concrete together. When sand or fine aggregate is added to paste the mixture is known as mortar which is suitable for thin cross sections. Grouts, plasters and stuccos are generally special mortars and contain much the same raw materials. Stone added to mortar makes concrete which can be used in structural or massive applications.

The cement most often used in construction is known as Portland cement. There are other types of construction cements, some used in masonry construction and other special cements used for repairs or high temperature applications. This paper addresses Portland cement and its derivatives only. The predominant chemical compounds in Portland cement are based upon oxides of calcium (lime), silicon (silica), aluminium (alumina) and iron. There are other compounds present in smaller quantities such as magnesia and carbon dioxide and a number of trace elements. The principal chemical compounds that combine with water (hydrate) to provide strength are calcium silicates. However, in all reported chemical analyses, the constituents of cement and concrete are reported simply as the appropriate oxides. Modern Portland cements, by definition, all tend to contain these compounds in a fairly tight range of values even if they come from different manufacturing facilities. Hydrated Portland cement has the unusual, and desirable, property that it will continue to gain strength (albeit at a decreasing rate) when in the presence of water. This complicates chemical analysis because the system is continually changing from the time of first mixing to the time of test.

The cement content analysis for Strade River bridge, Co. Mayo was undertaken on twelve samples. The samples came from deck, abutments and soffits in different levels. The mean cement content results for the twelve samples is 14% with a range of 8% – 20%. A summary table of the results is found below.

Location	Cement Content (%)	Compressive Strength (N/mm <sup>2</sup> ) – from core test
Area 1 Top Deck	13	18.9
Area 2 Top Deck	20	21.1
Area 3 Face deck	16	-
Area 3.1 Soffit	15	49.6
Area 4 Face deck	21	-
Area 4.1 Soffit	12	57.1
Area 5 Abutment	10	-
Area 5 Abutment	8	-
Area 6 Pier	14	-
Area 6 Pier	14	-
Area 7 Abutment	12	-
Area 7 Abutment	18	-

A cement content of 16-17% would normally indicate an approximate in-situ compressive strength of 50N. The values found here find that the expected cement content for the soffit is a little lower than expected. The biggest different is the cement content in the top deck versus the actual compressive strength. Albeit one of the cores in the soffit contained reinforcement, the density of these concrete versus the concrete in the deck is much higher.

#### 4.7 Half Cell and Resistivity

Corrosion of steel in concrete is one of the major problems with respect to the durability of reinforced concrete structures. Most concrete structures perform well even after a long period of use in normal environments. However, there are various reinforced concrete structures important for our infrastructure, especially bridges and buildings, which exhibit premature damage due to environmental actions (EN 206).

In contrast to mechanical actions (load, wind, etc.) the environmental actions are not reversible and accumulate hazardous components (such as chloride ions) in the concrete. A high percentage of the damage is caused by insufficient planning, wrong estimation of severity of environmental actions and by bad workmanship and this many of these structures need to be repaired after a short service life.

Half-cell potential measurements can be performed on structures with ordinary or stainless-steel reinforcement. Corrosion of prestressing steel in concrete can be assessed in the same way. Prestressing steel in the ducts of posttensioned cables cannot be assessed.

Half-cell potential measurements are suitable mainly on reinforced concrete structures exposed to the atmosphere. The method can be applied regardless of the depth of concrete cover and the rebar size. Half-cell potential measurements will indicate corroding rebars not only in the most external layers of reinforcement facing the reference electrode but also in greater depth. The method can be used at any time during the life of a structure and in any kind of climate providing the temperature is higher than +2°C. Half-cell potential measurements should be taken only on a free concrete surface. The presence of isolating layers (asphalt, organic coatings or paints etc.) may make measurements erroneous or impossible.

In the assessment of the half-cell results, ASTM C876 uses a numeric technique to assess the half-cell potential results.

Table 1: Relationship between the potential values and corrosion probability  
(adapted from ASTM C876)

Measured Potential(mV CSE)	Probability of steel corrosion activity
>-200	Less than 10%
-200 to -350	Uncertain
<-350	More than 90%

#### Half Cell Potential Results

Location	Mean (mV)	Lowest (mV)	Highest (mV)	Standard Deviation (mV)
Area 1 Top deck	-239	-268	-207	19.8
Area 3 Face deck	-54.9	-97	-27	21
Area 3.1 Soffit	-333.5	-368	-320	13.2
Area 4 Face deck	-237.7	-283	-198	28.3
Area 4.1 Soffit	-165.8	-179	-129	13

Based on this, it sets our three phases of corrosion activity – Initial Phase, Transient Phase, and the Final Phase. For any half-cell potential results that are  $> -200$  it is deemed to be in the initial phase where the probability of corrosion activity is less than 10%. Where the half-cell potential results that are in the range of  $-200$  to  $-350$  (Transient Phase), the probability of corrosion activity is uncertain. Where the half-cell potential results that are  $< -350$  (Final Phase), the probability of corrosion activity is more than 90%. Based on the results and visual examination of the bars on site when broken out, the likelihood of corrosion based on half-cell results is moving from the initial phase to the transient phase.

In addition to half-cell potential surveying of concrete, resistivity measurements of the same concrete material provide further information on the potential for further corrosion taking or to take place. Corrosion of reinforcing steel is an electro-chemical process. For corrosion of the steel to occur a current must pass between the anodic and cathodic regions of the concrete. The electrical resistivity of the concrete affects the flow of ions and the rate at which corrosion can occur. A higher concrete resistivity decreases the flow; an empirical relationship between corrosion rate and resistivity has been determined from measurements on actual structures.

Electrical resistivity measurement techniques are becoming popular among consulting / design engineers for the quality assessment and durability assessment of concrete. The concept of durability of concrete depends largely on the properties of its microstructure, such as pore size distribution and the shape of the interconnections (that is, tortuosity). A finer pore network, with less connectivity, leads to lower permeability. A porous microstructure with larger degree of interconnections, on the other hand, results in higher permeability and reduced durability in general. The principal idea behind most electrical resistivity techniques is to somehow quantify the conductive properties of the microstructure of concrete. Overall, the electrical resistivity of concrete can be described as the ability of concrete to withstand the transfer of ions subjected to an electrical field. In this context, resistivity measurement can be used to assess the size and extent of the interconnectivity of pores.

Various approaches for measuring resistivity are available but the four-probe device is the most suitable. Modern devices are spring-loaded and are applied directly to the surface. A current is applied between the two outer probes and the potential difference measured between the two inner probes. Resistivity measurement is useful for identifying areas of reinforced concrete at risk from corrosion. It should not be considered in isolation but used in conjunction with other techniques such as half-cell potential. BHP employed the use of the latest version of Proceq's Resipod with 50mm spacings between the four probes.

From the testing undertaken at this structure, we found that there was a negligible risk of corrosion based on the resistivity results.

Location	Result 1	Result 2	Result 3	Result 4	Result 5
Area 1 Top deck	106	112	172	185	190
Area 3 Face deck	69	55	72	-	-
Area 3.1 Soffit	285	278	303	256	272
Area 4 Face deck	186	156	194	-	-
Area 4.1 Soffit	196	206	209	255	272

# Appendix A



## COMPRESSIVE STRENGTH OF A CONCRETE CORE TEST REPORT



BHP/MTField/F058 V1 29/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-1  
**Order No:** Not Supplied  
**Date Tested:** 09/07/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Core

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 1 C1 Deck  
**Test Standard:** EN 12504-1:2019

Core Details			
Coring Date	12/07/2024	Age of specimen	Not Specified
End of core used as datum	Top	Reinforcement in test Specimen: Size (mm)	N/A
Drilling Direction	Vertical	Reinforcement in test Specimen: Position (mm)	N/A
Visual Assessment			
Condition of specimen when received	Good	Maximum nominal size of aggregate (mm)	20
Compaction of concrete	Good	Distribution of materials	Even
Excess Voids	1.5%	Ribbing on core surface	None
Honeycombing	Yes	Flatness	Pass
Presence of cracks	None	Perpendicularity	Pass
Type of aggregate	Crushed Rock	Straightness	Pass
Test Information			
<b>Preparation</b>		Surface condition at time of test	Dry
Length after end preparation	102	Type of failure	Satisfactory
Diameter after end preparation	99	Average Diameter (mm)	99
Length / diameter ratio of specimen	1.03	Maximum length of specimen, as received	144
		Minimum length of specimen, as received	144
		Density of the specimen, as received (kg/m <sup>3</sup> )	2280
		Max Load (KN)	144.8
		Compressive Strength (N/mm <sup>2</sup> )	18.9

### REMARKS:

Method of determining volume used was displacement. Method of end preparation used was sawn & capped. The sample was stored in a sealed container prior to testing.

Approved By:	Signature:
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 19/07/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.



## COMPRESSIVE STRENGTH OF A CONCRETE CORE TEST REPORT



BHP/MTIField/F058 V1 29/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-2  
**Order No:** Not Supplied  
**Date Tested:** 09/07/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Core

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 2 C2 Deck  
**Test Standard:** EN 12504-1:2019

Core Details			
Coring Date	12/07/2024	Age of specimen	Not Specified
End of core used as datum	Top	Reinforcement in test Specimen: Size (mm)	N/A
Drilling Direction	Vertical	Reinforcement in test Specimen: Position (mm)	N/A
Visual Assessment			
Condition of specimen when received	Good	Maximum nominal size of aggregate (mm)	20
Compaction of concrete	Good	Distribution of materials	Even
Excess Voids	2.5%	Ribbing on core surface	None
Honeycombing	Yes	Flatness	Pass
Presence of cracks	None	Perpendicularity	Pass
Type of aggregate	Crushed Rock	Straightness	Pass
Test Information			
<b>Preparation</b>		Surface condition at time of test	Dry
Length after end preparation	102	Type of failure	Satisfactory
Diameter after end preparation	99	Average Diameter (mm)	99
Length / diameter ratio of specimen	1.03	Maximum length of specimen, as received	123
		Minimum length of specimen, as received	123
		Density of the specimen, as received (kg/m <sup>3</sup> )	2300
		Max Load (KN)	161.8
		Compressive Strength (N/mm <sup>2</sup> )	21.1

### REMARKS:

Method of determining volume used was displacement. Method of end preparation used was sawn & capped. The sample was stored in a sealed container prior to testing.

Approved By:	Signature:
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 19/07/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.



## COMPRESSIVE STRENGTH OF A CONCRETE CORE TEST REPORT



BHP/MTIField/F058 V1 29/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-3  
**Order No:** Not Supplied  
**Date Tested:** 09/07/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Core

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 3.1 C3 Soffit  
**Test Standard:** EN 12504-1:2019

Core Details			
Coring Date	12/07/2024	Age of specimen	Not Specified
End of core used as datum	Top	Reinforcement in test Specimen: Size (mm)	Square (14x25mm)
Drilling Direction	Vertical	Reinforcement in test Specimen: Position (mm)	60
Visual Assessment			
Condition of specimen when received	Good	Maximum nominal size of aggregate (mm)	20
Compaction of concrete	Good	Distribution of materials	Even
Excess Voids	0.5%	Ribbing on core surface	None
Honeycombing	None	Flatness	Pass
Presence of cracks	None	Perpendicularity	Pass
Type of aggregate	Crushed Rock	Straightness	Pass
Test Information			
<b>Preparation</b>		Surface condition at time of test	Dry
Length after end preparation	102	Type of failure	Satisfactory
Diameter after end preparation	99	Average Diameter (mm)	99
Length / diameter ratio of specimen	1.03	Maximum length of specimen, as received	145
		Minimum length of specimen, as received	145
		Density of the specimen, as received (kg/m <sup>3</sup> )	2610
		Max Load (KN)	380.9
		Compressive Strength (N/mm <sup>2</sup> )	49.6

### REMARKS:

Method of determining volume used was displacement. Method of end preparation used was sawn & capped. The sample was stored in a sealed container prior to testing.

Approved By:	Signature:
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 28/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.



## COMPRESSIVE STRENGTH OF A CONCRETE CORE TEST REPORT



BHP/MTIField/F058 V1 29/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-4  
**Order No:** Not Supplied  
**Date Tested:** 09/07/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Core

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 4.1 C4 Soffit  
**Test Standard:** EN 12504-1:2019

Core Details			
Coring Date	12/07/2024	Age of specimen	Not Specified
End of core used as datum	Top	Reinforcement in test Specimen: Size (mm)	N/A
Drilling Direction	Vertical	Reinforcement in test Specimen: Position (mm)	N/A
Visual Assessment			
Condition of specimen when received	Good	Maximum nominal size of aggregate (mm)	20
Compaction of concrete	Good	Distribution of materials	Even
Excess Voids	0.5%	Ribbing on core surface	None
Honeycombing	None	Flatness	Pass
Presence of cracks	None	Perpendicularity	Pass
Type of aggregate	Crushed Rock	Straightness	Pass
Test Information			
Preparation		Surface condition at time of test	Dry
Length after end preparation	102	Type of failure	Satisfactory
Diameter after end preparation	99	Average Diameter (mm)	99
Length / diameter ratio of specimen	1.03	Maximum length of specimen, as received	135
		Minimum length of specimen, as received	120
		Density of the specimen, as received (kg/m <sup>3</sup> )	2380
		Max Load (KN)	438.9
		Compressive Strength (N/mm <sup>2</sup> )	57.1

### REMARKS:

Method of determining volume used was displacement. Method of end preparation used was sawn & capped. The sample was stored in a sealed container prior to testing.

Approved By:	Signature:
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 28/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# Appendix B

## BOND STRENGTH BY PULL OFF TEST REPORT



BHP/MTIField/F045 V1 15/04/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072  
**Order No:** Not Supplied  
**Date Tested:** 12/07/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Surface

**Project:** Mayo Bridges - Strade River Bridge  
**Location Reference:** See below  
**Test Standard:** BS EN 1542

Surface Condition: Wet  
Deck Surface Condition: As Supplied  
Test Direction: Vertical

Test Reference	Max Applied Load (MPa)	Depth of Failure (mm)	Failure Occurred In
Area 1 deck	1.4	3.0	Below adhesive on top of substrate
Area 1 deck	1.7	4.0	Below adhesive on top of substrate
Area 1 deck	2.3	5.0	Below adhesive on top of substrate
Area 1 deck	0.9	0.0	Below adhesive on top of substrate
Area 1 deck	2.6	4.0	Below adhesive on top of substrate
Mean	1.78		

### REMARKS:

Elcometer 506 Pull - Off Adhesion Tester

Approved By:	Signature:
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 13/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# Appendix C

**CARBONATION DEPTH OF CONCRETE  
TEST REPORT**




BHP/MTIField/F053 V1 15/05/24

<b>Client:</b>	TRIUR Construction Ltd 13 Society Street Ballinasloe Galway	<b>BHP Ref. No.:</b>	24/07/072
<b>FAO:</b>	Lurcan Donnellan	<b>Order No:</b>	Not Supplied
		<b>Date Tested:</b>	09/07/2024
		<b>Test Specification:</b>	Customer Spec.
		<b>Test Element:</b>	Concrete Core
<b>Project:</b>	Mayo Bridges Investigation - Strade River		
<b>Location Reference:</b>	See below		
<b>Test Standard:</b>	BS EN 14630		

Location Reference	Carbonation (mm)	Notes
Car 1	<1.0	Area 1
Car 2	<1.0	Area 2
Car 3	<1.0	Area 3
Car 4	16	Area 3.1
Car 5	<1.0	Area 4
Car 6	<1.0	Area 4.1
Car 7	>20	Area 5
Car 8	<1.0	Area 5
Car 9	<1.0	Area 6
Car 10	<1.0	Area 6
Car 11	<1.0	Area 7
Car 12	<1.0	Area 7

**REMARKS:**

Nil

Approved By:	Signature:
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# Appendix D

**TEST REPORT**

Analysing  
Testing  
Consulting  
Calibrating



**Account:** Triur Construction Ltd,  
13 Society Street,  
Ballinasloe,  
Galway

**BHP Ref No.:** 24/07/072  
**Order No.:** Not Supplied  
**Date Received:** Not Applicable  
**Date Tested:** 12/07/2024  
**Specification:** Client Specification

New Road  
Thomondgate  
Limerick  
Ireland  
Tel +353 61 455399  
Fax + 353 61 455447  
E Mail: [jamespurcell@bhp.ie](mailto:jamespurcell@bhp.ie)


**Customer:** Mr. Lurcan Donnellan.

**Customer Reference:** Reinforcement Scanning at Strade River Bridge, Co. Mayo

**Steel Reinforcement Survey**

On Tuesday 9th July and Friday 12<sup>th</sup> July 2024, BHP Laboratories visited Strade River bridge, Co. Mayo. The purpose of these specific works was to conduct a series of reinforcement scans to determine the concrete cover and reinforcement layout in top deck, face deck and soffit of bridge.

BHP undertook scans of the top deck, face deck and soffit to ascertain the reinforcement position and cover. BHP conducted this reinforcement scanning using the latest from Proceq – Ground Penetrating Radar (GPR).

**Site Location**

The scanning of the top deck, face deck and soffit bridge has found the following information / key points:

Scan Location	Rebar directions	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)	Minimum Spacing (mm)	Maximum Spacing (mm)
Area 1 top deck longitudinal scan 001	T	153	n/a	n/a	n/a	n/a	n/a
Area 1 top deck transverse scan 001	L	164	158	170	180	n/a	n/a
Area 2 top of deck longitudinal scan 001	T	160	137	183	640	n/a	n/a
Area 2 top of deck longitudinal scan 002	T	156	150	162	620	n/a	n/a
Area 2 top of deck transverse scan 001	L	204	144	238	405	130	680
Area 3 deck face vertical scan 001	L	142	136	148	60	n/a	n/a
Area 3 deck face horizontal scan 001	T	135	n/a	n/a	n/a	n/a	n/a
Area 3.1 soffit longitudinal scan 001	T	38	28	48	684	560	710
Area 3.1 soffit longitudinal scan 002	T	42	37	48	657	620	690
Area 3.1 soffit transverse scan 001	L	46	42	55	166	140	198
Area 3.1 soffit transverse scan 002	L	62	54	68	165	140	196
Area 4 Deck Face Vertical scan 001	L	106	92	120	120	n/a	n/a
Area 4 Deck Face Horizontal scan 001	T	n/a	n/a	n/a	n/a	n/a	n/a
Area 4.1 Soffit longitudinal scan 001	T	48	42	51	666	640	700
Area 4.1 Soffit longitudinal scan 002	T	51	42	56	707	640	750
Area 4.1 Soffit transverse scan 001	L	60	44	69	227	120	330
Area 4.1 Soffit transverse scan 002	L	65	55	76	216	120	319
Area 5 Abutment vertical scan 001	L	n/a	n/a	n/a	n/a	n/a	n/a

Scan Location	Rebar directions	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)	Minimum Spacing (mm)	Maximum Spacing (mm)
Area 5 Abutment horizontal scan 001	T	n/a	n/a	n/a	n/a	n/a	n/a
Area 6 Abutment horizontal scan 001	T	n/a	n/a	n/a	n/a	n/a	n/a
Area 6 Abutment Vertical scan 001	L	n/a	n/a	n/a	n/a	n/a	n/a
Area 7 Abutment Vertical scan 001	L	n/a	n/a	n/a	n/a	n/a	n/a
Area 7 Abutment Horizontal scan 001	T	n/a	n/a	n/a	n/a	n/a	n/a


\*Rebar directions: L- longitudinal, T- transverse

\* In Area 1(TP1), Area 2 (TP2) were not enough space to get more reinforcement readings due to lack of access for GPR


\* In Area 5 – Area 7 GPR did not find any reinforcement

Reinforcement found by completing a breakout	Actual cover (mm)	Diameter (mm)	Width(mm)
Area 1 top of deck top flange	150	n/a	n/a
Area 1 top of deck transverse rebar square	109	14.3/25.7	n/a
Area 3 face deck web	129	n/a	n/a
Area 3 face deck bottom flange	32	10.89	123mm
Area 3 face deck bottom side flange	68	n/a	n/a
Area 3 face deck top flange	104	n/a	n/a
Area 3 face deck distance top-bottom flange	117	n/a	n/a
Area 3.1 soffit bottom flange	34mm	n/a	n/a
Area 3.1 soffit transverse rebar square	59	15.3/28.9	n/a
Area 4 face deck top side flange	104	31.39	
Area 4 face deck web	132	n/a	n/a
Area 4 face deck bottom flange	80	n/a	n/a
Area 4 face deck bottom flange	37	8.86	n/a
Area 4.1 soffit bottom flange	47	n/a	n/a
Area 4.1 soffit transverse rebar square	51	13.5/23.6	


Area 3 beam sketch




Area 3.1 beam sketch




Area 4 beam sketch




Area 4.1 beam sketch






Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 1 top of footpath longitudinal scan	139	87	184	191




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 1 top of footpath transverse scan first layer	31	30	32	290

Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 1 top of footpath transverse I scan second layer	166	159	171	295




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 1 top of footpath transverse scan first layer 002	32	30	34	310


Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 1 top of footpath transverse scan second layer 002	159	152	164	227



Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 1 top deck longitudinal scan 001	153	n/a	n/a	n/a




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 1 top deck transverse scan 001	164	158	170	180




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 2 top of footpath longitudinal scan 001	34	34	34	1400

Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 2 top of footpath longitudinal scan 001	153	n/a	n/a	n/a




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 2 top of footpath transverse scan 001 first layer	67	57	85	385


Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 2 top of footpath transverse scan 001 second layer	116	102	138	260




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 2 top of footpath transverse scan 002	146	138	154	196




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 2 top of deck longitudinal scan 001	160	137	183	640




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 2 top of deck longitudinal scan 002	156	150	162	620



Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 2 top of deck transverse scan 001	204	144	238	405




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 3 deck face vertical scan 001	142	136	148	60




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 3 deck face horizontal scan 001	135	n/a	n/a	n/a

### Transverse Reinforcement




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 3.1 soffit longitudinal scan 001	38	28	48	249




Longitudinal I beams

Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 3.1 soffit longitudinal scan 002	42	37	48	657




Longitudinal I beams


Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 3.1 soffit transverse scan 001	46	42	55	166




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 3.1 soffit transverse scan 002	62	54	68	165




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 4 Deck Face Vertical scan 001	106	92	120	120



Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 4 Deck Face Vertical scan 001	106	92	120	120




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 4.1 Soffit longitudinal scan 001	48	42	51	666




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 4.1 Soffit longitudinal scan 002	51	42	56	707


Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 4.1 Soffit transverse scan 001	60	44	69	227




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 4.1 Soffit transverse scan 002	65	55	76	216




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 5 Abutment vertical scan 001	n/a	n/a	n/a	n/a




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 5 Abutment horizontal scan 001	n/a	n/a	n/a	n/a




Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 6 Abutment horizontal scan 001	n/a	n/a	n/a	n/a



Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 6 Abutment vertical scan 001	n/a	n/a	n/a	n/a



Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 7 Abutment vertical scan 001	n/a	n/a	n/a	n/a



Scan Location	Mean Cover (mm)	Lowest Cover (mm)	Highest Cover (mm)	Mean Spacing (mm)
Area 7 Abutment horizontal scan 001	n/a	n/a	n/a	n/a

## Photographs of breakout



Area 3 - Bottom flange 32mm



Area 3 - Bottom of side flange 68mm



Area 3 - Top side flange 105mm cover side



Area 3 - 300mm



Area 3 - Bottom flange 10.89mm



Area 3 - Bottom flange 124mm width



Area 3 - 117mm



Area 4



Area 3.1 uncovered area



Area 3.1 Soffit breakout



Cover bottom flange 34mm



Cover transverse square rebar 59mm



Transverse rebar 28.9mm



Transverse rebar 15.38mm



Spacing transverse 160mm centre



Area 4 Face deck breakout



Area 4 –top side flange cover 104mm



Area 4 - 132mm cover web



Area 4 - Cover 80mm side bottom flange



Area 4 – 37mm bottom flange



Area 4 – bottom flange 8.86



Area 4 - top flange 31.39mm



Area 4.1 soffit breakout



Area 4.1 uncovered area



Area 1 Top of deck Breakout



Cover 109mm Transverse square rebar



Transverse square rebar cover 51mm



13,5mm



23.68mm



Area 4.1 bottom flange 47mm cover



Authorised by:



James Purcell  
Structural Testing Manager  
**For and on behalf of BHP Laboratories Ltd.**

Date Issued: 26<sup>th</sup> August 2024

Test results relate only to this item.      This test report shall not be duplicated except in full and with the permission of the test laboratory
--

# Appendix E

# CHLORIDE CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F063 V1 08/07/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-1-6  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** See below  
**Test Standard:** BS 1881 Part 124

Location Reference	Sample Reference	Depth (mm)	Chloride Content % by mass of	
			Sample	Cement
Area 1 - Car 1	24/07/072-1	5-30	0.01	0.08
		30-55	0.01	0.08
		55-80	0.02	0.15
		80-105	0.01	0.08
Area 2 - Car 2	24/07/072-2	5-30	0.04	0.20
		30-55	0.03	0.15
		55-80	0.03	0.15
		80-105	0.01	0.05
Area 3 - Car 3	24/07/072-3	5-30	0.02	0.13
		30-55	0.02	0.13
		55-80	0.02	0.13
		80-105	0.02	0.13
Area 3.1 - Car 4	24/07/072-4	5-30	0.03	0.20
		30-55	0.02	0.13
		55-80	0.03	0.20
		80-105	0.03	0.20
Area 4 - Car 5	24/07/072-5	5-30	0.04	0.19
		30-55	0.02	0.10
		55-80	0.02	0.10
		80-105	0.02	0.10
Area 4.1 - Car 6	24/07/072-6	5-30	0.04	0.33
		30-55	0.03	0.25
		55-80	0.03	0.25
		80-105	0.04	0.33

**REMARKS:**  
The Chloride Content is a Acid Soluble Chloride value.  
The Chloride Content as a % by mass of cements as stated in EN 206 is a maximum allowable of 0.4% (containing embedded steel).

Approved By:	Signature:
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories  
Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie  
Issue Date: 27/08/2024  
This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CHLORIDE CONTENT OF CONCRETE TEST REPORT



BHP/MTIF/Field/F063 V1 08/07/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-7-12  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** See below  
**Test Standard:** BS 1881 Part 124

Location Reference	Sample Reference	Depth (mm)	Chloride Content % by mass of	
			Sample	Cement
Area 5 - Car 7	24/07/072-7	5-30	0.02	0.20
		30-55	0.01	0.10
		55-80	0.01	0.10
		80-105	0.01	0.10
Area 5 - Car 8	24/07/072-8	5-30	0.02	0.25
		30-55	0.01	0.13
		55-80	0.01	0.13
		80-105	0.01	0.13
Area 6 - Car 9	24/07/072-9	5-30	0.01	0.07
		30-55	0.01	0.07
		55-80	0.01	0.07
		80-105	0.01	0.07
Area 6 - Car 10	24/07/072-10	5-30	0.03	0.21
		30-55	0.03	0.21
		55-80	0.03	0.21
		80-105	0.03	0.21
Area 7 - Car 11	24/07/072-11	5-30	0.01	0.08
		30-55	0.01	0.08
		55-80	0.01	0.08
		80-105	0.01	0.08
Area 7 - Car 12	24/07/072-12	5-30	0.03	0.17
		30-55	0.03	0.17
		55-80	0.02	0.11
		80-105	0.02	0.11

## REMARKS:

The Chloride Content is a Acid Soluble Chloride value.  
The Chloride Content as a % by mass of cements as stated in EN 206 is a maxium allowable of 0.4% (containing embedded steel).

Approved By:	Signature:
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 27/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# Appendix F

# CEMENT CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F056 V1 20/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-1  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 1 - Car 1  
**Test Standard:** BS 1881 Part 124

<b>Sample Weight (g)</b>	<b>5</b>
<b>Determined Values</b>	
Insoluble residue (%)	<b>32.4</b>
Soluble silica (%)	<b>2.9</b>
Calcium oxide (%)	<b>49</b>
<b>Calculated Values</b>	
Cement Content (%)	
ex silica	<b>13.5</b>
ex lime	<b>76</b>
preferred / mean value %	<b>13.5</b>
Reported to nearest whole figure (%)	<b>13</b>
<b>Aggregate Content (%)</b>	
ex silica	<b>83.4</b>
ex lime	<b>6.6</b>
preferred / mean value	<b>83.4</b>
<b>Aggregate / Cement Ratio</b>	
ex silica	<b>6.2</b>
ex lime	<b>0.1</b>
preferred / mean value	<b>6.2</b>

## REMARKS:

The cement contents were determined in accordance with B.S. 1881:Part 124:2015+A1:2021. The silica content was determined using inductively coupled plasma optical emission spectroscopy.

Assumptions used for the cement and aggregate content calculations:

Silica content of cement (CEM I) 20.2%  
Soluble silica content of aggregate 0.5%  
Calcium oxide content of cement (CEM I) 64.5%

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CEMENT CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F056 V1 20/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-2  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 2 - Car 2  
**Test Standard:** BS 1881 Part 124

<b>Sample Weight (g)</b>	<b>9</b>
<b>Determined Values</b>	
Insoluble residue (%)	<b>15.2</b>
Soluble silica (%)	<b>4.2</b>
Calcium oxide (%)	<b>43.4</b>
<b>Calculated Values</b>	
Cement Content (%)	
ex silica	<b>19.9</b>
ex lime	<b>67.3</b>
preferred / mean value %	<b>19.9</b>
Reported to nearest whole figure (%)	<b>20</b>
<b>Aggregate Content (%)</b>	
ex silica	<b>75.5</b>
ex lime	<b>17.3</b>
preferred / mean value	<b>75.5</b>
<b>Aggregate / Cement Ratio</b>	
ex silica	<b>3.8</b>
ex lime	<b>0.3</b>
preferred / mean value	<b>3.8</b>

## REMARKS:

The cement contents were determined in accordance with B.S. 1881:Part 124:2015+A1:2021. The silica content was determined using inductively coupled plasma optical emission spectroscopy.  
Assumptions used for the cement and aggregate content calculations:  
Silica content of cement (CEM I) 20.2%  
Soluble silica content of aggregate 0.5%  
Calcium oxide content of cement (CEM I) 64.5%

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CEMENT CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F056 V1 20/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-4  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 3.1 - Car 4  
**Test Standard:** BS 1881 Part 124

<b>Sample Weight (g)</b>	<b>12</b>
<b>Determined Values</b>	
Insoluble residue (%)	<b>20.7</b>
Soluble silica (%)	<b>3.3</b>
Calcium oxide (%)	<b>40.6</b>
<b>Calculated Values</b>	
Cement Content (%)	
ex silica	<b>15.4</b>
ex lime	<b>63</b>
preferred / mean value %	<b>15.4</b>
Reported to nearest whole figure (%)	<b>15</b>
<b>Aggregate Content (%)</b>	
ex silica	<b>81</b>
ex lime	<b>22.6</b>
preferred / mean value	<b>81</b>
<b>Aggregate / Cement Ratio</b>	
ex silica	<b>5.2</b>
ex lime	<b>0.4</b>
preferred / mean value	<b>5.2</b>

## REMARKS:

The cement contents were determined in accordance with B.S. 1881:Part 124:2015+A1:2021. The silica content was determined using inductively coupled plasma optical emission spectroscopy.

Assumptions used for the cement and aggregate content calculations:

Silica content of cement (CEM I) 20.2%  
Soluble silica content of aggregate 0.5%  
Calcium oxide content of cement (CEM I) 64.5%

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CEMENT CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F056 V1 20/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-5  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 4 - Car 5  
**Test Standard:** BS 1881 Part 124

<b>Sample Weight (g)</b>	<b>17</b>
<b>Determined Values</b>	
Insoluble residue (%)	<b>10.3</b>
Soluble silica (%)	<b>4.4</b>
Calcium oxide (%)	<b>46.2</b>
<b>Calculated Values</b>	
Cement Content (%)	
ex silica	<b>21</b>
ex lime	<b>71.6</b>
preferred / mean value %	<b>21</b>
Reported to nearest whole figure (%)	<b>21</b>
<b>Aggregate Content (%)</b>	
ex silica	<b>74.1</b>
ex lime	<b>12</b>
preferred / mean value	<b>74.1</b>
<b>Aggregate / Cement Ratio</b>	
ex silica	<b>3.5</b>
ex lime	<b>0.2</b>
preferred / mean value	<b>3.5</b>

## REMARKS:

The cement contents were determined in accordance with B.S. 1881:Part 124:2015+A1:2021. The silica content was determined using inductively coupled plasma optical emission spectroscopy.

Assumptions used for the cement and aggregate content calculations:

Silica content of cement (CEM I) 20.2%  
Soluble silica content of aggregate 0.5%  
Calcium oxide content of cement (CEM I) 64.5%

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CEMENT CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F056 V1 20/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-6  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 4.1 - Car 6  
**Test Standard:** BS 1881 Part 124

<b>Sample Weight (g)</b>	<b>10</b>
<b>Determined Values</b>	
Insoluble residue (%)	<b>9.4</b>
Soluble silica (%)	<b>2.7</b>
Calcium oxide (%)	<b>46.7</b>
<b>Calculated Values</b>	
Cement Content (%)	
ex silica	<b>12.4</b>
ex lime	<b>72.4</b>
preferred / mean value %	<b>12.4</b>
Reported to nearest whole figure (%)	<b>12</b>
<b>Aggregate Content (%)</b>	
ex silica	<b>84.7</b>
ex lime	<b>11</b>
preferred / mean value	<b>84.7</b>
<b>Aggregate / Cement Ratio</b>	
ex silica	<b>6.8</b>
ex lime	<b>0.2</b>
preferred / mean value	<b>6.8</b>

## REMARKS:

The cement contents were determined in accordance with B.S. 1881:Part 124:2015+A1:2021. The silica content was determined using inductively coupled plasma optical emission spectroscopy.

Assumptions used for the cement and aggregate content calculations:

Silica content of cement (CEM I) 20.2%  
Soluble silica content of aggregate 0.5%  
Calcium oxide content of cement (CEM I) 64.5%

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CEMENT CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F056 V1 20/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-7  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 5 - Car 7  
**Test Standard:** BS 1881 Part 124

<b>Sample Weight (g)</b>	<b>12</b>
<b>Determined Values</b>	
Insoluble residue (%)	<b>18.4</b>
Soluble silica (%)	<b>2.1</b>
Calcium oxide (%)	<b>43.1</b>
<b>Calculated Values</b>	
Cement Content (%)	
ex silica	<b>9.6</b>
ex lime	<b>66.9</b>
preferred / mean value %	<b>9.6</b>
Reported to nearest whole figure (%)	<b>10</b>
<b>Aggregate Content (%)</b>	
ex silica	<b>88.2</b>
ex lime	<b>17.7</b>
preferred / mean value	<b>88.2</b>
<b>Aggregate / Cement Ratio</b>	
ex silica	<b>9.2</b>
ex lime	<b>0.3</b>
preferred / mean value	<b>9.2</b>

## REMARKS:

The cement contents were determined in accordance with B.S. 1881:Part 124:2015+A1:2021. The silica content was determined using inductively coupled plasma optical emission spectroscopy.

Assumptions used for the cement and aggregate content calculations:

Silica content of cement (CEM I) 20.2%  
Soluble silica content of aggregate 0.5%  
Calcium oxide content of cement (CEM I) 64.5%

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CEMENT CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F056 V1 20/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-8  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 5 - Car 8  
**Test Standard:** BS 1881 Part 124

<b>Sample Weight (g)</b>	<b>4</b>
<b>Determined Values</b>	
Insoluble residue (%)	<b>25.4</b>
Soluble silica (%)	<b>1.8</b>
Calcium oxide (%)	<b>37.9</b>
<b>Calculated Values</b>	
Cement Content (%)	
ex silica	<b>8</b>
ex lime	<b>58.8</b>
preferred / mean value %	<b>8</b>
Reported to nearest whole figure (%)	<b>8</b>
<b>Aggregate Content (%)</b>	
ex silica	<b>90.2</b>
ex lime	<b>27.7</b>
preferred / mean value	<b>90.2</b>
<b>Aggregate / Cement Ratio</b>	
ex silica	<b>11.3</b>
ex lime	<b>0.5</b>
preferred / mean value	<b>11.3</b>

## REMARKS:

The cement contents were determined in accordance with B.S. 1881:Part 124:2015+A1:2021. The silica content was determined using inductively coupled plasma optical emission spectroscopy.

Assumptions used for the cement and aggregate content calculations:

Silica content of cement (CEM I) 20.2%  
Soluble silica content of aggregate 0.5%  
Calcium oxide content of cement (CEM I) 64.5%

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CEMENT CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F056 V1 20/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-9  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 6 - Car 9  
**Test Standard:** BS 1881 Part 124

<b>Sample Weight (g)</b>	<b>10</b>
<b>Determined Values</b>	
Insoluble residue (%)	<b>35.2</b>
Soluble silica (%)	<b>2.9</b>
Calcium oxide (%)	<b>33</b>
<b>Calculated Values</b>	
Cement Content (%)	
ex silica	<b>13.6</b>
ex lime	<b>51.2</b>
preferred / mean value %	<b>13.6</b>
Reported to nearest whole figure (%)	<b>14</b>
<b>Aggregate Content (%)</b>	
ex silica	<b>83.3</b>
ex lime	<b>37</b>
preferred / mean value	<b>83.3</b>
<b>Aggregate / Cement Ratio</b>	
ex silica	<b>6.1</b>
ex lime	<b>0.7</b>
preferred / mean value	<b>6.1</b>

## REMARKS:

The cement contents were determined in accordance with B.S. 1881:Part 124:2015+A1:2021. The silica content was determined using inductively coupled plasma optical emission spectroscopy.  
Assumptions used for the cement and aggregate content calculations:  
Silica content of cement (CEM I) 20.2%  
Soluble silica content of aggregate 0.5%  
Calcium oxide content of cement (CEM I) 64.5%

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CEMENT CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F056 V1 20/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-10  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 6 - Car 10  
**Test Standard:** BS 1881 Part 124

<b>Sample Weight (g)</b>	<b>10</b>
<b>Determined Values</b>	
Insoluble residue (%)	<b>15.7</b>
Soluble silica (%)	<b>3</b>
Calcium oxide (%)	<b>42.1</b>
<b>Calculated Values</b>	
Cement Content (%)	
ex silica	<b>14</b>
ex lime	<b>65.3</b>
preferred / mean value %	<b>14</b>
Reported to nearest whole figure (%)	<b>14</b>
<b>Aggregate Content (%)</b>	
ex silica	<b>82.7</b>
ex lime	<b>19.7</b>
preferred / mean value	<b>82.7</b>
<b>Aggregate / Cement Ratio</b>	
ex silica	<b>5.9</b>
ex lime	<b>0.3</b>
preferred / mean value	<b>5.9</b>

## REMARKS:

The cement contents were determined in accordance with B.S. 1881:Part 124:2015+A1:2021. The silica content was determined using inductively coupled plasma optical emission spectroscopy.

Assumptions used for the cement and aggregate content calculations:

Silica content of cement (CEM I) 20.2%  
Soluble silica content of aggregate 0.5%  
Calcium oxide content of cement (CEM I) 64.5%

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CEMENT CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F056 V1 20/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-11  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 7 - Car 11  
**Test Standard:** BS 1881 Part 124

<b>Sample Weight (g)</b>	<b>9</b>
<b>Determined Values</b>	
Insoluble residue (%)	<b>19</b>
Soluble silica (%)	<b>2.5</b>
Calcium oxide (%)	<b>41.9</b>
<b>Calculated Values</b>	
Cement Content (%)	
ex silica	<b>11.7</b>
ex lime	<b>64.9</b>
preferred / mean value %	<b>11.7</b>
Reported to nearest whole figure (%)	<b>12</b>
<b>Aggregate Content (%)</b>	
ex silica	<b>85.6</b>
ex lime	<b>20.2</b>
preferred / mean value	<b>85.6</b>
<b>Aggregate / Cement Ratio</b>	
ex silica	<b>7.3</b>
ex lime	<b>0.3</b>
preferred / mean value	<b>7.3</b>

## REMARKS:

The cement contents were determined in accordance with B.S. 1881:Part 124:2015+A1:2021. The silica content was determined using inductively coupled plasma optical emission spectroscopy.

Assumptions used for the cement and aggregate content calculations:

Silica content of cement (CEM I) 20.2%  
Soluble silica content of aggregate 0.5%  
Calcium oxide content of cement (CEM I) 64.5%

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CEMENT CONTENT OF CONCRETE TEST REPORT



BHP/MTIField/F056 V1 20/05/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-12  
**Order No:** Not Supplied  
**Date Tested:** 20/08/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Dust

**Project:** Mayo Bridges Investigation - Strade River Bridge  
**Location Reference:** Area 7 - Car 12  
**Test Standard:** BS 1881 Part 124

<b>Sample Weight (g)</b>	<b>9</b>
<b>Determined Values</b>	
Insoluble residue (%)	<b>20.6</b>
Soluble silica (%)	<b>3.9</b>
Calcium oxide (%)	<b>39.4</b>
<b>Calculated Values</b>	
Cement Content (%)	
ex silica	<b>18.4</b>
ex lime	<b>61</b>
preferred / mean value %	<b>18.4</b>
Reported to nearest whole figure (%)	<b>18</b>
<b>Aggregate Content (%)</b>	
ex silica	<b>77.4</b>
ex lime	<b>25</b>
preferred / mean value	<b>77.4</b>
<b>Aggregate / Cement Ratio</b>	
ex silica	<b>4.2</b>
ex lime	<b>0.4</b>
preferred / mean value	<b>4.2</b>

## REMARKS:

The cement contents were determined in accordance with B.S. 1881:Part 124:2015+A1:2021. The silica content was determined using inductively coupled plasma optical emission spectroscopy.  
Assumptions used for the cement and aggregate content calculations:  
Silica content of cement (CEM I) 20.2%  
Soluble silica content of aggregate 0.5%  
Calcium oxide content of cement (CEM I) 64.5%

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date: 21/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# Appendix G

**CORROSION POTENTIAL ASSESSMENT OF STEEL  
REINFORCEMENT BY HALF CELL TESTING  
TEST REPORT**



BHP/MTIField/F057 V1 21/05/24


**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-1  
**Order No:** Not Supplied  
**Date Tested:** 12/07/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Deck

**Project:** Mayo Bridges - Strade River Bridge  
**Location Reference:** Area 1 C1 Deck  
**Test Standard:** ASTM C876

Test No.	1
No. of Readings	12
Median (mV)	-245
Mean (mV)	-239
Standard Deviation	19.8
Lowest (mV)	-268
Highest (mV)	-207
Reinforcement Condition	Intermediate Risk of Corrosion

**Graphical Representation of Measured Potential Field of Concrete Concrete Deck**



**REMARKS:**

This test was performed using a Copper-Copper Sulphate Electrode.

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date:

14/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CORROSION POTENTIAL ASSESSMENT OF STEEL REINFORCEMENT BY HALF CELL TESTING TEST REPORT




BHP/MTIField/F057 V1 21/05/24

<b>Client:</b>	TRIUR Construction Ltd 13 Society Street Ballinasloe Galway	<b>BHP Ref. No.:</b>	24/07/072-2
		<b>Order No:</b>	Not Supplied
		<b>Date Tested:</b>	12/07/2024
		<b>Test Specification:</b>	Customer Spec.
<b>FAO:</b>	Lurcan Donnellan	<b>Test Element:</b>	Concrete Deck

**Project:** Mayo Bridges - Strade River Bridge  
**Location Reference:** Area 3 Face Deck  
**Test Standard:** ASTM C876

Test No.	2
No. of Readings	15
Median (mV)	-49
Mean (mV)	-54.9
Standard Deviation	21
Lowest (mV)	-97
Highest (mV)	-27
Reinforcement Condition	Low risk of Corrosion

**Graphical Representation of Measured Potential Field of Concrete Concrete Deck**



**REMARKS:**

This test was performed using a Copper-Copper Sulphate Electrode.

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories

Issue Date:

14/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CORROSION POTENTIAL ASSESSMENT OF STEEL REINFORCEMENT BY HALF CELL TESTING TEST REPORT




BHP/MTIField/F057 V1 21/05/24

<b>Client:</b>	TRIUR Construction Ltd 13 Society Street Ballinasloe Galway	<b>BHP Ref. No.:</b>	24/07/072-3
		<b>Order No:</b>	Not Supplied
		<b>Date Tested:</b>	12/07/2024
<b>FAO:</b>	Lurcan Donnellan	<b>Test Specification:</b>	Customer Spec.
		<b>Test Element:</b>	Concrete Deck

**Project:** Mayo Bridges - Strade River Bridge  
**Location Reference:** Area 3.1 Soffit  
**Test Standard:** ASTM C876

Test No.	3
No. of Readings	12
Median (mV)	-335
Mean (mV)	-333.5
Standard Deviation	13.2
Lowest (mV)	-368
Highest (mV)	-320
Reinforcement Condition	Intermediate Risk of Corrosion



**REMARKS:**  
This test was performed using a Copper-Copper Sulphate Electrode.

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories Issue Date: 14/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# CORROSION POTENTIAL ASSESSMENT OF STEEL REINFORCEMENT BY HALF CELL TESTING TEST REPORT




BHP/MTIField/F057 V1 21/05/24

<b>Client:</b>	TRIUR Construction Ltd 13 Society Street Ballinasloe Galway	<b>BHP Ref. No.:</b>	24/07/072-4
		<b>Order No:</b>	Not Supplied
		<b>Date Tested:</b>	12/07/2024
<b>FAO:</b>	Lurcan Donnellan	<b>Test Specification:</b>	Customer Spec.
		<b>Test Element:</b>	Concrete Deck

**Project:** Mayo Bridges - Strade River Bridge  
**Location Reference:** Area 4 Face Deck  
**Test Standard:** ASTM C876

Test No.	4
No. of Readings	12
Median (mV)	-233
Mean (mV)	-237.7
Standard Deviation	28.3
Lowest (mV)	-283
Highest (mV)	-198
Reinforcement Condition	Intermediate Risk of Corrosion



**REMARKS:**  
 This test was performed using a Copper-Copper Sulphate Electrode.

<b>Approved By:</b>	<b>Signature:</b>
Lukasz Zalewski Field Service Manager	

For and On Behalf of BHP Laboratories Issue Date: 14/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

**CORROSION POTENTIAL ASSESSMENT OF STEEL  
REINFORCEMENT BY HALF CELL TESTING  
TEST REPORT**



BHP/MTIField/F057 V1 21/05/24


**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-5  
**Order No:** Not Supplied  
**Date Tested:** 12/07/2024  
**Test Specification:** Customer Spec.  
**Test Element:** Concrete Deck

**Project:** Mayo Bridges - Strade River Bridge  
**Location Reference:** Area 4.1 Soffit  
**Test Standard:** ASTM C876

Test No.	5
No. of Readings	16
Median (mV)	-170
Mean (mV)	-165.8
Standard Deviation	13
Lowest (mV)	-179
Highest (mV)	-129
Reinforcement Condition	Low risk of Corrosion

**Graphical Representation of Measured Potential Field of Concrete Concrete Deck**



**REMARKS:**

This test was performed using a Copper-Copper Sulphate Electrode.

**Approved By:**

Lukasz Zalewski  
Field Service Manager

**Signature:**

For and On Behalf of BHP Laboratories

Issue Date:

14/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# DETERMINATION OF RESISTIVITY OF CONCRETE



BHP/MTIField/F048 V1 30/04/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-1  
**Order No:** Not Supplied  
**Date Tested:** 09/07/2024  
**Test Specification:** Client Spec.  
**Material:** Concrete Element

**Project:** Mayo Bridges - Strade River Bridge  
**Location Reference:** Area 1 Top Deck  
**Test Standard:** EN 12390-19 2021

RESULTS				
Structural Element	Deck			
Measurement Mode	Surface			
Contact Spacing	50mm			
Specimen Shape	Flat			
Dimensions of Test Area (mm)	400x400			
Minimum Measurement (kΩcm)	106			
Maximum Measurement (kΩcm)	190			
Mean Value (kΩcm)	153			
Interpretation of Result	Negligible risk of corrosion			
Resistivity Measurements (kΩcm)				
106	112	172	185	190
0	0	0	0	0
0	0	0	0	0

## REMARKS:

Resistivity measurements can be used to estimate the likelihood of corrosion. When the electrical resistivity of the concrete is low, the likelihood of corrosion increases. When the electrical resistivity is high, the likelihood of corrosion decreases.

A guide to interpretation of resistivity results is:

When $\geq 100$ kΩcm	Negligible risk of corrosion
When 50 to 100 kΩcm	Low risk of corrosion
When 10 to 50 kΩcm	Moderate risk of corrosion
When $\leq 10$ kΩcm	High risk of corrosion

Equipment used was a Proceq Resipod

**Approved By:**

**Signature:**

Lukasz Zalewski  
Field Service Manager

For and On Behalf of BHP Laboratories

Issue Date:

28/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# DETERMINATION OF RESISTIVITY OF CONCRETE



BHP/MTIField/F048 V1 30/04/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-3  
**Order No:** Not Supplied  
**Date Tested:** 09/07/2024  
**Test Specification:** Client Spec.  
**Material:** Concrete Element

**Project:** Mayo Bridges - Strade River Bridge  
**Location Reference:** Area 3 Face dek  
**Test Standard:** EN 12390-19 2021

RESULTS				
Structural Element		Soffit		
Measurement Mode		Surface		
Contact Spacing		50mm		
Specimen Shape		Flat		
Dimensions of Test Area (mm)		200x200		
Minimum Measurement (kΩcm)		55		
Maximum Measurement (kΩcm)		72		
Mean Value (kΩcm)		65		
Interpretation of Result		Negligible risk of corrosion		
Resistivity Measurements (kΩcm)				
69	55	72	0	0
0	0	0	0	0
0	0	0	0	0

## REMARKS:

Resistivity measurements can be used to estimate the likelihood of corrosion. When the electrical resistivity of the concrete is low, the likelihood of corrosion increases. When the electrical resistivity is high, the likelihood of corrosion decreases.

A guide to interpretation of resistivity results is:

When $\geq 100$ kΩcm	Negligible risk of corrosion
When 50 to 100 kΩcm	Low risk of corrosion
When 10 to 50 kΩcm	Moderate risk of corrosion
When $\leq 10$ kΩcm	High risk of corrosion

Equipment used was a Proceq Resipod

**Approved By:**

**Signature:**

Lukasz Zalewski  
Field Service Manager

For and On Behalf of BHP Laboratories

Issue Date:

28/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# DETERMINATION OF RESISTIVITY OF CONCRETE



BHP/MTIField/F048 V1 30/04/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-4  
**Order No:** Not Supplied  
**Date Tested:** 09/07/2024  
**Test Specification:** Client Spec.  
**Material:** Concrete Element

**Project:** Mayo Bridges - Strade River Bridge  
**Location Reference:** Area 3.1 Soffit  
**Test Standard:** EN 12390-19 2021

RESULTS				
Structural Element		Soffit		
Measurement Mode		Surface		
Contact Spacing		50mm		
Specimen Shape		Flat		
Dimensions of Test Area (mm)		400x400		
Minimum Measurement (kΩcm)		256		
Maximum Measurement (kΩcm)		303		
Mean Value (kΩcm)		279		
Interpretation of Result		Negligible risk of corrosion		
Resistivity Measurements (kΩcm)				
285	278	303	256	272
0	0	0	0	0
0	0	0	0	0

## REMARKS:

Resistivity measurements can be used to estimate the likelihood of corrosion. When the electrical resistivity of the concrete is low, the likelihood of corrosion increases. When the electrical resistivity is high, the likelihood of corrosion decreases.

A guide to interpretation of resistivity results is:

When $\geq 100$ kΩcm	Negligible risk of corrosion
When 50 to 100 kΩcm	Low risk of corrosion
When 10 to 50 kΩcm	Moderate risk of corrosion
When $\leq 10$ kΩcm	High risk of corrosion

Equipment used was a Proceq Resipod

**Approved By:**

**Signature:**

Lukasz Zalewski  
Field Service Manager

For and On Behalf of BHP Laboratories

Issue Date:

28/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# DETERMINATION OF RESISTIVITY OF CONCRETE



BHP/MTIField/F048 V1 30/04/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-5  
**Order No:** Not Supplied  
**Date Tested:** 09/07/2024  
**Test Specification:** Client Spec.  
**Material:** Concrete Element

**Project:** Mayo Bridges - Strade River Bridge  
**Location Reference:** Area 4  
**Test Standard:** EN 12390-19 2021

RESULTS				
Structural Element		Face Deck		
Measurement Mode		Surface		
Contact Spacing		50mm		
Specimen Shape		Flat		
Dimensions of Test Area (mm)		200x200		
Minimum Measurement (kΩcm)		156		
Maximum Measurement (kΩcm)		194		
Mean Value (kΩcm)		179		
Interpretation of Result		Negligible risk of corrosion		
Resistivity Measurements (kΩcm)				
186	156	194	0	0
0	0	0	0	0
0	0	0	0	0

## REMARKS:

Resistivity measurements can be used to estimate the likelihood of corrosion. When the electrical resistivity of the concrete is low, the likelihood of corrosion increases. When the electrical resistivity is high, the likelihood of corrosion decreases.

A guide to interpretation of resistivity results is:

When $\geq 100$ kΩcm	Negligible risk of corrosion
When 50 to 100 kΩcm	Low risk of corrosion
When 10 to 50 kΩcm	Moderate risk of corrosion
When $\leq 10$ kΩcm	High risk of corrosion

Equipment used was a Proceq Resipod

**Approved By:**

**Signature:**

Lukasz Zalewski  
Field Service Manager

For and On Behalf of BHP Laboratories

Issue Date:

28/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# DETERMINATION OF RESISTIVITY OF CONCRETE



BHP/MTIField/F048 V1 30/04/24

**Client:** TRIUR Construction Ltd  
13 Society Street  
Ballinasloe  
Galway  
**FAO:** Lurcan Donnellan

**BHP Ref. No.:** 24/07/072-6  
**Order No:** Not Supplied  
**Date Tested:** 09/07/2024  
**Test Specification:** Client Spec.  
**Material:** Concrete Element

**Project:** Mayo Bridges - Strade River Bridge  
**Location Reference:** Area 4.1  
**Test Standard:** EN 12390-19 2021

RESULTS				
Structural Element		Face Deck		
Measurement Mode		Surface		
Contact Spacing		50mm		
Specimen Shape		Flat		
Dimensions of Test Area (mm)		400x400		
Minimum Measurement (kΩcm)		196		
Maximum Measurement (kΩcm)		272		
Mean Value (kΩcm)		228		
Interpretation of Result		Negligible risk of corrosion		
Resistivity Measurements (kΩcm)				
196	206	209	255	272
0	0	0	0	0
0	0	0	0	0

## REMARKS:

Resistivity measurements can be used to estimate the likelihood of corrosion. When the electrical resistivity of the concrete is low, the likelihood of corrosion increases. When the electrical resistivity is high, the likelihood of corrosion decreases.

A guide to interpretation of resistivity results is:

When $\geq 100$ kΩcm	Negligible risk of corrosion
When 50 to 100 kΩcm	Low risk of corrosion
When 10 to 50 kΩcm	Moderate risk of corrosion
When $\leq 10$ kΩcm	High risk of corrosion

Equipment used was a Proceq Resipod

**Approved By:**

**Signature:**

Lukasz Zalewski  
Field Service Manager

For and On Behalf of BHP Laboratories

Issue Date:

28/08/2024

Tested by BHP Laboratories, New Road, Thomondgate, Limerick. Phone: (061) 455399 Email: jamespurcell@bhp.ie

This test report shall not be duplicated in full without the permission of the test laboratory. Information identifying the 'Client', 'FAO', 'Project', 'Location Reference', 'Item', 'Test Specification' and 'Order No' has been provided by the customer. Results apply only to the sample tested and where the laboratory is not responsible for sampling, result apply to the sample as received. Sampling is outside the scope of accreditation.

# Appendix F. Structure Idealisation Model and Model Inputs




Figure F-1 – 3D Isometric view of the proposed model




Figure F-2 – Top view of the model with support conditions






Figure F-3 – Live load Surface lanes




# Appendix G. Calculations






	Project	TO315 Mayo Bridges - Assessments			Job ref 10088572	
	Part of Structure	Strade River Bridge MO-N58-001.00			Calc sheet no. rev 0	
	Drawing Ref	Calc By VP	Date 17-Dec-24	Check by MG	Date 17/12/2024	
Ref	Calculations				Output	
1 Introduction	1.1 Spreadsheet Purpose Stage 2 Assessment Calculations of Filler Beam Bridge.					
1.2 Limitations	There is no clear Data about the Foundation of the structure.					
2 Instructions for use	2.1 The Assessment is based on TII Publications AM-STR-06056 Stage 1 Structural Assessment of Road Structures and AM-STR-06057 The Stage 2 Structural Assessment of Sub-Standard Road Structures. Initial assessments of concrete composite decks were carried out using the strip method analysis as per AM-STR-06026 and AM-STR-06037. Assessment live loading comprised 40t HA loading in accordance with TII Publication AM-STR-06026.					
3 Updates	3.1 Previous Updates					
Revision    Date    Made By    Checked    Description						
R0    17-Dec-24    VP    MG						
3.2 Planned/Suggested updates	Date suggested    Made By    Description					


	Project Name				Job Number	
	TO315 Mayo Bridges - Assessments				10088572	
	Part of Structure				Sheet Number	Rev.
	Strade River Bridge MO-N58-001.00				of	0
			Originator	Date	Checker	Date
		VP	Dec-24	MG	Dec-24	
	Contents					
	<div>1 General</div> <div>2 Introduction</div> <div>3 Material parameters</div> <div>4 Grillage Analysis</div> <div>5 Load Calculation</div> <div>6 Investigation Summary</div> <div>7 Filler Beam Capacity</div> <div>8 Composite Section Properties</div> <div>9 Check bond stress of section</div> <div>10 Grillage Analysis Results Diagram</div>					




<div>AtkinsRéalis</div>	Project Name TO315 Mayo Bridges - Assessments			Job Number 10088572																																														
	Part of Structure Strade River Bridge MO-N58-001.00			Sheet Number of	Rev.																																													
	Drawing Reference	Originator VP	Date Dec-24	Checker MG	Date Dec-24																																													
AM-STR-06030 Table 1	<div>Partial Safety Factors</div> <p>For concrete, the values of <math>\gamma_m</math> is taken as 1.2 considering worst credible strengths which is taken from Table 4A (4.3.3.3.) of AM-STR-06031 . For Structural steel the <math>\gamma_m</math> is taken as 1.05. The partial safety factors taken from AM-STR-06030 Table 1 are represented below.</p> <div>Partial Safety Factors for Assessment</div> <table><tr><th>Load</th><th><math>\gamma_f</math> for ULS</th><th><math>\gamma_L</math> for ULS</th></tr><tr><td>Dead Load</td><td>1.1</td><td>1.15</td></tr><tr><td>Super Imposed Dead Load</td><td>1.1</td><td>1.75</td></tr><tr><td>Soil Fill</td><td>1.1</td><td>1.2</td></tr><tr><td>Type HA Loading</td><td>1.1</td><td>1.5</td></tr><tr><td>Type HB</td><td>1.1</td><td>1.3</td></tr><tr><td>SV 196</td><td>1.1</td><td>1.1</td></tr></table>					Load	$\gamma_f$ for ULS	$\gamma_L$ for ULS	Dead Load	1.1	1.15	Super Imposed Dead Load	1.1	1.75	Soil Fill	1.1	1.2	Type HA Loading	1.1	1.5	Type HB	1.1	1.3	SV 196	1.1	1.1																								
Load	$\gamma_f$ for ULS	$\gamma_L$ for ULS																																																
Dead Load	1.1	1.15																																																
Super Imposed Dead Load	1.1	1.75																																																
Soil Fill	1.1	1.2																																																
Type HA Loading	1.1	1.5																																																
Type HB	1.1	1.3																																																
SV 196	1.1	1.1																																																
4	<div>Grillage Analysis - 3D Model of Box</div> <p>Since the structure failed in the initial assessment, we created a grillage analysis for accurate bending results.</p> <div><div><div>3D Grillage Model</div></div><div><div>Composite Section property-Filler Beam</div></div></div>																																																	
5	<div>Load Calculation</div> <div>Dead Load</div> <p>Sections are defined in Midas and material property are defined .Self Weight is applied in the Midas.</p> <div>Soil Fill</div> <table><tr><td>Unit Weight of Soil Fill</td><td>=</td><td>20.0</td><td>kN/m3</td></tr><tr><td>Depth of infill material</td><td>=</td><td>0.15</td><td>m</td></tr><tr><td>Load per meter square</td><td>=</td><td>3.00</td><td>kN/m2</td></tr><tr><td>Average width of the Beam</td><td>=</td><td>0.60</td><td>m</td></tr><tr><td>Load per beam</td><td>=</td><td>1.8</td><td>kN/m2</td></tr></table> <div></div> <div>SIDL -Surfacing</div> <table><tr><td>Surfacing depth</td><td>100 mm thick</td><td>=</td><td>1.00</td><td>x</td><td>0.1</td><td>x</td><td>1</td><td>x</td><td>24.0</td></tr><tr><td>Weight of Surfacing - Load per meter square</td><td></td><td>=</td><td>2.40</td><td>kN/m2</td></tr><tr><td>Average width of the Beam</td><td></td><td>=</td><td>0.60</td><td>m</td></tr><tr><td>Load per beam</td><td></td><td>=</td><td>1.44</td><td>kN/m2</td></tr></table>					Unit Weight of Soil Fill	=	20.0	kN/m3	Depth of infill material	=	0.15	m	Load per meter square	=	3.00	kN/m2	Average width of the Beam	=	0.60	m	Load per beam	=	1.8	kN/m2	Surfacing depth	100 mm thick	=	1.00	x	0.1	x	1	x	24.0	Weight of Surfacing - Load per meter square		=	2.40	kN/m2	Average width of the Beam		=	0.60	m	Load per beam		=	1.44	kN/m2
Unit Weight of Soil Fill	=	20.0	kN/m3																																															
Depth of infill material	=	0.15	m																																															
Load per meter square	=	3.00	kN/m2																																															
Average width of the Beam	=	0.60	m																																															
Load per beam	=	1.8	kN/m2																																															
Surfacing depth	100 mm thick	=	1.00	x	0.1	x	1	x	24.0																																									
Weight of Surfacing - Load per meter square		=	2.40	kN/m2																																														
Average width of the Beam		=	0.60	m																																														
Load per beam		=	1.44	kN/m2																																														

	Project Name TO315 Mayo Bridges - Assessments			Job Number 10088572	
	Part of Structure Strade River Bridge MO-N58-001.00			Sheet Number of	Rev.
	Drawing Reference	Originator VP	Date Dec-24	Checker MG	Date Dec-24
	<p><b>Live Load</b></p> <p>Carriageway width = 6.89 m</p> <p>Number of Notional Lanes = 2</p> <p>The loading to be applied for a Stage 2 Structural Assessment shall be in accordance with the requirements of Chapter 5 of AM-STR-06026.Reduction factors for uniformly distributed load (UDL) and knife-edge load (KEL) shall be in accordance with Chapter 5 of AM-STR-06026 unless otherwise agreed with TII.</p> <p>For a Stage 2 Structural Assessment it is important to establish what component of the loading contributes most to the overall load effect. Therefore, load combinations shall be included for dead load, superimposed dead load and live load in isolation as well as in combination.</p> <p>The Live Load are Defined in the Midas Civil for the Following Cases.</p> <p>Additional cases will be added according to the requirements.</p> <ul style="list-style-type: none"> <li>i ) Type HA 40t</li> <li>ii ) Type HA + HB Combined</li> <li>iii ) Type HB 45 units</li> <li>iv ) SV 196</li> </ul> <div data-bbox="604 952 1556 1564">  </div> <p>Line lane Defined in Midas Civil for Live Load</p>				



	Project TO315 Mayo Bridges - Assessments			Job ref 10088572																																																													
	Part of Structure Strade River Bridge MO-N58-001.00			Calc sheet no. rev 1 0																																																													
	Drawing Ref Strade River Bridge M	Calc By VP	Date 17-Dec-24	Check by MG	Date 18-Dec-24																																																												
	Ref			Calculations																																																													
Output																																																																	
App.C2 SI Report	<b>CALCULATION OF WORST CREDIBLE STRENGTH</b>																																																																
	Input a maximum of 11 Core samples																																																																
	<table><thead><tr><th>LOCATION</th><th>CORE REFERENCE</th><th>ESTIMATED IN-SITU CUBE STRENGTH N/mm<sup>2</sup> (f<sub>c</sub>)</th><th>(f<sub>c</sub> - MEAN)<sup>2</sup></th></tr></thead><tbody><tr><td></td><td>C1</td><td>18.9</td><td>315.95</td></tr><tr><td></td><td>C2</td><td>21.1</td><td>242.58</td></tr><tr><td></td><td>C3</td><td>49.6</td><td>167.06</td></tr><tr><td></td><td>C4</td><td>57.1</td><td>417.18</td></tr><tr><td></td><td></td><td></td><td>-</td></tr><tr><td></td><td></td><td></td><td>-</td></tr><tr><td></td><td></td><td></td><td>-</td></tr><tr><td></td><td></td><td></td><td>-</td></tr><tr><td></td><td></td><td></td><td>-</td></tr><tr><td></td><td></td><td></td><td>-</td></tr><tr><td colspan="2">TOTAL</td><td>146.7</td><td>1142.7675</td></tr><tr><td colspan="2">No of cores</td><td>4</td><td></td></tr><tr><td colspan="2">MEAN</td><td>36.68</td><td></td></tr><tr><td colspan="2">Standard Deviation</td><td>19.52</td><td></td></tr></tbody></table>					LOCATION	CORE REFERENCE	ESTIMATED IN-SITU CUBE STRENGTH N/mm <sup>2</sup> (f <sub>c</sub> )	(f <sub>c</sub> - MEAN) <sup>2</sup>		C1	18.9	315.95		C2	21.1	242.58		C3	49.6	167.06		C4	57.1	417.18				-				-				-				-				-				-	TOTAL		146.7	1142.7675	No of cores		4		MEAN		36.68		Standard Deviation		19.52	
	LOCATION	CORE REFERENCE	ESTIMATED IN-SITU CUBE STRENGTH N/mm <sup>2</sup> (f <sub>c</sub> )	(f <sub>c</sub> - MEAN) <sup>2</sup>																																																													
		C1	18.9	315.95																																																													
		C2	21.1	242.58																																																													
		C3	49.6	167.06																																																													
		C4	57.1	417.18																																																													
				-																																																													
				-																																																													
				-																																																													
				-																																																													
				-																																																													
				-																																																													
	TOTAL		146.7	1142.7675																																																													
No of cores		4																																																															
MEAN		36.68																																																															
Standard Deviation		19.52																																																															
WCS will be calculated using 2 different methods:																																																																	
1) LOCATION : Using equation from BA 44/96 with n = total number of core samples																																																																	
Note - only use this for cores taken at the location of interest																																																																	
n = 4																																																																	
From BA 44/90,    WCS = (Total f <sub>c</sub> *(100-(20/n^0.5)))/100n																																																																	
WCS =				33.0 N/mm <sup>2</sup>																																																													
2) LOWEST CORE STRENGTH :																																																																	
Lowest core strength =				18.9 N/mm2																																																													
WCS =				18.9 N/mm <sup>2</sup>																																																													
Using the above results and engineering judgement, the proposed WCS = 18.9 N/mm <sup>2</sup>																																																																	



Ref

7

Filler Beam Capacity

SAGGING - SECTION PROPERTIES (Using BS 5400 Part 3;2000) for composite section

Slab		Width (mm)	Depth (mm)		f <sub>cu</sub> (MPa)	E(short Term)	Panel Length (mm)	Section depth mm	123
	Slab	600	309		18.9	25.1			
Haunch		Width (mm)	Depth (mm)		f <sub>cu</sub> (MPa)	E(short Term)	NA		
	Haunch	0	0		0	0	NA		
Girder		Width (mm)	Depth (mm)		f <sub>y</sub> (MPa)	E (GPa)	m	8.17	
	Top Flange	65	28		230	205.0			
	Web	10	85		230	205.0			
	Bottom Flange	123	10		230	205.0			

Bottom Cover37mm

e) Plastic Section Properties

nb if NA lies below the web this doesn't work

Stress in concrete = 0.4\*f<sub>cu</sub>

Stress in steel = σ<sub>y</sub>/γ<sub>m</sub>

γ<sub>m</sub> = 1.05

Condition factor for RC Filler-0.8

	Depth (mm)	Width (mm)	Area (mm <sup>2</sup> )	Stress (Nmm <sup>-2</sup> )	Force (kN)	Force above NA (kN)	Force below NA (kN)	y above NA (mm)	y below NA (mm)
Slab*	148.75	600	89250	8	675	675	-	81	-
Haunch	0	0	0	0	0	0	-	0	-
Top Flange	28	65	1820	219	399	90	309	3	11
Web	85	10	850	219	186	0	186	-22	64
Bottom Flange	10	123	1230	219	269	-	269	-	112

\*Concrete above beam only taken in properties

NA lies in Top Flange

Depth of Neutral Axis From Top Slab

	Depth (mm)
Slab	0.0
Haunch	0.0
Top Flange	155.1
Web	0.0

m=0.0

Concrete M<sub>plastic</sub> = 54 kNm

Single Beam M<sub>plastic</sub> = 37 kNm

Depth of Plastic NA = 155.1153.7

f) Compactness Check

If m < 0.5Check web depth is less than(34t<sub>w</sub>/m)\*(355/σ<sub>yw</sub>)^0.5n/ammmn/a

If m > 0.5Check web depth is less than(374t<sub>w</sub>/(13m-1))\*(355/σ<sub>yw</sub>)^0.5n/ammmn/a

If web fully in tension section is compactyes

Section is Compact

SAGGING - PLASTIC CHECKS (Using BS 5400 Part 3;2000)

2. ULS Bending Capacity of Section

M<sub>plastic</sub> = 100 kNm

M<sub>pe (unfactored)</sub> = 105 kNm

M<sub>D</sub> = M<sub>pe</sub> / 1.05 x 1.1 = 73 kNm (Also Adjusted by condition factor)

3. ULS Pure Shear Capacity of Section

Depth of panel = d<sub>we</sub> = 85 mm

Aspect Ratio = φ = a/d<sub>we</sub> = 1.000

b<sub>fe</sub> (top flange) = 0b<sub>fe</sub> (bottom flange) = 0

m<sub>fw</sub> (top flange) = σ<sub>yf</sub>b<sub>fe</sub>t<sub>f</sub><sup>2</sup>/(2d<sub>we</sub><sup>2</sup>t<sub>w</sub>σ<sub>yw</sub>) = 0.1763m<sub>fw</sub>(bot) = σ<sub>yf</sub>b<sub>fe</sub>t<sub>f</sub><sup>2</sup>/(2d<sub>we</sub><sup>2</sup>t<sub>w</sub>σ<sub>yw</sub>) = 0.0426

Minimum value of m<sub>fw</sub> for use in shear calcs. = 0.0426λ = (d<sub>we</sub>/t<sub>w</sub>)x(σ<sub>yw</sub>/355)<sup>1/2</sup> = 6.8


τ<sub>y</sub> = σ<sub>yw</sub>/√3 = 132.79


3/Fig12-18τ<sub>I</sub>/T<sub>y</sub> for m<sub>fw</sub> of 0.0426 = 1.295T<sub>I</sub> = 171.95


τ<sub>I</sub>/T<sub>y</sub> for m<sub>fw</sub> of 0.000 = 1.295T<sub>I</sub> = 171.95


3/9.9.2.2V<sub>D</sub> = (d<sub>w</sub>t<sub>w</sub>xT<sub>I</sub>) / (γ<sub>m</sub>γ<sub>f3</sub>) = 101.2 kNWhen m<sub>fw</sub> = 0.1763 (Adjusted by condition factor)


V<sub>R</sub> = "" = 101.2 kNWhen m<sub>fw</sub> = 0.0000 (Adjusted by condition factor)



	Project			TO315 Mayo Bridges - Assessments		Job ref 10088572																																																								
	Part of Structure Strade River Bridge MO-N58-001.00		Assessment using AM-STR-06026 Beam		Filler		Calc sheet no. rev 5 0																																																							
	Drawing Ref		Calc By VP		Date 17-Dec-24		Check by Date MG 18-Dec-24																																																							
Ref	Calculations						Output																																																							
BD21/01 AM-STR-06026	<b>Slab Details :</b> Filler Beam <table><tr><td>Depth of slab</td><td>(mm)</td><td>309</td></tr><tr><td>Clear Span</td><td>(m)</td><td>3.81</td></tr><tr><td>Effective Span</td><td>(m)</td><td>4.08</td></tr><tr><td>Slab width</td><td>(mm)</td><td>600</td></tr><tr><td>Total Depth of fill above Filler Slab</td><td>(mm)</td><td>250</td></tr><tr><td>Depth of surfacing</td><td>(mm)</td><td>100</td></tr><tr><td>Condition factor for RC Slab</td><td>-</td><td>0.80</td></tr></table> ( Significant section loss and Corrosion )						Depth of slab	(mm)	309	Clear Span	(m)	3.81	Effective Span	(m)	4.08	Slab width	(mm)	600	Total Depth of fill above Filler Slab	(mm)	250	Depth of surfacing	(mm)	100	Condition factor for RC Slab	-	0.80																																			
Depth of slab							(mm)	309																																																						
Clear Span							(m)	3.81																																																						
Effective Span							(m)	4.08																																																						
Slab width							(mm)	600																																																						
Total Depth of fill above Filler Slab							(mm)	250																																																						
Depth of surfacing							(mm)	100																																																						
Condition factor for RC Slab							-	0.80																																																						
CI 5.3.1.1 of BD44/95 AM-STR-06031																																																														
SI Report	<b>Material Details :</b> <table><tr><td rowspan="3">Main Tension Steel</td><td>Beam Depth</td><td>(mm)</td><td>123</td></tr><tr><td>Spacing</td><td>(mm)</td><td>600</td></tr><tr><td>As</td><td>(mm2)</td><td>4720</td></tr><tr><td colspan="2">Concrete cover to tension steel</td><td>(mm)</td><td>37</td></tr><tr><td colspan="2">Secondary reinforcement dia</td><td>(mm)</td><td>0</td></tr><tr><td colspan="2">Is tension steel the outer layer of rebar?</td><td>Y/N</td><td>Y</td></tr><tr><td>effective depth</td><td>d</td><td>(mm)</td><td>272</td></tr><tr><td>Concrete Density</td><td></td><td>kN/m3</td><td>25.0</td></tr><tr><td>Surfacing Density</td><td></td><td>kN/m3</td><td>24.0</td></tr><tr><td>Fill Density</td><td></td><td>kN/m3</td><td>20.0</td></tr><tr><td>Concrete WCS Strength</td><td>WCS, fcu</td><td></td><td>19</td></tr><tr><td>Steel Characteristic Strength</td><td>fy</td><td>(N/mm2)</td><td>230</td></tr><tr><td>Material Factor for Concrete</td><td>Ymc</td><td></td><td>1.20</td></tr><tr><td>Material Factor for Steel</td><td>Yms</td><td></td><td>1.05</td></tr></table>						Main Tension Steel	Beam Depth	(mm)	123	Spacing	(mm)	600	As	(mm2)	4720	Concrete cover to tension steel		(mm)	37	Secondary reinforcement dia		(mm)	0	Is tension steel the outer layer of rebar?		Y/N	Y	effective depth	d	(mm)	272	Concrete Density		kN/m3	25.0	Surfacing Density		kN/m3	24.0	Fill Density		kN/m3	20.0	Concrete WCS Strength	WCS, fcu		19	Steel Characteristic Strength	fy	(N/mm2)	230	Material Factor for Concrete	Ymc		1.20	Material Factor for Steel	Yms		1.05	Filler Beam Moment Capacity 72.8 kNm	
Main Tension Steel	Beam Depth	(mm)	123																																																											
	Spacing	(mm)	600																																																											
	As	(mm2)	4720																																																											
Concrete cover to tension steel		(mm)	37																																																											
Secondary reinforcement dia		(mm)	0																																																											
Is tension steel the outer layer of rebar?		Y/N	Y																																																											
effective depth	d	(mm)	272																																																											
Concrete Density		kN/m3	25.0																																																											
Surfacing Density		kN/m3	24.0																																																											
Fill Density		kN/m3	20.0																																																											
Concrete WCS Strength	WCS, fcu		19																																																											
Steel Characteristic Strength	fy	(N/mm2)	230																																																											
Material Factor for Concrete	Ymc		1.20																																																											
Material Factor for Steel	Yms		1.05																																																											
Page 1 Cl. 4.4 of BD21 Table 4A of BD44/95 AM-STR-06031	<b>Calculation of Moment Capacity of Section at Mid Span :</b> <table><tr><td>=&gt;</td><td>xu</td><td>(mm)</td><td>155.1</td></tr><tr><td>M. Capacity</td><td>M<sub>c</sub></td><td>(kNm/m)</td><td>73</td></tr></table>						=>	xu	(mm)	155.1	M. Capacity	M <sub>c</sub>	(kNm/m)	73	Slab Shear Capacity At 2d 101.2 kN/m At d 101.2 kN/m																																															
=>	xu	(mm)	155.1																																																											
M. Capacity	M <sub>c</sub>	(kNm/m)	73																																																											
Table 4A of BD44/95 AM-STR-06031	<b>Calculation of Shear Capacity of Section near supports :</b> <p>Shear checked at 2 locations (i) a<sub>v</sub> = d from face of support (with shear enhancement if applicable) (ii) a<sub>v</sub> = 2d from face of support (without shear enhancement)</p> <table><tr><td>100As/b<sub>w</sub>d</td><td>-</td><td>-</td><td>2.9</td></tr><tr><td>Depth Factor</td><td>ξ<sub>s</sub></td><td>-</td><td>1.19</td></tr><tr><td>Material FOS for Concrete in Shear</td><td>Ymc</td><td></td><td>1.15</td></tr><tr><td>Ultimate shear stress</td><td>vc</td><td>(N/mm2)</td><td>0.784</td></tr><tr><td>Shear link diameter</td><td>dia.</td><td>mm</td><td>0</td></tr><tr><td>No. Legs</td><td>-</td><td></td><td>0</td></tr><tr><td>Shear link spacing</td><td>sv</td><td>mm</td><td>0</td></tr><tr><td>Asv</td><td>Asv</td><td>mm2</td><td>0.0</td></tr><tr><td>S. capacity section</td><td>-</td><td>kN/m</td><td>101</td></tr><tr><td>S. capacity links</td><td>-</td><td>kN/m</td><td>0</td></tr><tr><td>S.Capacity at av = 2d</td><td>V<sub>c1</sub></td><td>kN/m</td><td>101</td></tr><tr><td>Shear enhancement allowed?</td><td>Y/N</td><td>-</td><td>Y</td></tr><tr><td>S.Capacity at av = d</td><td>V<sub>c2</sub></td><td>kN/m</td><td>101</td></tr></table>						100As/b <sub>w</sub> d	-	-	2.9	Depth Factor	ξ <sub>s</sub>	-	1.19	Material FOS for Concrete in Shear	Ymc		1.15	Ultimate shear stress	vc	(N/mm2)	0.784	Shear link diameter	dia.	mm	0	No. Legs	-		0	Shear link spacing	sv	mm	0	Asv	Asv	mm2	0.0	S. capacity section	-	kN/m	101	S. capacity links	-	kN/m	0	S.Capacity at av = 2d	V <sub>c1</sub>	kN/m	101	Shear enhancement allowed?	Y/N	-	Y	S.Capacity at av = d	V <sub>c2</sub>	kN/m	101				
100As/b <sub>w</sub> d	-	-	2.9																																																											
Depth Factor	ξ <sub>s</sub>	-	1.19																																																											
Material FOS for Concrete in Shear	Ymc		1.15																																																											
Ultimate shear stress	vc	(N/mm2)	0.784																																																											
Shear link diameter	dia.	mm	0																																																											
No. Legs	-		0																																																											
Shear link spacing	sv	mm	0																																																											
Asv	Asv	mm2	0.0																																																											
S. capacity section	-	kN/m	101																																																											
S. capacity links	-	kN/m	0																																																											
S.Capacity at av = 2d	V <sub>c1</sub>	kN/m	101																																																											
Shear enhancement allowed?	Y/N	-	Y																																																											
S.Capacity at av = d	V <sub>c2</sub>	kN/m	101																																																											
	Assumed shear carried by steel sections only																																																													

	Project				TO315 Mayo Bridges - Assessments		Job ref 10088572		
	Part of Structure Strade River Bridge MO-N58-001.00			Assessment using AM-STR-06026 RC Slabs			Calc sheet no. rev 6 0		
	Drawing Ref			Calc By VP		Date 17-Dec-24	Check by MG	Date 18-Dec-24	
Ref	Calculations							Output	
AM-STR-06026	Filler Beam								
	Calculation of Moment due to Permanent Loads at Mid Span &								
	Calculation of Shear due to Permanent Loads near supports:								
Table 3.1/ BD21 Cl.3. 1/ BD21 & Cl. 4.2.3/ BD 44 AM-STR-06031	Self weight	Load	(kN/m2)	4.9	SLS Shear (kN) 10.0				
		Yfl		1.15					
		Yf3		1.1					
		Msw	(kNm/m)	12.9					
		Vsw	(kN/m)	12.6					
Table 3.1/ BD21 Cl.3. 1/ BD21 & Cl. 4.2.3/ BD 44 AM-STR-06031	Surfacing	Load	(kN/m2)	1.4	2.9				
		Yfl		1.75					
		Yf3		1.1					
		Ms	(kNm/m)	5.8					
		Vs	(kN/m)	5.7					
Table 3.1/ BD21 Cl.3. 1/ BD21 & Cl. 4.2.3/ BD 44 AM-STR-06031	Fill	Load	(kN/m2)	1.8	3.7				
		Yfl		1.20					
		Yf3		1.1					
		Mfill	(kNm/m)	4.9					
		Vfill1	(kN/m)	5					
Hence, Capacity Available for LL, MCLL			(kNm/m)	49	16.6 kN				
Distance (x) from support to face of support			(mm)	136					
Shear at support	VLLsup	(kN/m)	23						
Shear at av1 = 2d	VLLav1 = 2d	(kN/m)	15						
Shear at av2 = d	VLLav2 = d	(kN/m)	18						
Hence, Capacity Available for LL, VCLL= 2d			(kNm/m)	86	At 2d At d	Moment 49.2 kNm			
Hence, Capacity Available for LL, VCLL= d			(kN/m)	83		Shear 85.8 kN/m 82.7 kN/m			
Cl. 5.21/ BD 21 AM-STR-06026	Traffic Flows & Surface Condition								Bridge Category Mg
	Annual Average Daily Traffic (Ref P I Report)				5364				
	Percentage of heavy vehicles				5%				
	Annual average hourly HGV flow (AAHHGVF)				11				
	Traffic Flow Cl.5.2.2 of BD 21			L/M/H	Medium				
	Condition of road surfacing (Good/ Poor)				Good				
	Therefore Bridge Category				Mg				
	Factor K for 40 tonne loading				0.76				
	HA + KEL and Equiv. 40 t Assessment Loading								
	AM-STR-06026 Cl. 5.18/ BD21	HA Loading	UDL	(kN/m)	130.9	SLS shear 48 kN			
		KEL	(kN)	120.0					
Lane Factor				1.0					
Adjustment Factor		AF		1.46					
Therefore, Equivalent 40 t loading		UDL	(kN/m2)	27.26					
CI 5.23/ BD 21 AM-STR-06026		KEL	(kN/m)	24.99					
		Yfl		1.50					
		Yf3		1.1					
	Moment Due 40 tonne loading	MLL	(kNm)	81					
	Shear due to 40t at support	VLLsup	(kN/m)	80					
CI 5.27/ BD 21 AM-STR-06026	Shear due to 40t av = 2d	Vav = 2d	(kN/m)	58					
	Shear due to 40t av = d	VLLav = d	(kN/m)	67					
	Factor C for Moment at midspan			0.46					
	Loading Capacity Moment at midspan			7.5t		as per Figure 5.6			
	Factor C for Shear at 3*d			0.82					
Factor C for Shear at d			1.08						
Loading Capacity Shear			7.5t	as per Figure 5.6					
Check bond stress at support where shear is maximum									
		Bond Stress (N/mm2)		Permissble Stress (N/mm2)					
SLS Shear at support Dead Load		kN	16.58	1.59		0.7			
SLS Shear at support Live Load		kN	48.38						

	<b>Project</b>		TO315 Mayo Bridges - Assessments		<b>Job ref</b> 10088572																									
	<b>Part of Structure</b>		Assessment using AM-STR-06026 RC		<b>Calc sheet no.</b> rev																									
	Strade River Bridge MO-N58-001.00		Slabs		6 0																									
	<b>Drawing Ref</b>		<b>Calc By</b> VP		<b>Date</b> 17-Dec-24	<b>Check by</b> MG	<b>Date</b> 18-Dec-24																							
Ref		Calculations				Output																								
<table><tr><td><b>Is bond stress okay? Y/N</b></td><td>N</td><td rowspan="5">Assuming no contribution from Concrete</td><td><b>Bond Capacity</b></td></tr><tr><td>Load Capacity where bond stress exceeded</td><td><b>7.5t</b></td><td><b>7.5t</b></td></tr><tr><td>Adequacy Factor for Bond Stress</td><td>101%</td><td></td></tr><tr><td>Adequacy Factor for Moment at Midspan</td><td>60%</td><td></td></tr><tr><td>Adequacy Factor for Shear</td><td>108%</td><td></td></tr><tr><td></td><td></td><td></td><td><b>40 t Adequacy</b></td></tr><tr><td></td><td></td><td></td><td><b>60%</b></td></tr></table>							<b>Is bond stress okay? Y/N</b>	N	Assuming no contribution from Concrete	<b>Bond Capacity</b>	Load Capacity where bond stress exceeded	<b>7.5t</b>	<b>7.5t</b>	Adequacy Factor for Bond Stress	101%		Adequacy Factor for Moment at Midspan	60%		Adequacy Factor for Shear	108%					<b>40 t Adequacy</b>				<b>60%</b>
<b>Is bond stress okay? Y/N</b>	N	Assuming no contribution from Concrete	<b>Bond Capacity</b>																											
Load Capacity where bond stress exceeded	<b>7.5t</b>		<b>7.5t</b>																											
Adequacy Factor for Bond Stress	101%																													
Adequacy Factor for Moment at Midspan	60%																													
Adequacy Factor for Shear	108%																													
			<b>40 t Adequacy</b>																											
			<b>60%</b>																											

	Project				TO315 Mayo Bridges - Assessments		Job ref 10088572	
	Part of Structure		Assessment using AM-STR-06026		RC Slabs		Calc sheet no. rev	
	Strade River Bridge MO-N58-001.00						7 0	
Drawing Ref		Calc By		Date		Check by		Date
Strade River Bridge MO-N58-001.00		VP		17-Dec-24		MG		18-Dec-24
Ref	Calculations						Output	
Table 5.3.1 of BD21 AM-STR-06026	<b>Single Axle Load</b>		Filler Beam	Moment	Shear	Adequacy	<div>Single Axle Load</div> <div>Moment Capacity</div> <div>3t</div> <div>Shear Capacity</div> <div>7.5t</div> <div>40 t Adequacy</div> <div>31%</div>	
				Check	Check	for 40t		
	Assessment Loading		(Tonne)	3.0	7.5	40.0		
	Nominal Single Axle Load		(kN)	43	86	170		
	Wheel Contact Area		(m)	0.140	0.198	0.278		
	Minimum Distance Possible from edge of slab to centre line of first wheel in width direction							
	on left side		(m)	1.50	1.50	1.50		
	on right side		(m)	3.00	3.00	3.00		
	Dispersion for one axle, in transvesre direction		b <sub>eff</sub>	1.40	1.52	1.68		
	Dispersion for two axle, in transverse direction		b' <sub>eff</sub>	2.80	2.97	3.21		
	Dispersion in longitudinal direction		b <sub>L</sub>	0.70	0.76	0.84		
	=> Load for one axle (P)		kN	43.0	86.0	170.0		
	Load for two axle (P')		kN	86	172	340		
	w = P/b <sub>eff</sub> b <sub>L</sub> assuming load dispersed long. & transversely		kN/m <sup>2</sup>	43.9	74.9	121.0		
	w' = P'/b' <sub>eff</sub> b <sub>L</sub> assuming load dispersed long. & transversely		kN/m <sup>2</sup>	43.9	76.3	126.2		
			Y <sub>fl</sub>	1.50	1.50	1.50		
			Y <sub>f3</sub>	1.1	1.1	1.1		
	Moment due to one axle		M <sub>LL</sub> (kNm)	47	-	153		
	Moment due to two axles		M <sub>LL</sub> (kNm)	47	-	160		
	Adequacy Factor			104%	-	31%		
	=>Loading Capacity (Moment)			3t	-	-		
	Shear Due due to one axle at support				84.9	150.2		
	Shear Due due to two axles at support				86.6	156.6		
	Shear due to one axle at av = d		V <sub>LLav = d</sub> (kN/m)	-	79	139		
	Shear due to two axle at av = d		V <sub>LLav = d</sub> (kN/m)	-	80	145		
	Adequacy Factor			-	103%	57%		
	=>Loading Capacity (Shear) (av = d)			-	7.5t	-		
	Shear due to one axle at av = 2d		V <sub>av = 2d</sub> (kN/m)	-	72	128		
	Shear due to two axles av = 2d		V <sub>av = 2d</sub> (kN/m)	-	74	133		
Adequacy Factor				116%	64%			
=>Loading Capacity (Shear)(av = 2d)			-	7.5t	-			
Table 5.3.1 of BD21 AM-STR-06026	<b>Single Wheel Load</b>			Moment	Shear	Adequacy	<div>Single Wheel Load</div> <div>Moment Capacity</div> <div>3t</div> <div>Shear Capacity</div> <div>7.5t</div> <div>40 t Adequacy</div> <div>32%</div>	
				Check	Check	for 40t		
	Assessment Loading		(Tonne)	3.0	7.5	40.0		
	Nominal Single Wheel Load		(kN)	21	43	86		
	Wheel Contact Area		(m)	0.138	0.198	0.280		
	Minimum Distance Possible from edge of slab to centre line of first wheel							
	on left side		(m)	1.50	1.50	1.50		
	on right side		(m)	3.00	3.00	3.00		
	Dispersion for Wheel Load		b <sub>eff</sub>	0.70	0.76	0.84		
	w = P/b <sub>eff</sub> <sup>2</sup> assuming load dispersed long. & transversely		kN/m <sup>2</sup>	43.1	74.9	122.0		
			Y <sub>fl</sub>	1.50	1.50	1.50		
			Y <sub>f3</sub>	1.1	1.1	1.1		
	Moment Due Single Wheel Load		M <sub>LL</sub> (kNm)	46.3	-	154.7		
	Adequacy Factor			106%	-	32%		
	=>Loading Capacity (Moment)			3t	-	-		
	Shear Due Single Wheel Load		V <sub>LL</sub> (kN)	-	84.9	151.6		
	Shear due to 40t av = d		V <sub>LLav = d</sub> (kN)	-	78.7	140.4		
	Adequacy Factor				105%	59%		
	=>Loading Capacity (Shear) (av = d)				7.5t	-		
	Shear due to 40t av = 2d		V <sub>av = 2d</sub> (kN)	-	72.5	129.1		
	Adequacy Factor				118%	66%		
	=>Loading Capacity (Shear)(av = 2d)				7.5t	-		

[Single Axle Load](#)

Moment Capacity  
3t

Shear Capacity  
7.5t


40 t Adequacy  
31%



[Single Wheel Load](#)

Moment Capacity  
3t

Shear Capacity  
7.5t

40 t Adequacy  
32%



	Project TO315 Mayo Bridges - Assessments				Job ref 10088572			
	Part of Structure Strade River Bridge MO-N58-001.00		Assessment using AM-STR-06026 RC Slabs		Calc sheet no. rev 1 0			
	Drawing Ref		Calc By VP		Date 17-Dec-24	Check by MG Date 18-Dec-24		
Ref	Calculations				Output			
Table 5.3.1 of BD21 AM-STR-06026	<b>SV Load</b>							
								
			Moment		Shear			
	Assessment Loading		SV	80.0	80.0			
	Nominal Single Axle Load		(kN)	130	130			
	Wheel Contact Area		(m)	0.172	0.172			
	Minimum Distance Possible from edge of slab to centre line of first wheel							
	on left side		(m)	1.14	1.14			
	on right side		(m)	2.94	2.94			
	Dispersion for HB Axle		beff	0.73	0.73			
	=> Load for HB axle		kN	65.0	65.0			
			kN/m	88.8	88.8			
			Yfl	1.50	Moment Factor as per Influence Line ↓ 0.6 0.6 0.0 0.0			
			Yf3	1.1				
	Moment Capacity Check							
	Position of first axle from left support centre line		x1	1.14				
	Hence, distance of other axle from left support		x2	2.9				
			x3	0.0				
			x4	0.0				
	Moment Due to HB Load		M <sub>LL</sub>	(kNm)			132	
	Adequacy Factor				37%			
	=>Loading Capacity (Moment)				<SV80			
	Shear Capacity Check			for shear at d	for shear at 2d	Shear Factor at d	Shear Factor at 2d	
	Position of first axle from left support centre line			x1	0.41	0.68	0.90	0.8
	Hence, distance of other axle from left support			x2	2.2	2.5	0.27	0.2
				x3	0.000	0.0	0.00	0.0
	Shear Due HB Loading			x4	0.000	0.0	0.00	0.0
	Shear at av = d		V <sub>LLav = d</sub>	(kN/m)	106	<b>SV Load</b>		
	Adequacy Factor				78%			
	=>Loading Capacity (Shear) (av = d)				<SV80			
						<b>Moment Capacity</b> <SV80		
	Shear at av = 2d		V <sub>av = 2d</sub>	(kN/m)	106			
	Adequacy Factor				81%			
	=>Loading Capacity (Shear)(av = 2d)				<SV80	<b>Shear Capacity</b> <SV80		
	<b>Assessment Summary</b>							
	Filler Beam							
			HA UDL & KEL	Single Axle	Single Wheel	HB	SV	
	Moment		7.5t	3t	3t	<30HB	<SV80	
Shear		7.5t	7.5t	7.5t	<30HB	<SV80		
Since the Filler beam slab failed under 40T GVW, we have carried out a grillage analysis taking into account the transverse distribution.								








Project TO315 Mayo Bridges - Assessments			Job ref 10088572	
Part of Structure Filler Beam Capacity			Calc sheet 1	Rev 0
Strade River Bridge MO-N58-001.00				
Drawing ref.	Calc by VP	Date 17/12/24	Check by MG	Date 18/12/24

Ref	Calculations	Ouptut
-----	--------------	--------

9 Check bond stress of section

Dimensions in mm		Short Term Ec (BD 44/95 cl. 4.3.2.1) $E_c = (20 + 0.27f_{cu}) = 25$ $E_s = 205 \quad m = E_s / E_c = 8.17$ Long Term Ec (BD 44/95 cl. 4.3.2.1) Twice Short Term $m = 16.33$  Allowable Conc stress = $0.75f_{cu}/\gamma_{mc}\gamma_{f3} = 12.273$ Allowable steel stress = $f_{st}/\gamma_{ms}\gamma_{f3} = 199.134$
Allowable $f_{cu} =$	18.9	
$\gamma_{mc} =$	1.05	
Allowable $f_{st} =$	230	
$\gamma_{ms} =$	1.05	
$\gamma_{f3} =$	1.1	
Bottom Cover =	37	
b =	600	
$d_c =$	308.75	
$d_s =$	123	
$A_{st} =$	1820	
$t_{ft} =$	28	
$t_{fb} =$	10	
$A_{sb} =$	1230	
$t_w =$	10	



Uncracked Section for Grillage Analysis

	Short Term	Long Term Ec
m =	8.17	16.33
x =	167.65	177.53 mm
Area of section (concrete units) =	217098.78	248947.57 mm <sup>2</sup>
Area of section (steel units) =	26584.54	15242.27 mm <sup>2</sup>
$I_{NA}$ (concrete units) =	1.62E+09	1.74E+09 mm <sup>4</sup>
$I_{NA}$ (steel units) =	2.16E+08	1.23E+08 mm <sup>4</sup>

Cracked Section

	Short Term	Long Term Ec
m =	8.17	16.33
x =	152.65	147.18 mm
Area of concrete in compression =	91591.59	88307.85 mm <sup>2</sup>
Centroid of conc. in comp.(from NA) =	76.33	73.59 mm
$I_{NA}$ (cracked section) =	6.74E+08	9.68E+08 mm <sup>4</sup>
$A * y / I_{NA} =$	0.01037	0.00671 /mm

AM-STR-06037 Cl 8.5.1: "The bond may be assumed to be developed uniformly only over both sides of the web and the upper surface of the top and bottom flanges of the steel beam where there is complete encasement and over both sides of the web and the upper surface of the top flange of the steel beam where the beam soffit is exposed."

Hence, as cover to soffit of bottom flange is 37mm,  $L_s = 348 \text{ mm}$



Project TO315 Mayo Bridges - Assessments			Job ref 10088572.00	
Part of Structure Filler Beam Capacity Strade River Bridge MO-N58-001.00			Calc sheet 2	Rev 0
Drawing ref.	Calc by VP	Date 17/12/2024	Check by MG	Date 18/12/2024

Ref	Calculations	Ouptut
-----	--------------	--------

#### Check for Max Shear (at support) HA Loading

Serviceability Loads (F)

Shear at support	kN
Dead Load	22.00
Live Load	39.00

Longt'l Shear Force =  $F_{Ay}/I_{NA}$       Live Load 404.27      Dead Load 147.66      N/mm

Bond stress = 1.162      0.424      N/mm<sup>2</sup>


Total bond stress = 1.586      N/mm<sup>2</sup>

Allowable bond stress at SLS = 0.700      N/mm<sup>2</sup>


**Result:** Section is unsuitable for composite action (see BD 61/10 Clause 8.5.1)


#### Check capacity of section unsuitable for composite action

Find distance x such that bond stress due to combined Dead Load and Live Load = 0.7N/mm2



#### Legend:

 bond stress <0.7N/mm2  
suitable for composite action

 bond stress >0.7N/mm2  
unsuitable for composite action

Vary x until bond stress = allowable bond stress

Try x = **1.42** m      (Max x = L/2 = 2.040875 m)

Okay      Hint: Use Goalseek

Serviceability Loads (F)

Shear at location x	kN
Dead Load	<b>5.00</b>
Live Load	<b>20.26</b>

Longt'l Shear Force =  $F_{Ay}/I_{NA}$       Live Load 210.04      Dead Load 33.56      N/mm

Bond stress using = 0.604      0.096      N/mm<sup>2</sup>

Total bond stress= **0.700**      N/mm<sup>2</sup>

Allowable bond stress at SLS = **0.700**      N/mm<sup>2</sup>

**Result:** Bond stress okay

#### Check corresponding moment capacity at x



Factor **K** for 40 tonne loading      0.76  
Moment Capacity of steel section      30.38      kNm  
Moment Capacity of composite section      36.54      kNm





ULS Moment at x	kNm
Dead Load	12.24
Available capacity for live load	24.30
Live Load	24.00

Factor **C** for Moment      0.77  
Loading Capacity Moment **7.5t**      as per Figure 5.6  
Adequacy Factor      1.01


**(HA + KEL Eqv.)**  
**Moment Capacity**  
**7.5t**

#### Results from Grillage analysis -Dead Load



<div>AtkinsRéalis</div>		Project TO315 Mayo Bridges - Assessments			Job ref 10088572	
		Part of Structure Filler Beam Capacity Strade River Bridge MO-N58-001.00			Calc sheet 3 Rev 0.00	
		Drawing ref.	Calc by VP	Date 17/12/2024	Check by MG	Date 18/12/2024
Ref	Calculations				Oupput	
	<div>HA 7.5T Shear Diagram</div> <div></div>				<div><div>MIDAS/Civil POST-PROCESSOR BEAM DIAGRAM SHEAR-z</div><div></div><div>CBALL: HA 7.5 T MAX : 2264 MIN : 2266 FILE: STRADE RI- UNIT: kN DATE: 10/22/2024 VIEW-DIRECTION X: -1.000 Y: 0.000 Z: 0.000</div></div>	
	<div>HA 7.5t GVW Moment Diagram</div> <div></div>				<div><div>MIDAS/Civil POST-PROCESSOR BEAM DIAGRAM MOMENT-y</div><div></div><div>CBALL: HA 7.5 T MAX : 2260 MIN : 2264 FILE: STRADE RI- UNIT: kN.m DATE: 10/22/2024 VIEW-DIRECTION X: -1.000 Y: 0.000 Z: 0.000</div></div>	
	<div><div>Vx9.78 kN</div><div>Vmax14.99 kN</div><div>Mx13.88 kNm</div><div>Mmax13.88 kNm</div><div>Mmax P at centre15.30 kNm</div></div>					
<div>Combined load effect</div>						
		per m width	ULS (Yf3=1.5)			
Combined Moment Mx		16.00 kNm	24.00			
Combined Shear Vx		20.26 kN	30.39			
			ULS (Yf3=1.5)			
Max M		23.00 kNm	34.50 kNm			
Max V		39.00 kN	58.50 kN			

<div>AtkinsRéalis</div>		Project TO315 Mayo Bridges - Assessments			Job ref 10088572.00																																																																											
		Part of Structure Filler Beam Capacity		Calc sheet Rev																																																																												
		Strade River Bridge MO-N58-001.00		4 0.00																																																																												
		Drawing ref.	Calc by VP	Date 17/12/2024	Check by MG	Date 18/12/2024																																																																										
Ref	Calculations				Ouptut																																																																											
<div>HB Live Load</div> <div>Check for Max Shear (at support) 45HB</div> <div>Serviceability Loads (F)</div> <table><tr><td>Shear at support</td><td>kN</td></tr><tr><td>Dead Load</td><td>22.00</td></tr><tr><td>Live Load</td><td>71.00</td></tr></table> <div><div>Longt'l Shear Force = <math>F_{Ay}/I_{NA}</math></div><div>Bond stress using=</div><div>Total bond stress using =</div><div>Allowable bond stress at SLS =</div><table><tr><td><u>Live Load</u></td><td><u>Dead Load</u></td><td></td></tr><tr><td>735.99</td><td>147.66</td><td>N/mm</td></tr><tr><td>2.115</td><td>0.424</td><td>N/mm<sup>2</sup></td></tr><tr><td>2.539</td><td></td><td>N/mm<sup>2</sup></td></tr><tr><td>0.700</td><td></td><td>N/mm<sup>2</sup></td></tr></table><div>Result: Bond Stress (2.54) greater or equal than Permissible Bond Stress (0.7) hence section is unsuitable for composite action (see BD 61/10 Clause 8.5.1)</div></div> <div>Check section at x</div> <div>45HB Loading</div> <div>Vary x until bond stress = allowable bond stress</div> <div>Try x = 1.70 m Load 45.00 HB</div> <div>x okay Hint:Use Goalseek</div> <div>Serviceability Loads (F)</div> <table><tr><td>Shear at location x</td><td>kN</td></tr><tr><td>Dead Load</td><td>4.00</td></tr><tr><td>Live Load</td><td>20.91</td></tr></table> <div>Check for Shear at x - 45HB</div> <div>Note: If bottom flange is exposed use L<sub>S1</sub> otherwise use L<sub>S2</sub></div> <div><div>Longt'l Shear Force = <math>F_{Ay}/I_{NA}</math></div><div>Bond stress=</div><div>Total bond stress=</div><div>Allowable bond stress at SLS =</div><table><tr><td><u>Live Load</u></td><td><u>Dead Load</u></td><td></td></tr><tr><td>217</td><td>26.85</td><td>N/mm</td></tr><tr><td>0.623</td><td>0.077</td><td>N/mm<sup>2</sup></td></tr><tr><td>0.700</td><td></td><td>N/mm<sup>2</sup></td></tr><tr><td>0.7</td><td>0.700</td><td>N/mm<sup>2</sup></td></tr></table><div>Result: Bond stress okay using Ls2</div><div><div><div>Base</div><div><div>POST-PROCESSOR</div><div>BEAM DIAGRAM</div><div>SHEAR-z</div><div><div></div><div>71</div><div>58</div><div>45</div><div>32</div><div>19</div><div>6</div><div>0</div><div>-19</div><div>-32</div><div>-45</div><div>-58</div><div>-71</div></div><div>MVALL: HB 45</div><div>MAX : 2252</div><div>MIN : 2229</div><div>FILE: STRADE RI-</div><div>UNIT: kN</div><div>DATE: 10/22/2024</div><div>VIEW-DIRECTION</div><div>Xz: 1.000</div><div>Yz: 0.000</div><div>Zz: 0.000</div></div><div><div>Base</div><div><div>POST-PROCESSOR</div><div>BEAM DIAGRAM</div><div>MOMENT-y</div><div><div></div><div>42</div><div>37</div><div>32</div><div>27</div><div>22</div><div>17</div><div>12</div><div>7</div><div>0</div><div>-4</div><div>-9</div><div>-14</div></div><div>MVALL: HB 45</div><div>MAX : 2203</div><div>MIN : 2003</div><div>FILE: STRADE RI-</div><div>UNIT: kN-m</div><div>DATE: 10/22/2024</div><div>VIEW-DIRECTION</div><div>Xz: 1.000</div><div>Yz: 0.000</div><div>Zz: 0.000</div></div></div></div><table><tr><td>Vx</td><td>4.00 kN</td><td>Vx</td><td>20.91 kN</td><td>31.37</td><td>kN</td></tr><tr><td>Vmax</td><td>22.00 kN</td><td>Vmax</td><td>71.00 kN</td><td>106.50</td><td>kN</td></tr><tr><td>Mx</td><td>14.00 kNm</td><td>Mx</td><td>37.00 kNm</td><td>55.50</td><td>kNm</td></tr><tr><td>Mmax</td><td>17.00 kNm</td><td>Mmax</td><td>42.00 kNm</td><td>63.00</td><td>kNm</td></tr></table><div>ULS</div><div>Check corresponding moment capacity at x</div><table><tr><td>ULS Moment at x</td><td>kNm</td></tr><tr><td>Dead Load</td><td>16.80</td></tr><tr><td>Available capacity for live load</td><td>13.58</td></tr><tr><td>45HB Live Load</td><td>55.50</td></tr></table><div>Adequacy 0.24 Fail</div><div>Moment Capacity &lt;45HB</div></div></div>							Shear at support	kN	Dead Load	22.00	Live Load	71.00	<u>Live Load</u>	<u>Dead Load</u>		735.99	147.66	N/mm	2.115	0.424	N/mm <sup>2</sup>	2.539		N/mm <sup>2</sup>	0.700		N/mm <sup>2</sup>	Shear at location x	kN	Dead Load	4.00	Live Load	20.91	<u>Live Load</u>	<u>Dead Load</u>		217	26.85	N/mm	0.623	0.077	N/mm <sup>2</sup>	0.700		N/mm <sup>2</sup>	0.7	0.700	N/mm <sup>2</sup>	Vx	4.00 kN	Vx	20.91 kN	31.37	kN	Vmax	22.00 kN	Vmax	71.00 kN	106.50	kN	Mx	14.00 kNm	Mx	37.00 kNm	55.50	kNm	Mmax	17.00 kNm	Mmax	42.00 kNm	63.00	kNm	ULS Moment at x	kNm	Dead Load	16.80	Available capacity for live load	13.58	45HB Live Load	55.50
Shear at support	kN																																																																															
Dead Load	22.00																																																																															
Live Load	71.00																																																																															
<u>Live Load</u>	<u>Dead Load</u>																																																																															
735.99	147.66	N/mm																																																																														
2.115	0.424	N/mm <sup>2</sup>																																																																														
2.539		N/mm <sup>2</sup>																																																																														
0.700		N/mm <sup>2</sup>																																																																														
Shear at location x	kN																																																																															
Dead Load	4.00																																																																															
Live Load	20.91																																																																															
<u>Live Load</u>	<u>Dead Load</u>																																																																															
217	26.85	N/mm																																																																														
0.623	0.077	N/mm <sup>2</sup>																																																																														
0.700		N/mm <sup>2</sup>																																																																														
0.7	0.700	N/mm <sup>2</sup>																																																																														
Vx	4.00 kN	Vx	20.91 kN	31.37	kN																																																																											
Vmax	22.00 kN	Vmax	71.00 kN	106.50	kN																																																																											
Mx	14.00 kNm	Mx	37.00 kNm	55.50	kNm																																																																											
Mmax	17.00 kNm	Mmax	42.00 kNm	63.00	kNm																																																																											
ULS Moment at x	kNm																																																																															
Dead Load	16.80																																																																															
Available capacity for live load	13.58																																																																															
45HB Live Load	55.50																																																																															



Ref

Calculations

Ouptut

HB Live Load

Check for Max Shear (at support) 30HB

Serviceability Loads (F)

Shear at support	kN
Dead Load	22.00
Live Load	70.50

Longt'l Shear Force =  $F_{Ay}/I_{NA}$

Bond stress using=

Total bond stress using =

Allowable bond stress at SLS =

	Live Load	Dead Load	
	730.80	147.66	N/mm
	2.100	0.424	N/mm <sup>2</sup>
	2.524		N/mm <sup>2</sup>
	0.700		N/mm <sup>2</sup>

Result: Bond Stress (2.52) greater or equal than Permissible Bond Stress (0.7) hence section is unsuitable for composite action (see BD 61/10 Clause 8.5.1)

Check section at x

30HB Loading

Vary x until bond stress = allowable bond stress

Try x = 1.62 m Load 30.00 HB

x okay Hint:Use Goalseek

Serviceability Loads (F)

Shear at location x	kN
Dead Load	4.50
Live Load	20.59

Check for Shear at x - 30HB

Note: If bottom flange is exposed use L<sub>s1</sub> otherwise use L<sub>s2</sub>

Longt'l Shear Force =  $F_{Ay}/I_{NA}$

Bond stress=


Total bond stress=

Allowable bond stress at SLS =

	Live Load	Dead Load	
	213	30.20	N/mm
	0.613	0.087	N/mm <sup>2</sup>
	0.700		N/mm <sup>2</sup>
	0.7		0.700 N/mm <sup>2</sup>

Result: Bond stress okay using Ls2

Base



Ref	Calculations	Ouptut
-----	--------------	--------

Serviceability Loads (F)	
Shear at support	kN
Dead Load	22.00
Live Load	71.00

**Note: If bottom flange is exposed use  $L_{S1}$  otherwise use  $L_{S2}$**

	<u>Live Load</u>	<u>Dead Load</u>	
Longitud Shear Force = $F_{Ay}/I_{NA}$	735.99	147.66	N/mm
Bond stress=	2.115	0.424	N/mm <sup>2</sup>
Total bond stress=	2.539		N/mm <sup>2</sup>
Allowable bond stress at SLS =	0.700		N/mm <sup>2</sup>

**Result:** Bond Stress (2.54) greater or equal than Permissible Bond Stress (0.7) hence section is unsuitable for composite action (see BD 61/10 Clause 8.5.1)

Vary  $x$  until bond stress = allowable bond stress


**Loading** Try  $x =$  **1.70** m Load **SV 80** HB  
x okay Hint: Use Goalseek

Serviceability Loads (F)	
Shear at location x	kN
Dead Load	<b>4.00</b>
Live Load	<b>20.91</b>

	<u>Live Load</u>	<u>Dead Load</u>	
Longitud Shear Force = $F_{Ay}/I_{NA}$	217	26.85	N/mm
Bond stress=	0.623	0.077	N/mm <sup>2</sup>
Total bond stress=	<b>0.700</b>		N/mm <sup>2</sup>
Allowable bond stress at SLS = 0.7	<b>0.700</b>		N/mm <sup>2</sup>

**Result:** Bond stress okay using Ls2

DEPTH (m)	tau	sigma
0.0	71	19
0.5	51	19
1.0	45	19
1.5	32	19
2.0	19	19
2.5	0	19
3.0	-6	19
3.5	-19	19
4.0	-32	19
4.5	-45	19
5.0	-58	19
5.5	-71	19



Vx	4.00 kN	Vx	13.94 kN	20.91 kN
Vmax	22.00 kN	Vmax	71.00 kN	106.50 kN
Mx	14.00 kNm	Mx	26.00 kNm	39.00 kNm
Mmax	17.00 kNm	Mmax	40.00 kNm	60.00 kNm

ULS Moment at x		kNm
Dead Load		16.80
Available capacity for live load		13.58
SV 80HB	Live Load	39.00

Adequacy	
0.35	Fail

## Moment Capacity <SV 80


Project Name TO315 Mayo Bridges - Assessments			Job Number <b>10088572</b>	
Calculation Location Strade River Bridge MO-N58-001.00			Sheet Number 15 of	Rev. 0
Drawing Reference 0	Originator VP	Date Oct-24	Checker MG	Date Oct-24

Ref.	Calculations	Output
------	--------------	--------

**10**

### Grillage Analysis Results Diagram


Since the Filler beam slab failed under 40T GVW, we have carried out a grillage analysis taking into account the transverse distribution.  
Dead Load + Super Imposed Dead load (SD\*)



Maximum of Moment along both axis (  $M_{xx}$  &  $M_{yy}$  )

Moment near Support (Sagging)	=	5	kNm
Maximum Sagging Moment	=	17	kNm
Maximum Shear at d from support	=	53	kN




Load effect due to Type HA 40t Loading - ULS Case 1 (SHA-40T\*)







Maximum of Moment along both axis (  $M_{xx}$  &  $M_{yy}$  )

	ULS Case 1 (SHA-40T*)	ULS Case 2 (SHA-26T*)
Moment near Support (Sagging)	= 12 kNm	10 kNm
Maximum Sagging Moment	= 56 kNm	55 kNm
Maximum Shear at d from support	= 85 kN	84 kN

*Since the structure also failed to have enough capacity under HA 40T, results for HA 26T units are only shown above.*

	Project Name TO315 Mayo Bridges - Assessments			Job Number 10088572																	
	Calculation Location Strade River Bridge MO-N58-001.00			Sheet Number 15 of	Rev. 0																
	Drawing Reference 0	Originator VP	Date Oct-24	Checker MG	Date Oct-24																
Ref.	Calculations			Output																	
	<p><u>Load effect due to Type HA +HB -combined ( 40T HA + HB -45units)</u></p> <div><div><div>Base</div><div></div></div><div><div>MIDAS/Civil POST-PROCESSOR</div><div>BEAM FORCE</div><div>MOMENT-y</div><div><div>84</div><div>71</div><div>58</div><div>46</div><div>33</div><div>20</div><div>7</div><div>0</div><div>-18</div><div>-31</div><div>-44</div><div>-57</div></div><div>CBALL: C2-TYPE ~</div><div>MAX : 2259</div><div>MIN : 2265</div><div>FILE: STRADE RI-</div><div>UNIT: kN-m</div><div>DATE: 10/22/2024</div><div>VIEW-DIRECTION</div><div>X: -0.612</div><div>Y: -0.612</div><div>Z: 0.500</div></div></div> <p>Maximum of Moment along both axis ( Mxx &amp; Myy)</p> <p>ULS Case 3 (SHA+HB-45*)</p> <table><tr><td>Moment near Support (Sagging)</td><td>=</td><td>20</td><td>kNm</td></tr><tr><td>Maximum Sagging Moment</td><td>=</td><td>84</td><td>kNm</td></tr><tr><td>Maximum Shear at d from support</td><td>=</td><td>146</td><td>kN</td></tr></table>			Moment near Support (Sagging)	=	20	kNm	Maximum Sagging Moment	=	84	kNm	Maximum Shear at d from support	=	146	kN						
Moment near Support (Sagging)	=	20	kNm																		
Maximum Sagging Moment	=	84	kNm																		
Maximum Shear at d from support	=	146	kN																		
	<p><u>Load effect due to Type HB 45 units Loading</u></p> <div><div><div>Base</div><div></div></div><div><div>MIDAS/Civil POST-PROCESSOR</div><div>BEAM FORCE</div><div>MOMENT-y</div><div><div>75</div><div>63</div><div>52</div><div>40</div><div>29</div><div>17</div><div>6</div><div>0</div><div>-17</div><div>-29</div><div>-40</div><div>-52</div></div><div>CBALL: C3-TYPE ~</div><div>MAX : 2318</div><div>MIN : 2293</div><div>FILE: STRADE RI-</div><div>UNIT: kN-m</div><div>DATE: 10/22/2024</div><div>VIEW-DIRECTION</div><div>X: -0.612</div><div>Y: -0.612</div><div>Z: 0.500</div></div></div> <p>Maximum of Moment along both axis ( Mxx &amp; Myy)</p> <table><thead><tr><th></th><th></th><th>ULS Case 4 (SHB-45*)</th><th>ULS Case 5 (SHB-30*)</th></tr></thead><tbody><tr><td>Moment near Support (Sagging)</td><td>=</td><td>14 kNm</td><td>12 kNm</td></tr><tr><td>Maximum Sagging Moment</td><td>=</td><td>75 kNm</td><td>55 kNm</td></tr><tr><td>Maximum Shear at d from support</td><td>=</td><td>121 kN</td><td>87 kN</td></tr></tbody></table>					ULS Case 4 (SHB-45*)	ULS Case 5 (SHB-30*)	Moment near Support (Sagging)	=	14 kNm	12 kNm	Maximum Sagging Moment	=	75 kNm	55 kNm	Maximum Shear at d from support	=	121 kN	87 kN		
		ULS Case 4 (SHB-45*)	ULS Case 5 (SHB-30*)																		
Moment near Support (Sagging)	=	14 kNm	12 kNm																		
Maximum Sagging Moment	=	75 kNm	55 kNm																		
Maximum Shear at d from support	=	121 kN	87 kN																		

	Project Name TO315 Mayo Bridges - Assessments			Job Number 10088572	
	Calculation Location Strade River Bridge MO-N58-001.00			Sheet Number 15 of	Rev. 0
	Drawing Reference 0	Originator VP	Date Oct-24	Checker MG	Date Oct-24
Ref.	Calculations			Output	
	<div><div><div>Load effect due to SV 196 Loading - ULS Case 6 (SV 196*)</div><div><div><div>Maximum of Moment along both axis ( Mxx &amp; Myy)</div><div>Moment near Support (Sagging) = 18 kNm</div><div>Maximum Sagging Moment = 66 kNm</div><div>Maximum Shear at d from support = 110 kN</div></div></div></div></div>				
	<div><div><div>Load effect due to SV 80 Loading - ULS Case 7 (SV 80*)</div><div>Since the structure also failed to have enough capacity under SV 100 vehicle, results for SV 80 are only shown below. SV 100 has the same 165 kN axle as SV 196.</div><div><div><div>Maximum of Moment along both axis ( Mxx &amp; Myy)</div><div>Moment near Support (Sagging) = 17 kNm</div><div>Maximum Sagging Moment = 60 kNm</div><div>Maximum Shear at d from support = 98 kN</div></div></div></div></div>				

	Project Name TO315 Mayo Bridges - Assessments				Job Number 10088572																																																																																																																																																																	
	Calculation Location Strade River Bridge MO-N58-001.00				Sheet Number 15 of		Rev. 0																																																																																																																																																															
	Drawing Reference 0		Originator VP	Date Oct-24	Checker MG		Date Oct-24																																																																																																																																																															
Ref.	Calculations				Output																																																																																																																																																																	
<div>Assessment Summary Table.</div> <table><thead><tr><th>Load Effect</th><th>RA*</th><th>SD*</th><th>Case 1 SHA-40T*</th><th>Case 2 SHA-7.5T*</th><th>Case 3 SHA+H45*</th><th>Case 4 SHB45*</th><th>Case 5 SHB30*</th><th>Case 6 SSV196*</th><th>Case 7 SSV80*</th></tr></thead><tbody><tr><td>Moment near Support (Sagging) (kNm)</td><td>73</td><td>5</td><td>12</td><td>10</td><td>20</td><td>14</td><td>12</td><td>18</td><td>17</td></tr><tr><td>RA*/SA*</td><td></td><td>14.6</td><td>6.1</td><td>7.3</td><td>3.6</td><td>5.2</td><td>6.1</td><td>4.0</td><td>4.3</td></tr><tr><td>Check</td><td></td><td>OK</td><td>OK</td><td>OK</td><td>OK</td><td>OK</td><td>OK</td><td>OK</td><td>OK</td></tr><tr><td>Maximum Sagging Moment (kNm)</td><td>73</td><td>17</td><td>56</td><td>55</td><td>84</td><td>75</td><td>55</td><td>66</td><td>60</td></tr><tr><td>RA*/SA*</td><td></td><td>4.28</td><td>1.30</td><td>1.32</td><td>0.87</td><td>0.971</td><td>1.32</td><td>1.10</td><td>1.21</td></tr><tr><td>Check</td><td></td><td>OK</td><td>OK</td><td>OK</td><td>Not Ok</td><td>Not Ok</td><td>OK</td><td>OK</td><td>OK</td></tr><tr><td>Maximum Shear at d from support (kN)</td><td>101</td><td>53</td><td>85</td><td>84</td><td>146</td><td>121</td><td>87</td><td>110</td><td>98</td></tr><tr><td>RA*/SA*</td><td></td><td>1.9</td><td>1.2</td><td>1.2</td><td>0.7</td><td>0.8</td><td>1.2</td><td>0.9</td><td>1.0</td></tr><tr><td>Check</td><td></td><td>OK</td><td>OK</td><td>OK</td><td>Not Ok</td><td>Not Ok</td><td>OK</td><td>Not Ok</td><td>OK</td></tr></tbody></table> <div>Where RA* = Assessment Resistance (flexure, shear etc.) SD* = Assessment load effects due to dead and superimposed dead loads SHA* = Assessment load effect due to the associated Type HA loading SHB* = Load effect due to HB loading SA* = Assessment load effects RA*/SA* = Structural Assessment Factor</div> <table><thead><tr><th>Element</th><th>Load Effect</th><th>RA*</th><th>SD*</th><th>SHA40t*</th><th>SHA+HB45*</th><th>SHB45*</th><th>SSV196*</th><th>RA*/SA*</th></tr></thead><tbody><tr><td rowspan="4">Filler beam slab bridge</td><td>Moment near Support (Sagging) (kNm)</td><td>73</td><td>5</td><td>12</td><td>20</td><td>14</td><td>18</td><td>3.64</td></tr><tr><td>Max. Sagging Moment (kNm)</td><td>73</td><td>17</td><td>56</td><td>84</td><td>75</td><td>66</td><td>0.87</td></tr><tr><td>Max. Shear (kN)</td><td>101</td><td>53</td><td>85</td><td>146</td><td>121</td><td>110</td><td>0.69</td></tr><tr><td>Bond Capacity</td><td colspan="2">7.5 T</td><td colspan="2">&lt; HB 30 units</td><td colspan="3">&lt; SV 80</td></tr></tbody></table> <table><thead><tr><th>Structure ID</th><th>Structure Name</th><th>Structure Type</th><th>No. of Spans</th><th>Span Length</th><th>Assessed Capacity (ALL)</th><th>HB Capacity</th><th>SV Capacity</th></tr></thead><tbody><tr><td>MO-N58-001.00</td><td>Strade River Bridge</td><td>Filler beam concrete slab</td><td>2</td><td>3.81</td><td>7.5t</td><td>Fails HB30 units</td><td>Fails SV 80</td></tr></tbody></table>									Load Effect	RA*	SD*	Case 1 SHA-40T*	Case 2 SHA-7.5T*	Case 3 SHA+H45*	Case 4 SHB45*	Case 5 SHB30*	Case 6 SSV196*	Case 7 SSV80*	Moment near Support (Sagging) (kNm)	73	5	12	10	20	14	12	18	17	RA*/SA*		14.6	6.1	7.3	3.6	5.2	6.1	4.0	4.3	Check		OK	OK	OK	OK	OK	OK	OK	OK	Maximum Sagging Moment (kNm)	73	17	56	55	84	75	55	66	60	RA*/SA*		4.28	1.30	1.32	0.87	0.971	1.32	1.10	1.21	Check		OK	OK	OK	Not Ok	Not Ok	OK	OK	OK	Maximum Shear at d from support (kN)	101	53	85	84	146	121	87	110	98	RA*/SA*		1.9	1.2	1.2	0.7	0.8	1.2	0.9	1.0	Check		OK	OK	OK	Not Ok	Not Ok	OK	Not Ok	OK	Element	Load Effect	RA*	SD*	SHA40t*	SHA+HB45*	SHB45*	SSV196*	RA*/SA*	Filler beam slab bridge	Moment near Support (Sagging) (kNm)	73	5	12	20	14	18	3.64	Max. Sagging Moment (kNm)	73	17	56	84	75	66	0.87	Max. Shear (kN)	101	53	85	146	121	110	0.69	Bond Capacity	7.5 T		< HB 30 units		< SV 80			Structure ID	Structure Name	Structure Type	No. of Spans	Span Length	Assessed Capacity (ALL)	HB Capacity	SV Capacity	MO-N58-001.00	Strade River Bridge	Filler beam concrete slab	2	3.81	7.5t	Fails HB30 units	Fails SV 80
Load Effect	RA*	SD*	Case 1 SHA-40T*	Case 2 SHA-7.5T*	Case 3 SHA+H45*	Case 4 SHB45*	Case 5 SHB30*	Case 6 SSV196*	Case 7 SSV80*																																																																																																																																																													
Moment near Support (Sagging) (kNm)	73	5	12	10	20	14	12	18	17																																																																																																																																																													
RA*/SA*		14.6	6.1	7.3	3.6	5.2	6.1	4.0	4.3																																																																																																																																																													
Check		OK	OK	OK	OK	OK	OK	OK	OK																																																																																																																																																													
Maximum Sagging Moment (kNm)	73	17	56	55	84	75	55	66	60																																																																																																																																																													
RA*/SA*		4.28	1.30	1.32	0.87	0.971	1.32	1.10	1.21																																																																																																																																																													
Check		OK	OK	OK	Not Ok	Not Ok	OK	OK	OK																																																																																																																																																													
Maximum Shear at d from support (kN)	101	53	85	84	146	121	87	110	98																																																																																																																																																													
RA*/SA*		1.9	1.2	1.2	0.7	0.8	1.2	0.9	1.0																																																																																																																																																													
Check		OK	OK	OK	Not Ok	Not Ok	OK	Not Ok	OK																																																																																																																																																													
Element	Load Effect	RA*	SD*	SHA40t*	SHA+HB45*	SHB45*	SSV196*	RA*/SA*																																																																																																																																																														
Filler beam slab bridge	Moment near Support (Sagging) (kNm)	73	5	12	20	14	18	3.64																																																																																																																																																														
	Max. Sagging Moment (kNm)	73	17	56	84	75	66	0.87																																																																																																																																																														
	Max. Shear (kN)	101	53	85	146	121	110	0.69																																																																																																																																																														
	Bond Capacity	7.5 T		< HB 30 units		< SV 80																																																																																																																																																																
Structure ID	Structure Name	Structure Type	No. of Spans	Span Length	Assessed Capacity (ALL)	HB Capacity	SV Capacity																																																																																																																																																															
MO-N58-001.00	Strade River Bridge	Filler beam concrete slab	2	3.81	7.5t	Fails HB30 units	Fails SV 80																																																																																																																																																															

## Appendix H. Photographs



Figure H-1 - View of the carriageway looking south



Figure H-2 - View of the cracking to the northwest corner of the carriageway



**Figure H-3 - View of the eastern footway**



**Figure H-4 - View of the western footway**



Figure H-5 - View of the eastern parapet



Figure H-6 - View of the western parapet



**Figure H-7 - View of the northwest embankment**



**Figure H-8 - View of the southeast embankment**



**Figure H-9 - View of the southwest wing wall**



**Figure H-10 - View of the south abutment**



**Figure H-11 - View of the north abutment**



**Figure H-12 - View of the northeast pier face**



**Figure H-13 – View of the south pier face**



**Figure H-14 – View of the cracking to the north face of the pier**



Figure H-15 – View of the north span deck slab



Figure H-16 – View of the south span deck slab



**Figure H-17 - South span - Cracking sealed with calcite**



**Figure H-18 - South span - spalling with exposed filler beam**



**Figure H-19 - North span - cracking sealed with calcite, water staining and spalling**



**Figure H-20 – North span - exposed filler beam with delamination evident**



**Figure H-21 – View of riverbed west of structure looking east**



**Figure H-22 - View of the west elevation**



Figure H-23 - View of the east elevation

# AtkinsRéalis



**WS Atkins Ireland Limited**

Unit 2B  
2200 Cork Airport Business Park  
Cork  
T12 R279

Tel: +353 21 429 0300

© WS Atkins Ireland Limited except where stated  
otherwise

# AtkinsRéalis



**WS Atkins Ireland Limited**

Unit 2B  
2200 Cork Airport Business Park  
Cork  
T12 R279

Tel: +353 21 429 0300

© WS Atkins Ireland Limited except where stated  
otherwise