Constant Energy Limited

Tirawley Wind Farm

Palmerstown Bridge Structural Assessment Report

25th January 2023

Constant Energy Limited 6th Floor, River Point, Lower Mallow Street, Limerick. V94 WC6A.



Jennings O'Donovan & Partners Limited,

Consulting Engineers, Finisklin Business Park, Sligo.

Tel.: 071 9161416 Fax: 071 9161080

email: info@jodireland.com



JENNINGS O'DONOVAN & PARTNERS LIMITED

Project, Civil and Structural Consulting Engineers, FINISKLIN BUSINESS PARK, SLIGO, IRELAND.

Telephone (071) 9161416 (071) 9161080

Email info@jodireland.com www.jodireland.com Web Site



<u>DOCUMENT APPROVAL</u>

| PROJECT | Tirawley Wind Farm | | |
|-----------------------|--|----------------------------|--|
| CLIENT / JOB NO | Constant Energy Limited 6289 | | |
| DOCUMENT TITLE/No. | Palmerstown Bridge Structural Assessment Report | 6289-JOD-00-XX-RP-S-001-P1 | |

| | Prepared by | Reviewed by | Approved by | |
|------------------------------|--------------------------------|-----------------|-------------|--|
| Issue / Revision | Name | Name | Name | |
| P1 | John McElvaney Eamon Morrissey | | David Kiely | |
| Date | Signature | Signature | Signature | |
| 25 th January2023 | for h Elanes | - Eason Morrisy | Land Kiely | |

This report, and information or advice which it contains, is provided by JENNINGS O'DONOVAN & PARTNERS LIMITED solely for internal use and reliance by its Client in performance of JENNINGS O'DONOVAN & PARTNERS LIMITED's duties and liabilities under its contract with the Client. Any advice, opinions, or recommendations within this report should be read and relied upon only in the context of the report as a whole. The advice and opinions in this report are based upon the information made available to JENNINGS O'DONOVAN & PARTNERS LIMITED at the date of this report and on current standards, codes, technology and construction practices as at the date of this report. Following final delivery of this report to the Client, JENNINGS O'DONOVAN & PARTNERS LIMITED will have no further obligations or duty to advise the Client on any matters, including development affecting the information or advice provided in this report. This report has been prepared by JENNINGS O'DONOVAN & PARTNERS LIMITED in their professional capacity as Consulting Engineers. The contents of the report on the provided any manner of ferral advices or online. This report is prepared in accordance with the terms and conditions of IENNINGS O'DONOVAN & PARTNERS. do not, in any way, purport to include any manner of legal advice or opinion. This report is prepared in accordance with the terms and conditions of JENNINGS O'DONOVAN & PARTNERS LIMITED contract with the Client. Regard should be had to those terms and conditions when considering and/or placing any reliance on this report. Should the Client wish to release this report to a Third Party for that party's reliance, JENNINGS O'DONOVAN & PARTNERS LIMITED may, at its discretion, agree to such release provided that:

- a Inite Party for that party's reliance, JENNINGS O'DONOVAN & PART NERS LIMITED may, at its discretion, agree to such release provided that:

 JENNINGS O'DONOVAN & PARTNERS LIMITED written agreement is obtained prior to such release, and

 By release of the report to the Third Party, that Third Party does not acquire any rights, contractual or otherwise, whatsoever against JENNINGS O'DONOVAN & PARTNERS LIMITED, accordingly, assume no duties, liabilities or obligations to that Third Party, and

 JENNINGS O'DONOVAN & PARTNERS LIMITED accepts no responsibility for any loss or damage incurred by the Client or for any conflict of JENNINGS O'DONOVAN &
- (c) PARTNERS LIMITED's interests arising out of the Client's release of this report to the Third Party.

CONTENTS

| 1. | INTI | RODUCTION | 1 |
|----|------|-----------------------------------|-----|
| | 1.1. | Terms of Reference | 1 |
| 2. | VISU | JAL INSPECTION | 5 |
| | 2.1. | Stage 1 – Bridge Inventory Survey | 5 |
| | | Stage 2 – Maintenance Inspection | |
| | 2.3. | Stage 3 – Engineering Inspection | 7 |
| | 2.4. | Photographic Record | 8 |
| | | ENGTH ASSESSMENT BY MEXE METHOD | |
| 4. | CON | ICLUSIONS & RECOMMENDATIONS | .15 |

1. <u>INTRODUCTION</u>

1.1. Terms of Reference

Jennings O'Donovan and Partners Ltd. (JOD) have been appointed by Constant Energy Limited to undertake a structural assessment of an existing bridge on the R314 regional road in Co. Mayo. The bridge is approximately 3.5 km to the northwest of Killala Town and crosses the Cloonaghmore River. The bridge is located on the proposed construction haul route for the Tirawley Wind Farm.

The location of the bridge is indicated in Figure 1 below.



Figure 1 – Bridge Location

The JOD scope of works includes an inspection and report on the existing bridge. This report contains information and comments relating to the structural condition and defects present at the time of an inspection carried out by JOD and an assessment of the structural integrity of the bridge. No opening up of the structures was carried out at the time of the inspections.

The reporting on the bridges follows the same format as set out in the document entitled 'Bridge Asset Management System for Regional and Local Roads', September 2019, developed by the Department of Transport, Tourism and Sport, that sets out Guidelines for;

- Identifying the location of the structure and recording its dimensions The Bridge Inventory Survey (BIS);
- Assigning an initial rating to the structure Maintenance Inspections (MI);
- Assigning Component Condition Ratings to individual structure elements (cCR's) and an overall Condition Rating to the Structure – Engineering Inspections (EI).

All naming conventions are as per the above guidelines.

The hydrology industry standard for riverbank and abutment description has been adopted, i.e. the left-hand riverbank (LHB) is always when the observer is facing downstream as indicated in Figure 2 below.




Figure 2 - River Bank and Abutment Description

Figures 3, 4, 5 and 6 below, are taken from the Guidelines noted above and to indicate the various dimensions referenced in this report.



Figure 3 – Total Span




Figure 4 – Span, Width and Skew Angle



Figure 5 – Maximum and Minimum Span



Figure 6 – Overall Bridge Length

2. <u>VISUAL INSPECTION</u>

John McElvaney of JOD carried out visual inspection of the bridge on 10th of January 2023. The inspection included measurement of key dimensions and a record of the condition of the various elements of the bridge.

2.1. Stage 1 – Bridge Inventory Survey

| Access Hazard | Deep water; Fast moving v | vater | |
|------------------------|--|----------------------------------|--|
| Culvert | No | | |
| Structure Type | Arch | | |
| Location | Latitude: 54.225210 Longitude: -9.269215 | | |
| Road Number | R314 | | |
| Structure Number | MO-R314-031.00 | | |
| Structure Name (Alias) | Palmerstown Bridge | | |
| Structure Material | Masonry | | |
| Number of Spans | 11 | | |
| Total Span | 49.2 m | | |
| Maximum Span | 3.1 m | | |
| Minimum Span | 3.1 m | | |
| Structure Length | 67.2 m | | |
| Structure Width | 5.5 m | | |
| Principle Function | Public Road | | |
| Structure Over | Cloonaghmore River | | |
| Height of Opening | 2.4 m (approx.) | | |
| Slew Angle | 0° | | |
| Services Present | Yes | | |
| Comments | The bridge is a traditional | stone arch structure with stone | |
| | parapet walls on either side | e. | |
| | The carriageway width bet | tween parapets is approximately | |
| | 4.6 m. | | |
| | The parapets are approxim | nately 400 to 450 mm wide by | |
| | 750 to 900 mm high. | | |
| | The arch is approximately | 400 mm deep. | |
| | The depth of fill above the | arch is approximately 600 mm. | |
| | A watermain is attached to | the upstream side of the bridge. | |

2.2. Stage 2 – Maintenance Inspection

| Maintenance Inspection Rating | | | | | |
|---|-----|-------|-------|-------------------|--------------------|
| Main Element | Red | Amber | Green | Not Applicable | |
| Parapets | | ✓ | | | Ę |
| Access and Egress | | | ✓ | | Non- Structural |
| Vegetation | | ✓ | | | Str |
| External Walls | | | ✓ | | le. |
| Abutments and Piers | | | ✓ | | Structura |
| Deck or Arch | | | ✓ | | Str |
| See Appendix 1 for explanation of rating system | | | | | |

| Maintenance Inspection Notes | | |
|------------------------------|--|--|
| Parapets | Vegetation obscures parapet in places. Some minor damage observed. Repairs to parts of the parapets have recently been undertaken. | |
| Access and Egress | Access is OK. Fast flowing and deep water made access to closely inspect the abutments and arches unsafe. | |
| Vegetation | Vegetation on left and right hand ends of upstream parapet / side wall and on left hand side of downstream parapet / side wall. | |
| External Walls | No major issues. Walls are partly obscured by vegetation. | |
| Abutments and Piers | Appeared to be in good condition. | |
| Deck or Arch | Appeared to be in good condition. Road surface in good condition – no defects or rutting apparent. | |

2.3. Stage 3 – Engineering Inspection

| | Component Condition Rating (cCR) | | | | |
|--|--------------------------------------|---|---|---|--|
| Component | I Insignificant Damage (VL) | Some Damage (L) Repair when convenient | Significant Damage (M) Repair needed very soon | 4 Critical Damage (H) Repair needed immediately. Consider load restriction/propping | 5 Ultimate Damage (U) Bridge closure/lane restriction needed |
| Bridge Surface | ✓ | | | | |
| Footpath, Verges, Rubbing Strips, Medians | ✓ | | | | |
| Parapets and safety Rails | | ✓ | | | |
| Embankment and Revetments | ✓ | | | | |
| Wing Walls and Retaining Walls | ✓ | | | | |
| Abutments (also see riverbed) | ✓ | | | | |
| Piers (also see riverbed) | ✓ | | | | |
| Spandrels | ✓ | | | | |
| Arch Barrels and External Voussoirs | ✓ | | | | |
| Beams / Girders | N/A | | | | |
| Slab / Deck | N/A | | | | |
| Riverbed | ✓ | | | | |
| Bearings and Expansion Joints | N/A | | | | |
| OVERALL BRIDGE CONDITION RATING | 1 | 2 | 3 | 4 | 5 |
| See Appendix 2 for explana | tion of rating sy | stem | | | |

| Engineering Inspection Notes | | | | |
|------------------------------|--------------------------------|--|--|--|
| Number | Component | Comment | | |
| 1 | Arch and Abutments | Close inspection of the arches, abutments and piers was not possible on the day of inspection. No obvious defects were observed. We recommend that a close inspection of the underside of the structure is undertaken when water levels are lower. | | |
| 2 | Parapets and Spandrel Walls | Parapets and spandrels walls partly overgrown with vegetation. We recommend that this is removed when convenient. | | |
| 3 | Parapets | Some minor damage and missing stones were observed. | | |

2.4. Photographic Record



Photo No. 2.4.1Upstream side of bridge from the left riverbank.



Photo No. 2.4.2Upstream side of bridge from the right riverbank.



Photo No. 2.4.3Downstream side of bridge from the right riverbank.



Photo No. 2.4.4Bridge number sign.



Photo No. 2.4.5

General view of bridge from its northern end looking south.



Photo No. 2.4.6

Typical example of repairs carried out on parapet walls.



Photo No. 2.4.7

Typical example of repairs carried out on parapet walls.



Photo No. 2.4.8

Damage observed on downstream parapet wall.



Photo No. 2.4.9

Arch on downstream side of bridge.



Photo No. 2.4.10

Arch on downstream side of bridge. Note arch appears to be in good condition.



Photo No. 2.4.11

Arch on downstream side of bridge. Note arch

appears to be in good condition.



Photo No. 2.4.12
Side wall on downstream side in good condition.



Photo No. 2.4.13Watermain attached to upstream side of bridge.
Note vegetation.



Photo No. 2.4.14Watermain attached to upstream side of bridge.
Note vegetation.



Photo No. 2.4.15Watermain attached to upstream side of bridge.
Note vegetation.



Photo No. 2.4.16Downstream side wall. Note vegetation.

3. STRENGTH ASSESSMENT BY MEXE METHOD

Bridge in its Current Condition

An assessment of the masonry arch has been carried out in accordance with BA 16/97: The Assessment of Highway Bridges and Structures. The assessment uses the modified MEXE method, detailed in Chapter 3 of BA 16/97, and uses the measurements taken on site.




Figure 1 – Bridge dimensions for MEXE method

Arch dimensions used

Provisional Axle Loading (PAL) (BA 3.10)

PAL =
$$[740 \text{ x } (d+h)^2] / L^{1.3}$$
 or 70 (whichever is less)
= $[740 \text{ x } (0.4+0.6)^2] / 3.1^{1.3}$ or 70 (whichever is less)
= 170.0 or 70 (whichever is less)

PAL = 70 tonnes

Modifying factors (NRA Design for Roads and Bridges – Assessment of Masonry Arch Bridges by the Modified MEXE Method):

- Span/rise = 3.1 / 1.5 = 2.07

- Span/Rise Factor (F_{sr}) = 1.00 (as actual span / rise is less than 4 – figure 3.3)

- Profile Factor (F_p) = $2.3 [(r_c - r_q) / r_c]^{0.6}$

 $= 2.3 \left[(1.5 - 1.3) / 1.5 \right]^{0.6}$

= 0.67

- Material Factor (F_m) = $[(F_b \times d) + (F_f \times h)] / (d + h)$

Where:

- Barrel Factor (F_b) = 1.0 (Table 3.1)

- Fill Factor (F_f) = 0.7 (Table 3.2)

Therefore:

- Material Factor (F_m) = $[(1.0 \times 0.4) + (0.7 \times 0.6)] / (0.4 + 0.6)$

= 0.82

- Joint Factor (F_j) = $F_w \times F_d \times F_{mo}$

Where:

- Width Factor (F_w) = 0.9 (Table 3.3)

- Mortar Factor (F_{mo}) = 0.9 (Table 3.4) – Shotcrete to arch soffit

- Depth Factor (F_d) = 0.8 (Table 3.5)

Therefore:

- Joint Factor (F_i) = 0.9 x 0.9 x 0.8

= 0.65

- Condition factor (F_{cM}) = 0.9 (based on proven capacity and good condition)

- Axle Factors (A_f) = 1.0 (Figure 3.5a) (no axle lift-off)

 $\label{eq:modified_Axle_Loading} \qquad = \qquad \quad F_{sr} \ x \ F_p \ x \ F_m \ x \ F_j \ x \ F_{cM} \ x \ PAL$

 $= 1 \times 0.67 \times 0.82 \times 0.65 \times 0.9 \times 70.0$

= 22.5 tonnes

It should be noted that this capacity is for the arch alone, and that the capacity of the full bridge is a combination of several other elements including fill materials, buttresses and foundations. It should also be noted that this method can return quite variable results as the modifying factors are subjective.

Due to the span and generally good condition of the arch, it is within the parameters of the MEXE calculation method. Accordingly, it is concluded that currently this arch is capable of supporting the maximum axial load applied by movement of standard roadworthy vehicles.

4. CONCLUSIONS & RECOMMENDATIONS

In general, the bridge is currently in a good structural condition. Our assessment indicates that the bridge is capable carrying the loads exerted on it by standard roadworthy vehicles.

The arches have not lost their shape and the joints, as observed, appeared to be even.

It was not possible to ascertain the condition or nature of the foundations or formation soils during the inspection. These, however, appear to be performing adequately.

The upstream and downstream parapet walls range in height from approximately 750 mm to 900 mm.

The Modified MEXE Method concludes an axle load capacity of 22.5 tonnes for the bridge in its current state. This assumes that there is no axle lift off. Accordingly, it is concluded that the bridge is capable of supporting the maximum axial load applied by standard roadworthy vehicles.

We also conclude that the bridge is capable of supporting wind farm traffic to the proposed Tirawley Wind Farm.

The carriageway width between the parapets is 4.6 m. This should be checked against any abnormal delivery loads to confirm if it is sufficient. Abnormal loads for the delivery of turbine components have been assessed in the Turbine Delivery Route Report, refer to **Appendix 17.1** of the EIAR.

Appendix 1
Maintenance Inspection Rating System

Appendix 2
Component Condition Rating System