

## NOTES;

- I. ALL DIMENSION IN MILLISMETERS UNLESS OTHERWISE STATED
- 2. REINSTATEMENTS TO COMPLY WITH REQUIREMENTS OF THE RELEVANT LOCAL AUTHORITY/ASSET OWNER
- 3. ENTRANCE AND EXIT DUCTS TO BE IN LINE
- 4. ALL MATERIALS AND WORKMANSHIP TO BE IN ACCORDANCE WITH NRA/T.I.I. SPECIFICATION FOR ROADWORKS, MAY 2005 & SUBSEQUENT REVISIONS
- 5. REINFORCED CONCRETE TO BE MINIMUM GRADE C32 / 40, SULPHATE RESISTING CEMENT TO BE USED WHERE AGGRESSIVE SOIL CONDITIONS APPLY, REFER TO TABLE 6.1 OF THE BRITISH STANDARD 8110.
- 6. CARRAIGEWAY COVERS AND FRAMES TO BE TO B.S EN 124.
- 7. ALL COVERS SHALL HAVE "ESB" LOGO INCORPORATED IN THEM TO THE APPROVAL OF EIRGRID
- STEP IRONS TO BE GOT DIPPED GALVANISED TO B.S 729 AND POSITIONED AS SHOWN ON ANY CHAMBER DEEPER THAN 700mm ON THE END REMOTE FROM ANY SIDE ENTRY DUCT.
- CONCRETE PRECAST CHAMBER AND COVER TO BE TESTED THROUGH 5 POINTS, 40 TONNES VERTICAL STATIC LOADING TEST BY AN INDEPENDENT TEST COMPANY. IF REQUIRED, FURTHER DETAILS WILL BE PROVIDED BY EIRGRID.
- 10. FINAL POSITION OF C2 CHAMBERS SHALL BE AGREED WITH EIRGRID
- II. IN A FOREST ENVIROMENT, BACKFILL WITH LEAN MIX OUTSIDE THE COVER FRAME WHERE THE ASPHALT IS SHOWN.





C2 Chamber Detail - Section A

SCALE 1:20



C2 Chamber Detail - Section B





Isometric: C2 Chamber Arrangement

SCALE 1:20



Head Office Beenreigh, Abbeydorney, Tralee, Co. Kerry Ireland Tel: 00353 66 7135710 CLIENT

Futur=nergy

Scart Mountain Wind Farm 110 kV Grid Connection

PROJECT NUMBER 05-854

SHEET NUMBER **05854-DR-213** 

Typical Communications
Chamber Details
DRAWING STATUS
For Planning

RECESS TO BE I - 2mm MORE

ISSUE/REVISION			
	P1	10.06.2024	Issued for Planning
	I/R	DATE	DESCRIPTION