



APPENDIX 12-5

*NOISE MODELLING
PARAMETERS*

APPENDIX 12-5. NOISE MODELLING PARAMETERS

Prediction calculations for proposed turbine noise have been conducted in accordance with ISO 9613: *Acoustics – Attenuation of sound outdoors, Part 2: General method of calculation*, 2024. Guidance in terms of the calculation settings has been obtained from the *Institute of Acoustics (IOA) Good Practice Guide to the Application of ETSU-R-97 for the Assessment and Rating of Wind Turbine Noise* (2013) (IOA GPG) and its associated supplementary guidance notes. The following are the main aspects that have been considered in terms of the noise predictions presented in this instance.

Ground Effect: Ground effect is the result of sound reflected by the ground interfering with the sound propagating directly from source to receiver. The prediction of ground effects is inherently complex and depend on source height receiver height propagation height between the source and receiver and the ground conditions.

The ground conditions are described according to a variable defined as G , which varies between 0.0 for hard ground (including paving, ice concrete) and 1.0 for soft ground (includes ground covered by grass trees or other vegetation).

Noise predictions have been carried out using a source height corresponding to the hub height of the proposed turbines, a receiver height of 4m and a ground effect factor of $G=0.5$.

Geometrical Divergence This term relates to the spherical spreading in the free-field from a point sound source resulting in an attenuation depending on distance according to the following equation:

$$A_{geo} = 10 \log(d) - 11 \text{ dB}$$

where d = distance from the source

A wind turbine may be considered as a point source beyond a distance corresponding to one rotor diameter.

Atmospheric Adsorption Sound propagation through the atmosphere is attenuated by the conversion of the sound energy into heat. This attenuation is dependent on the temperature and relative humidity of the air through which the sound is travelling and is frequency dependent with increasing attenuation towards higher frequencies.

In accordance with the guidance set out in the IOA GPG for calculations, a temperature of 10°C and a relative humidity of 70% have been used, which give relatively low levels of atmosphere attenuation and corresponding worst case noise predictions.

Topographic Screening In the IOA GPG, section 4.3.11 the following is stated: "*Topographic screening effects of the terrain (ISO 9613-2, Equation 12) should be limited to a reduction of no more than 2 dB, and then only if there is no direct line of sight between the highest point on the turbine rotor*

and the receiver location." The modelling software takes account of these limitations on the degree of screening from terrain. The "valley correction" from section 4.3.9 of the IOA GPG is also applied where relevant.