

GENERAL POLLUTION PREVENTION NOTES:

1. SITE MANAGEMENT PROPOSALS ARE INTENDED TO ENSURE PROTECTION AGAINST SURFACE WATER AND GROUNDWATER POLLUTION, SILTATION AND EROSION.
2. SUITABLE DRAINAGE CONTROL MEASURES WILL BE IN PLACE AT ALL TIMES TO PREVENT CONVEYANCE OF SIGNIFICANT VOLUMES OF SILT TO OFF SITE RECEIVING WATERCOURSES.
3. SILTY WATER CAN ARISE FROM DEWATERING EXCAVATIONS, EROSION OF EXPOSED/DISTURBED GROUND, TEMPORARY STOCKPILES, PLANT AND WHEEL WASH, SITE ROADS/TRACKS, AND DISTURBANCE OF EXISTING FIELD DRAINS AND DITCHES.

DISCHARGES

4. WATER CONTAINING SILT WILL NOT BE DISCHARGED OR PUMPED DIRECTLY TO ANY NATURAL WATERCOURSE. ALL DISCHARGES WILL BE MADE OVER OPEN GROUND OR INTO EXISTING FIELD DRAIN WITH SILT TRAP AT A MINIMUM OF 20M FROM NEAREST WATERCOURSE UNLESS OTHERWISE STATED.
5. NO EXCAVATED MATERIAL WILL BE STORED WITHIN ANY SURFACE WATER BUFFER ZONE.
6. PUMPED WATER WILL BE DIRECTED INTO TRACK SIDE DITCHES AND TREATED IN SETTLEMENT PONDS AND VEGETATION SWALES PRIOR TO OVERLAND DISCHARGE.
7. PUMPING OF CLEAN WATER FROM EXCAVATIONS / OR OVER-CUMPING IN DRAINS/DITCHES/STREAMS WILL BE COMPLETED IN A MANNER THAT WILL NOT CAUSE SCOUR OR EROSION AT THE POINT OF RELEASE/DISCHARGE. THIS WILL BE DONE BY REDUCING THE FLOW VELOCITIES OR BY USE OF SUITABLE SPLASH PLATES, AND/OR OTHER SIMILAR DISCHARGE CONTROLS.
8. VEGETATION WILL NOT BE STRIPPED FROM EXISTING DRAINS/DITCHES UNLESS ABSOLUTELY NECESSARY.

EXCAVATIONS

9. WHERE (TEMPORARY) DEEP EXCAVATIONS ARE PROPOSED, CUT-OFF DRAINS WILL BE USED TO REDUCE THE AMOUNT OF SURFACE WATER ENTERING THE EXCAVATION. THIS WILL BE THE CASE AROUND TURBINE BASE EXCAVATIONS.

EXPOSED GROUND & STOCKPILES

10. THE AMOUNT OF TEMPORARY EXPOSED GROUND AND TEMPORARY STOCKPILES OPEN/EXPOSED AT ANY TIME WILL BE MINIMISED.

SITE TRACKS

11. USE OF TRACK SIDE SWALES WITH CHECK DAMS, AND/OR FILTRATION CHECK DAMS WILL REDUCE SILT IN RUNOFF WATER AS REQUIRED.
12. CHECK DAMS TO BE INSPECTED AND CLEANED REGULARLY.

REFUELLING

13. REFUELLING OF MOBILE PLANT WILL BE COMPLETED IN DESIGNATED REFUELLING AREAS ONLY, ON AN IMPERMEABLE SURFACE AND AWAY FROM FIELD DRAINS / DITCHES AND WATERCOURSES/WATERBODIES.

CONCRETE

14. SPILL KITS AND DRIP TRAYS WILL BE AVAILABLE ON SITE FOR USE AS REQUIRED.
15. CONCRETE POURS WILL BE MANAGED AND SUPERVISED TO ENSURE THERE WILL BE NO LEAKAGE/SEEPAGE/DISCHARGE OF CONCRETE OR CONCRETE WATER DURING THE CONSTRUCTION PHASE.
16. CONCRETE WASH WATER, AND WASTE CONCRETE WILL BE MANAGED APPROPRIATELY ON SITE AT A LINED CONCRETE WASH OUT PIT.


IF WATER POLLUTION IS IDENTIFIED THE FOLLOWING STEPS WOULD BE ADHERED TO:

STOP – WORK IN THE IMMEDIATE AREA SHOULD BE STOPPED AND THE SOURCE OF THE POLLUTION IDENTIFIED.

CONTAIN – THE SOURCE OF THE POLLUTION SHOULD BE BUNDED USING A SUITABLE METHOD. NATURAL WATERCOURSES SHOULD BE TEMPORARILY DIVERTED AROUND ANY SOURCE OF POLLUTION.

NOTIFY – THE RELEVANT AUTHORITIES (SITE MANAGER / FISHERIES / NPWS / LOCAL AUTHORITY ETC.) SHOULD BE NOTIFIED IMMEDIATELY TO ENSURE THAT MEASURES CAN BE IMPLEMENTED DOWNSTREAM TO PROTECT FISHERIES AND OTHER SENSITIVE RECEPTORS.

CULVERT CROSSING DETAILS	
CROSSING NR.	SIZE
15 (EC19)	450MM
16	225MM
17	225MM
18	300MM
19	300MM
47 (PC2)	600MM
48 (PC2)	900MM
50 (EC15)	900MM
51 (EC4)	900MM
52	450MM
53 (EC3)	600MM
54	900MM
55 (EC2)	450MM
56 (EC1)	300MM
57	450MM
58	450MM
59	450MM
68	450MM
70	300MM
71	450MM




PROSPECTIVE DRAINAGE NOTES:

1. EXISTING DRAINAGE LAYOUT IS BASED ON MAPPING COMPLETED BY ENERO, HES, AND MKO, BY BOTH VISUAL INSPECTION AND BY DRONE SURVEYS.
2. EXISTING DRAINAGE REFLECTS ALL RESIDUAL DRAINS, CULVERTS, SETTLEMENT PONDS, SILT TRAPS AND SILT FENCING INSTALLED AS PART OF PREVIOUS CONSTRUCTION WORKS.
3. ONLY THE DOWNSTREAM CONNECTIONS TO WATERCOURSES VIA THE FORESTRY DRAINAGE NETWORK ARE SHOWN FOR EACH WIND FARM OUTFALL. THE ENTIRE DOWNSTREAM FORESTRY DRAINAGE NETWORK IS NOT SHOWN.
4. FROM THOSE WIND FARM OUTFALL LOCATIONS TREATED DRAINAGE WATER MAKES ITS WAY DOWNHILL AS SHOWN.
5. ADDITIONAL DRAINAGE ASSOCIATED WITH PROSPECTIVE DEVELOPMENT ARE PROPORTIONATE TO THE WORKS THAT ARE INTENDED IN EACH AREA. THIS IS BECAUSE MUCH OF THE EXISTING WIND FARM DRAINAGE NETWORK IS IN PLACE AND ALREADY STABLE AND FUNCTIONING CORRECTLY.
6. PREVIOUS WATER QUALITY MONITORING DEMONSTRATES THAT THE EXISTING WIND FARM DRAINAGE NETWORK IS SUFFICIENT TO PROTECT DOWNSTREAM WATER QUALITY.
7. MORE SIGNIFICANT ADDITIONAL DRAINAGE INFRASTRUCTURE IS PROPOSED IN AREAS WHERE THE MAIN ADDITIONAL WORKS ARE PROPOSED (I.E. AT BORROW PITS 2 AND 3, ACCESS TRACK TO T18, T18 AREA, ACCESS TRACK TO T2, T2 AREA, T11 AREA).
8. THE PROPOSED DRAINAGE REPLICATES WHAT WORKED WELL FROM THE EXISTING DRAINAGE LAYOUT, I.E. USE OF INTERCEPTOR/COLLECTOR DRAINS, SILT FENCING, SILT TRAPS, SETTLEMENT PONDS, AND ROUTING TREATED DRAINAGE DOWNSTREAM VIA EXISTING FORESTRY DRAINAGE NETWORK.

SITE ENTRANCE DETAILS SHOWN ON MNBG d051.1.0

PROPOSED AMENITY INFRASTRUCTURE (REFER TO MNBG d051.1.1)

PROPOSED FOOTBRIDGE (REFER TO MNBG d051.3.1)



DRAWING LEGEND :

- PLANNING APPLICATION BOUNDARY
- EXISTING DEVELOPMENT FOOTPRINT
- SITE LAYOUT IS UNDERLAIN BY 1M INTERVAL CONTOURS TO MOD MALIN HEAD
- SLOPE / DRAINAGE DIRECTION
- WATERCOURSES
- WATERCOURSE BUFFER 50M
- LAKES
- LAKES 50M BUFFER
- EXISTING NATURAL DRAINS
- DOWNSTREAM FORESTRY DRAIN
- EXISTING DRAINS
- EXISTING SETTLEMENT PONDS
- EXISTING CULVERT LOCATIONS
- EXISTING SILT FENCES (SF*)
- *SF - SINGLE SILT FENCE, DSF - DOUBLE SILT FENCE, MSF - MULTIPLE SILT FENCES
- EXISTING SILT TRAPS (SST*)
- *SST - SINGLE SILT TRAP, DST - DOUBLE SILT TRAP, MST - MULTIPLE SILT TRAPS
- UPSTREAM INTERCEPTOR DRAIN
- SWALES / DOWNSTREAM COLLECTOR DRAIN
- SETTLEMENT POND - VEGETATION FILTER - LEVEL SPREADER
- CHECK DAM 'TYPE B'
- DIRECTION OF FLOW
- PROPOSED SILT FENCE
- PROPOSED SILT TRAPS (PST)
- SETTLEMENT POND
- PROSPECTIVE DEVELOPMENT FOOTPRINT

- DRAWING NOTES
1. DRAWINGS ISSUED ARE FOR PLANNING APPLICATION PURPOSES ONLY.
 2. COPYRIGHT, ALL RIGHTS RESERVED. NO PART HERE WITH MAY BE COPIED OR REPRODUCED PARTIALLY OR WHOLLY IN ANY FORM WHATSOEVER WITHOUT THE PRIOR NOTICE OF THE COPYRIGHT OWNER HYDRO-ENVIRONMENTAL SERVICES.
 3. DO NOT SCALE OFF THIS DRAWING. FIGURED METRIC DIMENSIONS ONLY SHOULD BE TAKEN OFF THIS DRAWING.
 4. ALL DIMENSIONS ARE IN METRES.

Ordnance Survey Ireland Licence No. EN 0044726
© Ordnance Survey Ireland/Government of Ireland

Date	Description	Chkd	Signed
Revisions			

HYDRO ENVIRONMENTAL SERVICES

22 Lower Main St
Dungarvan
Co. Waterford
Ireland

tel: +353 (0) 58-44122
tel: +353 (0) 58-44244
email: info@hydroenvironmental.ie
web: www.hydroenvironmental.ie

Client: **PLANREE LTD**

Job: **MEENBOG WIND FARM, CO. DONEGAL**

Title: **PROSPECTIVE DEVELOPMENT DRAINAGE LAYOUT SHEET 3 OF 6**

Figure No: **D103**

Drawing No: P1249-9-0626-A1-D103-00A	
Sheet Size: A1	Project No.: P1249-9
Scale: 1:2,500 (A1)	Drawn By: MG/GA
Date: 25/06/2026	Checked By: MG