DETAIL 1: NEW ACCESS JUNCTION
SCALE 1:100 @A1



TYPICAL SECTION THROUGH NEW ACCESS JUNCTION:
SCALE 1:50 @A1

KEY:

- SITE BOUNDARY
- PROPOSED FOOTPATH
- PROPOSED ROAD
- PROPOSED HOMEZONE
- PERMEABLE PAVING
- TACTILE PAVING
- LANDSCAPING TO LANDSCAPE ARCHITECT'S SPECIFICATION
- EXISTING CONTOURS
- REAR GARDEN LANDSCAPING
- PROPOSED BUILDING OUTLINE
- SECURE BICYCLE PARKING UNIT
- VISITOR CYCLE PARKING SHEFFIELD STANDS
- CORDUROY PAVING

SCHEDULE OF ROAD MARKINGS

REF No.	LENGTH OF LINE (m)	LENGTH OF GAP (m)	WIDTH OF LINE (m)	COLOUR	KEY
RRM 001	CONTINUOUS	N/A	0.10	WHITE	
RRM 017	CONTINUOUS	N/A	0.20	WHITE	
RRM 018	1.0	1.0	0.20	WHITE	
M 112	TRAFFIC CALMING TRIANGLE AS PER SECTION 7.17 DOT TRAFFIC SIGNS MANUAL 2010			WHITE	
M 114	STOP MARKING AS PER SECTION 7.5 DOT TRAFFIC SIGNS MANUAL 2010			WHITE	STOP
M 115	TRIANGULAR YIELD MARKING AS PER SECTION 7.5 DOT TRAFFIC SIGNS MANUAL 2010			WHITE	
M 116	CYCLE SYMBOL AS PER SECTION 7.8 DOT TRAFFIC SIGNS MANUAL 2010			WHITE	
M 111	PEDESTRIAN SYMBOL AS PER SECTION 7.8 DOT TRAFFIC SIGNS MANUAL 2010			WHITE	
	ELEPHANT FEET MARKINGS (400mm wide, 40mm gap, 400mm mark)			WHITE	

SCHEDULE OF ROAD SIGNAGE

(FOR POLE SPECS, HEIGHTS AND POSITIONS REFER TO DOT TRAFFIC SIGNS MANUAL)

REF No.	DESCRIPTION	SIGN
RUS 026	YIELD SIGN	
RUS 027	STOP SIGN	
W 143 & P 005	POLE WITH WARNING SIGNS W 143 & P 005	

FOR PLANNING

REV	DESCRIPTION	BY	DATE
P01	FOR COSTING	IO	27.02.26
P02	FOR COSTING	IO	18.03.26
P03	PART 8 PLANNING	ED	27.05.26
P04	PART 8 PLANNING	ED	19.06.26
P05	PART 8 PLANNING	IO	06.07.26
P06	PART 8 PLANNING	AL	15.07.26

NOTES:

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT ARCHITECTURAL AND ENGINEERING DRAWINGS, ANY DISCREPANCIES, ERRORS OR OMISSIONS TO BE BROUGHT TO THE ATTENTION OF THE DESIGNER.
2. ALL DIMENSIONS TO BE CHECKED BY THE CONTRACTOR ON SITE PRIOR TO COMMENCEMENT OF WORKS.
3. ALL UNITS ARE IN METERS UNLESS OTHERWISE STATED.
4. ALL LEVELS ARE IN METERS TO MALIN HEAD ORDNANCE DATUM.
5. MEINHARDT LIMITED TO BE INFORMED BY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO THE COMMENCEMENT OF WORKS ON SITE.
6. DIMENSIONS OF ALL BOUNDARIES AND ADJOINING ROADS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
7. DO NOT SCALE, ALL MEASUREMENTS AND COORDINATES TO BE CHECKED ON SITE.
8. PLEASE REFER TO LANDSCAPE ARCHITECTS DRAWINGS FOR LANDSCAPING DETAILS.

MEINHARDT
The Greenway, Block C - Ardilaun Court, St. Stephen's Green, Dublin 2, D02 TD28
Telephone: +353 (0)1 525 2515
www.meinhardt.ie

PROJECT
NEW RESIDENTIAL DEVELOPMENT
HARBOUR ROAD
MULLINGAR, Co. WESTMEATH.

CLIENT
WESTMEATH COUNTY COUNCIL

TITLE
GENERAL ARRANGEMENT LAYOUT

DISCIPLINE			SCALE
CIVIL			1:500
DRAWN	DESIGNED	CHECKED	APPROVED
IO	AL	AL	BM
DRAWING No			ISSUE
26019-MHT-XX-ZZ-DR-C-0100			P06

DATE: 07/07/2026
FILE LOCATION: J:\PROJECTS\26019 - HARBOUR ROAD, MULLINGAR\1. MHTBIM\101 - CIVIL\01 - WIP\02 - SHEETS\26019-MHT-XX-ZZ-DR-C-0100.DWG

© MEINHARDT (IE). ALL RIGHTS RESERVED