

Lissinagroagh Wind Farm 110kV Grid Connection

CLIENT

FuturEnergy Ireland

CONSULTANTS

TOBIN
CONSULTING ENGINEERS

NOTES: -

LEGEND: -

- | | |
|---|--|
|  | 160mm Ø HDPE
POWER DUCT WITH
12mm DIAMETER PULL ROPE |
|  | 125mm Ø HDPE
COMMUNICATION DUCT WITH
12mm DIAMETER PULL ROPE |
|  | 125mm Ø HDPE
EARTH CONTINUITY CONDUCTOR
WITH 12mm DIAMETER PULL ROPE |
|  | RED MARKER STRIP OR
STEEL PLATES |
|  | YELLOW MARKER
WARNING TAPE |
|  | 6mm GALVANISED STEEL
PLATE |
|  | EXISTING SERVICE TAPE |

ISSUE/REVISION

P02	21.04.26	Issued for Planning
P01	20.04.26	Issued for Planning
P00	12.01.26	Issued for Planning
I/R	DATE	DESCRIPTION

PROJECT NUMBER

05-773

SHEET TITLE

Trench Sections For Overcrossing Existing Culvert/Service

SHEET NUMBER

05773-DR-127



SERVICE OVERCROSSING



- ## GENERAL NOTES

1. This drawing is subject to Design approval and is not to be used for construction.
2. This drawing is to be read in conjunction with all other relevant documentation.
3. Do not scale from this drawing use only printed dimensions
4. All dimensions are in millimetres, all chainages, levels and co-ordinates are in metres unless defined otherwise.
5. No excavation shall commence until the Contractor has consulted up to date services drawings and carried out an Electromagnetic Locator (EML) Scan.
6. Hand dig only within 500mm of existing services.
7. If compacting CBGM B could cause damage to the culvert / service below, use rapid hardening cement grade C25/30 following engineers prior approval.
8. For standard trench cross section drawings and minimum horizontal separation to existing services, see 05773-DR-119a (TREFOIL) and 05773-DR-124 (FLAT).
9. Where depths exceed 2500mm to the top of duct the Contractor shall consult the cable system design engineer for phase spacing requirements.
10. Backfill as per guidelines for the opening, backfilling and reinstatement of openings in public roads (2015).
11. **ESB's preference is to cross under existing services where possible.**
12. Backfill as per guidelines for the opening, backfilling and reinstatement of openings in public roads (2015)
13. The Contractor is responsible for the design and construction of all temporary works. The Contractor shall appoint a temporary works designer, and submit temporary works design to PSDP for review.
14. 225mm minimum concrete over ducts where they transition from standard cross section and where they are at less than standard cover to ground level.
15. Replace existing service marker tape over Yellow marker tape.
16. The owner of the existing utility being crossed must be consulted in advance of works commencing as per their guidelines.
17. The Contractor shall record detailed as-built information as per the specification. At all crossing locations these records shall include photographic evidence clearly demonstrating that minimum service clearances and duct separations have been achieved.