RECEIVED: 05/08/2026

Environmental Impact Assessment Report

Kingston Stables, Knocknacarra West Proposed Large-Scale Residential Development

RECEIVED: 05/08/2026

DOCUMENT DETAILS

Kingston Stables Ltd

Kingston Stables Knocknacarra Proposed Large-Scale Residential Development

Rev	Status	Date	Author(s)	Approved By
01	Final	24/07/2026	EC, TM, KM, KF, ES, FK, CK, PD, SM, CLS, MK, TP, RM, DM, LCE, DC, CM, KG, CW, JR, AB, MK, DB, SF, CB, MMG, AF, JW, MG	KM

RECEIVED: 05/08/2026

Table of Contents

TABLE OF CONTENTS.....i

TABLE OF TABLES.....xi

TABLE OF FIGURES.....xvii

TABLE OF PLATES.....xix

TABLE OF APPENDICES.....xxii

NON-TECHNICAL SUMMARY.....xxiv

1. INTRODUCTION 1-1

1.1 General Introduction 1-1
1.1.1 Development Referencing 1-1
1.2 Brief Description of the Proposed Development 1-2
1.3 Background to the Proposed Development 1-2
1.4 The Applicant 1-3
1.5 Need for the Proposed Development 1-6
1.6 Legislative Context 1-6
1.6.1 Introduction 1-6
1.6.2 EIA Screening 1-7
1.6.3 EIAR Guidance 1-8
1.7 Purpose and Scope of the EIAR 1-8
1.8 Structure and Content of the EIAR 1-8
1.8.1 General Structure 1-8
1.8.2 Description of Likely Significant Effects and Impacts 1-9
1.9 Project Team 1-11
1.9.1 Project Team Members 1-12
1.9.1.1 MKO 1-12
1.9.1.2 Tobin Consulting Engineers 1-18
1.9.1.3 John Cronin and Associates 1-18
1.10 Difficulties Encountered 1-19
1.11 Viewing and Purchasing the EIAR 1-19

2. BACKGROUND TO THE PROPOSED DEVELOPMENT 2-1

2.1 Introduction 2-1
2.2 Site of the Proposed Development 2-1
2.2.1 Site Location 2-1
2.2.2 Physical Characteristics of Site and Surrounding Lands 2-3
2.2.3 Site Access 2-5
2.2.4 Proposed Development in context of adjacent developments 2-5
2.3 Planning History 2-6
2.3.1 Planning Applications within the Proposed Project Boundary 2-7
2.3.2 Other Planning Applications within the Vicinity of the Proposed Development Site 2-9
2.4 Planning Policy 2-11
2.4.1 National Planning Policy 2-11
2.4.1.1 Project Ireland 2040 National Planning Framework First Revision (April 2025) 2-11
2.4.1.2 Design Manual for Urban Roads and Streets (DMURS) 2-13
2.4.1.3 The Cycle Design Manual (CDM) 2-14
2.4.1.4 Climate Action Plan 2025 2-14
2.4.2 Section 28 Ministerial Guidelines 2-15

RECEIVED: 05/08/2026

2.4.2.1 Urban Development and Building Heights Guidelines for Planning Authorities 2018 2-15
2.4.2.2 Planning Design Standards for Apartments Guidelines for Planning Authorities, 2025 2-15
2.4.2.3 Sustainable Residential Development and Compact Settlements: Guidelines for planning Authorities 2024 2-16
2.4.2.4 Childcare Facilities - Guidelines for Planning Authorities 2001 2-16
2.4.2.5 The Planning System and Flood Risk Management, Guidelines for Planning Authorities (2009) 2-17
2.4.3 Regional Planning Policy Context 2-17
2.4.3.1 Regional Spatial and Economic Strategy Northern & Western Regional Assembly 2020-2032 2-17
2.4.4 Local Planning Policy Context 2-18
2.4.4.1 Galway City Development Plan 2023-2029 2-18
2.4.4.2 Galway Urban Density and Building Heights Study 2021 2-20
2.5 Scoping and Consultation 2-20
2.5.1 Scoping Responses 2-21
2.5.2 Pre-Planning Meetings 2-30
2.5.2.1 Stage 1: Section 247 Meeting with Galway City Council 2-30
2.5.2.2 Stage 2: LRD Preplanning Meeting with Galway City Council 2-30
2.6 Cumulative Impact Assessment 2-30
2.6.1 Methodology Adopted 2-31
2.6.2 Cumulative Study Area 2-31
2.6.3 Projects Considered 2-34

3. REASONABLE ALTERNATIVES 3-1

3.1 Introduction 3-1
3.2 Consideration of Alternatives 3-2
3.3 Methodology 3-2
3.4 "Do-Nothing Alternative" 3-3
3.5 Alternative Locations 3-6
3.6 Alternative Design and Layouts 3-7
3.6.1 Background 3-7
3.6.2 Proposed Development Layout Evolution 3-7
3.6.2.2 Links and Connectivity 3-13
3.6.2.3 Transport 3-13
3.6.2.4 Green Infrastructure 3-13
3.6.2.5 Neighbourhoods 3-13
3.7 Alternative Land Uses 3-14
3.8 Alternative Processes 3-14
3.9 Alternative Mitigation 3-14

4. DESCRIPTION OF THE PROPOSED DEVELOPMENT 4-1

4.1 Introduction 4-1
4.2 Site Setting 4-2
4.2.1 Site Description 4-2
4.3 Proposed Site Development 4-5
4.3.1 Development Description 4-5
4.4 Construction Management 4-6
4.4.1 Construction Timing and Phasing 4-6
4.4.2 Working Hours 4-6
4.4.3 Construction Phase Monitoring and Oversight 4-6
4.5 Construction Methodologies 4-7
4.5.1 Site Establishment 4-7
4.5.2 Perimeter Fencing 4-7
4.5.3 Demolition Works 4-8
4.5.4 Site Excavation 4-8
4.5.5 Traffic Measures and Junction Upgrade Works 4-9
4.5.6 Proposed Site Roads and Footpaths 4-9
4.5.7 Services and Utilities 4-9
4.5.8 Residential Unit Construction 4-11
4.5.9 Landscaping Works 4-11
4.6 Management of Construction Phase Activities 4-12
4.6.1 Environmental Management 4-12

RECEIVED: 05/08/2026

4.6.2 Proposed Drainage Design 4-12
4.6.3 Protecting Water Quality 4-13
4.6.3.1 Prevention Pollution Control Measures 4-13
4.6.3.2 Cement Based Products Control Measures 4-15
4.6.3.3 Refuelling, Fuel and Hazardous Materials Storage 4-16
4.6.4 Dust Control 4-16
4.6.5 Noise Control 4-17
4.6.6 Vibration Control 4-18
4.6.7 Ecological Measures 4-19
4.6.8 Invasive Species Management 4-19
4.6.8.1 Treatment and Management Methodologies 4-20
4.6.8.2 Preliminary Stages 4-20
4.6.8.3 Three- Cornered Leek 4-20
4.6.8.4 Sea Buckthorn 4-21
4.6.8.5 Post Treatment Monitoring 4-21
4.6.8.6 Site Hygiene 4-22
4.6.9 Traffic Management 4-22
4.6.10 Archaeological Mitigation Measures 4-23
4.6.11 Waste Management 4-23
4.7 Operational Phase 4-24
4.7.1 Property Management – Operational Stage 4-24
4.7.2 Sustainable Energy Use 4-25
4.8 Decommissioning Phase 4-25

5. POPULATION AND HUMAN HEALTH 5-1

5.1 Introduction 5-1
5.2 Background 5-1
5.3 Statement of Authority 5-1
5.4 Relevant Legislation and Guidance 5-2
5.5 Scoping and Consultation 5-3
5.6 Methodology 5-4
5.6.1.1 Population 5-4
5.6.1.2 Health 5-4
5.6.1.3 Population and Human Health Study Area 5-5
5.6.2 Limitations and Difficulties Encountered 5-5
5.7 Receiving Environment 5-8
5.7.1 Population Baseline 5-8
5.7.1.1 Population Trends 5-8
5.7.1.2 Population Density 5-9
5.7.1.3 Household Statistics 5-10
5.7.1.4 Age Structure 5-10
5.7.1.5 Employment and Economic Activity 5-11
5.7.1.6 Land Use 5-13
5.7.1.7 Local Amenities 5-13
5.7.1.8 Tourism 5-14
5.7.1.9 Residential Amenity 5-16
5.7.2 Health Baseline 5-16
5.7.2.1 Air Quality 5-17
5.7.2.2 Water Quality 5-17
5.7.2.3 Traffic and Transport 5-18
5.7.2.4 Noise and Vibration 5-18
5.7.2.5 Vulnerability of the Project to Natural Disaster and Major Accidents 5-18
5.8 Likely Significant Effects and Associated Mitigation Measures 5-19
5.8.1 Do-Nothing Scenario 5-19
5.8.2 Construction Phase- Population 5-19
5.8.2.1 Population Levels 5-19
5.8.2.2 Employment and Investment 5-19
5.8.2.3 Land-use 5-20
5.8.2.4 Tourism 5-21
5.8.2.5 Residential Amenity 5-21
5.8.3 Construction Phase- Health 5-22
5.8.3.1 Health and Safety 5-22
5.8.3.2 Air Quality 5-23
5.8.3.3 Water Quality 5-24
5.8.3.4 Traffic and Transport 5-24
5.8.3.5 Noise and Vibration 5-25

RECEIVED: 05/08/2026

5.8.3.6 Major Accidents and Natural Disasters 5-26
5.8.4 Operational Phase- Population 5-27
5.8.4.1 Population 5-27
5.8.4.2 Employment and Investment 5-28
5.8.4.3 Land-use 5-28
5.8.4.4 Tourism 5-29
5.8.4.5 Residential Amenity 5-29
5.8.5 Operational Phase- Health 5-30
5.8.5.1 Air Quality 5-30
5.8.5.2 Water Quality 5-30
5.8.5.3 Traffic and Transport 5-31
5.8.5.4 Noise and Vibration 5-32
5.8.5.5 Major Accidents and Natural Disasters 5-32
5.8.6 Cumulative Impact Assessment 5-33

6. BIODIVERSITY 6-1

6.1 Introduction 6-1
6.2 Requirements for Ecological Impact Assessment 6-5
6.3 Review of Relevant Guidance and Sources of Consultation 6-7
6.3.1 Statement of Authority 6-8
6.4 Methodology 6-8
6.4.1 Desk Study 6-8
6.4.2 Scoping and Consultation 6-9
6.4.3 Field Surveys 6-10
6.4.3.1 Multi-disciplinary Walkover Surveys 6-11
6.4.3.2 Bird Surveys 6-11
6.4.3.3 Bat Survey 6-14
6.4.3.4 Non-volant Mammal Surveys 6-18
6.4.3.5 Invasive Species Survey 6-18
6.4.3.6 Survey limitations 6-19
6.4.4 Methodology for Assessment of Impacts and Effects 6-19
6.4.4.1 Identification of Target Receptors and Key Ecological Receptors 6-19
6.4.4.2 Determining Importance of Ecological Receptors 6-19
6.4.4.3 Characterisation of Impacts and Effects 6-20
6.4.4.4 Determining the Significance of Effects 6-20
6.4.4.5 Incorporation of Mitigation 6-21
6.5 Establishing the Ecological Baseline 6-22
6.5.1 Desk Study 6-22
6.5.1.1 Designated Sites 6-22
6.5.1.2 Article 17 Reporting 6-39
6.5.1.3 Protected Flora 6-39
6.5.1.4 National Biodiversity Data Centre (NBDC) Records 6-39
6.5.1.5 NPWS Protected Species Records 6-43
6.5.1.6 Invasive Species 6-44
6.5.1.7 Freshwater Pearl Mussel (*Margaritifera margaritifera*) 6-45
6.5.1.8 Hydrology 6-45
6.5.1.9 Conclusions of the Desktop Study 6-46
6.6 Ecological Walkover Survey Results 6-47
6.6.1 Description of Habitats, Flora & Fauna within the Ecological Survey Area 6-47
6.6.1.1 Habitats within the Proposed Development Site Boundary 6-50
6.6.1.2 Protected Flora 6-62
6.6.1.3 Invasive species 6-62
6.6.1.4 Fauna in the Existing Environment 6-66
6.6.2 Importance of Ecological Receptors 6-79
6.7 Ecological Impact Assessment 6-83
6.7.1 Do-Nothing Scenario 6-83
6.7.2 Construction Phase 6-83
6.7.2.1 Impacts on Habitats 6-83
6.7.2.2 Impacts on Water Quality 6-85
6.7.2.3 Invasive Species 6-87
6.7.2.4 Impacts on Fauna 6-89
6.7.3 Biosecurity and Site Hygiene 6-93
6.7.4 Operational Phase 6-95
6.7.4.1 Impacts on Habitats 6-95
6.7.4.2 Impacts on Water Quality 6-95
6.7.4.3 Impacts on Fauna 6-96
6.7.5 Decommissioning Phase 6-98

RECEIVED: 05/08/2026

6.7.6 Effects on Designated Sites 6-98
6.8 Cumulative Impacts 6-99
6.8.1 Assessment of Plans 6-99
6.8.2 Assessment of Projects 105
6.8.2.1 Proposed Development & Other Projects 105
6.8.2.2 Proposed Project & Other Projects 106
6.8.3 Assessment of Cumulative Effects 107
6.9 Conclusion 108

7. LAND, SOILS AND GEOLOGY 7-1

7.1 Introduction 7-1
7.1.1 Background & Objectives 7-1
7.1.2 Statement of Authority 7-1
7.1.3 Relevant Legislation 7-1
7.1.4 Relevant Guidance 7-2
7.2 Assessment Methodology 7-2
7.2.1 Desk Study 7-2
7.2.2 Baseline Data & Site Investigations 7-2
7.2.3 Scoping & Consultation 7-3
7.2.4 Impact Assessment Methodology 7-3
7.2.4.1 Importance/Sensitivity of the Existing Environment 7-3
7.2.4.2 Magnitude of Effects 7-4
7.3 Receiving Environment 7-6
7.3.1 Existing Landuse & Topography 7-6
7.3.2 Soils and Subsoils 7-6
7.3.3 Bedrock Geology 7-11
7.3.4 Geological Heritage and Designated Sites 7-11
7.3.5 Soil Contamination 7-11
7.3.6 Economic Geology 7-11
7.4 Receptor Sensitivity & Importance 7-12
7.5 Characteristics of the Proposed Development 7-12
7.5.1 Drainage and Utilities 7-12
7.6 Potential Impacts of the Proposed Development 7-13
7.6.1 Do Nothing Scenario 7-13
7.6.2 Likely Significant Effects and Mitigation Measures – Construction Stage 7-13
7.6.2.1 Subsoil Excavation and Bedrock Excavation 7-13
7.6.2.2 Contamination of Soil by Leakages and Spillages and Alteration of Soil Geochemistry 7-14
7.6.3 Potential Impacts and Mitigation Measures – Operational Stage 7-15
7.6.3.1 Assessment of Health Effects 7-15
7.6.4 Potential Cumulative Effects 7-15
7.7 Conclusion 7-16
7.8 Bibliography 7-18

8. HYDROLOGY AND HYDROGEOLOGY 8-1

8.1 Introduction 8-1
8.1.1 Background & Objectives 8-1
8.1.2 Statement of Authority 8-1
8.1.3 Relevant Legislation 8-2
8.1.4 Relevant Guidance 8-2
8.2 Methodology 8-3
8.2.1 Desk Study 8-3
8.2.2 Site Investigations 8-3
8.2.3 Scoping & Consultation 8-3
8.2.4 Impact Assessment Methodology 8-3
8.3 Receiving Environment 8-5
8.3.1 Existing Land Use & Topography 8-5
8.3.2 Water Balance 8-6
8.3.3 Regional & Local Hydrology 8-6
8.3.4 Site Drainage 8-7
8.3.5 Flood Risk Identification 8-7
8.3.6 Surface Water Hydrochemistry 8-7
8.3.7 Hydrogeology 8-10

RECEIVED: 05/08/2026

8.3.7.1 Bedrock Aquifer Classification 8-10
8.3.7.2 Groundwater Subsoil Permeability 8-13
8.3.7.3 Groundwater Vulnerability 8-13
8.3.7.4 Groundwater Levels and Flow 8-13
8.3.8 Water Resources 8-13
8.3.9 Groundwater Hydrochemistry 8-16
8.3.10 Water Framework Directive Water Body Status & Risk Assessment 8-22
8.3.11 Designated Sites & Protected Areas 8-22
8.3.12 Receptor Importance and Sensitivity 8-24
8.4 Characteristics of the Proposed Development 8-24
8.4.1 Proposed Site Infrastructure and Drainage Management 8-24
8.4.1.1 Surface Water Drainage 8-24
8.4.1.2 Wastewater Infrastructure 8-25
8.4.1.3 Water Supply 8-25
8.5 Potential Impacts and Mitigation Measures 8-25
8.5.1 Do Nothing Scenario 8-25
8.5.2 Construction Phase Potential Impacts 8-26
8.5.2.1 Earthworks 8-26
8.5.2.2 Potential Surface Water Quality Impacts from Shallow Excavation Dewatering 8-27
8.5.2.3 Potential Release of Hydrocarbons during Construction Stage 8-28
8.5.2.4 Groundwater and Surface Water Contamination from Wastewater Disposal 8-29
8.5.2.5 Release of Cement-Based Products 8-29
8.5.2.6 Potential Impacts on Hydrologically Connected Designated Sites 8-30
8.5.3 Operational Phase Impacts 8-31
8.5.3.1 Potential Increased in Downstream Flood Risk 8-31
8.5.3.2 Potential Downstream Water Quality Impacts from Surface Water Drainage 8-32
8.5.3.3 Potential Water Quality Impacts from Foul Drainage 8-32
8.5.3.4 Potential Impacts on Hydrologically Connected Designated Sites 8-33
8.5.4 Assessment of Potential Health Effects 8-34
8.5.5 Potential Cumulative Effects 8-34
8.5.6 Conclusion 8-36
8.6 References 8-37

9. AIR QUALITY 9-1

9.1 Introduction 9-1
9.1.1 Statement of Authority 9-1
9.1.2 Background 9-2
9.1.3 Limitations and Difficulties Encountered 9-2
9.2 Air Quality Guidance and Legislation 9-2
9.2.1 Relevant Guidance 9-2
9.2.2 Relevant Legislation 9-3
9.2.3 Air Quality Standards 9-5
9.2.3.1 Air Quality and Health 9-8
9.3 Methodology 9-11
9.3.1 Air Quality Zones 9-11
9.3.2 Air Quality Data Review 9-12
9.3.3 Dust 9-12
9.3.3.1 Defining the Sensitivity of the Area 9-14
9.3.4 Baseline Air Quality 9-17
9.3.4.1 Sulphur Dioxide (SO_2) 9-18
9.3.4.2 Particulate Matter (PM_{10}) 9-18
9.3.4.3 Nitrogen Dioxide (NO_2) 9-19
9.3.4.4 Carbon Monoxide (CO) 9-19
9.3.4.5 Ozone (O_3) 9-20
9.3.4.6 Dust 9-20
9.4 Likely and Significant Effects and Associated Mitigation Measures 9-25
9.4.1 “Do-Nothing” Scenario 9-25
9.4.2 Construction Phase 9-25
9.4.2.1 Exhaust Emissions 9-25
9.4.2.2 Operational Phase 9-28
9.4.2.3 Exhaust and Dust Emissions 9-28
9.4.3 Human Health 9-28
9.4.4 Cumulative Effects 9-29
9.5 Conclusion 9-30

10. CLIMATE 10-1

RECEIVED: 05/09/2026

10.1 Introduction 10-1
10.1.1 Background 10-1
10.1.2 Statement of Authority 10-1
10.1.3 Chapter Structure and Climate Study Areas 10-2
10.1.4 Limitations and Difficulties Encountered 10-3
10.1.5 Scoping and Consultation 10-3
10.2 Climate Legislation, Policy and Guidance 10-4
10.2.1 International Greenhouse Gas Emission and Climate Targets 10-4
10.2.2 National Greenhouse Gas Emissions and Climate Targets 10-8
10.2.3 Local Greenhouse Gas Emission and Climate Targets 10-9
10.2.3.1 Galway County Council Local Authority Climate Action Plan 2024-2029 10-9
10.2.3.2 Galway City Council Climate Action Plan 2024-2029 10-10
10.2.4 Relevant Guidance 10-11
10.3 Climate and Weather 10-11
10.3.1 Baseline Environment 10-11
10.3.1.1 Data Sources 10-11
10.3.1.2 Physical Environment 10-12
10.3.1.3 Existing Greenhouse Gas Emissions 18
10.3.2 Future Environment 18
10.3.2.1 Data Sources 19
10.3.2.2 Physical Environment 19
10.3.2.3 Greenhouse Gas Emissions Projections 21
10.3.3 Summary 22
10.4 Climate Scheme Sustainability Statement 22
10.5 Calculating Carbon Losses from the Proposed Development 24
10.5.1 Background 24
10.6 Likely Significant Effects and Associated Mitigation Measures 26
10.6.1 'Do-Nothing' Scenario 26
10.6.2 Construction Phase 26
10.6.2.1 Greenhouse Gas Emissions 26
10.6.3 Proposed Mitigation Measures 27
10.6.4 Operational Phase 29
10.6.4.1 Greenhouse Gas Emissions 29
10.6.5 Proposed Mitigation Measures 30
10.7 Cumulative Assessment 30
10.8 Conclusion 32

11. NOISE AND VIBRATION 11-1

11.1 Introduction 11-1
11.1.1 Overview 11-1
11.1.2 Proposed Development Summary 11-2
11.1.3 Statement of Authority 11-2
11.1.4 Difficulties 11-2
11.2 Assessment Methodology 11-3
11.2.1 Description of Effects 11-3
11.2.2 Guidance Documents Consulted 11-4
11.2.3 Construction Phase Noise 11-5
11.2.4 Construction Phase Traffic 11-6
11.2.5 Construction Phase Vibration 11-6
11.2.6 Operational Phase Noise 11-7
11.2.7 Operational Phase Traffic 11-8
11.2.8 Inward Noise Impacts 11-8
11.2.9 World Health Organisation (WHO) 11-9
11.2.10 Noise Action Plan 11-10
11.2.11 Scoping and Consultation 11-11
11.2.11.1 TII Scoping Response 11-11
11.3 Receiving Environment 11-11
11.3.1 Location 11-11
11.3.2 Receptors 11-14
11.3.3 Noise Mapping 11-16
11.3.4 Baseline Noise Data 11-18
11.3.5 Current Noise Risk Assessment 11-25
11.3.6 Future Trends 11-26

11.4 Likely Significant Effects 11-26
11.4.1 Do Nothing Scenario 11-26
11.4.2 Construction Phase Noise Levels 11-26
11.4.3 Construction Phase Noise Impacts 11-29
11.4.4 Construction Phase Traffic Noise 11-29
11.4.5 Construction Phase Vibration 11-29
11.4.6 Cumulative Construction Phase Noise Impacts – Proposed Project & Other Projects 11-30
11.4.7 Cumulative Construction Phase Noise Impacts – Proposed Development & Other Projects Excluding LRD East 11-32
11.4.8 Operational Phase Noise Impacts 11-32
11.4.9 Cumulative Operational Phase Noise – Proposed Project & Other Projects 11-33
11.4.10 Cumulative Operational Phase Noise – Proposed Development & Other Projects Excluding LRD East 11-33
11.4.11 Operational Phase Traffic Noise Impacts 11-33
11.4.11.1 Impacts At Surrounding Receptors Due To Proposed Development Traffic Movements On Onsite Roadways 11-34
11.4.11.2 Impacts At Altán Receptors Due To Proposed Development Traffic Movements On Main Access Roadway 11-34
11.4.11.3 Impacts Across Wider Area Due To Increases In Road Traffic On Surrounding Road Network As A Result Of Proposed Development 11-36
11.4.12 Cumulative Operational Traffic Noise Impacts – Proposed Project & Other Projects 11-36
11.4.12.1 Impacts At Surrounding Receptors Due To Proposed Project Traffic Movements On Proposed Project Roadways. 11-36
11.4.12.2 Impacts At Altán Receptors Due To Traffic Movements On Proposed Project Access Roadway 11-37
11.4.12.3 Impacts Across Wider Area Due To Increases In Road Traffic On Surrounding Road Network As A Result Of Proposed Project And Other Projects 11-38
11.4.13 Cumulative Operational Traffic Noise Impacts – Proposed Development & Other Projects Excluding LRD East Development 11-39
11.4.13.1 Impacts At Surrounding Receptors Due To Movements On Proposed Development Roadways. 11-39
11.4.13.2 Impacts At Altán Receptors Due To Movements On Proposed Development Access Roadway 11-40
11.4.13.3 Impacts Across Wider Area Due To Increases In Road Traffic On Surrounding Road Network As A Result Of Proposed Development And Other Projects 11-40
11.5 Inward Noise Impacts 11-41
11.5.1 ProPG Assessment Process 11-41
11.5.2 Step 1: Acoustic Principles Considered In Scheme Design 11-42
11.5.3 Step 2: Baseline Noise Model 11-42
11.5.4 Step 3: Model Validation 11-43
11.5.5 Step 4: Addition Of Proposed Development 11-46
11.5.6 Step 5: Future Traffic Growth 11-48
11.5.7 Step 6: Received Noise Levels 11-48
11.5.8 Step 7: Assessment Of Received Noise Levels – External 11-52
11.5.9 Step 8: Assessment Of Received Noise Levels – Internal, windows open 11-53
11.5.10 Step 9: Assessment Of Received Noise Levels – Internal, windows closed 11-56
11.5.11 Step 10: Assessment of L_{AFmax} Levels 11-58
11.5.12 Step 11: Assessment of cumulative issues 11-59
11.5.13 Step 12: Consideration Of Other Relevant Issues 11-65
11.5.14 Step 13: Mitigation Requirements For Inward Noise 11-65
11.6 Mitigation 11-66
11.6.1 Construction Phase 11-66
11.6.2 Operational Phase 11-66
11.6.3 Inward Noise 11-67
11.7 Residual Effects 11-69
11.7.1 Residual Impacts 11-69
11.7.2 Population & Human Health 11-70
11.7.3 Overall Residual Operational Effects 11-71
11.8 Glossary 11-72

12. CULTURAL HERITAGE 12-1

12.1 Introduction 12-1
12.1.1 Chapter Scope 12-1

RECEIVED: 05/03/2026

RECEIVED: 05/08/2026

12.1.2 Statement of Authority 12-1
12.1.3 Relevant Legislation and Planning Framework 12-1
12.1.4 Relevant Guidance 12-4
12.2 Methodology 12-4
12.2.1 Zone of Influence 12-4
12.2.2 Desktop Study 12-5
12.2.3 Field Survey 12-6
12.2.4 Consultation 12-6
12.2.5 Assessment Methodology 12-8
12.2.6 Limitations/Difficulties Encountered 12-10
12.3 Receiving Environment 12-10
12.3.1 Desktop Study 12-10
12.3.1.1 Introduction 12-10
12.3.1.2 Prehistoric Periods 12-12
12.3.1.3 Early Medieval Period 12-13
12.3.1.4 Late Medieval and Post Medieval Periods 12-13
12.3.1.5 Database of Irish Excavation Reports 12-14
12.3.1.6 National Museum of Ireland Topographical Files 12-14
12.3.1.7 Designated Architectural Heritage Constraints 12-14
12.3.1.8 Review of Cartographic Sources and Satellite/LiDAR Imagery 12-15
12.3.1.9 Undesignated Cultural Heritage Assets 12-21
12.3.2 Field Surveys 12-22
12.3.3 Conclusion 12-23
12.4 Assessment of Impacts 12-23
12.4.1 'Do-Nothing' Scenario 12-23
12.4.2 Construction Phase 12-24
12.4.3 Operation Phase 12-24
12.4.4 Cumulative Effects 12-25
12.5 Proposed Mitigation Measures 12-27
12.5.1 Pre-Construction Investigations 12-27
12.5.2 Monitoring of Mitigation Measures 12-27
12.6 Residual Effects 12-27
12.7 Bibliography 12-29

13. LANDSCAPE AND VISUAL 13-1

13.1 Introduction 13-1
13.1.1 Statement of Authority 13-1
13.1.2 Proposed Development Description 13-2
13.1.2.1 References to the Proposed Development 13-3
13.1.3 Essential aspects of the Development from an LVIA Perspective 13-5
13.2 Brief Methodology and Assessment Criteria 13-6
13.2.1 LVIA Guidance 13-6
13.2.2 Scope and Definition of the LVIA Study Area for Baseline Landscape and Visual Assessments 13-7
13.2.3 Methodology for Assessment of Likely Significant Landscape and Visual Effects. 13-8
13.3 Landscape Baseline 13-8
13.3.1 Landscape Policy Context 13-8
13.3.1.1 Galway City Development Plan 2023 - 2029 13-8
13.3.1.2 Land Use Zoning 13-8
13.3.1.3 Compact Growth and Regeneration 13-10
13.3.1.4 Housing and Sustainable Neighbourhoods 13-10
13.3.1.5 Green Network 13-10
13.3.1.6 Galway City Protected Views - Views of Special Amenity Value and Interest 13-12
13.3.1.7 Archaeology and Cultural Heritage 13-14
13.3.2 Landscape Character of the Proposed Development site 13-14
13.3.3 Wider Landscape Setting- LVIA Study Area 13-20
13.3.4 Landscape Sensitivity of the Proposed Development site 13-23
13.4 Visual Baseline 13-25
13.4.1.1 Visibility from Sensitive Visual Receptors (Protected Views, Recreational Amenities and Walking Trails) 13-25
13.4.1.2 Visibility from Residential Receptors and the Local Road Network 13-26
13.5 Cumulative Baseline 13-30
13.6 Photomontage Viewpoint Assessment 13-31
13.6.1 Viewpoint 1: Doire Gheal 13-33

RECEIVED: 05/08/2026

13.6.2 Viewpoint 2: L10111 Local Road nearby Knocknacarra National School 13-36
13.6.3 Viewpoint 3: Northerly end of Kingston Gardens 13-38
13.6.4 Viewpoint 4: Local access laneway to the south 13-41
13.6.5 Viewpoint 5: Clybaun Residential Estate 13-44
13.7 Likely Significant Landscape and Visual Effects 13-46
13.7.1 'Do-Nothing' Scenario 13-46
13.7.2 Construction Phase Effects 13-46
13.7.2.1 Likely Landscape Effects – Construction Phase 13-47
13.7.2.2 Likely Visual Effects – Construction Phase 13-47
13.7.3 Operational Phase Effects 13-48
13.7.3.1 Likely Significant Landscape Effects – Operational Phase 13-48
13.7.3.2 Likely Significant Visual Effects – Operational Phase 13-50
13.7.4 Cumulative Effects 13-52
13.7.4.1 Cumulative Landscape and Visual Effects 13-52
13.8 Conclusion 13-54

14. MAJOR ACCIDENTS AND NATURAL DISASTERS 14-1

14.1 Introduction 14-1
14.1.1 Statement of Authority 14-1
14.2 Assessment Methodology 14-2
14.2.1 Legislative Context 14-2
14.2.1.1 Legislation 14-2
14.2.2 Categorisation of the Baseline Environment 14-3
14.2.3 Impact Assessment Methodology 14-3
14.2.3.1 Introduction 14-3
14.2.3.2 Site-Specific Risk Assessment Methodology 14-3
14.3 Baseline Conditions 14-7
14.3.2 Additional Risks 14-9
14.3.2.1 Contamination 14-10
14.4 Risk Assessment 14-10
14.4.1 Likely Significant Effects 14-10
14.4.1.1 Do-Nothing Scenario 14-10
14.4.1.2 Identification of Effects During Construction 14-10
14.4.1.3 Identification of Effect During Operation 14-11
14.4.1.4 Assessment of Effect – Summary 14-13
14.4.2 Mitigation Measures 14-21
14.4.3 Residual Effects 14-22
14.4.4 Monitoring 14-22
14.4.4.1 Monitoring During Construction 14-22
14.4.4.2 Monitoring During Operation 14-22
14.4.5 Cumulative Impact Assessment 14-22

15. MATERIAL ASSETS 15-1

15.1 Introduction 15-1
15.2 Traffic and Transport 15-1
15.2.1 Introduction 15-1
15.2.2 Statement of Authority 15-2
15.2.3 Proposed Development 15-2
15.2.3.1 Parking Provision 15-2
15.2.3.2 Road Safety Audit 15-3
15.2.3.3 Existing Traffic Flows on the Local Network and the Traffic Impact of the Proposed Development 15-3
15.2.4 Methodology 15-4
15.2.5 Consultation/Scoping 15-5
15.2.6 Traffic Counts 15-6
15.2.7 Difficulties Encountered 15-6
15.2.8 Existing Receiving Environment 15-7
15.2.8.1 Location and Network Summary 15-7
15.2.9 Potential Impact of the Proposed Development 15-8
15.2.10 Do Nothing Scenario 15-9
15.2.10.1 Worst Case Scenario 15-9
15.2.10.2 Assessment Periods 15-9
15.2.10.3 Traffic Growth 15-10
15.2.10.4 Do Nothing Scenario 15-10
15.2.10.5 Baseline Traffic 15-10

RECEIVED: 05/08/2026

15.2.10.6 Construction Phase 15-10
15.2.10.7 Operational Phase 15-11
15.2.10.8 Proposed Project 15-12
15.2.10.9 Cumulative Assessment 15-16
15.2.11 Mitigation Measures 15-17
15.2.11.1 Mitigation Measures During the Construction Phase 15-17
15.2.11.2 Mitigation Measures During the Operational Phase 15-18
15.2.12 Residual Impact 15-19
15.2.12.1 Construction Phase 15-19
15.2.12.2 Operational Phase 15-19
15.2.13 Significance of Effects 15-20
15.2.14 Summary 15-20
15.2.15 Conclusion 15-21
15.3 Other Material Assets: Utilities, Water, Waste Management and Other Services 15-21
15.3.1 Introduction 15-21
15.3.2 Methodology 15-22
15.3.3 Legislation and Guidance 15-22
15.3.3.1 Difficulties Encountered 15-24
15.3.4 Scoping and Consultation 15-25
15.3.5 Zone of Influence 15-25
15.3.6 Desk Study - Receiving Environment 15-25
15.3.6.1 Electricity 15-25
15.3.6.2 Water Services 15-25
15.3.6.3 Wastewater Services 15-26
15.3.6.4 Gas 15-26
15.3.6.5 Waste Management 15-26
15.3.7 Likely and Significant Effects and Associated Mitigation Measures 15-27
15.3.7.1 'Do-Nothing' Scenario 15-27
15.3.7.2 Construction Phase 15-27
15.3.7.3 Operational Phase 15-30
15.3.7.4 Cumulative Impact Assessment 15-31

16. INTERACTION OF THE FOREGOING 16-1

16.1 Introduction 16-1
16.1.1 Statement of Authority 16-3
16.2 Impact Interactions 16-3
16.2.1 Population and Human Health 16-3
16.2.2 Biodiversity 16-4
16.2.3 Land, Soils and Geology 16-5
16.2.4 Climate 16-6
16.2.5 Air Quality 16-6
16.2.6 Landscape and Visual 16-6
16.2.7 Major Accidents and Natural Disasters 16-7
16.3 Mitigation and Residual Impacts 16-7

17. SCHEDULE OF MITIGATION 17-1

17.1 Introduction 17-1
17.2 EIAR Mitigation Measures 17-2
17.3 EIAR Monitoring Measures 17-24

RECEIVED: 05/08/2026

TABLE OF TABLES

Table 1-1 Impact Classification Terminology (EPA, 2022) 1-10
Table 1-2 Companies and Staff Responsible for EIAR Completion 1-12
Table 2-1 Planning Application History within Proposed Project Boundary 2-7
Table 2-2 Galway City Development Plan 2023 – 2029 Land Use Zoning Objectives 2-18
Table 2-3 EIAR Consultees and Responses 2-22
Table 2-4 Cumulative Assessment Study Areas 2-32
Table 3-1 Comparison of environmental effects when compared against the chosen option 3-3
Table 5-1 Population 2016 - 2022 (Source: CSO) 5-8
Table 5-2 Projected Population (2026 & 2031) for County Galway (including Galway city), and the Study Area (Source: DHPLG) 5-9
Table 5-3 Population Density in 2016 and 2022 (Source: CSO) 5-9
Table 5-4 Number of Households and Average Household Size 2016-2022 (Source: CSO) 5-10
Table 5-5 Population per Age Category in 2022 (Source: CSO) 5-10
Table 5-6 Economic Status of the Total Population Aged 15+ in 2022 (Source: CSO) 5-11
Table 5-7 Overseas Tourists Revenue and Numbers 2024 5-14
Table 5-8 Overseas Tourism to the West during 2017 (Source: Fáilte Ireland) 5-15
Table 5-9 2022 General Health Status 5-16
Table 6-1 Organisations consulted with regard to biodiversity 6-9
Table 6-2 Dates of ecological surveys undertaken 6-10
Table 6-3 Protocol for assessing the suitability of habitats within the Proposed Development site for bats (abridged, Collins, 2023). 6-14
Table 6-4. Bat Roost Potential Categories (abridged, Collins, 2023) 6-15
Table 6-5: Identification of designated sites within the Likely Zone of Influence 6-26
Table 6-6: Species listed designated under the Flora Protection Order (FPO) 2022 or the Irish Red Data Book 6-39
Table 6-7. NBDC records for protected fauna records (excl. birds) 6-40
Table 6-8: NBDC records for Birds 6-41
Table 6-9. NPWS records for rare and protected species 6-43
Table 6-10. NBDC records for invasive species (hectad M22) 6-45
Table 6-11: Watercourses within and downstream of the site with relevant water quality statuses 6-46
Table 6-12: Habitats recorded within the Proposed Development site wider EIAR Study Area 6-47
Table 6-13.Target Bird species, and amber listed bird species, recorded during the Winter Bird Surveys 6-67
Table 6-14. Target Bird species, and amber listed bird species, recorded during the 2024 Breeding Bird Surveys 6-69
Table 6-15. Target Bird species, and red and amber listed bird species, recorded during the 2026 Breeding Bird Surveys 6-71
Table 6-16 Dusk emergence surveys at PRFs. 6-78
Table 6-17: Key Ecological Receptors identified during the assessment 6-79

RECEIVED: 05/08/2026

Table 6-18 Assessment of impacts on treelines, hedgerow, scrub and Dry calcareous and neutral grassland 6-84
Table 6-19. Assessment of impacts on Water Quality 6-85
Table 6-20. Assessment of Potential effects associated with Invasive Alien Species 6-87
Table 6-21 Assessment of the potential impacts on bats during the construction phase 6-89
Table 6-22: Assessment of Potential Impacts on Birds during the construction phase 6-92
Table 6-23 Assessment of Potential Impacts on Water Quality 6-95
Table 6-24 Assessment of Potential Effects on bats 6-97
Table 6-25: Assessment of Plans 6-100
Table 7-1 Estimation of Importance (Sensitivity) of Land, Soil and Geology Criteria (taken from TII, 2008). 7-4
Table 7-2 Magnitude of Effects on Land, Soils and Geology receptors (taken from TII, 2008) 7-5
Table 7-3 Significance Matrix for Land, Soils and Geological Effects 7-6
Table 8-1 Estimation of Importance/Sensitivity of Hydrology Attributes (NRA, 2008) 8-4
Table 8-2 Estimation of Importance/Sensitivity of Hydrogeological Attributes (NRA, 2008) 8-5
Table 8-3 Additional Impact Characteristics Considered 8-5
Table 8-4 Mean Monthly Rainfall (mm) - Shannon Airport Synoptic Weather Station (1991-2020) 8-6
Table 8-5 Surface water field hydrochemistry 8-10
Table 8-6 Summary of Groundwater Depth 8-10
Table 8-7 Groundwater field parameters 8-16
Table 8-8 Groundwater Hydrochemistry 8-17
Table 9-1 Limit values of the CAFE Directive 2008/50EC 9-5
Table 9-2 Assessment Thresholds from the CAFE Directive 2008/50/EC 9-6
Table 9-3 Target values for Ozone defined in the Directive 2008/50/EC 9-8
Table 9-4 Threshold for Ozone defined in Directive 2008/50/EC (source: https//airquality.ie/information/air-quality standards and Directive 2008/50/EC) 9-8
Table 9-5 Description of Magnitude for nature of activities (Adapted from: IAQM. 2024. Guidance on the Assessment of Dust from Demolition and Construction, pages 16 & 17) 9-13
Table 9-6 Sensitivity of the Area to Dust Soiling Effects on People and Property. (Source: IAQM. 2024. Guidance on the Assessment of Dust from Demolition and Construction, page 21) 9-15
Table 9-7 Sensitivity of the Area to Human Health Impacts (Source: IAQM. 2024. Guidance on the Assessment of Dust from Demolition and Construction, page 22) 9-15
Table 9-8 Sensitivity of the Area to Ecological Impacts (Source: IAQM. 2024. Guidance on the Assessment of Dust from Demolition and Construction, page 23) 9-16
Table 9-9 Risk of Dust Impacts for Earthworks, Construction, Trackout (Adapted from IAQM, 2024, Guidance on the Assessment of Dust from Demolition and Construction, page 24) 9-17
Table 9-10 Correlation of Impact Classification Terminology to Risk Rating 9-17
Table 9-11 Sulphur Dioxide Date for Zone C Sites in 2024 9-18
Table 9-12 Average Particulate Matter (PM10) Data for Galway Rahoon, Galway Eyre Square and Galway Briarhill (Zone C) in 2024 9-18

RECEIVED: 05/08/2026

Table 9-13 Average Nitrogen Dioxide Data for Galway Eyre Square and Galway Briarhill Zone C Sites in 2024.....9-19

Table 9-14 Carbon Monoxide Data for Portlaoise and Dundalk - Zone C Site in 2024.....9-19

Table 9-15 Average Ozone Data for Zone C Sites in 2024.....9-20

Table 9-16 Number of Receptors (Residential) within 20m, 50m, 100m, and 250m of the Proposed Development Site Boundary.....9-20

Table 9-17 Sensitivity Assessment of the Area to Dust Soiling Effects on People and Property from Proposed Development construction works. (Adapted from: IAQM. 2024. Guidance on the Assessment of Dust from Demolition and Construction, page 21).....9-26

Table 9-18 Sensitivity Assessment of the Area to Human Health Impacts from Proposed Development construction works. (Adapted from: IAQM. 2024.Guidance on the Assessment of Dust from Demolition and Construction, page 22).....9-26

Table 9-19 Summary of Dust Risk for the Proposed Development Activities (Adapted from IAQM. 2024. Guidance on the Assessment of Dust from Demolition and Construction, page 24).....9-27

Table 10-1 International Instruments Relating to Greenhouse Gases and Climate Change Targets...10-5

Table 11-1 EPA Impact Assessment Scheme.....11-3

Table 11-2 DMRB construction noise impact assessment scale for daytime working hours.....11-6

Table 11-3 Refined DMRB construction noise impact assessment scale applied in this assessment.....11-6

Table 11-4 DMRB offsite construction traffic noise impact assessment scale.....11-6

Table 11-5 Human perception of vibration, from BS 5228-2:2009+A1:2014.....11-7

Table 11-6 Building vibration criteria, from the National Roads Authority (2014).....11-7

Table 11-7 Recommended vibration limits.....11-7

Table 11-8 DMRB scale for offsite operational traffic noise impact.....11-8

Table 11-9 Recommended internal criteria from BS 8233:2014 and ProPG.....11-8

Table 11-10 Baseline noise station details.....11-20

Table 11-11 Survey details.....11-20

Table 11-12 Recorded noise levels (dB) 17.04.23-18.04.23. 30 minute intervals are presented here..11-22

Table 11-13 Noise data summary (dB).....11-24

Table 11-14 Assignment of baseline noise data.....11-24

Table 11-15 Expected construction plant (dB at 10 m).....11-27

Table 11-16 Assessed construction phase scenarios. Works area refers to the onsite works zone assumed in each scenario for the purposes of modelling – the worst case scenario is assumed in relation to offsite receptors.....11-28

Table 11-17 Previously measured rock breaking PPV levels.....11-30

Table 11-18 $L_{Aeq\ T}$ levels at receptors adjacent to access road due to cars and light vans (dB).....11-35

Table 11-19 Access road traffic noise impacts (dB).....11-35

Table 11-20 Increase in road traffic volumes and noise levels (dB) due to the Proposed Development.....11-36

Table 11-21 $L_{Aeq\ T}$ levels at Altán receptors due to cars and light van movements associated with the Proposed Project and permitted aquatic centre (dB).....11-38

Table 11-22 Access road traffic noise impacts at Altán due to cumulative traffic movements associated with the Proposed Project and permitted aquatic centre (dB).....11-38

Table 11-23 Increase in road traffic volumes and noise levels at WDR roundabout 11-39

Table 11-24 $L_{Aeq\ T}$ levels at Altán receptors due to cars and light van movements associated with the Proposed Development and permitted aquatic centre(dB) 11-40

Table 11-25 Access road traffic noise impacts at Altán due to cumulative traffic movements associated with the Proposed Development and permitted aquatic centre (dB). 11-40

Table 11-26 Increase in road traffic volumes and noise levels at WDR roundabout. 11-41

Table 11-27 Traffic volumes applied in the noise model. 11-43

Table 11-28 Comparison on modelled, measured and mapped levels (dB) 11-43

Table 11-29 2044 traffic volumes applied in the noise model. 11-48

Table 11-30 Proposed Development receptor facades assessed. Liv = living room and dining area. 11-49

Table 11-31 Amenity area $L_{Aeq\ 16\ h}$ levels (dB). 11-52

Table 11-32 Amenity area L_{den} and L_{night} levels (dB). 11-53

Table 11-33: Internal noise levels (dB) with windows open. The $L_{Aeq\ 8\ h}$ criterion is not applicable to living rooms. Rooms where the daytime 35 dB $L_{Aeq\ 16\ h}$ and night-time 30 dB $L_{Aeq\ 8\ h}$ criteria will be exceeded are highlighted yellow. 11-54

Table 11-34: Attenuation assessment with windows closed – Daytime. $L_{Aeq\ 16\ h}$ levels (dB) listed are external 11-56

Table 11-35: Attenuation assessment with windows closed – Night-time. Criteria apply to bedrooms only. $L_{Aeq\ 8\ h}$ levels (dB) listed are external. 11-57

Table 11-36 Amenity area $L_{Aeq\ 16\ h}$ levels (dB) – Cumulative inward scenario. 11-61

Table 11-37: Internal $L_{Aeq\ 16\ h}$ noise levels (dB) with windows open – Cumulative inward scenario. Rooms where the daytime 35 dB $L_{Aeq\ 16\ h}$ criterion will be exceeded are shaded. 11-61

Table 11-38: Attenuation assessment with windows closed – Daytime, cumulative inward scenario. $L_{Aeq\ 16\ h}$ levels (dB) listed are external. 11-63

Table 11-39 Residual construction impacts post-mitigation. 11-69

Table 11-40 Residual operational impacts post-mitigation 11-70

Table 11-41 Summary of residual operational effects. 11-71

Table 12-1 Criteria for Assessment of Magnitude of Impact (based on ICOMOS 2011) 12-8

Table 12-2 Guidance Criteria for Assessment of Value/Sensitivity of Cultural Heritage Assets 12-9

Table 12-3 Description of Impact Significance 12-9

Table 12-4 Significance of Impacts Matrix 12-10

Table 12-5 Recorded Archaeological Sites within study area 12-11

Table 12-6 Protected Structures within study area 12-14

Table 12-7 Developments reviewed for potential cumulative effects 12-25

Table 13-1 GCDP Protected Views within the LVIA Study Area 13-13

Table 13-2 Indicators of Landscape Value 13-24

Table 13-3 Photomontage Viewpoint Locations 13-32

Table 13-4 Visual Impact Assessment: Viewpoint 1 13-34

Table 13-5 Visual Impact Assessment: Viewpoint 2 13-37

Table 13-6 Visual Impact Assessment: Viewpoint 3 13-39

RECEIVED: 05/09/2026

RECEIVED: 05/08/2026

Table 13-8 Visual Impact Assessment: Viewpoint 4 13-42
Table 13-7 Visual Impact Assessment: Viewpoint 5 13-45
Table 14-1 Classification of Likelihood (Source: DoEHLG, 2010) 14-4
Table 14-2 Classification of Impact (Source: DoEHLG, 2010) 14-5
Table 14-3 Classification of Impact (Source: DoEHLG, 2010) 14-7
Table 14-4 SEVESO/COMAH Sites in County Galway 14-8
Table 14-5 Risk Register - Construction Phase 14-10
Table 14-6 Risk Register – Operational Phase 14-12
Table 14-7 Overall Vulnerability of the Proposed Development to Risk of Major Accidents & Natural Disasters 14-13
Table 14-8 Risk Scores 14-20
Table 14-9 Risk Matrix 14-20
Table 15-1 Car Parking Requirements 15-3
Table 15-2 Classification of Passenger car Units 15-4
Table 15-3 Significance Criteria for Impacts on Traffic or Transportation 15-5
Table 15-4: Growth Factors for light vehicle (LV) and heavy vehicles (HV) - 2023 15-10
Table 15-5 Proposed Development Traffic Generation via Junction 1 15-11
Table 15-6 Proposed Development + Masterplan Traffic Generation via Junction 1 15-12
Table 15-7 Existing Roundabout Junction 1 15-12
Table 15-8 Active Travel Layout Roundabout Junction 1.1 15-13
Table 15-9 Existing Roundabout Junction 2 15-14
Table 15-10 Summary of Impact Assessment 15-15
Table 15-11 Built Services and Waste Management Scoping Responses 15-25
Table 16-1 Interaction Matrix: Potential for Interacting Impacts 16-2

TABLE OF FIGURES

RECEIVED: 05/08/2026

Figure 1-1 Site Location - EIAR Study Area 1-4
Figure 1-2 Site Location 1-5
Figure 2-1 Proposed Development Site Location 2-2
Figure 2-2 Designated Sites nearest Proposed Development 2-4
Figure 2-3 Resultant Masterplan 2-6
Figure 2-4 Planning History Search Area with a 1km buffer 2-10
Figure 2-5: Table 2.1 of the Revised NPF 2-12
Figure 2-6 Proposed Development Site & GCDP 2023-2029 zoning objectives 2-19
Figure 3-1 Original Masterplan Layout for the Wider Rahoon and Knocknacarra Lands 3-10
Figure 3-2 Final Layout Iteration for LRD East only. 3-11
Figure 3-3 Final Layout Iteration (Proposed Development). 3-12
Figure 4-1 Site Layout 4-4
Figure 5-1 Population and Human Health Study Area – Proposed Development Site 5-6
Figure 5-2 Population and Human Health Study Area – Proposed Project Site 5-7
Figure 5-3 % of Population per Age Category in 2022 (Source: CSO) 5-11
Figure 5-4 Employment by Socio-Economic Group in 2022 (Source: CSO) 5-12
Figure 5-5 Galway City Development Plan - Land Use Zoning- Note: Residential is zoned as yellow. 5-13
Figure 5-6 Trend in General Health Status of Study Area in 2016 and 2022 (Source: CSO) 5-17
Figure 6-1 Site Location 6-3
Figure 6-2: Site Layout 6-4
Figure 6-3: Vantage Points and Transects Surveyed for Birds 6-13
Figure 6-4. European Sites within the Likely Zone of Influence 6-24
Figure 6-5: Nationally Designated Sites 6-25
Figure 6-6: Habitat map of the EIAR Study Area 6-48
Figure 6-7: Habitat Map with Site Plan Overlain 6-49
Figure 6-8: Locations of Invasive Species Recorded 6-65
Figure 7-1 Soils Map 7-7
Figure 7-2 Quaternary Sediments (Subsoils) Map 7-8
Figure 7-3 Bedrock Geology Map 7-9
Figure 7-4 Geological Heritage and Designated Sites Map 7-10
Figure 8-1 Regional Hydrology Map 8-8
Figure 8-2 Bedrock. Local Hydrology and Surface Water and Groundwater Sampling Locations 8-9
Figure 8-3 Bedrock Aquifer Map 8-12
Figure 8-4 Subsoil Permeability Map 8-14
Figure 8-5 Groundwater Vulnerability Map 8-15
Figure 8-6 Designated Sites and Protected Areas 8-23

Figure 9-1 Seven Strategic Frameworks for Air Quality, with associated chapters in brackets. Reproduced as Figure 1 from Clean Air Strategy 2023 9-10
Figure 9-2 Receptors within 20m of the Proposed Development 9-21
Figure 9-3 Receptors within 50m of the Proposed Development 9-22
Figure 9-4 Receptors within 100m of the Proposed Development 9-23
Figure 9-5 Receptors within 250m of the Proposed Development 9-24
Figure 11-1 Site location. 11-13
Figure 11-2 Nearest receptors. 11-15
Figure 11-3 Mapped L_{den} contours. 11-16
Figure 11-4 Mapped L_{night} contours. 11-17
Figure 11-5 Baseline noise stations. 11-19
Figure 11-6 $L_{Aeq\ 1\ s}$ profile at N1. 11-23
Figure 11-7 $L_{Aeq\ 1\ s}$ profile at N2. 11-23
Figure 11-8 $L_{Aeq\ 1\ s}$ profile at N3. 11-23
Figure 11-9 $L_{Aeq\ 1\ s}$ profile at N4. 11-23
Figure 11-10 ProPG risk assessment scheme. 11-25
Figure 11-11 Modelled baseline traffic contours – $L_{Aeq\ 16\ h}$ at 4 m. 11-44
Figure 11-12 Modelled baseline traffic contours – L_{den} at 4 m. 11-45
Figure 11-13 Modelled baseline traffic contours – L_{night} at 4 m. 11-45
Figure 11-14 Proposed Development layout, including block numbering scheme applied in this assessment. 11-47
Figure 11-15 Modelled 2044 traffic contours – $L_{Aeq\ 16\ h}$ at 4 m. 11-50
Figure 11-16 Modelled 2044 traffic contours – L_{den} at 4 m. 11-51
Figure 11-17 Modelled 2044 traffic contours – L_{night} at 4 m. 11-51
Figure 11-18 Modelled 2044 traffic noise, aquatic centre noise, urban realm noise and retail centre noise – $L_{Aeq\ 16\ h}$ at 4 m 11-60
Figure 11-19 Facades where marginally enhanced acoustic glazing will be required, shown yellow. 11-68
Figure 12-1 Recorded archaeological sites and Zones of Notification within 500m (white line) of Proposed Development boundary 12-12
Figure 12-2 Protected Structures within 500m of Proposed Development boundary 12-15
Figure 12-3 Extract from William Petty's Down Survey map (1658) (Source: Trinity College, Dublin) (Rahoon area indicated with arrow) 12-16
Figure 12-4 Extract from first edition 6-inch Ordnance Survey map (1840) 12-17
Figure 12-5 Extract from 25-inch Ordnance Survey map (1899) 12-18
Figure 12-6 Extract from last edition 6-inch Ordnance Survey map published in 1948 12-19
Figure 12-7: 1996 – 2000 aerial view of Proposed Development site (Source: Historic Environment Viewer) 12-20
Figure 12-8: 2011 – 2013 aerial view of Proposed Development site (Source: Historic Environment Viewer) 12-20
Figure 12-9 LiDAR image of Proposed Development site (Source: Geological Survey of Ireland) 12-21

RECEIVED: 05/08/2026

Figure 12-10 Location of Proposed Development showing survey field numbers 12-23

Figure 13-1 Neighbourhoods - Excerpt extracted from the Urban Framework Plan Design Statement for the Proposed Project. 13-4

Figure 13-2 Section view of duplexes in the Altan Quarter – Excerpt Extracted from the Planning Drawings. 13-4

Figure 13-3 Section view of townhouses in the Kingston Quarter– Excerpt Extracted from the Planning Drawings. 13-5

Figure 13-4 CGI View of townhouses in Kingston Quarter 13-5

Figure 13-5 LVIA Study Area 13-7

Figure 13-6 GCDP Land-Use Zoning Map and Proposed Development Location 13-9

Figure 13-8 Map extracted from the GCDP Fig. 5.1 - Galway City Green Network 13-11

Figure 13-9 The Green Network and the LVIA Study Area 13-12

Figure 13-10 Galway City Protected Views in the LVIA Study Area 13-13

Figure 13-11 Aerial Map: Proposed Development site and other areas of the Proposed Project (EIAR Study Area) 13-15

Figure 13-12 Digital Surface Model of the EIAR Study Area 13-18

Figure 13-13 Landform of the LVIA Study Area 13-23

Figure 13-14 Receptors immediately surrounding the EIAR Study Area 13-27

Figure 13-16 Relevant Cumulative Development Map 13-30

Figure 13-17 Viewpoint location Map. 13-32

Figure 13-18 'Green Corridor' through the Proposed Project – Map Extracted from the 'Urban Framework Plan Design Statement' for the Proposed Project 13-50

Figure 15-1 Junction Locations 15-6

Figure 15-2 Site Location and Surrounding Road Network 15-7

RECEIVED: 05/08/2026

RECEIVED: 05/08/2026

TABLE OF PLATES

Plate 4-1: View from Centre of the site looking northwest 4-3

Plate 4-2: View from Centre of the site looking southwest towards existing residential houses 4-3

Plate 4-3.Silt Bag with water being pumped through. 4-15

Plate 4-4. Silt Bag under inspection. 4-15

Plate 4-5. Silt Fence (orange) surrounding the discharge from Silt Bag (pink). 4-15

Plate 4-6. Embedded Silt Fence 4-15

Plate 6-1. View of mulched vegetation and machinery tracks classified as Recolonising bare ground (ED3) /Spoil and bare ground (ED2) in the north of the EIAR Study Area. 6-51

Plate 6-2. View of recolonising rock and stone piles located in the north of the EIAR Study Area. Dry meadows and grassy verges (GS2) habitat was also recorded in this section of the EIAR Study Area... 6-51

Plate 6-3. View of black pine and Italian alder trees in the north-east of the wider EIAR Study Area, occurring in an area of Recolonising bare ground ED3/Spoil and bare ground ED2 and Dry meadows and grassy verges (GS2) habitat. 6-52

Plate 6-4. View of section of treeline (WL2) habitat dominated by ash and sycamore, recorded in the west of the EIAR Study Area 6-53

Plate 6-5. View of stone walls classified as Stone walls and other stonework (BL1) located in the south of the EIAR Study Area adjacent to the existing residential dwelling classified as Buildings and artificial surfaces (BL3). 6-54

Plate 6-6. View of old stone farm sheds and newly built stables classified as Buildings and artificial surfaces (BL3) located in the centre of the Proposed Development site. 6-54

Plate 6-7. View of unmanaged Dry meadows and grassy verges (GS2) recorded in the centre of the EIAR Study Area. 6-55

Plate 6-8. View of Dry meadows and grassy verges (GS2)/Dry calcareous and neutral grassland (GS1) habitat in the south of the wider EIAR Study Area by the dog pens. 6-56

Plate 6-9. View of unmanaged dry calcareous and neutral grassland (GS1) and stone wall (BL1) located in the south of the Proposed Development site. 6-57

Plate 6-10. View of heavily poached area in the Proposed Development site due to horses grazing the fields 6-57

Plate 6-11. View of gorse dominated Scrub (WS1) habitat recorded in the north of the Proposed Development site. 6-58

Plate 6-12. View of hedgerows (WL1) typical of that found in the Proposed Development site. 6-59

Plate 6-13. View of stagnant water in isolated drainage ditch (FW4) in the north-east of the wider EIAR Study Area. Note that this habitat does not occur within the boundary of the Proposed Development site 6-60

Plate 6-14. View of wet grassland (GS4) habitat recorded in the northern section of the Proposed Development site. 6-61

Plate 6-15. View of three-cornered garlic located in close proximity to the northern boundary of the Proposed Development site. 6-62

Plate 6-16: View of a single specimen of three-cornered leek, located in proximity to the northern boundary. 6-63

Plate 6-17: View of juvenile saplings of sea buckthorn recorded in proximity to the northern boundary in 2024. 6-63

Plate 6-18. View of Sea buckthorn growing along the hedgerow habitat which lies in proximity to the northern boundary of the Proposed Development site 6-64
Plate 13-1 Aerial View of the EIAR Study Area from the South 13-16
Plate 13-2 Existing Landcover in the Proposed Development site 13-16
Plate 13-3 Existing Landcover in the north of the Proposed Development site 13-17
Plate 13-4 Agricultural Fields to the South of the Proposed Development site. 13-17
Plate 13-5 View North from the centre of the Proposed Development site. 13-19
Plate 13-7 View East from the Northeast of the EIAR Study Area 13-19
Plate 13-8 View South from the Centre of the EIAR Study Area 13-20
Plate 13-9 View Southwest from the South of the EIAR Study Area. 13-20
Plate 13-11 Retail and Commercial Buildings to the North of the Proposed Development site 13-21
Plate 13-12 Residential Buildings on Bóthar Stiofáin, in Close Proximity to the Proposed Development site within 500m 13-21
Plate 13-13 View towards Galway Bay and Salthill Golf Club to the South of the Proposed Development site 13-22
Plate 13-14 Residential and Commercial Buildings to the west of Altán Apartments on the L-10111 in Close Proximity to Proposed Development site 13-22
Plate 13-15 View along Kingston Road, where the Proposed Development would be located behind the housing on the right of the image (Protected View 11, GCDP) 13-26
Plate 13-17 View towards the Proposed Development from the Back of An Logan Housing Estate 13-28
Plate 13-18 View towards the Proposed Development site from the southern section of The Orchard residential estate 13-29
Plate 13-19 Viewpoint 1 – Existing View: Doire Gheal Residential Estate 13-33
Plate 13-20 Viewpoint 1: Proposed View: Doire Gheal Residential Estate 13-34
Plate 13-21 Viewpoint 2 – Existing View: Local Road nearby Knocknacarra National School 13-36
Plate 13-22 Viewpoint 2 – Proposed View: Local Road nearby Knocknacarra National School 13-36
Plate 13-23 Viewpoint 3 – Existing View: The northerly end of Kingston Gardens. 13-38
Plate 13-24 Viewpoint 3 – Proposed View: The northerly end of Kingston Gardens. 13-39
Plate 13-27 Viewpoint 4- Existing View: Local access laneway 13-41
Plate 13-28 Viewpoint 4 – Proposed View: Local access laneway 13-41
Plate 13-29 Viewpoint 5 – Cumulative Proposed View: Local access laneway 13-42
Plate 13-25 Viewpoint 5 - Existing View: Clybaun Residential Estate 13-44
Plate 13-26 Viewpoint 5 - Proposed View: Clybaun Residential Estate 13-44

RECEIVED: 05/08/2026

TABLE OF APPENDICES

RECEIVED: 05/08/2026

Appendix 2-1	Planning Application history within 1km of the Proposed Development
Appendix 2-2	Scoping Responses
Appendix 2-3	King Knocknacarra Cumulative Long List Applications
Appendix 3-1	LRD Opinion Letter issued by Galway City Council on the 25th of May 2026
Appendix 4-1	CEMP
Appendix 4-2	Climate Scheme Sustainability Statement
Appendix 4-4	Urban Framework Plan Design Statement
Appendix 4-4	Urban Framework Plan Design Statement
Appendix 5-1	Human Health Assessment Guidelines
Appendix 6-1	Baseline Bat Report
Appendix 6-2	Invasive Species Management Plan
Appendix 6-3	Landscape Design Rationale Report
Appendix 6-4	Outdoor Lighting Report
Appendix 6-5	Bat Derogation Licence
Appendix 7-1	Ground Investigation Report, Causeway 2019
Appendix 7-2	Ground Investigation Report, Causeway 2025
Appendix 7-3	Geo-environmental Interpretive Report, MKO 2026
Appendix 8-1	Flood Risk Assessment
Appendix 8-2	Laboratory Reports Surface Water
Appendix 8-3	Laboratory Reports Groundwater
Appendix 8-4	Water Framework Directive Report
Appendix 10-1	Climate Change Legislation
Appendix 10-2	Carbon Calculations
Appendix 11-1	Construction Noise Levels
Appendix 11-2	Construction Noise Impacts
Appendix 11-3	Cumulative Construction Noise Levels - Proposed Project
Appendix 11-4	Cumulative Construction Noise impacts - Proposed Project
Appendix 11-5	Cumulative Construction Noise Levels - Proposed Development

Appendix 11-6 Cumulative Construction Noise Impacts - Proposed Development

Appendix 12-1 Photographic Records

Appendix 12-2 Summaries of Archaeological Excavations

Appendix 12-3 Architectural Conservation Report

Appendix 12-4 Structural Condition Assessment

Appendix 13-1 LVIA Methodology

Appendix 13-2 Photomontage Booklet

Appendix 14-1 Flood Risk Assessment

Appendix 15-1 Traffic Impact Assessment

Appendix 15-2 Road Safety Audit

Appendix 15-3 Junction 1 Arcady Analysis

Appendix 15-4 Junction 2 Arcady Analysis

Appendix 15-5 Design Manual for Urban Roads and Streets (2019)

RECEIVED: 05/08/2026