

## **Appendix A.9.1 - Part 3**

### **Ground Investigation Reports**

### **Appendix A.9.1.5**

Phase 3 Contract 2, N6 Galway  
City Transport Project Phase 3  
Ground Investigation Contract  
2, October 2015 to January  
2016



## **R15-16**

---

**N6 Galway City Transport Project**

**Phase 3 Ground Investigation**

**Contract No. 2 - Factual Report**

**Galway County Council**

**Prepared by BRG Ltd. on behalf of Priority Drilling Ltd.**

**Dave Blaney**

<b>Project</b>	<b>R15/16</b>
<b>Number:</b>	
Author(s):	Dave Blaney P. Geo
BRG Ltd.	Galway County Council
Date of Report:	May 2016



**R15/16**  
**N6 Galway City Transport Project - Phase 3 Ground Investigation**  
**Contract No. 2 - Factual Report**  
**Dave Blaney P.Geo**  
**May 2016**

**Contents**

1. Purpose and Scope of Works .....	3
2. Geological Setting and Ground Conditions .....	6
3. Ground Investigations .....	8
3.1 Setting Out / Surveying .....	8
3.2 Ground Geophysical Surveying .....	8
3.3 Rotary Borehole Investigation .....	10
3.3.1 Low Angle Drilling (HQ Core) .....	10
3.3.2 Vertical Drilling (PQ Core) .....	11
3.4 Discontinuity Logging .....	13
3.5 Piezometer Installations .....	13
3.6 Borehole Geophysical Surveying .....	14
3.7 Rock / Soil / Water - Laboratory Testing .....	14
3.8 In Situ Water Testing .....	25
3.9 Permeability Testing .....	26
3.10 Water level Measurements .....	27

**List of Figures**

Figure 1: Lackagh Quarry Ground Investigation Site - Yellow Polygon (Google 2015)	3
Figure 2: Site Area - Dashed Red Line	3
Figure 3: SAC Location (Red Hashed Area) (NPWS 2015)	4
Figure 4: Simplified Geology Map of the Menlo Region (GSI 1:100,000 series)	6
Figure 5: Microgravity Station Locations	9
Figure 6: 2D Electrical Resistivity Tomography (ERT) Line / Station Locations	9
Figure 8: Borehole Collar Locations, Traces and Line of Section	12
Figure 9: A - A' Drill Section (looking North) through the Lackagh Quarry GI Site	12

**Appendices**

Appendix I	Survey Location Data
------------	----------------------



Appendix II	Rotary Borehole Logs
Appendix III	Discontinuity Logs
Appendix IV	Piezometer Installations
Appendix V	Surface Geophysical Survey
Appendix VI	Borehole Geophysical Survey
Appendix VII	Laboratory Test Results
Appendix VIII	In Situ Test Results
Appendix IX	Falling Head Tests
Appendix X	Packer Tests
Appendix XI	Water Level Measurements
Appendix XII	Photographs

## 1. Purpose and Scope of Works

Galway County Council, on its own behalf and on behalf of Galway City Council, are committed to developing a solution to the existing transportation issues in Galway City and its environs, which are having a negative impact upon the local, regional and national road network. As part of this work it is necessary to undertake ground investigation works prior to the commencement of detailed design work.

The Menlo region, within and to the immediate west of Lackagh Quarry, has been selected as a possible route for the N6 road development (Figure 1).



**Figure 1:** Lackagh Quarry Ground Investigation Site - Yellow Polygon (Google 2015)

The site consists of a non-active quarry with associated derelict buildings, plant, structures and poor quality agricultural land used for the grazing of cattle (Figure 2).



**Figure 2:** Site Area - Dashed Red Line

This area is in an environmentally sensitive region, with the Lough Corrib cSAC Annex 1 habitat (candidate Special Area of Conservation) located immediately west and north of the Lackagh Quarry site (Figure 3).



**Figure 3:** SAC Location (Red Hashed Area) (NPWS 2015)

The objective of the ground investigation is as follows:

- Characterise the nature of the rockmass for tunnel design;
- Characterise the hydrogeology for tunnel design and the existing groundwater conditions;
- Identify any existing karst features and potential for karstic conditions with the rockmass
- Carryout in-situ and laboratory testing to provide geotechnical and hydrogeological parameters for tunnel design

In order to accomplish the stated objectives the following ground investigation was proposed:


- 1 No. Sub-horizontal rotary core drillhole along the proposed tunnel alignment for a length of approximately 300m
- 3 No. Vertical Rotary core drillholes to depths of 32.5m, 35.0m and 40.0m
- 3 No. Monitoring Installations (piezometers) with raised steel covers
- Geotechnical Laboratory Testing



- Downhole Geophysics
- Surface Geophysics
- Factual Reporting

## 2. Geological Setting and Ground Conditions

The site is underlain by Lower Carboniferous (Visean) Limestone located approximately 2km to the northeast of the contact with the Galway granitic intrusive complex (Figure 4). There is little published data for this region and Geological Survey of Ireland (GSI) 1:100,000 scale Bedrock Map series record this area as Undifferentiated Visean Shelf Limestones.



**Figure 4:** Simplified Geology Map of the Menlo Region (GSI 1:100,000 series)

The bedrock geology is dominated by light grey / grey, massively bedded, fine to medium grained pelley to weakly oolitic grainstones. Discrete, metric scale, beds of dark grey / black limestones are developed within the sequence. The black limestone beds are dominated by synsedimentary breccias with intraclastic clasts of grainstone supported in a black fine grained micritic matrix, this was only intersected by one of the ground investigation boreholes. There is evidence of burrowing and the brecciation may have been caused by bioturbation. Minor bioclastic debris is disseminated throughout, dominated by unrecognisable small shell fragments. Locally occurring coarse bioclastic fragments consist of thick shelled brachiopods and solitary corals. The fauna and well sorted nature of the rock are indicative of a shallow water, relatively high energy depositional environment. Thin (centimetric scale), horizons of grey / green to black mudstone form semi-continuous marker horizons within the geological sequence. The mudstone horizons (often known as clay wayboards) can be weakly tuffaceous, often containing a significant proportion of finely disseminated pyrite. The pyrite in these thin bands oxidises strongly and is responsible for the surficial iron staining present on parts of the lower benches at Lackagh Quarry.

The unconsolidated Quaternary geology of this region has been proven by the recent drilling to be much more complex than originally anticipated. A deep buried channel / trough is located to the west orientated along an east-west axis. Unconsolidated material deposited within this feature ranges from lacustrine, laminated (possibly varved) dark brown, organic clays to sands / gravels of a possibly fluvial origin, all overlain by very stiff, glacial boulder clays.

Extensive areas of limestone pavement are developed to the north and west of the quarry site and there are numerous glacial erratics scattered throughout, many of which are granitic.

### **3. Ground Investigations**

#### **3.1 Setting Out / Surveying**

Drawings and coordinates were provided by ARUP and were used to locate and position each borehole and geophysical station. The drillhole collar locations were positioned using a Trimble GeoExplorer 6000 RTK GPS system corrected to a differential base station through a phone modem link. Locations were measured relative to Irish Transverse Mercator.

The low angle borehole, BH01, was set out using the Trimble GeoExplorer 6000 RTK GPS system. The hole / working platform was orientated using a prismatic compass, accurate to  $\pm 0.5^\circ$ . The rig was then set up using a Reflex TN14 Gyrocompass to measure the exact dip and azimuth of the hole before coring commenced.

Downhole surveying of drillhole BH01 was carried out at 3m intervals using a Reflex EZ-TRAC digital downhole survey instrument. Owing to ground conditions (cavities and localised broken ground from 186m) the hole could only be surveyed from 175m back to surface. A core orientation tool had been used throughout the drilling that provided information about the dip of the hole, the driller noted no significant variation in dip from 175m. Refer to Appendix I for all surveying data.


#### **3.2 Ground Geophysical Surveying**

Ground geophysical surveying was specified for the Lackagh Quarry Ground Investigation. BRG Ltd were sub-contracted by Priority Drilling Ltd. to carry out the surveying. The geophysical surveys consisted of 2D Electrical Resistivity Tomography (ERT) and Microgravity across an initial area of roughly 300x30m, this area was subsequently extended to define the lateral and depth extent of a zone of deep overburden. The surveys were designed to test for subsurface heterogeneity and bedrock depths in advance of follow up rotary core drilling. Information on potential karst features were of particular interest to the client.


Microgravity data was acquired with measured sites along the centre line and 15m either side of the proposed tunnel section. These lines were measured with nominal station spacing of 10m, with gaps where scrub hawthorn was too thick. Extra stations were measured within the quarry on the first bench at 5-10m intervals. Measurements were taken using a Lacoste & Romberg model G gravity meter. Instrument drift was monitored by returning to a locally established base station at hourly intervals.

Stations were topographically surveyed using a Trimble GeoExplorer 6000 RTK GPS system corrected through phone modem link for both the ERT and the gravity surveys. The drift corrected gravity data was corrected for elevation, latitude, and reduced to Bouguer  $2.67\text{g/cm}^3$  to allow for local average rock densities. It was then gridded and exported for display and interpretation in the MapInfo GIS system (Figure 5).





**Figure 5:** Microgravity Station Locations



**Figure 6:** 2D Electrical Resistivity Tomography (ERT) Line / Station Locations



The depth mapping potential with the ERT is limited by the length of each spread. The variability of line lengths meant that the ERT surveying was capable of surveying to a minimum depth of 22m bgl on Line 5 to a maximum depth of 60m bgl on Line 6. Equipment used was an Allied Associates Tigre system which has the potential for up to 128 electrode takeouts. 2m station spacing was initially used to get the required detail along the chosen lines, with 3m intervals on the long lines (6, 7 & 8). Data was measured using a Wenner array, controlled by an Imager2006 programme with a laptop computer. Saved data was inverted using the Geotomo Res2Dinv programme and exported as an image file displaying a cross section of the inverted Resistivities with elevation data. The resultant resistivity sections were subsequently interpreted and an interpreted geological model developed.

Resistivity sections from the 2D ERT and the microgravity data show a marked contrast from high resistivity bedrock in the east with a sharp contact into very low resistivity zones to the west. The western region has a low gravity response coincident with the low resistivity. The base of the initial ERT lines did not penetrate below 30m, however, the low resistivity zone developed to the west suggests that this area was dominated by a significant deep overburden feature. Subsequent 2D ERT surveying, particularly line 6 defined a channel / basin shaped feature developed along a roughly east - west axis with sharp contacts to the north and south. The northern side of the feature seems to be step down into the core of the channel, which is roughly coincident with BH03. The surface geophysical report is appended as Appendix V.

### 3.3 Rotary Borehole Investigation

Five rotary boreholes were drilled during this phase of the investigation. Four vertical and one low angle borehole drilled from the quarry floor (Figures 5 & 6).

DHID	East	North	Elevation	Dip	Azimuth	Length (m)
BH01	530370.592	728426.557	16.712	-11.5°	268.3°	276.7
BH03	530023.824	728382.566	26.256	-90°	360°	109.9
BH04	530150.783	728400.125	32.167	-90°	360°	35
BH05	530186.649	728378.105	34.138	-90°	360°	40.3
BH06	530125.143	728383.081	30.799	-90°	360°	45

**Table 1:** Borehole Collar Locations

#### 3.3.1 Low Angle Drilling (HQ Core)

The low angle borehole, BH01, was drilled using a Dura Lite rig producing HQ diameter core (63.5mm). This borehole was drilled using a 3m hexagonal core barrel in order to minimise droop and deflection away from the planned section. The borehole was collared at an azimuth of 268.3° N<sub>mag</sub> and a dip of -11.5° to the horizontal. BH01 was located within the boundary of the quarry and was designed to drill into the quarry face. The hole was located at the base of the lower bench and rig

was stepped back approximately 6m from the quarry face. The face was scaled back before the rig was moved onto site using an excavator to remove loose, unstable rock material that was at risk of collapse. A concrete plinth was constructed between the borehole collar and the quarry face to support the rods whilst drilling and accordingly the first 6m cored from BH01 consists of concrete.

BH01 was drilled to a final depth of 276.7m. It was scheduled to drill to approximately 300m. However, poor quality and unconsolidated / cavernous ground intersected from 272.4m to the end of hole at 276.7m meant that the hole could not be continued.

After drilling was completed borehole BH01 was sealed at a depth of 175m using a Vann Ruth plug and was then backfilled with a cement / bentonite grout from 175m back to surface. The cavities in the lower part of the hole (175.0 - 276.7m) contributed to localised unstable ground conditions and it was considered a significant possibility that they may act as conduits to draw the cement / bentonite grout away from the hole, therefore, a plug was installed at 175m to seal the lower part of the hole.

### 3.3.2 Vertical Drilling (PQ Core)

The vertical boreholes (BH03, BH04, BH05 & BH06) were all drilled using a top drive Hang Seng drilling rig producing PQ diameter drill core (85mm). The holes were collared along the line of the proposed tunnel route to the west of the quarry. BH03 was scheduled to drill to a depth of 32.5m, however, it drilled through a deep overburden feature with very challenging, poorly consolidated ground, intersecting rock at a depth of 104.95m and stopping at a depth of 109.9m. The hole was cored to 85.55m in PQ and subsequently cased to 85m with PW casing. It was then open hole drilled using a HQ tricone until competent ground was intersected at 104.95m and continued to the end of hole with HQ core. Due to the instability of hole BH03 the planned piezometer could not be installed or the downhole geophysical survey carried out. It was backfilled with a cement / bentonite grout upon completion.


BH04 and BH05 were drilled to scheduled depths and intersected the expected geological succession of shallow overburden overlying competent, massively bedded limestones. Piezometers were installed in both of these holes. BH06 was an additional hole added to the ground investigation to test a zone of transition from competent to poorly consolidated rock / overburden that had been detected by the ground geophysical survey. This hole was drilled to a final depth of 45m in unconsolidated clay, sand and gravel it was backfilled with a cement grout from the end of hole back to a depth of 11.0m. A stand pipe was installed in the top of the hole.

The core from the rotary drilling was logged in accordance with the BS5930:1999 specification. A detailed geological description of the rock was generated and a


quantitative description of the fracture state of the rock core was provided for each borehole, including:

- Total Core Recovery (TCR)
- Solid Core Recovery (SCR)
- Fracture Index (FI)
- Fracture Number (FNo.)
- Rock Quality Designation (RQD)

The logs were generated using HoleBase AGS software (Hard copies - Appendix II).



**Figure 7:** Borehole Collar Locations, Traces and Line of Section



**Figure 8:** A - A' Drill Section (looking North) through the Lackagh Quarry GI Site

### 3.4 Discontinuity Logging

Discontinuity logging of rock cores was carried out using the ARUP "Rock Core Discontinuity Log" template for holes BH01, BH04 and BH05. The following headings were used:

- Orientation
- Spacing
- Roughness
- Weathering
- Infilling
- Number of Discontinuity Sets

The core from BH01 was orientated using a core orientation system mounted on the core barrel. and the discontinuities were measured relative to the invert of the core (NB: downhole direction is 180° up hole is 0°).

See Appendix III for the discontinuity logs.

### 3.5 Piezometer Installations

Three piezometers were installed in the vertical boreholes located to the west of the quarry. They were installed in boreholes BH04, BH05 and BH06. A summary of the installation design can be seen in Tables 2 - 4.

From (m)	To (m)	Installation
0.00	28.00	Blank 19mm PVC Pipe
28.00	34.00	Slotted 19mm PVC Pipe
34.00		End Cap
0.00	21.00	Cement Grout
21.00	23.00	Bentonite Pellets
23.00	24.00	Sand
24.00	34.00	Pea Gravel
34.00	35.00	Gravel Base

**Table 2:** BH04 Piezometer Installation Details

From (m)	To (m)	Installation
0.00	33.00	Blank 19mm PVC Pipe
33.00	39.00	Slotted 19mm PVC Pipe
39.00		End Cap
0.00	19.00	Cement Grout
19.00	23.00	Bentonite Pellets
23.00	24.00	Sand
24.00	39.00	Pea Gravel
39.00	40.30	Gravel Base

**Table 3:** BH05 Piezometer Installation Details

From (m)	To (m)	Installation
0.00	4.00	Blank 19mm PVC Pipe
4.00	10.00	Slotted 19mm PVC Pipe
10.00		End Cap
0.00	1.00	Cement Grout
1.00	2.00	Bentonite Pellets
2.00	3.00	Sand
3.00	11.00	Pea Gravel
11.00	45.00	Cement Grout

**Table 4:** BH06 Piezometer Installation Details

### 3.6 Borehole Geophysical Surveying

Ground geophysical surveying was specified for the Lackagh Quarry Ground Investigation. European Geophysical Services Ltd were sub-contracted by Priority Drilling Ltd. to carry out this surveying. It was originally intended to survey three boreholes, however, the poor ground conditions encountered in BH03 meant that only BH04 and BH05 were surveyed.

The geophysical surveys consisted of:

- Optical Televiwer
- Acoustic Televiwer
- Fluid Temperature and Conductivity, Natural Gamma Calliper
- Impeller Flowmeter
- Focused Resistivity
- Full Wave Sonic Velocity
- Pumped Temperature and Conductivity

Report attached as Appendix VI

### 3.7 Rock / Soil / Water - Laboratory Testing

Core samples were taken from the rock / soil recovered during the drilling operations and forwarded to two accredited laboratories for a testing. The Celtest Laboratory near Bangor in North Wales was selected to carry out the rock testing. The Priority Geotechnical Soil testing Laboratory was selected to carry out the soil testing.

Test	BH01 (No.)	BH04 (No.)	BH05 (No.)	Total Number of Tests
Deformability in Uniaxial Compression	10	5	5	20
Indirect Tensile Strength by Brazilian Test	3	1	1	5
Natural Water Content	40	10	9	59
Oxidisable Sulphate	5	1	1	7
pH Value	5	1	1	7
Point Load	58	25	25	108
Porosity / Density using Saturation & Buoyancy	15	2	3	20
Porosity / Density using Saturation & Calliper	15	2	3	20
Thin Section Petrography	2	1	1	4
Total Sulphur	6	1	1	8
Uniaxial Compressive Strength	36	10	10	56
<b>Total</b>	<b>195</b>	<b>59</b>	<b>60</b>	<b>314</b>

**Table 5:** Scheduled Rock Tests

Test	BH03 (No.)	BH06 (No.)	Total Number of Tests
Atterberg Limits	9	3	12
Moisture Content	19	3	22
Oedometer	4	3	7
Organic Matter Content	9	3	12
Particle Size Distribution	9	0	9
pH Value	5	0	5
Triaxial Test (Unconsolidated / Undrained)	5	3	8
<b>Total</b>	<b>60</b>	<b>15</b>	<b>75</b>

**Table 6:** Scheduled Soil Tests

A suite of aggregate tests had been scheduled in the Bill of Quantities, including:

- Slake Durability Index
- Los Angeles Coefficient
- Aggregate Crushing Value
- Ten Percent Fines
- Aggregate Impact Value
- Aggregate Abrasion Value
- Polished Stone Value
- Aggregate Frost Heave

The volume of material required to carry out these tests was excessive (e.g. the Aggregate Frost Heave test needs a minimum of 75kg of rock) and would have taken the bulk of the available drill core. Given the relatively homogenous nature of the limestone intersected it was agreed that a representative bulk sample would be acquired from the quarry and sent for the specified aggregate testing. Accordingly, a



composite, 275kg, representative sample was obtained from the quarry and sent to Celtest.

Water samples were obtained from the piezometers in boreholes BH04, BH05 and BH06 and sent to the IAS Laboratory in Bagenalstown, Co Carlow for testing for major cations and anions.

Test results are summarised in Tables 7 - 10 certificates are attached as Appendix VII

Location ID	Sample ID	Depth Top	Depth Base	Test	Result
BH01	48861	6.70	6.80	Moisture Content	1.20%
BH01	48862	10.36	10.46	Point Load	79.3MPa
BH01	48863	10.46	10.69	Uniaxial Compressive Strength	97MPa
BH01	48864	10.69	10.76	Point Load	78MPa
BH01	48865	10.89	10.97	Porosity / Density using Saturation and Buoyancy	0.5 / 2.63
BH01	48866	10.97	11.07	Porosity / Density using Saturation and Calliper	0.47/2.69
BH01	48867	11.57	11.94	Deformability in Uniaxial Compression	99.8MPa
BH01	48868	13.26	13.35	Moisture Content	1.60%
BH01	48869	13.35	13.45	Point Load	82.9MPa
BH01	48870	13.45	13.70	Uniaxial Compressive Strength	59MPa
BH01	48871	13.70	13.80	Point Load	71.9MPa
BH01	48872	16.30	16.40	Point Load	67.7MPa
BH01	48873	16.40	16.66	Uniaxial Compressive Strength	73MPa
BH01	48874	16.66	16.80	Point Load	76.5MPa
BH01	48875	22.40	22.50	Porosity / Density using Saturation and Calliper	0.58/2.65
BH01	48876	22.50	22.60	Porosity / Density using Saturation and Buoyancy	1.2 / 2.70
BH01	48877	26.20	26.36	Point Load	47.1MPa
BH01	48878	26.36	26.61	Uniaxial Compressive Strength	100MPa
BH01	48879	26.61	26.70	Point Load	60.5MPa
BH01	48880	27.85	28.15	Deformability in Uniaxial Compression	112.4MPa
BH01	48881	32.65	32.72	Moisture Content	1.40%
BH01	48882	34.44	34.48	Point Load	88.8MPa
BH01	48883	34.48	34.73	Uniaxial Compressive Strength	69MPa
BH01	48884	34.73	34.83	Point Load	62.2MPa
BH01	48885	44.35	44.40	Porosity / Density using Saturation and Calliper	0.54/2.70
BH01	48886	44.45	44.54	Point Load	84.8MPa
BH01	48887	44.54	44.79	Uniaxial Compressive Strength	83MPa
BH01	48888	44.79	44.90	Point Load	53.0MPa

BH01	<b>48889</b>	45.65	45.74	Porosity / Density using Saturation and Buoyancy	<b>0.5/2.68</b>
BH01	<b>48890</b>	48.90	49.16	Deformability in Uniaxial Compression	<b>187.5MPa</b>
BH01	<b>48891</b>	53.80	53.93	Total Sulphur	<b>&lt;0.1%</b>
BH01	<b>48892</b>	55.30	55.40	Oxidisable Sulphate	<b>&lt;0.01%</b>
BH01	<b>48893</b>	55.84	55.92	pH Value	<b>9.1</b>
BH01	<b>48894</b>	56.50	56.60	Point Load	<b>64.4MPa</b>
BH01	<b>48895</b>	56.60	56.85	Uniaxial Compressive Strength	<b>138MPa</b>
BH01	<b>48896</b>	56.85	56.93	Point Load	<b>63.9MPa</b>
BH01	<b>48897</b>	57.30	57.40	Moisture Content	<b>1.10%</b>
BH01	<b>48898</b>	61.65	61.75	Moisture Content	<b>1.20%</b>
BH01	<b>48899</b>	62.76	62.86	Point Load	<b>83.4MPa</b>
BH01	<b>48900</b>	62.86	63.05	Uniaxial Compressive Strength	<b>65MPa</b>
BH01	<b>50857</b>	63.05	63.16	Point Load	<b>49.6MPa</b>
BH01	<b>50858</b>	64.20	64.50	Indirect Tensile Strength by Brazilian Test	<b>7.8MPa</b>
BH01	<b>50859</b>	65.40	65.50	Total Sulphur	<b>&lt;0.1%</b>
BH01	<b>50860</b>	65.66	65.75	Porosity / Density using Saturation and Buoyancy	<b>0.2/2.72</b>
BH01	<b>50861</b>	65.75	65.92	Porosity / Density using Saturation and Calliper	<b>0.64/2.69</b>
BH01	<b>50862</b>	66.00	66.10	Point Load	<b>69.6MPa</b>
BH01	<b>50863</b>	66.10	66.34	Uniaxial Compressive Strength	<b>104MPa</b>
BH01	<b>50864</b>	66.34	66.45	Point Load	<b>62.6MPa</b>
BH01	<b>50865</b>	67.07	67.20	Moisture Content	<b>1.10%</b>
BH01	<b>50866</b>	67.20	67.28	Porosity / Density using Saturation and Calliper	<b>0.57/2.71</b>
BH01	<b>50867</b>	68.50	68.59	Porosity / Density using Saturation and Buoyancy	<b>0.2/2.63</b>
BH01	<b>50868</b>	70.10	70.20	Moisture Content	<b>1.30%</b>
BH01	<b>50869</b>	72.10	72.30	Deformability in Uniaxial Compression	<b>136.3MPa</b>
BH01	<b>50870</b>	73.03	73.10	Moisture Content	<b>1.60%</b>
BH01	<b>50871</b>	76.00	76.09	Moisture Content	<b>1.20%</b>
BH01	<b>50872</b>	79.10	79.18	Point Load	<b>51.8MPa</b>
BH01	<b>50873</b>	79.18	79.40	Uniaxial Compressive Strength	<b>62MPa</b>
BH01	<b>50874</b>	79.40	79.52	Point Load	<b>48.0MPa</b>
BH01	<b>50875</b>	80.04	80.12	Moisture Content	<b>1.20%</b>
BH01	<b>50876</b>	81.70	81.78	Moisture Content	<b>1.60%</b>
BH01	<b>50877</b>	87.50	87.57	Moisture Content	<b>1.80%</b>
BH01	<b>50878</b>	39.70	39.80	Moisture Content	<b>1.30%</b>
BH01	<b>50879</b>	91.10	91.20	Total Sulphur	<b>&lt;0.1%</b>
BH01	<b>50880</b>	91.34	91.42	Porosity / Density using Saturation and Calliper	<b>0.49/2.71</b>
BH01	<b>50881</b>	91.42	91.51	Porosity / Density using Saturation and Buoyancy	<b>1.0/2.70</b>
BH01	<b>50882</b>	91.63	91.71	Moisture Content	<b>1.80%</b>
BH01	<b>50883</b>	92.35	92.47	Point Load	<b>73.3MPa</b>
BH01	<b>50884</b>	92.47	92.70	Uniaxial Compressive Strength	<b>76MPa</b>



BH01	50885	92.70	92.79	Point Load	71.1
BH01	50886	93.00	93.10	Moisture Content	1.50%
BH01	50887	94.90	94.96	Oxidisable Sulphate	<0.01%
BH01	50888	94.96	95.05	pH Value	9.2
BH01	50889	97.34	97.43	Moisture Content	1.30%
BH01	50890	97.95	98.23	Deformability in Uniaxial Compression	110.0MPa
BH01	50891	101.36	101.45	Moisture Content	1.60%
BH01	50892	102.90	103.20	Indirect Tensile Strength by Brazilian Test	12.6MPa
BH01	50893	108.15	108.22	Point Load	61.2MPa
BH01	50894	108.22	108.51	Uniaxial Compressive Strength	107MPa
BH01	50895	108.51	108.62	Point Load	70.2MPa
BH01	50896	108.62	108.70	Moisture Content	1.20%
BH01	50897	110.27	110.37	Porosity / Density using Saturation and Calliper	0.57/2.69
BH01	50898	110.37	110.45	Porosity / Density using Saturation and Buoyancy	0.7/2.59
BH01	50899	113.00	113.08	Thin Section - Petrology	
BH01	50900	113.12	113.19	Moisture Content	1.50%
BH01	50901	115.89	116.05	Point Load	52.5MPa
BH01	50902	116.05	116.29	Uniaxial Compressive Strength	104MPa
BH01	50903	116.29	116.39	Point Load	62.2MPa
BH01	50904	118.82	118.88	Moisture Content	1.90%
BH01	50905	123.44	123.55	Moisture Content	2.20%
BH01	50906	125.90	126.00	Moisture Content	1.30%
BH01	50907	126.80	126.90	Moisture Content	2.50%
BH01	50908	128.80	128.89	Point Load	80.8MPa
BH01	50909	128.89	129.14	Uniaxial Compressive Strength	79MPa
BH01	50910	129.14	129.21	Point Load	84.0MPa
BH01	50911	131.12	131.17	Moisture Content	2.60%
BH01	50912	131.60	131.70	Moisture Content	1.20%
BH01	50913	132.65	132.62	Moisture Content	1.80%
BH01	50914	133.21	133.32	Point Load	69.2MPa
BH01	50915	133.32	133.54	Uniaxial Compressive Strength	110MPa
BH01	50916	133.54	133.63	Point Load	61.8MPa
BH01	50917	134.35	134.44	Moisture Content	1.10%
BH01	50918	137.06	137.20	Porosity / Density using Saturation and Calliper	0.76/2.81
BH01	50919	37.20	137.30	Porosity / Density using Saturation and Buoyancy	0.3/2.63
BH01	50920	138.60	138.72	pH Value	9.2
BH01	50921	140.00	140.20	Deformability in Uniaxial Compression	58.7MPa
BH01	50922	142.81	142.91	Moisture Content	1.30%
BH01	50923	146.20	146.30	Point Load	55.0MPa
BH01	50924	146.30	146.52	Uniaxial Compressive Strength	100MPa
BH01	50925	146.52	146.61	Point Load	62.6MPa
BH01	50926	148.97	149.05	Thin Section - Petrology	

BH01	<b>50927</b>	150.29	150.37	Porosity / Density using Saturation and Calliper	<b>0.61/2.75</b>
BH01	<b>50928</b>	151.67	151.75	Porosity / Density using Saturation and Buoyancy	<b>0.7/2.67</b>
BH01	<b>50929</b>	152.97	153.04	Total Sulphur	<b>&lt;0.1%</b>
BH01	<b>50930</b>	153.20	153.30	Oxidisable Sulphate	<b>&lt;0.01%</b>
BH01	<b>50931</b>	154.60	154.68	Moisture Content	<b>1.40%</b>
BH01	<b>50932</b>	155.20	155.28	Moisture Content	<b>1.70%</b>
BH01	<b>50933</b>	156.33	156.44	Point Load	<b>42.0MPa</b>
BH01	<b>50934</b>	156.44	156.68	Uniaxial Compressive Strength	<b>86MPa</b>
BH01	<b>50935</b>	156.68	156.76	Point Load	<b>47.3MPa</b>
BH01	<b>50936</b>	163.49	163.56	Moisture Content	<b>2.50%</b>
BH01	<b>50937</b>	165.17	165.25	Point Load	<b>77.7MPa</b>
BH01	<b>50938</b>	165.25	165.49	Uniaxial Compressive Strength	<b>83MPa</b>
BH01	<b>50939</b>	165.49	165.58	Point Load	<b>64.6MPa</b>
BH01	<b>50940</b>	166.00	166.10	Moisture Content	<b>1.30%</b>
BH01	<b>50941</b>	172.96	173.07	Porosity / Density using Saturation and Calliper	<b>0.49/2.68</b>
BH01	<b>50942</b>	173.07	173.20	Porosity / Density using Saturation and Buoyancy	<b>0.4/2.72</b>
BH01	<b>50943</b>	174.47	174.69	Uniaxial Compressive Strength	<b>76MPa</b>
BH01	<b>50944</b>	175.18	175.26	Point Load	<b>58.6MPa</b>
BH01	<b>50945</b>	175.26	175.50	Uniaxial Compressive Strength	<b>86MPa</b>
BH01	<b>50946</b>	175.50	175.59	Point Load	<b>58.6MPa</b>
BH01	<b>50947</b>	176.00	176.10	Moisture Content	<b>1.20%</b>
BH01	<b>50948</b>	180.24	180.50	Indirect Tensile Strength by Brazilian Test	<b>14.6MPa</b>
BH01	<b>50949</b>	182.12	182.20	pH Value	<b>9.3</b>
BH01	<b>50950</b>	183.17	183.40	Deformability in Uniaxial Compression	<b>118.6MPa</b>
BH01	<b>50951</b>	183.90	184.02	Point Load	<b>48.8MPa</b>
BH01	<b>50952</b>	184.02	184.25	Uniaxial Compressive Strength	<b>97MPa</b>
BH01	<b>50953</b>	184.25	184.34	Point Load	<b>70.1MPa</b>
BH01	<b>50954</b>	196.19	186.25	Moisture Content	<b>1.80%</b>
BH01	<b>50955</b>	193.60	193.68	Total Sulphur	<b>&lt;0.1%</b>
BH01	<b>50956</b>	194.13	194.20	Porosity / Density using Saturation and Calliper	<b>0.54/2.69</b>
BH01	<b>50957</b>	194.60	194.67	Point Load	<b>48.0MPa</b>
BH01	<b>50958</b>	194.67	194.90	Uniaxial Compressive Strength	<b>114MPa</b>
BH01	<b>50959</b>	194.90	194.99	Point Load	<b>57.6MPa</b>
BH01	<b>50960</b>	195.77	195.86	Porosity / Density using Saturation and Buoyancy	<b>0.5/2.71</b>
BH01	<b>50961</b>	201.47	201.55	Oxidisable Sulphate	<b>&lt;0.01%</b>
BH01	<b>50962</b>	204.62	204.70	Point Load	<b>83.6MPa</b>
BH01	<b>50963</b>	204.70	204.95	Uniaxial Compressive Strength	<b>132MPa</b>
BH01	<b>50964</b>	204.95	205.02	Point Load	<b>60.5</b>
BH01	<b>50965</b>	209.65	209.72	Moisture Content	<b>1.70%</b>
BH01	<b>50966</b>	210.18	210.30	Porosity / Density using Saturation and Calliper	<b>0.65/2.69</b>

BH01	50967	210.30	210.40	Porosity / Density using Saturation and Buoyancy	0.3/2.85
BH01	50968	210.57	210.82	Uniaxial Compressive Strength	111MPa
BH01	50969	211.10	211.20	Moisture Content	1.40%
BH01	50970	211.77	211.85	Point Load	56.2MPa
BH01	50971	211.85	212.10	Uniaxial Compressive Strength	52MPa
BH01	50972	212.10	212.20	Point Load	68.7MPa
BH01	50973	212.33	212.58	Deformability in Uniaxial Compression	104.7MPa
BH01	50974	213.80	213.90	pH Value	9.1
BH01	50975	218.20	218.28	Moisture Content	1.50%
BH01	50976	222.52	222.62	Moisture Content	1.00%
BH01	50977	223.70	223.80	Porosity / Density using Saturation and Calliper	0.56/2.75
BH01	50978	224.08	224.20	Porosity / Density using Saturation and Buoyancy	0.3/2.63
BH01	50979	225.65	225.74	Point Load	80.3MPa
BH01	50980	225.74	225.95	Uniaxial Compressive Strength	77MPa
BH01	50981	225.95	226.03	Point Load	72.3MPa
BH01	50982	228.16	228.24	Porosity / Density using Saturation and Calliper	0.64/2.70
BH01	50983	228.24	228.32	Porosity / Density using Saturation and Buoyancy	0.4/2.65
BH01	50984	230.13	230.20	Moisture Content	2.00%
BH01	50985	231.65	231.78	Point Load	53.0MPa
BH01	50986	231.78	232.00	Uniaxial Compressive Strength	111MPa
BH01	50987	232.00	232.10	Point Load	74.6MPa
BH01	50988	232.46	232.60	Deformability in Uniaxial Compression	69.6MPa
BH01	50989	235.04	235.10	Moisture Content	1.30%
BH01	50990	235.64	235.73	Total Sulphur	<0.1%
BH01	50991	236.73	237.03	Uniaxial Compressive Strength	80MPa
BH01	50992	237.17	237.43	Uniaxial Compressive Strength	76MPa
BH01	50993	242.82	242.92	Point Load	53.8MPa
BH01	50994	242.92	243.14	Uniaxial Compressive Strength	118MPa
BH01	50995	243.14	243.23	Point Load	64.6MPa
BH01	50996	250.30	250.56	Deformability in Uniaxial Compression	56.4MPa
BH01	50997	251.81	251.95	Point Load	52.5MPa
BH01	50998	251.95	252.22	Uniaxial Compressive Strength	121MPa
BH01	50999	252.22	252.32	Point Load	61.4MPa
BH01	51000	253.30	253.38	Oxidisable Sulphate	<0.01%
BH01	51001	259.72	259.82	Point Load	64.1MPa
BH01	51002	259.82	260.06	Uniaxial Compressive Strength	143MPa
BH01	51003	260.06	260.18	Point Load	44.9MPa
BH01	51004	262.43	262.63	Uniaxial Compressive Strength	66MPa
BH01	51005	262.63	262.73	Point Load	67.7MPa
BH01	51006	264.80	164.93	Point Load	48.5MPa
BH01	51007	264.93	264.15	Uniaxial Compressive Strength	83MPa
BH01	51008	265.15	265.25	Porosity / Density using Saturation and Calliper	0.63/2.65

BH01	51009	265.25	265.38	Porosity / Density using Saturation and Buoyancy	0.5/2.64
BH01	51010	268.30	268.40	Uniaxial Compressive Strength	90MPa
BH01	51011	271.70	271.90	Uniaxial Compressive Strength	91MPa

**Table 7:** Summary of Rock Test Results in BH01.

Location ID	Sample ID	Depth Top	Depth Base	Test	Certificate
BH03	48801	4.15	4.42	Triaxial - Unconsolidated / Undrained	x
BH03	48802	13.65	13.73	Moisture Content	x
BH03	48803	13.73	13.85	Atterberg Limits	x
BH03	48804	14.90	15.00	Particle Size Distribution	x
BH03	48805	19.00	19.10	Particle Size Distribution	x
BH03	48806	19.10	19.20	Atterberg Limits	x
BH03	48807	19.25	19.30	Moisture Content	x
BH03	48808	19.90	20.00	Moisture Content	x
BH03	48809	20.95	21.05	pH	x
BH03	48810	21.30	21.40	Moisture Content	x
BH03	48811	25.50	25.60	Particle Size Distribution	x
BH03	48812	25.80	25.90	Particle Size Distribution	x
BH03	48813	26.50	26.60	Particle Size Distribution	x
BH03	48814	26.70	26.80	Particle Size Distribution	x
BH03	48815	27.20	27.25	pH	x
BH03	48816	27.45	27.55	Atterberg Limits	x
BH03	48817	27.55	27.65	Particle Size Distribution	x
BH03	48818	30.25	30.33	Particle Size Distribution	x
BH03	48819	31.20	31.30	Moisture Content	x
BH03	48822	33.95	34.03	Moisture Content	x
BH03	48824	36.70	36.80	Particle Size Distribution	x
BH03	48825	38.60	38.70	Moisture Content	x
BH03	48826	38.95	39.05	Organic Matter Content	x
BH03	48827	39.25	39.30	Atterberg Limits	x
BH03	48828	39.45	39.55	Organic Matter Content	x
BH03	48829	39.80	39.83	Moisture Content	x
BH03	48830	40.65	40.77	Atterberg Limits	x
BH03	48831	41.20	41.25	pH	x
BH03	48832	41.30	41.50	Oedometer	x
BH03	48833	41.85	42.08	Triaxial - Unconsolidated / Undrained	x
BH03	48834	42.30	42.35	Moisture Content	x
BH03	48835	42.35	42.40	Organic Matter Content	x
BH03	48836	42.65	42.97	Triaxial - Unconsolidated / Undrained	x
BH03	48837	42.97	43.30	Oedometer	x
BH03	48838	44.05	44.20	Oedometer	x
BH03	48839	46.20	46.27	Organic Matter Content	x
BH03	48840	46.27	46.59	Triaxial - Unconsolidated / Undrained	x
BH03	48841	47.00	47.10	pH	x

BH03	48842	47.20	47.27	Moisture Content	x
BH03	48843	47.45	47.55	Organic Matter Content	x
BH03	48844	47.85	48.02	Oedometer	x
BH03	48845	48.20	48.30	Atterberg Limits	x
BH03	48846	48.45	48.70	Triaxial - Unconsolidated / Undrained	x
BH03	48847	49.00	49.10	Organic Matter Content	x
BH03	48848	49.30	49.40	Moisture Content	x
BH03	48849	63.15	63.22	Organic Matter Content	x
BH03	48850	63.38	63.43	pH	x
BH03	48851	63.50	63.55	Moisture Content	x
BH03	48852	63.90	63.95	Organic Matter Content	x
BH03	48853	64.30	64.35	Moisture Content	x
BH03	48854	64.90	64.95	Organic Matter Content	x
BH03	48855	65.50	65.60	Moisture Content	x
BH03	48856	66.95	67.05	Moisture Content	x
BH03	48857	68.40	68.45	Moisture Content	x
BH03	48858	70.40	70.50	Moisture Content	x
BH03	48859	70.75	70.85	Moisture Content	x
BH03	48860	71.60	71.70	Moisture Content	x
BH06	50742	5.25	5.50	Triaxial - Unconsolidated / Undrained	x
BH06	50744	16.20	16.50	Oedometer	x
BH06	50745	16.60	16.70	Moisture Content	x
BH06	50746	16.70	16.80	Atterberg Limits	x
BH06	50747	17.13	17.20	Organic Matter Content	x
BH06	50748	18.00	18.25	Triaxial - Unconsolidated / Undrained	x
BH06	50749	18.25	18.35	Moisture Content	x
BH06	50750	18.65	18.75	Atterberg Limits	x
BH06	50851	18.95	19.05	Organic Matter Content	x
BH06	50852	19.70	19.95	Oedometer	x
BH06	50853	20.00	20.25	Oedometer	x
BH06	50854	21.45	21.52	Moisture Content	x
BH06	50855	21.52	21.60	Atterberg Limits	x
BH06	50856	21.75	21.80	Organic Matter Content	x

**Table 8:** Summary of Soil Test Results in BH03 & BH06.

Location ID	Sample ID	Depth Top	Depth Base	Test	Result
BH04	48901	3.5	3.55	Moisture Content	0.20%
BH04	48902	5.4	5.48	Moisture Content	0.60%
BH04	48903	8.06	8.36	Deformability in Uniaxial Compression	119.9MPa
BH04	48904	9.3	9.36	Moisture Content	0.30%
BH04	48905	10.63	10.88	Deformability in Uniaxial Compression	41.6MPa
BH04	48906	11.77	11.83	Moisture Content	0.20%
BH04	48907	12.62	12.75	Point Load	59.2MPa
BH04	48908	12.85	13.1	Uniaxial Compressive Strength	76MPa
BH04	48909	13.1	13.25	Point Load	52.7MPa

BH04	<b>48910</b>	14.4	14.63	Deformability in Uniaxial Compression	<b>62.0MPa</b>
BH04	<b>48911</b>	14.63	14.74	Point Load	<b>49.2MPa</b>
BH04	<b>48912</b>	14.74	14.97	Uniaxial Compressive Strength	<b>86MPa</b>
BH04	<b>48913</b>	14.97	15.13	Point Load	<b>60.1MPa</b>
BH04	<b>48914</b>	11.77	11.83	Porosity / Density using Saturation and Calliper & Porosity / Density using Saturation and Buoyancy	<b>0.2/2.72</b>
BH04	<b>48915</b>	17.74	17.86	Point Load	<b>60.2MPa</b>
BH04	<b>48917</b>	18.12	18.2	Point Load	<b>56.5MPa</b>
BH04	<b>48918</b>	19.2	19.32	Point Load	<b>36.5MPa</b>
BH04	<b>48919</b>	20.05	20.12	Thin Section / Petrography	
BH04	<b>48920</b>	20.12	20.22	Point Load	<b>73.9MPa</b>
BH04	<b>48921</b>	20.22	20.5	Uniaxial Compressive Strength	<b>55MPa</b>
BH04	<b>48922</b>	20.8	20.85	Moisture Content	<b>0.40%</b>
BH04	<b>48923</b>	21.2	21.3	Point Load	<b>68.4MPa</b>
BH04	<b>48924</b>	21.8	21.9	Moisture Content	<b>1%</b>
BH04	<b>48925</b>	22.2	22.31	Point Load	<b>90.2MPa</b>
BH04	<b>48926</b>	22.6	22.78	Point Load	<b>60.1MPa</b>
BH04	<b>48927</b>	22.78	23.06	Uniaxial Compressive Strength	<b>53MPa</b>
BH04	<b>48928</b>	23.1	23.2	Point Load	<b>64.6MPa</b>
BH04	<b>48929</b>	21.8	21.9	Porosity / Density using Saturation and Calliper & Porosity / Density using Saturation and Buoyancy	<b>0.4/2.69</b>
BH04	<b>48930</b>	23.7	23.8	Point Load	<b>77.7MPa</b>
BH04	<b>48931</b>	23.8	24.1	Uniaxial Compressive Strength	<b>111MPa</b>
BH04	<b>48932</b>	24.17	24.28	Point Load	<b>74MPa</b>
BH04	<b>48933</b>	24.28	24.52	Uniaxial Compressive Strength	<b>91MPa</b>
BH04	<b>48934</b>	25.08	25.19	Point Load	<b>77.5MPa</b>
BH04	<b>48935</b>	25.19	25.41	Deformability in Uniaxial Compression	<b>64.1MPa</b>
BH04	<b>48936</b>	28.27	28.4	Porosity / Density using Saturation and Calliper	<b>0.5/2.65</b>
BH04	<b>48937</b>	27.91	28	Point Load	<b>89.4MPa</b>
BH04	<b>48938</b>	28.27	28.4	Moisture Content	<b>0.10%</b>
BH04	<b>48939</b>	28.4	28.44	Point Load	<b>68.3MPa</b>
BH04	<b>48941</b>	29.38	29.54	Indirect Tensile Strength by Brazilian Test	<b>5.97MPa</b>
BH04	<b>48943</b>	29.86	29.94	Point Load	<b>92MPa</b>
BH04	<b>48949</b>	30.93	30.03	Point Load	<b>76.6MPa</b>
BH04	<b>48950</b>	31.03	31.3	Uniaxial Compressive Strength	<b>76MPa</b>
BH04	<b>48951</b>	31.3	31.4	Point Load	<b>67.8MPa</b>
BH04	<b>48954</b>	31.66	31.7	Total Sulphur	<b>&lt;0.1%</b>
BH04	<b>48955</b>	31.76	31.84	Point Load	<b>59.6MPa</b>
BH04	<b>48956</b>	31.84	31.93	Oxidisable Sulphur	<b>0.04</b>
BH04	<b>48957</b>	31.93	32.15	Uniaxial Compressive Strength	<b>78MPa</b>
BH04	<b>48958</b>	32.15	32.26	Point Load	<b>55.4MPa</b>
BH04	<b>48959</b>	32.26	32.35	pH	<b>9.3</b>
BH04	<b>48962</b>	32.5	32.57	Point Load	<b>78.8MPa</b>
BH04	<b>48963</b>	32.57	32.85	Uniaxial Compressive Strength	<b>92MPa</b>
BH04	<b>48964</b>	32.85	32.96	Point Load	<b>65.5MPa</b>



BH04	<b>48965</b>	33.12	33.16	Moisture Content	<b>0.10%</b>
BH04	<b>48966</b>	33.2	33.48	Deformability in Uniaxial Compression	<b>66.5MPa</b>
BH04	<b>48967</b>	33.48	33.6	Point Load	<b>49.9MPa</b>
BH04	<b>48968</b>	32.35	32.43	Porosity / Density using Saturation and Buoyancy	<b>0.4/2.69</b>
BH04	<b>48969</b>	34.56	34.59	Moisture Content	<b>0.30%</b>
BH04	<b>48970</b>	34.96	35	Moisture Content	<b>0.20%</b>
BH05	<b>48971</b>	0.65	0.73	Moisture Content	<b>0.30%</b>
BH05	<b>48972</b>	0.98	1.04	Moisture Content	<b>0.10%</b>
BH05	<b>48973</b>	1.41	1.5	Moisture Content	<b>0.10%</b>
BH05	<b>48974</b>	2.62	2.67	Porosity / Density using Saturation and Calliper	<b>0.4/2.68</b>
BH05	<b>48975</b>	2.8	2.96	Point Load	<b>27.8Mpa</b>
BH05	<b>48976</b>	1.41	1.5	Porosity / Density using Saturation and Buoyancy	<b>0.3/2.65</b>
BH05	<b>48977</b>	7.73	7.84	Point Load	<b>63MPa</b>
BH05	<b>48978</b>	8.1	8.25	Point Load	<b>43.8MPa</b>
BH05	<b>48979</b>	8.54	8.66	Point Load	<b>62MPa</b>
BH05	<b>48980</b>	8.9	8.96	Moisture Content	<b>0.10%</b>
BH05	<b>48981</b>	9.46	9.57	Point Load	<b>91.5MPa</b>
BH05	<b>48982</b>	9.57	9.77	Uniaxial Compressive Strength	<b>91MPa</b>
BH05	<b>48983</b>	9.77	9.92	Point Load	<b>55.4MPa</b>
BH05	<b>48984</b>	10.2	10.26	Point Load	<b>101.0MPa</b>
BH05	<b>48985</b>	11.3	11.45	Point Load	<b>43.1MPa</b>
BH05	<b>48986</b>	11.45	11.72	Uniaxial Compressive Strength	<b>86MPa</b>
BH05	<b>48987</b>	11.72	11.83	Point Load	<b>77.2MPa</b>
BH05	<b>48988</b>	12.92	13.07	Moisture Content	<b>0.30%</b>
BH05	<b>48989</b>	13.5	13.6	Point Load	<b>141.1MPa</b>
BH05	<b>48990</b>	13.7	13.81	Point Load	<b>67.3MPa</b>
BH05	<b>48991</b>	13.81	14.07	Uniaxial Compressive Strength	<b>94MPa</b>
BH05	<b>48992</b>	14.07	14.15	Point Load	<b>84.4MPa</b>
BH05	<b>48993</b>	14.27	14.4	Point Load	<b>74.0MPa</b>
BH05	<b>48994</b>	14.65	14.89	Uniaxial Compressive Strength	<b>72MPa</b>
BH05	<b>48995</b>	15.43	15.55	Point Load	<b>81.8MPa</b>
BH05	<b>48996</b>	15.95	16.22	Deformability in Uniaxial Compression	<b>57.0MPa</b>
BH05	<b>48997</b>	16.45	16.55	Point Load	<b>67.3MPa</b>
BH05	<b>48998</b>	16.87	17.19	Uniaxial Compressive Strength	<b>77MPa</b>
BH05	<b>48999</b>	17.97	18.06	Porosity / Density using Saturation and Buoyancy	<b>0.3/2.69</b>
BH05	<b>50701</b>	19.7	19.92	Indirect Tensile Strength by Brazilian Test	<b>3.39MPa</b>
BH05	<b>50702</b>	28.85	28.95	Porosity / Density using Saturation and Calliper	<b>0.4/2.69</b>
BH05	<b>50703</b>	22.07	22.21	Point Load	<b>54.3MPa</b>
BH05	<b>50704</b>	22.9	23	Point Load	<b>87.3MPa</b>
BH05	<b>50705</b>	23.94	24.05	Point Load	<b>67.2MPa</b>
BH05	<b>50706</b>	24.05	24.3	Deformability in Uniaxial Compression	<b>44.9MPa</b>
BH05	<b>50707</b>	24.73	24.85	Point Load	<b>66.4MPa</b>
BH05	<b>50708</b>	25.2	25.4	Deformability in Uniaxial Compression	<b>22.6MPa</b>

BH05	50709	26	26.12	Point Load	76.4MPa
BH05	50710	26.12	26.35	Deformability in Uniaxial Compression	66.3MPa
BH05	50711	27.68	27.88	Uniaxial Compressive Strength	79MPa
BH05	50712	28.75	28.85	Moisture Content	0.10%
BH05	50715	29.09	29.18	Total Sulphur	<0.1
BH05	50716	29.18	29.3	Oxidisable Sulphur	<0.01
BH05	50717	29.3	29.4	pH	9.2
BH05	50718	30.3	30.4	Moisture Content	0.40%
BH05	50721	30.88	30.92	Moisture Content	0.30%
BH05	50725	32.44	32.54	Point Load	76.8MPa
BH05	50726	32.54	32.6	Moisture Content	0.20%
BH05	50727	32.83	32.92	Point Load	66.7MPa
BH05	50728	32.92	33	Thin Section / Petrography	
BH05	50729	33	33.26	Uniaxial Compressive Strength	116MPa
BH05	50730	33.22	33.26	Porosity / Density using Saturation and Calliper	0.6/2.69
BH05	50731	33.5	33.7	Uniaxial Compressive Strength	51MPa
BH05	50733	33.92	33.16	Uniaxial Compressive Strength	54MPa
BH05	50735	34.5	34.7	Porosity / Density using Saturation and Buoyancy	0.4/2.68
BH05	50736	37.4	37.5	Point Load	80.7MPa
BH05	50737	37.5	37.82	Uniaxial Compressive Strength	131MPa
BH05	50738	37.82	37.92	Point Load	77.2MPa
BH05	50740	37.92	38.08	Point Load	52.3MPa

Table 9: Summary of Rock Test Results in BH04 &amp; BH05

Sample	Test	Result
Bulk Sample	Aggregate Crushing Value	23%
Bulk Sample	Aggregate Impact Value	17%
Bulk Sample	Aggregate Abrasion Value	12
Bulk Sample	Polished Stone Value	38
Bulk Sample	Slake Durability	99.40%
Bulk Sample	Los Angeles Coefficient	28
Bulk Sample	Soundness by Magnesium Sulphate	1
Bulk Sample	10% Fines	150kN
Bulk Sample	Frost Heave	3.3mm

Table 10: Summary of Rock Test Results in Bulk Sample

### 3.8 In Situ Water Testing

Water samples were obtained from boreholes BH04, BH05 and BH06 and tested for pH, Temperature, Conductivity and Dissolved O<sub>2</sub>. Three water samples were obtained and the pH, Temperature, Conductivity and dissolved O<sub>2</sub> data was acquired using a Watterra Pump with each borehole purged for at least 30 minutes. This work was carried out by Ronan Doyle of Ronan Doyle Monitoring Solutions, Ballinrobe County Mayo.



Borehole	pH	Temperature (°C)	Conductivity (µS)	Dissolved O <sub>2</sub> (mg/l)
BH04	7.47	10.5	295	0.21
BH05	7.77	10.5	420	0.8
BH06	12.53	9.8	6187	0.8

**Table 11:** In Situ Water Testing Results

### 3.9 Permeability Testing

Falling Head and Packer Testing was carried out on boreholes BH04 and BH05. The ground conditions intersected in boreholes BH03 and BH06 was considered too unstable for permeability testing.

A falling head test was carried out in BH04 on the 5th of January 2016. The rods were removed from the hole and the water level in the borehole was recorded at 17.88m bgl before the test commenced. Initially a volume of 130 litres was pumped into the hole, upon cessation of pumping the water level recovered almost immediately (i.e. faster than the dip meter could be lowered into the hole). A second test was subsequently carried out and 500 litres were pumped into the hole and same rapid recovery to 17.88m bgl was observed.

Falling head tests were carried out in BH05 on the 7th of January 2016. The rods were removed from the hole and the water level in this borehole was recorded at 19.45m bgl before commencement of the test. Initially a volume of 215 litres was pumped into the hole and the hole recovered back to 19.42m bgl and had stabilised after 40 minutes. A second test using a greater volume of water was carried out and 1000 litres of water was pumped into the hole. This test had proceeded almost to conclusion when the water level rose slightly (c.1.0cm) and a obstruction could be felt in the hole. The driller ran the rods back into the hole to assist with the piezometer installation and found that there was clay in the hole from 19.3 to 20.8m. The Falling Head test data is presented in Appendix XI.

Packer testing was carried out in boreholes BH04 and BH05 on the 18th of December 2015 and the 6th of January 2016 respectively. Set up details are presented in Table 12 and the results in Appendix X.

Borehole	Top (m)	Bottom (m)	Midpoint (m)
BH04	18	20	19
BH04	21	23	22
BH04	24	26	25
BH04	28	30	29
BH05	36	38	37
BH05	30	32	31
BH05	24	27	25.5
BH05	20	23	21.5

**Table 12:** Packer Test Installation Details

The Packer Tests carried out at 28-30m and 21-23m in BH04 suffered from loss of water pressure due to cavities / fractures. For both of these tests only one stage could be measured. All of the scheduled packer tests were carried out in BH05.

It was noted that the water pressure recovery once pumping had ceased was instantaneous in all of the test intervals.

### **3.10 Water level Measurements**

Throughout the ground investigation water level measurements were taken from all of the vertical drillholes, both during and after drilling. It should be noted that owing to ground instability and the need to keep holes open for the ground geophysical surveying, the bulk of the readings from boreholes BH03 and BH04 were taken when the holes were cased with PW steel casing, which extended from surface to the base of the hole.

## APPENDIX I

Hole	East	North	Elevation
BH1	530370.592	728426.557	16.712
BH3	530023.824	728382.566	26.256
BH4	530150.783	728400.125	32.167
BH5	530186.649	728378.105	34.138
BH6	530125.143	728383.081	30.799

Survey name	Station	East	North	Elevation	Dip	Azimuth	Tool-	Gravity	Mag.Str.	Mag.Dip	Mag.X	Mag.Y	Mag.Z	Roll Angle	Mag.T/face	DLS
*	Metres	Metres	Metres	Metres	Degrees	Degrees	Centigrade	G	nT	Degrees	nT	nT	nT	Degrees	Degrees	deg./30m
BH-1	1	0	0	0	-11.5	268.3	11	1.000147	48955	67.9	18396	0	45367	90	292.4	0
BH-1	4	-2.94	-0.09	-0.6	-11.5	268.1	11	1.00047	48954	67.9	18424	0	45355	90	292.4	1.9
BH-1	7	-5.88	-0.18	-1.2	-11.5	268.4	11	1.000677	48946	67.9	18415	0	45350	89.7	292.1	2.3
BH-1	10	-8.81	-0.28	-1.8	-11.7	267.9	11	1.00063	49023	67.9	18436	0	45424	89	291.5	5.4
BH-1	13	-11.75	-0.39	-2.41	-11.7	267.9	11	1.001172	49022	67.9	18468	0	45410	88.4	290.9	0.4
BH-1	16	-14.68	-0.5	-3.02	-11.8	267.6	11	1.000628	49027	67.9	18422	0	45434	88.4	290.8	3
BH-1	19	-17.62	-0.62	-3.63	-11.9	267.5	11	1.00041	49014	67.9	18451	0	45408	88.2	290.7	0.9
BH-1	22	-20.54	-0.81	-4.27	-12.6	265.4	11	1.002129	49028	68.5	17966	0	45618	89.2	291	22.5
BH-1	25	-23.47	-0.99	-4.91	-12.1	267.2	11	1.000351	49037	67.9	18457	0	45431	88.7	291.1	19
BH-1	28	-26.4	-1.13	-5.54	-12.2	267.3	11	1.000495	49044	67.9	18458	0	45438	88.4	290.8	1.2
BH-1	31	-29.33	-1.28	-6.18	-12.4	267.1	11	1.000687	49069	67.9	18452	0	45467	88.5	290.9	3.2
BH-1	34	-32.25	-1.43	-6.83	-12.6	266.9	11	1.000132	49044	67.9	18419	0	45454	88.4	290.8	2.8
BH-1	37	-35.18	-1.58	-7.48	-12.6	267.1	11	1.000742	49065	67.9	18458	0	45460	88.3	290.7	2.2
BH-1	40	-38.1	-1.73	-8.13	-12.6	267.1	11	1.000358	49075	67.9	18479	0	45463	88.3	290.8	0.4
BH-1	43	-41.02	-1.88	-8.79	-12.6	267.1	11	1.000171	49057	67.9	18429	0	45464	88.5	290.9	0.6
BH-1	46	-43.95	-2.02	-9.44	-12.5	267.3	11	1.000035	49054	67.9	18466	0	45446	88.8	291.3	2
BH-1	49	-46.87	-2.17	-10.09	-12.7	267	11	1.000317	49034	67.9	18438	0	45435	89.4	291.8	2.7
BH-1	52	-49.8	-2.32	-10.75	-12.7	267.1	11	1.000291	49062	68	18415	0	45475	89.7	292.1	0.4
BH-1	55	-52.72	-2.47	-11.41	-12.7	266.9	11	1.000127	49043	67.9	18450	0	45440	90.4	292.9	2
BH-1	58	-55.64	-2.61	-12.06	-12.5	267.8	11	0.99969	49044	67.6	18658	0	45356	90.8	293.6	9.5
BH-1	61	-58.57	-2.74	-12.72	-12.8	267.1	11	1.000477	49098	67.9	18474	0	45490	92.3	294.8	8
BH-1	64	-61.49	-2.89	-13.38	-12.8	267	11	1.00001	49037	67.9	18460	0	45430	93.1	295.6	0.4
BH-1	67	-64.41	-3.04	-14.05	-12.9	266.9	11	1.000212	49044	67.9	18458	0	45438	93.5	296	1.5
BH-1	70	-67.33	-3.2	-14.72	-12.9	267	11	1.0002	49029	67.9	18458	0	45422	94.5	297	1.4
BH-1	73	-70.25	-3.35	-15.39	-12.9	266.9	11	1.000355	49071	67.9	18437	0	45476	94.9	297.4	1.7
BH-1	76	-73.17	-3.51	-16.06	-12.9	267	11	1.000287	49068	67.8	18512	0	45442	95.4	297.9	1.8
BH-1	79	-76.11	-3.53	-16.68	-10.9	272	11	0.992033	49037	67.9	18432	0	45441	95.8	298.3	52.4

Survey name	Station	East	North	Elevation	Dip	Azimuth	Tool-	Gravity	Mag.Str.	Mag.Dip	Mag.X	Mag.Y	Mag.Z	Roll Angle	Mag.T/face	DLS
*	Metres	Metres	Metres	Metres	Degrees	Degrees	Centigrade	G	nT	Degrees	nT	nT	nT	Degrees	Degrees	deg./30m
BH-1	82	-79.04	-3.56	-17.3	-13	266.9	11	1.000459	49018	67.9	18469	0	45406	96.3	298.8	53.7
BH-1	85	-81.96	-3.72	-17.98	-13.2	266.6	11	1.000487	49052	67.9	18490	0	45434	96.5	299.1	3.2
BH-1	88	-84.87	-3.89	-18.66	-13.1	266.8	11	1.000296	49038	67.9	18437	0	45440	96.8	299.2	1.2
BH-1	91	-87.79	-4.06	-19.34	-13.1	266.8	11	1.000282	49031	67.9	18455	0	45426	96.8	299.3	0.7
BH-1	94	-90.71	-4.22	-20.03	-13.1	266.7	11	1.000122	49080	67.9	18447	0	45482	97.2	299.7	1
BH-1	97	-93.62	-4.39	-20.71	-13.2	266.7	11	1.000303	49066	67.9	18470	0	45457	97.6	300.1	0.6
BH-1	100	-96.54	-4.55	-21.4	-13.2	266.7	11	1.000268	49068	67.8	18503	0	45445	97.5	300.1	0.5
BH-1	103	-99.47	-4.63	-22.05	-11.8	270.2	11	0.995246	49056	68.6	17887	0	45678	98.2	300	37
BH-1	106	-102.39	-4.71	-22.7	-13.3	266.7	11	1.00031	49060	67.9	18480	0	45446	97.7	300.2	37.4
BH-1	109	-105.31	-4.88	-23.39	-13.3	266.6	11	1.000017	49021	67.9	18429	0	45425	97.8	300.3	0.7
BH-1	112	-108.22	-5.05	-24.08	-13.4	266.5	11	1.000223	49056	67.9	18482	0	45442	98	300.5	1.5
BH-1	115	-111.13	-5.22	-24.78	-13.4	266.7	11	1.000889	49063	67.9	18460	0	45457	98	300.5	1.4
BH-1	118	-114.05	-5.4	-25.48	-13.5	266.5	11	1.000317	49027	67.9	18468	0	45416	98.3	300.8	2.1
BH-1	121	-116.96	-5.58	-26.18	-13.4	266.6	11	1.000141	49042	67.9	18448	0	45440	98.3	300.8	1.2
BH-1	124	-119.87	-5.75	-26.88	-13.5	266.5	11	1.000272	49046	67.9	18477	0	45433	98.3	300.9	0.9
BH-1	127	-122.78	-5.93	-27.58	-13.5	266.5	11	0.99995	49034	67.9	18473	0	45422	98.3	300.8	0.6
BH-1	130	-125.69	-6.11	-28.28	-13.6	266.4	11	1.000699	49079	67.9	18430	0	45487	98.2	300.7	0.8
BH-1	133	-128.6	-6.29	-28.99	-13.6	266.6	11	1.00039	49055	67.9	18443	0	45456	98.2	300.8	1.6
BH-1	136	-131.51	-6.47	-29.7	-13.7	266.3	11	0.999701	49064	67.9	18444	0	45466	98	300.5	2.8
BH-1	139	-134.42	-6.65	-30.41	-13.7	266.4	11	1.000129	49052	67.9	18462	0	45445	98.2	300.7	0.9
BH-1	142	-137.33	-6.83	-31.12	-13.8	266.4	11	1.000614	49054	67.9	18477	0	45441	98.7	301.3	0.9
BH-1	145	-140.24	-7.02	-31.83	-13.8	266.3	11	1.000523	49075	67.9	18474	0	45465	98.7	301.2	0.7
BH-1	148	-143.14	-7.21	-32.55	-13.8	266.3	11	1.000394	49034	67.9	18471	0	45422	98.9	301.5	0.6

Survey name	Station	East	North	Elevation	Dip	Azimuth	Tool-	Gravity	Mag.Str.	Mag.Dip	Mag.X	Mag.Y	Mag.Z	Roll Angle	Mag.T/face	DLS
*	Metres	Metres	Metres	Metres	Degrees	Degrees	Centigrade	G	nT	Degrees	nT	nT	nT	Degrees	Degrees	deg./30m
BH-1	151	-146.05	-7.39	-33.26	-13.8	266.4	11	1.000164	49043	67.9	18474	0	45430	98.9	301.5	1.5
BH-1	154	-148.96	-7.57	-33.98	-13.9	266.4	11	1.000365	49066	67.9	18451	0	45464	99.1	301.6	1
BH-1	157	-151.87	-7.76	-34.7	-13.9	266.3	11	1.000252	49055	67.8	18506	0	45430	99.2	301.8	1
BH-1	160	-154.77	-7.95	-35.43	-14	266.2	11	0.999691	49068	67.9	18477	0	45456	99.2	301.7	0.6
BH-1	163	-157.68	-8.14	-36.15	-14	266.3	11	1.001008	49040	67.9	18411	0	45453	99.3	301.8	0.5
BH-1	166	-160.58	-8.33	-36.88	-14	266.2	11	0.999912	49061	67.9	18462	0	45455	100.3	302.8	0.6
BH-1	169	-163.48	-8.52	-37.6	-14	266.3	11	1.00026	49044	67.9	18480	0	45430	100.3	302.9	1.2
BH-1	172	-166.39	-8.71	-38.33	-14.1	266.4	11	1.000443	49080	67.9	18462	0	45476	100.3	302.8	0.4
BH-1	175	-169.29	-8.89	-39.06	-14.1	266.2	11	0.999983	49089	67.9	18458	0	45487	100.3	302.8	1.5

## APPENDIX II





# Rotary Core Log

Borehole No.

**BH01**

Sheet 1 of 28

Project Name: Lackagh Quarry Preliminary  
Ground InvestigationProject No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		0.00 - 5.60								Concrete Plinth	1
											2
											3
											4
		5.60 - 6.30	14	100	60	41	5.60	11.11		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. (Core invert not marked)	6
		6.30 - 7.52	3	100	100	100	6.30	10.41		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Sub-vertical stylolites, occasional coarse shelled bioclast (Brachiopod)	7
		7.52 - 10.15	6	100	89	81	7.52	9.19		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Occasional fine grained scattered bioclasts, minor stylolites	8
											9
											10

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 2 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		10.15 - 11.10	2	88	88	88	10.15	6.56		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Very occasional fine grained bioclast	11
		11.10 - 12.66	5	100	44	38	11.10	5.61		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. pellety / slightly oolitic texture	12
		12.66 - 14.20	2	100	100	96	12.66	4.05		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. pellety / slightly oolitic intervals with small rounded bioclasts	13
		14.20 - 14.58	18	100	29	29	14.20	2.51		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Intersecting conjugate joints	14
		14.58 - 15.46	2	100	100	100	14.58	2.13		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Minor white calcite fill along joint	15
		15.46 - 15.86	15	100	25	0	15.46	1.25		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. White calcite fill and weak oxidation along steeply dipping joint surface	16
		15.86 - 17.04	2	100	100	100	15.86	0.85		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. pellety / slightly oolitic texture, minor thick shelled brachiopods	17
		17.04 - 21.07	3	97	87	86	17.04	-0.33		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Slightly pellety scattered fine bioclastic debris with occasional coarse shelled brachiopod fragment	18
											19
											20

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 3 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							21.07	-4.36		Strong. fresh, grey / pale grey, fine to medium grained, massive LIMESTONE. minor bioclastic debris and white calcite veinlets, basal 10cm is rubble	21
		21.07 - 21.60	23	100	53	40	21.60	-4.89			22
		21.60 - 22.75	3	100	100	100	22.75	-6.04			23
		22.75 - 24.34	4	100	78	65	24.34	-7.63			24
		24.34 - 24.73	15	92	0	0	24.73	-8.02			25
		24.73 - 31.68	2	100	100	100					26
										Continued on next sheet	30

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 4 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							31.68	-14.97		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. fine sub-vertical stylolites. 31.78m calcite filled vugs locally developed	31
		31.68 - 33.22	7	100	77	55					32
							33.22	-16.51		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Small scattered bioclasts, very rare coarse shell and coral fragment. Minor fine stylolites	33
		33.22 - 37.10	2	100	97	95					34
							37.10	-20.39		Strong. fresh, brownish pale grey, fine to medium grained, massive LIMESTONE. Fine grained scattered bioclastic debris, minor very fine stylolites	35
		37.10 - 38.70	6	100	59	51					36
							38.70	-21.99		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Very minor scattered bioclastic debris, minor orange limonitic staining along a joint surface at 39.35m	37
		38.70 - 40.45	2	100	100	100					38
											39
											40

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 5 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							40.45	-23.74		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Minor bioclastic debris, and fine stylolites	41
		40.45 - 43.30	3	100	90	88					42
							43.30	-26.59		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Fine vuggy texture and faint stylolites	43
		43.30 - 44.30	6	90	9	0					44
							44.30	-27.59		Strong. fresh, light grey, fine to medium grained, massive LIMESTONE. Scattered bioclastic debris, fragments of coarse shelled brachiopods or solitary corals. locally developed fine vuggy texture (49.1 - 49.55m). White calcite veinlets dip 90°, azimuth 020° to core invert	45
											46
											47
		44.30 - 52.98	6	100	96	91					48
											49
											50

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 6 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
											51
											52
		52.98 - 53.74	9	97	37	13	52.98	-36.27		Strong. fresh, light grey, fine to medium grained, massive LIMESTONE. Minor fine stylolites	53
		53.74 - 56.10	3	94	94	90	53.74	-37.03		Strong. fresh, light grey, fine to medium grained, massive LIMESTONE. Very rare small bioclastic fragments, fine stylolites	54
		56.10 - 58.60	3	100	96	92	56.10	-39.39		Strong. fresh, grey, medium grained, massive LIMESTONE. Pellety texture with scattered small bioclastic fragments and faint stylolites.	56
							58.60	-41.89		Strong. fresh, light grey, fine to medium grained, massive LIMESTONE. Minor bioclastic debris, and fine stylolites	59
Continued on next sheet											60

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 7 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		58.60 - 61.47	3	100	99	99					61
		61.47 - 62.25	10	100	55	47	61.47	-44.76		Strong. fresh, light grey, fine to medium grained, massive LIMESTONE. Fine vuggy texture, 61.94m a 1cm thick white calcite vein dipping at 80° azimuth 185° to core invert	62
		62.25 - 63.73	1	100	100	100	62.25	-45.54		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Occasional fine stylolite	63
		63.73 - 64.22	10	94	69	61	63.73	-47.02		Strong. fresh, grey/light grey, fine to medium grained, massive LIMESTONE. Minor bioclastic debris, and fine stylolites. Some coarse vugs (6mm wide) irregular shaped with orange/brown limonitic infill	64
		64.22 - 67.85	3	100	100	100	64.22	-47.51		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Incipient pelley texture, scatted bioclastic debris, and faint stylolites	65
											66
											67
		67.85 - 68.78	9	92	77	60	67.88	-51.17		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Minor bioclastic debris, and fine stylolites	68
											69
											70

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 8 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway





Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description		
				TCR	SCR	RQD						
		68.78 - 72.31	3	98	96	96	72.31	-55.60			71	
		72.31 - 73.39	6	100	30	19					73	
		73.39 - 75.70	3	100	94	94	75.70	-56.68			74	
		75.70 - 76.37	12	96	67	16					76	
		76.37 - 77.60	2	100	100	95	77.60	-58.99			77	
		77.60 - 78.20	20	100	12	0					78	
							78.20	-59.66			79	
											80	

Remarks







# Rotary Core Log

Borehole No.

**BH01**

Sheet 9 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway




Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description								
				TCR	SCR	RQD												
		78.20 - 86.15	3	99	99	98	86.15	-69.44			81							
											82							
											83							
											84							
											85							
											86							
		86.15 - 88.77	2	100	96	96	88.77	-72.06		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Occasional stylolites and fine grained bioclastic debris. 87.06m - 1cm thick white calcite vein	87							
											88							
											88.77 - 90.30	7	100	49	23		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. 90.09m - 2cm thick white calcite vein. Locally developed fine vuggy texture	89
																		90
Continued on next sheet																		

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 10 of 28

Project Name: Lackagh Quarry Preliminary  
Ground InvestigationProject No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							90.30	-73.59		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Minor faint stylolites	91
		90.30 - 95.95	2	100	99	98					92
											93
							95.95	-79.24		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. small scattered bioclasts with some large (7cm dia.) coarse shelled brachiopods	94
		95.95 - 100.33	3	99	94	89					95
											96
											97
											98
											99
											100

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 11 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							100.33	-83.62		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Scattered small partially oxidised vugs. 101.4 & 101.43m 1cm thick white calcite veins dip 90° Azimuth 360°	101
		100.33 - 102.74	6	97	85	71					102
							102.74	-86.03		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Fine bioclastic debris scattered throughout	103
		102.74 - 105.90	3	100	99	99					104
							105.90	-89.19			105
							105.90	-89.19		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Thin (c.1mm), randomly orientated white / brown calcite veinlets over top 40cm. scattered fine bioclastic debris and fine stylolites	106
		105.90 - 108.60	2	100	100	99					107
							108.60	-91.89		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Occasional scattered fine bioclastic debris and fine stylolites. Minor white calcite veining dipping at 85° to 180°	108
											109
											110
										Continued on next sheet	

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 12 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		108.60 - 111.55	5	100	98	86	111.55	-94.84		Strong. fresh, grey, fine grained, massive LIMESTONE. Fine black stylolites	111
		111.55 - 113.73	1	100	100	100					112
		113.73 - 114.33	3	100	0	0	113.73	-97.02		Strong. fresh, grey, fine grained, massive LIMESTONE. Fine grained bioclastic debris. Axial parallel jointing	113
		114.33 - 119.52	1	100	100	98	114.33	-97.62		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Disseminated very fine grained bioclastic debris	114
							119.52	-102.81		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Faint pelley texture, etched stylolites and scattered small vugs, often	115
										Continued on next sheet	116
											117
											118
											119
											120

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 13 of 28

Project Name: Lackagh Quarry Preliminary  
Ground InvestigationProject No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		119.52 - 127.29	4	100	95	87	127.29	-110.58		weakly oxidised. Disseminated fine grained bioclastic debris	121
											122
											123
							127.29	-110.58			124
											125
											126
		127.29 - 128.75	6	99	97	82	128.75	-112.04		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Incipient mottled texture and scattered fine bioclastic debris.	127
											128
											129
							128.75	-112.04		Strong. fresh, dark grey, fine to medium grained, massive LIMESTONE. Wispy black argillaceous partings. Scattered fine bioclastic debris with some coarse shelled brachiopods / gastropods. thick black stylolites with argillic infill. Occasional white calcite veinlet	130

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 14 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		128.75 - 134.90	1	100	97	97					131
											132
											133
											134
		134.90 - 136.05	4	84	84	84	134.90	-118.19		Strong. fresh, dark grey, fine to medium grained, massive LIMESTONE. Wispy black argillaceous partings. Scattered fine bioclastic debris with some coarse shelled brachiopods.	135
		136.05 - 137.52	3	100	100	95	136.05	-119.34		Strong. fresh, dark grey, fine to medium grained, massive LIMESTONE. Weak intraclastic breccia texture minor stylolites and black argillic partings	136
		137.52 - 141.84	2	100	100	100	137.52	-120.81		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Small scattered bioclasts, incipient intraclastic breccia texture locally developed minor discontinuous white calcite veinlets	137
											138
											139
											140

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 15 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway






Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							141.84	-125.13			141
		141.84 - 142.93	3	100	100	100				Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Small scattered bioclasts, incipient bioturbated / burrowed texture	142
		142.93 - 143.70	0	100	100	100	142.93	-126.22		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE.. Pellety / almost oolitic texture	143
							143.70	-126.99		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Intraclastic breccia texture sub-rounded clasts 0.5 - 2.0cm dia. possibly related to bioturbation / burrowing. Minor stylolites and a very rare bioclast	144
		143.70 - 148.30	1	100	100	100					145
							148.30	-131.59		Core is crosscut by a 2cm thick band of weak / very weak, fresh, fine grained Black MUDSTONE. Soft / Friable texture, locally altered to clay dip 32' to 060'	148
		148.30 - 148.90	10	100	0	0					149
							148.90	-132.19		Strong. fresh, dark grey / black, fine to medium grained, massive LIMESTONE. Intraclastic breccia texture poorly sorted, very irregular / angular clasts of fine grained limestone (micrite) in a black / dark grey locally argillaceous matrix. Intensity of brecciation decreasing with depth	150

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 16 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		148.90 - 154.60	2	100	99	97	154.60	-137.89		Strong, fresh, grey, fine to medium grained, massive LIMESTONE. Stylolites locally up to 3mm thick. Minor bioclastic debris. Locally developed incipient intraclastic breccia / bioturbation textures	151
		154.60 - 161.75	1	100	100	71					152
											153
											154
											155
											156
											157
											158
											159
											160

Continued on next sheet

Remarks







# Rotary Core Log

Borehole No.

**BH01**

Sheet 17 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway





Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description		
				TCR	SCR	RQD						
							161.75	-145.04			161	
		161.75 - 166.30	1	100	100	98					Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Locally developed pellety / oolitic texture. Scattered bioclastic debris	162
												163
												164
							165					
							166					
							166.30	-149.59				Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Numerous coarse bioclasts and white calcite infilling small voids
		168										
		168.90	-152.19		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Slight pellety texture. Scattered fine to medium grained bioclasts	169						
						170						
Continued on next sheet												

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 18 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		168.90 - 172.00	1	100	100	100	172.00	-155.29		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE.	171
		172.00 - 175.65	2	100	100	99					172
		175.65 - 177.00	1	100	100	100	175.65	-158.94		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Scattered coarse shelled brachiopods	176
		177.00 - 182.50	1	100	100	100	177.00	-160.29		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Minor stylolites, some up to 2mm thick. Scattered fine bioclastic debris	177
										Continued on next sheet	180

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 19 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							182.50	-165.79			181
											182
		182.50 - 186.80	1	100	100	99				Strong, fresh, pale grey, fine to medium grained, massive LIMESTONE. Locally developed incipient intraclastic breccia texture. Fine stylolites and minor bioclasts	183
											184
											185
											186
							186.80	-170.09			187
		186.80 - 189.00	0	0	0	0				Cavity - No recovery. Pitting / dissolution textures and slight brown oxidation on contacts	188
							189.00	-172.29			189
		189.00 - 190.30		100	0	0				Soft to firm, light brown, fine grained sandy CLAY. Some tabular / angular clasts of light brown oxidised mudstone within the clay	
											190

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 20 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
			0				190.30	-173.59			
		190.30 - 191.20	0	100	100	100	191.20	-174.49		Strong. fresh, grey, fine to medium grained, massive LIMESTONE.	191
		191.20 - 192.85	8	100	64	41	192.85	-176.14		Strong. fresh, grey / dark grey, fine to medium grained, massive LIMESTONE.	192
		192.85 - 195.70	1	100	100	100	195.70	-178.99		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Light brown sandy clay coating joint surfaces	193
		195.70 - 198.70	1	100	100	100	198.70	-181.99		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Scattered coarse shelled brachiopods	194
											195
											196
											197
											198
											199
											200

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 21 of 28

Project Name: Lackagh Quarry Preliminary  
Ground InvestigationProject No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		198.70 - 203.00	2	91	91	91					201
											202
		203.00 - 203.90	9	94	94	56	203.00	-186.29		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Minor coarse shelled brachiopods. Joints coated with light brown fine sandy clay	203
							203.90	-187.19		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Scattered coarse shelled brachiopods	204
		203.90 - 207.50	1	100	98	98					205
											206
											207
							207.50	-190.79		Strong. fresh, grey, fine to medium grained, massive LIMESTONE.	208
											209
											210

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 22 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		207.50 - 214.50	1	100	100	99					211
											212
											213
											214
							214.50	-197.79			215
		214.50 - 216.90	2	100	90	90				Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. disseminated bioclastic debris	216
							216.90	-200.19		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Slightly vuggy with minor oxidation focused upon vugs	217
		216.90 - 217.60	3	100	100	100					
							217.60	-200.89		Strong. fresh, light grey / grey, fine to medium grained, massive LIMESTONE.	218
		217.60 - 221.55	4	97	87	78					219
											220

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 23 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							221.55	-204.84			221
		221.55 - 223.55	5	100	98	96				Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Minor oxidation and light brown clay localised along joints and along some stylolites	222
							223.55	-206.84		Strong. fresh, pale grey/ grey, medium grained, massive LIMESTONE. Distinct pelley texture, fine grained bioclastic debris. 226.4 - 226.5 evidence of oxidation, dissolution (pitting) along a shallowly dipping joint plane	224
		223.55 - 226.55	3	97	84	81					225
							226.55	-209.84		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. slight dissolution and oxidation focused on some joint surfaces	227
		226.55 - 229.10	3	100	97	95					228
		229.10 - 229.20	0	0	0	0	229.10	-212.39		Cavity infilled with light brown soft / firm sticky clay	229
							229.20	-212.49		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Slight discolouration and oxidation along some joint surfaces	230

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 24 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		229.20 - 231.10	4	95	91	86	231.10	-214.39		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE.	231
		231.10 - 233.20	1	100	98	95	233.20	-216.49		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Joints and fractures infilled with light brown fine / medium grained sand. 232.78 2cm white calcite vein	232
		233.20 - 234.15	11	91	79	45	234.15	-217.44		Strong. fresh, grey, fine to medium grained, massive LIMESTONE. Locally developed fine vuggy texture. 236.6m joint with intense bright orange Fe Staining.	233
		234.15 - 237.55	6	99	80	70	237.55	-220.84		CAVITY - coarse grained yellow sand and angular gravel with some light brown silt. Recover 30 - 35%	234
		237.55 - 239.20	0	0	0	0	239.20	-222.49		Strong. fresh, light grey / grey, fine to medium grained, massive LIMESTONE. Locally developed coarse vuggy texture - vugs up to 5mm dia.	235
											236
											237
											238
											239
											240

Continued on next sheet

Remarks







# Rotary Core Log

Borehole No.

**BH01**

Sheet 25 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		239.20 - 241.40	6	50	19	13	241.40	-224.69		Strong. fresh, pale grey, fine to medium grained, massive LIMESTONE. Scattered poorly sorted bioclastic debris. Fine grained orange brown sand coating joint surfaces	241
		241.40 - 243.90	4	100	97	95	243.90	-227.19			242
		243.90 - 245.58	7	85	36	29	245.58	-228.87			243
		245.58 - 247.25	0	0	0	0	247.25	-230.54		Strong. slightly weathered, pale grey, fine to medium grained, massive LIMESTONE. 243.9-244.35m axial parallel discontinuity with black argillaceous lamina. Orange brown clayey sand coating joint surfaces	244
		247.25 - 248.37	4	100	61	38	248.37	-231.66		CAVITY - 5% recovery of yellow brown fine to medium grained sand	245
		248.37 - 250.20	3	100	97	93				Strong. fresh, pale grey / grey, mottled, fine to medium grained, massive LIMESTONE. Fine vuggy texture with minor oxidation / Fe staining localised within the vugs. Some axial parallel jointing	246
										Strong. fresh, dark grey, medium grained, massive LIMESTONE. Poorly sorted bioclastic debris	247
											248
											249
											250

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 26 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway








Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		250.20 - 253.00	2	100	98	98	250.20	-233.49		Strong. fresh, dark grey, medium grained, massive LIMESTONE. Poorly sorted bioclastic debris. Discontinuous randomly orientated white calcite veinlets	251
		253.00 - 255.50	2	100	92	92	253.00	-236.29		Strong. fresh, grey, medium grained, massive LIMESTONE. Scattered poorly sorted bioclastic debris. Incipient intraclastic breccia texture	253
		255.50 - 255.90	7	100	0	0	255.50	-238.79		Strong. grey LIMESTONE cross cut by cavity / dissolution zone bright orange staining and dissolution textures on cavity contact	255
		255.90 - 256.90	4	100	60	60	255.90	-239.19		Strong. fresh, grey, medium grained, massive LIMESTONE. Scattered bioclastic debris	256
		256.90 - 257.35	22	78	0	0	256.90	-240.19		Moderately strong, black, fine to medium grained LIMESTONE - black argillite rich zones - Rubble poorly sorted fragments with some polished surfaces.	257
		257.35 - 259.40	3	100	68	68	257.35	-240.64		Moderately strong. black / dark grey, fine to medium grained, massive LIMESTONE. Intraclastic breccia, irregular poorly sorted limestone clasts in a black argillite rich matrix	258
		259.40 - 259.50	0	100	0	0	259.40	-242.69		Strong. fresh, dark grey, medium grained, massive LIMESTONE.	259
											260

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 27 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway

Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		259.50 - 263.10	3	100	90	87					261
											262
											263
		263.10 - 263.70	3	58	0	0	263.10	-246.39		Weak, black / grey MUDSTONE, running sub-parallel to core axis band is 2 - 3cm thick and partially altered to clay. The contact with the limestone shows evidence of oxidation / Fe staining	263
							263.70	-246.99		Strong, fresh, grey / pale grey, medium grained, massive LIMESTONE. Mottled and evidence of bioturbation / burrowing. 265.4 - 265.46 fracture zone with rubble and coarse brown sand	264
		263.70 - 266.40	2	100	100	100					265
											266
							266.40	-249.69		Strong, fresh, grey / pale grey, medium grained, massive LIMESTONE. Mottled and evidence of bioturbation / burrowing. Core is coated with coarse brown sand	267
		266.40 - 267.10	17	100	40	40	267.10	-250.39		Strong, fresh, grey / pale grey, medium grained, massive LIMESTONE. Mottled and evidence of bioturbation / burrowing.	267
		267.10 - 267.70	2	100	100	100					268
							267.70	-250.99		Strong, fresh, grey / dark grey, medium grained, massive LIMESTONE. Occasional stylolitic and axial parallel joint	269
		267.70 - 270.30	6	100	55	52					270

Continued on next sheet

Remarks





# Rotary Core Log

Borehole No.

**BH01**

Sheet 28 of 28

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530370.59 - 728426.56

Hole Type  
RC

Location: Galway



Level: 16.71

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 21/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		270.30 - 272.40	1	100	100	100	270.30	-253.59		Strong, fresh, grey / dark grey, medium grained, massive LIMESTONE.	271
		272.40 - 273.40	0	0	0	0	272.40	-255.69		CAVITY no recovery	272
		273.40 - 274.16	5	79	39	20	273.40	-256.69		Strong, fresh, very pale grey, medium grained, massive LIMESTONE. Probably a boulder within cavity / unconsolidated sediments	273
		274.16 - 276.70	0	8	0	0	274.16	-257.45		CAVITY - unconsolidated ground only 10% medium to coarse limestone cobbles and some gravel recovered	274
							276.70	-259.99		End of borehole at 276.70 m	275
											276
											277
											278
											279
											280

Remarks





# Rotary Core Log

Borehole No.

**BH03**

Sheet 1 of 11

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530023.82 - 728382.57

Hole Type  
RC

Location: Galway

Level: 26.26

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 09/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		4.15 - 4.42	C							No Recovery	
							1.20	25.06			1
							1.45	24.81		Very soft, light brown, sandy CLAY with minor angular gravel	
										Rubble of sub-angular to sub-rounded grey Limestone fragments and minor creamy coloured calcite. Lumps of soft light grey/brown clay. (Recovery 0.35m)	2
							2.70	23.56			
							3.00	23.26		Stiff, grey brown, sandy CLAY, occasional sub angular gravel and cobbles of dark grey limestone	3
							3.20	23.06		Coarse cobbles of dark grey limestone with firm / stiff grey brown sandy clay	
							3.55	22.71		Coarse COBBLES with gravel. Sub-angular to sub-rounded grey / dark grey limestone with minor pink (tonalitic) granite	
							4.00	22.26		Core loss	4
										Stiff / very stiff, light grey/brown sandy CLAY with minor (10 - 15%) scattered angular limestone gravel	
							4.85	21.41			5
										Stiff / very stiff, light grey/brown sandy CLAY with angular limestone gravel & cobbles	
							6.00	20.26		Core loss	6
							6.55	19.71			
							6.85	19.41		Stiff / very stiff, light grey/brown sandy CLAY with angular limestone gravel, cobbles and occasional boulders	7
										Stiff / very stiff, grey / brown sandy CLAY with (12 - 20%) angular limestone gravel and occasional sub-rounded cobbles	
							7.65	18.61		Core loss	
							8.05	18.21			8
							8.25	18.01		Loose angular GRAVEL with cobbles. Coated with stiff sandy clay	
										Stiff / very stiff, light grey / brown, sandy CLAY, 20% sub-angular / sub-rounded gravel and occasional sub-rounded cobble and small boulder	9
											10

Continued on next sheet

Remarks

All angles measured relative to core normal





# Rotary Core Log

Borehole No.

**BH03**

Sheet 2 of 11

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530023.82 - 728382.57

Hole Type  
RC

Location: Galway

Level: 26.26

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 09/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		13.65 - 13.73 13.73 - 13.85	D D				11.55	14.71		Stiff / very stiff, light grey / brown, sandy CLAY, 205 sub-angular / sub-rounded gravel and occasional sub-angular cobbles and small boulder	11
							12.94 12.98	13.32 13.28		Soft, dark chocolate brown CLAY Core Loss	12
							13.65	12.61		Soft / very soft, greenish grey, fine sandy SILT (recovery 0.5m)	13
							14.75	11.51		Core Loss	14
							16.15 16.45	10.11 9.81		Soft / firm, grey / green SILT	15
							16.85	9.41		Soft / very soft, grey brown SILT with very thin clay laminae (Mobilised and coating surface by drilling additive) Core loss	16
							18.60	7.66		Soft / very soft, grey SILT	17
							19.25	7.01		Soft / firm, grey SILT, locally developed faint brown laminae (smearing of clay surface)	18
											19
											20
		19.00 - 19.10 19.10 - 19.20 19.25 - 19.30	D D D								
		19.90 - 20.00	D								

Continued on next sheet

Remarks

All angles measured relative to core normal







# Rotary Core Log

Borehole No.

**BH03**

Sheet 3 of 11

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530023.82 - 728382.57

Hole Type  
RC

Location: Galway

Level: 26.26

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 09/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		20.95 - 21.05	D				21.70	4.56	XXXXXX XXXXXX XXXXXX XXXXXX XXXXXX		21
		21.30 - 21.40	D								
							23.00	3.26	XXXXXX XXXXXX XXXXXX XXXXXX XXXXXX	Very soft / soft, grey SILT (Recovery 50%)	22
							25.20	1.06	XXXXXX XXXXXX XXXXXX XXXXXX XXXXXX	Soft / firm, grey SILT (Recovery 60%)	23
		25.50 - 25.60	D				27.50	-1.24	XXXXXX XXXXXX XXXXXX XXXXXX XXXXXX	Soft / very soft, grey SILT (Recovery 90%)	25
		25.80 - 25.90	D								26
		26.50 - 26.60	D								
		26.70 - 26.80	D								27
							28.45	-2.19	XXXXXX XXXXXX XXXXXX XXXXXX XXXXXX	Firm grey SILT with centimetric scale horizontal banding	28
		27.20 - 27.25	D								
		27.45 - 27.55	D								
		27.55 - 27.65	D								
											29
							30.00	-3.74	XXXXXX XXXXXX XXXXXX XXXXXX XXXXXX	Soft, grey SILT (recovery 60%)	30

Continued on next sheet

Remarks

All angles measured relative to core normal





# Rotary Core Log

Borehole No.

**BH03**

Sheet 4 of 11

Project Name: Lackagh Quarry Preliminary  
Ground InvestigationProject No.  
Lackagh Quarry

Co-ords: 530023.82 - 728382.57

Hole Type  
RC

Location: Galway

Level: 26.26

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 09/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		30.25 - 30.33	D						XXXXXX	Soft / firm grey SILT	
		31.20 - 31.30	D				31.73	-5.47	XXXXXX		31
		31.35 - 31.45	D						XXXXXX		
							32.40	-6.14	XXXXXX	Firm, grey / brown SILT	32
									XXXXXX	Soft, grey SILT	
		33.70 - 33.80	D						XXXXXX		33
		33.95 - 34.03	D						XXXXXX		
							34.60	-8.34	XXXXXX	Soft / Firm, light grey SILT. Minor fine grained sand	34
									XXXXXX		
		36.05 - 36.15	D				36.05	-9.79	XXXXXX	Loose / medium dense, light grey / brown, silty SAND (recovery 30%)	35
		36.70 - 36.80	D						XXXXXX		
									XXXXXX		36
									XXXXXX		
							38.38	-12.12	XXXXXX	Firm, dark chocolate brown organic CLAY, Small fibres bottom 0.5m of core coated with fine grained grey sand	37
		38.60 - 38.70	D						XXXXXX		
		38.95 - 39.05	D						XXXXXX		38
		39.25 - 39.30	D						XXXXXX		
		39.45 - 39.55	D						XXXXXX		
		39.80 - 39.83	D						XXXXXX		39
									XXXXXX		
									XXXXXX		40

Continued on next sheet

Remarks

All angles measured relative to core normal





# Rotary Core Log

Borehole No.

**BH03**

Sheet 5 of 11

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530023.82 - 728382.57

Hole Type  
RC

Location: Galway

Level: 26.26

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 09/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		40.65 - 40.77	D				40.65	-14.39		Loose / medium dense, grey, fine to medium grained SAND (recovery 60%)	41
		41.20 - 41.25 41.30 - 41.50	D C				41.00	-14.74			
		41.85 - 42.08	C				41.80	-15.54		Stiff / very stiff, dark brown, organic CLAY. Basal 4cm laminated - light / dark brown millimetric scale laminae	42
		42.30 - 42.35 42.35 - 42.40 42.65 - 42.97	D D C				42.40	-16.14			
		42.97 - 43.30	C				43.25	-16.99		Soft to firm light grey CLAY	43
		44.05 - 44.20	C				44.20	-17.94			
							44.85	-18.59		Firm, dark grey brown CLAY	45
							45.24 45.30	-18.98 -19.04			
		46.20 - 46.27 46.27 - 46.59	D C							Soft, grey SILT Very Stiff, Dark brown / grey, organic CLAY	46
		47.00 - 47.10 47.20 - 47.27 47.45 - 47.55	D D D								
		47.85 - 48.02	C								48
		48.20 - 48.30 48.45 - 48.70	D C								
		49.00 - 49.10 49.30 - 49.40	D D								49
							50.00	-23.74			

Continued on next sheet

Remarks

All angles measured relative to core normal





# Rotary Core Log

Borehole No.

**BH03**

Sheet 6 of 11

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530023.82 - 728382.57

Hole Type  
RC

Location: Galway

Level: 26.26

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 09/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							50.35	-24.09		Firm grey CLAY, with cobbles of strong pale grey limestone rounded to sub-angular	51
										Soft, light greyish brown, cobbly CLAY, cobbles of pale grey limestone, comprise 50% of material	
							51.30	-25.04		Boulder of pale grey massive limestone, stylolitic with stylolites rotated to sub-vertical orientation	52
							52.56	-26.30		Soft / firm, brownish grey gravelly CLAY, angular gravel (10 - 20%), sub-rounded coarse cobbles / small boulders (30 - 40%) of light grey massive limestone. (recovery 80%)	53
											54
							56.40	-30.14		Sub-rounded COBBLES with coarse gravel - coated by soft light grey clay	55
							57.15	-30.89		Soft / firm Pale grey CLAY with angular cobbles of grey limestone (recovery 40%)	56
							57.85	-31.59		Soft grey brown CLAY with angular gravel and cobbles (Recovery 40%)	57
											58
											59
											60

Continued on next sheet

Remarks

All angles measured relative to core normal





# Rotary Core Log

Borehole No.

**BH03**

Sheet 7 of 11

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530023.82 - 728382.57

Hole Type  
RC

Location: Galway

Level: 26.26

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 09/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							60.55	-34.29		BOULDER of strong, pale grey, fine to medium grained Limestone	61
							62.20	-35.94		Soft to firm grey brown cobbly CLAY - cobbles of angular limestone	62
							62.52	-36.26		Stiff brown, organic CLAY	
		63.15 - 63.22	D								63
		63.38 - 63.43	D								
		63.50 - 63.55	D								
		63.90 - 63.95	D								
		64.30 - 64.35	D				64.05 64.11	-37.79 -37.85		Loose / medium dense, brown / grey, medium grained SAND	64
		64.90 - 64.95	D							Firm / stiff, brown / dark brown, organic CLAY, Finely laminated (0.5 - 1.5mm laminae) light / dark brown. Occasional small white clay flecks / blebs. Millimetric to centimetric scale bands of fine to medium grained sand, locally developed grading - coarsening down	65
		65.50 - 65.60	D								
							65.78 65.85	-39.52 -39.59		Stiff pale grey CLAY	66
							66.48	-40.22		Firm / stiff, brownish grey, finely laminated CLAY with sub-rounded cobbles of grey limestone, locally friable and broken up in situ	
		66.95 - 67.05	D				66.85	-40.59		Firm grey, fine sandy CLAY, with 10% angular gravel	
										Firm, pale creamy grey, fine grained sandy CLAY (recovery 80%)	67
		68.40 - 68.45	D				67.65	-41.39		Firm, grey / creamy grey fine sandy CLAY laminated and banded texture with small clasts of creamy white, soft weather limestone	68
							69.15	-42.89		BOULDER of strong, fresh pale grey, fine grained Limestone	69
							69.89	-43.63			70

Continued on next sheet

Remarks

All angles measured relative to core normal





# Rotary Core Log

Borehole No.

**BH03**

Sheet 8 of 11

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530023.82 - 728382.57

Hole Type  
RC

Location: Galway

Level: 26.26

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 09/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		70.40 - 70.50	D							Firm, dark brown / grey, laminated CLAY, with boulders of light grey limestone	71
		70.75 - 70.85	D								72
							72.98	-46.72		Soft / firm, grey / brown fine sandy CLAY with angular fine to medium grained limestone gravel and cobbles	73
							73.95	-47.69		Loose, light grey / brown medium grained SAND, with bands of soft brown clay (Recovery 50%)	74
							75.00	-48.74		BOULDER of strong, fresh, pale grey Limestone	75
							76.14	-49.88		Firm dark brown organic CLAY, minor coarse grained gravel	76
							76.35	-50.09		Soft dark brown organic CLAY - very light / low density	77
							76.42	-50.16		Soft light brown / grey, gravelly CLAY, 50 -60% coarse angular gravel and occasional cobbles, poor recovery of clay but all cobbles / gravel have a clay coating	
											78
							79.10	-52.84		BOULDER of strong light grey limestone	79
							79.54	-53.28		Soft / firm grey brown sandy CLAY, with sub-angular limestone gravel / cobbles	80
										Continued on next sheet	

Remarks

All angles measured relative to core normal





# Rotary Core Log

Borehole No.

**BH03**

Sheet 9 of 11

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530023.82 - 728382.57

Hole Type  
RC

Location: Galway



Level: 26.26

Scale  
1:50

Client: Galway County Council

Dates: 13/11/2015 - 09/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							80.10	-53.84		Loose coarse gravelly COBBLES of light grey limestone. evidence of reworking by the bit	81
							85.55	-59.29		Tricone drilling - Open hole drilling - no recovery	82 83 84 85 86 87 88 89 90

Continued on next sheet

Remarks

All angles measured relative to core normal











# Rotary Core Log

Borehole No.

**BH04**

Sheet 1 of 7

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530150.78 - 728400.13

Hole Type  
RC

Location: Galway

Level: 32.17

Scale  
1:25

Client: Galway County Council

Dates: 11/11/2015 - 12/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		0.00 - 1.20		0	0	0				No Recovery sandy gravelly soil	1
		1.20 - 1.35		100	0	0	1.20	30.97		Mid brown, soft CLAY, with fine to medium grained, angular, limestone gravel	
		1.35 - 1.50		100	0	0	1.35	30.82		Light grey to pale brown soft CLAY	
		1.50 - 2.84		37	0	0	1.50	30.67		Rubble comprising - Strong, Slightly weathered pale grey fine to medium grained LIMESTONE	2
		2.84 - 3.36		87	13	0	2.84	29.33		Strong, fresh, pale grey to brownish grey, fine to medium grained LIMESTONE	3
		3.36 - 4.00		100	0	0	3.36	28.81		Strong, fresh, pale grey / brown, fine to medium grained massive LIMESTONE. Broken in chaotic angular fragments clasts ranging in size from 0.5cm to 10cm across in a matrix of firm to stiff brown / grey clay between fragments and in bands up to 10cm thick.	
		4.00 - 4.20	25	100	0	0	4.00	28.17		Strong, fresh, pale grey / brown, fine to medium grained massive LIMESTONE. two fracture sets, 1. dipping at 25° Planar / Rough, 2. Dipping at 85°, Planar / Rough coated with grey / brown clay.	4
		4.20 - 4.45		100	0	0	4.20	27.97		A rubble of Strong, fresh, pale grey / brown, fine to medium grained massive LIMESTONE.	
		4.45 - 4.90	9	100	24	24	4.45	27.72		Strong, fresh, pale grey / brown, fine to medium grained massive LIMESTONE. Two fracture sets, 1. dipping at 15-30° Planar to slightly undulating / Rough, infilled with grey / brown grey stiff clay with fine grained sand, 2. Dipping at 65°, Planar / Rough	
							4.90	27.27		Continued on next sheet	5

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH04**

Sheet 2 of 7

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530150.78 - 728400.13

Hole Type  
RC

Location: Galway

Level: 32.17

Scale  
1:25

Client: Galway County Council

Dates: 11/11/2015 - 12/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		4.90 - 5.95	10	100	10	10				Strong, fresh, pale grey / brown, fine to medium grained massive LIMESTONE. Etched, sub-horizontal stylolites. Two fracture sets, 1. Closely spaced, dipping at 15-25' Planar to slightly undulating / Rough, coated with light brown / grey clay and fine sand, 2. Dipping at 70 - 90', Planar -undulating/ Rough coated with grey / brown clay and fine grained sand.	
		5.95 - 6.20		88	0	0	5.95	26.22		Rubble of Strong, fresh, pale grey / brown, fine to medium grained massive LIMESTONE. Fragments angular and 1 - 7cm across.	6
		6.20 - 7.30	8	100	0	0	6.20	25.97		Strong, fresh, pale grey / brown, fine to medium grained massive LIMESTONE.. Slightly etched stylolites. two fracture sets, 1. dipping at 5 - 20' Planar / Rough,, grey clay infill 2. Dipping at 70 - 90', Planar - undulating / Rough coated with grey / brown clay.	7
		7.30 - 7.53	2	100	100	70	7.30	24.87		Strong, fresh, pale grey / brown, fine to medium grained massive LIMESTONE. One fracture set, dipping at 10' Planar / Rough,	
		7.53 - 7.80	7	100	0	0	7.53	24.64		Strong, fresh, pale grey / brown, fine to medium grained massive LIMESTONE. Sub-horizontal stylolites. 3 - 10cm apart. One fracture set dipping at 70 - 90' Undulating / Rough, brown clay fill - aperture width up to 2mm..	
		7.80 - 8.60	3	100	93	93	7.80	24.37		Strong, fresh, pale grey / brown, fine to medium grained massive LIMESTONE. Sub horizontal, well developed stylolites two fracture sets, 1. dipping at 5 - 10' Planar / Rough, 2. Dipping at 45', Planar / Rough no infill	8
		8.60 - 11.36	5	100	13	13	8.60	23.57		Strong, fresh, pale grey / brown, fine to medium grained massive LIMESTONE. Sub horizontal stylolites 10-20cm apart. Locally developed, sub -vertical white calcite veinlets at 9.7m. Three fracture sets, 1. dipping at 10 - 25' Undulating to Planar / Rough, locally developed light brown clay and fine grained sand, 2. Dipping at 70 - 90, Planar / Rough coated / infilled with with grey / brown clay. 3. Locally developed (between 9.4 - 97m), dipping at 85' Planar / Rough controlled by hairline white calcite veinlets	9
											10

Continued on next sheet

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH04**

Sheet 3 of 7

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530150.78 - 728400.13

Hole Type  
RC

Location: Galway

Level: 32.17

Scale  
1:25

Client: Galway County Council

Dates: 11/11/2015 - 12/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							11.36	20.81			11
		11.36 - 12.50	8	100	72	66				Strong, fresh, grey, fine to medium grained massive LIMESTONE. two fracture sets, 1. dipping at 5-15' Planar / Rough, locally developed thin clay light brown coating, 2. Dipping at 55', Planar / Rough coated with white grey calcite.	12
		12.50 - 15.86	1	100	100	100	12.50	19.67		Strong, fresh, grey / pale grey, fine to medium grained massive LIMESTONE. Sub horizontal stylolites., minor fine bioclastic debris. One fracture set dipping at 10' Planar / Rough.	13
											14
											15

Continued on next sheet

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH04**

Sheet 4 of 7

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530150.78 - 728400.13

Hole Type  
RC

Location: Galway

Level: 32.17

Scale  
1:25

Client: Galway County Council

Dates: 11/11/2015 - 12/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							15.86	16.31		Strong, fresh, grey, slightly mottled, fine to medium grained, massive LIMESTONE. Two fracture sets, 1. dipping at 10-25' undulating / Rough, Grey/brown to orange-brown clay coating fracture surfaces. and locally infilling fractures - aperture up to 2mm thick. 2. Dipping at 60 - 70', Planar / Rough very minor clay coating.	16
		15.86 - 17.74	6	100	41	41					17
							17.74	14.43		Strong, fresh, pale grey / grey, slightly mottled, fine to medium grained, massive LIMESTONE. 5mm wide calcite vein dipping at 85'.	18
		17.74 - 18.40	0	100	100	100					
		18.40 - 18.50		100	0	0	18.40	13.77		Very soft, dark bluish grey CLAY	
		18.50 - 18.60		100	0	0	18.50	13.67			
							18.60	13.57		Medium strength, fresh, faintly laminated, black MUDSTONE. Disseminated, sub mm to mm scale blebs of crystalline pyrite. Basal contact has a wavy / undulating nature. Strong, fresh, grey / dark grey, fine to medium grained, massive LIMESTONE. Faint brecciated intraclastic texture. - very irregular shaped angular, centimetric scale clasts in a dark grey fine grained matrix. Chaotic network of shaley stylolitic partings - incipient randomly orientated fracturing. One fracture set. dipping at 5' Planar / Rough, no infill	19
		18.60 - 19.36	1	100	100	100					
		19.36 - 19.55		79	0	0	19.36	12.81		Dark grey, soft CLAY with friable angular / tabular grey limestone fragments 2 - 5mm across Strong, fresh, grey / dark grey, slightly mottled, fine to medium grained, massive LIMESTONE. Brecciated texture, angular / irregularly shaped intraclasts 0.5 - 3cm across, in a dark grey fine grained matrix (micrite), clasts are matrix	
		19.55 - 19.95	18	100	58	40	19.55	12.62			
							19.95	12.22			20

Continued on next sheet

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH04**

Sheet 5 of 7

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530150.78 - 728400.13

Hole Type  
RC

Location: Galway

Level: 32.17

Scale  
1:25

Client: Galway County Council

Dates: 11/11/2015 - 12/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		19.95 - 20.78	0	100	100	100	20.78	11.39		supported. One fracture set, dipping at 40-45' Planar / Rough, minor grey/brown clay. Strong, fresh, grey, slightly mottled, fine to medium grained, massive LIMESTONE. Brecciated texture, sub-angular, irregular shaped, intraclasts in a dark grey fine grained matrix. Minor bioclastic debris.	21
		20.78 - 21.64	2	100	100	100	21.64	10.53		Strong, fresh, grey, fine to medium grained, massive LIMESTONE. Incipient breccia texture. Sub-horizontal stylolites 10 - 15cm apart, minor scattered bioclasts. One fracture set dipping at 25' Planar / Rough, no infill (rubbly)	22
		21.64 - 22.60	9	96	57	57	22.60	9.57		Strong, fresh, grey / pale grey, slightly mottled, fine to medium grained, massive LIMESTONE. Sub-horizontal stylolites and very small discontinuous white calcite veins. Three fracture sets, 1. dipping at 5-10' Planar to slightly stepped / Rough, 2. Dipping at 30 - 40', Planar / Rough, 3. Dipping at 70 - 75' Planar / Rough minor orange brown clay particularly over top 20cm. .	23
		22.60 - 26.50	2	100	100	99				Strong, fresh, pale grey / brownish grey, fine to medium grained, massive LIMESTONE. Scattered small bioclasts and an occasional larger (2- 3cm) coral fragment. Sub-horizontal stylolites 20 - 30cm apart. One fracture set dipping at 5-10' Planar / Rough, minor pale brown sandy clay coating.	24
										Continued on next sheet	25

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH04**

Sheet 6 of 7

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530150.78 - 728400.13

Hole Type  
RC

Location: Galway

Level: 32.17

Scale  
1:25

Client: Galway County Council

Dates: 11/11/2015 - 12/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							26.50	5.67			26
		26.50 - 27.20	9	100	46	20				Strong, fresh, pale grey / brownish grey, fine to medium grained, massive LIMESTONE. Two fracture sets, 1. dipping at 5-10 Planar / Rough, no infill. 2. Dipping at 55-60', Planar / Rough, very minor yellowish brown clay coating.	27
							27.20	4.97		Strong, fresh, pale grey, fine to medium grained, massive LIMESTONE. Two fracture sets, 1. closely / medium spaced, dipping at 5-10' Planar / Rough, Grey/brown to orange-brown clay coating fracture surfaces. and locally infilling fractures - aperture up to 2mm thick. 2. Dipping at 45", Planar / Rough	28
		27.20 - 28.95	4	100	87	78					
							28.95	3.22		CAVITY. Contacts display evidence of dissolution, pitting etc... thin coatings of yellowish brown clay	29
		28.95 - 29.32		0	0	0					
							29.32	2.85		Strong, fresh, pale grey, fine to medium grained, massive LIMESTONE. Sub-horizontal stylolites 10 - 20cm apart. One fracture set, 1. Closely spaced, dipping at 0-5' Planar / Rough,	30
		29.32 - 30.20	3	100	100	100					

Continued on next sheet

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH04**

Sheet 7 of 7

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530150.78 - 728400.13

Hole Type  
RC

Location: Galway







Level: 32.17

Scale  
1:25

Client: Galway County Council

Dates: 11/11/2015 - 12/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		30.20 - 30.40		100	0	0	30.20 30.40	1.97 1.77		Very soft light brown / grey CLAY with a band of pale brown sand 5cm thick at top. Cavity Fill?	
										Strong, fresh, pale grey, fine to medium grained, massive LIMESTONE. Sub-horizontal stylolites. One fracture sets dipping at 5-20' Planar / Rough, Medium spaced.	
		30.40 - 33.72	2	100	100	98					31 32
		33.72 - 34.30	7	100	0	0	33.72 34.20	-1.55 -2.03		Strong, fresh, pale grey, fine to medium grained, massive LIMESTONE. Sub-horizontal stylolites. Two fracture sets 1. dipping at 5-10' Planar / Rough, no infill. 2. dipping at 75-85', Planar / Rough.	34
		34.30 - 35.00	1	100	100	100				Strong, fresh, pale grey, fine to medium grained, massive LIMESTONE. Minor sub-horizontal stylolites. One fracture sets dipping at 250' Planar to undulating / Rough, no infill.	
							35.00	-2.83		End of borehole at 35.00 m	35

Remarks

All angles measured relative to short core axis







# Rotary Core Log

Borehole No.

**BH05**

Sheet 1 of 9

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530186.65 - 728378.11

Hole Type  
RC

Location: Galway







Level: 34.14

Scale  
1:25

Client: Galway County Council

Dates: 06/11/2015 - 10/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							0.40	33.74		Overburden minor cobbles recovered	
		0.40 - 0.95	13	100	0	0				Strong, pale grey, medium grained, massive LIMESTONE. Joint set dipping at 5 - 10' Planar / Rough, no infill. Joint set dipping at 85 - 90' Planar / Rough, grey calcite coating joint surface	
		0.95 - 1.17	0	100	100	100	0.95	33.19		Strong, pale grey, medium grained, massive pellety LIMESTONE	
		1.17 - 1.50	12	100	0	0			1.17	32.97	
		1.50 - 2.30	11	100	0	0	1.50	32.64			
		2.30 - 3.27	11	100	32	32			2.30	31.84	
		3.27 - 5.80	8	99	0	0	3.27	30.87			
Continued on next sheet											5

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH05**

Sheet 2 of 9

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530186.65 - 728378.11

Hole Type  
RC

Location: Galway

Level: 34.14

Scale  
1:25

Client: Galway County Council

Dates: 06/11/2015 - 10/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		5.80 - 8.00	6	100	0	0	5.80	28.34		Strong, pale grey, medium grained, pellety, massive LIMESTONE. fine grained scattered bioclastic debris, Sub horizontal stylolites. Very closely to closely spaced fractures dipping at 5 - 20', Planar to slightly undulating / Rough, minor fine grained grey sand infill. Axial parallel conjugate jointing dipping at 85 - 90' striking 120 / 60 relative to each other. minor clay coating	6
		8.00 - 8.68	1	91	91	91	8.00	26.14		Strong, pale grey, medium grained, massive LIMESTONE. fine grained scattered bioclastic debris, Sub horizontal stylolites.	8
		8.68 - 9.50	11	100	88	37	8.68	25.46		Strong, pale grey, fine grained, massive LIMESTONE. Sub horizontal stylolites. Fractures dipping at 5 - 10', Planar / Rough, Fractures dipping at 45' Planar - slightly undulating / Rough	9
		9.50 - 10.25	0	100	100	100	9.50	24.64		Strong, pale grey, fine grained, massive LIMESTONE. fine, sub horizontal stylolites, spaced 5 - 10cm.	10

Continued on next sheet

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH05**

Sheet 3 of 9

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530186.65 - 728378.11

Hole Type  
RC

Location: Galway





Level: 34.14

Scale  
1:25

Client: Galway County Council

Dates: 06/11/2015 - 10/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							10.25	23.89		Strong, pale grey, fine grained, massive LIMESTONE. Sub horizontal stylolites. Three fractures sets 1. dipping at 5 - 10', Planar / Rough, no infill; 2. dipping at 45 - 50' planar to slightly undulating / Rough, fine sand coating fracture surfaces. 3. dipping at 85 - 90', Planar to slightly undulating / Rough cross-cutting the other fracture sets.	11
		10.25 - 11.34	13	100	0	0					
							11.34	22.80		Strong, pale grey, fine to medium grained, massive LIMESTONE. Sub horizontal stylolites. Two fracture sets 1. dipping at 5 - 10', Planar to slightly undulating / Rough, 2. dipping at 85 - 90', Planar / Rough very minor iron staining.	12
		11.34 - 12.62	3	100	100	78					
							12.62	21.52		Strong, pale grey / grey, fine / medium grained, massive LIMESTONE. Two fractures sets 1. Close to very closely spaced dipping at 5 - 20', Planar / Rough; 2. dipping at 70 - 80', Planar / Rough	13
12.62 - 13.27	15	100	0	0							
						13.27	20.87		Strong, grey, fine / medium grained, massive LIMESTONE. Very small scattered bioclasts, Occasional sub-horizontal stylolites. Small elongate calcite filled "Birdseyes", elongate sub vertical long axis 5 - 10mm long and 0.5mm wide. Two fracture sets 1. Medium spaced dipping at 5 - 15', Planar / Rough; 2. Widely spaced, dipping at 55', Planar / Rough	14	
		13.27 - 15.04	4	100	100	96					15
Continued on next sheet											

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH05**

Sheet 4 of 9

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530186.65 - 728378.11

Hole Type  
RC

Location: Galway

Level: 34.14

Scale  
1:25

Client: Galway County Council

Dates: 06/11/2015 - 10/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description		
				TCR	SCR	RQD						
		15.04 - 15.44	18	100	100	0	15.04	19.10		Strong, grey, fine / medium grained, massive LIMESTONE. Very small scattered bioclasts and a large 1cm dia. gastropod , Occasional sub-horizontal stylolites. Two fracture sets 1. Closely to very closely spaced dipping at 5 - 15', Planar / Rough; 2. Dipping at 85', Planar to slightly undulating / Rough	16	
		15.44 - 16.82	2		100	100	15.44	18.70				
		16.82 - 18.40	8	100	100	63	16.82	17.32		Strong, grey, fine / medium grained, massive LIMESTONE. Fine grained scattered bioclastic debris. Locally developed intraclasts, clasts are rounded to sub-rounded 1 - 2cm in dia. Two fracture sets 1. Medium spaced dipping at 10 - 15', Planar / Rough, minor associated rubble; 2. Sub-vertical - undulating dipping at 80 - 90', Planar / Rough	17	
		18.40 - 19.26	7	100	95	60	18.40	15.74				
		19.26 - 19.95	3	100	100	100	19.26	14.88		Strong, pale grey, fine / medium grained, massive, pelley LIMESTONE. Fine scattered bioclasts, Occasional sub-horizontal stylolites. Fracture set dipping at 5 - 10', Planar / Rough, no infill.	19	
							19.95	14.19				
		Continued on next sheet										

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH05**

Sheet 5 of 9

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530186.65 - 728378.11

Hole Type  
RC

Location: Galway

Level: 34.14

Scale  
1:25

Client: Galway County Council

Dates: 06/11/2015 - 10/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description				
				TCR	SCR	RQD								
		19.95 - 20.20	24	100	60	0	20.20 20.30 20.45	13.94 13.84 13.69		Strong, grey, fine / medium grained, massive LIMESTONE. Two fracture sets 1. Closely spaced dipping at 5 - 10', Planar / Rough; 2. Dipping at 45', Planar / Rough light brown clay infill, up to 2mm thick. Core loss Very stiff, light brown / orange brown CLAY. Finely laminated.	21			
		20.20 - 20.30	0	0	0	0								
		20.30 - 20.45	0	100	100	100								
		20.45 - 20.75	20	100	0	0								
		20.75 - 21.50	9	100	35	24	21.50	12.64		Strong, grey, fine / medium grained, massive LIMESTONE. Small black millimetric scale blebs- burrowing? Three fracture sets 1. Very closely spaced, dipping at 5', Planar / Rough; 2. Dipping at 80', Planar / Rough with white calcite coating fracture surfaces. 3. dipping at 70', undulating / rough crosscut by set 2. Strong, grey pale grey mottled, fine / medium grained, massive, pellety LIMESTONE. Intraclastic texture sub-angular to sub-rounded clasts 1 - 2cm dia. in a darker grey fine grained matrix. Two fracture sets 1. Dipping at 10 - 15', Planar / Rough; 2. Dipping at 60', Planar to undulating / Rough, fracture surfaces coated with light brown clay		22		
		21.50 - 22.40	4	100	94	94								
		22.40 - 23.73	5	100	16	16	22.40	11.74		Strong, grey, medium grained, massive LIMESTONE. Very small scattered bioclasts with occasional coarse brachiopods. Minor sub-horizontal stylolites. Two fracture sets 1. Medium spaced dipping at 10', Planar / Rough; 2. Medium spaced, dipping at 35', Planar / Rough  Strong, pale grey, fine / medium grained, massive LIMESTONE. Occasional sub-horizontal stylolites with minor oxidation. Thin hairline, steeply dipping white calcite veinlets. Two fracture sets 1. Medium spaced dipping at 5 - 10', Planar / Rough; 2. Dipping at 80-85', Planar / Rough, light brown clay coating fracture surfaces, locally developed fracture infill up to 1mm thick			23	
		23.73 - 25.55	2	100	93	93								
23.73 - 25.55	2	100	93	93	23.73	10.41		Strong, grey / grey brown, fine / medium grained, massive LIMESTONE. Occasional faint, sub-horizontal stylolites. Minor scatter fine bioclastic debris. Two fracture sets 1. Medium spaced dipping at 5 - 10', Planar / Rough; 2. Dipping at 60', Planar / Rough	24					
23.73 - 25.55	2	100	93	93										
Continued on next sheet											25			

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH05**

Sheet 6 of 9

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530186.65 - 728378.11

Hole Type  
RC

Location: Galway

Level: 34.14

Scale  
1:25

Client: Galway County Council

Dates: 06/11/2015 - 10/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		25.55 - 25.85	13	100	80	80	25.55	8.59		Strong, grey / brownish grey, fine / medium grained, massive LIMESTONE. Very small scattered bioclasts. Two fracture sets 1. dipping at 10 - 20', Planar / Rough; 2. Dipping at 50', Planar / Rough no infill	26
		25.85 - 26.60	3	100	91	91	25.85	8.29		Strong, grey, fine / medium grained, massive LIMESTONE. Slightly oxidised sub-horizontal stylolites. Fracture set dipping at 5 - 10', Planar / Rough; no infill	
		26.60 - 27.65	9	100	37	37	26.60	7.54		Strong, pale grey / brownish grey, fine / medium grained, massive LIMESTONE. Occasional thick shelled bioclasts - brachiopod, Three fracture sets 1. Dipping at 10 - 20', Planar / Rough; 2. Close spaced, dipping at 55 - 60', Planar / Rough; 3. Dipping at 85', Planar / Rough minor white calcite coating fracture surfaces	27
		27.65 - 28.03	3	100	100	100	27.65	6.49		Strong, pale grey / brownish grey, fine / medium grained, massive LIMESTONE. Occasional sub-horizontal stylolites. Fracture set dipping at 5', Planar / Rough, no infill	28
							28.03	6.11		Strong, pale grey / brownish grey, fine / medium grained, massive LIMESTONE. Three fracture sets 1. Close spaced dipping at 5 - 20', Planar / Rough; 2. Widely spaced, dipping at 40-50', Planar / Rough, at 31.7m light brown clay infill 1mm thick; 3. Axial parallel - 90', crosscuts all the other fracture sets. Planar / rough with a thin coating of white calcite.	
											29
											30

Continued on next sheet

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH05**

Sheet 7 of 9

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530186.65 - 728378.11

Hole Type  
RC

Location: Galway

Level: 34.14

Scale  
1:25

Client: Galway County Council

Dates: 06/11/2015 - 10/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		28.03 - 32.03	3	100	0	0					31
							32.03	2.11		Strong, pale grey / brownish grey, fine / medium grained, massive LIMESTONE. Occasional sub-horizontal stylolites. One fracture set, close to Medium spaced, dipping at 5 - 20°, Planar / Rough, no infill.	32
		32.03 - 34.72	4	100	100	97					33
							34.72	-0.58		Strong, grey . brownish grey, fine / medium grained, massive LIMESTONE. Very small scattered bioclasts, and a rare thick shelled	34
											35

Continued on next sheet

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH05**

Sheet 8 of 9

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530186.65 - 728378.11

Hole Type  
RC

Location: Galway

Level: 34.14

Scale  
1:25

Client: Galway County Council

Dates: 06/11/2015 - 10/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		34.72 - 37.20	6	100	4	4	37.20	-3.06		brachiopod . Occasional sub-horizontal stylolites. Three fracture sets 1. Close spaced dipping at 10 - 20', Planar / Rough; 2. Very widely spaced, dipping at 35-40', Planar / Rough; 3. 75 - 85' Undulating / rough, fracture surface coated with light brown clay. Crosscuts other fracture sets	36
		37.20 - 38.00	0	100	100	100				Strong, grey / pale grey, fine / medium grained, massive LIMESTONE.	37
		38.00 - 40.00		100	0	0				Strong, pale grey, fine to medium grained, massive LIMESTONE. Occasional stylolites, two fracture sets. 1. dipping at 5', planar / rough , 2. dipping at 85-90' Planar / rough coated and partially infilled by light brown clay	38
											39
											40

Continued on next sheet

Remarks

All angles measured relative to short core axis







# Rotary Core Log

Borehole No.

**BH05**

Sheet 9 of 9

Project Name: Lackagh Quarry Preliminary  
Ground InvestigationProject No.  
Lackagh Quarry

Co-ords: 530186.65 - 728378.11

Hole Type  
RC

Location: Galway



Level: 34.14

Scale  
1:25

Client: Galway County Council

Dates: 06/11/2015 - 10/11/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / Fl	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							40.30	-6.16	 	End of borehole at 40.30 m	
											41
											42
											43
											44
											45

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH06**

Sheet 1 of 5

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530125.14 - 728383.08

Hole Type  
RC

Location: Galway

Level: 30.80

Scale  
1:50

Client: Galway County Council

Dates: 10/12/2015 - 18/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							0.10	30.70		TOPSOIL Soft, pale grey, sandy CLAY (Recovery 35%)	
							1.05	29.75		Loose grey to dark grey cobbly BOULDERS of bioclastic limestone, minor pale grey sandy clay	1
							1.50	29.30		Firm, light yellowish brown, sandy CLAY, coarse grained sub-angular cobbles of dark grey limestone and occasional granite cobble (recovery 45%)	2
							3.10	27.70		Very stiff, light yellowish brown sandy CLAY with coarse gravel / cobbles and occasional boulders of sub-rounded to sub-angular limestone with minor granite	3
		5.25 - 5.50	C							Firm / stiff light grey CLAY	4
							7.91	22.89		Very stiff, light brown sandy CLAY with minor light orange oxidation spots / patches. Coarse gravel / cobbles and occasional boulders of sub-rounded to sub-angular limestone with minor granite	5
							7.96	22.84		Very stiff, light brown sandy CLAY with minor light orange oxidation spots / patches. Coarse gravel / cobbles and occasional boulders of sub-rounded to sub-angular limestone with minor granite	6
										Very stiff, light brown sandy CLAY with minor light orange oxidation spots / patches. Coarse gravel / cobbles and occasional boulders of sub-rounded to sub-angular limestone with minor granite	7
										Very stiff, light brown sandy CLAY with minor light orange oxidation spots / patches. Coarse gravel / cobbles and occasional boulders of sub-rounded to sub-angular limestone with minor granite	8
										Very stiff, light brown sandy CLAY with minor light orange oxidation spots / patches. Coarse gravel / cobbles and occasional boulders of sub-rounded to sub-angular limestone with minor granite	9
		9.95 - 10.20	C							Very stiff, light brown sandy CLAY with minor light orange oxidation spots / patches. Coarse gravel / cobbles and occasional boulders of sub-rounded to sub-angular limestone with minor granite	10

Continued on next sheet

Remarks

All angles measured relative to short core axis







# Rotary Core Log

Borehole No.

**BH06**

Sheet 3 of 5

Project Name: Lackagh Quarry Preliminary  
Ground InvestigationProject No.  
Lackagh Quarry

Co-ords: 530125.14 - 728383.08

Hole Type  
RC

Location: Galway

Level: 30.80

Scale  
1:50

Client: Galway County Council

Dates: 10/12/2015 - 18/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
		21.45 - 21.52 21.52 - 21.60	D D				21.20	9.60		Firm grey CLAY	21
							21.48	9.32		Firm / Stiff finely laminated dark brown / brown CLAY	
							21.82	8.98		Firm, dark brown CLAY with 60% tabular angular gravel	22
							21.92	8.88		Firm grey fine sandy CLAY with angular limestone gravel and some coarse cobbles and small boulders	
							22.60	8.20		Very soft, light grey sandy CLAY with rounded gravel	
							22.84	7.96		Soft, grey sandy CLAY angular gravel / cobbles	23
							23.30	7.50		Firm / Stiff grey sandy CLAY with sub-angular / angular matrix supported coarse gravel and cobbles	
							23.60	7.20		Soft, grey, sandy CLAY with medium / coarse grained, angular gravel and an occasional boulder (25cm dia.	24
											25
							25.50	5.30		Soft / firm grey / green sandy CLAY with sub angular cobbles and boulders. Some of the clay is washed out and is just coated the cobbles and boulders	26
							26.65	4.15		Stiff / very stiff, light grey CLAY occasional boulder of pale grey limestone	27
							27.30	3.50		Loose, grey / dark grey cobbly GRAVEL with occasional boulders of limestone coated with very soft brownish grey clay	28
											29
											30

Continued on next sheet

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH06**

Sheet 4 of 5

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530125.14 - 728383.08

Hole Type  
RC

Location: Galway

Level: 30.80

Scale  
1:50

Client: Galway County Council

Dates: 10/12/2015 - 18/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							30.85	-0.05		Soft / very soft, pale grey / greenish grey bouldery CLAY, cobbles and coarse gravel, clay washed out and just left coating fragments in some areas.	31
											32
											33
							33.20	-2.40		Firm greenish grey (Khaki) CLAY with angular coarse cobbles of pale grey limestone	
							33.50	-2.70		Firm, greenish grey gravelly CLAY, gavel composed of dark grey limestone	
							33.70	-2.90		Pale grey, medium grained, fresh, massively bedded limestone BOULDER Broken up along a series of fractures - undulating rough dipping at 70-80° and planar rough dipping at 50-60°. Minor grey clay coating joint surfaces.	34
							34.70	-3.90		Loose sub-angular COBBLES coated with soft pale grey clay	35
							35.10	-4.30		Soft greenish grey sandy, gravelly CLAY with angular cobbles and small boulders of pale grey / occasionally black limestone	36
											37
											38
							39.10	-8.30		Loose sub-angular COBBLES of very dark grey limestone (Recovery 30%)	39
											40

Continued on next sheet

Remarks

All angles measured relative to short core axis





# Rotary Core Log

Borehole No.

**BH06**

Sheet 5 of 5

Project Name: Lackagh Quarry Preliminary Ground Investigation

Project No.  
Lackagh Quarry

Co-ords: 530125.14 - 728383.08

Hole Type  
RC

Location: Galway

Level: 30.80

Scale  
1:50

Client: Galway County Council

Dates: 10/12/2015 - 18/12/2015

Logged By  
Dave Blaney

Well	Water Strikes	Depth (m)	Type / FI	Coring			Depth (m)	Level (m)	Legend	Stratum Description	
				TCR	SCR	RQD					
							40.60	-9.80		Loose, coarse gravelly COBBLES, angular to sub-angular with some coated by greenish grey clay occasional small boulder	41
							44.40	-13.60		BOULDER of strong, fresh, fine / medium grained, massively bedded Limestone. 44.8m a joint filled with soft, dark grey clay, 2cm thick (Possibly bedrock)	42
							45.00	-14.20		End of borehole at 45.00 m	43
											44
											45
											46
											47
											48
											49
											50

Remarks

All angles measured relative to short core axis



## APPENDIX III

Depth of Discontinuity (m BGL)	Azimuth	Dip	PROJECT NAM   Lackagh Quarry																				REPORT NO:		Hole Azimuth	Hole Dip	True Azimuth	True Dip				
			CLIENT:   Galway County Council																				HOLE NO:						BH-01			
			ENGINEER: ARUP																				LOGGED BY:						Dave Blaney			
			Non Intact? (NI)	Roughness						Aperture				Filling					Weathering													
Stepped				Undulating			Planar			Other	V Open	Open	Mod Open	Tight	V Tight	Clean	Staining	% Soil	% Mineral	Clay	No	SI	Mod		High	Comp						
			R	Sm	St	R	Sm	St	R		Sm	St		>10 mm	2.5-10	0.5-2.5	0.1-0.5	<0.1														
5.80		45					X								X			X				X						No Invert marked	268	-11.5		
5.95		10								X					X			X				X						No Invert marked	268	-11.5		
6.10		20								X					X			X				X						No Invert marked	268	-11.5		
6.18		25	X							X					X			X				X						No Invert marked	268	-11.5		
6.30		65	X							X					X			X				X						No Invert marked	268	-11.5		
6.90	180	85								X					X			X				X							268	-11.5		
7.08	190	60								X					X			X				X							268	-11.5		
7.52	165	65								X					X			X				X							268	-11.5		
7.58	165	65								X					X			X				X							268	-11.5		
7.66	230	70								X					X			X				X							268	-11.5		
7.90	180	55					X								X			X				X							268	-11.5		
8.35	285	90								X					X			X				X							268	-11.5		
8.55	210	75								X					X			X				X							268	-11.5		
8.72	135	72								X					X			X				X							268	-11.5		
8.83	60	82								X					X			X				X							268	-11.5		
8.85	150	90					X								X			X				X							268	-11.5		
9.35	195	78								X					X			X				X							268	-11.5		
9.67	215	90								X					X			X				X							268	-11.5		
9.81	130	62								X					X			X				X							268	-11.5		
9.90	335	82								X					X			X				X							268	-11.5		
10.17	330	90								X					X			X				X							268	-11.7		
10.20	180	90					X								X			X				X							268	-11.7		
10.71	10	90								X					X			X				X							268	-11.7		
10.90	5	82								X					X			X				X							268	-11.7		
11.42	0	75								X					X			X				X							268	-11.7		
11.44	115	74								X					X			X					X				Slight Fe Staining	268	-11.7			
11.54	200	40	X							X					X			X				X							268	-11.7		
11.92	145	45								X					X			X				X							268	-11.7		
11.97	180	85								X					X			X				X							268	-11.7		
12.20	285	45					X								X			X				X							268	-11.7		
12.35	350	50	X							X					X			X				X							268	-11.7		
12.47	100	65								X					X			X				X							268	-11.7		
13.02	150	60								X					X			X				X							268	-11.7		
13.33	220	60								X					X					x		X					Partial coating of white calcite	268	-11.7			
13.43	350	75								X					X			X				X							268	-11.7		
14.32	25	72								X					X			X				X							268	-11.7		
14.36	120	85								X					X			X				X							268	-11.7		
14.39	185	62								X					X			X				X							268	-11.7		
14.42	30	80								X					X			X				X							268	-11.7		
14.45	120	80								X					X			X				X							268	-11.7		
14.52	140	65								X					X					X	X	X					Minor white calcite and smears of pale brown clay	268	-11.7			
14.56	50	80								X					X							X							268	-11.7		
14.70	170	80								X					X					X			X				White clacite and small patches of Fe Staining	268	-11.7			
15.27	165	80								X					X					X		X					Very Minor white calcite	268	-11.7			
15.47	170	80								X					X					X		X						268	-11.7			
15.58	130	72								X					X						X	X	X				White clacite and minor clay smears	268	-11.7			
15.63	355	50								X					X				X			X						268	-11.7			
15.68	75	90								X					X				X			X						268	-11.7			
15.76	135	85								X					X			X				X						268	-11.7			
15.83	195	60								X					X					X	X	X					Minor light brown clay	268	-11.7			
16.33	170	85								X					X				X			X						268	-11.8			
17.05	180	85								X					X				X			X						268	-11.8			





[illegible]

58.48	0	80								X						X			X											Possible drillers break	267	-12.7		
58.80	5	90									X					X			X											Triae due to intersecting stylolite	267	-12.7		
59.47	355	90								X						X			X												267	-12.7		
59.63	160	85								X						X			X												267	-12.7		
59.83	170	80							X							X			X											Curved / Arcuate joint surface	267	-12.7		
60.00	5	90								X						X			X												267	-12.7		
61.02	180	80								X						X			X												267	-12.8		
61.47	140	70								X						X			X				X							Trace grey calcite	267	-12.8		
61.80	90	85	X							X						X			X				X								267	-12.8		
61.85	200	65								X						X			X			X								Partial orange / brown Fe staining	267	-12.8		
62.02	20	80								X						X			X				X							Very Rough joint surface	267	-12.8		
62.17	50	60								X						X			X				X								267	-12.8		
62.58	145	60								X						X			X				X							Light grey calcite coating	267	-12.8		
63.77	40	50								X						X			X				X								267	-12.8		
63.97	200	42								X						X			X				X								267	-12.8		
64.06	30	65								X						X			X				X								267	-12.8		
64.20	210	50								X						X			X				X								267	-12.8		
64.50	345	50								X						X			X				X								267	-12.8		
64.98	180	85								X						X			X				X								267	-12.8		
65.72	130	75								X						X			X				X								267	-12.8		
65.88	130	80								X						X			X				X								267	-12.8		
66.97	50	80								X						X			X				X								267	-12.8		
66.99	50	78								X						X			X				X								267	-12.8		
67.20	175	78								X						X			X				X								267	-12.9		
67.60	220	80								X						X			X				X								267	-12.9		
67.70	45	90								X						X			X				X								267	-12.9		
67.90	60	72	X							X						X			X				X								267	-12.9		
68.38	350	90								X						X			X				X								267	-12.9		
68.60	355	90								X						X			X				X								267	-12.9		
68.66	350	90								X						X			X				X								267	-12.9		
68.73	0	90								X						X			X				X							Calcite vein 1mm thick	267	-12.9		
68.78	0	80								X						X			X				X							Calcite vein	267	-12.9		
68.90	170	75								X						X			X				X							Very irregular	267	-12.9		
69.25	355	90								X						X			X				X								267	-12.9		
69.66	20	75								X						X			X				X								267	-12.9		
69.93	325	85	X							X						X			X				X								267	-12.9		
69.98	140	75								X						X			X				X								267	-12.9		
70.13	10	80								X						X			X				X								267	-12.9		
70.27	15	80								X						X			X				X								267	-12.9		
70.60	5	80														X			X				X							Slickensides, plunging at 25' to 270'	267	-12.9		
71.43	355	80								X						X			X				X							Curved Arcuate Joint	267	-12.9		
71.90	50	82								X						X			X				X								267	-12.9		
72.34	310	80								X						X			X				X								267	-12.9		
72.45	50	30								X						X			X				X								267	-12.9		
72.50	135	45	X							X						X			X				X							Slight pale orange Fe staining	267	-12.9		
72.80	0	90								X						X			X				X								267	-12.9		
73.20	295	30								X						X			X				X								267	-12.9		
73.74	35	72								X						X			X				X								267	-12.9		
73.98	75	65								X						X			X				X							very small mm scale steps	267	-12.9		
74.50	350	78														X			X				X							White grey calcite vein, sub-horizontal striae	267	-12.9		
74.60	80	75								X									X				X								267	-12.9		
74.73	195	72								X						X			X				X							Very rough texture - almost stepped	267	-12.9		
75.14	5	80								X						X			X				X								267	-12.9		
75.27	150	55								X						X			X				X								267	-12.9		
75.50	170	85														X			X				X							Faint stating	267	-12.9		
75.80	20	75	X							X						X			X				X								267	-12.9		
75.92	30	65								X						X			X				X								267	-12.9		
76.09	25	70								X						X			X				X								267	-12.9		
76.19	165	60								X						X			X				X								267	-12.9		
76.39	50	50	X							X						X			X				X								267	-12.9		
76.72	200	70								X						X			X				X								267	-12.9		
77.10	325	70								X						X			X				X								267	-12.9		









[illegible]



222.05	25	52										X					X																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								</
--------	----	----	--	--	--	--	--	--	--	--	--	---	--	--	--	--	---	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	----



269.00		85	X						X						X			X					X						No Invert Marked - Conjugate Jointing	266	-14.1		
269.00		75				X									X			X					X						No Invert Marked - Conjugate Jointing	266	-14.1		
269.52	140	76							X						X			X					X							266	-14.1		
269.75	90	48							X						X			X					X							266	-14.1		
270.15	310	30							X						X			X					X							266	-14.1		
271.54	180	82							X						X			X					X							266	-14.1		

		PROJECT NAME   Lackagh Quarry																			REPORT NO:							
		CLIENT:   Glaway County Council																			HOLE NO:		BH-04					
		ENGINEER: ARUP																			LOGGED BY:		Dave Blaney					
Depth of Discontinuity (m BGL)	Orient.to Short Core Axis	Non Intact? (NI)	Roughness										Aperture					Filling				Weathering					Comments	
			Stepped			Undulating			Planar			Other	V Open	Open	Mod Open	Tight	V Tight	Clean	Staining	% Soil	% Mineral	Clay	No	SI	Mod	High		Comp
			R	Sm	St	R	Sm	St	R	Sm	St		>10m m	2.5-10	0.5-2.5	0.1-0.5	<0.1											
5.30	20								X						X							X	X					Grey brown soft clay
5.40	20								X						X							X	X					Grey brown soft clay
5.60	50								X						X							X	X					Grey brown soft clay
5.70	80					X									X							X	X					Grey brown soft clay
6.35	10					X									X							X	X					Grey brown soft clay
6.40	90								X							X						X	X					Minor clay smeared on fracture surface
6.70	90								X							X						X	X					Minor clay smeared on fracture surface
6.50	15					X									X			X					X					
6.68	35					X									X			X					X					
6.95	85								X						X							X	X					Minor br/gy clay smeared on fracture surface
7.02	5								X						X			X					X					
7.37	15								X						X			X					X					
7.54	15								X						X			X					X					
7.73	75					X									X			X					X					
7.75	80					X									X							X	X					Stiff / Firm br/gy clay 1mm aperture
7.86	10								X						X			X					X					
8.20	10					X									X			X					X					
8.70	70					X									X			X					X					
8.90	80					X									X							X	X					Firm gy/br clay 2mm aperture
8.95	5					X									X							X	X					Minor gy/br clay smearing fract. Surface
9.05	80					X									X							X	X					Firm gy/br clay 1mm aperture
9.10	10					X									X							X	X					
9.16	80					X									X							X	X					
9.24	55					X									X			X					X					
9.72	85					X									X							X	X					
9.33	85					X									X							X	X					
9.40	50					X									X			X					X					
9.50	85								X						X							X	X					Minor light grey clay smearing
10.00	80					X									X							X	X					Minor light grey clay smearing
10.50	80					X									X							X	X					Localised small smears of light grey clay
10.87	5								X						X			X					X					
11.06	80					X									X			X					X					
11.30	60					X									X			X					X					
11.60	45								X						X			X					X					

		PROJECT NAME    Lackagh Quarry																				REPORT NO:								
		CLIENT:    Glaway County Council																				HOLE NO:	BH-04							
		ENGINEER: ARUP																				LOGGED BY:	Dave Blaney							
Depth of Discontinuity (m BGL)	Orient to Short Core Axis	Non Intact? (NI)	Roughness												Aperture					Filling					Weathering					Comments
			Stepped			Undulating			Planar			Other	V Open	Open	Mod Open	Tight	V Tight	Clean	Staining	% Soil	% Mineral	Clay	No	SI	Mod	High	Comp			
			R	Sm	St	R	Sm	St	R	Sm	St		>10m m	2.5-10	0.5-2.5	0.1-0.5	<0.1													
11.63	5	x							x							x						x								
11.79	45								x							x						x								
11.80	5	x							x							x						x								
11.97	15					x										x						x								
12.50	60								x							x				x									White / grey calcite coating	
12.51	15								x							x						x								
12.92	15					x										x						x								
14.40	10					x										x						x								
15.14	10					x										x						x								
15.90	70								x											x	x								Minor light grey clay smearing fract. Surface	
16.38	10					x									x								x						Minor etching / pitting on fract. Surface	
16.55	70					x										x						x								
16.77	5					x										x						x								
17.05	10					x										x						x							Strongly undulating - 30mm amplitude	
17.40	10					x									x						x	x							Orange / brown clay infill	
17.50	80					x															x		x						Minor clay and localised Fe. staining	
17.60	45	x							x							x						x								
17.65	70	x							x							x						x								
18.77	10								x							x						x								
19.93	25					x							x									x								
20.98	10								x							x						x								
21.85	60					x										x						x								
22.05	20					x									x							x								
22.15	40								x							x						x								
22.35	10								x							x						x								
23.10	10								x							x								x					Slight Fe Staining	
23.13	0								x							x						x								
23.62	5								x							x						x								
24.17	20								x							x						x								
24.98	5					x										x						x								
25.16	10					x									x								x						Slight Fe Staining	
25.58	10								x							x						x								
25.80	10								x							x						x								

		PROJECT NAME   Lackagh Quarry																			REPORT NO:								
		CLIENT:   Glaway County Council																			HOLE NO:		BH-04						
		ENGINEER: ARUP																			LOGGED BY:		Dave Blaney						
Depth of Discontinuity (m BGL)	Orient.to Short Core Axis	Non Intact? (NI)	Roughness										Aperture					Filling					Weathering					Comments	
			Stepped			Undulating			Planar			Other	V Open	Open	Mod Open	Tight	V Tight	Clean	Staining	% Soil	% Mineral	Clay	No	SI	Mod	High	Comp		
			R	Sm	St	R	Sm	St	R	Sm	St		>10m m	2.5-10	0.5-2.5	0.1-0.5	<0.1												
26.52	5					x									x							x							
26.70	75								x							x					x	x							Fine smear of light brown clay
26.72	20	x							x							x						x							
26.96	5					x										x						x							
27.06	60	x							x							x						x							
27.09	15	x							x							x						x							
27.13	10	x							x							x						x							
27.18	60	x							x							x						x							
27.53	5								x							x						x							
27.84	5					x										x						x							
27.87	5								x							x						x							
27.98	5								x							x						x							
28.25	5								x							x					x	x							Trace light grey clay coating
28.55	50								x							x						x							
28.90						x							x								x		x						37cm wide void - minor clay / slight oxidat.
29.77	5								x							x						x							
29.94	5								x							x						x							
30.10	5								x							x						x							
30.63	15					x										x					x	x							Minor light brown clay smearing
30.69	5								x							x						x	x						Minor light brown clay smearing
30.92	10					x										x						x							
31.43	10					x										x						x	x						Minor light brown clay smearing
31.60	5					x										x						x	x						Minor light brown clay smearing
32.47	20								x							x						x							
32.90	5								x							x						x							
33.94	10	x							x							x						x							
34.00	85								x							x						x							
34.04	10	x							x							x						x							
34.30	10	x							x							x						x							
34.52	75								x							x						x							
34.57	15	x							x							x						x							
34.96	15								x							x						x							

		PROJECT NAME   Lackagh Quarry																		REPORT NO:								
		CLIENT:   Galway County Council																		HOLE NO:		BH-05						
		ENGINEER: ARUP																		LOGGED BY:		Dave Blaney						
Depth of Discontinuity (m BGL)	Orient.to Short Core Axis	Non Intact? (NI)	Roughness										Aperture					Filling					Weathering					Comments
			Stepped			Undulating			Planar			Other	V Open	Open	Mod Open	Tight	V Tight	Clean	Staining	% Soil	% Mineral	Clay	X	Sl	Mod	High	Comp	
			R	Sm	St	R	Sm	St	R	Sm	St		>10m m	2.5-10	0.5-2.5	0.1-0.5	<0.1											
0.52	5	X				X								X				X				X						
0.60	5					X								X				X				X						
0.63	85								X					X				X			X							White / brown crystalline calcite
0.63	85								X					X				X				X						
0.68	5					X								X				X				X						
0.75	5	X							X					X				X				X						
0.84	5	X							X					X				X				X						
0.90	5								X					X				X				X						
1.31	15								X					X							X	X						Pale brown clay smearing fract. Surface
1.37	10	X				X								X							X	X						Pale brown clay smearing fract. Surface
1.40	10	X				X								X							X	X						Pale brown clay smearing fract. Surface
1.50	85	X							X					X							X	X						Pale brown clay smearing fract. Surface
1.66	5					X								X							X	X						Pale brown clay smearing fract. Surface
1.83	85	X							X					X				X				X						
2.13	10								X					X				X				X						
2.22	20		X											X				X				X						
2.42	5								X					X				X				X						
2.47	10								X					X				X				X						
2.57	10								X					X				X				X						
2.64	5								X					X				X				X						
2.70	10								X					X				X				X						
2.77	20					X								X				X				X						
2.82	5								X					X				X				X						
2.99	15								X					X				X				X						
3.07	10					X								X				X				X						
3.20	10								X					X				X				X						
3.27	20								X					X				X				X						
3.50	85					X								X				X				X						Minor fine gr. Sand coating fract. Surface
3.45	15	X				X								X				X				X						
3.62	20	X				X			X					X				X				X						
4.02	15								X					X				X				X						
4.10	85								X					X							X			X				Fine sandy clay coating & weak Fe staining
4.10	85								X					X							X			X				Joints are sub-parallel c.2-3cm apart
4.16	5								X					X				X				X						

	PROJECT NAME    Lackagh Quarry																				REPORT NO:								
	CLIENT:    Galway County Council																				HOLE NO:		BH-05						
	ENGINEER: ARUP																				LOGGED BY:		Dave Blaney						
Depth of Discontinuity (m BGL)	Orient.to Short Core Axis	Non Intact? (NI)	Roughness										Aperture					Filling					Weathering					Comments	
			Stepped			Undulating			Planar			Other	V Open	Open	Mod Open	Tight	V Tight	Clean	Staining	% Soil	% Mineral	Clay	X	SI	Mod	High	Comp		
			R	Sm	St	R	Sm	St	R	Sm	St		>10m m	2.5-10	0.5-2.5	0.1-0.5	<0.1												
4.25	5	X							X						X						X								
4.50	5	X							X						X						X								
4.73	5	X							X						X						X								
4.60	85								X						X						X			X				Fine sandy clay coating & weak Fe staining	
4.60	85								X						X						X			X				Fine sandy clay coating & weak Fe staining. Joints are parallel and 2cm apart	
4.74	5	X							X						X					X									
4.83	5	X							X						X					X									
3.85-8.0	85-90								X						X					X	X			X				Fine sandy clay coating & Fe staining. Fracture is are axial parallel and continue for 4.15m. From 6.5m white calcite deposited on fracture surface. 7.0-7.65m firm brown/grey clay infill - aperture up to 4mm wide	
4.97	5	X							X						X					X									
5.07	10	X							X						X						X	X						Minor clay coating fracture surface	
5.13	20	X							X						X						X	X						Minor clay coating fracture surface	
5.20	75	X							X						X					X								Conjugate with vertical joint	
5.16	10	X							X						X					X									
5.61	20	X				X									X					X									
5.73	10	X							X						X					X									
5.80	5	X							X						X					X									
5.97	5	X							X						X					X									
6.10	85	X	X												X					X	X							Conjugate with vertical fracture strike 120 / 60'	
6.26	5	X							X						X					X									
6.38	10	X							X						X					X	X							Light brown clay	
6.48	5	X							X						X					X									
6.60	5	X							X						X					X									
6.74	5	X							X						X					X									
6.78	5	X							X						X					X									
6.88	15	X				X									X					X									
6.91	10	X				X									X					X									
7.13	5	X							X						X					X									
7.37	5	X							X						X					X									
7.57	10	X							X						X					X									
7.74	15								X						X					X									
8.64	0								X							X					X							Orange brown Fe staining	
8.68	50								X							X					X							Orange brown Fe staining	
8.73	50								X							X					X							Orange brown Fe staining	




		PROJECT NAME   Lackagh Quarry																			REPORT NO:								
		CLIENT:   Galway County Council																			HOLE NO:		BH-05						
		ENGINEER: ARUP																			LOGGED BY:		Dave Blaney						
Depth of Discontinuity (m BGL)	Orient.to Short Core Axis	Non Intact? (NI)	Roughness											Aperture					Filling					Weathering					Comments
			Stepped			Undulating			Planar			Other	V Open	Open	Mod Open	Tight	V Tight	Clean	Staining	% Soil	% Mineral	Clay	X	SI	Mod	High	Comp		
			R	Sm	St	R	Sm	St	R	Sm	St		>10m m	2.5-10	0.5-2.5	0.1-0.5	<0.1												
8.92	45		X												X				X					X				Orange brown Fe staining	
9.20	45								X						X						X		X					Orange brown Fe staining	
9.35	60		X												X				X				X					Orange brown Fe staining, light brown clay smearing	
10.25	5								X						X							X							
10.4 - 11.3	85								X						X				X	X		X						Axial parallel fracture, minor calcite and orange brown clay coating fracture surface	
10.50	5								X						X							X							
11.20	50					X									X				X	X	X							Light grey calcite and minor brown clay coating fracture surface	
11.30	5								X						X							X							
11.90	5		X												X						X		X					Fracture devoped along stylolite, black argillite lining	
11.95	80	X							X						X			X					X					Minor Fe staining	
12.05	15					X									X			X				X							
12.42	10		X												X					X		X						Fracture devoped along stylolite, black argillite lining	
12.60	55								X						X							X							
12.6 - 13.4	85								X						X				X				X					Minor Fe staining	
12.78	0	X							X						X						X	X						Minor light brown clay	
12.84	5	X							X						X						X	X						Minor light brown clay	
13.02	5	X							X						X				X			X							
13.26	5	X							X						X				X			X							
13.52	20								X						X				X			X							
13.82	5								X						X				X			X							
14.39	30								X						X						X	X						Sand/clay coating, minor Fe staining	
14.72	55								X						X				X			X							
15.00	30								X						X				X			X							
15.15	15		X												X						X		X					Fracture devoped along stylolite, black argillite lining	
15.20	85	X				X									X				X			X							
15.33	85	X				X									X				X			X							
15.40	20					X									X						X	X						Minor brown clay	
15.55	10		X												X						X		X					Fracture devoped along stylolite, black argillite lining	
16.59	10					X									X				X			X							
16.86	10								X						X						X		X					Minor light brown clay, some pitting & weak oxidation of fracture surface	
16.90	30								X						X						X		X					Minor light brown clay, some pitting & weak oxidation of fracture surface	

		PROJECT NAME   Lackagh Quarry																			REPORT NO:									
		CLIENT:   Galway County Council																			HOLE NO:		BH-05							
		ENGINEER: ARUP																			LOGGED BY:		Dave Blaney							
Depth of Discontinuity (m BGL)	Orient to Short Core Axis	Non Intact? (NI)	Roughness												Aperture					Filling					Weathering					Comments
			Stepped			Undulating			Planar			Other	V Open	Open	Mod Open	Tight	V Tight	Clean	Staining	% Soil	% Mineral	Clay	X	SI	Mod	High	Comp			
			R	Sm	St	R	Sm	St	R	Sm	St		>10mm	2.5-10	0.5-2.5	0.1-0.5	<0.1													
17.20	10								X							X					X	X						Grey/brown clay coating fract. Surface		
17.25	85	X				X										X					X	X						Minor grey / brown clay		
17.40	45					X										X					X	X						Minor grey/brown clay coating fract. Surface		
17.78	5					X										X					X	X						Undulating - amplitude 2cm, brown clay infill		
18.03	15		X													X					X	X						Minor clay		
18.30	15					X										X				X		X								
18.50	85	X							X							X				X		X						Minor white calcite		
18.60	20								X							X					X	X						Orange/brown clay smeared on fract surface		
18.80	10								X							X					X	X						Orange/brown clay smeared on fract surface		
18.90	85								X							X				X		X						Minor white calcite		
18.97	10					X										X						X								
19.20	20					X										X					X	X						Orange/brown clay infill		
19.60	5								X							X				X		X								
19.98	45	X							X							X					X	X						Orange/brown clay infill, aperture up to 2mm thick		
20.00	45	X							X							X					X	X						Orange/brown clay infill, aperture up to 2mm thick		
20.04	45								X							X						X								
20.12	10								X							X				X		X								
20.60	85								X							X				X		X								
20.60	75					X										X					X	X						Orange/brown clay coating fract. Surface		
20.52	10								X							X				X		X								
20.73	20	X	X													X					X	X						Very rough - Orange/brown clay coating fract. Surface		
20.87	35	X	X													X					X	X						Very rough - Orange/brown clay coating fract. Surface		
20.97	50					X										X					X	X						Orange/brown clay coating fract. Surface		
21.23	55					X										X					X	X						Brown sandy clay coating		
21.35	55					X										X					X	X						Brown sandy clay coating		
21.42	55					X							X								X	X						Joint aperture is >10mm infilled with orange brown clay		
21.86	30	X							X							X				X		X								
21.90	20								X							X				X		X								
22.05	45								X							X				X		X								


		PROJECT NAME   Lackagh Quarry																	REPORT NO:										
		CLIENT:   Galway County Council																	HOLE NO:		BH-05								
		ENGINEER: ARUP																	LOGGED BY:		Dave Blaney								
Depth of Discontinuity (m BGL)	Orient to Short Core Axis	Non Intact? (NI)	Roughness										Aperture					Filling					Weathering					Comments	
			Stepped			Undulating			Planar			Other	V Open	Open	Mod Open	Tight	V Tight	Clean	Staining	% Soil	% Mineral	Clay	X	SI	Mod	High	Comp		
			R	Sm	St	R	Sm	St	R	Sm	St		>10m m	2.5-10	0.5-2.5	0.1-0.5	<0.1												
22.10	5								X						X					X									
22.45	85	X							X						X				X		X								Clay coating fract surface minor Fe staining
22.92	10	X							X						X				X	X									Clay coating fract surface
23.40	70								X						X				X	X									Light brown clay over basal 30cm
23.60	5	X							X						X				X										
23.72	10								X						X				X										Minor light grey calcite
24.40	60								X						X				X										
24.50	0								X						X				X										
25.04	0								X						X				X										
25.52	45								X						X				X										Minor light grey calcite
25.82	25					X									X				X										
26.37	5								X						X				X										
26.61	5								X						X				X										
26.70	80	X							X						X		X		X										Minor Fe staining
27.10	85								X						X				X										Minor white calcite
27.14	20	X	X												X				X										
27.27	55								X						X				X										
27.62	55		X												X				X										
27.88	0								X						X				X										
28.05	5	X							X						X				X										
28.12	60	X							X						X				X										
28.16	5	X					X								X				X										
28.25	90								X						X				X										Minor white calcite veining
28.40	55	X							X						X				X										
28.1 - 32.35	85-90								X						X				X										Axial parallel fracture, surfaces partially coated with white calcite
28.81	15	X							X						X				X										
28.90	20	X							X						X				X										
29.05	30	X							X						X				X										
29.35	10	X							X						X				X										
29.40	60	X							X						X				X										
30.00	5	X							X						X				X										
30.30	40	X							X						X				X										
30.38	10	X					X								X				X										
30.50	10	X							X						X				X										

		PROJECT NAME   Lackagh Quarry																		REPORT NO:									
		CLIENT:   Galway County Council																		HOLE NO:		BH-05							
		ENGINEER: ARUP																		LOGGED BY:		Dave Blaney							
Depth of Discontinuity (m BGL)	Orient.to Short Core Axis	Non Intact? (NI)	Roughness										Aperture					Filling					Weathering					Comments	
			Stepped			Undulating			Planar			Other	V Open	Open	Mod Open	Tight	V Tight	Clean	Staining	% Soil	% Mineral	Clay	X	SI	Mod	High	Comp		
			R	Sm	St	R	Sm	St	R	Sm	St		>10m m	2.5-10	0.5-2.5	0.1-0.5	<0.1												
30.78	10	X							X						X							X							
30.90	35	X							X						X							X							
31.30	50	X							X						X								X						
31.60	70	X							X						X								X						
31.90	45	X							X						X							X							
32.07	35								X						X							X							
32.24	5								X						X							X							
32.85	15								X						X							X							
32.91	20								X						X							X							
33.30	5								X						X							X							
33.55	5								X						X							X							
33.80	5								X						X							X							
33.94	10					X									X							X							
34.55	10								X						X							X							
34.73	45								X						X							X							
34.9 - 37.2	85					X									X				X			X	X						Locally stepped aspect, trace clay coating surfaces, slight Fe staining over top 1.5m
34.90	20								X						X							X							
35.00	45	X							X						X							X							
35.23	20	X		X											X							X							
35.37	10	X							X						X							X							
35.54	15	X							X						X							X							
35.63	10								X						X							X							
35.73	10								X						X							X							
36.10	5	X							X						X					X		X	X						Minor clay, slight Fe Staining
36.40	20	X							X						X							X							
36.47	10								X						X							X							
36.88	45	X							X						X							X							
37.20	30					X									X					X	X								Traces of orange brown clay
38.05	10								X						X					X		X							
37.95 - 40.0	85					X									X				X			X	X						Minor clay smearing surfaces and localised Fe staining
38.64	10	X							X						X							X							
39.64	10	X							X						X							X							
39.75	55	X							X						X							X							
39.90	65	X							X						X							X							


## APPENDIX IV



**Piezometer Installation BH04**



Piezometer Installation BH05



**Piezometer Installation BH06**



## APPENDIX V

**R13/16**

**Report on Geophysical Surveys  
completed at  
Lackagh Quarry  
Co. Galway  
for Arup**

**Graham Reid P.Geo.**

**Project Number:** R13/16  
**Author(s):** Graham Reid P.Geo,  
**BRG Ltd.** Arup  
**Date of Report:** January 2016



**R13/16**

## **Private & Confidential**

**THE DATA PRESENTED IN THIS REPORT WAS ACQUIRED FROM GEOPHYSICAL NON-INVASIVE TECHNIQUES CARRIED OUT AT SURFACE. INTERPRETATIONS ARE DERIVED FROM A COMBINATION OF GROUND CONDITIONS, TYPICAL GEOPHYSICAL RESPONSES AND THE KNOWLEDGE/EXPERIENCE OF THE AUTHOR. BRG LTD HAS COMPILED AND INTERPRETED THE DATA TO BEST INDUSTRY STANDARDS AND WITH ALL REASONABLE SKILL AND DILIGENCE IN RELATION TO THE TECHNIQUES AND RESOURCES APPLIED IN AGREEMENT WITH THE CLIENT. ANY FUTURE USE OF THIS REPORT SHOULD TAKE ITS INTERPRETIVE NATURE INTO CONSIDERATION.**

<b>Report Number</b>	<b>Author</b>	<b>Checked By</b>	<b>Version</b>	<b>Date</b>
R13/16	Graham Reid P. Geo	Dave Blaney P. Geo	V1	18/01/2016
Signed				

**R13/16**  
**Report on Geophysical Surveys at Lackagh, Co. Galway**  
**Graham Reid, January 2016**

**Contents**

1. Executive Summary .....	4
2. Introduction .....	5
2.1 Survey Objectives .....	6
3. Geological setting.....	6
4. Survey Equipment and methodology .....	7
5. Discussion of Results (Figures 3-16).....	7

**List of Figures**

Figure 1: Aerial Photograph Site Location Map .....	5
Figure 2: Location Map.....	6
Figure 3: Resistivity Line Location map.....	10
Figure 4: ERT1 - Section & Interpretation .....	11
Figure 5: ERT2 - Section & Interpretation .....	12
Figure 6: ERT3 - Section & Interpretation .....	13
Figure 7: ERT4 - Section & Interpretation .....	14
Figure 8: ERT5 - Section & Interpretation .....	15
Figure 9: ERT6 - Section & Interpretation .....	16
Figure 10: ERT7 - Section & Interpretation .....	17
Figure 11: ERT8 - Section & Interpretation .....	18
Figure 12: ERT9 - Section & Interpretation .....	19
Figure 13: ERT10 - Section & Interpretation .....	20
Figure 14: Microgravity Line Location Map .....	21
Figure 15: Microgravity Bouguer Gravity Map .....	22
Figure 16: Geophysical Interpretation Map .....	23

## **1. Executive Summary**

BRG Ltd completed geophysical surveys in an area to the west of the abandoned Lackagh Quarry, Menlo, Co. Galway as part of the Priority Drilling Ltd preliminary site investigation for the proposed new road alignment through this area. The geophysical surveys consisted of 2D Electrical Resistivity Tomography (ERT) and Microgravity across an initial area of roughly 300\*30m, subsequently extended to better define the extent of a deep weathering/karst zone.

The surveys were designed to test for subsurface details and bedrock depths in advance of follow up rotary core drilling. Information on potential karst features were of particular interest to the client. The bedrock exposed in the quarry and outcropping to the west consists of strong, thickly bedded Visean limestones dipping gently to the south-west. A thin Tuff band is reputed to control a local aquifer, with more thinly bedded limestones and thin shaley bands developed beneath.

Outcrop to the west of the quarry consists of well-developed limestone pavement extending c,80-100m to the west, which gives way to grass fields across the remainder of the survey area.

Resistivity sections from the 2D ERT and gravity data show a marked contrast from high resistivity bedrock in the east with a sharp contact into very low resistivity zones to the west. The western region has a low gravity response coincident with the low resistivity. The base of the initial ERT lines did not penetrate below 30m in the west suggesting that this area could be a deep overburden/weathered zone, possibly a karst filled sinkhole or more shaley unit.


The work was completed over three separate periods:

- 6 day period from 27<sup>th</sup> October to 3<sup>rd</sup> November 2015.
- 1 day, 25<sup>th</sup> November
- 3 days, 13-15<sup>th</sup> January


## 2. Introduction

BRG was hired by Priority drilling Ltd. to acquire 2D ERT and microgravity data along a planned potential route for the new Galway ring road located to the west of Lackagh Quarry.

The Quarry is located to the north of Galway city with easy access off the Coolagh Road. The quarry is abandoned and fenced off and site access was organised through Sean Ross of Arup. The work was completed mainly across fields and limestone pavement to the west of the quarry and outside the quarry footprint. A rough track running from inside the quarry bounds allowing access into the fields. Loose cattle including a bull were running free within the fields and surrounding scrub, however these were fenced out of the fields when ERT lines were being acquired. A minor microgravity grid was also added on the first bench within the quarry over the area where the proposed horizontal borehole was drilled.



**Figure 1:** Aerial Photograph Site Location Map



**Figure 2: Location Map**

## 2.1 Survey Objectives

- 1) Acquire 2D Resistivity and Microgravity data across the specified region within and proximal to the Lackagh Quarry site.
- 2) Generate Maps and sections showing the geophysical characteristics of the site and generate interpretative maps and sections of the overburden/bedrock model over the chosen areas.
- 3) Outline potential areas for future intrusive investigations (in particular to assist with locating follow up rotary drilling)

## 3. Geological setting

The mapped geology from the Geological Survey of Ireland (1:100,000) shows the site to be underlain by undifferentiated Visean limestones / shaley limestones. The rocks are well exposed within the quarry and to the west as outcropping weathered limestone pavement. These limestones are massive, thickly bedded micritic / grainstone units, generally strong and dipping to the southwest. Overburden appears to be mostly clay and gravels and most likely glacially derived soils (the site walk over noted rounded granite boulders scattered across the limestone pavement, these are probably glacial erratics). A pronounced Tuff band clearly exposed in the quarry underlies the massive limestones and is thought to control a local aquifer. It also appears to host minor sulphides (pyrite) with iron staining developed on the surface of the underlying, slightly argillaceous, limestones.

#### **4. Survey Equipment and methodology**

The geophysical surveys were chosen to provide detailed overburden/bedrock profiles along the chosen lines (ERT) and to identify any significant anomalous zones that could be a result of faults/fractures or karst development (ERT and Microgravity).

The depth mapping potential with the ERT is limited by the length of each spread so that individual spreads were capable of surveying to from 22m b.g.l. in Line 5 to a maximum of 60m b.g.l. with Line 6. Equipment consisted of an Allied Associates Tigre system which has the potential for up to 128 electrode takeouts. 2m station spacing was initially used to get the required detail along the chosen lines, with 3m intervals on the long lines (6, 7 & 8). Data was measured using a Wenner array, controlled by an Imager2006 programme with a laptop computer. Saved data was inverted using the Geotomo Res2Dinv programme and exported as an image file displaying a cross section of the inverted Resistivities with elevation data. The resultant resistivity sections were subsequently interpreted and an interpreted geological model developed.

Microgravity data was acquired with measured sites along the centre line and 15m either side of the proposed tunnel section. These lines were measured with nominal station spacing of 10m, with gaps where scrub hawthorn was too thick. Extra stations were measured within the quarry on the first bench at 5-10m intervals. Measurement was taken using a Lacoste & Romberg model G gravity meter. Instrument drift was monitored by returning to a locally established base station at hourly intervals.

Stations were topographically surveyed using a Trimble GeoExplorer 6000 RTK GPS system corrected through phone modem link for both the ERT and the gravity surveys. The drift corrected gravity data was corrected for elevation, latitude, and reduced to Bouguer  $2.67\text{g/cm}^3$  to allow for local average rock densities. It was then gridded and exported for display and interpretation in the MapInfo GIS system.

All points were surveyed in Irish Transverse Mercator (ITM) projection.

#### **5. Discussion of Results (Figures 3-16)**

The 2D ERT data defines a marked contrast between the resistive massive limestones to the east and exposed within the quarry and a narrow, deep, conductive response that was detected to the west. This contact is clearly seen on lines 1 (at station 114) & 2 (station 134) where it is shown as steep westerly dipping feature. Lines 3 & 4 are almost entirely mapping the lower resistivity unit which is greater than 14m deep. This conductive zone could represent a combination of thicker overburden and underlying weathered bedrock. Line 5 was surveyed entirely on the edge of the



outcropping limestone pavement and displays a thin conductive overburden layer over resistive bedrock.

Line 6 was extended N-S perpendicular to the long axis of the fields with the aim of mapping the edges of the deep overburden feature – this line was surveyed while BH3 was still in progress, with the inversion model shows the hole located within a significant deep overburden (low resistivity) feature. The southern contact of the deep overburden feature is mapped as being sub-vertical with the overburden depth increasing from <1.0m to >55.0m within a few meters. The northern side of the deep overburden feature exhibits a steeped nature with a rapid shallowing at station 210 to a depth of c.35m bgl, and the northern edge seen at station 275 where the overburden depth shallows rapidly.

Lines 7 & 8 were surveyed along similar locations to 2 & 1 respectively; however they were surveyed at 3m electrode spacing and extended to the west. Line 7 exhibits a strange higher resistivity shallow zone to the west of station 96 with lower resistivity below – this most likely reflects the line location proximal to the southern contact of the deep overburden feature resulting in the inversion model displaying some “edge” effects.

Lines 9 & 10 were also designed to map the edges of the deep overburden feature, and this has been successfully achieved along the southern contact and only partially successful in the north (where thick hawthorn bush in an environmentally sensitive area restricted access to extend the lines). These lines were surveyed using a 2m electrode spacing.


The microgravity data shows the same general scenario as the resistivity data. Higher density and more coherent limestones in the east give way to a lower density zone to the west with an irregular sinuous contact between the two. Measurements on the bench within the quarry give the same relatively high density limestone situation as seen at the area underlain by limestone pavement. However, the lower gravity readings located in zones along the edges of the quarry faces are interpreted as the effect of terrain factors

The geophysical interpretation (Figure 16) is derived from a combination of both the Microgravity and 2D ERT methods. This outlines the contact zone at about 530,130E between shallow limestones to the east and deeper overburden/weathered zone to the west. The original ERT lines and microgravity provided limited definition of the contact zones and these have been refined by the extended 3m interval lines. The rotary drilling has shown that the ERT models correlate well with the underlying geology. The mapped low resistivity zone closely follows the field outline. Completed drillholes have been located on the model sections, with those annotated as “offset”

projected from up to 10m away onto the sections (N.B. there is some slight discrepancy between the plotted holes and the modelled section inversion as the holes have been extrapolated from up to 10m off line)

The unusual nature of these grass fields and where they sit within the surrounding limestone pavement would also support the possibility that they reflect the surface expression of an infilled topographic feature such as a slot canyon.

# ERT Line Locations



West

# Resistivity – ERT Line 1

2m Electrode Takeouts

East





Figure 4

# Resistivity – ERT Line 2

West

2m Electrode Takeouts

East





Figure 5

# Resistivity – ERT Line 3

2m Electrode Takeouts

SW

NE





Figure 6



# Resistivity – ERT Line 4

2m Electrode Takeouts

SW

NE





Figure 7

# Resistivity – ERT Line 5

2m Electrode Takeouts

SW

NE





Figure 8



# Resistivity – ERT Line 6

3m Electrode Takeouts

S

N





Figure 9

# Resistivity – ERT Line 7

3m Electrode Takeouts

W

E





Figure 10

# Resistivity – ERT Line 8

3m Electrode Takeouts

W

E





Figure 11



# Resistivity – ERT Line 9

2m Electrode Takeouts

S

N





Figure 12

# Resistivity – ERT Line 10

2m Electrode Takeouts

S

N





Figure 13

# Microgravity Station Location Map




Figure 14

# Microgravity Bouguer Gravity Map





Figure 15



# Geophysical Interpretation Map





## APPENDIX VI



## EUROPEAN GEOPHYSICAL SERVICES

**REPORT ON THE  
GEOPHYSICAL LOGGING  
OF TWO BOREHOLES  
AT  
LACKAGH QUARRY**

**Prepared For:**

**Priority Drilling Ltd.**  
Killimor, Ballinasloe,  
Co. Galway, Ireland



**JAN 2016/PRIO1502\_ rpt/IRL**

	Name	Date
Logged by:	Rhys Powell	8/9.12.15
Report by:	Rhys Powell	4.1.16
Checked by:	James Whitford	6.1.15

**European Geophysical Services Ltd**

22 The Stables, Sansaw Business Park, Hadnall, Shrewsbury. SY4 4AS  
Tel: 01939 210710 | Fax: 01939 210532 E-mail: [eurogeophys@europeangeophysical.com](mailto:eurogeophys@europeangeophysical.com) |  
[www.europeangeophysical.com](http://www.europeangeophysical.com)

Registered in England and Wales No. 2962962 | VAT No. GB 648 4148 18

## CONTENTS

1. INTRODUCTION .....	1
2. THE GEOPHYSICAL LOGGING METHODS.....	2
3. SITE DETAILS.....	6
4. PROCESSING AND PRESENTATION OF IMAGER RESULTS .....	7
5. BOREHOLE LOGGING CONSTRAINTS.....	8

## LIST OF FIGURES

---

Figure 3.1	Location map showing Lackagh Quarry highlighted by red square
Figure 3.2	Aerial image showing approximate borehole locations.

---

Appendix 1	Defect Classification
Appendix 2	Geophysical Logs

---

## 1.0 INTRODUCTION

At the request of Priority Drilling Ltd., borehole imaging and geophysical logging was carried out in two boreholes at Lackagh Quarry, Co. Galway, Ireland.

The work was carried out by European Geophysical Services on the 8<sup>th</sup> and 9<sup>th</sup> of December 2015.

The following logs were run:-

BH	Logs	From (m)	To (m)
4	Optical Imager, Acoustic Imager	3.1	34.0
4	Fluid Temperature and Conductivity, Natural Gamma, Caliper	3.1	34.2
4	Impeller Flowmeter	16.0	33.7
4	Focused Resistivity	15.5	34.0
4	Full Wave Sonic	15.5	34.0
4	Pumped Temperature and Conductivity	18.8	34.2

BH	Logs	From (m)	To (m)
5	Optical Imager, Acoustic Imager	1.0	39.9
5	Fluid Temperature and Conductivity, Natural Gamma, Caliper	1.0	40.0
5	Impeller Flowmeter	17.6	40.0
5	Focused Resistivity	17.6	40.0
5	Full Wave Sonic	17.6	40.0
5	Pumped Temperature and Conductivity	24.1	40.0

## **2.0 THE GEOPHYSICAL LOGGING METHODS**

### **The Equipment and Field Procedure**

A fully digital logging system with a 600m capacity motorised winch mounted in a Land Rover was used.

All logging data was recorded digitally for reprocessing and archiving purposes.

With the exception of the fluid logs, all logs were run from the bottom of the boreholes upward.

The optical imager survey was carried out first to avoid the disturbance of the fluid by the geophysical logs which may affect water clarity.

### **Fluid Temperature (T)**

There is a natural geothermal gradient of increasing temperature with depth. This gradient varies with the thermal conductivity of the geological formation and is modified by water flowing in, out or vertically through the borehole.

This log is used to determine any flow pattern within the borehole and to identify flow zones.

Differential logs are produced over a one metre spacing, these are an interpretative aid to detect gradient changes.

### **Fluid Conductivity (EC or EC25)**

The electrical conductivity (EC) of the water is related to its salinity and dissolved solids and is therefore a measure of the quality of the borehole water. The shape of the log trace can indicate zones of inflow.

Using data from the temperature log the electrical conductivity is corrected to 25°C (EC25).

This log is used to identify different zones of water quality.

Differential logs are produced over a one metre spacing, these are an interpretative aid to detect gradient changes.

---

## **2.0 THE GEOPHYSICAL LOGGING METHODS**

### **Optical Borehole Imager (Optical)**

A precision-machined prism and CCD camera assembly permits a high definition video image of the borehole wall to be captured in a variety of horizontal and vertical resolutions. The resulting image is digitised in the sonde for transmission to the surface acquisition system.

The image is then orientated to Magnetic North and displayed as an unwrapped image log. This enables a detailed structural interpretation to be made if required.

For the best results the optical imager should be run above the water level or in clean, clear fluid. The logging tool is centralised during data acquisition by two sets of bow springs. The bow springs are adjusted to a variety of borehole diameters prior to acquisition. The image is recorded on the way down the borehole to limit disturbance to the clarity of the water in the borehole by the logging tool.

Images and associated data are viewed in real time during the data acquisition.

The orientation system employs a flux gate magnetometer and therefore the recorded data within approximately one metre of magnetic steel casing is un-orientated. This is corrected manually during the post-processing stage

### **Acoustic Borehole Imager (Amplitude and Travel Time)**

This tool scans the borehole wall through 360 degrees and records the acoustic reflection of the resulting signal in terms of amplitude and transit time (the travel time from the tool to the borehole wall). This technique requires a fluid filled borehole with a minimum of suspended solids, polymers or muds within the fluid column.

This sensitive technique responds to small diameter changes, rugosity and the acoustic nature of the borehole wall. It is primarily used for detecting fractures and other discontinuities. The resultant images are orientated (to magnetic North) 0° through 90°, 180° and 270° back to 0°.

The logging tool is centralised during data acquisition by two sets of bow springs. The bow springs are adjusted to a variety of borehole diameters prior to acquisition. The image is viewed on the way down the borehole to allow fine tuning of the acquisition parameters. The settings are then adjusted and the image recorded on the way up the borehole which ensures a constant line speed during acquisition.

Images and associated data are viewed in real time during the data acquisition.

The orientation system employs a flux gate magnetometer and therefore the recorded data within approximately one metre of magnetic steel casing is un-orientated. This is corrected manually during the post-processing stage

---

## **2.0 THE GEOPHYSICAL LOGGING METHODS**

### **Impeller Flowmeter (FV)**

This log is used to determine any flow pattern within the borehole and identify flow zones. The tool uses an impeller and is normally run at a constant logging speed against the anticipated flow for the best response. The data is corrected for logging speed and a fluid velocity (FV) log is produced.

### **Caliper (Cal)**

This tool measures the mean diameter of the borehole. It is used to check the integrity of the borehole lining, and where the borehole is unlined to identify zones of washout, breakout or fissures.

### **Natural Gamma (Gam)**

The tool measures the naturally occurring gamma radiation found in rocks and sediments. It is mainly used to detect the clays that contain potassium  $K^{40}$ , though the  $U^{238}$  series of elements and the  $Th^{232}$  series of elements also emit gamma radiation.

The higher the concentration of these clay minerals the greater the responses on the natural gamma log.

### **Focused Resistivity Log (Res Deep and Res Shallow)**

The Focused Resistivity tool uses Guard Electrodes to focus the current into the formation. This gives excellent vertical resolution and good penetration, especially in highly conductive borehole fluids where a Normal Resistivity Sonde would not be as effective.

The tool has two electrode spacing's to allow a deep and shallow depth of investigation.

The response of this log is a function of porosity, type of formation / mineralogy and its pore water quality. These logs aid in the identification of strata and quality of the pore water.

---

## **2.0 THE GEOPHYSICAL LOGGING METHODS**

### **Full Wave Sonic (VDL)**

This tool has been specially designed to provide a full wave form recording of sonic signals and uses fixed spaced transmitter – receivers.

The received signals are digitised at a fast sampling rate with high resolution. Data may be sampled at typically 5cm or 10cm intervals dependant upon resolution required.

The data is processed for P wave velocity (or transit time) and amplitude.

This tool can only be used in fluid filled unlined boreholes.


---



### 3.0 SITE DETAILS

**Site:**  
**Lackagh Quarry**

**Irish Grid Ref:** M 30240 28372



**Figure 3.1** Location map showing location highlighted by red circle.  
© 2014 Ordnance Survey Ireland.



**Figure 3.2** Aerial image showing approximate borehole locations. © Google 2016.

## 4.0 PROCESSING AND PRESENTATION OF RESULTS

Detailed logs of the imager data have been produced at a vertical scale of 1:10. Composite geophysical logs have been produced at 1:50. Full Wave Sonic results are presented separately at 1:50 with Imager, Natural Gamma and Caliper data to aid interpretation.

Constructional details and information on each borehole are given in the headers of each log.

All images have been referenced to Magnetic North.

The borehole's azimuth and tilt are plotted alongside the images.

The image of the borehole wall is presented in an unwrapped form with a horizontal scale marked 0° - North, through 90° - East, 180° - South, 270° - West, back to North.

Structural features and discontinuities have been picked from the images in the form of colour coded sinusoidal projections - see Appendix 1 for details. This 'Discontinuities' log is also presented with a horizontal scale marked 0° - North, through 90° - East, 180° - South, 270° - West, back to North.

Structure picking is not a definitive analysis of all the features within a borehole. Only the discontinuities that have a linear dip and direction are 'picked' and used in the analysis of the discontinuities. Features that do not have a regular sinusoidal shape do not have a linear dip and direction, 'best fit' picking of these features is done if approximately 80% coverage of the sinusoid can be achieved. Below this percentage the inaccuracy of the picking is too great and if included in any structural analysis may adversely skew the results. Vughs, solution holes, and angular break outs are examples of features not picked.

The apparent azimuth and apparent dip (i.e. relative to the borehole's azimuth and tilt) of the discontinuities are calculated using the diameter of the borehole and the geometric parameters of the sinusoids overlaid on the discontinuities. The final processing stage is to correct these apparent values to true azimuth (in relation to Magnetic North) and true dip (from horizontal) by correcting for the borehole's azimuth and tilt.

The final results are presented as a 'tadpole' plot (Discontinuities - True°). The horizontal position of the tadpole's head gives the defect's true dip angle and its tail points in the direction of the defect's azimuth. These logs are presented with a horizontal scale in degrees. By convention the top of the page is North (Magnetic) and the right hand edge of the paper is East.

The true structural data has been presented in digital format as an excel file (xls).

---

## 5.0 BOREHOLE LOGGING CONSTRAINTS

- **Vehicle access restrictions**  
Poor ground conditions, soft ground access to borehole locations
  - **Tool access restrictions**  
None
  - **Borehole conditions / risk to equipment**  
Drill rods left in boreholes prior to logging to prevent collapse. Highly fractured rock below casing in BH4.
  - **Lack of fluid filled column / cloudy fluid**  
Optical and Acoustic run in both boreholes due to cloudy water. Boreholes pumped dry during pumped TC logging, not possible to run pumped flowmeter.
  - **Time constraint**  
None
  - **Borehole construction / casing**  
BH4 not cased deep enough – loose rock below casing. No casing in BH5.
-

## Appendix 1

### Discontinuity Classification.

Discontinuity	Colour	Classification Parameters
Major Fracture or Fissure	Blue	An open break in the formation, that is <b><u>continuous</u></b> across the entire image.
Minor Fracture or Fissure	Turquoise	A thin or closed break in the formation, that is <b><u>continuous or discontinuous</u></b> across the image.
Vein	Green	That may be <b><u>continuous or discontinuous</u></b> across the entire image.
Fabric	Red	Defines a feature generally metamorphic, igneous or sedimentary in origin that may be <b><u>continuous or discontinuous</u></b> across the image, such as bedding and cross-bedding, schistosity or gneissosity.
Intrusions	Purple	Intrusive features such as dykes and sills, generally <b><u>continuous</u></b> across the image
Unknown	Black	Faint features which <b>can not</b> be classified.

**Appendix 2**  
**Geophysical Logs**





EUROPEAN GEOPHYSICAL SERVICES LTD

Client:	Priority Drilling	Log Type: <b>Composite</b>
Borehole:	BH4	


Location: **Lackagh Quarry**      Area: **Co. Galway**      Grid Ref:      Elevation:


Drilled Depth: (m)	35	Date:	8.12.15 / 9.12.15
Logged Depth: (m)	34.1	Recorded By:	Rhys Powell
Logging Datum:	Ground Level	Remarks: Rods pulled immediately before logging.	
Logged Interval: (m)	3.1 - 34.1		
Fluid Level: (m)	14.6 / 15.5		
Ref:			

BOREHOLE RECORD			CASING RECORD			
Bit: (mm)	From: (m)	To: (m)	Type	Size: (mm)	From: (m)	To: (m)
122	0.1	35	Steel	130	0.0	3.1













EUROPEAN GEOPHYSICAL SERVICES LTD

Client:

Priority Drilling

Borehole:

BH4

Log Type:

Image

Location: Lackagh Quarry



Area: Co. Galway


Grid Ref:

Elevation:

Drilled Depth: (m)	35	Date:	8.12.15
Logged Depth: (m)	34.0	Recorded By:	Rhys Powell
Logging Datum:	Ground Level	Remarks: Rods pulled immediately before logging.	
Logged Interval: (m)	3.1 - 34.0		
Fluid Level: (m)	14.6		
Ref:			


BOREHOLE RECORD			CASING RECORD			
Bit: (mm)	From: (m)	To: (m)	Type	Size: (mm)	From: (m)	To: (m)
PQ	0.1	35	Steel	130	0.0	3.1










































EUROPEAN GEOPHYSICAL SERVICES LTD

Client:  
Priority Drilling

Borehole:  
BH4

Log Type:  
Full Wave Sonic

Location: Lackagh Quarry



Area: Co. Galway


Grid Ref:

Elevation:

Drilled Depth: (m)	35	Date:	9.12.15
Logged Depth: (m)	33.5	Recorded By:	Rhys Powell
Logging Datum:	Ground Level	Remarks:	
Logged Interval: (m)	16.0 - 33.5		
Fluid Level: (m)	16.0		
Ref:			

BOREHOLE RECORD			CASING RECORD			
Bit: (mm)	From: (m)	To: (m)	Type	Size: (mm)	From: (m)	To: (m)
122	0.0	35	Steel	130	0.0	3.1









EUROPEAN GEOPHYSICAL SERVICES LTD

Client:	Priority Drilling	Log Type: <b>Composite</b>
Borehole:	BH5	

Location: **Lackagh Quarry**      Area: **Co. Galway**      Grid Ref:      Elevation:


Drilled Depth: (m)	40.3	Date:	8.12.15
Logged Depth: (m)	40.1	Recorded By:	Rhys Powell
Logging Datum:	Ground Level	Remarks:	
Logged Interval: (m)	1.0 - 40.1		
Fluid Level: (m)	17.6		
		Ref:	


BOREHOLE RECORD			CASING RECORD			
Bit: (mm)	From: (m)	To: (m)	Type	Size: (mm)	From: (m)	To: (m)
PQ	0.0	40.3	None			















EUROPEAN GEOPHYSICAL SERVICES LTD


Client:	Priority Drilling	Log Type: <i>Image</i>
Borehole:	BH5	

Location: Lackagh Quarry      Area: Co. Galway      Grid Ref:      Elevation:


Drilled Depth: (m)	40.3	Date:	8.12.15
Logged Depth: (m)	39.9	Recorded By:	Rhys Powell
Logging Datum:	Ground Level	Remarks: Rods pulled immediately before logging.	
Logged Interval: (m)	1.0 - 39.9		
Fluid Level: (m)	17.9		
Ref:			



BOREHOLE RECORD			CASING RECORD			
Bit: (mm)	From: (m)	To: (m)	Type	Size: (mm)	From: (m)	To: (m)
122	0.1	40.3	None			




















































EUROPEAN GEOPHYSICAL SERVICES LTD

Client: **Priority Drilling**

Borehole: **BH5**

Log Type:  
**Full Wave Sonic**

Location: **Lackagh Quarry**



Area: **Co. Galway**


Grid Ref:




Elevation:

Drilled Depth: (m)	40.3	Date:	8.12.15
Logged Depth: (m)	39.2	Recorded By:	Rhys Powell
Logging Datum:	Ground Level	Remarks:	
Logged Interval: (m)	16.9 - 39.2		
Fluid Level: (m)	16.9		
		Ref:	

BOREHOLE RECORD			CASING RECORD			
Bit: (mm)	From: (m)	To: (m)	Type	Size: (mm)	From: (m)	To: (m)
122	0.0	40.3	None			





40.00												

## APPENDIX VII

## 10% Fines

Priority Construction Ltd  
162 Clontarf Road

Date: 29 February 2016  
Test Report Ref: STR 448031

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Ten Per Cent Fines Value (TFV) of aggregate sample 10mm and greater in accordance with **BS 812: Part 111: 1990**.

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	Bulk Sample
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	21/02/2016
Sampling Location:	Unknown
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Aggregate
Target Specification	N/A

#### **RESULTS:**

**Ten per cent fines value (DRY) = 150 kN**

#### **Comments**

Has the "as received material" been altered by crushing in the laboratory: **Yes**

Report to nearest 10kN for forces of 100kN or more report to nearest 5kN for forces less than 100kN.

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

## Aggregate Abrasion Value



Priority Construction Ltd  
162 Clontarf Road

Date: 29 February 2016  
Test Report Ref: STR 448026

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Aggregate Abrasion Value (AAV) of aggregate sample, in accordance with **BS EN 1097-8 : 2009 Annex A**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	Bulk Sample
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	23/02/2016
Sampling Location:	Unknown
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Aggregate
Target Specification:	N/A

#### **RESULTS:**

Aggregate Abrasion Value (Test 1) =	12.1 (three significant figures)
Aggregate Abrasion Value (Test 2) =	12.4 (three significant figures)

Mean Aggregate Abrasion Value =	12 (two significant figures)
---------------------------------	------------------------------

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

## **Aggregate Crushing Value**

Priority Construction Ltd  
162 Clontarf Road

Date: 29 February 2016  
Test Report Ref: STR 448024

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Aggregate Crushing Value (ACV) of aggregate sample, in accordance with **BS 812: Part 110: 1990**.

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	Bulk Sample
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	20/02/2016
Sampling Location:	Unknown
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Aggregate
Target Specification:	N/A

#### **RESULTS:**

**Aggregate Crushing Value (%) = 23 (nearest whole number)**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

## **Aggregate Impact Value**

Priority Construction Ltd  
162 Clontarf Road

Date: 29 February 2016  
Test Report Ref: STR 448025

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Aggregate Impact Value (AIV) of aggregate sample – DRY, in accordance with **BS 812: Part 112: 1990.**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>Bulk Sample</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>21/02/2016</b>
Sampling Location:	<b>Unknown</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Aggregate</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Aggregate Impact Value (DRY) (%) = 17 (nearest whole number)**

#### **Comments**

**If the AIV is greater than 30 then, the results should be treated with caution.**  
No departure from specified procedure.

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

## **Deformability in Uniaxial Compression and Brazil Tests**

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
REP. Of Ireland.  
VAT No: 9D539711

Date: 15<sup>th</sup> February 2016  
Test Report Ref. STR: 443020

Page 1 of 12

## **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** Unconfined compressive strength, elastic moduli & indirect tensile strength by Brazil.

### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. No:	Various
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	8/12/2016
Date of Start of Test.:	15/12/2015
Sampling Location:	Various
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Aggregate Type and Nominal Size:	Core
Target Specification:	N/A

### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The work was carried out by our competent, sub contracted laboratory.

### **RESULTS**

( ) E. R. Goulden  
Technical Manager  
Approved Signatories


( ) E. N. Jones  
Soils Laboratory Manager




(✓) N Dumbarton  
Assistant Laboratory Manager




Test Report Ref. STR: 443020 Page 2 of 12







Test Report Ref. STR: 443020 Page 4 of 12




Test Report Ref. STR: 443020 Page 5 of 12




Test Report Ref. STR: 443020 Page 6 of 12
















Test Report Ref. STR: 443020 Page 9 of 12



Test Report Ref. STR: 443020 Page 10 of 12





Test Report Ref. STR: 443020 Page 11 of 12


<b>BOREHOLE</b> <b>CORE RUN</b> <b>DEPTH</b> <b>SAMPLE DIAMETER</b> mm <b>SAMPLE THICKNESS</b> mm <b>WATER CONTENT</b> % <b>DEGREE OF SATURATION</b> % <b>STRESS RATE</b> kN/s <b>TEST DURATION</b> secs <b>DATE OF TESTING</b> <b>LOAD FRAME USED</b> <b>ORIENTATION OF LOADING</b> <b>TENSILE STRENGTH</b> MPa	<b>BH04</b> <b>48941</b> <b>29.38-29.54</b> <b>82.10</b> <b>38.53</b> <b>0.1</b> <b>N/A</b> <b>1.90</b> <b>16</b> <b>21-Jan-16</b> <b>Impact</b> <b>Diam</b> <b>5.97</b>	<b>SAMPLE FAILURE SHAPE</b> 
<b>BOREHOLE</b> <b>CORE RUN</b> <b>DEPTH</b> <b>SAMPLE DIAMETER</b> mm <b>SAMPLE THICKNESS</b> mm <b>WATER CONTENT</b> % <b>DEGREE OF SATURATION</b> % <b>STRESS RATE</b> kN/s <b>TEST DURATION</b> secs <b>DATE OF TESTING</b> <b>LOAD FRAME USED</b> <b>ORIENTATION OF LOADING</b> <b>TENSILE STRENGTH</b> MPa		<b>SAMPLE FAILURE SHAPE</b> 
<b>BOREHOLE</b> <b>CORE RUN</b> <b>DEPTH</b> <b>SAMPLE DIAMETER</b> mm <b>SAMPLE THICKNESS</b> mm <b>WATER CONTENT</b> % <b>DEGREE OF SATURATION</b> % <b>STRESS RATE</b> kN/s <b>TEST DURATION</b> secs <b>DATE OF TESTING</b> <b>LOAD FRAME USED</b> <b>ORIENTATION OF LOADING</b> <b>TENSILE STRENGTH</b> MPa		<b>SAMPLE FAILURE SHAPE</b> 



Test Report Ref. STR: 443020 Page 12 of 12

BOREHOLE		BH05	<b>SAMPLE FAILURE SHAPE</b> 
CORE RUN		50701	
DEPTH		19.70-19.92	
SAMPLE DIAMETER	mm	82.24	
SAMPLE THICKNESS	mm	41.12	
WATER CONTENT	%	0.2	
DEGREE OF SATURATION	%	N/A	
STRESS RATE	kN/s	0.80	
TEST DURATION	secs	22	
DATE OF TESTING		21-Jan-16	
LOAD FRAME USED		Impact	
ORIENTATION OF LOADING		Diam	
TENSILE STRENGTH	MPa	3.39	

BOREHOLE			<b>SAMPLE FAILURE SHAPE</b> 
CORE RUN			
DEPTH			
SAMPLE DIAMETER	mm		
SAMPLE THICKNESS	mm		
WATER CONTENT	%		
DEGREE OF SATURATION	%		
STRESS RATE	kN/s		
TEST DURATION	secs		
DATE OF TESTING			
LOAD FRAME USED			
ORIENTATION OF LOADING			
TENSILE STRENGTH	MPa		

BOREHOLE			<b>SAMPLE FAILURE SHAPE</b> 
CORE RUN			
DEPTH			
SAMPLE DIAMETER	mm		
SAMPLE THICKNESS	mm		
WATER CONTENT	%		
DEGREE OF SATURATION	%		
STRESS RATE	kN/s		
TEST DURATION	secs		
DATE OF TESTING			
LOAD FRAME USED			
ORIENTATION OF LOADING			
TENSILE STRENGTH	MPa		

Priority Drilling Ltd.  
Killimor  
Ballinasloe  
Co Galway  
Ireland  
8D23036i

Date: 29<sup>th</sup> March 2016  
Test Report Ref. STR: 447866

Page 1 of 12

## **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** Unconfined compressive strength, elastic moduli & indirect tensile strength by Brazil.

### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	Various
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test.:	18/03/2016
Sampling Location:	Various
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Aggregate Type and Nominal Size:	Rock Testing
Target Specification:	N/A

### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The work was carried out by our competent, sub contracted laboratory.

### **RESULTS**


( ) E. R. Goulden  
Technical Manager  
Approved Signatories


( ) E. N. Jones  
Soils Laboratory Manager




(✓) N Dumbarton  
Assistant Laboratory Manager

Test Report Ref. STR: 447866 Page 2 of 12












Test Report Ref. STR: 447866 Page 5 of 12




Test Report Ref. STR: 447866 Page 6 of 12





Test Report Ref. STR: 447866 Page 7 of 12



















Test Report Ref. STR: 447866 Page 12 of 12

BOREHOLE		BH01		<b>SAMPLE FAILURE SHAPE</b> 
CORE RUN		50858		
DEPTH		64.20-64.50		
SAMPLE DIAMETER	mm	60.97		
SAMPLE THICKNESS	mm	30.76		
WATER CONTENT	%	0.3		
DEGREE OF SATURATION	%	N/A		
STRESS RATE	kN/s	1.10		
TEST DURATION	secs	20		
DATE OF TESTING		21-Mar-16		
LOAD FRAME USED		2000kN		
ORIENTATION OF LOADING		Diam		
TENSILE STRENGTH	MPa	7.80		
BOREHOLE		BH01		<b>SAMPLE FAILURE SHAPE</b> 
CORE RUN		50892		
DEPTH		102.90-103.20		
SAMPLE DIAMETER	mm	61.19		
SAMPLE THICKNESS	mm	30.52		
WATER CONTENT	%	0.1		
DEGREE OF SATURATION	%	N/A		
STRESS RATE	kN/s	1.50		
TEST DURATION	secs	24		
DATE OF TESTING		21-Mar-16		
LOAD FRAME USED		2000kN		
ORIENTATION OF LOADING		Diam		
TENSILE STRENGTH	MPa	12.60		
BOREHOLE		BH01		<b>SAMPLE FAILURE SHAPE</b> 
CORE RUN		50948		
DEPTH		180.24-180.50		
SAMPLE DIAMETER	mm	61.51		
SAMPLE THICKNESS	mm	30.46		
WATER CONTENT	%	3.9		
DEGREE OF SATURATION	%	N/A		
STRESS RATE	kN/s	1.7		
TEST DURATION	secs	26		
DATE OF TESTING		21-Mar-16		
LOAD FRAME USED		2000kN		
ORIENTATION OF LOADING		Diam		
TENSILE STRENGTH	MPa	14.60		

## Frost Heave

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 448032

Dublin 3  
Ireland  
VAT No: 9D53971I

Page 1 of 2

Contract: Lackagh Quarry

### LABORATORY TEST REPORT

#### TEST REQUIREMENTS:

To determine the Frost Heave of Unbound Aggregate in accordance with **BS 812: Part 124: 2009 - Annex B (Use of Comparator Specimens)**

#### SAMPLE DETAILS:

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>Bulk Samples</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>24/02/2016</b>
Sampling Location:	<b>Unknown</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Aggregate</b>
Target Specification	<b>SHW Series 800: clause 801.8</b>

#### RESULTS:

Were any unrepresentative lumps present? No

#### Frost Heave Test Result:

Maximum Heave Observed in 96 hours (mm)		
Comparator Specimen 1	11.5	(nearest 0.5mm)
Comparator Specimen 2	12.0	(nearest 0.5mm)
Comparator Specimen 3	12.0	(nearest 0.5mm)
Mean	<b>11.8</b>	(nearest 0.1mm)
Test Specimen 1	3.5	(nearest 0.5mm)
Test Specimen 2	2.0	(nearest 0.5mm)
Test Specimen 3	4.5	(nearest 0.5mm)
<b>Mean Frost Heave</b>	<b>3.3</b>	<b>(nearest 0.1mm)</b>

In accordance with SHW Series 800: clause 801.8 the sample is classified as being  
**Non Frost Susceptible (mean frost heave  $\leq$  15mm)**


Test Report Ref: STR 448032 Page 2 of 2

**RESULTS CONTINUED:**

**Laboratory Dry Density & Water Content Test Result**

Maximum Dry Density	2.18 Mg/m3
Optimum Water Content	6.5 %
Actual Dry Density	2.18 Mg/m3
Actual Water Content	6.5 %

**Particle Size Distribution Test Result**



**Comments**

None

Certificate  
Prepared by:-

Mathew Sayer  
Assistant Laboratory Manager

Approved by: -

Eric Goulden  
Technical Manager

## Los Angeles Coefficient

Priority Construction Ltd  
162 Clontarf Road

Date: 29 February 2016  
Test Report Ref: STR 448029

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Fragmentation of Aggregate - Los Angeles  
Test Method in accordance with **BS EN 1097-2: 2010**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	Bulk Sample
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	21/02/2016
Sampling Location:	Unknown
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Aggregate
Target Specification:	N/A

#### **RESULTS:**

Size fraction from which the test portion was obtained: 14mm to 12.5mm  
12.5mm to 10.0mm

Los Angeles Coefficient (LA) = 28

#### **Comments**

None

Certificate  
Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



## **Magnesium Sulphate Soundness**

Priority Construction Ltd  
162 Clontarf Road

Date: 29 February 2016  
Test Report Ref: STR 448030

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Magnesium Sulfate Value of aggregate sample within the size range 10mm to 14mm in accordance with **BS EN 1367-2 : 2009**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	Bulk Sample
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	26/02/2016
Sampling Location:	Unknown
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Aggregate
Target Specification:	N/A

#### **RESULTS:**

Magnesium Sulfate Value Portion 1 ( $MS_1$ ) =	0.6
Magnesium Sulfate Value Portion 2 ( $MS_2$ ) =	0.3
Mean Magnesium Sulfate Value ( $MS$ ) =	1

#### **Comments**

Proportion by mass of laboratory sample used for the test portion = 5% (nearest 5%)

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

## Moisture Content

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447817

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 48861</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:6.70 Depth Base:6.80</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447830

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 48868</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:13.26 Depth Base:13.35</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.6**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447843

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 48881</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:32.65 Depth Base:32.72</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.4**

#### **Comments**

None


Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447861

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 48897</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:57.30 Depth Base:57.40</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.1**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447862

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 48898</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:61.65 Depth Base:61.75</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447873

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50865</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:67.07 Depth Base:67.20</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.1**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447876

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50868</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:70.10 Depth Base:70.20</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.3**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447878

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50870</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:73.03 Depth Base:73.10</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.6**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447879

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50871</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:76.00 Depth Base:76.09</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447883

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50875</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:80.04 Depth Base:80.12</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447884

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50876</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:81.70 Depth Base:81.78</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.6**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447885

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50877</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:87.50 Depth Base:87.57</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.8**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447886

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50878</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:39.70 Depth Base:39.80</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.3**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447890

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50882</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:91.63 Depth Base:91.71</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.8**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447894

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50886</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:93.00 Depth Base:93.10</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.5**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447897

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50889</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:94.96 Depth Base:95.05</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.3**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447899

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50891</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:101.36 Depth Base:101.45</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.6**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447904

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50896</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:108.62 Depth Base:108.70</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447908

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50900</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:113.12 Depth Base:113.19</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.5**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447912

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50904</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:118.82 Depth Base:118.88</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.9**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447908

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50900</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:113.12 Depth Base:113.19</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.5**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447912

Dublin 3

Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50904</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:118.82 Depth Base:118.88</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.9**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447913

Dublin 3

Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50905</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:123.44 Depth Base:123.55</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 2.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447914

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50906</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:125.90 Depth Base:126.00</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.3**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447915

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50907</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:126.80 Depth Base:126.90</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 2.5**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447919

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50911</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:131.12 Depth Base:131.17</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 2.6**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447920

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50912</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:131.60 Depth Base:131.70</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447921

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50913</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:132.65 Depth Base:132.62</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.8**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447925

Dublin 3

Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50917</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:134.35 Depth Base:134.44</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.1**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447930

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50922</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:142.81 Depth Base:142.91</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.3**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447940

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50931</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:154.60 Depth Base:154.68</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.4**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447941

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50932</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:155.20 Depth Base:155.28</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.7**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447945

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50936</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:163.49 Depth Base:163.56</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 2.5**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447949

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50940</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:172.96 Depth Base:173.07</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.3**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447949

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50940</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:172.96 Depth Base:173.07</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.3**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447957

Dublin 3

Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50947</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:176.00 Depth Base:176.10</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447964

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50954</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:196.19 Depth Base:186.25</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.8**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447975

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50965</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:209.65 Depth Base:209.72</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.7**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447979

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50969</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:211.10 Depth Base:211.20</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.4**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447985

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50975</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:218.20 Depth Base:218.28</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.5**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447986

Dublin 3

Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50976</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:222.52 Depth Base:222.62</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.0**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447994

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50984</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:230.13 Depth Base:230.20</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 2.0**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 24 February 2016  
Test Report Ref: STR 447999

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50989</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:235.04 Depth Base:235.10</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.3**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 February 2016  
Test Report Ref: STR 443012

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH04 - 48901</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 3.5 Depth Base: 3.55</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443013

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

**LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

**SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. No:	BH04 - 48902
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	15/12/2015
Sampling Location:	Depth Top: 5.4 Depth Base: 5.48
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

**RESULTS:**

**Water Content (%) = 0.6**

**Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443016

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH04 - 48904</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 9.3 Depth Base: 9.36</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.3**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443018

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH04 - 48906</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 11.77 Depth Base: 11.83</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 21 December 2015  
Test Report Ref: STR 443020

Dublin 3  
Ireland

VAT No: 9D53971I

Page 1 of 2

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Uniaxial Compressive Strength in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. :	Various
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	08/12/2015
Sampling Location:	Various
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See attached

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Test Report Ref: STR 443020 - Page 2 of 2

BH	Core Diameter (mm)	Height/ Diameter Ratio	Uniaxial compressive strength (MPa)	Mode of Failure	EN ISO 14689-1 Term	Water content (%)
BH04 48908	82	2.6:1	76	N	Strong	0.1
BH04 48912	82.3	1.9:1	86	N	Strong	0.3
BH04 48921	82.3	1.5:1	55	N	Strong	0.1
BH04 48927	82.1	1.6:1	53	N	Strong	0.2
BH04 48931	82.2	2.6:1	111	N	Very Strong	0.1
BH04 48933	82	2.1:1	91	N	Strong	0.2
BH04 48950	82	2.5:1	76	N	Strong	0.2
BH04 48957	82	2:1	78	N	Strong	0.3
BH04 48963	82.2	2.4:1	92	N	Strong	0.1
BH05 48982	82	1.8:1	91	N	Strong	0.2
BH05 48986	81.5	2.6:1	86	N	Strong	0.4
BH05 48991	81.4	2.5:1	94	N	Strong	0.1
BH05 48994	82	1.9:1	72	N	Strong	0.2
BH05 48998	82.2	2.6:1	77	N	Strong	0.2
BH05 50711	78.5	1.8:1	79	N	Strong	0.2
BH05 50729	79	2.5:1	116	N	Very Strong	0.3
BH05 50731	81.4	2.6:1	51	N	Strong	0.1
BH05 50733	81.6	2.1:1	54	N	Strong	0.2
BH05 50737	82	1.5:1	131	N	Very Strong	0.2

### Comments

- 1) The uniaxial compressive strength was carried out in accordance with ISRM guidelines.
- 2) Stress Rate: 0.7Mpa/s.

3)

EN ISO 14689-1 : 2003 Rock Strength Terms	
Compressive Strength mpa	Term
<1.0	Extremely Weak
1 to 5	Very Weak
5 to 25	Weak
25 to 50	Meduim Strong
50 to 100	Strong
100 to 250	Very Strong
> 250	Extremely Strong

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443034

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH04 - 48922</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 20.8 Depth Base: 20.85</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.4**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443036

Dublin 3

Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH04 - 48924</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 21.8 Depth Base: 21.9</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 1.0**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443050

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH04 - 48938</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 28.27 Depth Base: 38.4</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.1**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443067

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Total Sulfur Content of an Aggregate Sample  
in accordance with **BS EN 1744-1 : 2009 : Clause 11**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. No:	BH04 - 48954
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	21/12/2015
Sampling Location:	Depth Top: 31.66 Depth Base: 31.7
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

<b>Total Sulfur Content as S (%) =</b>	<b>&lt;0.1</b>
<i>95% Confidence limit*</i>	<i>&lt;0.06% - &lt;0.14%</i>

#### **Comments / Departure from specified Procedure**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443069

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Oxidisable sulphides (OS) content of an Sample  
by calculation of **TRL Report 447 Test No. 2 and Test No. 4**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. :	<b>BH04 - 48956</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>24/12/2015</b>
Sampling Location:	<b>Depth Top: 31.84 Depth Base: 31.93</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>&lt;0.5 % SO<sub>4</sub> - If deposited within 500mm of Cementitious Materials</b> <b>&lt;0.06 % SO<sub>4</sub> - If deposited within 500mm of Metallic Structural Elements</b>

#### **RESULTS:**

**Oxidisable Sulphides (OS) (%) = 0.04 SO<sub>4</sub>**

#### **Comments**

The work was carried out by our accredited, competent, sub contracted laboratory.

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443072

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the pH Value of Soils in accordance with  
**BS 1377:Part 3:1990 - Clause 9, Electrometric Method.**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. No:	BH04 - 48959
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	22/12/2015
Sampling Location:	Depth Top: 32.26 Depth Base: 32.35
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

<b>pH Value =</b>	<b>9.3</b>
<i>95% Confidence limit*</i>	<i>9.06% - 9.54%</i>

#### **Comments**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2


Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443081

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH04 - 48965</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 33.12 Depth Base: 33.16</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.1**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443085

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH04 - 48969</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 34.56 Depth Base: 34.59</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.3**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443086

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH04 - 48970</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 34.96 Depth Base: 35</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443087

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH05 - 48971</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 0.65 Depth Base: 0.73</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.3**

#### **Comments**

None


Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443088

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH05 - 48972</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 0.98 Depth Base: 1.04</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.1**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443089

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH05 - 48973</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 1.41 Depth Base: 1.5</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.1**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443096

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH05 - 48980</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 8.9 Depth Base: 8.96</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.1**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443104

Dublin 3  
Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH05 - 48988</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 12.92 Depth Base: 13.07</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.3**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443128

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH05 - 50712</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 28.75 Depth Base: 28.85</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.1**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443132

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Oxidisable sulphides (OS) content of an Sample by calculation of **TRL Report 447 Test No. 2 and Test No. 4**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. :	BH05 - 50716
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	24/12/2015
Sampling Location:	Depth Top: 29.18 Depth Base: 29.3
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	<0.5 % SO <sub>4</sub> - If deposited within 500mm of Cementitious Materials <0.06 % SO <sub>4</sub> - If deposited within 500mm of Metallic Structural Elements

#### **RESULTS:**

**Oxidisable Sulphides (OS) (%) =** <0.01 SO<sub>4</sub>

#### **Comments**

The work was carried out by our accredited, competent, sub contracted laboratory.

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443133

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the pH Value of Soils in accordance with  
**BS 1377:Part 3:1990 - Clause 9, Electrometric Method.**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. No:	BH05 - 50717
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	22/12/2015
Sampling Location:	Depth Top: 29.3 Depth Base: 29.4
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

<b>pH Value =</b>	<b>9.2</b>
<i>95% Confidence limit*</i>	<i>8.96% - 9.44%</i>

#### **Comments**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443134

Dublin 3

Ireland

VAT No: 9D539711

Page 1 of 1

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH05 - 50718</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 30.3 Depth Base: 30.4</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.4**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443137

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

**LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

**SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. No:	BH05 - 50721
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	15/12/2015
Sampling Location:	Depth Top: 30.88 Depth Base: 30.92
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

**RESULTS:**

**Water Content (%) = 0.3**

**Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443142

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS** To determine the Water Content of aggregates by – drying in a ventilated oven according to **BS EN 1097-5: 2008**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH05 - 50726</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 32.54 Depth Base: 32.6</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Water Content (%) = 0.2**

#### **Comments**

None

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



## **Oxidisable Sulphur**

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447856

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Oxidisable sulphides (OS) content of an Sample  
by calculation of **TRL Report 447 Test No. 2 and Test No. 4**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. :	<b>BH01 - 48892</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:55.30 Depth Base:55.40</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>&lt;0.5 % SO<sub>4</sub> - If deposited within 500mm of Cementitious Materials</b> <b>&lt;0.06 % SO<sub>4</sub> - If deposited within 500mm of Metallic Structural Elements</b>

#### **RESULTS:**

**Oxidisable Sulphides (OS) (%) =** **<0.01 SO<sub>4</sub>**

#### **Comments**

The work was carried out by our accredited, competent, sub contracted laboratory.

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447895

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Oxidisable sulphides (OS) content of an Sample by calculation of **TRL Report 447 Test No. 2 and Test No. 4**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. :	<b>BH01 - 50887</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:94.90 Depth Base:94.96</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>&lt;0.5 % SO<sub>4</sub> - If deposited within 500mm of Cementitious Materials</b> <b>&lt;0.06 % SO<sub>4</sub> - If deposited within 500mm of Metallic Structural Elements</b>

#### **RESULTS:**

**Oxidisable Sulphides (OS) (%) =** **<0.01 SO<sub>4</sub>**

#### **Comments**

The work was carried out by our accredited, competent, sub contracted laboratory.

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447938

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Oxidisable sulphides (OS) content of an Sample  
by calculation of **TRL Report 447 Test No. 2 and Test No. 4**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. :	<b>BH01 - 50930</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:153.20 Depth Base:153.30</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>&lt;0.5 % SO<sub>4</sub> - If deposited within 500mm of Cementitious Materials</b> <b>&lt;0.06 % SO<sub>4</sub> - If deposited within 500mm of Metallic Structural Elements</b>

#### **RESULTS:**

**Oxidisable Sulphides (OS) (%) =** **<0.01 SO<sub>4</sub>**

#### **Comments**

The work was carried out by our accredited, competent, sub contracted laboratory.


Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447971

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Oxidisable sulphides (OS) content of an Sample  
by calculation of **TRL Report 447 Test No. 2 and Test No. 4**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. :	<b>BH01 - 50961</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:201.47 Depth Base:201.55</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>&lt;0.5 % SO<sub>4</sub> - If deposited within 500mm of Cementitious Materials</b> <b>&lt;0.06 % SO<sub>4</sub> - If deposited within 500mm of Metallic Structural Elements</b>

#### **RESULTS:**

**Oxidisable Sulphides (OS) (%) =** **<0.01 SO<sub>4</sub>**

#### **Comments**

The work was carried out by our accredited, competent, sub contracted laboratory.

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 448010

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Oxidisable sulphides (OS) content of an Sample  
by calculation of **TRL Report 447 Test No. 2 and Test No. 4**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. :	<b>BH01 - 51000</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>17/02/2016</b>
Sampling Location:	<b>Depth Top:253.30 Depth Base:253.38</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>&lt;0.5 % SO<sub>4</sub> - If deposited within 500mm of Cementitious Materials</b> <b>&lt;0.06 % SO<sub>4</sub> - If deposited within 500mm of Metallic Structural Elements</b>

#### **RESULTS:**

**Oxidisable Sulphides (OS) (%) =** **<0.01 SO<sub>4</sub>**

#### **Comments**

The work was carried out by our accredited, competent, sub contracted laboratory.

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443069

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Oxidisable sulphides (OS) content of an Sample  
by calculation of **TRL Report 447 Test No. 2 and Test No. 4**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. :	<b>BH04 - 48956</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>24/12/2015</b>
Sampling Location:	<b>Depth Top: 31.84 Depth Base: 31.93</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>&lt;0.5 % SO<sub>4</sub> - If deposited within 500mm of Cementitious Materials</b> <b>&lt;0.06 % SO<sub>4</sub> - If deposited within 500mm of Metallic Structural Elements</b>

#### **RESULTS:**

**Oxidisable Sulphides (OS) (%) = 0.04 SO<sub>4</sub>**

#### **Comments**

The work was carried out by our accredited, competent, sub contracted laboratory.

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443132

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Oxidisable sulphides (OS) content of an Sample by calculation of **TRL Report 447 Test No. 2 and Test No. 4**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. :	BH05 - 50716
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	24/12/2015
Sampling Location:	Depth Top: 29.18 Depth Base: 29.3
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	<0.5 % SO <sub>4</sub> - If deposited within 500mm of Cementitious Materials <0.06 % SO <sub>4</sub> - If deposited within 500mm of Metallic Structural Elements

#### **RESULTS:**

**Oxidisable Sulphides (OS) (%) =** <0.01 SO<sub>4</sub>

#### **Comments**

The work was carried out by our accredited, competent, sub contracted laboratory.

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



## pH Value

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447857

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the pH Value of Soils in accordance with  
**BS 1377:Part 3:1990 - Clause 9, Electrometric Method.**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	BH01 - 48893
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	09/02/2016
Sampling Location:	Depth Top:55.84 Depth Base:55.92
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

<b>pH Value =</b>	<b>9.1</b>
<i>95% Confidence limit*</i>	<i>8.86% - 9.34%</i>

#### **Comments**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447896

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the pH Value of Soils in accordance with  
**BS 1377:Part 3:1990 - Clause 9, Electrometric Method.**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	BH01 - 50888
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	09/02/2016
Sampling Location:	Depth Top:94.96 Depth Base:95.05
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

<b>pH Value =</b>	<b>9.2</b>
<i>95% Confidence limit*</i>	<i>8.96% - 9.44%</i>

#### **Comments**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447928

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the pH Value of Soils in accordance with  
**BS 1377:Part 3:1990 - Clause 9, Electrometric Method.**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	BH01 - 50920
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	09/02/2016
Sampling Location:	Depth Top:138.60 Depth Base:138.72
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

<b>pH Value =</b>	<b>9.2</b>
<i>95% Confidence limit*</i>	<i>8.96% - 9.44%</i>

#### **Comments**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2


Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447959

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the pH Value of Soils in accordance with  
**BS 1377:Part 3:1990 - Clause 9, Electrometric Method.**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	BH01 - 50949
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	09/02/2016
Sampling Location:	Depth Top:182.12 Depth Base:182.20
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

<b>pH Value =</b>	<b>9.3</b>
<i>95% Confidence limit*</i>	<i>9.06% - 9.54%</i>

#### **Comments**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447984

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the pH Value of Soils in accordance with  
**BS 1377:Part 3:1990 - Clause 9, Electrometric Method.**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	BH01 - 50974
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	09/02/2016
Sampling Location:	Depth Top:213.80 Depth Base:213.90
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

<b>pH Value =</b>	<b>9.1</b>
<i>95% Confidence limit*</i>	<i>8.86% - 9.34%</i>

#### **Comments**


\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate  
Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443072

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the pH Value of Soils in accordance with  
**BS 1377:Part 3:1990 - Clause 9, Electrometric Method.**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. No:	BH04 - 48959
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	22/12/2015
Sampling Location:	Depth Top: 32.26 Depth Base: 32.35
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

<b>pH Value =</b>	<b>9.3</b>
<i>95% Confidence limit*</i>	<i>9.06% - 9.54%</i>

#### **Comments**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443133

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the pH Value of Soils in accordance with  
**BS 1377:Part 3:1990 - Clause 9, Electrometric Method.**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. No:	BH05 - 50717
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	22/12/2015
Sampling Location:	Depth Top: 29.3 Depth Base: 29.4
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

<b>pH Value =</b>	<b>9.2</b>
<i>95% Confidence limit*</i>	<i>8.96% - 9.44%</i>

#### **Comments**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



## Point Load Testing

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443019

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48907
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 12.62 Depth Base: 12.75
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443019 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48907												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	112	20.0	8960	11408	1.75	1.41	2.47	59.2	
2													
3													
4													
5													
6													
7													
8													
9													
10													
			</										

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443021

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48909
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 13.1 Depth Base: 13.25
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443021 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH04 48909											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	130	20.0	10400	13242	1.51	1.46	2.20	52.7
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	52.7

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443023

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48911
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 14.63 Depth Base: 14.74
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443023 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH04 48911											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	105	15.8	8400	10695	1.48	1.39	2.05	49.2
2												
3												
4												
5												
6												
7												
8												
9												
10												

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443025

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48913
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 14.97 Depth Base: 15.13
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443025 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48913												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	125	22.1	10000	12732	1.74	1.44	2.50	60.1	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	60.1	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443027

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48915
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 17.74 Depth Base: 17.86
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443027 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48915												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	135	23.5	10800	13751	1.71	1.47	2.51	60.2	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	60.2	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443029

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48917
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 18.12 Depth Base: 18.2
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443029 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48917												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	85	15.4	6800	8658	1.78	1.32	2.35	56.5	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	56.5	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443030

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56158</b>
Client Ref. No.:	<b>BH04 - 48918</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>08/12/2015</b>
Date of Start of Test.:	<b>8/12/2015</b>
Sampling Location:	<b>Depth Top: 19.2 Depth Base: 19.32</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443030 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48918												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	120	13.0	9600	12223	1.06	1.43	1.52	36.5	
2													
3													
4													
5													
6													
7													
8													
9													
10													
										</			

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443032

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48920
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 20.12 Depth Base: 20.22
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443032 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH04 48920											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	98	22.5	7840	9982	2.25	1.37	3.08	73.9
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	73.9

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443035

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48923
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 21.2 Depth Base: 21.3
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443035 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48923												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	87	19.0	6960	8862	2.14	1.33	2.85	68.4	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	68.4	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443037

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48925
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 22.2 Depth Base: 22.31
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443037 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48925												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	100	27.9	8000	10186	2.74	1.37	3.76	90.2	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	90.2	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443038

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48926
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 22.6 Depth Base: 22.78
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443038 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48926												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	142	24.4	11360	14464	1.69	1.48	2.50	60.1	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	60.1	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443040

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48928
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 23.1 Depth Base: 23.2
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443040 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48928												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	100	20.0	8000	10186	1.96	1.37	2.69	64.6	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	64.6	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443042

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48930
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 23.7 Depth Base: 23.8
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443042 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48930												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	95	23.1	7600	9677	2.39	1.36	3.24	77.7	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	77.7	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443044

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48932
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 24.17 Depth Base: 24.28
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443044 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH04 48932											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	100	22.9	8000	10186	2.25	1.37	3.08	74.0
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	74.0

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443047

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48934
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 25.08 Depth Base: 25.19
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443047 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48934												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	111	26.0	8880	11306	2.30	1.40	3.23	77.5	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	77.5	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443049

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48937
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 27.91 Depth Base: 28
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443049 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48937												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	86	24.6	6880	8760	2.81	1.33	3.72	89.4	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	89.4	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443051

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48939
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 28.4 Depth Base: 28.44
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443051 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48939												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	104	21.8	8320	10593	2.06	1.38	2.85	68.3	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	68.3	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443051

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48939
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 28.4 Depth Base: 28.44
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443051 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48939												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	104	21.8	8320	10593	2.06	1.38	2.85	68.3	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	68.3	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443054

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48943
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 29.86 Depth Base: 29.94
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443054 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH04 48943												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Lump	b		80	40	14.0	3200	4074	3.44	1.12	3.84	92.0	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	92.0	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443062

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48949
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 30.93 Depth Base: 30.03
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443062 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH04 48949											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	85	20.9	6800	8658	2.41	1.32	3.19	76.6
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	76.6

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443064

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48951
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 31.3 Depth Base: 31.4
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443064 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH04 48951											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	112	22.9	8960	11408	2.01	1.41	2.82	67.8
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	67.8

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443068

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48955
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 31.76 Depth Base: 31.84
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443068 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH04 48955											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	90	17.0	7200	9167	1.85	1.34	2.48	59.6
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	59.6

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443071

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48958
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 32.15 Depth Base: 32.26
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443071 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH04 48958											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Lump	b		59	125	16.1	7375	9390	1.71	1.35	2.31	55.4
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	55.4

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443075

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48962
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 32.5 Depth Base: 32.57
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443075 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH04 48962											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Lump	b		68	75	17.2	5100	6494	2.65	1.24	3.28	78.8
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	78.8

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443077

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48964
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 32.85 Depth Base: 32.96
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443077 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH04 48964											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Lump	b		65	90	15.9	5850	7448	2.13	1.28	2.73	65.5
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	65.5

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443083

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH04 - 48967
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 33.48 Depth Base: 33.6
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443083 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH04 48967											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	115	17.2	9200	11714	1.47	1.42	2.08	49.9
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	49.9

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443091

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48975
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 2.8 Depth Base: 2.96
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443091 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 48975												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	170	13.0	13600	17316	0.75	1.55	1.16	27.8	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	27.8	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443093

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48977
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 7.73 Depth Base: 7.84
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443093 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 48977												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	110	21.0	8800	11205	1.87	1.40	2.63	63.0	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	63.0	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443094

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48978
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 8.1 Depth Base: 8.25
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443094 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 48978												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	160	19.5	12800	16297	1.20	1.52	1.82	43.8	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	43.8	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443095

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48979
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 8.54 Depth Base: 8.66
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443095 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH05 48979											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	120	22.1	9600	12223	1.81	1.43	2.58	62.0
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	62.0

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443097

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48981
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 9.46 Depth Base: 9.57
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443097 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 48981												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	100	28.3	8000	10186	2.78	1.37	3.81	91.5	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	91.5	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443099

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48983
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 9.77 Depth Base: 9.92
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443099 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 48983												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	126	20.5	10080	12834	1.60	1.44	2.31	55.4	
2													
3													
4													
5													
6													
7													
8													
9													
10													

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443100

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48984
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 10.2 Depth Base: 10.26
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443100 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH05 48984											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Lump	b		80	48	17.7	3840	4889	3.62	1.16	4.21	101.0
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	101.0

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443101

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48985
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 11.3 Depth Base: 11.45
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443101 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 48985												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	146	17.9	11680	14871	1.20	1.49	1.80	43.1	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	43.1	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443103

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48987
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 11.72 Depth Base: 11.83
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443103 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 48987												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	100	23.9	8000	10186	2.35	1.37	3.22	77.2	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	77.2	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443105

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48989
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 13.5 Depth Base: 13.6
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443105 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 48989												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Lump	b		80	43	22.7	3440	4380	5.18	1.13	5.88	141.1	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	141.1	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443106

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48990
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 13.7 Depth Base: 13.81
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443106 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 48990												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	108	22.1	8640	11001	2.01	1.40	2.80	67.3	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	67.3	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443108

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48992
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 14.07 Depth Base: 14.15
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443108 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH05 48992											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Lump	b		80	70	19.8	5600	7130	2.78	1.27	3.52	84.4
2												
3												
4												
5												
6												
7												
8												
9												
10												
										Mean	84.4	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443109

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48993
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 14.27 Depth Base: 14.4
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443109 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 48993												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	95	22.0	7600	9677	2.27	1.36	3.08	74.0	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	74.0	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443111

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48995
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 15.43 Depth Base: 15.55
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443111 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH05 48995											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	80	21.3	6400	8149	2.61	1.30	3.41	81.8
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	81.8

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443113

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 48997
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 16.45 Depth Base: 16.55
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443113 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH05 48997											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	95	20.0	7600	9677	2.07	1.36	2.80	67.3
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	67.3

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443119

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 50703
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 22.07 Depth Base: 22.21
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443119 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH05 50703											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		80	150	23.0	12000	15279	1.51	1.50	2.26	54.3
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	54.3

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443120

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 50704
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 22.9 Depth Base: 23
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443120 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH05 50704											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Lump	b		80	55	17.0	4400	5602	3.03	1.20	3.64	87.3
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	87.3

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443121

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 50705
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 23.94 Depth Base: 24.05
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443121 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 50705												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	100	20.8	8000	10186	2.04	1.37	2.80	67.2	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	67.2	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443123

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 50707
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 24.73 Depth Base: 24.85
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443123 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 50707												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		75	90	18.0	6750	8594	2.09	1.32	2.77	66.4	
2													
3													
4													
5													
6													
7													
8													
9													
10													

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443125

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 50709
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 26 Depth Base: 26.12
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443125 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 50709												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		75	103	23.0	7725	9836	2.34	1.36	3.18	76.4	
2													
3													
4													
5													
6													
7													
8													
9													
10													
			</										

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443141

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 50725
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 32.44 Depth Base: 32.54
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443141 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 50725												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	80	20.0	6400	8149	2.45	1.30	3.20	76.8	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	76.8	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443143

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 50727
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 32.83 Depth Base: 32.92
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 443143 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56158											
Date Recived	8.12.15											
Sample Ref	BH05 50727											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Lump	b		80	72	16.0	5760	7334	2.18	1.27	2.78	66.7
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	66.7

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443154

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56158</b>
Client Ref. No.:	<b>BH05 - 50736</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>08/12/2015</b>
Date of Start of Test.:	<b>8/12/2015</b>
Sampling Location:	<b>Depth Top: 37.4 Depth Base: 37.5</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443154 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 50736												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	95	24.0	7600	9677	2.48	1.36	3.36	80.7	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	80.7	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 21<sup>st</sup> December 2015  
Test Report Ref.: STR: 443156

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56158
Client Ref. No.:	BH05 - 50738
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	08/12/2015
Date of Start of Test.:	8/12/2015
Sampling Location:	Depth Top: 37.82 Depth Base: 37.92
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 443156 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56158												
Date Recived	8.12.15												
Sample Ref	BH05 50738												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	100	23.9	8000	10186	2.35	1.37	3.22	77.2	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	77.2	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447819

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48862
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:10.36 Depth Base:10.46
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447819 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 48862												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	70	14.9	4200	5348	2.79	1.19	3.31	79.3	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	79.3	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447825

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48864
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:10.69 Depth Base:10.76
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 447825 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 48864											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	60	13.0	3600	4584	2.84	1.15	3.25	78.0
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	78.0

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447831

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48869
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:13.35 Depth Base:13.45
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447831 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 48869											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	85	18.1	5100	6494	2.79	1.24	3.46	82.9
2												
3												
4												
5												
6												
7												
8												
9												
10												
										Mean	82.9	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447833

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48871
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:13.70 Depth Base:13.80
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447833 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 48871											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	90	16.4	5400	6875	2.39	1.26	3.00	71.9
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	71.9

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447834

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56595</b>
Client Ref. No.:	<b>BH01 - 48872</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>18/1/2016</b>
Date of Start of Test.:	<b>18/1/2016</b>
Sampling Location:	<b>Depth Top:16.30 Depth Base:16.40</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447834 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 48872												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	95	16.1	5700	7257	2.22	1.27	2.82	67.7	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	67.7	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447836

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48874
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:16.66 Depth Base:16.80
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 447836- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 48874											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	115	21.1	6900	8785	2.40	1.33	3.19	76.5
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	76.5

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447839

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56595</b>
Client Ref. No.:	<b>BH01 - 48877</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>18/1/2016</b>
Date of Start of Test.:	<b>18/1/2016</b>
Sampling Location:	<b>Depth Top:26.20 Depth Base:26.36</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447839 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 48877												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	165	17.2	9900	12605	1.36	1.44	1.96	47.1	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	47.1	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447841

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48879
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:26.61 Depth Base:26.70
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447841 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 48879												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	85	13.2	5100	6494	2.03	1.24	2.52	60.5	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	60.5	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447844

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48882
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:34.44 Depth Base:34.48
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447844 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 48882											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	d		39	60	10.6	2340	2979	3.56	1.04	3.70	88.8
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	88.8

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447846

Page 1 of 2

Order No:

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

### **SAMPLE DETAILS:**


Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48884
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:34.73 Depth Base: 34.83
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

### **RESULTS:**

See Attached

### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 447846 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 48884												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	95	14.8	5700	7257	2.04	1.27	2.59	62.2	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	62.2	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447848

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48886
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:44.45 Depth Base:44.54
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447848 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 48886												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	75	16.8	4500	5730	2.93	1.21	3.53	84.8	
2													
3													
4													
5													
6													
7													
8													
9													
10													
										Mean	84.8		

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447851

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48888
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:44.79 Depth Base:44.90
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447851- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 48888											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	90	12.1	5400	6875	1.76	1.26	2.21	53.0
2												
3												
4												
5												
6												
7												
8												
9												
10												
										Mean	53.0	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447858

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56595</b>
Client Ref. No.:	<b>BH01 - 48894</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>18/1/2016</b>
Date of Start of Test.:	<b>18/1/2016</b>
Sampling Location:	<b>Depth Top:56.50 Depth Base:56.60</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447858 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 48894											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	70	12.1	4200	5348	2.26	1.19	2.68	64.4
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	64.4

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447860

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48896
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:56.85 Depth Base:56.93
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR :447860 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 48896											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	70	12.0	4200	5348	2.24	1.19	2.66	63.9
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	63.9

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447863

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 48899
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:62.76 Depth Base:62.86
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR :447863- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 48899											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	85	18.2	5100	6494	2.80	1.24	3.47	83.4
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	83.4

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447865

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50857
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:63.05 Depth Base:63.16
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447865 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50857											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	125	14.6	7500	9549	1.53	1.35	2.07	49.6
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	49.6

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447870

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50862
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:66.00 Depth Base:66.10
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447870 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50862											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	80	14.5	4800	6112	2.37	1.22	2.90	69.6
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	69.6

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447872

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50864
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:66.34 Depth Base:66.45
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 447872- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50864											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	105	16.1	6300	8021	2.01	1.30	2.61	62.6
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	62.6

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447880

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56595</b>
Client Ref. No.:	<b>BH01 - 50872</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>18/1/2016</b>
Date of Start of Test.:	<b>18/1/2016</b>
Sampling Location:	<b>Depth Top:79.10 Depth Base:79.18</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR :447880 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50872											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	85	11.3	5100	6494	1.74	1.24	2.16	51.8
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	51.8

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447882

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50874
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:79.40 Depth Base:79.52
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447882 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50874											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	110	12.8	6600	8403	1.52	1.31	2.00	48.0
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	48.0

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447891

Page 1 of 2

Order No:

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50883
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:92.35 Depth Base:92.47
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

### **RESULTS:**

See Attached

### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447891- Page 2 of 2

<b>Client</b>	Priority Construction Ltd											
<b>Sample Number</b>	S56595											
<b>Date Recived</b>	18.1.16											
<b>Sample Ref</b>	BH01 50883											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test 0.3W < D < W							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type	D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*						
<b>Axial, Block or Lump Tests</b>												
1	Core	a	60	85	16.0	5100	6494	2.46	1.24	3.05	73.3	
2												
3												
4												
5												
6												
7												
8												
9												
10												
										Mean	<b>73.3</b>	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447893

Page 1 of 2

Order No:

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50885
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:92.70 Depth Base:92.79
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

### **RESULTS:**

See Attached

### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 447893- Page 2 of 2

[illegible]

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447901

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50893
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:108.15 Depth Base:108.22
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447901- Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50893												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	70	11.5	4200	5348	2.15	1.19	2.55	61.2	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	61.2	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447903

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50895
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:108.51 Depth Base:108.62
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447903 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50895												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	75	13.9	4500	5730	2.43	1.21	2.92	70.2	
2													
3													
4													
5													
6													
7													
8													
9													
10													
				</									

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447909

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50901
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:115.89 Depth Base:116.05
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447909- Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50901												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	110	14.0	6600	8403	1.67	1.31	2.19	52.5	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	52.5	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447911

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50903
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:116.29 Depth Base:116.39
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR :447911- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50903											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	95	14.8	5700	7257	2.04	1.27	2.59	62.2
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	62.2

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447916

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56595</b>
Client Ref. No.:	<b>BH01 - 50908</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>18/1/2016</b>
Date of Start of Test.:	<b>18/1/2016</b>
Sampling Location:	<b>Depth Top:128.80 Depth Base:128.89</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447916- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50908											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	75	16.0	4500	5730	2.79	1.21	3.37	80.8
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	80.8

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447918

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50910
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:129.14 Depth Base:129.21
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447918 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50910											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	60	14.0	3600	4584	3.05	1.15	3.50	84.0
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	84.0

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447922

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50914
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:133.21 Depth Base:133.32
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447922 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50914											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	85	15.1	5100	6494	2.33	1.24	2.88	69.2
2												
3												
4												
5												
6												
7												
8												
9												
10												
										Mean	69.2	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447924

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50916
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:133.54 Depth Base:133.63
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR :447924 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50916											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	85	13.5	5100	6494	2.08	1.24	2.58	61.8
2												
3												
4												
5												
6												
7												
8												
9												
10												
										Mean	61.8	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447931

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50923
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:146.20 Depth Base:146.30
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447931 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50923												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	85	12.0	5100	6494	1.85	1.24	2.29	55.0	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	55.0	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447933

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50925
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:146.52 Depth Base146.61
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447933 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50925												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	95	14.9	5700	7257	2.05	1.27	2.61	62.6	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	62.6	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447942

Page 1 of 2

Order No:

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

### **SAMPLE DETAILS:**


Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50933
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:156.33 Depth Base:156.44
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

### **RESULTS:**

See Attached

### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447942- Page 2 of 2

[illegible]

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447944

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50935
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:156.68 Depth Base:156.76
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 447944- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50935											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
<b>Axial, Block or Lump Tests</b>												
1	Core	a		60	90	10.8	5400	6875	1.57	1.26	1.97	47.3
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	<b>47.3</b>

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447946

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50937
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:165.17 Depth Base:165.25
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447946 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50937											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	75	15.4	4500	5730	2.69	1.21	3.24	77.7
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	77.7

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447948

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50939
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:166.00 Depth Base:166.10
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447948 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50939												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	85	14.1	5100	6494	2.17	1.24	2.69	64.6	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	64.6	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447953

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50944
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:175.18 Depth Base:175.26
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447953 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50944												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	85	12.8	5100	6494	1.97	1.24	2.44	58.6	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	58.6	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447956

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56595</b>
Client Ref. No.:	<b>BH01 - 50946</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>18/1/2016</b>
Date of Start of Test.:	<b>18/1/2016</b>
Sampling Location:	<b>Depth Top:175.50 Depth Base:175.59</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR :447956- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50944											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	85	12.8	5100	6494	1.97	1.24	2.44	58.6
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	58.6

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447961

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56595</b>
Client Ref. No.:	<b>BH01 - 50951</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>18/1/2016</b>
Date of Start of Test.:	<b>18/1/2016</b>
Sampling Location:	<b>Depth Top:183.90 Depth Base:184.20</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447961 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50951											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	110	13.0	6600	8403	1.55	1.31	2.03	48.8
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	48.8

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447963

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56595</b>
Client Ref. No.:	<b>BH01 - 50953</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>18/1/2016</b>
Date of Start of Test.:	<b>18/1/2016</b>
Sampling Location:	<b>Depth Top:184.25 Depth Base:184.34</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR :447963- Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50953												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	90	16.0	5400	6875	2.33	1.26	2.92	70.1	
2													
3													
4													
5													
6													
7													
8													
9													
10													

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447967

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56595</b>
Client Ref. No.:	<b>BH01 - 50957</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>18/1/2016</b>
Date of Start of Test.:	<b>18/1/2016</b>
Sampling Location:	<b>Depth Top:194.60 Depth Base:194.67</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447967 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50957												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	60	8.0	3600	4584	1.75	1.15	2.00	48.0	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	48.0	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447969

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50959
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:194.90 Depth Base:194.99
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 447969 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50959											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	80	12.0	4800	6112	1.96	1.22	2.40	57.6
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	57.6

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447972

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50962
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:204.62 Depth Base:204.70
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447972- Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50962												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	80	17.4	4800	6112	2.85	1.22	3.48	83.6	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	83.6	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 11<sup>th</sup> April 2016  
Test Report Ref.: STR: 447974

Page 1 of 2

Order No:

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

### **SAMPLE DETAILS:**


Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50964
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:204.95 Depth Base:205.02
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

### **RESULTS:**

See Attached

### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447974 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50964												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	85	13.2	5100	6494	2.03	1.24	2.52	60.5	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	60.5	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447980

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56595</b>
Client Ref. No.:	<b>BH01 - 50970</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>18/1/2016</b>
Date of Start of Test.:	<b>18/1/2016</b>
Sampling Location:	<b>Depth Top:211.77 Depth Base:211.85</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447980- Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50970												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	75	11.2	4500	5730	1.95	1.21	2.36	56.5	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	56.5	

Point load test results  
STR : 447982- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50972											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	100	17.0	6000	7639	2.23	1.29	2.86	68.7
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	68.7



Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447982

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50972
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:212.10 Depth Base:212.20
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447989

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50979
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:225.65 Depth Base:225.74
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447989- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50979											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	95	19.1	5700	7257	2.63	1.27	3.34	80.3
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	80.3

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447991

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50981
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:225.95 Depth Base:226.03
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447991 Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50981											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	95	17.2	5700	7257	2.37	1.27	3.01	72.3
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	72.3

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447995

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50985
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:231.65 Depth Base:231.78
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 447994- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50985											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	120	15.1	7200	9167	1.65	1.34	2.21	53.0
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	53.0

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 447997

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50987
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:232.00 Depth Base:232.10
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 447997- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50987											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	70	14.0	4200	5348	2.62	1.19	3.11	74.6
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	74.6

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 448003

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50993
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:242.82 Depth Base:242.92
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 448003- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50993											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	95	12.8	5700	7257	1.76	1.27	2.24	53.8
2												
3												
4												
5												
6												
7												
8												
9												
10												
										Mean	53.8	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 448005

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50995
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:243.14 Depth Base:243.23
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 448005 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50995											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	85	14.1	5100	6494	2.17	1.24	2.69	64.6
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	64.6

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 448007

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50997
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:251.81 Depth Base:251.95
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 448007 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 50997											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	110	14.0	6600	8403	1.67	1.31	2.19	52.5
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	52.5

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 448009

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 50999
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:252.22 Depth Base:252.32
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR : 448009- Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 50999												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	90	14.0	5400	6875	2.04	1.26	2.56	61.4	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	61.4	

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 448011

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 51001
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:259.72 Depth Base:259.82
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 448011- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 51001											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	85	14.0	5100	6494	2.16	1.24	2.67	64.1
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	64.1

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 448013

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 51003
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:260.06 Depth Base:260.18
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR :448013- Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 51003											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	120	12.8	7200	9167	1.40	1.34	1.87	44.9
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	44.9

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 448015

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56595</b>
Client Ref. No.:	<b>BH01 - 51005</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>18/1/2016</b>
Date of Start of Test.:	<b>18/1/2016</b>
Sampling Location:	<b>Depth Top:262.63 Depth Base:262.73</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 448015 - Page 2 of 2

Client	Priority Construction Ltd											
Sample Number	S56595											
Date Recived	18.1.16											
Sample Ref	BH01 51005											
Key : -												
D	Always distance between platen contact points							D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction							P	Load failure in KN			
	ie core diameter for axial tests.							Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.							Is (50)	Point load strength index			
A	W*D minimum x-sectional area							F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$							#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests							//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )
*	*	*	*	*	*	*						
Axial, Block or Lump Tests												
1	Core	a		60	95	16.1	5700	7257	2.22	1.27	2.82	67.7
2												
3												
4												
5												
6												
7												
8												
9												
10												
											Mean	67.7

Priority Construction Ltd  
Killmor  
Ballinasloe  
Co. Galway  
Ireland

Date: 24<sup>th</sup> February 2016  
Test Report Ref.: STR: 448016

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No.:	S56595
Client Ref. No.:	BH01 - 51006
Date and Time of Sampling:	Unknown
Date of Receipt at Lab.:	18/1/2016
Date of Start of Test.:	18/1/2016
Sampling Location:	Depth Top:264.80 Depth Base:164.93
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager



Point load test results  
STR :448016 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S56595												
Date Recived	18.1.16												
Sample Ref	BH01 51006												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	a		60	100	12.0	6000	7639	1.57	1.29	2.02	48.5	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	48.5	

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 15<sup>th</sup> February 2016  
Test Report Ref.: STR: 451474

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Point Load Index of Rock in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**


Certificate of sampling received:	<b>No</b>
Laboratory Ref. No.:	<b>S56158</b>
Client Ref. No.:	<b>BH05 - 50740</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab.:	<b>08/12/2015</b>
Date of Start of Test.:	<b>15/12/2015</b>
Sampling Location:	<b>Depth Top: 37.92 Depth Base: 38.08</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

See Attached

#### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The specimens were perpendicular to the axis of loading with respect to the existing planes of anisotropy.



Nick Dumbarton – Assistant Laboratory Manager

Point load test results  
STR : 451474 - Page 2 of 2

Client	Priority Construction Ltd												
Sample Number	S6158												
Date Recived	8.12.15												
Sample Ref	BH05 50740												
Key : -													
D	Always distance between platen contact points								D*D	= 4A/pi for axial (a) and irregular block (b) tests			
W	Smallest width perpendicular to loading direction								P	Load failure in KN			
	ie core diameter for axial tests.								Is	Uncorrected strength index			
	W =( W1 + W2)/2 for irregular blocks.								Is (50)	Point load strength index			
A	W*D minimum x-sectional area								F	Size correction factor			
	For axial or irregular block test $0.3W < D < W$								#	Test perpendicular to fabric			
D*D	= D*D for diametral (d) tests								//	Test parallel to fabric			
Sample no	Sample type	Test type		D mm	W mm	P KN	A =W*D	D*D	Is	F	Is (50)	Approx. Compressive Strength ( MPa )	
*	*	*	*	*	*	*							
Axial, Block or Lump Tests													
1	Core	d		80	140	21.0	11200	14260	1.47	1.48	2.18	52.3	
2													
3													
4													
5													
6													
7													
8													
9													
10													
											Mean	52.3	

## Porosity / Density Testing

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 22<sup>nd</sup> March 2016  
Test Report No: STR: 443026


Page 1 of 2

### **LABORATORY TEST REPORT**

**REQUIREMENTS:** To determine the Porosity & Density using saturation and calliper in accordance with **ISRM Part 1: Test 2**

### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref.:	<b>Various</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>11/02/2016</b>
Sampling Location:	<b>Various</b>
Name of Supplier:	<b>Lackagh Quarry</b>
Name and Location of Quarry	<b>Unknown</b>
Sampled By:	<b>Client</b>
Method of Sampling:	<b>Rock Testing</b>



Nick Dumbarton – Laboratory Manager

Test Report No: STR 443026 Page 2 of 2

**RESULTS:**

Sample ref:	Porosity (%)	Dry Density of Rock (Kg/m <sup>3</sup> )
BH4 - 48929	0.4	2.69
BH4 - 48936	0.5	2.65
BH5 - 48974	0.4	2.68
BH5 – 50702	0.4	2.69
BH5 – 50730	0.6	2.69

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 22<sup>nd</sup> March 2016  
Test Report No: STR: 443115


Page 1 of 2

### **LABORATORY TEST REPORT**

**REQUIREMENTS:** To determine the Porosity & Density using saturation and buoyancy in accordance with **ISRM Part 1: Test 3**

### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref.:	<b>Various</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>08/12/2015</b>
Date of Start of Test:	<b>11/02/2016</b>
Sampling Location:	<b>Various</b>
Name of Supplier:	<b>Lackagh Quarry</b>
Name and Location of Quarry	<b>Unknown</b>
Sampled By:	<b>Client</b>
Method of Sampling:	<b>Rock Testing</b>



Nick Dumbarton – Laboratory Manager

Test Report No: STR: 443115 Page 2 of 2

**RESULTS:**

Sample ref:	Porosity (%)	Dry Density of Rock (Kg/m <sup>3</sup> )
BH4 - 48914	0.2	2.72
BH4 - 48968	0.4	2.69
BH5 - 48976	0.3	2.65
BH5 - 48999	0.3	2.69
BH5 - 50735	0.4	2.68



Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 17<sup>th</sup> March 2016  
Test Report No: STR: 447826


Page 1 of 2

### **LABORATORY TEST REPORT**

**REQUIREMENTS:** To determine the Porosity & Density using saturation and buoyancy in accordance with **ISRM Part 1: Test 3**

### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref.:	<b>Various</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/1/2016</b>
Date of Start of Test:	<b>21/2/2016</b>
Sampling Location:	<b>Various</b>
Name of Supplier:	<b>Lackagh Quarry</b>
Name and Location of Quarry	<b>Unknown</b>
Sampled By:	<b>Client</b>
Method of Sampling:	<b>Rock Testing</b>



Nick Dumbarton – Laboratory Manager

Test Report No: STR: 447826 Page 1 of 2

**RESULTS:**

Sample ref:	Porosity (%)	Dry Density of Rock (Kg/m <sup>3</sup> )
BH01 - 48865	0.5	2.63
BH01 - 48876	1.2	2.70
BH01 - 48889	0.5	2.68
BH01 - 50860	0.2	2.72
BH01 - 50867	0.2	2.63
BH01 - 50881	1.0	2.70
BH01 - 50898	0.7	2.59
BH01 - 50919	0.3	2.63
BH01 - 50928	0.7	2.67
BH01 - 50942	0.4	2.72
BH01 - 50960	0.5	2.71
BH01 - 50967	0.3	2.85
BH01 - 50978	0.3	2.63
BH01 - 50983	0.4	2.65
BH01 - 51009	0.5	2.64

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D53971I

Date: 17<sup>th</sup> March 2016  
Test Report No: STR: 447828


Page 1 of 2

### **LABORATORY TEST REPORT**

**REQUIREMENTS:** To determine the Porosity & Density using saturation and calliper in accordance with **ISRM Part 1: Test 2**

### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref.:	<b>Various</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>21/02/2016</b>
Sampling Location:	<b>Various</b>
Name of Supplier:	<b>Lackagh Quarry</b>
Name and Location of Quarry	<b>Unknown</b>
Sampled By:	<b>Client</b>
Method of Sampling:	<b>Rock Testing</b>



Nick Dumbarton – Laboratory Manager

Test Report No: STR: 447828 Page 1 of 2

**RESULTS:**

Sample ref:	Porosity (%)	Dry Density of Rock (Kg/m <sup>3</sup> )
BH01 - 48866	0.47	2.69
BH01 - 48875	0.58	2.65
BH01 - 48885	0.54	2.70
BH01 - 50861	0.64	2.69
BH01 - 50866	0.57	2.71
BH01 - 50880	0.49	2.71
BH01 - 50897	0.57	2.69
BH01 - 50918	0.76	2.81
BH01 - 50927	0.61	2.75
BH01 - 50941	0.49	2.68
BH01 - 50956	0.54	2.69
BH01 - 50966	0.65	2.69
BH01 - 50977	0.56	2.75
BH01 - 50982	0.64	2.70
BH01 - 51008	0.63	2.65

## Polish Stone Value

Priority Construction Ltd  
162 Clontarf Road

Date: 01 March 2016  
Test Report Ref: STR 448027

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### LABORATORY TEST REPORT

#### TEST REQUIREMENTS:

To determine the Polished Stone Value (PSV) of aggregate sample in accordance with **BS EN 1097-8 : 2009**

#### SAMPLE DETAILS:

Certificate of sampling received:	<b>No</b>	Name of Source:	<b>Lackagh Quarry</b>
Laboratory Ref. No:	<b>S56595</b>	Method of Sampling:	<b>Unknown</b>
Client Ref. No:	<b>Bulk Sample</b>	Sampled By:	<b>Client</b>
Date and Time of Sampling:	<b>Unknown</b>		
Date of Receipt at Lab:	<b>18/01/2016</b>		
Date of Start of Test:	<b>23/02/2016</b>		
Sampling Location:	<b>Unknown</b>		
Material Description:	<b>Aggregate</b>		

#### RESULTS:

Recorded Polished Stone Value

Test Specimen	Test Run 1	(i)	35.3	Mean Recorded Value (S) = <b>35.8</b>
		(ii)	35.7	
	Test Run 2	(iii)	35.0	
		(iv)	37.0	


Control Stone	Test Run 1	(i)	47.7	Mean Recorded Value (C) = <b>47.2</b>
		(ii)	47.3	
	Test Run 2	(iii)	47.0	
		(iv)	46.7	

Corrected Polished Stone Value:  $S + 49^* - C =$  **38**

#### Comments

\*New Control Stone

Certificate  
Prepared by:-

  
Mathew Sayer  
Assistant Laboratory Manager

Approved by: -

  
Eric Goulden  
Technical Manager

## Slake Durability

Priority Construction Ltd  
162 Clontarf Road

Date: 29 February 2016  
Test Report Ref: STR 448028

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Slake Durability Index of an aggregate sample in accordance with **ISRM guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. :	<b>Bulk Sample</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test:	<b>18/02/2016</b>
Sampling Location:	<b>Unknown</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Aggregate</b>
Target Specification:	<b>N/A</b>

#### **RESULTS:**

**Slake Durability Index = 99.4 %**

#### **Comments**

None

Certificate  
Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



## Soil Testing



# Natural Moisture Content/Atterberg Limits Summary

Job Ref

BS 1377 : Part 2 : 1990 : Clause 3

Location

Galway PDL

P16005

Hole ID	Sample Ref	Depth (m)	Sample Type	Sample Description	MC	LL	PL	PI	% Pass 425
BH03		13.65	B		26				
BH03		13.73	B			34	NP	NP	100
BH03		19.1	B			29	NP	NP	100
BH03		19.25	B		30				
BH03		19.9	B		30				
BH03		21.3	B		30				
BH03		27.45	B			28	NP	NP	100
BH03		31.2	B		25				
BH03		33.95	B		27				
BH03		38.6	B		36				
BH03		39.25	B			56	44	12	100
BH03		39.8	B		38				
BH03		40.65	B			27	20	7	100
BH03		42.3	B		31				
BH03		47.2	B		32				
BH03		48.2	B			54	43	11	100
BH03		49.3	B		37				
BH03		63.5	B		20				
BH03		64.3	B		29				
BH03		65.5	B		24				
BH03		66.95	B		38				
BH03		68.4	B		37				



# Natural Moisture Content/Atterberg Limits Summary

Job Ref

BS 1377 : Part 2 : 1990 : Clause 3

Location

Galway PDL

P16005

Hole ID	Sample Ref	Depth (m)	Sample Type	Sample Description	MC	LL	PL	PI	% Pass 425
BH03		70.4	B		21				
BH03		70.75	B		21				
BH03		71.6	B		25				
BH06		16.6	B		22				
BH06		16.7	B			38	27	11	100
BH06		18.25	B		28				
BH06		18.65	B			49	38	11	100
BH06		21.45	B		26				
BH06		21.52	B			39	30	9	100



# PARTICLE SIZE DISTRIBUTION

BS 1377 : Part 2 : 1990 : Clause 9

Job Ref

P16005

Borehole / Pit  
No

BH03

Location

Galway PDL

Sample No

0


Depth

14.90 m

Soil Description

Sample type

B



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5	100		
3.35	100		
2	100		
1.18	100		
0.6	99		
0.425	99		
0.3	99		
0.212	99		
0.15	82		
0.063	38		

Test Method	
BS 1377 : Part 2 : 1990	
Sieving	Clause 9.2
Sedimentation	N/A

Sample Proportions	
Cobbles	0.0
Gravel	0.3
Sand	62.2
Silt & Clay	37.5

Grading Analysis	
D100	3.350
D60	0.106
D10	
Uniformity Coefficient	N/A



# PARTICLE SIZE DISTRIBUTION

BS 1377 : Part 2 : 1990 : Clause 9

Job Ref

P16005

Borehole / Pit  
No

BH03

Location

Galway PDL

Sample No

0


Depth

19.00 m

Soil Description

Sample type

B



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5	100		
3.35	100		
2	100		
1.18	100		
0.6	100		
0.425	100		
0.3	99		
0.212	97		
0.15	84		
0.063	51		

Test Method	
BS 1377 : Part 2 : 1990	
Sieving	Clause 9.2
Sedimentation	N/A

Sample Proportions	
Cobbles	0.0
Gravel	0.0
Sand	48.5
Silt & Clay	51.5

Grading Analysis	
D100	2.000
D60	0.086
D10	
Uniformity Coefficient	N/A



# PARTICLE SIZE DISTRIBUTION

BS 1377 : Part 2 : 1990 : Clause 9

Job Ref

P16005

Borehole / Pit  
No

BH03

Location

Galway PDL

Sample No

0


Depth

25.50 m

Soil Description

Sample type

B



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5	100		
3.35	100		
2	100		
1.18	100		
0.6	99		
0.425	98		
0.3	97		
0.212	95		
0.15	89		
0.063	23		

Test Method	
BS 1377 : Part 2 : 1990	
Sieving	Clause 9.2
Sedimentation	N/A

Sample Proportions	
Cobbles	0.0
Gravel	0.0
Sand	77.1
Silt & Clay	22.9

Grading Analysis	
D100	2.000
D60	0.112
D10	
Uniformity Coefficient	N/A



# PARTICLE SIZE DISTRIBUTION

BS 1377 : Part 2 : 1990 : Clause 9

Job Ref

P16005

Borehole / Pit  
No

BH03

Location

Galway PDL

Sample No

0


Depth

25.80 m

Soil Description

Sample type

B



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5	100		
3.35	100		
2	100		
1.18	100		
0.6	100		
0.425	100		
0.3	99		
0.212	98		
0.15	90		
0.063	21		

Test Method	
BS 1377 : Part 2 : 1990	
Sieving	Clause 9.2
Sedimentation	N/A

Sample Proportions	
Cobbles	0.0
Gravel	0.0
Sand	78.8
Silt & Clay	21.2

Grading Analysis	
D100	3.350
D60	0.112
D10	
Uniformity Coefficient	N/A



# PARTICLE SIZE DISTRIBUTION

BS 1377 : Part 2 : 1990 : Clause 9

Job Ref

P16005

Borehole / Pit  
No

BH03

Location

Galway PDL

Sample No

0


Depth

26.50 m

Soil Description

Sample type

B



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5	100		
3.35	100		
2	100		
1.18	100		
0.6	100		
0.425	100		
0.3	99		
0.212	99		
0.15	93		
0.063	34		

Test Method	
BS 1377 : Part 2 : 1990	
Sieving	Clause 9.2
Sedimentation	N/A

Sample Proportions	
Cobbles	0.0
Gravel	0.0
Sand	66.0
Silt & Clay	34.0

Grading Analysis	
D100	2.000
D60	0.102
D10	
Uniformity Coefficient	N/A





# PARTICLE SIZE DISTRIBUTION

BS 1377 : Part 2 : 1990 : Clause 9

Job Ref

P16005

Borehole / Pit  
No

BH03

Location

Galway PDL

Sample No

0


Depth

26.70 m

Soil Description

Sample type

B



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5	100		
3.35	100		
2	100		
1.18	100		
0.6	100		
0.425	100		
0.3	100		
0.212	99		
0.15	93		
0.063	35		

Test Method	
BS 1377 : Part 2 : 1990	
Sieving	Clause 9.2
Sedimentation	N/A

Sample Proportions	
Cobbles	0.0
Gravel	0.0
Sand	65.4
Silt & Clay	34.6

Grading Analysis	
D100	2.000
D60	0.101
D10	
Uniformity Coefficient	N/A



# PARTICLE SIZE DISTRIBUTION

BS 1377 : Part 2 : 1990 : Clause 9

Job Ref

P16005

Borehole / Pit  
No

BH03

Location

Galway PDL

Sample No

0


Depth

27.55 m

Soil Description

Sample type

B



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5	100		
3.35	100		
2	100		
1.18	100		
0.6	100		
0.425	100		
0.3	99		
0.212	90		
0.15	66		
0.063	44		

Test Method	
BS 1377 : Part 2 : 1990	
Sieving	Clause 9.2
Sedimentation	N/A

Sample Proportions	
Cobbles	0.0
Gravel	0.0
Sand	55.8
Silt & Clay	44.2

Grading Analysis	
D100	2.000
D60	0.127
D10	
Uniformity Coefficient	N/A



# PARTICLE SIZE DISTRIBUTION

BS 1377 : Part 2 : 1990 : Clause 9

Job Ref

P16005

Borehole / Pit  
No

BH03

Location

Galway PDL

Sample No

0


Depth

30.25 m

Soil Description

Sample type

B



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5	100		
3.35	100		
2	100		
1.18	100		
0.6	70		
0.425	38		
0.3	18		
0.212	12		
0.15	9		
0.063	8		

Test Method	
BS 1377 : Part 2 : 1990	
Sieving	Clause 9.2
Sedimentation	N/A

Sample Proportions	
Cobbles	0.0
Gravel	0.0
Sand	91.5
Silt & Clay	8.4

Grading Analysis	
D100	3.350
D60	0.545
D10	0.165
Uniformity Coefficient	3



# PARTICLE SIZE DISTRIBUTION

BS 1377 : Part 2 : 1990 : Clause 9

Job Ref

P16005

Borehole / Pit No

BH03

Location

Galway PDL

Sample No

0


Depth

36.70 m

Soil Description

Sample type

B



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100		
90	100		
75	100		
63	100		
50	100		
37.5	100		
28	100		
20	100		
14	100		
10	100		
6.3	100		
5	100		
3.35	100		
2	100		
1.18	100		
0.6	99		
0.425	95		
0.3	81		
0.212	59		
0.15	30		
0.063	14		

Test Method	
BS 1377 : Part 2 : 1990	
Sieving	Clause 9.2
Sedimentation	N/A

Sample Proportions	
Cobbles	0.0
Gravel	0.1
Sand	85.8
Silt & Clay	14.1

Grading Analysis	
D100	6.300
D60	0.217
D10	
Uniformity Coefficient	N/A



**Sulphate Content & pH Value**  
BS 1377 : Part 3 : 1990 : Clause 5.5 & 9.5

Job Ref

Location

Galway PDL

P16005

Hole ID	Sample Ref	Depth (m)	Sample Type	Sample Description	% < 2.0 mm	pH Value	Sulphate Content as SO3			Sulphate Content as SO4		
							GW g/L	Total Sulphate %	Water Soluble g/L	GW g/L	Total Sulphate %	Water Soluble g/L
BH03		20.95	B			9.08						
BH03		27.20	B			8.93						
BH03		41.20	B			8.27						
BH03		47.00	B			7.77						
BH03		63.38	B			7.5						

—

—



# Organic Matter Content

BS 1377 : Part 3 : 1990 : Clause 3

Job Ref

Location

Galway PDL

P16005

Hole ID	Sample Ref	Depth (m)	Sample Type	Sample Description	% Mass < 2 mm	Organic Matter Content %
BH03		38.95	B		100	8.85
BH03		39.45	B		100	5.63
BH03		42.35	B		100	7.04
BH03		46.20	B		100	15.12
BH03		47.45	B		99.97	6.64
BH03		49.00	B		100	6.49
BH03		63.15	B		98.97	10.22
BH03		63.90	B		100	5.99
BH03		64.90	B		99.3	7.68
BH06		17.13	B		99.51	3.15
BH06		18.95	B		99.5	3.17
BH06		21.75	B		99.93	12.51



# UNDRAINED TRIAXIAL COMPRESSION

BS 1377 : Part 7 : 1990 Clause 8

Job Ref

P16005

Location

Galway PDL

Borehole / Pit  
No

BH03

Sample No

Soils Description

Depth

4.15 m

Date

## Sample Details

### Specimen 1

Sample Condition		Undisturbed
Height	mm	185.0
Diameter	mm	82.0
Moisture Content	%	7.9
Bulk Density	Mg/m <sup>3</sup>	2.34
Dry Density	Mg/m <sup>3</sup>	2.17

## Test Details



Membrane Thickness	mm	0.36
Membrane Correction	kPa	0.33
Rate of Axial Displacement	%/min	1.62
Cell Pressure	kPa	40
Strain at Failure	%	2.7
Maximum Deviator Stress	kPa	227
Shear Strength	kPa	114
Mode of Failure		Brittle

Position and orientation within  
the original sample

## Shear Strength Parameters

C 114 kPa  
Phi 0.0 °

Specimen 1





# UNDRAINED TRIAXIAL COMPRESSION

BS 1377 : Part 7 : 1990 Clause 8

Location

Galway PDL

Soils Description

Job Ref

P16005

Borehole / Pit  
No

BH03

Sample No

Depth

41.85 m

Date

## Sample Details

### Specimen 1

Sample Condition		Undisturbed
Height	mm	208.0
Diameter	mm	83.0
Moisture Content	%	41
Bulk Density	Mg/m <sup>3</sup>	1.78
Dry Density	Mg/m <sup>3</sup>	1.26

## Test Details



Membrane Thickness	mm	0.36
Membrane Correction	kPa	0.40
Rate of Axial Displacement	%/min	1.44
Cell Pressure	kPa	400
Strain at Failure	%	3.4
Maximum Deviator Stress	kPa	571
Shear Strength	kPa	286
Mode of Failure		Brittle

Position and orientation within  
the original sample

## Shear Strength Parameters

C 286 kPa  
Phi 0.0 °

Specimen 1







# UNDRAINED TRIAXIAL COMPRESSION

BS 1377 : Part 7 : 1990 Clause 8

Location	Galway PDL	Job Ref	P16005
		Borehole / Pit No	BH03
		Sample No	
Soils Description		Depth	42.81 m
		Date	

## Sample Details

## Specimen 1

Sample Condition		Undisturbed
Height	mm	205.0
Diameter	mm	83.0
Moisture Content	%	43
Bulk Density	Mg/m <sup>3</sup>	1.95
Dry Density	Mg/m <sup>3</sup>	1.36

## Test Details



Membrane Thickness	mm	0.36
Membrane Correction	kPa	0.45
Rate of Axial Displacement	%/min	1.46
Cell Pressure	kPa	410
Strain at Failure	%	3.9
Maximum Deviator Stress	kPa	239
Shear Strength	kPa	120
Mode of Failure		Brittle

Position and orientation within  
the original sample

## Shear Strength Parameters

C 120 kPa  
Phi 0.0 °

Specimen 1





# UNDRAINED TRIAXIAL COMPRESSION

BS 1377 : Part 7 : 1990 Clause 8

Job Ref

P16005

Borehole / Pit  
No

BH03

Location

Galway PDL

Sample No

Soils Description

Depth

46.43 m

Date

## Sample Details

## Specimen 1

Sample Condition		Undisturbed
Height	mm	201.0
Diameter	mm	80.0
Moisture Content	%	38
Bulk Density	Mg/m <sup>3</sup>	1.73
Dry Density	Mg/m <sup>3</sup>	1.26

## Test Details



Membrane Thickness	mm	0.36
Membrane Correction	kPa	0.48
Rate of Axial Displacement	%/min	1.49
Cell Pressure	kPa	440
Strain at Failure	%	4.0
Maximum Deviator Stress	kPa	141
Shear Strength	kPa	71
Mode of Failure		Compound

Position and orientation within  
the original sample

## Shear Strength Parameters

C 71 kPa  
Phi 0.0 °

Specimen 1





# UNDRAINED TRIAXIAL COMPRESSION

BS 1377 : Part 7 : 1990 Clause 8

Job Ref	P16005
Borehole / Pit No	BH03
Sample No	
Depth	48.45 m
Date	

Location

Galway PDL

Soils Description

## Sample Details

## Specimen 1

Sample Condition		Undisturbed
Height	mm	210.0
Diameter	mm	83.0
Moisture Content	%	31
Bulk Density	Mg/m <sup>3</sup>	1.92
Dry Density	Mg/m <sup>3</sup>	1.47

## Test Details



Membrane Thickness	mm	0.36
Membrane Correction	kPa	0.44
Rate of Axial Displacement	%/min	1.43
Cell Pressure	kPa	460
Strain at Failure	%	3.8
Maximum Deviator Stress	kPa	264
Shear Strength	kPa	132
Mode of Failure		Brittle

Position and orientation within the original sample

## Shear Strength Parameters

C 132 kPa  
Phi 0.0 °

Specimen 1





# UNDRAINED TRIAXIAL COMPRESSION

BS 1377 : Part 7 : 1990 Clause 8

Job Ref

P16005

Location

Galway PDL

Borehole / Pit  
No

BH06

Sample No

Soils Description

Depth

5.25 m

Date

## Sample Details

### Specimen 1

Sample Condition		Undisturbed
Height	mm	196.0
Diameter	mm	82.0
Moisture Content	%	6.1
Bulk Density	Mg/m <sup>3</sup>	2.39
Dry Density	Mg/m <sup>3</sup>	2.26

## Test Details



Membrane Thickness	mm	0.36
Membrane Correction	kPa	0.55
Rate of Axial Displacement	%/min	1.53
Cell Pressure	kPa	51
Strain at Failure	%	4.8
Maximum Deviator Stress	kPa	174
Shear Strength	kPa	87
Mode of Failure		Brittle

Position and orientation within  
the original sample

## Shear Strength Parameters

C 87 kPa  
Phi 0.0 °

Specimen 1





# UNDRAINED TRIAXIAL COMPRESSION

BS 1377 : Part 7 : 1990 Clause 8

Job Ref	P16005
Borehole / Pit No	BH06
Sample No	
Depth	18 m
Date	

Location

Galway PDL

Soils Description

## Sample Details

## Specimen 1

Sample Condition		Undisturbed
Height	mm	206.0
Diameter	mm	82.0
Moisture Content	%	30
Bulk Density	Mg/m <sup>3</sup>	2.09
Dry Density	Mg/m <sup>3</sup>	1.61

## Test Details



Membrane Thickness	mm	0.36
Membrane Correction	kPa	0.65
Rate of Axial Displacement	%/min	1.46
Cell Pressure	kPa	170
Strain at Failure	%	5.8
Maximum Deviator Stress	kPa	239
Shear Strength	kPa	119
Mode of Failure		Brittle

Position and orientation within the original sample

## Shear Strength Parameters

C 119 kPa  
Phi 0.0 °

Specimen 1





# Laboratory Report



GEO Site & Testing Services Ltd

## Contract Number: 30522

Client's Reference: **P16005**

Report Date: **09-05-2016**

Client **Priority Geotechnical Limited**  
**Unit 12**  
**Owenacurra Business Park**  
**Midleton**  
**Co. Cork.**

Contract Title: **N6 Galway Bypass**  
For the attention of: **Colette Kelly**

Date Received: **07-04-2016**  
Date Commenced: **07-04-2016**  
Date Completed: **09-05-2016**

Test Description	Qty
<b>One-dimensional Consolidation 75mm or 50mm diameter specimens (5 days)</b> 1377 : 1990 Part 5 : 3 - * UKAS	7
<b>As 4.01 each additional day</b> 1377 : 1990 Part 5 : 3	18
<b>Disposal of Samples on Project</b>	1

**Notes:** Observations and Interpretations are outside the UKAS Accreditation  
\* - denotes test included in laboratory scope of accreditation  
# - denotes test carried out by approved contractor  
@ - denotes non accredited tests

This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced in full, without the prior written approval of the laboratory.

**Approved Signatories:**


Alex Wynn (Associate Director) - Benjamin Sharp (Contracts Manager) - Emma Sharp (Office Manager)  
Paul Evans (Quality/Technical Manager) - Vaughan Edwards (Managing Director)

# ONE DIMENSIONAL CONSOLIDATION

BS1377: Part 5: 1990

Client ref: P16005  
 Location: N6 Galway Bypass  
 Contract Number: 30522-070416  
 Hole/Sample Number: BH03  
 Depth (m): 41.30 - 41.50  
 Sample Type: B

Initial Conditions		Pressure Range	Mv	Cv	Method of time fitting used
Moisture Content (%):	33	kPa	m2/MN	m2/yr	Cv Calculated using t90
Bulk Density (Mg/m3):	1.89	0 - 50	0.20	23	Nominal Laboratory Temperature
Dry Density (Mg/m3):	1.43	50 - 100	0.20	15	20°C
Voids Ratio:	0.8590	100 - 200	0.070	24	Location of specimen with sample
Degree of saturation:	101.4	200 - 400	0.063	13	top
Height (mm):	19.96	400 - 800	0.043	7.4	Remarks:
Diameter (mm)	50.06	800 - 1600	0.027	9.8	
Particle Density (Mg/m3):	2.65	1600 - 3200	0.022	11	
Assumed		3200 - 15	0.013	20	



**GSTL**  
 GEO SITE & TESTING SERVICES LTD

*Katam*

Checked By

09/05/16

Date

*D P Grant*

Approved By

09/05/16

Date




# ONE DIMENSIONAL CONSOLIDATION

BS1377: Part 5: 1990

Client ref: P16005  
 Location: N6 Galway Bypass  
 Contract Number: 30522-070416  
 Hole/Sample Number: BH03  
 Depth (m): 42.97 - 43.00  
 Sample Type: B

Initial Conditions		Pressure Range	Mv	Cv	Method of time fitting used
Moisture Content (%):	29	kPa	m2/MN	m2/yr	Cv Calculated using t90
Bulk Density (Mg/m3):	1.93	0 - 50	0.18	31	Nominal Laboratory Temperature
Dry Density (Mg/m3):	1.50	50 - 100	0.10	11	20°C
Voids Ratio:	0.7721	100 - 200	0.050	36	Location of specimen with sample
Degree of saturation:	99.6	200 - 400	0.033	11	top
Height (mm):	20.02	400 - 800	0.027	12	Remarks:
Diameter (mm)	50.05	800 - 1600	0.015	25	
Particle Density (Mg/m3):	2.65	1600 - 3200	0.012	10	
Assumed		3200 - 15	0.0086	31	



**GSTL**  
 GEO SITE & TESTING SERVICES LTD

*Katam*

Checked By

09/05/16

Date

*D P Gans*

Approved By

09/05/16

Date






# ONE DIMENSIONAL CONSOLIDATION

BS1377: Part 5: 1990

Client ref: P16005  
 Location: N6 Galway Bypass  
 Contract Number: 30522-070416  
 Hole/Sample Number: BH03  
 Depth (m): 44.05 - 44.20  
 Sample Type: B

Initial Conditions		Pressure Range	Mv	Cv	Method of time fitting used
Moisture Content (%):	21	kPa	m2/MN	m2/yr	Cv Calculated using t90
Bulk Density (Mg/m3):	2.11	0 - 50	0.025	19	Nominal Laboratory Temperature
Dry Density (Mg/m3):	1.75	50 - 100	0.078	0.53	20°C
Voids Ratio:	0.5171	100 - 200	0.012	19	Location of specimen with sample
Degree of saturation:	105.2	200 - 400	0.035	4.8	top
Height (mm):	20.03	400 - 800	0.013	6.2	Remarks:
Diameter (mm)	50	800 - 1600	0.0086	19	
Particle Density (Mg/m3):	2.65	1600 - 3200	0.0075	10	
Assumed		3200 - 15	0.0029	53	



**GSTL**  
 GEO SITE & TESTING SERVICES LTD

*Katam*

Checked By

09/05/16

Date

*D P Grant*

Approved By

09/05/16

Date




# ONE DIMENSIONAL CONSOLIDATION

BS1377: Part 5: 1990

Client ref: P16005  
 Location: N6 Galway Bypass  
 Contract Number: 30522-070416  
 Hole/Sample Number: BH03  
 Depth (m): 47.85 - 48.02  
 Sample Type: B

Initial Conditions		Pressure Range	Mv	Cv	Method of time fitting used
Moisture Content (%):	40	kPa	m2/MN	m2/yr	Cv Calculated using t90
Bulk Density (Mg/m3):	1.59	0 - 50	0.13	18	Nominal Laboratory Temperature
Dry Density (Mg/m3):	1.14	50 - 100	0.18	5.6	20°C
Voids Ratio:	1.3346	100 - 200	0.097	18	Location of specimen with sample
Degree of saturation:	79.1	200 - 400	0.080	4.1	top
Height (mm):	20.04	400 - 800	0.057	0.63	Remarks:
Diameter (mm)	50.02	800 - 1600	0.042	15	
Particle Density (Mg/m3):	2.65	1600 - 3200	0.037	9.2	
Assumed		3200 - 15	0.030	2.8	



**GSTL**  
 GEO SITE & TESTING SERVICES LTD

*Katam*

Checked By

09/05/16

Date

*D P Gans*

Approved By

09/05/16

Date




# ONE DIMENSIONAL CONSOLIDATION

BS1377: Part 5: 1990

Client ref: P16005  
 Location: N6 Galway Bypass  
 Contract Number: 30522-070416  
 Hole/Sample Number: BH06  
 Depth (m): 16.20 - 16.50  
 Sample Type: B

Initial Conditions		Pressure Range	Mv	Cv	Method of time fitting used
Moisture Content (%):	26	kPa	m2/MN	m2/yr	Cv Calculated using t90
Bulk Density (Mg/m3):	1.95	0 - 50	0.046	17	Nominal Laboratory Temperature
Dry Density (Mg/m3):	1.54	50 - 100	0.18	12	20°C
Voids Ratio:	0.7221	100 - 200	0.10	10	Location of specimen with sample
Degree of saturation:	96.9	200 - 400	0.048	16	top
Height (mm):	20.04	400 - 800	0.037	6.2	Remarks:
Diameter (mm)	50.02	800 - 1600	0.022	11	
Particle Density (Mg/m3):	2.65	1600 - 3200	0.020	14	
Assumed		3200 - 15	0.010	10	



**GSTL**  
 GEO SITE & TESTING SERVICES LTD

*Katam*

Checked By

09/05/16

Date

*D P Grant*

Approved By

09/05/16

Date




# ONE DIMENSIONAL CONSOLIDATION

BS1377: Part 5: 1990

Client ref: P16005  
 Location: N6 Galway Bypass  
 Contract Number: 30522-070416  
 Hole/Sample Number: BH06  
 Depth (m): 19.70 - 19.95  
 Sample Type: B

Initial Conditions		Pressure Range	Mv	Cv	Method of time fitting used
Moisture Content (%):	27	kPa	m2/MN	m2/yr	Cv Calculated using t90
Bulk Density (Mg/m3):	1.87	0 - 50	0.084	12	Nominal Laboratory Temperature
Dry Density (Mg/m3):	1.47	50 - 100	0.13	12	20°C
Voids Ratio:	0.7973	100 - 200	0.079	27	Location of specimen with sample
Degree of saturation:	90.1	200 - 400	0.055	11	top
Height (mm):	20.13	400 - 800	0.039	4.3	Remarks:
Diameter (mm)	50.01	800 - 1600	0.025	16	
Particle Density (Mg/m3):	2.65	1600 - 3200	0.021	15	
Assumed		3200 - 15	0.013	16	



**GSTL**  
 GEO SITE & TESTING SERVICES LTD

*Katam*

Checked By

09/05/16

Date

*D P Grant*

Approved By

09/05/16

Date




# ONE DIMENSIONAL CONSOLIDATION

BS1377: Part 5: 1990

Client ref: P16005  
 Location: N6 Galway Bypass  
 Contract Number: 30522-070416  
 Hole/Sample Number: BH06  
 Depth (m): 20.00 - 20.25  
 Sample Type: B

Initial Conditions		Pressure Range	Mv	Cv	Method of time fitting used
Moisture Content (%):	30	kPa	m2/MN	m2/yr	Cv Calculated using t90
Bulk Density (Mg/m3):	1.94	0 - 50	0.35	18	Nominal Laboratory Temperature
Dry Density (Mg/m3):	1.49	50 - 100	0.22	15	20°C
Voids Ratio:	0.7762	100 - 200	0.11	27	Location of specimen with sample
Degree of saturation:	101.7	200 - 400	0.075	16	top
Height (mm):	19.92	400 - 800	0.054	7.0	Remarks:
Diameter (mm)	50.02	800 - 1600	0.033	21	
Particle Density (Mg/m3):	2.65	1600 - 3200	0.024	14	
Assumed		3200 - 15	0.016	7.1	



**GSTL**  
 GEO SITE & TESTING SERVICES LTD

*Katam*

Checked By

09/05/16

Date

*D P Grant*

Approved By

09/05/16

Date



## Thin Section / Petrography

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 16<sup>th</sup> February 2016  
Test Report Ref.: 443031

Page 1 of 8

## **LABORATORY TEST REPORT**

**Test Requirements:** Petrographic Examination of Natural Stone in accordance with  
BS EN 12047:2007

### **Sample details:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. No:	BH04 - 48919
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	29/1/2016
Date of Start of Test.:	21/1/2016
Sampling Location:	Depth Top: 20.05 Depth Base: 20.12
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The work was carried out by our accredited, competent, sub contracted laboratory.

### **RESULTS**

See Attached



Nick Dumbarton – Assistant Laboratory Manager

Petrographic Examination Natural Stone– BS EN 12407:2007

**HAND SPECIMEN DESCRIPTION**

The sample was hard, fine to very coarse grained, anisotropic limestone breccia. The sample exhibited small to very large, medium grey limestone clasts (up to >70mm across), cemented or surrounded by dark grey materials comprising chiefly much smaller limestone and calcite grains, and including some clay materials. The sample did not appear macroporous.

**MICROSCOPICAL DESCRIPTION**

Constituents <sup>1</sup>	Visual Estimated Proportions <sup>2</sup> %	Range of Crystal/Grain Size	Petrographic Details	Origin
Calcite	94	Up to 4mm	Fresh, angular to well rounded calcium carbonate, including abundant bioclasts. The sample was partially stained in accordance with Dickson's method. This suggested that the calcite was non-ferroan.	Primary
Clay materials	2-3	<4µm	Very fine grained materials beyond the conclusive resolution of the petrographic microscope, which could be better investigated by scanning electron microscopy (SEM).	Primary
Opaque minerals	1-2	Up to 800µm	Irregular, anhedral to euhedral, fresh to partially oxidised isotropic minerals apparently comprising both framboidal and faceted, probably pyritic materials. Scanning electron microscopy should be used if necessary for better resolution and description of the opaque minerals.	Primary
Iron oxide compounds	<<1	N/A	Small amorphous by-products of the partial or complete oxidation of opaque minerals.	Secondary

The sample was a fine to very coarse grained LIMESTONE BRECCIA, comprising chiefly calcium carbonate (chiefly as limestone clasts), with a minor proportion of clay materials and trace to minor proportion of opaque minerals.

The individual limestone constituents were typically fine to medium grained. The dark grey areas of the sample comprised chiefly smaller calcium carbonate, with a minor proportion of clay materials. The opaque minerals were unevenly distributed and were frequently observed concentrated in thin, irregular and randomly orientated layers within the dark grey areas of the sample.

The sample fractured relatively easily along irregular and randomly distributed fracture surfaces within the dark grey areas of the sample during the cutting process to produce the thin section slice. This suggested that the dark grey areas of the sample exhibited frequent planes of weakness, which were probably associated with clay materials and the irregular layers of opaque minerals.

Only rare voids up to 0.4mm were observed. These voids appeared chiefly associated with loss of materials during the sampling process and did not appear interconnected. The void content was visually estimated as being well below 1%.


The sample was fresh and exhibited Grade I weathering.




Test Report Ref.: 443031 – Page 3 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007

Profile view of the sample as received




Another profile view of the sample as received



Test Report Ref.: 443031 – Page 4 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007




**Description**

View of a section through the limestone, showing limestone and calcite clasts (grey/pale brown/white, pale pink/greyish brown: B2, B6, B9, B12, F2 and H6) and section of the dark grey areas (greyish black: A8, D3 and I2) comprising smaller limestone and calcite clasts/grains and some clay materials.



Test Report Ref.: 443031 – Page 5 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007




**Description**

Closer view of a section through a dark grey area of the sample, showing clay materials (brown: A6, A11 and G1) and randomly distributed layers of opaque minerals (black: A7 to D1, D4 to F7 and E12 to I7).

Test Report Ref.: 443031 – Page 6 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007




**Description**

Closer view of a section through the sample, showing faceted opaque minerals (brass coloured: A9, B4, D7 and F8) and apparent framboidal opaque minerals (black/brass: A1, D7 and F6).

Test Report Ref.: 443031 – Page 7 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007



**Description**

View of a section through the sample, showing opaque minerals (black: A3, A6 and C9) an oxidised opaque minerals (dusky red, reddish orange: A10, E8, H5/6 and H9) irregular voids (yellow: B6, D6 and H9).



Petrographic Examination Natural Stone– BS EN 12407:2007

Glossary of Terms Used in the Descriptions

Proportions	Major: constituent present at a level $\geq 10\%$ ; Minor: constituent present at level $\geq 2\%$ but $< 10\%$ ; Trace: constituent present at $< 2\%$ level
Frequency	<ul style="list-style-type: none"> <li>Rare – only found by thorough searching</li> <li>Sporadic – only occasionally observed during normal examination</li> <li>Common – easily observed during normal examination</li> <li>Frequent – easily observed with minimal examination</li> <li>Abundant – immediately apparent to initial examination</li> </ul>
Hardness	<ul style="list-style-type: none"> <li>Very soft: can be penetrated easily by a finger</li> <li>Soft: scores with a fingernail</li> <li>Moderately soft: scores using a copper coin</li> <li>Moderately hard: scores easily with a penknife</li> <li>Hard: not easily scored with a penknife</li> <li>Very hard: cannot be scored with a steel point or knife.</li> </ul>
Weathering/ alteration	<ul style="list-style-type: none"> <li>Grade I (Fresh): Unchanged from original state</li> <li>Grade II (Slightly Weathered): Slight discoloration, slight weakening;</li> <li>Grade III (Moderately Weathered): Considerably weakened, penetrative discoloration, large pieces cannot be broken by hand</li> <li>Grade IV (Highly Weathered): large pieces can be broken by hand, does not readily disaggregate (slake) when dry sample immersed in water</li> <li>Grade V (Completely Weathered): considerably weakened, slakes, original texture apparent; Grade VI (Residual Soil)</li> <li>Soil derived by in-situ weathering but retaining none of the original texture or fabric.</li> </ul>
Origin	<ul style="list-style-type: none"> <li>Primary constituents: Constituents present within the rock at its formation.</li> <li>Secondary constituents: Constituents formed by the alteration of pre-existing primary constituents or introduced from an external source after the rock was formed</li> </ul>
Size	Mega: $> 60\text{mm}$ ; Macro: $2\text{--}60\text{mm}$ ; Meso: $60\mu\text{m--}2\text{mm}$ ; Micro: $2\text{--}60\mu\text{m}$ ; Crypto: $< 2\mu\text{m}$ ; Glassy: without visible crystallinity
Bedding/Layering	Thick: $> 600\text{mm}$ ; Medium: $200\text{--}600\text{mm}$ ; Thin: $60\text{--}200\text{mm}$ ; Very thin: $20\text{--}60\text{mm}$
Lamination	Thick: $6\text{--}20\text{mm}$ ; Thin: $2\text{--}6\text{mm}$ ; Very thin: $600\mu\text{m--}2\text{mm}$ ; Extremely thin: $< 600\mu\text{m}$
Cleavage	Extremely wide: $> 2\text{mm}$ ; Very wide: $600\mu\text{m--}2\text{mm}$ ; Wide: $200\text{--}600\mu\text{m}$ ; Medium: $60\text{--}200\mu\text{m}$ ; Close: $20\text{--}60\mu\text{m}$ ; Very close: $6\text{--}20\mu\text{m}$ ; Extremely close: $< 6\mu\text{m}$ .
Cracks	<ul style="list-style-type: none"> <li>Fine microcracks (<math>&lt; 1\mu\text{m}</math> wide)</li> <li>Microcracks (<math>1\text{--}10\mu\text{m}</math> wide)</li> <li>Fine cracks (<math>10\text{--}100\mu\text{m}</math> wide)</li> <li>Cracks (<math>100\mu\text{m--}1\text{mm}</math> wide)</li> <li>Large cracks (<math>&gt; 1\text{mm}</math> wide).</li> </ul>
Limestone Classification Schemes	<p>Folk, R. L. 1959. Practical petrographic classification of limestones. <i>Bull. Am. Ass. Petro. Geol.</i> 43, 1-38.</p> <p>Dunham, R. J. 1962. Classification of carbonate rocks according to depositional texture. In: <i>Classification of Carbonate Rocks</i> (Ed. By W. E. Ham), pp. 108-121. <i>Mem. Am. Ass. Petrol. Geol.</i> 1, Tulsa.</p>

Priority Construction Ltd  
162 Clontarf Road  
Dublin 3  
Ireland  
VAT No: 9D539711

Date: 16<sup>th</sup> February 2016  
Test Report Ref.: 443144

Page 1 of 8

## **LABORATORY TEST REPORT**

**Test Requirements:** Petrographic Examination of Natural Stone in accordance with  
BS EN 12047:2007

### **Sample details:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56158</b>
Client Ref. No:	<b>BH05 - 50728</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>29/1/2016</b>
Date of Start of Test.:	<b>21/1/2016</b>
Sampling Location:	<b>Depth Top: 32.92 Depth Base: 33</b>
Name of Source:	<b>Lackagh Quarry SI</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Core</b>
Target Specification:	<b>N/A</b>

### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The work was carried out by our accredited, competent, sub contracted laboratory.

### **RESULTS**

See Attached



Nick Dumbarton – Assistant Laboratory Manager

## Petrographic Examination Natural Stone– BS EN 12407:2007

### HAND SPECIMEN DESCRIPTION

The sample was hard, fine grained, massive, not macroporous limestone. The sample was almost isotropic, except for the presence of a small stylolite (irregular suture) typically <200µm across, running more or less perpendicular to the coring direction. Sporadic small irregular voids up to approximately 1mm across were observed chiefly associated with apparent loss of materials along the stylolite.

### MICROSCOPICAL DESCRIPTION

Constituents <sup>1</sup>	Visual Estimated Proportions <sup>2</sup> %	Range of Crystal/Grain Size	Petrographic Details	Origin
Calcite	99	Up to 800µm	Fresh, angular to well rounded calcium carbonate, including frequent bioclasts. The sample was partially stained in accordance with Dickson's method. This suggested that the calcite was non-ferroan.	Primary
Opaque minerals	<1	Up to 80µm	Fresh to partially altered, chiefly euhedral isotropic minerals apparently comprising facettted, probably pyritic materials. SEM should be used if necessary for better resolution and description of the opaque minerals.	Primary
Iron oxide compounds	<<1	N/A	Rare amorphous by-products of the partial or complete oxidation of opaque minerals.	Secondary

The sample was a fine grained LIMESTONE, comprising almost entirely calcium carbonate, with trace amounts of opaque minerals and associated iron oxide compounds.

The sample exhibited stylolite comprising coarser crystals of calcite.


The sporadic voids observed associated with the stylolite did not appeared interconnected. The void content was visually estimated as being well below 1%.

The sample was fresh and exhibited Grade I weathering.




Test Report Ref.: 443144 – Page 3 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007




Closer view of the stylolite with 90 degrees rotation of the photograph



Test Report Ref.: 443144 – Page 4 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007




**Description**

View of a section through the limestone particles showing almost entire calcium carbonate (brown, dusky brown, greyish brown, grey/blue/green, pale pink: A9, B/C1, C9, F7 and G5), including bioclasts (dusky brown/greyish black: A5, C/D4, F10 and G5).



Test Report Ref.: 443144 – Page 5 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007




**Description**

Closer view of a section through the limestone, showing sections of the stylolite (pale pink: A7, E5, E9, H4 and I9) and voids (yellow: B7/8, D8, F8 and I9) associated with the stylolite.

Test Report Ref.: 443144 – Page 6 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007




**Description**

View of a section through the limestone, showing opaque minerals (black: E/F7).



Test Report Ref.: 443144 – Page 7 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007



**Description**

View of a section through the limestone, showing partially oxidised opaque mineral (red: D7) and iron oxide compounds (reddish orange: G6 and G/H5).

Petrographic Examination Natural Stone– BS EN 12407:2007

Glossary of Terms Used in the Descriptions

Proportions	Major: constituent present at a level $\geq 10\%$ ; Minor: constituent present at level $\geq 2\%$ but $< 10\%$ ; Trace: constituent present at $< 2\%$ level
Frequency	<ul style="list-style-type: none"> <li>Rare – only found by thorough searching</li> <li>Sporadic – only occasionally observed during normal examination</li> <li>Common – easily observed during normal examination</li> <li>Frequent – easily observed with minimal examination</li> <li>Abundant – immediately apparent to initial examination</li> </ul>
Hardness	<ul style="list-style-type: none"> <li>Very soft: can be penetrated easily by a finger</li> <li>Soft: scores with a fingernail</li> <li>Moderately soft: scores using a copper coin</li> <li>Moderately hard: scores easily with a penknife</li> <li>Hard: not easily scored with a penknife</li> <li>Very hard: cannot be scored with a steel point or knife.</li> </ul>
Weathering/ alteration	<ul style="list-style-type: none"> <li>Grade I (Fresh): Unchanged from original state</li> <li>Grade II (Slightly Weathered): Slight discoloration, slight weakening;</li> <li>Grade III (Moderately Weathered): Considerably weakened, penetrative discoloration, large pieces cannot be broken by hand</li> <li>Grade IV (Highly Weathered): large pieces can be broken by hand, does not readily disaggregate (slake) when dry sample immersed in water</li> <li>Grade V (Completely Weathered): considerably weakened, slakes, original texture apparent; Grade VI (Residual Soil)</li> <li>Soil derived by in-situ weathering but retaining none of the original texture or fabric.</li> </ul>
Origin	<ul style="list-style-type: none"> <li>Primary constituents: Constituents present within the rock at its formation.</li> <li>Secondary constituents: Constituents formed by the alteration of pre-existing primary constituents or introduced from an external source after the rock was formed</li> </ul>
Size	Mega: $> 60\text{mm}$ ; Macro: $2\text{--}60\text{mm}$ ; Meso: $60\mu\text{m--}2\text{mm}$ ; Micro: $2\text{--}60\mu\text{m}$ ; Crypto: $< 2\mu\text{m}$ ; Glassy: without visible crystallinity
Bedding/Layering	Thick: $> 600\text{mm}$ ; Medium: $200\text{--}600\text{mm}$ ; Thin: $60\text{--}200\text{mm}$ ; Very thin: $20\text{--}60\text{mm}$
Lamination	Thick: $6\text{--}20\text{mm}$ ; Thin: $2\text{--}6\text{mm}$ ; Very thin: $600\mu\text{m--}2\text{mm}$ ; Extremely thin: $< 600\mu\text{m}$
Cleavage	Extremely wide: $> 2\text{mm}$ ; Very wide: $600\mu\text{m--}2\text{mm}$ ; Wide: $200\text{--}600\mu\text{m}$ ; Medium: $60\text{--}200\mu\text{m}$ ; Close: $20\text{--}60\mu\text{m}$ ; Very close: $6\text{--}20\mu\text{m}$ ; Extremely close: $< 6\mu\text{m}$ .
Cracks	<ul style="list-style-type: none"> <li>Fine microcracks (<math>&lt; 1\mu\text{m}</math> wide)</li> <li>Microcracks (<math>1\text{--}10\mu\text{m}</math> wide)</li> <li>Fine cracks (<math>10\text{--}100\mu\text{m}</math> wide)</li> <li>Cracks (<math>100\mu\text{m--}1\text{mm}</math> wide)</li> <li>Large cracks (<math>&gt; 1\text{mm}</math> wide).</li> </ul>
Limestone Classification Schemes	<p>Folk, R. L. 1959. Practical petrographic classification of limestones. <i>Bull. Am. Ass. Petro. Geol.</i> 43, 1-38.</p> <p>Dunham, R. J. 1962. Classification of carbonate rocks according to depositional texture. In: <i>Classification of Carbonate Rocks</i> (Ed. By W. E. Ham), pp. 108-121. <i>Mem. Am. Ass. Petro. Geol.</i> 1, Tulsa.</p>

Priority Drilling Ltd.  
Killimor  
Ballinasloe  
Co Galway  
Ireland  
8D23036i

Date: 6<sup>th</sup> April 2016  
Test Report Ref.: 447907

Page 1 of 8

## **LABORATORY TEST REPORT**

**Test Requirements:** Petrographic Examination of Natural Stone in accordance with  
BS EN 12047:2007

### **Sample details:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50899</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test.:	<b>18/03/2016</b>
Sampling Location:	<b>Depth Top:113.00 Depth Base:113.08</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The work was carried out by our accredited, competent, sub contracted laboratory.

### **RESULTS**

See Attached



Nick Dumbarton – Assistant Laboratory Manager

## Petrographic Examination Natural Stone– BS EN 12407:2007

### HAND SPECIMEN DESCRIPTION

The sample was a moderately hard, fine to medium grained, massive, not macroporous limestone. The sample was chiefly medium dark grey, but exhibited common, randomly distributed, very light grey to medium grey grains that constituted the medium sized grains of the rock. The sample was almost isotropic, except for the presence of sporadic, randomly orientated small dark grey apparent stylolite (irregular suture) typically <500µm across and rare vein <400µm. Sporadic unevenly distributed patches of iron oxide compounds were observed.

### MICROSCOPICAL DESCRIPTION

Constituents <sup>1</sup>	Visual Estimated Proportions <sup>2</sup> %	Range of Crystal/Grain Size	Petrographic Details	Origin
Calcite	99	Up to 2500µm	Fresh, anhedral to euhedral crystals comprising chiefly microcrystalline calcite (calcite crystals <4µm), with a lesser proportion of sparry calcite (calcite crystals >4µm) and large discrete calcium carbonate grains. The sparry calcite and larger discrete calcium carbonate grains were chiefly observed within randomly distributed, abundant bioclasts and rare calcite veins.  The sample was partially stained in accordance with Dickson's method. This suggested that the calcite was predominantly non-ferroan, with a trace amount of possibly ferroan calcite.	Primary
Opaque minerals	<1	Up to 50µm	Fresh, chiefly anhedral isotropic minerals apparently comprising chiefly framboidal, probably pyritic grains. Scanning electron microscopy (SEM) should be used if necessary for better resolution and description of the opaque minerals.	Primary
Iron oxide compounds	<<1	N/A	Rare amorphous by-products of the oxidation of opaque minerals on the surface of the rock core.	Secondary


The sample was a fine to medium grained bioclastic LIMESTONE, comprising almost entirely calcium carbonate, with trace amounts of opaque minerals. No iron oxide compounds was observed in the thin section, suggesting that the patches observed on the hand specimen were superficial oxidation of the opaque minerals exposed to the element. The sample exhibited sporadic, unevenly distributed and randomly orientated stylolites comprising abundant opaque minerals.  
  
Rare irregular voids up to 100µm across were only observed associated with stylolites.  
  
The void content was visually estimated as being approximately 0%.  
  
The sample was fresh and exhibited Grade I weathering.



Test Report Ref.: 447907 – Page 3 of 8


Petrographic Examination Natural Stone– BS EN 12407:2007

Profile view of the sample as received



Test Report Ref.: 447907 – Page 4 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007




**Description**

View of a section through the sample, showing bioclasts (brown, yellowish grey, pale green: A9, B3, C/D2, D6, G2, G6 and G10), discrete calcite (dark grey (I2/3) cemented by microcrystalline calcite matrix (brown/dusky brown: A8, E8 and H3).

Test Report Ref.: 447907 – Page 5 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007




**Description**

View of a section through the sample, showing calcite vein (C112 to H1)



Petrographic Examination Natural Stone— BS EN 12407:2007




**Description**

View through the stained section of the sample, showing stylolite rich in opaque minerals (black: A10 to H1, A11 to B12 and G6 to I7).

The reddish brown colours (F3) observed throughout the field of view are due to the staining compound used and not due to oxidation.

Test Report Ref.: 447907 – Page 7 of 8

Petrographic Examination Natural Stone– BS EN 12407:2007



**Description**

Closer view of the section through a stylolite, showing apparent framboidal pyritic grains (black, bras coloured: E5, F6 and G4).

Petrographic Examination Natural Stone– BS EN 12407:2007

Glossary of Terms Used in the Descriptions

Proportions	Major: constituent present at a level $\geq 10\%$ ; Minor: constituent present at level $\geq 2\%$ but $< 10\%$ ; Trace: constituent present at $< 2\%$ level
Frequency	<ul style="list-style-type: none"> <li>Rare – only found by thorough searching</li> <li>Sporadic – only occasionally observed during normal examination</li> <li>Common – easily observed during normal examination</li> <li>Frequent – easily observed with minimal examination</li> <li>Abundant – immediately apparent to initial examination</li> </ul>
Hardness	<ul style="list-style-type: none"> <li>Very soft: can be penetrated easily by a finger</li> <li>Soft: scores with a fingernail</li> <li>Moderately soft: scores using a copper coin</li> <li>Moderately hard: scores easily with a penknife</li> <li>Hard: not easily scored with a penknife</li> <li>Very hard: cannot be scored with a steel point or knife.</li> </ul>
Weathering/alteration	<ul style="list-style-type: none"> <li>Grade I (Fresh): Unchanged from original state</li> <li>Grade II (Slightly Weathered): Slight discoloration, slight weakening;</li> <li>Grade III (Moderately Weathered): Considerably weakened, penetrative discoloration, large pieces cannot be broken by hand</li> <li>Grade IV (Highly Weathered): large pieces can be broken by hand, does not readily disaggregate (slake) when dry sample immersed in water</li> <li>Grade V (Completely Weathered): considerably weakened, slakes, original texture apparent; Grade VI (Residual Soil)</li> <li>Soil derived by in-situ weathering but retaining none of the original texture or fabric.</li> </ul>
Origin	<ul style="list-style-type: none"> <li>Primary constituents: Constituents present within the rock at its formation.</li> <li>Secondary constituents: Constituents formed by the alteration of pre-existing primary constituents or introduced from an external source after the rock was formed</li> </ul>
Size	Mega: $> 60\text{mm}$ ; Macro: $2\text{--}60\text{mm}$ ; Meso: $60\mu\text{m}\text{--}2\text{mm}$ ; Micro: $2\text{--}60\mu\text{m}$ ; Crypto: $< 2\mu\text{m}$ ; Glassy: without visible crystallinity
Bedding/Layering	Thick: $> 600\text{mm}$ ; Medium: $200\text{--}600\text{mm}$ ; Thin: $60\text{--}200\text{mm}$ ; Very thin: $20\text{--}60\text{mm}$
Lamination	Thick: $6\text{--}20\text{mm}$ ; Thin: $2\text{--}6\text{mm}$ ; Very thin: $600\mu\text{m}\text{--}2\text{mm}$ ; Extremely thin: $< 600\mu\text{m}$
Cleavage	Extremely wide: $> 2\text{mm}$ ; Very wide: $600\mu\text{m}\text{--}2\text{mm}$ ; Wide: $200\text{--}600\mu\text{m}$ ; Medium: $60\text{--}200\mu\text{m}$ ; Close: $20\text{--}60\mu\text{m}$ ; Very close: $6\text{--}20\mu\text{m}$ ; Extremely close: $< 6\mu\text{m}$ .
Cracks	<ul style="list-style-type: none"> <li>Fine microcracks (<math>&lt; 1\mu\text{m}</math> wide)</li> <li>Microcracks (<math>1\text{--}10\mu\text{m}</math> wide)</li> <li>Fine cracks (<math>10\text{--}100\mu\text{m}</math> wide)</li> <li>Cracks (<math>100\mu\text{m}\text{--}1\text{mm}</math> wide)</li> <li>Large cracks (<math>&gt; 1\text{mm}</math> wide).</li> </ul>
Colour	Description based on geological rock-color chart, produced by Munsell Color, 2009 Revised, 2011 Production.
Limestone Classification Schemes	<p>Folk, R. L. 1959. Practical petrographic classification of limestones. <i>Bull. Am. Ass. Petro. Geol.</i> 43, 1-38.</p> <p>Dunham, R. J. 1962. Classification of carbonate rocks according to depositional texture. In: <i>Classification of Carbonate Rocks</i> (Ed. By W. E. Ham), pp. 108-121. <i>Mem. Am. Ass. Petrol. Geol.</i> 1, Tulsa.</p>



Priority Drilling Ltd.  
Killimor  
Ballinasloe  
Co Galway  
Ireland  
8D23036i

Date: 6<sup>th</sup> April 2016  
Test Report Ref.: 447934

Page 1 of 9

## **LABORATORY TEST REPORT**

**Test Requirements:** Petrographic Examination of Natural Stone in accordance with  
BS EN 12047:2007

### **Sample details:**

Certificate of sampling received:	<b>No</b>
Laboratory Ref. No:	<b>S56595</b>
Client Ref. No:	<b>BH01 - 50926</b>
Date and Time of Sampling:	<b>Unknown</b>
Date of Receipt at Lab:	<b>18/01/2016</b>
Date of Start of Test.:	<b>18/03/2016</b>
Sampling Location:	<b>Depth Top:148.97 Depth Base:149.05</b>
Name of Source:	<b>Lackagh Quarry</b>
Method of Sampling:	<b>Unknown</b>
Sampled By:	<b>Client</b>
Material Description:	<b>Rock Testing</b>
Target Specification:	<b>N/A</b>

### **COMMENTS/ DEPARTURE FROM SPECIFIED PROCEDURE**

The work was carried out by our accredited, competent, sub contracted laboratory.

### **RESULTS**

See Attached



Nick Dumbarton – Assistant Laboratory Manager

Petrographic Examination Natural Stone– BS EN 12407:2007

**HAND SPECIMEN DESCRIPTION**

The sample was a moderately hard, fine to very coarse grained, not macroporous limestone. The sample was anisotropic. The sample exhibited medium grey to greyish black variously thick band/layers, unevenly distributed white bioclastic calcite materials up to 8mm across and a large irregular pyritic material up to approximated 2mm across. The sample also exhibited sporadic, randomly distributed and randomly orientated calcite veins up to <200µm across.

**MICROSCOPICAL DESCRIPTION**

Constituents <sup>1</sup>	Visual Estimated Proportions <sup>2</sup> %	Range of Crystal/Grain Size	Petrographic Details	Origin
Calcite	97	Up to 1600µm	Fresh, anhedral to euhedral crystals comprising significant amounts of both microcrystalline calcite (calcite crystals <4µm) and sparry calcite (calcite crystals >4µm), with minor proportion of discrete calcium carbonate grains that appeared to have replaced bioclasts. The bioclasts chiefly comprised both microcrystalline calcite and sparry calcite.  The sample was partially stained in accordance with Dickson's method. The result of the staining process suggests that the calcite was chiefly non-ferroan	Primary
Opaque minerals	1-2	Up to 2000µm	Fresh, chiefly anhedral isotropic minerals apparently comprising almost entirely framboidal, probably pyritic grains. Scanning electron microscopy (SEM) should be used if necessary for better resolution and description of the opaque minerals.	Primary
Clay materials	1-2	<4µm	Very fine grained materials associated with abundant microcrystalline calcite, thus beyond the conclusive resolution of the petrographic microscope. This could be investigated further by scanning electron microscopy (SEM).	Primary

The sample was a fine to very coarse grained bioclastic LIMESTONE, comprising almost entirely calcium carbonate, with trace to minor proportions of opaque minerals, and trace to minor proportions of potentially clay minerals that were beyond the resolution of the petrographic microscope.

The limestone also exhibited abundant intraclasts (apparently reworked limestone fragments probably from nearby sediments).

The greyish black bands/layers appeared brecciated as they comprised limestone fragments and discrete calcite grains cemented by very fine grained matrix comprising chiefly microcrystalline calcite, with trace to minor proportions of opaque minerals and possibly trace to minor proportions of clay materials.

No void was observed. The void content was visually estimated as being 0%.


The sample was fresh and exhibited Grade I weathering.



Test Report Ref.: 447934 – Page 3 of 9

Petrographic Examination Natural Stone– BS EN 12407:2007

Profile view of the sample as received



Profile view of another side of the sample as received



Test Report Ref.: 447934 – Page 4 of 9

Petrographic Examination Natural Stone– BS EN 12407:2007




**Description**

View of a section through a part-stained section of the sample, showing bioclasts (pink, pale pink, light brown, purple/green: A3, A11, B5, D5, E6 and E11) and calcite vein (light brown/pale pink/white: C12 to H1).



Test Report Ref.: 447934 – Page 5 of 9

Petrographic Examination Natural Stone— BS EN 12407:2007




**Description**

View through a typical medium grey section of the sample, showing bioclasts (pale pink, light brown, pale yellow: D3, D5, D7, D8, D12 and H5) cemented by chiefly microcrystalline calcite (brownish grey: E9).

An apparent intraclasts are highlighted in yellow.

Test Report Ref.: 447934 – Page 6 of 9

Petrographic Examination Natural Stone– BS EN 12407:2007




**Description**

View of a section through a greyish black band/layer, showing apparent limestone fragments (pale pink, light brown, pale yellow: A5, C1, D2, D7, D11, G7 and G9), cemented by very fine grained matrix (dusky brown: A8, E5 and H12).



Test Report Ref.: 447934 – Page 7 of 9

Petrographic Examination Natural Stone– BS EN 12407:2007



**Description**

Closer view through the matrix of the greyish black section of the sample, showing very fine grained materials beyond the conclusive resolution of the petrographic microscope. Opaque minerals appear black (A5 and E6). The remainder of the field of view appear to comprise both microcrystalline calcite and possibly some clay minerals.

The moderate red colour (D9) observed throughout the photomicrograph are due to the staining compound used and not due to oxidation.

Test Report Ref.: 447934 – Page 8 of 9

Petrographic Examination Natural Stone– BS EN 12407:2007



**Description**

Closer view of the section through the sample, showing framboidal pyritic grains (brass colour: C7 and G5).

## Petrographic Examination Natural Stone– BS EN 12407:2007

### Glossary of Terms Used in the Descriptions

Proportions	Major: constituent present at a level $\geq 10\%$ ; Minor: constituent present at level $\geq 2\%$ but $< 10\%$ ; Trace: constituent present at $< 2\%$ level
Frequency	<ul style="list-style-type: none"> <li>Rare – only found by thorough searching</li> <li>Sporadic – only occasionally observed during normal examination</li> <li>Common – easily observed during normal examination</li> <li>Frequent – easily observed with minimal examination</li> <li>Abundant – immediately apparent to initial examination</li> </ul>
Hardness	<ul style="list-style-type: none"> <li>Very soft: can be penetrated easily by a finger</li> <li>Soft: scores with a fingernail</li> <li>Moderately soft: scores using a copper coin</li> <li>Moderately hard: scores easily with a penknife</li> <li>Hard: not easily scored with a penknife</li> <li>Very hard: cannot be scored with a steel point or knife.</li> </ul>
Weathering/ alteration	<ul style="list-style-type: none"> <li>Grade I (Fresh): Unchanged from original state</li> <li>Grade II (Slightly Weathered): Slight discoloration, slight weakening;</li> <li>Grade III (Moderately Weathered): Considerably weakened, penetrative discoloration, large pieces cannot be broken by hand</li> <li>Grade IV (Highly Weathered): large pieces can be broken by hand, does not readily disaggregate (slake) when dry sample immersed in water</li> <li>Grade V (Completely Weathered): considerably weakened, slakes, original texture apparent; Grade VI (Residual Soil)</li> <li>Soil derived by in-situ weathering but retaining none of the original texture or fabric.</li> </ul>
Origin	<ul style="list-style-type: none"> <li>Primary constituents: Constituents present within the rock at its formation.</li> <li>Secondary constituents: Constituents formed by the alteration of pre-existing primary constituents or introduced from an external source after the rock was formed</li> </ul>
Size	Mega: $> 60\text{mm}$ ; Macro: $2\text{--}60\text{mm}$ ; Meso: $60\mu\text{m--}2\text{mm}$ ; Micro: $2\text{--}60\mu\text{m}$ ; Crypto: $< 2\mu\text{m}$ ; Glassy: without visible crystallinity
Bedding/Layering	Thick: $> 600\text{mm}$ ; Medium: $200\text{--}600\text{mm}$ ; Thin: $60\text{--}200\text{mm}$ ; Very thin: $20\text{--}60\text{mm}$
Lamination	Thick: $6\text{--}20\text{mm}$ ; Thin: $2\text{--}6\text{mm}$ ; Very thin: $600\mu\text{m--}2\text{mm}$ ; Extremely thin: $< 600\mu\text{m}$
Cleavage	Extremely wide: $> 2\text{mm}$ ; Very wide: $600\mu\text{m--}2\text{mm}$ ; Wide: $200\text{--}600\mu\text{m}$ ; Medium: $60\text{--}200\mu\text{m}$ ; Close: $20\text{--}60\mu\text{m}$ ; Very close: $6\text{--}20\mu\text{m}$ ; Extremely close: $< 6\mu\text{m}$ .
Cracks	<ul style="list-style-type: none"> <li>Fine microcracks (<math>&lt; 1\mu\text{m}</math> wide)</li> <li>Microcracks (<math>1\text{--}10\mu\text{m}</math> wide)</li> <li>Fine cracks (<math>10\text{--}100\mu\text{m}</math> wide)</li> <li>Cracks (<math>100\mu\text{m--}1\text{mm}</math> wide)</li> <li>Large cracks (<math>&gt; 1\text{mm}</math> wide).</li> </ul>
Colour	Description based on geological rock-color chart, produced by Munsell Color, 2009 Revised, 2011 Production.
Limestone Classification Schemes	<p>Folk, R. L. 1959. Practical petrographic classification of limestones. <i>Bull. Am. Ass. Petro. Geol.</i> 43, 1-38.</p> <p>Dunham, R. J. 1962. Classification of carbonate rocks according to depositional texture. In: <i>Classification of Carbonate Rocks</i> (Ed. By W. E. Ham), pp. 108-121. <i>Mem. Am. Ass. Petro. Geol.</i> 1, Tulsa.</p>

## Total Sulphur



Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447855

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Total Sulfur Content of an Aggregate Sample  
in accordance with **BS EN 1744-1 : 2009 : Clause 11**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	BH01 - 48891
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	19/02/2016
Sampling Location:	Depth Top:53.80 Depth Base:453.93
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

<b>Total Sulfur Content as S (%) =</b>	<b>&lt;0.1</b>
<i>95% Confidence limit*</i>	<i>&lt;0.06% - &lt;0.14%</i>

#### **Comments / Departure from specified Procedure**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate  
Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447867

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Total Sulfur Content of an Aggregate Sample  
in accordance with **BS EN 1744-1 : 2009 : Clause 11**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	BH01 - 50859
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	17/02/2016
Sampling Location:	Depth Top:65.40 Depth Base:65.50
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

<b>Total Sulfur Content as S (%) =</b>	<b>&lt;0.1</b>
<i>95% Confidence limit*</i>	<i>&lt;0.06% - &lt;0.14%</i>

#### **Comments / Departure from specified Procedure**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447887

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Total Sulfur Content of an Aggregate Sample  
in accordance with **BS EN 1744-1 : 2009 : Clause 11**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	BH01 - 50879
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	19/02/2016
Sampling Location:	Depth Top:91.10 Depth Base:91.20
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

<b>Total Sulfur Content as S (%) =</b>	<b>&lt;0.1</b>
<i>95% Confidence limit*</i>	<i>&lt;0.06% - &lt;0.14%</i>

#### **Comments / Departure from specified Procedure**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447937

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Total Sulfur Content of an Aggregate Sample  
in accordance with **BS EN 1744-1 : 2009 : Clause 11**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	BH01 - 50929
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	17/02/2016
Sampling Location:	Depth Top:152.97 Depth Base:153.04
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

<b>Total Sulfur Content as S (%) =</b>	<b>&lt;0.1</b>
<i>95% Confidence limit*</i>	<i>&lt;0.06% - &lt;0.14%</i>

#### **Comments / Departure from specified Procedure**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 447965

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Total Sulfur Content of an Aggregate Sample  
in accordance with **BS EN 1744-1 : 2009 : Clause 11**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	BH01 - 50955
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	17/02/2016
Sampling Location:	Depth Top:193.60 Depth Base:193.68
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

<b>Total Sulfur Content as S (%) =</b>	<b>&lt;0.1</b>
<i>95% Confidence limit*</i>	<i>&lt;0.06% - &lt;0.14%</i>

#### **Comments / Departure from specified Procedure**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 16 March 2016  
Test Report Ref: STR 448000

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Total Sulfur Content of an Aggregate Sample  
in accordance with **BS EN 1744-1 : 2009 : Clause 11**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. No:	BH01 - 50990
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	17/02/2016
Sampling Location:	Depth Top:235.64 Depth Base:235.73
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Testing
Target Specification:	N/A

#### **RESULTS:**

<b>Total Sulfur Content as S (%) =</b>	<b>&lt;0.1</b>
<i>95% Confidence limit*</i>	<i>&lt;0.06% - &lt;0.14%</i>

#### **Comments / Departure from specified Procedure**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443067

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Total Sulfur Content of an Aggregate Sample  
in accordance with **BS EN 1744-1 : 2009 : Clause 11**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. No:	BH04 - 48954
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	21/12/2015
Sampling Location:	Depth Top: 31.66 Depth Base: 31.7
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

<b>Total Sulfur Content as S (%) =</b>	<b>&lt;0.1</b>
<i>95% Confidence limit*</i>	<i>&lt;0.06% - &lt;0.14%</i>

#### **Comments / Departure from specified Procedure**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Priority Construction Ltd  
162 Clontarf Road

Date: 15 February 2016  
Test Report Ref: STR 443131

Dublin 3  
Ireland  
VAT No: 9D539711  
Contract: Lackagh Quarry

Page 1 of 1

### **LABORATORY TEST REPORT**

#### **TEST REQUIREMENTS:**

To determine the Total Sulfur Content of an Aggregate Sample  
in accordance with **BS EN 1744-1 : 2009 : Clause 11**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. No:	BH05 - 50715
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	21/12/2015
Sampling Location:	Depth Top: 29.09 Depth Base: 29.18
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

<b>Total Sulfur Content as S (%) =</b>	<b>&lt;0.1</b>
<i>95% Confidence limit*</i>	<i>&lt;0.06% - &lt;0.14%</i>

#### **Comments / Departure from specified Procedure**

\*95% Confidence limit is the expanded uncertainty which is the combined uncertainty standard multiplied by a factor (k) of 2

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager



**UCS**

Priority Drilling Ltd,  
Killimor,  
Ballinasloe,  
Co. Galway,  
Ireland

Date: 10 March 2016  
Test Report Ref: STR 447821a  
Revision 1

Page 1 of 2

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Uniaxial Compressive Strength in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56595
Client Ref. :	Various
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	18/01/2016
Date of Start of Test:	18/01/2016
Sampling Location:	Various
Name of Source:	Lackagh Quarry
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Rock Cores
Target Specification:	N/A

#### **RESULTS:**

See attached

Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Test Report Ref: STR 447821a - Page 2 of 2

BH	Core Diameter (mm)	Height/ Diameter Ratio	Uniaxial compressive strength (MPa)	Mode of Failure	EN ISO 14689-1 Term	Water content (%)
BH01 48863	60.7	3.5:1	97	N	Strong	0.3
Bh01 48870	60.8	3.5:1	59	N	Strong	0.2
BH01 48873	60.7	3.5:1	73	N	Strong	0.1
BH01 48878	60.7	3:1	100	N	Strong	0.1
BH01 48883	60.7	3:1	69	N	Strong	0.3
BH01 48887	60.7	3:1	83	N	Strong	0.2
BH01 50943	60.8	3:1	76	N	Strong	0.1
BH01 48895	61	3.4:1	138	N	Very Strong	0.3
BH01 48900	60.8	2.5:1	65	N	Strong	0.1
BH01 50863	60.6	1.7:1	104	N	Very Strong	0.2
BH01 50873	60.7	3:1	62	N	Strong	0.2
BH01 50884	60.6	3:1	76	N	Strong	0.2
BH01 50894	60.7	3.4:1	107	N	Very Strong	0.2
BH01 50902	60.7	3:1	104	N	Very Strong	0.1
BH01 50909	60.8	2.1:1	79	N	Strong	0.2
Bh01 50915	60.8	3.1:1	110	N	Very Strong	0.3
Bh01 50924	60.7	1.4:1	100	N	Very Strong	0.2
BH01 50934	60.7	3.1:1	86	N	Strong	0.4
BH01 50938	60.6	3.4:1	83	N	Strong	0.2
BH01 50945	60.8	3.4:1	86	N	Strong	0.2
BH01 50952	60.6	3.2:1	97	N	Strong	0.5
BH01 50958	60.8	3.2:1	114	N	Very Strong	0.3
BH01 50963	60.6	3.1:	132	N	Very Strong	0.2
BH01 50968	60.6	3.3:1	111	N	Very Strong	0.1
BH01 50971	60.5	3.5:1	52	N	Strong	0.3
BH01 50980	60.5	2.8:1	77	N	Strong	0.2
BH01 50986	60.5	3:1	111	N	Very Strong	0.4
BH01 50991	60.6	3.5:1	80	N	Strong	0.2
BH01 50992	60.6	2.3:1	76	N	Strong	0.2
BH01 50994	60.6	3:1	118	N	Very Strong	0.2
BH01 50998	60.7	2.1:1	121	N	Very Strong	0.3
BH01 51002	60.4	3.3:1	143	N	Very Strong	0.2

BH01 51004	60.4	2.6:	<b>66</b>	N	Strong	0.2
BH01 51007	60.8	2.5:1	<b>83</b>	N	Strong	0.3
BH01 51010	60.6	2.5:1	<b>90</b>	N	Strong	0.3
BH01 51011	60.3	2.9:1	<b>91</b>	N	Strong	0.2

### Comments

- 1) The uniaxial compressive strength was carried out in accordance with ISRM guidelines.
- 2) Stress Rate: 0.7Mpa/s.

3)

EN ISO 14689-1 : 2003 Rock Strength Terms	
Compressive Strength mpa	Term
<1.0	Extremely Weak
1 to 5	Very Weak
5 to 25	Weak
25 to 50	Meduim Strong
50 to 100	Strong
100 to 250	Very Strong
> 250	Extremely Strong

Priority Construction Ltd  
162 Clontarf Road

Date: 21 December 2015  
Test Report Ref: STR 443020

Dublin 3  
Ireland

VAT No: 9D53971I

Page 1 of 2

Contract: Lackagh Quarry

### **LABORATORY TEST REPORT**

**TEST REQUIREMENTS:** To determine the Uniaxial Compressive Strength in accordance with  
**ISRM Guidelines**

#### **SAMPLE DETAILS:**

Certificate of sampling received:	No
Laboratory Ref. No:	S56158
Client Ref. :	Various
Date and Time of Sampling:	Unknown
Date of Receipt at Lab:	08/12/2015
Date of Start of Test:	08/12/2015
Sampling Location:	Various
Name of Source:	Lackagh Quarry SI
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	Core
Target Specification:	N/A

#### **RESULTS:**

See attached


Certificate

Prepared by:-



Mathew Sayer  
Assistant Laboratory Manager

Approved by: -



Eric Goulden  
Technical Manager

Test Report Ref: STR 443020 - Page 2 of 2

BH	Core Diameter (mm)	Height/ Diameter Ratio	Uniaxial compressive strength (MPa)	Mode of Failure	EN ISO 14689-1 Term	Water content (%)
BH04 48908	82	2.6:1	76	N	Strong	0.1
BH04 48912	82.3	1.9:1	86	N	Strong	0.3
BH04 48921	82.3	1.5:1	55	N	Strong	0.1
BH04 48927	82.1	1.6:1	53	N	Strong	0.2
BH04 48931	82.2	2.6:1	111	N	Very Strong	0.1
BH04 48933	82	2.1:1	91	N	Strong	0.2
BH04 48950	82	2.5:1	76	N	Strong	0.2
BH04 48957	82	2:1	78	N	Strong	0.3
BH04 48963	82.2	2.4:1	92	N	Strong	0.1
BH05 48982	82	1.8:1	91	N	Strong	0.2
BH05 48986	81.5	2.6:1	86	N	Strong	0.4
BH05 48991	81.4	2.5:1	94	N	Strong	0.1
BH05 48994	82	1.9:1	72	N	Strong	0.2
BH05 48998	82.2	2.6:1	77	N	Strong	0.2
BH05 50711	78.5	1.8:1	79	N	Strong	0.2
BH05 50729	79	2.5:1	116	N	Very Strong	0.3
BH05 50731	81.4	2.6:1	51	N	Strong	0.1
BH05 50733	81.6	2.1:1	54	N	Strong	0.2
BH05 50737	82	1.5:1	131	N	Very Strong	0.2

### Comments

- 1) The uniaxial compressive strength was carried out in accordance with ISRM guidelines.
- 2) Stress Rate: 0.7Mpa/s.

- 3)

EN ISO 14689-1 : 2003 Rock Strength Terms	
Compressive Strength mpa	Term
<1.0	Extremely Weak
1 to 5	Very Weak
5 to 25	Weak
25 to 50	Meduim Strong
50 to 100	Strong
100 to 250	Very Strong
> 250	Extremely Strong

## Water Tests

# Test Report

<b>Lab Report Number:</b> 2165101		<b>Analysis Number:</b> 99A/89470	
<b>Customer ID:</b>	BRG.L1	<b>Analysis Type:</b>	Misc. Tests (99A)
<b>Contact Name:</b>	DAVID BLANEY	<b>Delivery By:</b>	An Post
<b>Company Name:</b>	BRG LTD	<b>Sample Card Number:</b>	AAAQ1194/3
<b>Address:</b>	8B UNIT 3 ATHY BUSINESS CAMPUS ATHY CO KILDARE	<b>Sample Condition:</b>	Acceptable
<b>Sample Type:</b>	Ground Water	<b>Date Sample Received:</b>	15/03/2016
<b>Sample Reference:</b>	GROUND WATER	<b>Date Analysis Commenced:</b>	15/03/2016
<b>Sample Description:</b>	BH-04	<b>Date Certificate Issued:</b>	29/03/2016

Parameter	Method	Result	Unit
Calcium	ICP-MS	82.9	mg/l
Chloride	Konelab Aquakem SOP 2065	32.10	mg/l
Potassium	ICP-MS	0.94	mg/l
Magnesium	ICP-MS	2.50	mg/l
Sodium	ICP-MS	17.1	mg/l
Nitrite	Konelab Aquakem SOP 2059	<0.03	mg/l NO2
Sulphate	Konelab Aquakem SOP 2062	6.26	mg/l SO4

Signed: Wendy McCall  
**Wendy McCall - Laboratory Manager**

Date: 29/03/2016

\* = not INAB Accredited    ^ = Subcontracted

This report must not be reproduced, except in full, without the prior written approval of IAS Laboratories. This report relates only to the sample submitted. Opinions and interpretations expressed herein are outside the scope of INAB accreditation. Uncertainty of Measurement has been calculated for all INAB accredited tests and is available upon request.





# Test Report

Lab Report Number: 2165102

Analysis Number: 99A/89471

<b>Customer ID:</b>	BRG.L1	<b>Analysis Type:</b>	Misc. Tests (99A)
<b>Contact Name:</b>	DAVID BLANEY	<b>Delivery By:</b>	An Post
<b>Company Name:</b>	BRG LTD	<b>Sample Card Number:</b>	AAAQ1194/3
<b>Address:</b>	8B UNIT 3 ATHY BUSINESS CAMPUS ATHY CO KILDARE	<b>Sample Condition:</b>	Acceptable
<b>Sample Type:</b>	Ground Water	<b>Date Sample Received:</b>	15/03/2016
<b>Sample Reference:</b>	GROUND WATER	<b>Date Analysis Commenced:</b>	15/03/2016
<b>Sample Description:</b>	BH-05	<b>Date Certificate Issued:</b>	29/03/2016

Parameter	Method	Result	Unit
Calcium	ICP-MS	92.6	mg/l
Chloride	Konelab Aquakem SOP 2065	25.38	mg/l
Potassium	ICP-MS	6.26	mg/l
Magnesium	ICP-MS	2.98	mg/l
Sodium	ICP-MS	14.4	mg/l
Nitrite	Konelab Aquakem SOP 2059	0.03	mg/l NO2
Sulphate	Konelab Aquakem SOP 2062	15.41	mg/l SO4

Signed: Wendy McCall  
**Wendy McCall - Laboratory Manager**

Date: 29/03/2016

\* = not INAB Accredited    ^ = Subcontracted

This report must not be reproduced, except in full, without the prior written approval of IAS Laboratories. This report relates only to the sample submitted. Opinions and interpretations expressed herein are outside the scope of INAB accreditation. Uncertainty of Measurement has been calculated for all INAB accredited tests and is available upon request.



# Test Report

<b>Lab Report Number:</b> 2165103		<b>Analysis Number:</b> 99A/89472	
<b>Customer ID:</b>	BRG.L1	<b>Analysis Type:</b>	Misc. Tests (99A)
<b>Contact Name:</b>	DAVID BLANEY	<b>Delivery By:</b>	An Post
<b>Company Name:</b>	BRG LTD	<b>Sample Card Number:</b>	AAAQ1194/3
<b>Address:</b>	8B UNIT 3 ATHY BUSINESS CAMPUS ATHY CO KILDARE	<b>Sample Condition:</b>	Acceptable
<b>Sample Type:</b>	Ground Water	<b>Date Sample Received:</b>	15/03/2016
<b>Sample Reference:</b>	GROUND WATER	<b>Date Analysis Commenced:</b>	15/03/2016
<b>Sample Description:</b>	BH-06	<b>Date Certificate Issued:</b>	29/03/2016

Parameter	Method	Result	Unit
Calcium	ICP-MS	430.1	mg/l
Chloride	Konelab Aquakem SOP 2065	152.22	mg/l
Potassium	ICP-MS	39.3	mg/l
Magnesium	ICP-MS	<0.5	mg/l
Sodium	ICP-MS	306.1	mg/l
Nitrite	Konelab Aquakem SOP 2059	1.02	mg/l NO2
Sulphate	Konelab Aquakem SOP 2062	36.32	mg/l SO4

Signed:

*Wendy McCall*

Date: 29/03/2016

**Wendy McCall - Laboratory Manager**

\* = not INAB Accredited    ^ = Subcontracted

This report must not be reproduced, except in full, without the prior written approval of IAS Laboratories. This report relates only to the sample submitted. Opinions and interpretations expressed herein are outside the scope of INAB accreditation. Uncertainty of Measurement has been calculated for all INAB accredited tests and is available upon request.



## APPENDIX VIII

# Monitoring Well Sampling Log

**Well Number: BH-04**

## Project Details

Project No.:	Lackagh	Location (GPS):	530150 728400
Date:	12-3-16	Sampler:	Ronan Doyle

## Sample Details

Well No.:	BH-04	Measurement Point:	TOR
Stick Up:		T.O.C Elevation:	
Water Level:	19.65m	Well Depth:	33.06m
Head:	13.41m	Well Diameter:	
Volume in Well (L):		Volume Purged (L):	Pumped for 1 hr
Decon. Procedure:		Bailer Type:	Watterra Pump
Containers Used:			

## Field Parameters

Observed Colour:	Brown Tint	Odour:	None
Temperature (°C):	10.5C	Conductivity (µS):	295
pH:	7.47	pH MV:	-58mv ORP=231mv

## Comments

DO=0.21mg/l 1.8%

Ronan Doyle Monitoring Solutions,  
Castlebar Road, Ballinrobe, County Mayo.



# Monitoring Well Sampling Log

**Well Number: BH-05**

## Project Details

Project No.:	Lackagh	Location (GPS):	530186 728378
Date:	12-3-16	Sampler:	Ronan Doyle

## Sample Details

Well No.:	BH-05	Measurement Point:	TOR
Stick Up:		T.O.C Elevation:	
Water Level:	21.70m	Well Depth:	39.53m
Head:	17.83m	Well Diameter:	
Volume in Well (L):		Volume Purged (L):	Pumped for 1 hr
Decon. Procedure:		Bailer Type:	Watterra Pump
Containers Used:			

## Field Parameters

Observed Colour:	Brown Tint	Odour:	None
Temperature (°C):	10.5C	Conductivity (µS):	420
pH:	7.77	pH MV:	-74.8mv ORP=216.9mv

## Comments

DO=0.8mg/l 9.2%

**Ronan Doyle Monitoring Solutions,**

Castlebar Road, Ballinrobe, County Mayo.





# Monitoring Well Sampling Log

**Well Number: BH-06**

## Project Details

Project No.:	Lackagh	Location (GPS):	530125 728383
Date:	12-3-16	Sampler:	Ronan Doyle

## Sample Details

Well No.:	BH-06	Measurement Point:	TOR
Stick Up:		T.O.C Elevation:	
Water Level:	4.02m	Well Depth:	7.48m
Head:	3.46m	Well Diameter:	
Volume in Well (L):		Volume Purged (L):	Pumped for 30min
Decon. Procedure:		Bailer Type:	Watterra Pump
Containers Used:			

## Field Parameters

Observed Colour:	Milky brown	Odour:	None
Temperature (°C):	9.8C	Conductivity (µS):	6187
pH:	12.53	pH MV:	-333mv ORP=51.7mv

## Comments

DO=0.8mg/l 9.4%

**Ronan Doyle Monitoring Solutions,**

Castlebar Road, Ballinrobe, County Mayo.



## APPENDIX IX

**Borehole ID**

**BH5**

**Water Level Start**

**19.45m**

**Water volume inserted**

**215 ltrs**

Time (min)	Water Level (m)
1	18.1
1.5	18.52
2	18.82
2.5	19
3	19.14
3.5	19.22
4	19.26
4.5	19.29
5	19.31
5.5	19.32
6	19.33
8	19.35
11	19.38
14	19.39
18	19.4
22	19.405
26	19.41
30	19.41
34	19.415
40	19.42



**Borehole ID**

**BH5**

**Water Level Start**

**19.42m**

**Water volume inserted**

**1000 ltrs**

Time (min)	Water Level (m)	Comments
1	17.62	
1.5	18.22	
2	18.51	
2.5	18.74	
3	18.93	
3.5	19.04	
4	19.11	
4.5	19.17	
5	19.21	
5.5	19.24	
6	19.26	
6.5	19.28	
7.5	19.29	
9	19.31	
12	19.33	
14	19.335	
17	19.34	
20	19.345	
24	19.345	
30	19.35	
40	19.34	Could feel material in the hole test stopped - driller reports clearing clay after test in order to install piezometer.

## APPENDIX X

## BH04 - Packer Test 18/12/15

Depth Top	Bottom	Midpoint	Packer Pressure (psi)	Pressure (psi)	Flow (litres)	Time minutes										Total	
						1	2	3	4	5	6	7	8	9	10		
28	30	29	175	49	↓	59	113	168	225	282	343	399	456	518	579	Total	Unable to continue at
						59	57	56	56	56	57	57	57	58	58	I/m	
24	26	25	175	50		18.5	35	52	70	86	103	121	138	155.6	174	Total	
						19	18	17	18	17	17	17	17	17	17	I/m	
				65		29	58	87	117	147	176	207	236	267	297	Total	
						29	29	29	29	29	29	30	30	30	30	I/m	
				84		44	89	134	179	224	270	316	363	410	456	Total	
						44	45	45	45	45	45	45	45	46	46	I/m	
				65		32	73	113	152	193	232	273	313	354	395	Total	
						32	37	38	38	39	39	39	39	39	40	I/m	
				50		34	67	101	135	169	202	236	270	303	337	Total	
						34	34	34	34	34	34	34	34	34	34	I/m	
21	23	22	175	40		60	120	179	237	296	355	414	473	533	591	Total	Unable to continue at
						60	60	60	59	59	59	59	59	59	59	I/m	
				50		67	134	200	266	331	397	464	530	576	662	Total	
						67	67	67	67	66	66	66	66	64	66	I/m	
18	20	19	160	40		20	42	66	91	115	140	164	189	214	240	Total	
						20	21	22	23	23	23	23	24	24	24	I/m	
				60		31	64	96	128	160	192	225	257	289	322	Total	
						31	32	32	32	32	32	32	32	32	32	I/m	
				80		37	75	113	152	190	228	267	306	345	383	Total	
						37	38	38	38	38	38	38	38	38	38	I/m	
				60		33	66	99	132	165	198	231	264	297	328	Total	
						33	33	33	33	33	33	33	33	33	33	I/m	
				40		25	50	75	101	126	150	175	200	224	249	Total	
						25	25	25	25	25	25	25	25	25	25	I/m	

## BH05 - Packer Test 6/1/16

Water Depth Start 19.26m Finish 19.2

Depth Top	Bottom	Midpoint	Packer Pressure (psi)	Pressure (psi)	Flow (litres)	Time minutes →										
						1	2	3	4	5	6	7	8	9	10	
36	38	37	160	30		58.9	117.1	176.1	234.4	292.9	350.1	408.7	466.7	524.9	581.7	Total
						59	59	59	59	59	58	58	58	58	58	I/m
					45	70.1	139.9	209.1	279.1	348.7	417.9	485.1	554.6	620.5	686.1	Total
						70	70	70	70	70	70	69	69	69	69	I/m
					60	76.8	153.7	231.2	304.4	383.7	461.5	537.7	613.7	691.6	768.4	Total
						77	77	77	76	77	77	77	77	77	77	I/m
					45	73	145.7	212.8	278.1	351.5	421.4	493.3	564.4	634.6	705.9	Total
						73	73	71	70	70	70	70	71	71	71	I/m
					30	64.2	128.6	192.7	256.3	319.1	383.6	448.5	513.7	576.7	641.5	Total
						59	59	59	59	59	58	58	58	58	58	I/m
30	32	31	175	30		54.2	110.3	166.4	222.2	278.7	335.7	392.4	448.1	505.2	561.7	Total
						54	55	55	56	56	56	56	56	56	56	I/m
					45	67.3	135.1	204.1	273.5	342.4	411.7	481.2	530.4	619.3	688.1	Total
						67	68	68	68	68	69	69	66	69	69	I/m
					60	78.7	155.8	234.8	311.7	390.1	468.4	546.7	633.5	701.3	779.4	Total
						79	78	78	78	78	78	78	79	78	78	I/m
					45	69.7	139.7	209.6	286.5	346.5	414.5	481.7	550.7	621.8	693	Total
						70	70	70	72	69	69	69	69	69	69	I/m
					30	61.1	122.4	184.7	247.5	309.7	372.5	435.1	498.3	563.5	626.7	Total
						61	61	62	62	62	62	62	62	63	63	I/m
24	27	25.5	175	30		54.1	111.4	166.5	222.3	277	332.4	387.4	462.1	497.1	551.7	Total
						54	56	56	56	55	55	55	58	55	55	I/m
					45	67.1	135.4	200.4	268.2	335.3	402.1	468.3	535.3	602.7	667.1	Total
						67	68	67	67	67	67	67	67	67	67	I/m
					60	77.3	153.7	231.2	308.9	385.7	463.7	540.1	617.5	695	772.6	Total
						77	77	77	77	77	77	77	77	77	77	I/m
					45	65.6	130.5	196.3	261.1	326.7	391.6	457.5	512.9	587.2	652.5	Total
						66	65	65	65	65	65	65	64	65	65	I/m
					30	56.9	112.5	167.7	223.5	279.4	335.2	390.1	446	501.7	557.1	Total
						57	56	56	56	56	56	56	56	56	56	I/m
20	23	21.5	175	30		54.2	108.5	162	216.7	270.3	324.5	378	421.7	480	539	Total
						54	54	54	54	54	54	54	53	53	54	I/m
					45	65.6	131.8	197.3	262.5	328.3	394.5	459.8	524.7	590.3	655.7	Total
						66	66	66	66	66	66	66	66	66	66	I/m
					60	77.1	154.1	230.4	306.9	383.7	459.7	536.2	611.9	688.5	764.1	Total
						77	77	77	77	77	77	77	76	77	76	I/m
					45	67.7	135.2	203.1	271.4	337.9	403.3	468.2	530.7	592.8	656.7	Total
						68	68	68	68	68	67	67	66	66	66	I/m
					30	57.7	115.4	173.2	230.8	287.1	342.9	399.1	455.5	512.5	567.1	Total
						58	58	58	58	57	57	57	57	57	57	I/m

## APPENDIX XI

	<b>BH3</b>	<b>BH4</b>	<b>BH5</b>	<b>BH6</b>
<b>Elavation</b>	26.256	32.167	34.138	30.799

Date	BH3 bgl	BH3 aod	BH4 bgl	BH4 aod	BH5 bgl	BH5 aod	BH6 bgl	BH6 aod	Comments
08/11/2015					1.31	32.83			Hole at deth of 3.15m
09/11/2015					Dry				Hole at deth of 7.4m
12/11/2015			5.34	26.827					Morning
12/11/2015			Dry						Evening
13/11/2015			17.46	14.707					Rods in hole
13/11/2015	0.65	25.606							Hole at 5.3m. Rods in Hole
16/11/2015	0.11	26.146							Hole at 5.3m. Rods in Hole
17/11/2015	7.51	18.746							Hole at 25.2m. Rods in Hole, Casing to 15m
18/11/2015	6.5	19.756							Hole at 25.2m. Rods in Hole, Casing to 15m
18/11/2015			15.76	16.407					Rods to EOH 35.0m
18/11/2015					17.69	16.45			Rods to EOH 40.3m
21/11/2015	7.5	18.756							Hole at 25.2m. Rods in Hole, Casing to 21m
21/11/2015			17.52	14.647					Rods to EOH 35.0m
21/11/2015					19.5	14.64			Rods to EOH 40.3m
23/11/2015	9	17.256							Hole at 50m. Rods in Hole, Casing to 21m
23/11/2015			18.79	13.377					Rods to EOH 35.0m
23/11/2015					20.56	13.58			Rods to EOH 40.3m
24/11/2015	8.5	17.756							Hole at 57.15m. Rods in Hole, Casing to 21m
24/11/2015			18.84	13.327					Rods to EOH 35.0m
24/11/2015					20.58	13.56			Rods to EOH 40.3m
25/11/2015	12	14.256							Hole at 65.78m. Rods in Hole, Casing to 21m
25/11/2015			18.92	13.247					Rods to EOH 35.0m
25/11/2015					20.72	13.42			Rods to EOH 40.3m
26/11/2015	13.21	13.046							Hole at 79.54m. Rods in Hole, Casing to 50m
26/11/2015			19.04	13.127					Rods to EOH 35.0m
26/11/2015					20.86	13.28			Rods to EOH 40.3m
02/12/2015	12.38	13.876							Hole at 104.95m. Rods in Hole, Casing to 50m
02/12/2015			16.02	16.147					Rods to EOH 35.0m
02/12/2015					17.77	16.37			Rods to EOH 40.3m

08/12/2015			16.14	16.027					Rods to EOH 35.0m
09/12/2015					17.33	16.81			Rods to EOH 40.3m
10/12/2015			15.47	16.697					Rods to EOH 35.0m
10/12/2015					16.98	17.16			Rods to EOH 40.3m
11/12/2015			17.56	14.607					Rods to EOH 35.0m
11/12/2015					16.99	17.15			Rods to EOH 40.3m
14/12/2015			15.65	16.517					Rods to EOH 35.0m
14/12/2015					15.49	18.65			Rods to EOH 40.3m
15/12/2015			16.48	15.687					Rods to EOH 35.0m
15/12/2015					15.51	18.63			Rods to EOH 40.3m
15/12/2015							15.6	15.199	Hole at deth of 45m Rods in hole
17/12/2015			16.87	15.297					Rods to EOH 35.0m
17/12/2015					15.58	18.56			Rods to EOH 40.3m
04/01/2016							2.81	27.989	Piezometer Installed
04/01/2016					14.46	19.68			Rods to EOH 40.3m
05/01/2016							2.83	27.969	Piezometer Installed
05/01/2016					14.68	19.46			Rods to EOH 40.3m
05/01/2016			17.88	14.287					Rods out of hole
06/01/2016					19.45	14.69			Rods out of hole
08/01/2016			16.46	15.707			3.39	27.409	Piezometer Installed
11/01/2016			16.43	15.737	17.48	16.658	3.05	27.749	Piezometer Installed
11/03/2016			18.96	13.207	20.86	13.278	3.59	27.209	Piezometer Installed

aod - Above Ordnance Datum (Sea Level)

### **Appendix A.9.1.6**

Phase 3 Contract 3, N6 Galway  
City Transport Project Phase 3  
Ground Investigation Contract  
3, November to December 2016





Our Ref: JMS/Rp/P16185 + attachments (\*.pdf)

09<sup>th</sup> May, 2017

**Messrs. ARUP**

Corporate House,  
City East Business Park,  
Ballybrit,  
Galway,  
H91K5YD.

**Re: N6 Galway City Transport Project (GCTP) Phase 3 Contract 3 – Ground Investigation, Factual report.**

**Introduction**

In November 2016, Priority Geotechnical were requested by Arup acting as Employer's Representative on behalf of Galway County Council, to undertake a ground investigation around the east of Galway City, with the majority in Ballybrit, Co. Galway, adjacent to the Galway Racecourse as part of the phase 3 contract 3 – ground investigation. The site works were carried out on private property. Invasive works were primarily in fields with two locations in a paved area.

**Scope**

The scope of the ground investigation, which was specified by Arup, comprised of:

- 1No. Cable percussion borehole;
- 3No. Rotary boreholes (5no. completed);
- 11No. Soakaway tests in accordance with BRE Digest 365 (17no. completed);
- 4No. Trial pits (5no. completed);
- 1No. 12m deep rotary pumping well;
- In situ testing, including Standard Penetration Tests;

- Surface geophysics survey (2D resistivity and seismic refraction);
- Crack monitoring;
- Groundwater monitoring;
- All associated sampling;
- Associated lab testing and
- Factual reporting.

## **Objectives**

The purpose of the site investigation was to provide information on the soil and rock ground conditions, groundwater levels and karst activity along the proposed route alignment.

This factual report presents the fieldworks records and data obtained with regard to the ground investigation for the N6 GCTP phase 3 contract 3 - Ground Investigation and should be read in conjunction with the exploratory and photographic records and laboratory test data accompanying this report (attached).

## **Site Works**

This investigation was carried out in accordance with Eurocode 7- Geotechnical Design Part 2, ground investigation and testing (BS EN 1997-2: 2007) and the relevant British Standards BS 5930 (2015) Code of Practice for Site Investigation and BS 1377, Method of Tests for Soil for Civil Engineering Purposes, *in situ* Tests Parts 1 to 9).

The fieldworks were undertaken between the 2<sup>th</sup> November and the 22<sup>nd</sup> December, 2017 under the supervision of PGL, Engineering Geologist(s). Details of the plant and equipment used are detailed on the relevant exploratory records, attached herein.

## **Cable Percussion Boreholes**

A single (1) cable percussion borehole (BH03-62) was drilled to a depth of 1.90m below existing ground level (bgl) using PGL's Dando 2000 rig. The records are attached, herein.

### **Rotary boreholes**

Five (5) rotary boreholes (RC03-60, RC03-61, RC03-62, RC03-63 and RC03-64) were drilled to depths between 8.0m bgl and 30.0m bgl using PGL's Deltabase 520, 6t rotary rig. The records are attached, herein.

A single (1) 200mm dia. pumping well (PW01) was drilled to a depth of 12.0m bgl by Dempsey Drilling on behalf of PGL.

### **Trial pits**

A total of five (5) number trial pit excavations (TP03-19, TP03-50, TP03-51, TP03-52 and TP03-53) were excavated to depths of 0.8m below existing ground level (bgl) to 4.0m bgl using a 14t tracked excavator. Trial pits terminated above the scheduled depth of 4.5m bgl for a variety of reasons outlined on the relevant exploratory records attached, herein.

### **Soakaway Tests**

A total of seventeen (17) number infiltration/ soakaway tests were carried out in in general accordance with BRE Digest 365, Soakaway Design (2003/ 2007). The data from the testing is presented accompanying the relevant exploratory records, SW03-03, SW03-04, SW03-05, SW03-06, SW03-07, SW03-08, SW03-09, SW03-10, SW03-11, SW03-12, SW03-13, SW03-14, SW03-15, SW03-16, SW03-17, SW03-18, and SW03-19.

### **Sampling**

A total of fifty seven (57) bulk disturbed samples (B), thirty two (32) small disturbed samples (D) and rotary core were recovered from the exploratory holes in accordance with Geotechnical Investigation and Sampling – Sampling Methods and Groundwater Measurements (EN ISO 22475-1:2006).

### **Survey and Drawings**

Upon completion of the fieldworks, the 'as built' exploration locations were surveyed using Trimble 5700/5800 GPS equipment to the Ordinance Survey Irish Transverse Mercator system of co-ordinates (ITM) and elevations to Malin Head datum. The

exploratory locations were shown on the Exploratory Location layout and Plan (P16185-SI-A) attached.

## **In-Situ Testing**

### **Standard Penetration Test**

Standard Penetration Tests, N values, were typically carried out in the boreholes using the 60° solid cone in place of the standard split barrel sampler. The Standard Penetration Test was carried out in accordance with Geotechnical Investigation and Testing, Part 3 Standard penetration test, BS EN ISO 22476-3:2005+A1:2011. The data is presented on the exploratory logs accompanying this factual report. Elevated SPT (SPT = >50) values are attributed to cobble and boulder inclusions.

A geophysical survey consisting of 2D-Resistivity and seismic refraction (p-wave) was carried out as part of the N6 GTCP Phase 3 Contract 3 - Ground Investigation. The reporting is issued separately.

An *In situ* variable head (falling and rising) permeability test was carried out in 200mm diameter standpipe well, BH-MW64. *In-situ* permeability tests were carried out in accordance with BS5930: 1999, Section 4: Cl. 25.4, within the superficial deposits over duration of one (1) hour. The processed test data is presented with this factual report. The shape or intake factor, *f* was derived from the condition at the base of the borehole at the test depth and test geometry as per Hvorslev (1951).

$$k = \frac{A}{fd} \frac{\log_e (H_o / H_i)}{t}$$

Generally for all tests the specific depth range of the test was the slotted pipe of the standpipe. The ratio *L/d* was 20 to 60. A mean *k* measured (*k<sub>H</sub>* = *k<sub>V</sub>*), permeability in the soil was assumed equal in both horizontal and vertical direction, (*k<sub>H</sub>*/ *k<sub>V</sub>* = 1.). The test geometry provided a shape factor, *f* of 20 for the tests undertaken.

## SUMMARY OF IN-SITU TESTING

Type	Quantity	Remarks
Standard Penetration Test, N values	28No.	Nspt ranging from 8 to 91 including refusal >50. Nspt average = 36
Soakaway tests	17No.	See attached results
Rising head permeability test	01No.	1.20E-08ms <sup>-1</sup>
Geophysical Survey	2D-Res 5671lin.m Seismic refraction,	See attached results

## Laboratory Testing

Laboratory testing was scheduled by Arup and carried out by GSTL on behalf of PGL in accordance with BS1377 (1990), Methods of test for soils for civil engineering purposes and the ISRM suggested methods for rock characterisation, testing and monitoring. The laboratory data accompanies the report and was summarised as follows;

Type	GSTL No.	PGL No.	Remarks
Natural Moisture Content	40	2	4.4% to 48%
Atterberg limits	24	2	Liquid limit, LL 25% and 63% Plastic limit, PL 14% to 46% incl. non plastic soils Plasticity index, PI 11 to 28
Particle size distribution analysis	32	2	Incl. 31 hydrometer on fines. Refer to attached results,
pH	4		7.5 to 7.91 units
Water soluble Sulphate, SO <sub>4</sub>	4		<0.01g/l to 0.02g/l
Organic Content	5		0.9% to 11.4%
Consolidated Drained Shearbox	3		See attached results.
Consolidated Undrained Shearbox	2		See attached results.

## **Published Geology**

The geology of the study area (GSI 1:100,000 mapping Sheet 14) is defined the Burren Formation (BU), described as pale grey clean skeletal Limestone. Karst features in the form of turloughs, enclosed depressions, caves and springs are common within the formation. Karst is a design risk. The national groundwater aquifer vulnerability mapping indicates high to extreme vulnerability. The extreme rating is likely due to bedrock at or near the surface. A review of geotechnical report ref: 1340 titled 'N6 Galway Eastern Approach Road' identified a series of historical rotary boreholes. Rock was encountered at depths between 0.05m bgl to 0.8m bgl.

Teagasc subsoil mapping indicates that the area is underlain glacial till derived chiefly from Limestone parent rock. Outcropping karstified Limestone bedrock was also indicated on the subsoil mapping.

## **Ground and groundwater conditions**


The full details of the ground conditions encountered are provided for on the exploratory records accompanying this report. The records provide descriptions, in accordance with BS 5930 (2015) and Eurocode 7, Geotechnical Investigation and Testing, Identification and classification of soils, Part 1, Identification and description (EN ISO 14688-1:2002),– Identification and Classification of Soil, Part 2: Classification Principles (EN ISO 14688-2:2004) and Identification and Classification of Rock, Part 1: Identification & Description (EN ISO 14689-1:2004) of the materials encountered, in situ testing and details of the samples taken, together with any observations made during the ground investigation.

Groundwater was recorded when encountered during boring and trial pit excavations over a period of 20 minutes, noting any changes that may occur. Groundwater levels were also monitored at start and end of drilling shifts. It should be noted that the normal rate of boring may not permit the recording of equilibrium groundwater levels for any one groundwater water strike where casing may exclude low volume flows as the borehole progresses. Groundwater conditions observed in the borings or pits are those appertaining to the period of the investigation. Groundwater levels may be subject to diurnal, seasonal and climatic variations and can also be affected by drainage

conditions, tidal variations etc. The groundwater regime should be assessed from standpipe well installations, where available.

Groundwater was monitored using Rugged Troll 100 Levelloggers. Continuous, absolute pressure (hydrostatic and barometric pressure) was measured *in situ* to determine continual groundwater levels at three (3) number locations RC63, RC64 and PW01. Loggers were installed in standpipe well installations as specified by Arup. Levels were monitored during pumping tests on PW01 to determine drawdown, if any on groundwater levels in the area. Levels were obtained prior to the pump test, during pumping and during the recharge phase. Accuracy was within 0.05% in water depths up to 30m. The data loggers are presented as digital spreadsheet data (\*.xls).

Five (5) 50mm diameter standpipes were constructed at locations RC03-60, RC03-61, RC03-62, RC03-63 and RC03-64 to allow for groundwater monitoring, else exploratory boreholes were backfilled with (pelletised) cement-bentonite grout. A summary of groundwater monitoring is shown below.



P16185 - N6 GTCP Phase 3 Contract 3	
Groundwater Readings	
Borehole No.	24/01/2017
RC03-60	14.02m
RC03-61	6.85m
RC03-62	6.15m
RC03-63	7.23m
RC03-64	5.15m
Pump Well	14.19m

Should you have any queries in relation to the data collected, please do not hesitate to contact our office.

Yours sincerely,  
For **Priority Geotechnical**,



**James McSweeney BSc**  
**Engineering Geologist**

*No responsibility can be held by PGL for ground conditions between exploratory locations. The exploratory logs provide for ground profiles and configuration of strata relevant to the investigation depths achieved during the fieldworks. Caution shall be taken when extrapolating between such exploratory locations. No liability is accepted for ground conditions extraneous to the exploratory locations.*

*No account has been taken of potential subsidence or ground movement due to mineral extraction, mining works or karstification below or in proximity to the site, unless specifically addressed.*

*This report has been prepared for Employer and their Representative as outline, herein. The information should not be used without their prior written permission. PGL accepts no responsibility or liability for this document being used other than for the purposes for which it was intended.*



# KEY TO SYMBOLS ON EXPLORATORY HOLE RECORDS

All linear dimensions are in metres or millimetres

## DESCRIPTIONS

\*\* Drillers Description  
Friable Easily crumbled

## SAMPLES

U( ) Undisturbed 102mm diameter sample, ( ) denotes number of blows to drive sampler  
U( )F, U( )P F- not recovered, P-partially recovered  
U38 Undisturbed 38mm diameter sample  
P(F), (P) Piston sample - disturbed  
B Bulk sample - disturbed  
D Jar Sample - disturbed  
W Water Sample  
CBR California Bearing Ratio mould sample  
ES Chemical Sample for Contamination Analysis  
SPTLS Standard Penetration Test S lump sample from split sampler

## CORE RECOVERY AND ROCK QUALITY

TCR Total Core Recovery (% of Core Run)  
SCR Solid Core Recovery (length of core having at least one full diameter as % of core run)  
RQD Rock Quality Designation (length of solid core greater than 100mm as % of core run)  
Where there is insufficient space for the TCR, SCR and RQD, the results may be found in the remarks column  
If Fracture Spacing in mm (Minimum/Average/Maximum) NI - non intact, NR - no recovery  
AZCL Assumed Zone of Core Loss  
NI Non intact

## GROUNDWATER

▽ Groundwater strike  
▼ Groundwater level after standing period  
Date/Water Date of shift (day/month)/Depth to water at end of previous shift shown above the date and depth to water at beginning of shift given below the date

## INSITU TESTING

S Standard Penetration Test - split barrel sampler  
C Standard Penetration Test - solid 60° cone  
SW Self Weight Penetration  
Ivp, HVp (R) In Situ Vane Test, Hand Vane Test (R) demonstrates remoulded strength  
K(F), (C), (R), (P) Permeability Test  
HP Hand Penetrometer Test

## MEASURED PROPERTIES

N Standard Penetration Test - blows required to drive 300mm after seating drive  
x/y Denotes x blows for y mm within the Standard Penetration Test  
x\*/y Denotes x blows for y mm within the seating drive  
c<sub>u</sub> Undrained Shear Strength (kN/m<sup>2</sup>)  
CBR California Bearing Ratio

## ROTARY DRILLING SIZES

Index Letter	Nominal Diameter (mm)	
	Borehole	Core
N	75	54
H	99	76
P	120	92
S	146	113



Priority Geotechnical Ltd.  
Tel: 021 4631600  
Fax: 021 4638690  
www.prioritygeotechnical.ie

Drilled By:

PC

Logged By:

AH

Borehole No.

**BH03-62**

Sheet 1 of 1

<b>Project Name:</b>	N6 GCTP Phase 3	<b>Project No.</b>	P16185	<b>Co-ords:</b>	532896E - 728291N	<b>Hole Type</b>	CP
----------------------	-----------------	--------------------	--------	-----------------	-------------------	------------------	----

<b>Location:</b>	Galway City, Co. Galway	<b>Level:</b>	17.77m OD	<b>Scale</b>	1:50
------------------	-------------------------	---------------	-----------	--------------	------

<b>Client:</b>	Arup	<b>Date:</b>	05/12/2016 - 05/12/2016
----------------	------	--------------	-------------------------

Well	Water Strike (m)	Sample and In Situ Testing			Depth (m)	Level (mOD)	Legend	Stratum Description	
		Depth (m)	Type	Results					
		0.00 - 0.50	B					Topsoil. CLAY.	
		0.00 - 0.50	D						
		0.50	SPT (C)	N=8 (1,1/2,2,2,2)	0.40	17.37		Firm, brown, slightly sandy slightly gravelly CLAY with low cobble content. Sand is fine to coarse. Gravel is fine to coarse, sub-angular to sub-rounded. Cobbles are 200mm dia and sub-angular.	1
		1.00 - 1.80	B		1.00	16.77		Light brown, slightly sandy slightly gravelly CLAY with cobble content. Sand is fine to coarse. Gravel is fine to medium, sub-angular to sub-rounded.	
		1.80	SPT (C)	50 (25 for 0mm/50 for 75mm)	1.90	15.87			
		1.90	SPT (C)	50 (25 for 0mm/50 for 75mm)				End of Borehole at 1.900m	2
									3
									4
									5
									6
									7
									8
									9

<b>Groundwater:</b>					<b>Hole Information:</b>			<b>Chiselling:</b>			
Struck (m)	Rose to	After (mins)	Sealed	Comment	Hole Depth (m)	Hole Dia (mm)	Casing Dia (mm)	Depth Top	Depth Base	Duration	Tool
				None encountered.	1.90	200	200	1.80	1.90	01:00	Chisel.
					<b>Equipment:</b>						
					Dando 2000.						

<b>Remarks:</b> Borehole terminated at 1.90m bgl due to obstruction, dense strata - refer to chiseling records.	<b>Shift Data:</b>		Groundwater	Shift	Hole Depth (m)	Remarks
			Dry	05/12/2016 08:00 05/12/2016 18:00	0.00 1.90	Start of shift. End of borehole.

Groundwater	Shift	Hole Depth (m)	Remarks
	02/12/2016 08:00	0.00	Start of shift.
Dry	02/12/2016 18:00	15.40	End of borehole.

Groundwater	Shift	Hole Depth (m)	Remarks
	02/12/2016 08:00	0.00	Start of shift.
Dry	02/12/2016 18:00	15.40	End of borehole.



<p><b>Number:</b> RC03-60</p>	<p><b>Project</b> N6 GCTP  <b>Project No</b> P16185  <b>Engineer</b> Arup</p>	
-------------------------------	---	--





Number: RC03-60

Project  
Project No  
Engineer


N6 GCTP  
P16185  
Arup





Number: RC03-60

Project  
Project No  
Engineer

N6 GCTP  
P16185  
Arup

				<b>Priority Geotechnical Ltd.</b> Tel: 021 4631600 Fax: 021 4638690 www.prioritygeotechnical.ie				Borehole No. <b>RC03-61</b> Sheet 1 of 2			
Project Name: N6 GCTP Phase 3				Project No. P16185		Co-ords: 533623.69 - 728217.59		Hole Type RC			
Location: Galway City, Co. Galway						Level: 57.19m OD		Scale 1:50			
Client: Arup						Dates: 05/12/2016		Logged By AH			

Well	Water Strike (m)	Depth (m)	Type /Fs	Coring			Depth (m) / FI	Level (mOD)	Legend	Stratum Description	
				TCR	SCR	RQD					
		10 (25 for 90mm/10 for 0mm) (C)					1.20	55.99		Open hole boring. Driller described: Topsoil, Clay.	1
		1.70 - 3.20				87	28	0		Open hole boring. Driller described: Weathered rock. Assumed Limetstone.	2
		3.20 - 4.70	124mm 422mm			100	73	73		Lithology: Moderately strong to strong, grey, LIMESTONE.  Weathering: Moderately weathered with clay smearing on fracture surfaces.  Fractures: Main set oriented 10-25 degrees, close to widely spaced, with undulating rough fracture surfaces. <i>1.70m to 2.40m bgl not intact.</i>	3
		4.70 - 6.20				100	80	15			4
		6.20 - 7.70	46mm 562mm			100	83	83			5
		7.70 - 9.20				100	100	80			6
											7
											8
											9

<b>Groundwater:</b> Struck, m: 8.30 Rose to:      After, min:      Sealed:      Comment: See shift data.					<b>Hole Information:</b> Hole Depth (m): 15.50 Hole Dia (mm): 76 Casing Dia (mm):			<b>Chiselling:</b> Depth Top:      Depth Base:      Duration:      Tool:															
					<b>Equipment:</b> Deltabase 520																		
<b>Remarks:</b> Borehole terminated at 15.50m bgl.							<b>Shift Data:</b> <table border="1"> <thead> <tr> <th>Groundwater</th> <th>Shift</th> <th>Hole Depth (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>05/12/2016 08:00</td> <td>0.00</td> <td>Start of shift.</td> <td></td> </tr> <tr> <td>8.3</td> <td>05/12/2016 18:00</td> <td>15.50</td> <td>End of borehole.</td> </tr> </tbody> </table>					Groundwater	Shift	Hole Depth (m)	Remarks	05/12/2016 08:00	0.00	Start of shift.		8.3	05/12/2016 18:00	15.50	End of borehole.
Groundwater	Shift	Hole Depth (m)	Remarks																				
05/12/2016 08:00	0.00	Start of shift.																					
8.3	05/12/2016 18:00	15.50	End of borehole.																				



Groundwater	Shift	Hole Depth (m)	Remarks
	05/12/2016 08:00	0.00	Start of shift.
8.3	05/12/2016 18:00	15.50	End of borehole.



Number: RC03-61

Project  
Project No  
Engineer

N6 GCTP  
P16185  
Arup



Number: RC03-61

Project  
Project No  
Engineer

N6 GCTP  
P16185  
Arup





Number: RC03-61


Project  
Project No  
Engineer



N6 GCTP  
P16185  
Arup

Groundwater	Shift	Hole Depth (m)	Remarks
	06/12/2016 08:00	0.00	Start of shift.
18.00	06/12/2016 18:00	30.00	End of borehole.

Groundwater	Shift	Hole Depth (m)	Remarks
	06/12/2016 08:00	0.00	Start of shift.
18.00	06/12/2016 18:00	30.00	End of borehole.



				<b>Priority Geotechnical Ltd.</b> Tel: 021 4631600 Fax: 021 4638690 www.prioritygeotechnical.ie				Borehole No. <b>RC03-62</b> Sheet 4 of 4			
Project Name: N6 GCTP Phase 3				Project No. P16185		Co-ords: 532895.64 - 728290.66		Hole Type RO			
Location: Galway City, Co. Galway				Level: 17.77m OD		Scale 1:50		Logged By			
Client: Arup				Dates: 06/12/2016							

Well	Water Strike (m)	Depth (m)	Type /Fs	Coring			Depth (m) / FI	Level (mOD)	Legend	Stratum Description	
				TCR	SCR	RQD					
		50 (25 for 0mm/50 for 0mm) (C)									28
		28.50 - 30.00 25 (10,16/25 for 10mm) (C)	B							28.50 - 30.00m: Locally medium dense.	29
		50 (25 for 50mm/50 for 10mm) (C)					30.00	-12.23		End of Borehole at 30.000m	30
											31
											32
											33
											34
											35
											36

<b>Groundwater:</b> Struck, m: 10.50    Rose to:    After, min:    Sealed:    Comment: See shift data.						<b>Hole Information:</b> Hole Depth (m): 30.00    Hole Dia (mm): 131    Casing Dia (mm): 131			<b>Chiselling:</b> Depth Top:    Depth Base:    Duration:    Tool:														
						<b>Equipment:</b> Deltabase 520																	
<b>Remarks:</b> Borehole terminated at 30.00m bgl.									<b>Shift Data:</b> <table border="1"> <thead> <tr> <th>Groundwater</th> <th>Shift</th> <th>Hole Depth (m)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>06/12/2016 08:00</td> <td>0.00</td> <td></td> <td>Start of shift.</td> </tr> <tr> <td>18.00</td> <td>06/12/2016 18:00</td> <td>30.00</td> <td>End of borehole.</td> </tr> </tbody> </table>			Groundwater	Shift	Hole Depth (m)	Remarks	06/12/2016 08:00	0.00		Start of shift.	18.00	06/12/2016 18:00	30.00	End of borehole.
Groundwater	Shift	Hole Depth (m)	Remarks																				
06/12/2016 08:00	0.00		Start of shift.																				
18.00	06/12/2016 18:00	30.00	End of borehole.																				





Groundwater	Shift	Hole Depth (m)	Remarks
	01/12/2016 08:00	0.00	Start of shift.
Dry	01/12/2016 18:00	10.00	End of borehole.

						Priority Geotechnical Ltd. Tel: 021 4631600 Fax: 021 4638690 www.prioritygeotechnical.ie							Borehole No. <b>RC03-63</b> Sheet 2 of 2				
Project Name: N6 GCTP Phase 3						Project No. P16185			Co-ords: 534688.05 - 726922.21					Hole Type RO			
Location: Galway City, Co. Galway						Level: 36.20m OD					Scale 1:50						
Client: Arup						Dates: 01/12/2016					Logged By						
Well	Water Strike (m)	Depth (m)	Type /Fs	Coring			Depth (m) / Fl	Level (mOD)	Legend	Stratum Description							
				TCR	SCR	RQD											
							10.00	26.20		Open hole boring. Driller described: Rock.							
										End of Borehole at 10.000m	10						
											11						
											12						
											13						
											14						
											15						
											16						
											17						
											18						
<b>Groundwater:</b> Struck, m    Rose to    After, min    Sealed    Comment None encountered.							<b>Hole Information:</b> Hole Depth (m)    Hole Dia (mm)    Casing Dia (mm) 10.00                  131                  131				<b>Chiselling:</b> Depth Top    Depth Base    Duration    Tool						
							<b>Equipment:</b> Deltabase 520.										
<b>Remarks:</b> Borehole terminated at 10.00m bgl. 50mm dia standpipe installed. Response zone from 4.0m to 10.0m bgl.									<b>Shift Data:</b> Groundwater    Shift    Hole Depth (m)    Remarks Dry    01/12/2016 08:00    0.00    Start of shift. 01/12/2016 18:00    10.00    End of borehole.								

Groundwater:					Hole Information:			Chiselling:					
Struck, m	Rose to	After, min	Sealed	Comment	Hole Depth (m)	Hole Dia (mm)	Casing Dia (mm)	Depth Top	Depth Base	Duration	Tool		
				None encountered.	8.00	131	131						
					Equipment:								
					Deltabase 520								
Remarks:							Shift Data:						
Borehole terminated at 8.00m bgl. 50mm dia standpipe installed. Response zone from 5.0m to 8.0m.							Groundwater		Shift		Hole Depth (m)		Remarks
									01/12/2016 08:00		0.00		Start of shift
							Dry		01/12/2016 18:00		8.00		None encountered

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 531192.33 - 728489.43 <b>Level:</b> 18.88	<b>Date</b> 12/12/2016
--------------------------------------	---------------------------	--	------------------------

<b>Location:</b> Galway City, Co. Galway	<b>Dimensions (m):</b> 4.20 2.00	<b>Scale</b> 1:25
<b>Client:</b> Arup	<b>Depth:</b> 0.25	<b>Logged</b> VT


Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description
	Depth	Type	Results				
	0.20			0.20	18.68		Topsoil. Soft, brown, slightly gravelly sandy SILT. Gravel is fine to coarse, angular to sub-angular, Limestone lithology. Sand is fine to coarse.
	0.25			0.25	18.63		Firm, light grey to light brown, slightly sandy gravelly SILT with high cobble content and medium boulder content. Sand is fine to coarse. Gravel is fine to coarse, angular to sub-angular, Limestone lithology. Cobbles are angular to sub-rounded, 63-200mm dia. Limestone lithology. Boulders are angular to sub-angular, 200-700mm dia. Limestone lithology.
							End of Pit at 0.25m
							1
							2
							3
							4
							5







<b>Stability:</b> Good.	<b>Groundwater:</b> None encountered.
<b>Plant:</b> 6t track machine.	
<b>Backfill:</b> Arisings.	
<b>Remarks:</b> Trial pit terminated at 0.25m bgl on bedrock.	



**Number: TP03-19**

**Project** N6 GCTP  
**Project No** P16185  
**Engineer** Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 532910.81 - 728281.73 <b>Level:</b> 18.04	<b>Date</b> 01/12/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 1.30  4.00	<b>Scale</b> 1:25
<b>Client:</b> Arup		<b>Depth:</b> 4.00	<b>Logged</b> AH

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.40	17.64		Topsoil.	
	0.80 - 1.50 0.80 - 1.50	B D		0.80	17.24		Soft to firm, grey, slightly gravelly sandy CLAY. Sand is fine to coarse. Gravel is fine to coarse and sub-angular.	1
	1.50 - 2.00 1.50 - 2.00	B D					Firm, grey, slightly sandy gravelly CLAY with high cobble content. Sand is fine to coarse. Gravel is fine to coarse, sub-rounded to rounded. Cobbles are 63mm to 200mm dia, sub-rounded to rounded.	
	2.00 - 3.00 2.00 - 3.00	B D		2.00	16.04		Very sandy very clayey GRAVEL.	2
	3.00 - 4.00 3.00 - 4.00	B D		3.00	15.04		Firm, grey, slightly sandy slightly gravelly CLAY. Sand is fine to coarse. Gravel is fine to coarse..	3
				4.00	14.04		End of Pit at 4.00m	4
								5

<b>Stability:</b> Good.	<b>Groundwater:</b> None encountered.
<b>Plant:</b> 14T track machine.	
<b>Backfill:</b> Arisings.	
<b>Remarks:</b> Trial pit terminated at 4.00m bgl, rock/ boulder obstruction.	





Number: TP03-50

Project  
Project No  
Engineer

N6 GCTP  
P16185  
Arup



Number: TP03-50

Project  
Project No  
Engineer

N6 GCTP  
P16185  
Arup







Number: TP03-51

Project N6 GCTP  
Project No P16185  
Engineer Arup





Number: TP03-51

Project N6 GCTP  
Project No P16185  
Engineer Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 533536.07 - 728203.64 <b>Level:</b> 56.79	<b>Date</b> 06/12/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 2.20 1.30	<b>Scale</b> 1:25
<b>Client:</b> Arup		<b>Depth:</b> 1.25	<b>Logged</b> DMC

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
	0.20 - 0.50 0.20 - 0.50	B D		0.15	56.64		Topsoil.	
							Soft, light brown, slightly sandy gravelly SILT. Sand is fine to coarse.	
	0.50 - 1.20 0.50 - 1.20	B D		0.50	56.29		Soft to firm, slightly sandy gravelly CLAY with low cobble content. Sand is fine to coarse. Gravel is fine to coarse, sub-angular to sub-rounded. Cobbles are sub-rounded.	1
				1.25	55.54		End of Pit at 1.25m	2
								3
								4
								5

<b>Stability:</b> Moderate.	<b>Groundwater:</b> None encountered.
<b>Plant:</b> 14T track machine.	
<b>Backfill:</b> Arisings.	
<b>Remarks:</b> Trial pit terminated at 1.25m bgl, on bedrock.	





Number: TP03-52

Project N6 GCTP  
Project No P16185  
Engineer Arup












Number: TP03-52

Project N6 GCTP  
Project No P16185  
Engineer Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 533686.85 - 728181.43 <b>Level:</b> 56.85	<b>Date</b> 06/12/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 1.50 <span style="border: 1px solid black; padding: 2px 10px;">3.50</span>	<b>Scale</b> 1:25
<b>Client:</b> Arup		<b>Depth:</b> 4.00	<b>Logged</b> DMC

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.40	56.45		Topsoil.	
	0.50 - 0.90 0.50 - 0.90	B D					Soft, brown, slightly gravelly slightly sandy CLAY. Sand is fine to coarse.	
	1.00 - 1.50 1.00 - 1.50	B D		0.95	55.90		Soft to firm, light grey, slightly gravelly sandy CLAY with medium cobble content, low boulder content. Sand is fine to coarse. Gravel is fine to coarse, sub-angular to sub-rounded. Cobbles are 63mm to 200mm dia and sub-rounded. Boulders are 200mm to 300mm dia, sub-rounded to rounded.	1
	2.00 - 2.50 2.00 - 2.50	B D						2
	2.50 - 3.50 2.50 - 3.50	B D		2.50	54.35		Firm to stiff, light grey, slightly sandy gravelly SILT with medium cobble content. Cobbles are sub-rounded to rounded, Limestone lithology.	3
	3.50 - 4.00 3.50 - 4.00	B D		3.50	53.35		Sandy very silty very gravelly COBBLES.	
				4.00	52.85		End of Pit at 4.00m	4
								5

**Stability:** Good.  
**Plant:** 14T track machine.  
**Backfill:** Arisings.  
**Remarks:** Trial pit terminated at 4.00m bgl. Difficult to excavate very stiff strata.

**Groundwater:** None encountered.





Number: TP03-53


Project N6 GCTP  
Project No P16185  
Engineer Arup





Number: TP03-53

Project N6 GCTP  
Project No P16185  
Engineer Arup



**Date**  
13/12/2016

Logged  
VT

4 -

Backfill: Fillings:	
Remarks:	Soakaway pit terminated at 0.45m bgl on bedrock. Soakaway test carried out (BRE 365)

P16185

N6 GCTP

Test 1


SW3/03

13/12/2016

l, m 3.35 b, m 1 d, m 0.47  
 l\_base, m 3.35 d\_eff, m 0.17  
 l\_eff, m 3.35 d\_act, m 0.15

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.3	0	0.17	0.00	0.000
0.5	0.32	30	0.15	0.02	0.067
1	0.33	60	0.14	0.03	0.101
1.5	0.33	90	0.14	0.03	0.101
2	0.33	120	0.14	0.03	0.101
2.5	0.34	150	0.13	0.04	0.134
3	0.34	180	0.13	0.04	0.134
3.5	0.34	210	0.13	0.04	0.134
4	0.34	240	0.13	0.04	0.134
4.5	0.34	270	0.13	0.04	0.134
5	0.34	300	0.13	0.04	0.134
6	0.34	360	0.13	0.04	0.134
7	0.35	420	0.12	0.05	0.168
8	0.35	480	0.12	0.05	0.168
9	0.35	540	0.12	0.05	0.168
10	0.35	600	0.12	0.05	0.168
11	0.36	660	0.11	0.06	0.201
12	0.37	720	0.10	0.07	0.235
13	0.37	780	0.10	0.07	0.235
14	0.37	840	0.10	0.07	0.235
15	0.38	900	0.09	0.08	0.268
20	0.4	1200	0.07	0.10	0.335
25	0.41	1500	0.06	0.11	0.369
30	0.42	1800	0.05	0.12	0.402
40	0.43	2400	0.04	0.13	0.436
50	0.44	3000	0.03	0.14	0.469
60	0.45	3600	0.02	0.15	0.503

Area 3.35 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub> 4.0895 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 0.28475 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> 4.0025 m<sup>2</sup> V<sub>p75-25 actual</sub> volume 0.25125 m<sup>3</sup>  
 t<sub>p75-25 actual</sub> time 1440.00 s  
 Infiltration Coefficient *f* 4.359E-05 ms<sup>-1</sup>

**NOTES:**

See SW3/03 log for detailed soil strata details: slightly sandy gravelly SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.

P16185

N6 GCTP

Test 2

SW3/03


13/12/2016

			d, m	0.47
l, m	3.35	b, m	1	d_eff, m
l_base, m	3.35			d_act, m
l_eff, m	3.35			0.17

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.3	0	0.17	0.00	0.000
0.5	0.31	30	0.16	0.01	0.034
1	0.32	60	0.15	0.02	0.067
1.5	0.32	90	0.15	0.02	0.067
2	0.32	120	0.15	0.02	0.067
2.5	0.32	150	0.15	0.02	0.067
3	0.33	180	0.14	0.03	0.101
3.5	0.33	210	0.14	0.03	0.101
4	0.33	240	0.14	0.03	0.101
4.5	0.33	270	0.14	0.03	0.101
5	0.33	300	0.14	0.03	0.101
6	0.33	360	0.14	0.03	0.101
7	0.33	420	0.14	0.03	0.101
8	0.34	480	0.13	0.04	0.134
9	0.34	540	0.13	0.04	0.134
10	0.34	600	0.13	0.04	0.134
11	0.34	660	0.13	0.04	0.134
12	0.34	720	0.13	0.04	0.134
13	0.34	780	0.13	0.04	0.134
14	0.35	840	0.12	0.05	0.168
15	0.35	900	0.12	0.05	0.168
20	0.36	1200	0.11	0.06	0.201
25	0.37	1500	0.10	0.07	0.235
30	0.38	1800	0.09	0.08	0.268
40	0.39	2400	0.08	0.09	0.302
50	0.41	3000	0.06	0.11	0.369
60	0.43	3600	0.04	0.13	0.436
80	0.44	4800	0.03	0.14	0.469
100	0.45	6000	0.02	0.15	0.503
120	0.45	7200	0.02	0.15	0.503
140	0.46	8400	0.01	0.16	0.536
160	0.47	9600	0.00	0.17	0.570

Area 3.35 m<sup>2</sup>50% Area\_eff, a<sub>p50</sub>4.0895 m<sup>2</sup>V<sub>p75-25 theory</sub> volume0.28475 m<sup>3</sup>50% Area\_act, a<sub>p50</sub>4.0895 m<sup>2</sup>V<sub>p75-25 actu</sub> volume0.28475 m<sup>3</sup>t<sub>p75-25 actual</sub> time

2970.00 s

Infiltration Coefficient *f* 2.34443E-05 ms<sup>-1</sup>**NOTES:**

See SW3/03 log for detailed soil strata details: slightly sandy gravelly SILT

No groundwater was encountered, pit assumed saturated for second test.

Infiltration rate calculated over actual fall.



P16185

N6 GCTP

Test 3

SW3/11

13/12/2016

l, m  
l\_base, m  
l\_eff, m

3.35  
3.35  
3.35

b, m

1

d, m  
d\_eff, m  
d\_act, m

0.47  
0.25  
0.25

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.22	0	0.25	0.00	0.000
0.5	0.24	30	0.23	0.02	0.067
1	0.25	60	0.22	0.03	0.101
1.5	0.27	90	0.20	0.05	0.168
2	0.27	120	0.20	0.05	0.168
2.5	0.27	150	0.20	0.05	0.168
3	0.28	180	0.19	0.06	0.201
3.5	0.28	210	0.19	0.06	0.201
4	0.28	240	0.19	0.06	0.201
4.5	0.28	270	0.19	0.06	0.201
5	0.28	300	0.19	0.06	0.201
6	0.29	360	0.18	0.07	0.235
7	0.29	420	0.18	0.07	0.235
8	0.3	480	0.17	0.08	0.268
9	0.3	540	0.17	0.08	0.268
10	0.3	600	0.17	0.08	0.268
11	0.3	660	0.17	0.08	0.268
12	0.31	720	0.16	0.09	0.302
13	0.31	780	0.16	0.09	0.302
14	0.31	840	0.16	0.09	0.302
15	0.31	900	0.16	0.09	0.302
20	0.32	1200	0.15	0.10	0.335
25	0.33	1500	0.14	0.11	0.369
30	0.34	1800	0.13	0.12	0.402
40	0.36	2400	0.11	0.14	0.469
50	0.38	3000	0.09	0.16	0.536
60	0.39	3600	0.08	0.17	0.570
80	0.40	4800	0.07	0.18	0.603
100	0.42	6000	0.05	0.20	0.670
120	0.43	7200	0.04	0.21	0.704
140	0.45	8400	0.02	0.23	0.771
160	0.47	9600	0.00	0.25	0.838

Area  
50% Area\_eff, a<sub>p50</sub>  
50% Area\_act, a<sub>p50</sub>

3.35 m<sup>2</sup>4.4375 m<sup>2</sup>4.4375 m<sup>2</sup>V<sub>p75-25 theory</sub>

volume


0.41875 m<sup>3</sup>V<sub>p 75 - 25 actual</sub>

volume

0.41875 m<sup>3</sup>t<sub>p 75-25 actual</sub>

time

5500.00 s

Infiltration Coefficient *f* 1.71575E-05 ms<sup>-1</sup>**NOTES:**

See SW3/03 log for detailed soil strata details: slightly sandy gravelly SILT  
No groundwater was encountered, pit assumed saturated for third test.  
Infiltration rate calculated over actual fall.



Number: SW03-03

Project N6 GCTP  
Project No P16185  
Engineer Arup





Number: SW03-03

Project N6 GCTP  
Project No P16185  
Engineer Arup



Priority Geotechnical Ltd.  
Tel: 021 4631600  
Fax: 021 4638690  
www.prioritygeotechnical.ie

Trial Pit No  
**SW03-04**  
Sheet 1 of 1

**Project Name:** N6 GCTP Phase 3


**Project No.**  
P16185

**Co-ords:** 533188.89 - 728353.66  
**Level:** 52.77

**Date**  
01/12/2016

**Location:** Galway City, Co. Galway

**Dimensions (m):**



**Scale**  
1:25

**Client:** Arup

**Depth:**  
0.35

**Logged**  
DMC

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.35	52.42		Topsoil. Soft, brown, slightly gravelly SILT.	
							End of Pit at 0.35m	
								1
								2
								3
								4
								5

**Stability:** Good.  
**Plant:** 14T track machine.  
**Backfill:** Arisings.

**Groundwater:** None encountered.

**Remarks:** Soakaway pit terminated at 0.35m bgl, on bedrock. Soakaway test carried out (BRE 365).



P16185

N6 GCTP

Test 1


SW3/04

01/12/2016

l, m 1.5 b, m 1.3 d, m 0.35  
 l\_base, m 1.5 d\_eff, m 0.35  
 l\_eff, m 1.5 d\_act, m 0.35

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0	0	0.35	0.00	0.000
0.5	0.1	30	0.25	0.10	0.195
1	0.1	60	0.25	0.10	0.195
1.5	0.12	90	0.23	0.12	0.234
2	0.14	120	0.21	0.14	0.273
2.5	0.14	150	0.21	0.14	0.273
3	0.14	180	0.21	0.14	0.273
3.5	0.14	210	0.21	0.14	0.273
4	0.14	240	0.21	0.14	0.273
4.5	0.14	270	0.21	0.14	0.273
5	0.15	300	0.20	0.15	0.293
6	0.16	360	0.19	0.16	0.312
7	0.16	420	0.19	0.16	0.312
8	0.17	480	0.18	0.17	0.332
9	0.17	540	0.18	0.17	0.332
10	0.17	600	0.18	0.17	0.332
11	0.17	660	0.18	0.17	0.332
12	0.18	720	0.17	0.18	0.351
13	0.18	780	0.17	0.18	0.351
14	0.19	840	0.16	0.19	0.371
15	0.2	900	0.15	0.20	0.390
20	0.21	1200	0.14	0.21	0.410
25	0.24	1500	0.11	0.24	0.468
30	0.26	1800	0.09	0.26	0.507
35	0.30	2100	0.05	0.30	0.585
40	0.35	2400	0.00	0.35	0.683

Area 1.95 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub> 2.93 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 0.34125 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> 2.93 m<sup>2</sup> V<sub>p 75 - 25 actual</sub> volume 0.34125 m<sup>3</sup>  
 t<sub>p 75- 25 actual</sub> time 1818.00 s  
 Infiltration Coefficient *f* 6.406E-05 ms<sup>-1</sup>

**NOTES:**

See SW3/04 log for detailed soil strata details: slightly gravelly SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.

P16185

N6 GCTP

Test 2


SW3/04

01/12/2016

l, m 1.5 d, m 0.35  
 l\_base, m 1.5 d\_eff, m 0.35  
 l\_eff, m 1.5 d\_act, m 0.34

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0	0	0.35	0.00	0.000
0.5	0.07	30	0.28	0.07	0.137
1	0.07	60	0.28	0.07	0.137
2	0.07	120	0.28	0.07	0.137
3	0.08	180	0.27	0.08	0.156
4	0.08	240	0.27	0.08	0.156
5	0.09	300	0.26	0.09	0.176
6	0.09	360	0.26	0.09	0.176
7	0.09	420	0.26	0.09	0.176
8	0.1	480	0.25	0.10	0.195
9	0.1	540	0.25	0.10	0.195
10	0.11	600	0.24	0.11	0.215
11	0.11	660	0.24	0.11	0.215
12	0.11	720	0.24	0.11	0.215
13	0.11	780	0.24	0.11	0.215
14	0.12	840	0.23	0.12	0.234
15	0.12	900	0.23	0.12	0.234
20	0.12	1200	0.23	0.12	0.234
25	0.13	1500	0.22	0.13	0.254
30	0.14	1800	0.21	0.14	0.273
40	0.16	2400	0.19	0.16	0.312
50	0.18	3000	0.17	0.18	0.351
60	0.20	3600	0.15	0.20	0.390
80	0.27	4800	0.08	0.27	0.527
100	0.34	6000	0.01	0.34	0.663

Area 1.95  
 50% Area\_eff, a<sub>p50</sub> 2.93 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 0.34125 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> 2.902 m<sup>2</sup> V<sub>p75-25 actu</sub> volume 0.3315 m<sup>3</sup>  
 t<sub>p75-25 actual</sub> time 4620.00 s  
 Infiltration Coefficient *f* 2.47254E-05 ms<sup>-1</sup>

**NOTES:**

See SW3/04 log for detailed soil strata details: slightly gravelly SILT

No groundwater was encountered, pit assumed saturated for second test.

Infiltration rate calculated over actual fall.

P16185

N6 GCTP

Test 3

SW3/04


01/12/2016

l, m 1.5 b, m 1.3 d, m 0.35  
 l\_base, m 1.5 d\_eff, m 0.35  
 l\_eff, m 1.5 d\_act, m 0.35

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0	0	0.35	0.00	0.000
0.5	0.12	30	0.23	0.12	0.234
1	0.12	60	0.23	0.12	0.234
2	0.12	120	0.23	0.12	0.234
3	0.12	180	0.23	0.12	0.234
4	0.12	240	0.23	0.12	0.234
5	0.12	300	0.23	0.12	0.234
40	0.13	2400	0.22	0.13	0.254
90	0.24	5400	0.11	0.24	0.468
135	0.35	8100	0.00	0.35	0.683

Area 1.95  
 50% Area\_eff, a<sub>p50</sub> 2.93 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 0.34125 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> 2.93 m<sup>2</sup> V<sub>p 75 - 25 actu</sub> volume 0.34125 m<sup>3</sup>  
 t<sub>p 75- 25 actual</sub> time 6066.00 s

Infiltration Coefficient *f* 1.92001E-05 ms<sup>-1</sup>

**NOTES:**

See SW3/04 log for detailed soil strata details: slightly gravelly SILT

No groundwater was encountered, pit assumed saturated for third test.

Infiltration rate calculated over actual fall.



Number: SW03-04

Project N6 GCTP  
Project No P16185  
Engineer Arup





Number: SW03-04

Project N6 GCTP  
Project No P16185  
Engineer Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 532788.59 - 727597.04 <b>Level:</b> 42.27	<b>Date</b> 30/11/2016
--------------------------------------	---------------------------	--	------------------------

<b>Location:</b> Galway City, Co. Galway	<b>Dimensions (m):</b> 1.60 x 2.40	<b>Scale</b> 1:25
<b>Client:</b> Arup	<b>Depth:</b> 0.90	<b>Logged</b> VT

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.20	42.07		Topsoil. Firm, brown, slightly gravelly SILT with medium cobble content. Gravel is fine to coarse, angular to sub-rounded. Cobbles are 63mm to 200mm dia, angular to sub-rounded, Limestone lithology.	
				0.90	41.37		Soft to firm, slightly gravelly sandy SILT with high cobble content, high boulder content. Sand is fine to coarse. Gravel is fine to coarse, angular to sub-angular. Cobbles are 63mm to 200mm dia, sub-angular to sub-rounded. Boulders are 200mm to 500mm dia, sub-angular to sub-rounded.	
							End of Pit at 0.90m	1
								2
								3
								4
								5

<b>Stability:</b> Good. <b>Plant:</b> 12T track machine. <b>Backfill:</b> Arisings.	<b>Groundwater:</b> None encountered.
<b>Remarks:</b> Soakaway pit terminated at 0.90m bgl, on bedrock. Soakaway test carried out (BRE 365).	



P16185

N6 GCTP

Test 1


SW3/05

30/11/2016

l, m 2.4 b, m 1.6 d, m 0.9  
 l\_base, m 2.4 d\_eff, m 0.74  
 l\_eff, m 2.4 d\_act, m 0.74

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.16	0	0.74	0.00	0.000
0.5	0.2	30	0.70	0.04	0.154
1	0.23	60	0.67	0.07	0.269
1.5	0.24	90	0.66	0.08	0.307
2	0.24	120	0.66	0.08	0.307
2.5	0.26	150	0.64	0.10	0.384
3	0.27	180	0.63	0.11	0.422
3.5	0.28	210	0.62	0.12	0.461
4	0.3	240	0.60	0.14	0.538
4.5	0.31	270	0.59	0.15	0.576
5	0.32	300	0.58	0.16	0.614
6	0.33	360	0.57	0.17	0.653
7	0.34	420	0.56	0.18	0.691
8	0.36	480	0.54	0.20	0.768
9	0.38	540	0.52	0.22	0.845
10	0.42	600	0.48	0.26	0.998
11	0.44	660	0.46	0.28	1.075
12	0.47	720	0.43	0.31	1.190
13	0.49	780	0.41	0.33	1.267
14	0.5	840	0.40	0.34	1.306
15	0.52	900	0.38	0.36	1.382
20	0.57	1200	0.33	0.41	1.574
25	0.61	1500	0.29	0.45	1.728
30	0.68	1800	0.22	0.52	1.997
40	0.81	2400	0.09	0.65	2.496
50	0.87	3000	0.03	0.71	2.726
60	0.90	3600	0.00	0.74	2.842

Area 3.84 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub> 6.8 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 1.4208 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> 6.8 m<sup>2</sup> V<sub>p75-25 actual</sub> volume 1.4208 m<sup>3</sup>  
 t<sub>p75-25 actual</sub> time 1800.00 s  
 Infiltration Coefficient *f* 0.000116 ms<sup>-1</sup>

**NOTES:**

See SW3/05 log for detailed soil strata details: slightly gravelly sandy SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.

P16185

N6 GCTP


Test 2

SW3/05

30/11/2016

l, m 2.4 d, m 0.9  
 l\_base, m 2.4 d\_eff, m 0.65  
 l\_eff, m 2.4 d\_act, m 0.65

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.25	0	0.65	0.00	0.000
0.5	0.3	30	0.60	0.05	0.192
1	0.32	60	0.58	0.07	0.269
1.5	0.36	90	0.54	0.11	0.422
2	0.37	120	0.53	0.12	0.461
2.5	0.37	150	0.53	0.12	0.461
3	0.38	180	0.52	0.13	0.499
3.5	0.39	210	0.51	0.14	0.538
4	0.4	240	0.50	0.15	0.576
4.5	0.41	270	0.49	0.16	0.614
5	0.42	300	0.48	0.17	0.653
6	0.44	360	0.46	0.19	0.730
7	0.46	420	0.44	0.21	0.806
8	0.47	480	0.43	0.22	0.845
9	0.47	540	0.43	0.22	0.845
10	0.48	600	0.42	0.23	0.883
11	0.49	660	0.41	0.24	0.922
12	0.5	720	0.40	0.25	0.960
13	0.51	780	0.39	0.26	0.998
14	0.52	840	0.38	0.27	1.037
15	0.54	900	0.36	0.29	1.114
20	0.58	1200	0.32	0.33	1.267
25	0.62	1500	0.28	0.37	1.421
30	0.66	1800	0.24	0.41	1.574
40	0.78	2400	0.12	0.53	2.035
50	0.86	3000	0.04	0.61	2.342
60	0.90	3600	0.00	0.65	2.496

Area 3.84 m<sup>2</sup>50% Area\_eff, a<sub>p5</sub> 6.44 m<sup>2</sup>V<sub>p75-25 theory</sub> volume 1.248 m<sup>3</sup>50% Area\_act, a<sub>p5</sub> 6.44 m<sup>2</sup>V<sub>p75-25 actu</sub> volume 1.248 m<sup>3</sup>t<sub>p75-25 actual</sub> time 1630.00 sInfiltration Coefficient *f* 0.000118889 ms<sup>-1</sup>**NOTES:**

See SW3/05 log for detailed soil strata details: slightly gravelly sandy SILT

Second test pit assumed saturated.

Infiltration rate calculated over actual fall.



P16185

N6 GCTP

Test 3

SW3/05


30/11/2016

l, m 2.4 b, m 1.6 d, m 0.9  
 l\_base, m 2.4 d\_eff, m 0.77  
 l\_eff, m 2.4 d\_act, m 0.77

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.13	0	0.77	0.00	0.000
0.5	0.15	30	0.75	0.02	0.077
1	0.17	60	0.73	0.04	0.154
1.5	0.19	90	0.71	0.06	0.230
2	0.2	120	0.70	0.07	0.269
2.5	0.2	150	0.70	0.07	0.269
3	0.22	180	0.68	0.09	0.346
3.5	0.23	210	0.67	0.10	0.384
4	0.24	240	0.66	0.11	0.422
4.5	0.24	270	0.66	0.11	0.422
5	0.24	300	0.66	0.11	0.422
6	0.25	360	0.65	0.12	0.461
7	0.26	420	0.64	0.13	0.499
8	0.27	480	0.63	0.14	0.538
9	0.28	540	0.62	0.15	0.576
10	0.29	600	0.61	0.16	0.614
11	0.29	660	0.61	0.16	0.614
12	0.3	720	0.60	0.17	0.653
13	0.32	780	0.58	0.19	0.730
14	0.33	840	0.57	0.20	0.768
15	0.34	900	0.56	0.21	0.806
20	0.38	1200	0.52	0.25	0.960
25	0.43	1500	0.47	0.30	1.152
30	0.49	1800	0.41	0.36	1.382
40	0.59	2400	0.31	0.46	1.766
50	0.68	3000	0.22	0.55	2.112
60	0.78	3600	0.12	0.65	2.496
80	0.90	4800	0.00	0.77	2.957

Area 3.84 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub> 6.92 m<sup>2</sup> V<sub>p75-25 theor</sub> volume 1.4784 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> 6.92 m<sup>2</sup> V<sub>p75-25 actl</sub> volume 1.4784 m<sup>3</sup>  
 t<sub>p75-25 actual</sub> time 2280.00 s

Infiltration Coefficient *f* 9.37025E-05 ms<sup>-1</sup>

**NOTES:**

See SW3/05 log for detailed soil strata details: slightly gravelly sandy SILT

Third test pit assumed saturated.

Infiltration rate calculated over actual fall.



Number: SW03-05


Project N6 GCTP  
Project No P16185  
Engineer Arup








Number: SW03-05

Project N6 GCTP  
Project No P16185  
Engineer Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 534038.37 - 727783.11 <b>Level:</b> 48.56	<b>Date</b> 05/12/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 1.20  2.50	<b>Scale</b> 1:25
<b>Client:</b> Arup		<b>Depth:</b> 1.50	<b>Logged</b> DMC

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.40	48.16		Topsoil.	
				0.80	47.76		Soft, brown, slightly sandy slightly gravelly SILT.	1
				1.50	47.06		Light grey, slightly sandy gravelly SILT.	
							End of Pit at 1.50m	2
								3
								4
								5

**Stability:** Moderate.  
**Plant:** 14T track machine.  
**Backfill:** Arisings.  
**Remarks:** Soakaway pit terminated at required depth of 1.50m bgl.

**Groundwater:** None encountered.

P16185

N6 GCTP


Test 3

SW3/06

05/12/2016

l, m 2.5 b, m 1.2 d, m 1.5  
 l\_base, m 2.5 d\_eff, m 1.42  
 l\_eff, m 2.5 d\_act, m 0.84

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.08	0	1.42	0.00	0.000
0.5	0.08	30	1.42	0.00	0.000
1	0.09	60	1.41	0.01	0.030
1.5	0.09	90	1.41	0.01	0.030
2	0.1	120	1.40	0.02	0.060
2.5	0.1	150	1.40	0.02	0.060
3	0.11	180	1.39	0.03	0.090
3.5	0.11	210	1.39	0.03	0.090
4	0.11	240	1.39	0.03	0.090
4.5	0.11	270	1.39	0.03	0.090
5	0.12	300	1.38	0.04	0.120
6	0.12	360	1.38	0.04	0.120
7	0.13	420	1.37	0.05	0.150
8	0.13	480	1.37	0.05	0.150
9	0.13	540	1.37	0.05	0.150
15	0.15	900	1.35	0.07	0.210
20	0.18	1200	1.32	0.10	0.300
25	0.19	1500	1.31	0.11	0.330
30	0.20	1800	1.30	0.12	0.360
40	0.23	2400	1.27	0.15	0.450
50	0.26	3000	1.24	0.18	0.540
60	0.28	3600	1.22	0.20	0.600
70	0.30	4200	1.20	0.22	0.660
80	0.32	4800	1.18	0.24	0.720
100	0.35	6000	1.15	0.27	0.810
120	0.38	7200	1.12	0.30	0.900
140	0.41	8400	1.09	0.33	0.990
160	0.44	9600	1.06	0.36	1.080
205	0.46	12300	1.04	0.38	1.140
225	0.48	13500	1.02	0.40	1.200
245	0.50	14700	1.00	0.42	1.260
265	0.52	15900	0.98	0.44	1.320
285	0.53	17100	0.97	0.45	1.350
305	0.54	18300	0.96	0.46	1.380
1140	0.90	68400	0.60	0.82	2.460
1500	0.90	90000	0.60	0.82	2.460
1680	0.92	100800	0.58	0.84	2.520

Area 3 m<sup>2</sup>50% Area\_eff, a<sub>p50</sub> 8.254 m<sup>2</sup>V<sub>p75-25 theory</sub> volume 2.13 m<sup>3</sup>50% Area\_act, a<sub>p50</sub> 6.108 m<sup>2</sup>V<sub>p75-25 actual</sub> volume 1.26 m<sup>3</sup>t<sub>p75-25 actual</sub> time 38087.40 sInfiltration Coefficient *f* 5.42E-06 ms<sup>-1</sup>**NOTES:**

See SW3/06 log for detailed soil strata details: slightly sandy gravelly SILT

No groundwater was encountered, pit assumed unsaturated.

Infiltration rate calculated over actual fall.





Number: SW03-06

Project N6 GCTP  
Project No P16185  
Engineer Arup






Number: SW03-06

Project N6 GCTP  
Project No P16185  
Engineer Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 534619.39 - 726923.63 <b>Level:</b> 37.08	<b>Date</b> 29/11/2016
--------------------------------------	------------------------------	--	---------------------------

<b>Location:</b> Galway City, Co. Galway	<b>Dimensions (m):</b> 1.60 <span style="border: 1px solid black; padding: 2px 10px;">3.00</span>	<b>Scale</b> 1:25
<b>Client:</b> Arup	<b>Depth:</b> 1.10	<b>Logged</b> VT

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				1.10	35.98		<p>Firm, brown, slightly sandy slightly gravelly SILT with high cobble content, high boulder content. Sand is fine to coarse. Gravel is fine to coarse, angular to sub-angular. Cobbles are 63mm to 200mm dia, angular to sub-angular, Limestone lithology. Boulders are 200mm to 500mm dia, angular to sub-angular, Limestone lithology.</p>	1
							End of Pit at 1.10m	2
								3
								4
								5

<b>Stability:</b> Moderate to good. <b>Plant:</b> 12T track machine. <b>Backfill:</b> Arisings.	<b>Groundwater:</b> None encountered.
<b>Remarks:</b> Soakaway pit terminated at 1.10m bgl on bedrock. Soakaway test carried out (BRE 365).	



P16185

N6 GCTP

Test 1

SW3/07


29/11/2016

l, m                    3      b, m                    1.6      d, m                    1.1  
 l\_base, m            3                                    d\_eff, m            1.03  
 l\_eff, m                3                                    d\_act, m            1.03

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.07	0	1.03	0.00	0.000
0.5	0.14	30	0.96	0.07	0.336
1	0.2	60	0.90	0.13	0.624
1.5	0.23	90	0.87	0.16	0.768
2	0.26	120	0.84	0.19	0.912
2.5	0.31	150	0.79	0.24	1.152
3	0.33	180	0.77	0.26	1.248
3.5	0.38	210	0.72	0.31	1.488
4	0.41	240	0.69	0.34	1.632
4.5	0.42	270	0.68	0.35	1.680
5	0.44	300	0.66	0.37	1.776
6	0.49	360	0.61	0.42	2.016
7	0.52	420	0.58	0.45	2.160
8	0.56	480	0.54	0.49	2.352
9	0.6	540	0.50	0.53	2.544
10	0.62	600	0.48	0.55	2.640
11	0.68	660	0.42	0.61	2.928
12	0.7	720	0.40	0.63	3.024
13	0.74	780	0.36	0.67	3.216
14	0.78	840	0.32	0.71	3.408
15	0.8	900	0.30	0.73	3.504
20	0.84	1200	0.26	0.77	3.696
25	0.98	1500	0.12	0.91	4.368
30	1.04	1800	0.06	0.97	4.656
40	1.10	2400	0.00	1.03	4.944

Area                    4.8 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub>    9.538 m<sup>2</sup>      V<sub>p75-25 theory</sub>    volume      2.472 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub>    9.538 m<sup>2</sup>      V<sub>p 75 - 25 actual</sub>    volume      2.472 m<sup>3</sup>  
    t<sub>p 75- 25 actual</sub>    time      1029.00 s

Infiltration Coefficient    f      0.0002519 ms<sup>-1</sup>

**NOTES:**

See SW3/07 log for detailed soil strata details: slightly gravelly slightly sandy SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.

P16185

N6 GCTP

Test 2

SW3/07

29/11/2016

l, m  
l\_base, m  
l\_eff, m


3  
3  
3

b, m

1.6

d, m 1.1  
d\_eff, m 1.02  
d\_act, m 1.02

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.08	0	1.02	0.00	0.000
0.5	0.14	30	0.96	0.06	0.288
1	0.21	60	0.89	0.13	0.624
1.5	0.26	90	0.84	0.18	0.864
2	0.28	120	0.82	0.20	0.960
2.5	0.31	150	0.79	0.23	1.104
3	0.33	180	0.77	0.25	1.200
3.5	0.36	210	0.74	0.28	1.344
4	0.38	240	0.72	0.30	1.440
4.5	0.39	270	0.71	0.31	1.488
5	0.4	300	0.70	0.32	1.536
6	0.43	360	0.67	0.35	1.680
7	0.46	420	0.64	0.38	1.824
8	0.48	480	0.62	0.40	1.920
9	0.52	540	0.58	0.44	2.112
10	0.54	600	0.56	0.46	2.208
11	0.57	660	0.53	0.49	2.352
12	0.6	720	0.50	0.52	2.496
13	0.64	780	0.46	0.56	2.688
14	0.66	840	0.44	0.58	2.784
15	0.68	900	0.42	0.60	2.880
20	0.78	1200	0.32	0.70	3.360
25	0.88	1500	0.22	0.80	3.840
30	0.91	1800	0.19	0.83	3.984
40	1.03	2400	0.07	0.95	4.560
50	1.08	3000	0.02	1.00	4.800
60	1.10	3600	0.00	1.02	4.896

Area 4.8 m<sup>2</sup>50% Area\_eff, ε 9.492 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 2.448 m<sup>3</sup>50% Area\_act, i 9.492 m<sup>2</sup> V<sub>p 75 - 25 actu</sub> volume 2.448 m<sup>3</sup>t<sub>p 75- 25 actual</sub> time 1211.00 sInfiltration Coefficient f 0.000213 ms<sup>-1</sup>**NOTES:**

See SW3/07 log for detailed soil strata details: slightly gravelly slightly sandy SILT

No groundwater was encountered, pit assumed saturated on second test.

Infiltration rate calculated over actual fall.

**N6 GCTP**

### Test 3

SW3/07

**29/11/2016**

l, m  
l\_base, m  
l\_eff, m

3  
3  
3

b, m

## 1.6

d, m	1.1
d_eff, m	0.95
d_act, m	0.95

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.15	0	0.95	0.00	0.000
0.5	0.22	30	0.88	0.07	0.336
1	0.26	60	0.84	0.11	0.528
1.5	0.29	90	0.81	0.14	0.672
2	0.31	120	0.79	0.16	0.768
2.5	0.33	150	0.77	0.18	0.864
3	0.34	180	0.76	0.19	0.912
3.5	0.36	210	0.74	0.21	1.008
4	0.38	240	0.72	0.23	1.104
4.5	0.41	270	0.69	0.26	1.248
5	0.43	300	0.67	0.28	1.344
6	0.45	360	0.65	0.30	1.440
7	0.48	420	0.62	0.33	1.584
8	0.5	480	0.60	0.35	1.680
9	0.52	540	0.58	0.37	1.776
10	0.54	600	0.56	0.39	1.872
11	0.55	660	0.55	0.40	1.920
12	0.58	720	0.52	0.43	2.064
13	0.6	780	0.50	0.45	2.160
14	0.62	840	0.48	0.47	2.256
15	0.65	900	0.45	0.50	2.400
20	0.75	1200	0.35	0.60	2.880
25	0.83	1500	0.27	0.68	3.264
30	0.89	1800	0.21	0.74	3.552
40	0.95	2400	0.15	0.80	3.840
50	1.01	3000	0.09	0.86	4.128
60	1.06	3600	0.04	0.91	4.368
70	1.09	4200	0.01	0.94	4.512
80	1.10	4800	0.00	0.95	4.560

Area

4.8 m<sup>2</sup>

50% Area\_eff,  $a_{p50}$

9.17 m<sup>2</sup>

$V_{p75-25 \text{ theor}}$  volume 2.28 m<sup>3</sup>


50% Area\_act,  $a_{p50}$

9.17 m<sup>2</sup>

$V_{p75-25}$  actual volume 2.28 m<sup>3</sup>

$t_{p\ 75-25}$  actual time 1492.00 s

Infiltration Coefficient $f$	0.000167 ms <sup>-1</sup>
------------------------------	---------------------------



**NOTES:**

See SW3/07 log for detailed soil strata details: slightly gravelly slightly sandy SILT  
No groundwater was encountered, pit assumed saturated on third test.  
Infiltration rate calculated over actual fall.



Number: SW03-07

Project N6 GCTP  
Project No P16185  
Engineer Arup






Number: SW03-07

Project  
Project No  
Engineer

N6 GCTP  
P16185  
Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 534660.70 - 726868.16 <b>Level:</b> 34.45	<b>Date</b> 29/11/2016
--------------------------------------	------------------------------	--	---------------------------

<b>Location:</b> Galway City, Co. Galway	<b>Dimensions (m):</b> 1.50 <span style="border: 1px solid black; padding: 2px 10px;">3.20</span>	<b>Scale</b> 1:25
<b>Client:</b> Arup	<b>Depth:</b> 1.60	<b>Logged</b> VT

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.35	34.10		<p>Topsoil. Soft to firm, brown, slightly sandy slightly gravelly SILT with high cobble content. Sand is fine to coarse. Gravel is fine to coarse, angular to sub-rounded. Cobbles are 63mm to 200mm dia, angular to sub-rounded, Limestone lithology.</p>	1
				1.60	32.85		<p>Firm, brown grey, slightly gravelly sandy SILT with high cobble content, high boulder content. Sand is fine to coarse. Gravel is fine to coarse, angular to sub-rounded. Cobbles are 63mm to 200mm dia, angular to sub-angular. Boulders are 200mm to 500mm dia, angular to sub-angular, Limestone lithology.</p>	2
							End of Pit at 1.60m	3
								4
								5

<b>Stability:</b> Good to moderate. <b>Plant:</b> 12T track machine. <b>Backfill:</b> Arisings.	<b>Groundwater:</b> None encountered.
---	---------------------------------------

**Remarks:** Soakaway pit terminated at 1.60m bgl on bedrock. Soakaway test carried out (BRE 365).

P16185

N6 GCTP

Test 1


SW3/08

29/01/2016

l, m 2.9      b, m 1.5      d, m 1.65  
 l\_base, m 2.9      d\_eff, m 1.20  
 l\_eff, m 2.9      d\_act, m 1.20

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.45	0	1.20	0.00	0.000
0.5	0.55	30	1.10	0.10	0.435
1	0.64	60	1.01	0.19	0.827
1.5	0.7	90	0.95	0.25	1.088
2	0.78	120	0.87	0.33	1.436
2.5	0.82	150	0.83	0.37	1.610
3	0.86	180	0.79	0.41	1.784
3.5	0.89	210	0.76	0.44	1.914
4	0.91	240	0.74	0.46	2.001
4.5	0.98	270	0.67	0.53	2.306
5	1	300	0.65	0.55	2.393
6	1.05	360	0.60	0.60	2.610
7	1.11	420	0.54	0.66	2.871
8	1.17	480	0.48	0.72	3.132
9	1.21	540	0.44	0.76	3.306
10	1.25	600	0.40	0.80	3.480
11	1.3	660	0.35	0.85	3.698
12	1.33	720	0.32	0.88	3.828
13	1.36	780	0.29	0.91	3.959
14	1.41	840	0.24	0.96	4.176
15	1.47	900	0.18	1.02	4.437
20	1.57	1200	0.08	1.12	4.872
25	1.61	1500	0.04	1.16	5.046
30	1.64	1800	0.01	1.19	5.177
40	1.65	2400	0.00	1.20	5.220

Area 4.35 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub> 9.63 m<sup>2</sup>      V<sub>p75-25 theory</sub> volume 2.61 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> 9.63 m<sup>2</sup>      V<sub>p 75 - 25 actual</sub> volume 2.61 m<sup>3</sup>  
    t<sub>p 75- 25 actual</sub> time 651.00 s  
 Infiltration Coefficient *f* 0.0004163 ms<sup>-1</sup>

**NOTES:**

See SW3/08 log for detailed soil strata details: slightly gravelly sandy SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.

P16185

N6 GCTP

Test 2

SW3/08

29/01/2016

l, m 2.9  
 l\_base, m 2.9  
 l\_eff, m 2.9


b, m 1.5  
 d, m 1.65  
 d\_eff, m 1.30  
 d\_act, m 1.30

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.35	0	1.30	0.00	0.000
0.5	0.52	30	1.13	0.17	0.740
1	0.56	60	1.09	0.21	0.914
1.5	0.7	90	0.95	0.35	1.523
2	0.75	120	0.90	0.40	1.740
2.5	0.8	150	0.85	0.45	1.958
3	0.9	180	0.75	0.55	2.393
3.5	0.93	210	0.72	0.58	2.523
4	0.96	240	0.69	0.61	2.654
4.5	0.99	270	0.66	0.64	2.784
5	1.02	300	0.63	0.67	2.915
6	1.07	360	0.58	0.72	3.132
7	1.13	420	0.52	0.78	3.393
8	1.19	480	0.46	0.84	3.654
9	1.24	540	0.41	0.89	3.872
10	1.27	600	0.38	0.92	4.002
11	1.33	660	0.32	0.98	4.263
12	1.37	720	0.28	1.02	4.437
13	1.4	780	0.25	1.05	4.568
14	1.45	840	0.20	1.10	4.785
15	1.49	900	0.16	1.14	4.959
20	1.6	1200	0.05	1.25	5.438
25	1.64	1500	0.01	1.29	5.612
30	1.65	1800	0.00	1.30	5.655
40	1.65	2400	0.00	1.30	5.655

Area 4.35 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub> 10.07 m<sup>2</sup>  
 50% Area\_act, a<sub>p50</sub> 10.07 m<sup>2</sup>

V<sub>p75-25 theory</sub> volume 2.8275 m<sup>3</sup>  
 V<sub>p 75 - 25 actu</sub> volume 2.8275 m<sup>3</sup>  
 t<sub>p 75- 25 actual</sub> time 571.00 s

Infiltration Coefficient *f* 0.000492 ms<sup>-1</sup>

**NOTES:**

See SW3/08 log for detailed soil strata details: slightly gravelly sandy SILT

No groundwater was encountered, pit assumed saturated for second test.

Infiltration rate calculated over actual fall.



P16185

N6 GCTP

Test 2

SW3/08

29/01/2016

l, m  
l\_base, m  
l\_eff, m


2.9  
2.9  
2.9

b, m

1.5

d, m 1.65  
d\_eff, m 1.25  
d\_act, m 1.25

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.4	0	1.25	0.00	0.000
0.5	0.48	30	1.17	0.08	0.348
1	0.55	60	1.10	0.15	0.653
1.5	0.64	90	1.01	0.24	1.044
2	0.71	120	0.94	0.31	1.349
2.5	0.75	150	0.90	0.35	1.523
3	0.8	180	0.85	0.40	1.740
3.5	0.85	210	0.80	0.45	1.958
4	0.9	240	0.75	0.50	2.175
4.5	0.96	270	0.69	0.56	2.436
5	1	300	0.65	0.60	2.610
6	1.07	360	0.58	0.67	2.915
7	1.15	420	0.50	0.75	3.263
8	1.19	480	0.46	0.79	3.437
9	1.22	540	0.43	0.82	3.567
10	1.28	600	0.37	0.88	3.828
11	1.32	660	0.33	0.92	4.002
12	1.36	720	0.29	0.96	4.176
13	1.39	780	0.26	0.99	4.307
14	1.42	840	0.23	1.02	4.437
15	1.47	900	0.18	1.07	4.655
20	1.53	1200	0.12	1.13	4.916
25	1.59	1500	0.06	1.19	5.177
30	1.63	1800	0.02	1.23	5.351
40	1.65	2400	0.00	1.25	5.438

Area 4.35 m<sup>2</sup>50% Area\_eff, a<sub>p50</sub> 9.85 m<sup>2</sup>50% Area\_act, a<sub>p5</sub> 9.85 m<sup>2</sup>V<sub>p75-25 theor</sub> volume 2.71875 m<sup>3</sup>V<sub>p 75 - 25 actu</sub> volume 2.71875 m<sup>3</sup>t<sub>p 75- 25 actual</sub> time 623.00 sInfiltration Coefficient *f* 0.000443 ms<sup>-1</sup>**NOTES:**

See SW3/08 log for detailed soil strata details: slightly gravelly sandy SILT

No groundwater was encountered, pit assumed saturated on third test.

Infiltration rate calculated over actual fall.



Number: SW03-08

Project N6 GCTP  
Project No P16185  
Engineer Arup






Number: SW03-08



Project N6 GCTP  
Project No P16185  
Engineer Arup



Priority Geotechnical Ltd.  
Tel: 021 4631600  
Fax: 021 4638690  
www.prioritygeotechnical.ie

Trial Pit No  
**SW03-09**  
Sheet 1 of 1

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords: -</b> <b>Level:</b>	<b>Date</b> 29/11/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 1.55  2.80	<b>Scale</b> 1:25
<b>Client:</b> Arup		<b>Depth:</b> 0.80	<b>Logged</b> VT

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.20			Topsoil. Firm, brown, slightly sandy SILT.	
				0.80			Soft to firm, brown grey, slightly gravelly very sandy SILT with high cobble content, medium boulder content. Sand is fine to coarse. Gravel is fine to coarse, angular to sub-rounded. Cobbles are 63mm to 200mm dia, angular to sub-rounded, Limestone lithology. Boulders are 200mm to 400mm dia, angular to sub-rounded, Limestone lithology.	
							End of Pit at 0.80m	

<b>Stability:</b> Good. <b>Plant:</b> 12T track machine. <b>Backfill:</b> Arisings.	<b>Groundwater:</b> None encountered.
---	---------------------------------------

**Remarks:** Soakaway pit terminated at 0.80m bgl due to obstruction.

P16185

N6 GCTP

Test 1


SW3/09

30/11/2016

l, m 2.8      b, m 0.55      d, m 0.8  
 l\_base, m 2.8      d\_eff, m 0.70  
 l\_eff, m 2.8      d\_act, m 0.70

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.1	0	0.70	0.00	0.000
0.5	0.15	30	0.65	0.05	0.077
1	0.23	60	0.57	0.13	0.200
1.5	0.26	90	0.54	0.16	0.246
2	0.3	120	0.50	0.20	0.308
2.5	0.33	150	0.47	0.23	0.354
3	0.35	180	0.45	0.25	0.385
3.5	0.37	210	0.43	0.27	0.416
4	0.39	240	0.41	0.29	0.447
4.5	0.41	270	0.39	0.31	0.477
5	0.43	300	0.37	0.33	0.508
6	0.46	360	0.34	0.36	0.554
7	0.48	420	0.32	0.38	0.585
8	0.49	480	0.31	0.39	0.601
9	0.52	540	0.28	0.42	0.647
10	0.55	600	0.25	0.45	0.693
11	0.58	660	0.22	0.48	0.739
12	0.6	720	0.20	0.50	0.770
13	0.62	780	0.18	0.52	0.801
14	0.66	840	0.14	0.56	0.862
15	0.72	900	0.08	0.62	0.955
20	0.76	1200	0.04	0.66	1.016
25	0.78	1500	0.02	0.68	1.047
30	0.80	1800	0.00	0.70	1.078

Area 1.54 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub> 3.885 m<sup>2</sup>      V<sub>p75-25 theory</sub> volume 0.539 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> 3.885 m<sup>2</sup>      V<sub>p 75 - 25 actual</sub> volume 0.539 m<sup>3</sup>  
    t<sub>p 75-25 actual</sub> time 690.00 s  
 Infiltration Coefficient *f* 0.0002011 ms<sup>-1</sup>

**NOTES:**

See SW3/09 log for detailed soil strata details: slightly gravelly slightly sandy SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.

**P16185 N6 GCTP**

**Test 2**


**SW3/09**

**30/11/2016**

			d, m	0.8
l, m	2.8	b, m	d_eff, m	0.67
l_base, m	2.8		d_act, m	0.67
l_eff, m	2.8			

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.13	0	0.67	0.00	0.000
0.5	0.16	30	0.64	0.03	0.046
1	0.17	60	0.63	0.04	0.062
1.5	0.17	90	0.63	0.04	0.062
2	0.18	120	0.62	0.05	0.077
2.5	0.19	150	0.61	0.06	0.092
3	0.19	180	0.61	0.06	0.092
3.5	0.21	210	0.59	0.08	0.123
4	0.23	240	0.57	0.10	0.154
4.5	0.24	270	0.56	0.11	0.169
5	0.26	300	0.54	0.13	0.200
6	0.28	360	0.52	0.15	0.231
7	0.29	420	0.51	0.16	0.246
8	0.31	480	0.49	0.18	0.277
9	0.33	540	0.47	0.20	0.308
10	0.34	600	0.46	0.21	0.323
11	0.36	660	0.44	0.23	0.354
12	0.37	720	0.43	0.24	0.370
13	0.38	780	0.42	0.25	0.385
14	0.39	840	0.41	0.26	0.400
15	0.4	900	0.40	0.27	0.416
20	0.43	1200	0.37	0.30	0.462
25	0.44	1500	0.36	0.31	0.477
30	0.46	1800	0.34	0.33	0.508
40	0.48	2400	0.32	0.35	0.539
50	0.54	3000	0.26	0.41	0.631
60	0.59	3600	0.21	0.46	0.708
80	0.75	4800	0.05	0.62	0.955
100	0.8	6000	0.00	0.67	1.032

Area	1.54 m^2		
50% Area_1	3.7845 m^2	V <sub>p75-25 theory</sub> volume	0.5159 m^3
50% Area_2	3.7845 m^2	V <sub>p 75 - 25 actual</sub> volume	0.5159 m^3
		t <sub>p 75-25 actual</sub> time	3667.00 s
Infiltration Coefficient <i>f</i>			3.71746E-05 ms^-1



**NOTES:**

See SW3/09 log for detailed soil strata details: slightly gravelly sandy SILT  
 No groundwater was encountered, pit assumed saturated for second test.  
 Infiltration rate calculated over actual fall.

P16185

N6 GCTP

## Test 3

SW3/09


30/11/2016

l, m 2.8 b, m 0.55 d, m 0.8  
 l\_base, m 2.8 d\_eff, m 0.67  
 l\_eff, m 2.8 d\_act, m 0.67

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.13	0	0.67	0.00	0.000
0.5	0.16	30	0.64	0.03	0.046
1	0.21	60	0.59	0.08	0.123
1.5	0.23	90	0.57	0.10	0.154
2	0.24	120	0.56	0.11	0.169
2.5	0.24	150	0.56	0.11	0.169
3	0.25	180	0.55	0.12	0.185
3.5	0.25	210	0.55	0.12	0.185
4	0.25	240	0.55	0.12	0.185
4.5	0.24	270	0.56	0.11	0.169
5	0.26	300	0.54	0.13	0.200
6	0.26	360	0.54	0.13	0.200
7	0.27	420	0.53	0.14	0.216
8	0.28	480	0.52	0.15	0.231
9	0.28	540	0.52	0.15	0.231
10	0.29	600	0.51	0.16	0.246
11	0.29	660	0.51	0.16	0.246
12	0.29	720	0.51	0.16	0.246
13	0.3	780	0.50	0.17	0.262
14	0.3	840	0.50	0.17	0.262
15	0.31	900	0.49	0.18	0.277
20	0.34	1200	0.46	0.21	0.323
25	0.36	1500	0.44	0.23	0.354
30	0.4	1800	0.40	0.27	0.416
40	0.45	2400	0.35	0.32	0.493
50	0.49	3000	0.31	0.36	0.554
60	0.53	3600	0.27	0.40	0.616
80	0.64	4800	0.16	0.51	0.785
105	0.72	6300	0.08	0.59	0.909
120	0.80	7200	0.00	0.67	1.032

Area 1.54 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub> 3.7845 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 0.5159 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> 3.7845 m<sup>2</sup> V<sub>p75 - 25 actual</sub> volume 0.5159 m<sup>3</sup>  
 t<sub>p75-25 actual</sub> time 3947.00 s

Infiltration Coefficient *f* 3.45374E-05 ms<sup>-1</sup>



## NOTES:

See SW3/09 log for detailed soil strata details: slightly gravelly sandy SILT  
 No groundwater was encountered, pit assumed saturated for third test.  
 Infiltration rate calculated over actual fall.





Number: SW03-09

Project  
Project No  
Engineer


N6 GCTP  
P16185  
Arup





Number: SW03-09

Project N6 GCTP  
Project No P16185  
Engineer Arup



**Date**  
02/12/2016

**Scale**  
1:25

Logged  
DMC

<b>Stability:</b> Moderate. <b>Plant:</b> 14T track machine. <b>Backfill:</b> Arisings.	<b>Groundwater:</b> None encountered.
<b>Remarks:</b> Soakaway pit terminated at 0.70m bgl. on bedrock. Soakaway test carried out (BRE 365).	

Remarks:	Soakaway pit terminated at 0.70m bgl, on bedrock. Soakaway test carried out (BRE 365).
----------	--

P16185 N6 GCTP

Test 1


SW3/10

02/12/2016

l, m 1.9      b, m 1.5      d, m 0.7  
 l\_base, m 1.9      d\_eff, m 0.55  
 l\_eff, m 1.9      d\_act, m 0.55

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.15	0	0.55	0.00	0.000
0.5	0.17	30	0.53	0.02	0.057
1	0.18	60	0.52	0.03	0.085
1.5	0.19	90	0.51	0.04	0.114
2	0.2	120	0.50	0.05	0.143
2.5	0.21	150	0.49	0.06	0.171
3	0.22	180	0.48	0.07	0.200
3.5	0.22	210	0.48	0.07	0.200
4	0.23	240	0.47	0.08	0.228
4.5	0.23	270	0.47	0.08	0.228
5	0.24	300	0.46	0.09	0.257
6	0.25	360	0.45	0.10	0.285
7	0.26	420	0.44	0.11	0.314
8	0.27	480	0.43	0.12	0.342
9	0.28	540	0.42	0.13	0.371
10	0.3	600	0.40	0.15	0.428
11	0.3	660	0.40	0.15	0.428
12	0.31	720	0.39	0.16	0.456
13	0.33	780	0.37	0.18	0.513
14	0.34	840	0.36	0.19	0.542
15	0.35	900	0.35	0.20	0.570
20	0.41	1200	0.29	0.26	0.741
25	0.45	1500	0.25	0.30	0.855
30	0.50	1800	0.20	0.35	0.998
40	0.57	2400	0.13	0.42	1.197
50	0.63	3000	0.07	0.48	1.368
60	0.70	3600	0.00	0.55	1.568

Area 2.85 m<sup>2</sup>  
 50% Area\_eff, 4.72 m<sup>2</sup>      V<sub>p75-25 theory</sub> volume 0.78375 m<sup>3</sup>  
 50% Area\_act, 4.72 m<sup>2</sup>      V<sub>p 75 - 25 actual</sub> volume 0.78375 m<sup>3</sup>  
                                  t<sub>p 75- 25 actual</sub> time 1759.00 s  
 Infiltration Coefficient *f* 9.44E-05 ms<sup>-1</sup>

**NOTES:**

See SW3/10 log for detailed soil strata details: slightly sandy gravelly SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.

P16185 N6 GCTP

Test 2


SW3/10

02/12/2016

l, m            1.9      b, m            1.5      d, m            0.7  
 l\_base, m      1.9                      d\_eff, m       0.58  
 l\_eff, m        1.9                      d\_act, m       0.58

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.12	0	0.58	0.00	0.000
0.5	0.14	30	0.56	0.02	0.057
1	0.15	60	0.55	0.03	0.086
1.5	0.15	90	0.55	0.03	0.086
2	0.16	120	0.54	0.04	0.114
2.5	0.16	150	0.54	0.04	0.114
3	0.16	180	0.54	0.04	0.114
3.5	0.17	210	0.53	0.05	0.143
4	0.17	240	0.53	0.05	0.143
4.5	0.18	270	0.52	0.06	0.171
5	0.18	300	0.52	0.06	0.171
6	0.19	360	0.51	0.07	0.200
7	0.2	420	0.50	0.08	0.228
8	0.2	480	0.50	0.08	0.228
9	0.21	540	0.49	0.09	0.257
10	0.22	600	0.48	0.10	0.285
11	0.23	660	0.47	0.11	0.314
12	0.23	720	0.47	0.11	0.314
13	0.24	780	0.46	0.12	0.342
14	0.24	840	0.46	0.12	0.342
15	0.25	900	0.45	0.13	0.371
20	0.28	1200	0.42	0.16	0.456
25	0.32	1500	0.38	0.20	0.570
30	0.35	1800	0.35	0.23	0.656
40	0.40	2400	0.30	0.28	0.798
50	0.45	3000	0.25	0.33	0.941
60	0.51	3600	0.19	0.39	1.112
80	0.62	4800	0.08	0.50	1.425
100	0.70	6000	0.00	0.58	1.653

Area            2.85 m<sup>2</sup>  
 50% Area\_      4.822 m<sup>2</sup>      V<sub>p75-25 theory</sub> volume            0.8265 m<sup>3</sup>  
 50% Area\_      2.85 m<sup>2</sup>      V<sub>p 75 - 25 actu</sub> volume            0.8265 m<sup>3</sup>  
                          t<sub>p 75-25 actual</sub> time            4464.00 s  
 Infiltration Coefficient *f*            6.49642E-05 ms<sup>-1</sup>

**NOTES:**

See SW3/10 log for detailed soil strata details: slightly sandy gravelly SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.




**P16185 N6 GCTP**
**Test 3**
**SW3/10**
**02/12/2016**

l, m **1.9**      b, m **1.5**      d, m **0.7**  
 l\_base, m **1.9**      d\_eff, m **0.60**  
 l\_eff, m **1.9**      d\_act, m **0.60**

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.1	0	0.60	0.00	0.000
0.5	0.11	30	0.59	0.01	0.029
1	0.12	60	0.58	0.02	0.057
1.5	0.12	90	0.58	0.02	0.057
2	0.13	120	0.57	0.03	0.086
2.5	0.13	150	0.57	0.03	0.086
3	0.14	180	0.56	0.04	0.114
3.5	0.14	210	0.56	0.04	0.114
4	0.14	240	0.56	0.04	0.114
4.5	0.15	270	0.55	0.05	0.143
5	0.15	300	0.55	0.05	0.143
6	0.16	360	0.54	0.06	0.171
7	0.16	420	0.54	0.06	0.171
8	0.17	480	0.53	0.07	0.200
9	0.18	540	0.52	0.08	0.228
10	0.19	600	0.51	0.09	0.257
15	0.24	900	0.46	0.14	0.399
20	0.26	1200	0.44	0.16	0.456
25	0.29	1500	0.41	0.19	0.542
30	0.32	1800	0.38	0.22	0.627
40	0.38	2400	0.32	0.28	0.798
50	0.42	3000	0.28	0.32	0.912
60	0.48	3600	0.22	0.38	1.083
80	0.58	4800	0.12	0.48	1.368
100	0.71	6000	-0.01	0.60	1.710

Area **2.85 m^2**  
 50% Area\_ **4.89 m^2**       $V_{p75-25 \text{ theory volume}}$  **0.855 m^3**  
 50% Area\_ **4.89 m^2**       $V_{p75-25 \text{ actu volume}}$  **0.855 m^3**  
 $t_{p75-25 \text{ actual time}}$  **3090.00 s**  
 Infiltration Coefficient  $f$  **5.66E-05 ms^-1**


**NOTES:**

See SW3/10 log for detailed soil strata details: slightly sandy gravelly SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.



Number: SW03-10

Project N6 GCTP  
Project No P16185  
Engineer Arup



Number: SW03-10


Project N6 GCTP  
Project No P16185  
Engineer Arup








Priority Geotechnical Ltd.  
Tel: 021 4631600  
Fax: 021 4638690  
www.prioritygeotechnical.ie

Trial Pit No  
**SW03-11**  
Sheet 1 of 1

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 535486.56 - 726929.33 <b>Level:</b> 37.68	<b>Date</b> 02/12/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 1.30  <b>Depth:</b> 1.00	<b>Scale</b> 1:25
<b>Client:</b> Arup			<b>Logged</b> DMC

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.30	37.38		Topsoil.	
				0.70	36.98		Soft to firm, light grey, slightly sandy gravelly SILT with low cobble content. Sand is fine to coarse. Gravel is fine to coarse and sub-angular. Cobbles are sub-rounded to rounded, Limestone lithology.	
				1.00	36.68		Weathered rock. Recovered as: BOULDERS. Boulders are angular, Limestone lithology.	
							End of Pit at 1.00m	1
								2
								3
								4
								5

<b>Stability:</b> Good. <b>Plant:</b> 14T track machine. <b>Backfill:</b> Arisings.	<b>Groundwater:</b> None encountered.
<b>Remarks:</b> Soakaway pit terminated at 1.00m bgl, on bedrock. Soakaway test carried out (BRE 365).	



P16185 N6 GCTP

## Test 1


SW3/11

#####

l, m 1.6 b, m 1.3 d, m 1  
 l\_base, m 1.6 d\_eff, m 0.90  
 l\_eff, m 1.6 d\_act, m 0.83

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.1	0	0.90	0.00	0.000
0.5	0.11	30	0.89	0.01	0.021
1	0.11	60	0.89	0.01	0.021
1.5	0.12	90	0.88	0.02	0.042
2	0.13	120	0.87	0.03	0.062
2.5	0.13	150	0.87	0.03	0.062
3	0.14	180	0.86	0.04	0.083
3.5	0.16	210	0.84	0.06	0.125
4	0.17	240	0.83	0.07	0.146
4.5	0.18	270	0.82	0.08	0.166
5	0.19	300	0.81	0.09	0.187
6	0.19	360	0.81	0.09	0.187
7	0.2	420	0.80	0.10	0.208
8	0.22	480	0.78	0.12	0.250
9	0.23	540	0.77	0.13	0.270
10	0.25	600	0.75	0.15	0.312
11	0.26	660	0.74	0.16	0.333
12	0.27	720	0.73	0.17	0.354
13	0.29	780	0.71	0.19	0.395
14	0.3	840	0.70	0.20	0.416
15	0.31	900	0.69	0.21	0.437
20	0.37	1200	0.63	0.27	0.562
25	0.42	1500	0.58	0.32	0.666
30	0.47	1800	0.53	0.37	0.770
40	0.56	2400	0.44	0.46	0.957
50	0.60	3000	0.40	0.50	1.040
60	0.71	3600	0.29	0.61	1.269
80	0.93	4800	0.07	0.83	1.726

Area 2.08 m<sup>2</sup>  
 50% Area\_eff, 4.69 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 0.936 m<sup>3</sup>  
 50% Area\_act, 4.487 m<sup>2</sup> V<sub>p 75 - 25 actual</sub> volume 0.8632 m<sup>3</sup>  
 t<sub>p 75- 25 actual</sub> time 2755.00 s  
 Infiltration Coefficient *f* 6.983E-05 ms<sup>-1</sup>

**NOTES:**


See SW3/11 log for detailed soil strata details: slightly sandy gravelly SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.

**P16185 N6 GCTP****Test 2****SW3/11****02/12/2016**

l, m            **1.6**      b, m            **1.3**      d, m            **1**  
 l\_base, m      **1.6**                      d\_eff, m        **0.80**  
 l\_eff, m        **1.6**                      d\_act, m        **0.73**

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.2	0	0.80	0.00	0.000
0.5	0.22	30	0.78	0.02	0.042
1	0.23	60	0.77	0.03	0.062
1.5	0.24	90	0.76	0.04	0.083
2	0.25	120	0.75	0.05	0.104
2.5	0.26	150	0.74	0.06	0.125
3	0.27	180	0.73	0.07	0.146
3.5	0.28	210	0.72	0.08	0.166
4	0.28	240	0.72	0.08	0.166
4.5	0.3	270	0.70	0.10	0.208
5	0.3	300	0.70	0.10	0.208
6	0.31	360	0.69	0.11	0.229
7	0.33	420	0.67	0.13	0.270
8	0.35	480	0.65	0.15	0.312
9	0.37	540	0.63	0.17	0.354
10	0.38	600	0.62	0.18	0.374
11	0.39	660	0.61	0.19	0.395
12	0.4	720	0.60	0.20	0.416
13	0.41	780	0.59	0.21	0.437
14	0.42	840	0.58	0.22	0.458
15	0.44	900	0.56	0.24	0.499
20	0.5	1200	0.50	0.30	0.624
25	0.55	1500	0.45	0.35	0.728
40	0.72	2400	0.28	0.52	1.082
50	0.80	3000	0.20	0.60	1.248
60	0.93	3600	0.07	0.73	1.518

Area                    2.08 m<sup>2</sup>  
 50% Area\_            4.4 m<sup>2</sup>      V<sub>p75-25 theory</sub> volume                    0.832 m<sup>3</sup>  
 50% Area\_            4.197 m<sup>2</sup>      V<sub>p 75 - 25 actu</sub> volume                    0.7592 m<sup>3</sup>  
                                  t<sub>p 75- 25 actual</sub> time                    1794.00 s  
 Infiltration Coefficient *f*                    0.000100831 ms<sup>-1</sup>

**NOTES:**

See SW3/11 log for detailed soil strata details: slightly sandy gravelly SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.

**P16185 N6 GCTP**

**Test 3**


**SW3/11**

**02/12/2016**

l, m **1.6** b, m **1.3** d, m **1**  
l\_base, m **1.6** d\_eff, m **0.80**  
l\_eff, m **1.6** d\_act, m **0.73**

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.2	0	0.80	0.00	0.000
0.5	0.22	30	0.78	0.02	0.042
1	0.23	60	0.77	0.03	0.062
1.5	0.24	90	0.76	0.04	0.083
2	0.25	120	0.75	0.05	0.104
2.5	0.26	150	0.74	0.06	0.125
3	0.27	180	0.73	0.07	0.146
3.5	0.28	210	0.72	0.08	0.166
4	0.28	240	0.72	0.08	0.166
4.5	0.3	270	0.70	0.10	0.208
5	0.3	300	0.70	0.10	0.208
6	0.31	360	0.69	0.11	0.229
7	0.33	420	0.67	0.13	0.270
8	0.35	480	0.65	0.15	0.312
9	0.37	540	0.63	0.17	0.354
10	0.38	600	0.62	0.18	0.374
11	0.39	660	0.61	0.19	0.395
12	0.4	720	0.60	0.20	0.416
13	0.41	780	0.59	0.21	0.437
14	0.42	840	0.58	0.22	0.458
15	0.44	900	0.56	0.24	0.499
20	0.5	1200	0.50	0.30	0.624
25	0.55	1500	0.45	0.35	0.728
40	0.72	2400	0.28	0.52	1.082
50	0.80	3000	0.20	0.60	1.248
60	0.93	3600	0.07	0.73	1.518

Area 2.08 m<sup>2</sup>  
50% Area\_ 4.4 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 0.832 m<sup>3</sup>  
50% Area\_ 4.197 m<sup>2</sup> V<sub>p 75 - 25 actu</sub> volume 0.7592 m<sup>3</sup>  
t<sub>p 75-25 actual</sub> time 2384.00 s  
Infiltration Coefficient *f* 7.58771E-05 ms<sup>-1</sup>



**NOTES:**

See SW3/11 log for detailed soil strata details: slightly sandy gravelly SILT  
No groundwater was encountered, pit assumed unsaturated.  
Infiltration rate calculated over actual fall.








**Number:** SW03-11

**Project** N6 GCTP  
**Project No** P16185  
**Engineer** Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 532982.03 - 728221.91 <b>Level:</b> 30.50	<b>Date</b> 01/12/2016
--------------------------------------	------------------------------	--	---------------------------

<b>Location:</b> Galway City, Co. Galway	<b>Dimensions (m):</b> 1.30 <span style="border:1px solid black; padding: 2px 10px;">1.90</span>	<b>Scale</b> 1:25
<b>Client:</b> Arup	<b>Depth:</b> 3.50	<b>Logged</b> DMC

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.40	30.10		Topsoil.	
				0.80	29.70		Soft, brown, slightly gravelly CLAY. Gravel fine to coarse.	
	1.00 - 2.00	B					Firm, grey, slightly sandy gravelly SILT with high cobble content. Sand is fine to coarse. Gravel is fine to coarse. Cobbles are sub-angular, Limestone lithology.	1
	2.00 - 3.00	B					2.00 - 3.00m: Decreasing gravel content.	2
				3.50	27.00		End of Pit at 3.50m	3
								4
								5

<b>Stability:</b> Good. <b>Plant:</b> 14T track machine. <b>Backfill:</b> Arisings.	<b>Groundwater:</b> None encountered.
<b>Remarks:</b> Trial pit terminated at 3.50m bgl, on bedrock. Soakaway test carried out (BRE 365).	

P16185

N6 GCTP

Test 1


SW3/12

01/12/2016

l, m 1.9 b, m 1.3 d, m 3.5  
 l\_base, m 1.9 d\_eff, m 3.15  
 l\_eff, m 1.9 d\_act, m 1.17

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.35	0	3.15	0.00	0.000
0.5	0.35	30	3.15	0.00	0.000
1	0.35	60	3.15	0.00	0.000
1.5	0.36	90	3.14	0.01	0.025
2	0.37	120	3.13	0.02	0.049
2.5	0.38	150	3.12	0.03	0.074
3	0.39	180	3.11	0.04	0.099
3.5	0.39	210	3.11	0.04	0.099
4	0.39	240	3.11	0.04	0.099
4.5	0.39	270	3.11	0.04	0.099
5	0.4	300	3.10	0.05	0.124
6	0.41	360	3.09	0.06	0.148
7	0.42	420	3.08	0.07	0.173
8	0.43	480	3.07	0.08	0.198
9	0.44	540	3.06	0.09	0.222
10	0.45	600	3.05	0.10	0.247
11	0.45	660	3.05	0.10	0.247
12	0.46	720	3.04	0.11	0.272
13	0.47	780	3.03	0.12	0.296
14	0.47	840	3.03	0.12	0.296
15	0.47	900	3.03	0.12	0.296
20	0.5	1200	3.00	0.15	0.371
25	0.53	1500	2.97	0.18	0.445
30	0.56	1800	2.94	0.21	0.519
40	0.59	2400	2.91	0.24	0.593
120	0.82	7200	2.68	0.47	1.161
200	0.86	12000	2.64	0.51	1.260
230	0.90	13800	2.60	0.55	1.359
280	0.97	16800	2.53	0.62	1.531
1110	1.52	66600	1.98	1.17	2.890

Area 2.47 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub> 12.55 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 3.89025 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> 6.214 m<sup>2</sup> V<sub>p75-25 actual</sub> volume 1.44495 m<sup>3</sup>  
 t<sub>p75-25 actual</sub> time 36702.00 s  
 Infiltration Coefficient *f* 6.336E-06 ms<sup>-1</sup>

**NOTES:**

See SW3/12 log for detailed soil strata details: slightly sandy gravelly SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.





Number: SW03-12


Project N6 GCTP  
Project No P16185  
Engineer Arup






Number: SW03-12

Project N6 GCTP  
Project No P16185  
Engineer Arup



<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 533661.00 - 728105.09 <b>Level:</b> 56.48	<b>Date</b> 06/12/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 1.20  2.30	<b>Scale</b> 1:25
<b>Client:</b> Arup		<b>Depth:</b> 3.80	<b>Logged</b> DMC

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.60	55.88		Topsoil.	
				1.20	55.28		Firm, grey, sandy gravelly SILT with medium cobble content. Sand is fine to coarse. Gravel is fine to coarse, sub-angular to rounded. Cobbles are angular to sub-rounded, Limestone lithology.	1
	1.50 - 2.50	B					Firm to stiff, slightly sandy gravelly SILT with high cobble content, low boulder content. Sand is fine to coarse. Cobbles are sub-rounded to rounded, Limestone lithology. Boulders are 200mm to 300mm dia, sub-rounded, Limestone lithology.	2
				3.80	52.68		End of Pit at 3.80m	3
								4
								5

**Stability:** Good.  
**Plant:** 14T track machine.  
**Backfill:** Arisings.

**Groundwater:** None encountered.

**Remarks:** Soakaway pit terminated at 3.80m bgl. Soakaway test carried out (BRE 365).

P16185

N6 GCTP

Test 1


SW3/13

06/12/2016

d, m	3.8		
l, m	2.3	b, m	1.2
l_base, m	2.3		
l_eff, m	2.3		
d_eff, m	2.50		
d_act, m	0.03		

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	1.3	0	2.50	0.00	0.000
1	1.31	60	2.49	0.01	0.028
2	1.31	120	2.49	0.01	0.028
3	1.31	180	2.49	0.01	0.028
4	1.31	240	2.49	0.01	0.028
5	1.31	300	2.49	0.01	0.028
10	1.31	600	2.49	0.01	0.028
15	1.31	900	2.49	0.01	0.028
90	1.33	5400	2.47	0.03	0.083

Area	2.76 m <sup>2</sup>		
50% Area_eff, a <sub>p50</sub>	11.51 m <sup>2</sup>	V <sub>p75-25 theory</sub>	volume 3.45 m <sup>3</sup>
50% Area_act, a <sub>p50</sub>	2.865 m <sup>2</sup>	V <sub>p 75 - 25 actual</sub>	volume 0.0414 m <sup>3</sup>
		t <sub>p 75- 25 actual</sub>	time 3600.00 s
		Infiltration Coefficient	f 4.014E-06 ms <sup>-1</sup>

**NOTES:**

See SW3/13 log for detailed soil strata details: slightly sandy gravelly SILT

No groundwater was encountered, pit assumed unsaturated.

Infiltration rate calculated over actual fall.


**P16185 N6 GCTP****Test 2****SW3/13****06/12/2016**

l, m                    **2.3**                    b, m                    **1.2**                    d, m                    **3.8**  
 l\_base, m            **2.3**                    d\_eff, m               **3.33**  
 l\_eff, m               **2.3**                    d\_act, m               **0.73**

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.47	0	3.33	0.00	0.000
5	0.47	300	3.33	0.00	0.000
20	0.52	1200	3.28	0.05	0.138
45	0.56	2700	3.24	0.09	0.248
60	0.57	3600	3.23	0.10	0.276
150	0.67	9000	3.13	0.20	0.552
270	0.77	16200	3.03	0.30	0.828
330	0.8	19800	3.00	0.33	0.911
1200	1.2	72000	2.60	0.73	2.015

Area                    2.76 m<sup>2</sup>  
 50% Area\_ef           14.415 m<sup>2</sup>           V<sub>p75-25 theory</sub> volume           4.5954 m<sup>3</sup>  
 50% Area\_ac           5.315 m<sup>2</sup>           V<sub>p 75 - 25 actu</sub> volume           1.0074 m<sup>3</sup>  
                                  t<sub>p 75- 25 actual</sub> time           39960.00 s

Infiltration Coefficient *f*           4.74322E-06 ms<sup>-1</sup>

**NOTES:**

See SW3/13 log for detailed soil strata details: slightly sandy gravelly SILT

No groundwater was encountered, pit assumed unsaturated.

Infiltration rate calculated over actual fall.



Number: SW03-13

Project N6 GCTP  
Project No P16185  
Engineer Arup











Number: SW03-13

Project N6 GCTP  
Project No P16185  
Engineer Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 533110.49 - 728555.83 <b>Level:</b> 21.68	<b>Date</b> 08/12/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 1.20 x 3.50 <b>Depth:</b> 4.50	<b>Scale</b> 1:25 <b>Logged</b> DMC
<b>Client:</b> Arup			

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.20	21.48		Topsoil.	
				0.40	21.28		Soft, grey, slightly sandy SILT.	
	0.50 - 1.50 0.50 - 1.50	B D					Soft, brown, slightly sandy slightly gravelly CLAY. Gravel is fine to coarse and angular.	1
	2.00 - 2.50 2.00 - 2.50	B D		1.70	19.98		Soft to firm, light grey, slightly sandy CLAY. Sand is fine to medium.	2
	3.00 - 3.50 3.00 - 3.50	B D		2.90	18.78		Dark grey black, slightly gravelly slightly sandy peaty SILT.	3
	4.00 - 4.50 4.00 - 4.50	B D						4
				4.50	17.18		End of Pit at 4.50m	5

**Stability:** Good.  
**Plant:** 14T track machine.  
**Backfill:** Arisings.  
**Groundwater:** None encountered.  
**Remarks:** Soakaway pit terminated at required depth of 4.50m bgl. Soakaway test carried out (BRE 365).

P16185

N6 GCTP

Test 1


SW3/14

08/12/2016

d, m	4.5
l, m	3.5
b, m	1.2
d_eff, m	0.86
l_base, m	3.5
d_act, m	0.00
l_eff, m	3.5

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	3.64	0	0.86	0.00	0.000
0.5	3.64	30	0.86	0.00	0.000
1	3.64	60	0.86	0.00	0.000
1.5	3.64	90	0.86	0.00	0.000
2	3.64	120	0.86	0.00	0.000
3	3.64	180	0.86	0.00	0.000
5	3.64	300	0.86	0.00	0.000
10	3.64	600	0.86	0.00	0.000
20	3.64	1200	0.86	0.00	0.000
30	3.64	1800	0.86	0.00	0.000
45	3.64	2700	0.86	0.00	0.000
60	3.64	3600	0.86	0.00	0.000

Area	4.2 m <sup>2</sup>			
50% Area_eff, a <sub>p50</sub>	8.242 m <sup>2</sup>	V <sub>p75-25 theory</sub>	volume	1.806 m <sup>3</sup>
50% Area_act, a <sub>p50</sub>	m <sup>2</sup>	V <sub>p 75 - 25 actual</sub>	volume	m <sup>3</sup>
		t <sub>p 75- 25 actual</sub>	time	s
	Infiltration Coefficient	f		ms <sup>-1</sup>

**NOTES:**

See SW3/15 log for detailed soil strata details: slightly gravelly sandy CLAY/SILT

No groundwater was encountered, pit assumed unsaturated.

Infiltration rate not applicable.

Pit wall collapsed overnight.Final reading disregarded.





Number: SW03-14


Project N6 GCTP  
Project No P16185  
Engineer Arup










Number: SW03-14

Project N6 GCTP  
Project No P16185  
Engineer Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 533069.52 - 728487.25 <b>Level:</b> 22.73	<b>Date</b> 08/12/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 1.20  3.80	<b>Scale</b> 1:25
<b>Client:</b> Arup		<b>Depth:</b> 4.50	<b>Logged</b> DMC

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.20	22.53		Topsoil.	
	0.50 - 1.00 0.50 - 1.00	B D					Soft, brown, slightly gravelly slightly sandy SILT. Sand is fine to coarse.	1
	1.50 - 2.00 1.50 - 2.00	B D		1.10	21.63		Stiff, light grey brown, slightly gravelly very sandy SILT with medium cobble content. Sand is fine to coarse. Gravel is fine to coarse, sub-angular to sub-rounded. Cobbles are 63mm to 200mm dia, sub-rounded, Limestone lithology. <i>Cobble content increases with depth.</i>	2
	2.50 - 3.00 2.50 - 3.00	B D		2.50	20.23		Light grey brown, very sandy very silty GRAVEL with cobble content.	3
	3.50 - 4.50 3.50 - 4.50	B D		3.50	19.23		Light grey brown, slightly gravelly slightly sandy SILT with cobble content.	4
				4.50	18.23		End of Pit at 4.50m	5

**Stability:** Good.  
**Plant:** 14T track machine.  
**Backfill:** Arisings.  
**Groundwater:** None encountered.  
**Remarks:** Soakaway pit terminated at required depth of 4.50m bgl. Soakaway test carried out (BRE 365).

P16185

N6 GCTP

Test 1


SW3/15

08/12/2016

d, m	4.5
l, m	3.8
b, m	1.2
d_eff, m	1.05
l_base, m	3.8
d_act, m	0.10
l_eff, m	3.8

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	3.45	0	1.05	0.00	0.000
0.5	3.45	30	1.05	0.00	0.000
1	3.46	60	1.04	0.01	0.046
1.5	3.46	90	1.04	0.01	0.046
2	3.48	120	1.02	0.03	0.137
2.5	3.48	150	1.02	0.03	0.137
10	3.5	600	1.00	0.05	0.228
20	3.51	1200	0.99	0.06	0.274
25	3.51	1500	0.99	0.06	0.274
30	3.52	1800	0.98	0.07	0.319
45	3.52	2700	0.98	0.07	0.319
60	3.53	3600	0.97	0.08	0.365
80	3.54	4800	0.96	0.09	0.410
100	3.54	6000	0.96	0.09	0.410
120	3.54	7200	0.96	0.09	0.410
140	3.54	8400	0.96	0.09	0.410
1050	3.55	63000	0.95	0.10	0.456

Area	4.56 m <sup>2</sup>			
50% Area_eff, a <sub>p50</sub>	9.81 m <sup>2</sup>	V <sub>p75-25 theory</sub>	volume	2.394 m <sup>3</sup>
50% Area_act, a <sub>p50</sub>	5.06 m <sup>2</sup>	V <sub>p 75 - 25 actual</sub>	volume	0.228 m <sup>3</sup>
		t <sub>p 75- 25 actual</sub>	time	3082.00 s
		Infiltration Coefficient	f	1.462E-05 ms <sup>-1</sup>

**NOTES:**

See SW3/15 log for detailed soil strata details: slightly gravelly sandy SILT

No groundwater was encountered, pit assumed unsaturated.

Infiltration rate calculated over actual fall.



Number: SW03-15

Project  
Project No  
Engineer

N6 GCTP  
P16185  
Arup










Number: SW03-15

Project N6 GCTP  
Project No P16185  
Engineer Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 533014.93 - 728441.91 <b>Level:</b> 19.56	<b>Date</b> 08/12/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 3.20 <b>Depth:</b> 4.30	<b>Scale</b> 1:25 <b>Logged</b> DMC
<b>Client:</b> Arup			

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.30	19.26		Topsoil.	
	0.50 - 1.50 0.50 - 1.50	B D					Soft to firm, light grey cream, CLAY.	1
	1.50 - 2.90 1.50 - 2.90	B D		1.50	18.06		Stiff, dark grey, slightly sandy gravelly CLAY with cobble content. Sand is fine to coarse. Gravel is fine to coarse, sub-angular to sub-rounded.	2
	3.00 - 4.00 3.00 - 4.00	B D		2.90	16.66		Firm, yellowish brown, very sandy very silty GRAVEL with medium cobble content. Sand is fine to coarse. Gravel is fine to coarse, sub-angular to sub-rounded. Cobbles are 63mm to 200mm dia sub-rounded, Limestone lithology. <i>Cobble content increases with depth.</i>	3
				4.30	15.26		End of Pit at 4.30m	4
								5

<b>Stability:</b> Good.	<b>Groundwater:</b> None encountered.
<b>Plant:</b> 14T track machine.	
<b>Backfill:</b> Arisings.	
<b>Remarks:</b> Soakaway pit terminated at 4.30m bgl. Soakaway test carried out (BRE 365).	

P16185

N6 GCTP

Test 1


SW3/16

08/12/2016

d, m	4.3
l, m	3.2
b, m	1.6
d_eff, m	1.40
l_base, m	3.2
d_act, m	0.59
l_eff, m	3.2

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	2.9	0	1.40	0.00	0.000
1	2.9	60	1.40	0.00	0.000
2	2.92	120	1.38	0.02	0.102
3	2.93	180	1.37	0.03	0.154
4	2.94	240	1.36	0.04	0.205
5	2.95	300	1.35	0.05	0.256
10	3	600	1.30	0.10	0.512
15	3	900	1.30	0.10	0.512
45	3.02	2700	1.28	0.12	0.614
60	3.07	3600	1.23	0.17	0.870
80	3.1	4800	1.20	0.20	1.024
180	3.14	10800	1.16	0.24	1.229
270	3.18	16200	1.12	0.28	1.434
330	3.28	19800	1.02	0.38	1.946
855	3.48	51300	0.82	0.58	2.970
930	3.49	55800	0.81	0.59	3.021

Area	5.12 m <sup>2</sup>			
50% Area_eff, a <sub>p50</sub>	11.84 m <sup>2</sup>	V <sub>p75-25 theory</sub>	volume	3.584 m <sup>3</sup>
50% Area_act, a <sub>p50</sub>	7.952 m <sup>2</sup>	V <sub>p 75 - 25 actual</sub>	volume	1.5104 m <sup>3</sup>
		t <sub>p 75- 25 actual</sub>	time	25767.00 s
		Infiltration Coefficient	f	7.371E-06 ms <sup>-1</sup>

**NOTES:**

See SW3/16 log for detailed soil strata details: slightly gravelly slightly sandy SILT  
 No groundwater was encountered, pit assumed unsaturated.  
 Infiltration rate calculated over actual fall.





Number: SW03-16





Project N6 GCTP  
Project No P16185  
Engineer Arup



Number: SW03-16

Project N6 GCTP  
Project No P16185  
Engineer Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 532695.57 - 728363.07 <b>Level:</b> 16.35	<b>Date</b> 07/12/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 1.25 <span style="border: 1px solid black; padding: 2px;">1.70</span>	<b>Scale</b> 1:25
<b>Client:</b> Arup		<b>Depth:</b> 1.60	<b>Logged</b> DMC

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
	0.20 - 0.40 0.20 - 0.40	B D		0.15	16.20		Topsoil.	
							Soft, grey brown, slightly gravelly sandy CLAY. Gravel is fine and sub-angular.	
	0.50 - 1.50 0.50 - 1.50	B D		0.40	15.95		Soft to firm, brown, CLAY.	
							1.50 - 1.60: Grey in colour.	
				1.60	14.75		End of Pit at 1.60m	

<b>Stability:</b> Good.	<b>Groundwater:</b> None encountered.
<b>Plant:</b> 14T track machine.	
<b>Backfill:</b> Arisings.	
<b>Remarks:</b> Soakaway pit terminated at required depth of 1.60m bgl. Soakaway test carried out (BRE 365).	



P16185

N6 GCTP

Test 1

SW3/17


07/12/2016

l, m 1.7 b, m 1.25 d, m 1.6  
 l\_base, m 1.7 d\_eff, m 1.50  
 l\_eff, m 1.7 d\_act, m 0.22

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.1	0	1.50	0.00	0.000
1	0.1	60	1.50	0.00	0.000
5	0.1	300	1.50	0.00	0.000
10	0.105	600	1.50	0.00	0.011
15	0.11	900	1.49	0.01	0.021
45	0.11	2700	1.49	0.01	0.021
60	0.11	3600	1.49	0.01	0.021
80	0.11	4800	1.49	0.01	0.021
100	0.13	6000	1.47	0.03	0.064
120	0.14	7200	1.46	0.04	0.085
140	0.14	8400	1.46	0.04	0.085
160	0.14	9600	1.46	0.04	0.085
180	0.15	10800	1.45	0.05	0.106
200	0.15	12000	1.45	0.05	0.106
220	0.15	13200	1.45	0.05	0.106
240	0.16	14400	1.44	0.06	0.128
260	0.16	15600	1.44	0.06	0.128
300	0.16	18000	1.44	0.06	0.128
350	0.17	21000	1.43	0.07	0.149
1440	0.32	86400	1.28	0.22	0.468

Area 2.125 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub> 6.55 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 1.59375 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> 2.774 m<sup>2</sup> V<sub>p75-25 actual</sub> volume 0.23375 m<sup>3</sup>  
 t<sub>p75-25 actual</sub> time 48342.00 s

Infiltration Coefficient *f* 1.743E-06 ms<sup>-1</sup>

**NOTES:**

See SW3/17 log for detailed soil strata details: slightly gravelly SILT/CLAY

No groundwater was encountered, pit assumed unsaturated.







Infiltration rate calculated over actual fall.



Number: SW03-17

Project N6 GCTP  
Project No P16185  
Engineer Arup

<b>Project Name:</b> N6 GCTP Phase 3	<b>Project No.</b> P16185	<b>Co-ords:</b> 532711.15 - 728444.80 <b>Level:</b> 16.07	<b>Date</b> 07/12/2016
<b>Location:</b> Galway City, Co. Galway		<b>Dimensions (m):</b> 1.20 x 1.80 <b>Depth:</b> 4.50	<b>Scale</b> 1:25 <b>Logged</b> DMC
<b>Client:</b> Arup			

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description	
	Depth	Type	Results					
				0.20	15.87		Topsoil.	
	0.50 - 1.00 0.50 - 1.00	B D					Soft to firm, slightly sandy slightly gravelly CLAY. Gravel is fine to medium and sub-angular.	1
	1.50 - 2.00 1.50 - 2.00	B D		1.40	14.67		Soft, light grey, slightly sandy gravelly SILT. Sand is fine to coarse. Gravel is fine to coarse and sub-angular.	
	2.00 - 2.50 2.00 - 2.50	B D		2.00	14.07		Soft to firm, grey brown, slightly gravelly slightly sandy CLAY. <i>2.00 - 3.50m: Thin bands of fine sand (5mm).</i>	2
	3.00 - 3.50 3.00 - 3.50	B D					Soft, blue, CLAY.	3
	3.50 - 4.50 3.50 - 4.50	B D		3.50	12.57			4
				4.50	11.57		End of Pit at 4.50m	5

**Stability:** Good.  
**Plant:** 14T track machine.  
**Backfill:** Arisings.  
**Groundwater:** None encountered.  
**Remarks:** Soakaway pit terminated at required depth of 4.50m bgl. Soakaway test carried out (BRE 365).

P16185

N6 GCTP

Test 1


SW3/18

07/12/2016

l, m 1.8 b, m 1.2 d, m 4.5  
 l\_base, m 1.8 d\_eff, m 1.02  
 l\_eff, m 1.8 d\_act, m

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	3.48	0	1.02	0.00	0.000
1	3.48	60	1.02	0.00	0.000
5	3.48	300	1.02	0.00	0.000
10	3.48	600	1.02	0.00	0.000
20	3.48	1200	1.02	0.00	0.000
30	3.48	1800	1.02	0.00	0.000
45	3.47	2700	1.03	-0.01	-0.022
60	3.47	3600	1.03	-0.01	-0.022
80	3.47	4800	1.03	-0.01	-0.022
100	3.47	6000	1.03	-0.01	-0.022
120	3.47	7200	1.03	-0.01	-0.022
140	3.47	8400	1.03	-0.01	-0.022
160	3.47	9600	1.03	-0.01	-0.022
180	3.47	10800	1.03	-0.01	-0.022
200	3.47	12000	1.03	-0.01	-0.022
220	3.47	13200	1.03	-0.01	-0.022
240	3.47	14400	1.03	-0.01	-0.022
1200	3.47	72000	1.03	-0.01	-0.022

Area 2.16 m<sup>2</sup>  
 50% Area\_eff, a<sub>p50</sub> 5.22 m<sup>2</sup> V<sub>p75-25 theory</sub> volume 1.1016 m<sup>3</sup>  
 50% Area\_act, a<sub>p50</sub> m<sup>2</sup> V<sub>p 75 - 25 actual</sub> volume m<sup>3</sup>  
 t<sub>p 75- 25 actual</sub> time s  
 Infiltration Coefficient *f* ms<sup>-1</sup>

**NOTES:**

See SW3/18 log for detailed soil strata details: slightly gravelly slightly sandy SILT

No groundwater was encountered, pit assumed unsaturated.

Infiltration rate not applicable.





Number: SW03-18

Project  
Project No  
Engineer

N6 GCTP  
P16185  
Arup





Number: SW03-18

Project N6 GCTP  
Project No P16185  
Engineer Arup



**N6 GCTP**

## Test 1

SW3/19


**12/12/2016**

				d, m	<b>0.35</b>
l, m	<b>2.3</b>	b, m	<b>1</b>	d_eff, m	<b>0.27</b>
l_base, m	<b>2.3</b>			d_act, m	<b>0.05</b>
l_eff, m	<b>2.3</b>				

Time, min	Measure, m bgl	Time, sec	Depth water, m	Fall, m	Volume
0	0.08	0	0.27	0.00	0.000
0.5	0.1	30	0.25	0.02	0.046
1	0.12	60	0.23	0.04	0.092
1.5	0.13	90	0.22	0.05	0.115
2	0.13	120	0.22	0.05	0.115
2.5	0.13	150	0.22	0.05	0.115
3	0.13	180	0.22	0.05	0.115
3.5	0.13	210	0.22	0.05	0.115
4	0.13	240	0.22	0.05	0.115
4.5	0.13	270	0.22	0.05	0.115
5	0.13	300	0.22	0.05	0.115
6	0.13	360	0.22	0.05	0.115
7	0.13	420	0.22	0.05	0.115
8	0.13	480	0.22	0.05	0.115
9	0.13	540	0.22	0.05	0.115
10	0.13	600	0.22	0.05	0.115
15	0.13	900	0.22	0.05	0.115
30	0.13	1800	0.22	0.05	0.115
50	0.13	3000	0.22	0.05	0.115
100	0.13	6000	0.22	0.05	0.115
140	0.13	8400	0.22	0.05	0.115
180	0.13	10800	0.22	0.05	0.115
220	0.13	13200	0.22	0.05	0.115
260	0.13	15600	0.22	0.05	0.115
1140	0.13	68400	0.22	0.05	0.115

Area	2.3 m^2			
50% Area_eff,	3.191 m^2	V <sub>p75-25 theory</sub>	volume	0.3105 m^3
50% Area_act,	2.465 m^2	V <sub>p 75 - 25 actual</sub>	volume	0.0575 m^3
		t <sub>p 75- 25 actual</sub>	time	36.60 s

Infiltration Coefficient	$f$	0.0006373 ms <sup>-1</sup>
--------------------------	-----	----------------------------



**NOTES:**

See SW3/19 log for detailed soil strata details: slightly sandy gravelly SILT  
No groundwater was encountered, pit assumed unsaturated.  
Infiltration rate calculated over actual fall.





Number: SW03-19


Project N6 GCTP  
Project No P16185  
Engineer Arup

**P16185 Rising head permeability test**

Location **Monitoring well**  
 BH ID **BH-MW64**  $H_w/H_o$  **2.99**  
 Casing diameter **200** mm  
 Casing depth **8.3** m  
 Borehole depth **8.3** m  
 Groundwater level **4.10** mbgl  
 Date **28/03/2017**

Min	Sec	depth, m bgl	vol, cu.m	$H_t$	$\log H_o/H_t$
1	60	7.090	0.22263	2.990	0.000
2	120	7.090	0.22263	2.990	0.000
3	180	7.090	0.22263	2.990	0.000
4	240	7.090	0.22263	2.990	0.000
5	300	7.090	0.22263	2.990	0.000
10	600	7.080	0.22231	2.980	0.001
15	900	7.080	0.22231	2.980	0.001
20	1200	7.080	0.22231	2.980	0.001
25	1500	7.080	0.22231	2.980	0.001
30	1800	7.080	0.22231	2.980	0.001
35	2100	7.080	0.22231	2.980	0.001
40	2400	7.080	0.22231	2.980	0.001
45	2700	7.080	0.22231	2.980	0.001
60	3600	7.070	0.22200	2.970	0.003
90	5400	7.060	0.22168	2.960	0.004
120	7200	7.050	0.22137	2.950	0.006
150	9000	7.045	0.22121	2.945	0.007
180	10800	7.035	0.22090	2.935	0.008
210	12600	7.030	0.22074	2.930	0.009
240	14400	7.025	0.22059	2.925	0.010

$k_{mean}$  **1.20E-08 ms<sup>-1</sup>**  
 $k_H = k_V$



## N6 GWTP Stepped Pump Test

Flow Rate ( L / min )	Time ( min )	Pump Well	MW 3/63	MW 3/64	Note
0	0	4.52	7.22	5.09	15 mins spent getting accurate 1 L/min reading
1 L / min	0.5				
	1	4.57	7.22	5.09	
	1.5				
	2	4.57	7.22	5.09	
	2.5				
	3	4.5	7.22	5.09	
	3.5				
	4	4.65	7.22	5.09	
	4.5				
	5	4.75	7.22	5.09	
	5.5				
	6	4.77	7.22	5.09	
	6.5	4.79	7.22	5.09	
	7	4.81	7.22	5.09	
	7.5	4.83	7.22	5.09	
	8	4.85	7.22	5.09	
	8.5	4.87	7.22	5.09	
	9	4.88	7.22	5.09	
	9.5	4.89	7.22	5.09	
	10	4.9	7.22	5.09	
	12	4.96	7.22	5.09	
	14	5.03	7.22	5.09	
	16	5.1	7.22	5.09	Pump stopped pumping due to height of hose
	18	5.11	7.22	5.09	
	20	5.11	7.22	5.09	
	25		7.22	5.09	
	30	5.28	7.22	5.09	
	35	5.475	7.22	5.09	
	40	5.58	7.22	5.095	
	45	5.67	7.22	5.1	
	50	5.75	7.22	5.1	
	55	5.81	7.22	5.1	
	60	5.88	7.22	5.1	

Depth before data loggers removed-

PW 4.52 m

MW 3/63 7.22m

MW 3/64 5.09m

N.B all levels are from top of standpipe.

Top of standpipe to groundlevel, PW- 0.49m

MW 3/63- 0.85m

MW 3/64- 0.96m

Pump installed at 15m below top of standpipe on pump well ( PW)



## N6 GWTP Stepped Pump Test

Flow Rate ( L / min )	Time ( min )	Pump Well	MW 3/63	MW 3/64	Note
0	60 mins	5.88	7.22	5.1	2 mins spent getting accurate 2 L/min reading
2 L / min	0.5	5.87			
	1	5.89	7.22	5.1	
	1.5	5.93			
	2	5.99	7.22	5.1	
	2.5	6.02			
	3	6.08	7.22	5.1	
	3.5	6.08			
	4	6.1	7.22	5.1	
	4.5	6.11			
	5	6.12	7.22	5.1	
	5.5	6.16			
	6	6.19	7.22	5.1	
	6.5	6.215	7.22	5.1	
	7	6.24	7.22	5.1	
	7.5	6.27	7.22	5.1	
	8	6.29	7.22	5.1	
	8.5	6.32	7.22	5.1	
	9	6.345	7.22	5.1	
	9.5	6.37	7.22	5.1	
	10	6.4	7.22	5.1	
	12	6.49	7.22	5.1	
	14	6.58	7.22	5.1	
	16	6.665	7.22	5.1	
	18	6.77	7.22	5.1	
	20	6.85	7.22	5.1	
	25	7.045	7.22	5.1	
	30	7.23	7.22	5.1	
	35	7.32	7.22	5.1	
	40	7.455	7.22	5.1	
	45	7.69	7.22	5.1	
	50	7.915	7.22	5.1	
	55	8.1	7.22	5.1	
	60	8.26	7.22	5.1	

Depth before data loggers removed-

PW 4.52 m

MW 3/63 7.22m

MW 3/64 5.09m

N.B all levels are from top of standpipe.

Top of standpipe to groundlevel, PW- 0.49m

MW 3/63- 0.85m

MW 3/64- 0.96m

## N6 GWTP Stepped Pump Test

Flow Rate ( L / min )	Time ( min )	Pump Well	MW 3/63	MW 3/64	Note
0	120 mins	8.26	7.22	5.1	5 mins spent getting accurate 3 L/min reading
3 L / min	0.5				
	1		7.22	5.1	
	1.5	8.42			
	2	8.45	7.22	5.1	
	2.5	8.5			
	3	8.55	7.22	5.1	
	3.5	8.59			
	4	8.635	7.22	5.1	
	4.5	8.73			
	5	8.735	7.22	5.1	
	5.5	8.76			
	6	8.8	7.22	5.1	
	6.5	8.84	7.22	5.1	
	7	8.89	7.22	5.1	
	7.5	8.93	7.22	5.1	
	8	8.97	7.22	5.1	
	8.5	9	7.22	5.1	
	9	9.05	7.22	5.1	
	9.5	9.09	7.22	5.1	
	10	9.12	7.22	5.1	
	12	9.295	7.22	5.1	
	14	9.47	7.22	5.1	
	16	9.63	7.22	5.1	
	18	9.76	7.22	5.1	
	20	9.91	7.22	5.1	
	25	10.09	7.22	5.1	
	30	10.31	7.22	5.1	
	35	10.67	7.225	5.1	
	40	10.94	7.225	5.1	
	45		7.225	5.1	
	50	11.51	7.225	5.1	
	55	11.785	7.225	5.1	
	60	12.06	7.225	5.1	

Depth before data loggers removed-

PW 4.52 m

MW 3/63 7.22m

MW 3/64 5.09m

N.B all levels are from top of standpipe.

Top of standpipe to groundlevel, PW- 0.49m

MW 3/63- 0.85m

MW 3/64- 0.96m

## N6 GWTP Stepped Pump Test

Flow Rate ( L / min )	Time ( min )	Pump Well	MW 3/63	MW 3/64	Note
0	180 mins	12.06	7.225	5.1	5 mins spent getting accurate 3.5 L/min reading
3.5 L /min	0.5	12.15			
	1	12.18	7.225	5.1	
	1.5	12.22			
	2	12.27	7.225	5.1	
	2.5	12.31			
	3	12.35	7.225	5.1	
	3.5	12.39			
	4	12.44	7.225	5.1	
	4.5	12.51			
	5	12.57	7.225	5.1	
	5.5				
	6		7.225	5.1	
	6.5	12.75	7.225	5.1	
	7	12.82	7.225	5.1	
	7.5	12.86	7.225	5.1	
	8	12.91	7.225	5.1	
	8.5	12.97	7.225	5.1	
	9	13.04	7.225	5.1	
	9.5	13.08	7.225	5.1	
	10	13.13	7.225	5.1	
	12	13.36	7.225	5.1	
	14	13.58	7.225	5.1	
	16	13.74	7.225	5.1	
	18	13.87	7.225	5.1	
	20	14.07	7.225	5.1	
	25	14.57	7.225	5.1	
	30	15.01	7.225	5.1	
	35				
	40				
	45				
	50				
	55				
	60				

Depth before data loggers removed-

PW 4.52 m

MW 3/63 7.22m

MW 3/64 5.09m

N.B all levels are from top of standpipe.

Top of standpipe to groundlevel, PW- 0.49m

MW 3/63- 0.85m

MW 3/64- 0.96m

# N6 GWTP Stepped Pump Test

## RECHARGE

Flow Rate ( L / min )	Time ( min )	Pump Well	MW 3/63	MW 3/64	Note
0	0	15.01	7.225	5.1	
	0.5	14.94			
	1	14.94	7.225	5.1	
	1.5	14.94			
	2	14.94	7.225	5.1	
	2.5	14.94			
	3	14.94	7.225	5.1	
	3.5	14.94			
	4	14.94	7.225	5.1	
	4.5	14.93			
	5	14.93	7.225	5.1	
	5.5	14.93			
	6	14.93	7.225	5.1	
	6.5	14.93	7.225	5.1	
	7	14.93	7.225	5.1	
	7.5	14.93	7.225	5.1	
	8	14.93	7.225	5.1	
	8.5	14.93	7.225	5.1	
	9	14.92	7.225	5.1	
	9.5	14.92	7.225	5.1	
	10	14.92	7.225	5.1	
	12	14.92	7.225	5.1	
	14	14.92	7.225	5.1	
	16	14.92	7.225	5.1	
	18	14.92	7.225	5.1	
	20	14.92	7.225	5.1	
	25	14.915	7.225	5.1	
	30	14.915	7.225	5.1	
	35	14.915	7.225	5.1	
	40	14.91	7.225	5.1	
	45	14.91	7.225	5.1	
	50	14.91	7.225	5.1	
	55	14.9	7.225	5.1	
	60	14.9	7.225	5.1	
	70	14.89	7.225	5.1	
	80	14.885	7.225	5.1	
	90	14.88	7.225	5.1	

Depth before data loggers removed-

PW 4.52 m

MW 3/63 7.22m

MW 3/64 5.09m

N.B all levels are from top of standpipe.

Top of standpipe to groundlevel, PW- 0.49m

MW 3/63- 0.85m

MW 3/64- 0.96m

## KEY TO SYMBOLS - LABORATORY TEST RESULT

U	Undisturbed Sample	
P	Piston Sample	
TWS	Thin Wall Sample	
B	Bulk Sample - Disturbed	
D	Jar Sample - Disturbed	
W	Water Sample	
pH	Acidity/Alkalinity Index	
SO <sub>3</sub>	% - Total Sulphate Content (acid soluble)	
SO <sub>3</sub>	g/ltr - Water Soluble Sulphate (Water or 2:1 Aqueous Soil Extract)	
+	Calcareous Reaction	
Cl	Chloride Content	
PI	Plasticity Index	
<425	% of material in sample passing 425 micron sieve	
LL	Liquid Limit	
PL	Plastic Limit	
MC	Water Content	
NP	Non Plastic	
Y <sub>b</sub>	Bulk Density	
Y <sub>d</sub>	Dry Density	
Ps	Particle Density	
U/D	Undrained/Drained Triaxial	
U/C	Unconsolidated/Consolidated Triaxial	
T/M	Single Stage/Multistage Triaxial	
100/38	Sample Diameter (mm)	
REM	Remoulded Triaxial Test Specimen	
TST	Triaxial Suction Test	
V	Vane Test	
DSB	Drained Shear Box	
RSB	Residual Shear Box	
RS	Ring Shear	
σ <sub>3</sub>	Cell Pressure	
σ <sub>1</sub> -σ <sub>3</sub>	Deviator Stress	
c	Cohesion	
c <sub>-</sub>	Effective Cohesion Intercept	
φ	Angle of Shearing Resistance - Degrees	
φ <sub>-</sub>	Effective Angle of Shearing Resistance	
ε <sub>f</sub>	Strain at Failure	
*	Failed under 1 <sup>st</sup> Load	
**	Failed under 2 <sup>nd</sup> Load	
#	Untestable	
##	Excessive Strain	
p <sub>o</sub>	Effective Overburden Pressure	
m <sub>v</sub>	Coefficient of Volume Decrease	
c <sub>v</sub>	Coefficient of Consolidation	
Opt	Optimum	
Nat	Natural	
Std	Standard Compaction - 2.5kg Rammer	(¶ CBR)
Hvy	Heavy Compaction - 4.5kg Rammer	(§ CBR)
Vib	Vibratory Compaction	
CBR	California Bearing Ratio	
Sat m.c.	Saturation Moisture Content	
MCV	Moisture Condition Value	



Natural Moisture Content/Atterberg Limits Summary

Job Ref

BS 1377 : Part 2 : 1990 : Clause 3

Location

N6 GCTP Phase 3

P16185

Hole ID	Sample Ref	Depth (m)	Sample Type	Sample Description	MC	LL	PL	PI	% Pass 425
SW03-03	2	0.15	D	Very silty very gravelly SAND	48	63	46	17	85.6
SW03-19	2	0.2	D	Very sandy very silty GRAVEL	19	42	28	14	59.1



# PARTICLE SIZE DISTRIBUTION

BS 1377 : Part 2 : 1990 : Clause 9

Job Ref

P16185

Borehole / Pit No

SW03-03

Location

N6 GCTP Phase 3

Sample No

1

Depth


0.15 m

Soil Description

Very silty very gravelly SAND with high cobble content

Sample type

B




Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.063	15
90	70	0.048	15
75	65	0.034	14
63	54	0.024	13
50	50	0.018	12
37.5	47	0.009	9
28	44	0.007	7
20	43	0.005	5
14	41	0.004	4
10	40	0.003	3
6.3	39	0.002	2
5	38		
3.35	38		
2	37		
1.18	34		
0.6	30		
0.425	28		
0.3	24		
0.212	21		
0.15	18		
0.063	15		

Test Method	
BS 1377 : Part 2 : 1990	
Sieving	Clause 9.2
Sedimentation	Clause 9.5

Sample Proportions	
Cobbles	46.7
Gravel	16.8
Sand	21.3
Silt	13.1
Clay	2.1

Grading Analysis	
D100	125.000
D60	69.153
D10	0.012
Uniformity Coefficient	5791





# PARTICLE SIZE DISTRIBUTION

BS 1377 : Part 2 : 1990 : Clause 9

Job Ref

P16185

Borehole / Pit  
No

SW03-19

Location

N6 GCTP Phase 3

Sample No

1

Depth


0.20 m

Soil Description

Very sandy very silty GRAVEL with medium cobble content

Sample type

B



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	100	0.059	22
90	100	0.043	21
75	100	0.031	20
63	83	0.023	17
50	83	0.017	15
37.5	77	0.009	13
28	73	0.006	12
20	69	0.005	10
14	62	0.003	9
10	58	0.003	8
6.3	52	0.002	6
5	48		
3.35	45		
2	40		
1.18	37		
0.6	34		
0.425	32		
0.3	31		
0.212	29		
0.15	27		
0.063	22		

Test Method	
BS 1377 : Part 2 : 1990	
Sieving	Clause 9.2
Sedimentation	Clause 9.5

Sample Proportions	
Cobbles	17.2
Gravel	42.4
Sand	18.7
Silt	14.8
Clay	6.8

Grading Analysis	
D100	75.000
D60	12.112
D10	0.005
Uniformity Coefficient	2566



## Contract Number: 33812

Client's Reference: **P16185**

Report Date: **03-02-2017**

Client **Priority Geotechnical Limited**  
**Unit 12**  
**Owenacurra Business Park**  
**Midleton**  
**Co. Cork.**

Contract Title: **Galway GCT**  
For the attention of: **Colette Kelly**

Date Received: **17-01-2017**  
Date Commenced: **17-01-2017**  
Date Completed: **03-02-2017**

Test Description	Qty
<b>Moisture Content</b> 1377 : 1990 Part 2 : 3.2 - * UKAS	40
<b>4 Point Liquid &amp; Plastic Limit (LL/PL)</b> 1377 : 1990 Part 2 : 4.3 & 5.3 - * UKAS	24
<b>PSD Wet Sieve method</b> 1377 : 1990 Part 2 : 9.2 - * UKAS	32
<b>PSD: Sedimentation by hydrometer</b> 1377 : 1990 Part 2 : 9.5 - @ Non Accredited Test	31
<b>Organic Matter Content-dichromate method</b> 1377 : 1990 Part 3 : 3 - @ Non Accredited Test	5
<b>Water Soluble Sulphate 2:1 extract</b> 1377 : 1990 Part 3 : 5 - @ Non Accredited Test	4
<b>pH Value of Soil...</b> 1377 : 1990 Part 3 : 9 - @ Non Accredited Test	4

**Notes:** Observations and Interpretations are outside the UKAS Accreditation  
\* - denotes test included in laboratory scope of accreditation  
# - denotes test carried out by approved contractor  
@ - denotes non accredited tests

This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.

**Approved Signatories:**

Alex Wynn (Associate Director) - Benjamin Sharp (Contracts Manager) - Emma Sharp (Office Manager)  
Paul Evans (Quality/Technical Manager) - Vaughan Edwards (Managing Director)



# Laboratory Report



GEO Site & Testing Services Ltd

## Contract Number: 33812

Test Description	Qty
<b>Consolidated Drained Peak Shear Strength - set of 3 - 60 x 60mm Shear Box Specimens by Direct Shearing (3 days)</b> 1377 : 1990 Part 7 : 4 - * UKAS	3
<b>CUD 38mm Consolidated undrained triaxial compression test on a set of three x 38 mm diameter specimens with the measurement of pore water pressure including saturation and consolidation, test duration four days.</b> 1377 : 1990 Part 8 : 7 - @ Non Accredited Test	2
<b>Disposal of Samples on Project</b>	1

**Notes:** Observations and Interpretations are outside the UKAS Accreditation

\* - denotes test included in laboratory scope of accreditation

# - denotes test carried out by approved contractor

@ - denotes non accredited tests

This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced except in full, without the prior written approval of the laboratory.

**Approved Signatories:**

Alex Wynn (Associate Director) - Benjamin Sharp (Contracts Manager) - Emma Sharp (Office Manager)

Paul Evans (Quality/Technical Manager) - Vaughan Edwards (Managing Director)

GEO Site & Testing Services Ltd

Unit 3-4, Heol Aur, Dafen Ind Estate, Dafen, Llanelli, Carmarthenshire SA14 8QN


Tel: 01554 784040 Fax: 01554 784041 info@gstl.co.uk gstl.co.uk

Test Report: Method of the Determination of the plastic limit and plasticity index  
BS 1377 : Part 2 : 1990 Method 5

Client ref: P16185  
Location: Galway GCT  
Contract Number: 33812-

Hole/ Sample Number	Sample Type	Depth m	Moisture Content % Cl. 3.2	Liquid Limit % Cl. 4.3/4.4	Plastic Limit % Cl. 5.	Plasticity Index % Cl. 6.	% Passing .425mm	Remarks
SW03-12/1	B	1.00	11					
SW03-12/2	B	2.00	11					
SW03-13/1	B	1.50	12					
SW03-14/2	D	0.50	22	41	19	22	100	CI Intermediate Plasticity
SW03-14/4	D	2.00	21	42	20	22	100	CI Intermediate Plasticity
SW03-14/6	D	3.00	24		NP		100	
SW03-14/8	D	4.00	41		NP		100	
SW03-15/1	B	0.50	16		NP		70	
SW03-15/2	D	0.50	25					
SW03-15/4	D	1.50	7.8		NP		60	
SW03-15/5	B	2.50	6.9					
SW03-15/6	D	2.50	9.6					
SW03-15/8	D	3.50	4.4		NP		25	
SW03-16/1	B	0.50	24	42	18	24	100	CI Intermediate Plasticity
SW03-16/2	D	0.50	22					
SW03-16/4	D	1.50	4.5					
SW03-16/6	D	3.00	6.9					

Symbols: NP : Non Plastic # : Liquid Limit and Plastic Limit Wet Sieved  
PLASTICITY CHART FOR CASAGRANDE CLASSIFICATION.  
BS 5930:1999+A2:2010



**GSTL**  
GEO SITE & TESTING SERVICES LTD

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)  
Date: 31.1.17

*Emma Sharp*






Test Report: Method of the Determination of the plastic limit and plasticity index  
BS 1377 : Part 2 : 1990 Method 5

Client ref: P16185  
Location: Galway GCT  
Contract Number: 33812-

Hole/ Sample Number	Sample Type	Depth m	Moisture Content % Cl. 3.2	Liquid Limit % Cl. 4.3/4.4	Plastic Limit % Cl. 5.	Plasticity Index % Cl. 6.	% Passing .425mm	Remarks
TP03-50/1	B	0.80	8.9	25	14	11	70	CL Low Plasticity
TP03-50/2	D	0.80	9.1					
TP03-50/4	D	1.50	7.4		NP		56	
TP03-50/6	D	2.00	8.7	29	15	14	75	CL Low Plasticity
TP03-50/8	D	3.00	7.7	29	14	15	70	CL Low Plasticity
TP03-52/2	D	0.20	28					
TP03-52/3	B	0.50	10	30	13	17	70	CL Low Plasticity
TP03-52/4	D	0.50	23	40	16	24	80	CI Intermediate Plasticity
TP03-53/2	D	0.50	22					
TP03-53/3	B	1.00	11	35	15	20	82	CL/I Low/Inter. Plasticity
TP03-53/4	D	1.00	13					
TP03-53/5	B	2.00	9.1	33	16	17	80	CL Low Plasticity
TP03-53/6	D	2.00	10					
TP03-53/8	D	2.50	7.8		NP		60	
TP03-53/10	D	3.50	7.9	28	14	14	69	CL Low Plasticity
BH03-62/1	B	0.00	34	58	29	29	60	CH High Plasticity
BH03-62/2	B	1.00	37					

Symbols: NP : Non Plastic # : Liquid Limit and Plastic Limit Wet Sieved  
PLASTICITY CHART FOR CASAGRANDE CLASSIFICATION.  
BS 5930:1999+A2:2010



**GSTL**  
GEO SITE & TESTING SERVICES LTD

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)  
Date: 31.1.17

*Emma Sharp*





Unit 4  
Heol Aur  
Dafen Ind EstateDafen  
Carmarthenshire  
SA14 8QN  
Tel: 01554 784040  
01554 750752  
Fax: 01554 770529  
01554 784041  
Web: www.geo.uk.com

## Certificate of Analysis

Date: 25-01-17

Client: Priority

Our Reference: 33812

Client Reference: P1S185

Contract Title: Galway

Description: (Total Samples) 9

Date Received: 23-01-17

Date Started: #REF!

Date Completed: 25-01-17

Test Procedures: (BRE BR 279)

Notes:

Solid samples will be disposed 1 month and liquids 2 weeks  
after the date of issue of this test certificate

Approved By:

A handwritten signature in black ink, appearing to read 'Emma Sharp'.

Authorised Signatories:

Emma Sharp  
Laboratory Office Manager

Ben Sharp  
Contracts Manager

Paul Evans  
Quality Manager



Contract No: 33812  
Client Ref: P1S185  
Location: Galway  
Date: 25-01-2017

# Summary of Chemical Analysis

(BRE BR 279)

[illegible]

NCP - No Chloride present

Test Report:

# Particle Size Distribution Test

BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: BH03-62

Sample Number: 2  
Depth from (m): 1.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown gravelly sandy fine to medium silty CLAY.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-12

Sample Number: 1  
Depth from (m): 1.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey sandy fine to coarse GRAVEL



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
**Emma Sharp (Office Manager)**

Date: **30.1.17**

*Handwritten signature*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test

BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-12

Sample Number: 2  
Depth from (m): 2.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey sandy fine to coarse GRAVEL



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-13

Sample Number: 1  
Depth from (m): 1.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown fine to coarse gravelly silty clayey SAND.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:


# Particle Size Distribution Test BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-14

Sample Number: 1  
Depth from (m): 0.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown fine to medium sandy silty CLAY.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-14

Sample Number: 3  
Depth from (m): 2.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown fine to medium sandy silty CLAY.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD





Test Report:


# Particle Size Distribution Test BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-14

Sample Number: 5  
Depth from (m): 3.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown fine to medium silty clayey gravelly SAND containing organic material.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test

BS 1377 Part 2:1990.


Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-14

Sample Number: 7  
Depth from (m): 4.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT

Description: Brown fine to medium clayey silty gravelly SAND containing organic material.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-15

Sample Number: 1  
Depth from (m): 0.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown clayey silty fine to coarse gravelly SAND.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:


# Particle Size Distribution Test BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-15

Sample Number: 3  
Depth from (m): 1.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey fine to coarse gravelly SAND.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-15

Sample Number: 5  
Depth from (m): 2.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey sandy fine to coarse GRAVEL.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
**Emma Sharp (Office Manager)**

Date: **30.1.17**

*Signature*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-15

Sample Number: 5  
Depth from (m): 3.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown gravelly silty clayey sandy fine to coarse SAND.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD




Test Report:

# Particle Size Distribution Test BS 1377 Part 2:1990. Wet Sieve, Clause 9.2

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-16

Sample Number: 3  
Depth from (m): 1.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey sandy fine to coarse GRAVEL with one large cobble.



## Remarks:

# - not determined

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 3.2.17

*Signature*





Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-16

Sample Number: 5  
Depth from (m): 3.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey sandy fine to coarse GRAVEL.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-17

Sample Number: 1  
Depth from (m): 0.20  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown gravelly clayey silty fine to medium SAND.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Signature*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:


# Particle Size Distribution Test BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-17

Sample Number: 3  
Depth from (m): 0.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty CLAY.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-18

Sample Number: 1  
Depth from (m): 0.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown slightly sandy silty CLAY.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 30.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-18

Sample Number: 3  
Depth from (m): 1.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty fine to coarse gravelly clayey SAND.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-18

Sample Number: 5  
Depth from (m): 2.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown fine sandy silty CLAY.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Signature*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test

BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-18

Sample Number: 7  
Depth from (m): 3.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown sandy fine to coarse gravelly silty CLAY.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD





Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: SW03-18

Sample Number: 9  
Depth from (m): 3.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Greyish brown silty CLAY.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:


# Particle Size Distribution Test BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: TP03

Sample Number: 1  
Depth from (m): 0.80  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey fine to coarse gravelly SAND.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
**Emma Sharp (Office Manager)**

Date: **31.1.17**

*Handwritten signature*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: TP03-50

Sample Number: 3  
Depth from (m): 1.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey fine to coarse sandy GRAVEL.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Signature*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: TP03-50

Sample Number: 5  
Depth from (m): 2.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey fine to coarse sandy GRAVEL with many cobbles.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: TP03-50

Sample Number: 7  
Depth from (m): 3.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey fine to coarse sandy GRAVEL.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test

BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185

Contract Number: 33812-

Hole Number: TP03-52

Sample Number: 1

Depth from (m): 0.20

Depth to (m): N/A

Sample Type: B

Location: Galway GCT

Description: Brown gravelly silty clayey fine SAND.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test


BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: TP03-52

Sample Number: 3  
Depth from (m): 0.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey sandy fine to coarse GRAVEL.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Handwritten signature*

**GSTL**  
GEO SITE & TESTING SERVICES LTD





Test Report:

# Particle Size Distribution Test

BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185

Contract Number: 33812-

Hole Number: TP03-53

Sample Number: 1

Depth from (m): 0.50

Depth to (m): N/A

Sample Type: B

Location: Galway GCT

Description: Brown gravelly silty clayey fine to coarse SAND.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Emma Sharp*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test

BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185

Contract Number: 33812-

Hole Number: TP03-53

Sample Number: 3

Depth from (m): 1.00

Depth to (m): N/A

Sample Type: B

Location: Galway GCT

Description: Brown fine to coarse gravelly silty clayey SAND.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Signature*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:

# Particle Size Distribution Test BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: TP03-53

Sample Number: 3  
Depth from (m): 2.00  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey fine to coarse gravelly SAND.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
**Emma Sharp (Office Manager)**

Date: **31.1.17**

*Signature*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:


# Particle Size Distribution Test BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: TP03-53

Sample Number: 7  
Depth from (m): 2.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty sandy clayey fine to coarse GRAVEL.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
**Emma Sharp (Office Manager)**

Date: **31.1.17**

*Signature*

**GSTL**  
GEO SITE & TESTING SERVICES LTD



Test Report:


# Particle Size Distribution Test BS 1377 Part 2:1990.

Wet Sieve & Pipette Analysis, Clause 9.2 & 9.4

Client ref: P16185  
Contract Number: 33812-  
Hole Number: TP03-53

Sample Number: 9  
Depth from (m): 3.50  
Depth to (m): N/A  
Sample Type: B

Location: Galway GCT  
Description: Brown silty clayey sandy fine to coarse GRAVEL with many cobbles.



## Remarks:

Cl 9.4.8 - Sample has not been pretreated

For and behalf of GEO Site & Testing Services Ltd

Authorised By:  
Emma Sharp (Office Manager)

Date: 31.1.17

*Emma Sharp*


**GSTL**  
GEO SITE & TESTING SERVICES LTD



# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number:	TP03-52	Depth from (m):	0.50
Sample Number :		Depth to (m):	3.00
Sample Type:	B		
Particle Density - Mg/m3:	2.65 (Assumed)		
Specimen Tested:	Submerged, Remoulded (Light Tamping) Material above 2mm removed.		
Sample Description:			
Brown slightly silty gravelly (fine-coarse/angular-subrounded) sandy CLAY			
STAGE	1	2	3
Initial Conditions			
Height - mm:	24.27	24.27	24.27
Length - mm:	59.97	59.97	59.97
Moisture Content - %:	9	9	9
Bulk Density - Mg/m3:	2.10	2.10	2.10
Dry Density - Mg/m3:	1.92	1.92	1.92
Voids Ratio:	0.3811	0.3827	0.3825
Normal Pressure- kPa	20	40	60
Consolidation			
Consolidated Height - mm:	24.21	24.03	23.85
Shear			
Rate of Strain (mm/min)	0.010	0.010	0.010
Strain at peak shear stress (mm)	8.38	7.34	7.33
Peak shear Stress - kPa:	9	19	29
PEAK			
Angle of Shearing Resistance: (ϕ)			25.5
Effective Cohesion - kPa:			0



*D.P. Gans*  
Checked Pages 1-4 by:

31/01/17  
Date:

*D.P. Gans*  
Approved Pages 1-4 by:

31/01/17  
Date

Contract No.:  
33812

Galway GCT

Client Ref Number:




P16185

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-52  
Sample Number :

Depth from (m): 0.50  
Depth to (m): 3.00



Galway GCT

Contract No.:  
33812

Client Ref Number:  
P16185  
Figure.






# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-52  
Sample Number :

Depth from (m): 0.50  
Depth to (m): 3.00



Galway GCT

Contract No.:  
33812




Client Ref Number:  
P16185

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-52  
Sample Number :

Depth from (m): 0.50  
Depth to (m): 3.00



Contract No.:  
33812


Galway GCT

Client Ref Number:  
P16185

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number:	TP03-52	Depth from (m):	0.50
Sample Number :	B3	Depth to (m):	3.00
Sample Type:	B		
Particle Density - Mg/m3:	2.65 (Assumed)		
Specimen Tested:	Submerged, Remoulded (Light Tamping) Material above 2mm removed.		
Sample Description:			
Brown slightly silty gravelly (fine-coarse/angular-subrounded) sandy CLAY			
STAGE	1	2	3
Initial Conditions			
Height - mm:	24.27	24.27	24.27
Length - mm:	59.97	59.97	59.97
Moisture Content - %:	9	9	9
Bulk Density - Mg/m3:	2.10	2.10	2.10
Dry Density - Mg/m3:	1.92	1.92	1.92
Voids Ratio:	0.3811	0.3827	0.3825
Normal Pressure- kPa	20	40	60
Consolidation			
Consolidated Height - mm:	24.21	24.03	23.85
Shear			
Rate of Strain (mm/min)	0.010	0.010	0.010
Strain at peak shear stress (mm)	8.38	7.34	7.33
Peak shear Stress - kPa:	9	19	29
PEAK			
Angle of Shearing Resistance: (θ)			25.5
Effective Cohesion - kPa:			



*D.P. Gans*  
Checked Pages 1-4 by:

01/02/17  
Date:

*D.P. Gans*  
Approved Pages 1-4 by: 01/02/17  
Date

Contract No.:  
33812

Galway GCT




Client Ref Number:

P16185

Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.  
BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-52  
Sample Number : B3

Depth from (m): 0.50  
Depth to (m): 3.00



Galway GCT




Contract No.: 33812  
Client Ref Number: P16185  
Figure.

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-52  
Sample Number : B3

Depth from (m): 0.50  
Depth to (m): 3.00



Galway GCT

Contract No.:  
33812




Client Ref Number:  
P16185

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-52  
Sample Number : B3

Depth from (m): 0.50  
Depth to (m): 3.00



Galway GCT


Contract No.:  
33812

Client Ref Number:  
P16185

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number:	TP03-53	Depth from (m):	1.00
Sample Number :	B3	Depth to (m):	3.00
Sample Type:	B		
Particle Density - Mg/m3:	2.65 (Assumed)		
Specimen Tested:	Submerged, Remoulded (Light Tamping) Material above 2mm removed.		
Sample Description:			
Brown slightly silty sandy gravelly (fine-coarse/angular-subrounded) soft CLAY			
STAGE	1	2	3
Initial Conditions			
Height - mm:	24.27	24.27	24.27
Length - mm:	59.97	59.97	59.97
Moisture Content - %:	10	10	10
Bulk Density - Mg/m3:	2.24	2.25	2.25
Dry Density - Mg/m3:	2.05	2.05	2.05
Voids Ratio:	0.2942	0.2931	0.2935
Normal Pressure- kPa	20	40	60
Consolidation			
Consolidated Height - mm:	24.04	23.79	23.54
Shear			
Rate of Strain (mm/min)	0.010	0.010	0.010
Strain at peak shear stress (mm)	9.52	8.44	6.35
Peak shear Stress - kPa:	13	23	34
PEAK			
Angle of Shearing Resistance: (θ)	27.0		
Effective Cohesion - kPa:	3		



*DP Gans*  
Checked Pages 1-4 by:

01/02/17  
Date:

*DP Gans*  
Approved Pages 1-4 by:

01/02/17  
Date

Contract No.:  
33812

Galway GCT

Client Ref Number:

P16185






# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-53  
Sample Number : B3

Depth from (m): 1.00  
Depth to (m): 3.00



Galway GCT

Contract No.:  
33812




Client Ref Number:  
P16185  
Figure.

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-53  
Sample Number : B3

Depth from (m): 1.00  
Depth to (m): 3.00



Galway GCT

Contract No.:  
33812




Client Ref Number:  
P16185

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-53  
Sample Number : B3

Depth from (m): 1.00  
Depth to (m): 3.00



Contract No.:  
33812


Galway GCT

Client Ref Number:  
P16185

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number:	TP03-53	Depth from (m):	2.00
Sample Number :	B5	Depth to (m):	5.00
Sample Type:	B		
Particle Density - Mg/m3:	2.65 (Assumed)		
Specimen Tested:	Submerged, Remoulded (Light Tamping) Material above 2mm removed.		
Sample Description:			
Brown slightly silty sandy gravelly (fine-coarse/angular-subrounded) soft CLAY			
STAGE	1	2	3
Initial Conditions			
Height - mm:	24.50	24.50	24.50
Length - mm:	59.90	59.90	59.90
Moisture Content - %:	11	11	11
Bulk Density - Mg/m3:	2.22	2.22	2.22
Dry Density - Mg/m3:	2.00	2.00	2.00
Voids Ratio:	0.3241	0.3236	0.3242
Normal Pressure- kPa	20	40	60
Consolidation			
Consolidated Height - mm:	24.28	23.97	23.66
Shear			
Rate of Strain (mm/min)	0.010	0.010	0.010
Strain at peak shear stress (mm)	9.74	8.17	7.15
Peak shear Stress - kPa:	13	24	35
PEAK			
Angle of Shearing Resistance: (ϴ)			28.5
Effective Cohesion - kPa:			2



*DP Gans*  
Checked Pages 1-4 by:

01/02/17  
Date:

*DP Gans*  
Approved Pages 1-4 by:

01/02/17  
Date

Contract No.:  
33812

Galway GCT

Client Ref Number:




P16185

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-53  
Sample Number : B5

Depth from (m): 2.00  
Depth to (m): 5.00



Galway GCT

Contract No.:  
33812




Client Ref Number:  
P16185  
Figure.

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-53  
Sample Number : B5

Depth from (m): 2.00  
Depth to (m): 5.00



Galway GCT

Contract No.:  
33812




Client Ref Number:  
P16185

# Test Report: CONSOLIDATED DRAINED SHEARBOX TEST.

BS1377:Part 7:4.5 :1990.

Borehole Number: TP03-53  
Sample Number : B5

Depth from (m): 2.00  
Depth to (m): 5.00



Contract No.:  
33812

Galway GCT

Client Ref Number:  
P16185



Consolidated Undrained Triaxial Compression Test  
BS 1377 : Part 8 : 1990 : 38mm Set of Three

Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00
Date		02/02/2017
Disturbed / Undisturbed		Disturbed

Description of Specimen

Brown silty firm CLAY
-----------------------

Initial Specimen Conditions

Height	mm	76.00	76.00	76.00
Diameter	mm	38.00	38.00	38.00
Area	mm <sup>2</sup>	1134.11	1134.11	1134.11
Volume	cm <sup>3</sup>	86.19	86.19	86.19
Mass	g	192.80	171.00	170.00
Dry Mass	g	135.10	144.00	141.00
Density	Mg/m <sup>3</sup>	2.24	1.98	1.97
Dry Density	Mg/m <sup>3</sup>	1.57	1.67	1.64
Moisture Content	%	43	19	21
Specific Gravity	kN/m <sup>3</sup>	2.65	2.65	2.65
	(assumed/measured)	assumed	assumed	assumed

Final Specimen Conditions

Moisture Content	%	19	19	18
Density	Mg/m <sup>3</sup>	2.40	2.41	2.70
Dry Density	Mg/m <sup>3</sup>	2.01	2.03	2.28

*DP Gnan*

Checked and Approved By

02/02/17  
Date

Client Ref  
P16185

Galway GCT

Contract No

33812

# Consolidated Undrained Triaxial Compression Test

## BS 1377 : Part 8 : 1990 : 38mm Set of Three

### Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

### Test Setup

Date started	31/01/2017	26/01/2017	26/01/2017
Date Finished	01/02/2017	00/01/1900	00/01/1900
Top Drain Used	y	y	y
Base Drain Used	y	y	y
Side Drains Used	y	y	y
Pressure System Number	P11	P10	P11
Cell Number	C11	C10	C11

### Saturation

Cell Pressure Incr.	kPa	100.00	100.00	100.00
Back Pressure Incr.	kPa	95.00	95.00	95.00
Differential Pressure	kPa	5.00	5.00	5.00
Final Cell Pressure	kPa	300.00	500.00	500.00
Final Pore Pressure	kPa	296.00	395.50	495.00
Final B Value		0.97	0.95	0.97

### Consolidation

Effective Pressure	kPa	200.00	300.00	400.00
Cell Pressure	kPa	300.00	500.00	500.00
Back Pressure	kPa	100.00	200.00	100.00
Excess Pore Pressure	kPa	196.00	296.00	395.00
Pore Pressure at End	kPa	100.00	200.00	100.00
Consolidated Volume	cm <sup>3</sup>	67.19	70.94	61.89
Consolidated Height	mm	70.42	71.52	68.86
Consolidated Area	mm <sup>2</sup>	967.45	1000.34	920.96
Vol. Compressibility	m <sup>2</sup> /MN	2.20436	0.88465	2.81926
Consolidation Coef.	m <sup>2</sup> /yr.	0.29190	0.02043	0.37693

*DP Gans*

Checked and Approved By

02/02/17  
Date

Galway GCT

Client Ref

P16185

Contract No



33812

# Consolidated Undrained Triaxial Compression Test BS 1377 : Part 8 : 1990 : 38mm Set of Three

## Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

## Consolidation Stage



*DP Gao*

Checked and Approved By

02/02/17

Date

Client Ref

P16185

Galway GCT

Contract No

33812


Consolidated Undrained Triaxial Compression Test  
BS 1377 : Part 8 : 1990 : 38mm Set of Three

Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

Shearing

Initial Cell Pressure	kPa	300	500	500
Initial Pore Pressure	kPa	100	200	100
Rate of Strain	mm/min	0.0150	0.0011	0.0189
Max Deviator Stress				
Axial Strain		9.856	8.977	8.801
Axial Stress	kPa	383.891	562.01	689.23
Cor. Deviator stress	kPa	372.470	549.77	676.95
Effective Major Stress	kPa	516.470	770.27	951.95
Effective Minor Stress	kPa	145.000	220.50	275.00
Effective Stress Ratio		3.562	3.493	3.46
s'	kPa	330.735	495.39	613.47
t'	kPa	185.735	274.89	338.47
Max Effective Principle Stress Ratio				
Axial Strain		8.592	8.355	8.801
Axial Stress	kPa	382.659	561.823	689.225
Cor. Deviator stress	kPa	370.498	549.710	676.947
Effective Major Stress	kPa	513.498	768.710	951.947
Effective Minor Stress	kPa	143.000	219.000	275.000
Effective Stress Ratio		3.591	3.510	3.462
s'	kPa	328.249	493.855	613.473
t'	kPa	185.249	274.855	338.473
Shear Resistance Angle	degs	33.0		
Cohesion c'	kPa	5		

  
Checked and Approved By

02/02/17  
Date

Galway GCT



Client Ref  
P16185  
Contract No  
33812

# Consolidated Undrained Triaxial Compression Test BS 1377 : Part 8 : 1990 : 38mm Set of Three

## Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

## Shearing Stage



DP Gans

Checked and Approved By

02/02/17  
Date

Galway GCT

Client Ref  
P16185

Contract No

33812



# Consolidated Undrained Triaxial Compression Test

## BS 1377 : Part 8 : 1990 : 38mm Set of Three

### Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

### Shearing Stage



*DP Gans*

Checked and Approved By

02/02/17

Date

Client Ref

P16185

Galway GCT

Contract No


33812

Consolidated Undrained Triaxial Compression Test  
BS 1377 : Part 8 : 1990 : 38mm Set of Three

Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

Shearing Stage



*DP GCT*

Checked and Approved By

02/02/17  
Date

Galway GCT

Client Ref

P16185

Contract No

33812



Consolidated Undrained Triaxial Compression Test  
BS 1377 : Part 8 : 1990 : 38mm Set of Three

Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00



*DP Gans*

Checked and Approved By

02/02/17  
Date

Client Ref  
P16185

Contract No  
33812

## Consolidated Undrained Triaxial Compression Test

BS 1377 : Part 8 : 1990 : 38mm Set of Three

### Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00
Date		02/02/2017
Disturbed / Undisturbed		Disturbed

### Description of Specimen

Brown silty firm CLAY
-----------------------

### Initial Specimen Conditions

Height	mm	76.00	74.00	76.00
Diameter	mm	38.00	37.00	38.00
Area	mm <sup>2</sup>	1134.11	1075.21	1134.11
Volume	cm <sup>3</sup>	86.19	79.57	86.19
Mass	g	197.80	196.20	192.80
Dry Mass	g	179.00	180.20	177.30
Density	Mg/m <sup>3</sup>	2.29	2.47	2.24
Dry Density	Mg/m <sup>3</sup>	2.08	2.26	2.06
Moisture Content	%	11	9	9
Specific Gravity	kN/m <sup>3</sup>	2.65	2.65	2.65
	(assumed/measured)	assumed	assumed	assumed

### Final Specimen Conditions

Moisture Content	%	10	9	9
Density	Mg/m <sup>3</sup>	2.52	2.54	2.63
Dry Density	Mg/m <sup>3</sup>	2.30	2.34	2.42

DP Gnan

Checked and Approved By

02/02/17  
Date

Client Ref

P16185

Contract No

33812

Galway GCT

## Consolidated Undrained Triaxial Compression Test

BS 1377 : Part 8 : 1990 : 38mm Set of Three

### Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

### Test Setup

Date started	31/01/2017	26/01/2017	26/01/2017
Date Finished	01/02/2017	00/01/1900	00/01/1900
Top Drain Used	y	y	y
Base Drain Used	y	y	y
Side Drains Used	y	y	y
Pressure System Number	P11	P10	P11
Cell Number	C11	C10	C11

### Saturation

Cell Pressure Incr.	kPa	100.00	100.00	100.00
Back Pressure Incr.	kPa	95.00	95.00	95.00
Differential Pressure	kPa	5.00	5.00	5.00
Final Cell Pressure	kPa	300.00	500.00	500.00
Final Pore Pressure	kPa	296.00	396.50	497.00
Final B Value		0.97	0.95	0.97

### Consolidation

Effective Pressure	kPa	200.00	300.00	400.00
Cell Pressure	kPa	300.00	500.00	500.00
Back Pressure	kPa	100.00	200.00	100.00
Excess Pore Pressure	kPa	196.00	297.00	397.00
Pore Pressure at End	kPa	100.00	200.00	100.00
Consolidated Volume	cm <sup>3</sup>	77.99	77.12	73.19
Consolidated Height	mm	73.59	73.24	72.18
Consolidated Area	mm <sup>2</sup>	1062.19	1053.14	1020.08
Vol. Compressibility	m <sup>2</sup> /MN	0.95136	0.15396	1.50825
Consolidation Coef.	m <sup>2</sup> /yr.	2.64027	0.02043	2.16131

*DP Gans*

Checked and Approved By

02/02/17

Date

Client Ref

P16185

Galway GCT

Contract No

33812



# Consolidated Undrained Triaxial Compression Test

BS 1377 : Part 8 : 1990 : 38mm Set of Three

## Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

## Consolidation Stage



*DP Gao*  
Checked and Approved By

02/02/17  
Date

Galway GCT

Client Ref

P16185

Contract No

33812

## Consolidated Undrained Triaxial Compression Test

BS 1377 : Part 8 : 1990 : 38mm Set of Three

### Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

### Shearing


Initial Cell Pressure	kPa	300	500	500
Initial Pore Pressure	kPa	100	200	100
Rate of Strain	mm/min	0.1418	0.0011	0.1139

### Max Deviator Stress

Axial Strain		6.713	6.704	7.398
Axial Stress	kPa	597.215	807.04	1037.60
Cor. Deviator stress	kPa	586.438	795.27	1025.55
Effective Major Stress	kPa	772.438	1063.27	1375.55
Effective Minor Stress	kPa	187.000	268.00	350.00
Effective Stress Ratio		4.131	3.967	3.93
s'	kPa	479.719	665.63	862.77
t'	kPa	292.719	397.63	512.77

### Max Effective Principle Stress Ratio

Axial Strain		5.612	6.404	6.359
Axial Stress	kPa	586.489	804.753	1032.722
Cor. Deviator stress	kPa	574.937	793.039	1020.835
Effective Major Stress	kPa	757.937	1060.039	1368.835
Effective Minor Stress	kPa	183.000	267.000	348.000
Effective Stress Ratio		4.142	3.970	3.933
s'	kPa	470.469	663.520	858.418
t'	kPa	287.469	396.520	510.418
Shear Resistance Angle	deg	35.6		
Cohesion c'	kPa	15		

  
 Checked and Approved By

02/02/17  
 Date

Client Ref  
 P16185

Galway GCT

Contract No

33812



# Consolidated Undrained Triaxial Compression Test

BS 1377 : Part 8 : 1990 : 38mm Set of Three

## Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

## Shearing Stage



DP Gans

Checked and Approved By

02/02/17

Date

Client Ref

P16185

Galway GCT

Contract No

33812



# Consolidated Undrained Triaxial Compression Test

BS 1377 : Part 8 : 1990 : 38mm Set of Three

## Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

## Shearing Stage



*DP Gans*

Checked and Approved By

02/02/17

Date

Client Ref

P16185

Galway GCT

Contract No

33812




## Consolidated Undrained Triaxial Compression Test

BS 1377 : Part 8 : 1990 : 38mm Set of Three

### Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00

### Shearing Stage



*DP Gung*

Checked and Approved By

02/02/17

Date

Galway GCT

Client Ref

P16185

Contract No

33812

# Consolidated Undrained Triaxial Compression Test

BS 1377 : Part 8 : 1990 : 38mm Set of Three

## Specimen Details

Borehole		TP03-50
Sample No.		1
Depth	from(m)	0.50
Depth	to(m)	1.00



*DP Gans*

Checked and Approved By

02/02/17  
Date

Client Ref

P16185

Contract No

33812

# Priority Geotechnical Limited



Project

**N6 GCTP Phase 3**

Project No

P16185

Carried out by

GH

06/01/2017

Test Type

D - Diametral, A - Axial, I - Irregular Lump

Direction (U = unknown or random)

Par - parallel to planes of weakness

Per - perpendicular to planes of weakness

Dimensions


Dps - Distance between platens (platen separation)

Dps' - at failure

Lne - Length from platens to nearest free end

W - Width of shortest dimension perpendicular to load, P

Machine Ram Area, cm<sup>2</sup>



## Point Load Test Results

Borehole	Sample Top, m BGL	Sample Ref	Sample Type	Sample Base, m BGL	Specimen Ref	Specimen Depth, m BGL	Description	Test Type see ISRM Fig 5 and 8		Failure Valid (Y/N)	Dimensions			Gauge reading, kN	P Failure Load, kN	De equivalent diameter, mm	Is MPa	Is(50) point load index, MPa	Remarks
								Type (D, A, I)	Direction (Par/Per/U)		L mm	Dps, mm	W mm						
RC03-60	1.6						Limestone	D	Par	Y	80	86	86	10.21	10.21	86.0	1.38	1.76	Undulating Rough
RC03-60	2.7						Limestone	D	Par	Y	76	86	86	9.44	9.44	86.0	1.28	1.63	Undulating Rough
RC03-60	6.9						Limestone	D	Par	Y	101	86	86	19.95	19.95	86.0	2.70	3.44	Undulating Rough
RC03-60	7.8						Limestone	D	Par	Y	160	86	86	29.13	29.13	86.0	3.94	5.03	Undulating Smooth
RC03-60	12						Limestone	D	Par	Y	110	86	86	22.24	22.24	86.0	3.01	3.84	Undulating Rough
RC03-60	15.3						Limestone	D	Par	Y	82	86	86	16.12	16.12	86.0	2.18	2.78	Undulating Rough
RC03-61	5.0						Limestone	I	Par	Y	95	60	78	16.6	16.60	77.2	2.79	3.39	Undulating Rough
RC03-61	9.1						Limestone	D	Par	Y	68	86	86	27.93	27.93	86.0	3.78	4.82	Undulating Rough
RC03-61	11.3						Limestone	D	Par	Y	89	86	86	28.33	28.33	86.0	3.83	4.89	Undulating Rough
RC03-61	13.9						Limestone	D	Par	Y	126	86	86	23.96	23.96	86.0	3.24	4.14	Undulating Rough

# Unconfined Compressive Strength, UCS

Job Name	N6 GCTP Phase 3
Job Number	P16185
Borehole:	RC03-60
Depth:	3.5 m
Rock Type	Limestone
Bulk Density	2.69 Mg/m <sup>3</sup>
Load at Failure, P	147.9 kN
Stress at Failure	25.41 MPa



NOTES:

Operator	GH
Checked	CK

# Unconfined Compressive Strength, UCS

Job Name	N6 GCTP Phase 3
Job Number	P16185
Borehole:	RC03-60
Depth:	4.3 m
Rock Type	Limestone
Bulk Density	2.69 Mg/m <sup>3</sup>
Load at Failure, P	455.6 kN
Stress at Failure	78.41 MPa



NOTES:

Operator	GH
Checked	CK



# Unconfined Compressive Strength, UCS

Job Name	N6 GCTP Phase 3
Job Number	P16185
Borehole:	RC03-61
Depth:	3.3 m
Rock Type	Limestone
Bulk Density	2.69 Mg/m <sup>3</sup>
Load at Failure, P	292.8 kN
Stress at Failure	50.41 MPa



NOTES:

Operator	GH
Checked	CK

# Unconfined Compressive Strength, UCS

Job Name	N6 GCTP Phase 3
Job Number	P16185
Borehole:	RC03-61
Depth:	6.3 m
Rock Type	Limestone
Bulk Density	2.69 Mg/m <sup>3</sup>
Load at Failure, P	455 kN
Stress at Failure	78.36 MPa



NOTES:

Operator	GH
Checked	CK



# Unconfined Compressive Strength, UCS

Job Name	N6 GCTP Phase 3
Job Number	P16185
Borehole:	RC03-60
Depth:	9.6 m
Rock Type	Limestone
Bulk Density	2.68 Mg/m <sup>3</sup>
Load at Failure, P	208.1 kN
Stress at Failure	35.1 MPa



NOTES:

Operator	GH
Checked	CK

# Unconfined Compressive Strength, UCS


Job Name	N6 GCTP Phase 3
Job Number	P16185
Borehole:	RC03-61
Depth:	13.25 m
Rock Type	Limestone
Bulk Density	2.70 Mg/m <sup>3</sup>
Load at Failure, P	560.4 kN
Stress at Failure	96.51 MPa



NOTES:

Operator	GH
Checked	CK





Priority Geotechnical Site

JOB NAME:	
Galway N6 GCTP Phase 3	
Sheet Title:	
EXPLORATORY LOCATION LAYOUT	
JOB NUMBER:	
P16185	
DRAWING NUMBER:	
P16185-SI-A	
DRAWN BY:	
Gary Curtin	
DATE:	
02/02/2017	
SCALE:	APPROVED:
1:20,000 ON A3	GH
REVISION:	
D01	





KEY:

- SW00** Denotes Slit Trench and Datum location
- TP00** Denotes Trial Pit location
- BH00** Denotes Borehole location
- RC00** Denotes Rotary Core location

JOB NAME:

Galway N6 GCTP Phase 3

Sheet Title:

EXPLORATION LOCATION PLAN

JOB NUMBER:

P16185

DRAWING NUMBER:

P16185-SI-01

DRAWN BY:

Gary Curtin

DATE:

02/02/2017

SCALE:


1:1,000 ON A3

APPROVED:

GH

REVISION:

D01



KEY:

- ☒ SW00 Denotes Slit Trench and Datum location
- TP00 Denotes Trial Pit location
- BH00 Denotes Borehole location
- ⊕ RC00 Denotes Rotary Core location

JOB NAME:

Galway N6 GCTP Phase 3

Sheet Title:

EXPLORATION LOCATION PLAN

JOB NUMBER:

P16185

DRAWING NUMBER:

P16185-SI-02

DRAWN BY:

Gary Curtin

DATE:

02/02/2017

SCALE:

1:1,000 ON A3

APPROVED:

GH

REVISION:

D01



KEY:

- SW00 Denotes Slit Trench and Datum location
- TP00 Denotes Trial Pit location
- BH00 Denotes Borehole location
- RC00 Denotes Rotary Core location

JOB NAME:

Galway N6 GCTP Phase 3

Sheet Title:

EXPLORATION LOCATION PLAN

JOB NUMBER:

P16185

DRAWING NUMBER:

P16185-SI-03

DRAWN BY:

Gary Curtin

DATE:

02/02/2017

SCALE:


1:1,000 ON A3

APPROVED:

GH

REVISION:

D01



KEY:

- SW00 Denotes Slit Trench and Datum location
- TP00 Denotes Trial Pit location
- BH00 Denotes Borehole location
- RC00 Denotes Rotary Core location

JOB NAME:

Galway N6 GCTP Phase 3

Sheet Title:

EXPLORATION LOCATION PLAN

JOB NUMBER:

P16185

DRAWING NUMBER:

P16185-SI-04

DRAWN BY:

Gary Curtin

DATE:

02/02/2017

SCALE:

1:1,000 ON A3


APPROVED:

GH

REVISION:

D01





KEY:

- SW00 Denotes Slit Trench and Datum location
- TP00 Denotes Trial Pit location
- BH00 Denotes Borehole location
- RC00 Denotes Rotary Core location
- PW00 Denotes Pump Well location

JOB NAME:

Galway N6 GCTP Phase 3

Sheet Title:

EXPLORATION LOCATION PLAN

JOB NUMBER:

P16185

DRAWING NUMBER:

P16185-SI-05

DRAWN BY:

Gary Curtin

DATE:

02/02/2017

SCALE:


1:1,000 ON A3

APPROVED:

GH

REVISION:

D01



KEY:

- SW00 Denotes Slit Trench and Datum location
- TP00 Denotes Trial Pit location
- BH00 Denotes Borehole location
- RC00 Denotes Rotary Core location

JOB NAME:

Galway N6 GCTP Phase 3

Sheet Title:

EXPLORATION LOCATION PLAN

JOB NUMBER:

P16185

DRAWING NUMBER:

P16185-SI-06

DRAWN BY:

Gary Curtin

DATE:

02/02/2017

SCALE:

1:1,000 ON A3

APPROVED:

GH

REVISION:

D01