



- | | | | | | |
|---|---|--|--|--|---|
| <p>1. Existing historic granite footpath: Retained. Coal cellar covers also retained</p> | <p>5. Paved Raised Table Crossing: European granite to match existing historic granite in tone, colour, and petrographic qualities; Laid in small sets for greater flexural strength</p> | <p>9. Kerbing: European granite to match existing historic granite in tone, colour, and petrographic qualities; 400mm wide</p> | <p>13. Removable Bollard: Granite; to control day-to-day entry; removed for parades and events as required</p> | <p>17. Double-sided City Bench: Timber with steel structure; Back and armrests for certain segments; accent uplighters from below set into pavement;</p> | <p>21. Water Pool Fountain: Jets, misters, and lighting to create visual and sonic interest at the west entrance to the space</p> |
| <p>2. Proposed Paving Slabs: European granite to match existing historic granite in tone, colour, and petrographic qualities. Laid in varying sizes as per historic footpaths</p> | <p>6. Paved Carriageway: European granite to match existing historic granite in tone, colour, and petrographic qualities; Laid in small sets for greater flexural strength; Lane markings in stone</p> | <p>10. Dropped Kerb: European granite to match existing historic granite in tone, colour, and petrographic qualities; 400mm wide</p> | <p>14. In-ground Services: Water and Power (separately); with paving in-set to conceal cover; potential for artwork or quotes incorporated</p> | <p>18. Movable Tables and Chairs: Associated with Library for daytime use and cafe; the new public realm creates potential for High Lane Gallery and Chapter One to install similar</p> | <p>22. Public Drinking Fountain: Drinking water provision as a civic good; to reduce single-use plastic bottle waste</p> |
| <p>3. Proposed Paving Setts: European granite to match existing historic granite in tone, colour, and petrographic qualities. Laid in smaller sets for greater flexural strength (events etc.)</p> | <p>7. Existing Concrete Footpaths: Outside red-line boundary; Retained</p> | <p>11. Dished Drainage Channel: European granite to match existing historic granite in tone, colour, and petrographic qualities; 300mm wide; 25mm additional edge for probing canes</p> | <p>15. Drop-off zone: To capture existing bus stopping, and dropoffs to Library, Hugh Lane, and other existing facilities</p> | <p>19. Library Wifi point: open access library wifi out in the public realm; driver concealed within bench or streetlight</p> | <p>23. Existing Streetlight Fixtures: Repainted black; Bulbs upgraded to warm-temperature LED with greater luminosity; Ino. beside Garden of Remembrance north entrance reinstated</p> |
| <p>4. Entrance Paving to Library: European granite to match existing historic granite in tone, colour, and petrographic qualities. Laid in larger slabs and continues into internal spaces.</p> | <p>8. Tarmacadam Roadway: Retained along Parnell Square West and Parnell Square East</p> | <p>12. Tactile Paving: Various shapes and materials as per role; Controlled crossings, Uncontrolled crossings, Linear Guidance; Corduroy; see Landscape Report</p> | <p>16. Mobility-impaired Parking: the 5no. existing spaces relocated to west side of Parnell Sq West, and to west side of Frederick St, to allow increase to the PSCQ pedestrian area</p> | <p>20. Street Tree: London Plane (or similar); Bespoke tree grille with uplighters inset; SUDS drainage chamber for rainwater runoff</p> | <p>24. Traffic Lights: Retained in situ or relocated to fit the new traffic pattern</p> |
| | | | | | <p>25. Public Bike Stands: Black painted metal; sensitive to heritage context</p> |
| | | | | | <p>26. Dublin Bike Station: Relocation of the existing 20no. stands to accommodate Library entrance</p> |
| | | | | | <p>27. E-car charge point: Reinstated to adjacent parking spaces 15m southeast, in order to facilitate Dublin Bikes Station</p> |
| | | | | | <p>28. Miami Showband Memorial: Potential in-ground position for relocated memorial; due to basement reinstatement of 20 & 21</p> |

Bernard Seymour Landscape Architects
 4 Mary's Abbey, Dublin 7 | +353 1 8747764 | info@bslarch.com

Project: Parnell Square Cultural Quarter: New Dublin City Library and Public Realm Works
Client: Dublin City Council & PSCQ Development Ltd (Joint Applicants)

Drawing: Public Realm Render Plan | **Dwg No:** DNI407-P-GF-Prop-R
Date: 10/2018 | **Scale:** 1:250 @ A1 | **Stage:** Planning
Drawn by: DN | **Drawn by:** BS | **Issue:** Rev 0

The drawings are copyright of the landscape architect. Where permission is given to disseminate these drawings they are to be used for the project and the matter must be referred to the landscape architect. If the drawings include copyright details, the matter must be referred to the copyright holder. All generations must be checked for the landscape architect's name and the date. The landscape architect must be named by the Contractor of any subsequent construction work.