

AMIL Properties Ltd.
Creagh SHD, Ballowen/Ramsfortpark, Gorey, Co. Wexford

Cut/Fill Report

12-Feb-19



Buildings		
Cut	m3	18579
Fill		30292
Fill Provided by Subbase etc.		7425
Balance		4288 of fill required

Foul Drainage		
Initial Excavation /		
Trench Volume	m3	7784
Pipe and Bed Volume		2378
Backfill		5406 from excavated material
Balance		2378 excess created

Storm Drainage		
Initial Excavation /		
Trench Volume	m3	18076
Pipe and Bed Volume		2180
Attenuation System		4200
Backfill		11696 from excavated material
Balance		6380 excess created

Total Fill Remaining	m3	4288
Total Excess Created		8758 goes to fill required
Balance	m3	4470 excess for disposal