



Schedule Of Building Fabric Repair Works

Please note, all works to historic buildings will be carried out in accordance with the Conservation Architects recommendations.

Please see the Conservation Architect's Specifications for further information.

Summary of works

Windows:

Early timber windows to remain in situ following repair by specialist joiners.

All modern uPVC/Alumini windows within the existing facade to be replaced with multi-pane vertical sliding sash in box frames unless otherwise stated.

All blocked openings and missing windows within the existing facade to be replaced with multi-pane vertical sliding sash in box frames unless otherwise stated.

Roof

Salvage all existing stone slate on the historic structures for reuse on the building. Remove all concrete roof tiles and other contemporary roof finishes, repair, replace and treat roofing elements as necessary, and finish with salvaged and replacement stone slates.

Historic roof timbers to be repaired on a minimum intervention basis.

Leadwork

All existing lead flashings, parapet gutters and dpc to roof fabric to be removed and replaced with appropriate materials as recommended by the Conservation Architect.

Chimney Repair

Generally all existing brick chimneys are to be repaired and repointed.

Chimneys that are plaster rendered are to have render removed, flashings replaced and re-rendered.

In cases where the masonry is loose and damaged and there is risk of moisture penetration the conservation architect may instruct the top few courses of brick to be removed and rebbed on a bitumen coated lead dpc.

Existing Timber Floor

Generally all existing suspended timber floors are to be retained, repaired and upgraded to meet loading requirements.

Internal Plaster Repair

Repair all existing lime plaster in accordance with Conservation Architects recommendations.

Rainwater Goods

Replace all circular down pipes & decorative hopper heads with heritage cast iron rainwater goods.

Brick Restoration System

Clean and treat brickwork in accordance with Conservation Architects recommendations. Allow for reporting of brickwork and repairs to brickwork and stone as necessary.

Painting Specification

All internal plaster surfaces and joinery to be finished in matt emulsion and oil paints, and external plaster rendered surfaces to be finished in mineral paint as recommended by the Conservation Architect.

Existing Door Upgrading

An intumescent system is to be used to upgrade raised and fielded panel doors to fire rated doors. Envirotgraf papers to be used in conjunction with intumescent paints to achieve 30 min fire rating.

Building Usage

- Apartment
- Commercial
- Cafe / Restaurant / Bar
- Cultural
- Retail
- Residential
- Residential Garden

Proposed Key:

- 1 Consolidate rear wall following demolition of former rear extension including removal of render finish as required
- 2 Construct new door within former opening location allowing for enlarging opening to suit new stoop
- 3 Proposed door opening set partially within existing opening to maintain existing brick jambs/ conc. cills where possible as indicated on elevations
- 4 New partition walls to form apartment layout as shown
- 5 New balconies serving apartments and providing private outdoor space
- 6 Construct new podium over street level to provide private outdoor space to apartment
- 7 Stair to be refurbished in accordance with Conservation Officers report/approval. Area upgraded to a protected stairway to provide 60 minutes fire resistance including No1 Patrick Street & 4&5 Ellen Street
- 8 Open atrium landing area
- 9 Grazed atrium linking new-build host with former Georgian buildings incorporated into Apartment
- 10 Area of new floor in-fill

Note: Automatic Water Fire Suppression System to be installed throughout all properties where identified within MAE Engineers proposals.

Key

- New Construction
- Existing Construction



Project Management Initials: Designer: SL
Checked: AW
Approved: SP
ISO A3 841mm x 1189mm

For Site Levels refer to Landscape Architects Drawings
All levels referenced to Malin Head Datum
KEY PLAN



ISSUE/REVISION HISTORY

IR	DATE	DESCRIPTION
1	Jan 19	Planning Submission

PROJECT NUMBER
60568520

SHEET TITLE
Parcel 2A - Proposed First Floor Plan

1 : 100 @ A0
SHEET NUMBER
OPRA-ACM-ZZA-01-DR-AR-11003

Last Printed: 06/02/2019 12:14:11
Filename: G:\ACAD\2019\60568520_Project\Opera\A0\Diag\01_VP\01_BIM\01_Central\03_Zone 2A\OPRA_ACM_ZZA_ZZ_AR_0001.dwg

This drawing has been prepared for the use of AECOM's staff & may not be used, modified, reproduced or relied upon by AECOM or any other party without the prior written consent of AECOM. All measurements must be obtained from the stated dimensions.