

**Summary of works**

**Windows:**  
Early timber windows to remain in situ following repair by specialist joiners.

All modern uPVC/Alumin windows within the existing facade to be replaced with multi-pane vertical sliding sash in box frames unless otherwise stated.

All blocked openings and missing windows within the existing facade to be replaced with multi-pane vertical sliding sash in box frames unless otherwise stated.

**Roof**  
Salvage all existing stone slate on the historic structures for reuse on the building. Remove all concrete roof tiles and other contemporary roof finishes, repair, replace and treat roofing elements as necessary, and finish with salvaged and replacement stone slates.

Historic roof timbers to be repaired on a minimum intervention basis.

**Leadwork**  
All existing lead flashings, parapet gutters and dpc to roof fabric to be removed and replaced with appropriate materials as recommended by the Conservation Architect.

**Chimney Repair**  
Generally all existing brick chimneys are to be repaired and reported. Chimneys that are plaster rendered are to have render removed, flashings replaced and re-rendered.

In cases where the masonry is loose and damaged and there is risk of moisture penetration the conservation architect may instruct the top few courses of bricks to be removed and rebedded on a bitumen coated lead dpc.

**Existing Timber Floor**  
Generally all existing suspended timber floors are to be retained, repaired and upgraded to meet loading requirements.

**Internal Plaster Repair**  
Repair all existing lime plaster in accordance with Conservation Architects recommendations.

**Rainwater Goods**  
Replace all circular down pipes & decorative hopper heads with heritage cast iron rainwater goods.

**Brick Restoration System**  
Clean and treat brickwork in accordance with Conservation Architects recommendations. Allow for repointing of brickwork and repairs to brickwork and stone as necessary.

**Painting Specification**  
All internal plaster surfaces and joinery to be finished in matt emulsion and oil paints, and external plaster rendered surfaces to be finished in mineral paint as recommended by the Conservation Architect.

**Existing Door Upgrading**  
An intumescent system is to be used to upgrade raised and fielded panel doors to fire rated doors. Engrainal papers to be used in conjunction with intumescent paints to achieve 30 min fire rating.

Size  
Existing Construction  
New Construction

Building Use  
Apartment  
Commercial  
Cafe / Restaurant / Bar  
Cultural  
Retail  
Residential

Note: All levels referenced to Malin Head Datum  
For site levels refer to Landscape Architects drawings

KEY PLAN



ISSUE/REVISION HISTORY

IR	DATE	DESCRIPTION
1	Jan 2019	Planning Submission

PROJECT NUMBER

60568520

SHEET TITLE

Parcel 3A+4 - Proposed Ground Floor Plan


1 : 100 @ A0

SHEET NUMBER

OPRA-ACM-Z3A4-OG-DR-AR-11002

REV

1



Project Management Initials - Designer :  
 Checked : AW  
 Approved : SP  
 ISO A3 841mm x 1189mm

Last Printed : 1/22/2019 3:18:41 PM  
 Filename : C:\Users\jwilliam.campbell\Documents\OPRA-ACM-Z3A4-OG-DR-AR-001 - main\main\comp\0022.rvt  
 This drawing has been prepared for the use of AECOM's staff & their partners, users of AECOM or as required by AECOM or as required by law. AECOM accepts no responsibility, and denies any liability, whatsoever, to any party, for uses or relies on this drawing, which AECOM expressly reserves the right to modify, without notice, at any time. All measurements must be obtained from the stated dimensions.