



Appendix 14.3

Junction Analyses Report

Proposed RB Central Apartments Development, Sandyford, Dublin 18

On behalf of

IRES Residential Properties Limited

Prepared by

CST GROUP Chartered Consulting Engineers
1, O'Connell St, Sligo, F91 W7YV

March 2019

Table of Contents:

Revision History..... 3

1. Introduction..... 4

2. Traffic Surveys 5

3. Committed Development..... 6

4. Road Improvement Schemes 8

5. Committed Development Trip Generation 10

6. Background Traffic Growth 11


7. Trip Generation 12

8. Impact of the Proposed Development Traffic on the Junctions 14

9. Junction Capacity Assessments 15

Appendices:

- APPENDIX I SURVEY DATA
- APPENDIX II TRAFFIC FLOW FIGURES
- APPENDIX III JUNCTION ANALYSIS OUTPUTS

Report By: 
Philip Bayfield BEng MSc CEng MIEI
Chartered Engineer

Date 28 March 2019

Approved By: 
Francis Fidgeon BE CEng MIEI
Chartered Engineer

Date 28 March 2019

Revision History

Revision History:	R0	R1	R2						
Purpose of Issue: P=Preliminary PG=Progress C=Comment I=Information FC=Fire Cert Q=Quotation PL=Planning T=Tender CN=construction CT=Contract	C	PL	PL						
Date:	17 10 18	07 12 18	28 03 19						
Originator:	PB	PB	PB						
Checked By:	FF	FF	FF						
Approved By:	FF	FF	FF						

1. Introduction

CST Group Chartered Consulting Engineers has carried out an assessment of five junctions in the vicinity of the development site. These include the following junctions:

- Junction 1 Blackthorn Dr/Carmanhall Rd/Birch Ave four-arm signalised junction
- Junction 2 Carmanhall Rd/Site Access – three-arm priority junction
- Junction 3 Carmanhall Rd/Corrig Rd – three-arm priority junction
- Junction 4 Carmanhall Rd/Blackthorn Rd – three-arm priority junction
- Junction 5 Blackthorn Dr/Site Access – three-arm road priority junction




Figure 1: Junction Locations © OpenStreetMap contributors

Junction Locations – for assessment

It is anticipated that the year of opening of the development would be 2021. It has been agreed with DLRC that the junction assessments will be carried out for the year of opening as well as the 10-year horizon.

2. Traffic Surveys

Traffic Surveys were carried out at junctions 1, 3, 4 and 5 on Thursday 08/12/16 between 07.00 – 10.00 hours and 16.00-19.00 hours. The Travel Habit Surveys were also carried out on the same day.

Additionally, traffic counts were taken within the existing development car park on the car park ramps since the car parking is allocated on the basis of upper basement (-1 level) – retail units (including Aldi and EZ Living), and lower basement (-2 level) – residential units (419 total). This provided a clear breakdown of the trip generation for the existing residential units and retail units. These trip profiles were subsequently used for the trip generation for the proposed 428 no. residential units now proposed under the scheme.

The peak traffic hours were 08.15 to 09.15 hours, and 17.00 to 18.00 hours for the respective AM and PM peaks.

The Traffic survey information is summarised in Appendix A.

Existing Traffic Flows for the 2016 peak hours are shown on Appendix B - Figure 1.

3. Committed Development

There are a number of sites which have been received planning approval by DLRC, which are assumed to be committed development, which will have an impact on the roads in the vicinity of the RB Central site. They are:

1. Avid site – (D16A/0158) – 147 apartments plus minor retail/office space;
2. Wexele site (D15A/0827) – 21,099m² offices;
3. Febvre site (D15A/0827) – 27,751m² offices;
4. Ulster Bank Site (D15A/0560) – 41,871m² offices;
5. Microsoft Site (South County Business Park) (D14A/0351) 34,554 m² offices;
6. South County Gateway site (South County Business Park) (D15A/0695) 26,525 m² offices;
7. Tivway site (ABP-301428-18) 459 apartments plus crèche.
8. Sentinel Office Block 13,287m² offices (within the overall Rockbrook site but currently frame only works carried out).

The development locations are shown in the figure below




Figure 2: Development Locations © OpenStreetMap contributors

Assumptions:

- That the committed developments are completed and occupied by the 2021 opening year. This is a very conservative approach considering the quantum of development.
- That the peak hour flows for the committed sites coincide with the peak hour flows surveyed for the junctions assessed.
- That the traffic flows derived for each of the sites is as was assessed with each of the Transport Assessments which accompanied the relevant planning applications.

4. Road Improvement Schemes

The SUFP identified a number of road improvement schemes which would be needed to ensure adequate capacity for further development within the Sandyford District under a six-year time frame. These include (numbers as per the SUFP numbering system):

- (1) M50 Diverge Ramp to ESB Link Road (preferred) or Heather Road;
- (2a) Leopardstown Link Road;
- (3) Bracken Road Extension;
- (6) ESB Link Road & Link to Arena Road;
- (7) Leopardstown Roundabout Reconfiguration;
- (9) Bus Priority Schemes.

The locations of the schemes are set out in the figure below:




Figure 3: 6 Year Road Infrastructure Objectives Excerpt from SUFP Drawing 8

Of these schemes, 2a and 7 have recently been completed and are opened to the public whilst scheme 6 has planning approval and will be expected to be complete by 2021. These proposed and completed road schemes will further enhance capacity within the Sandyford district.

The committed development proposals for Sites 1, 2, and 3 traffic assessments take account of Scheme 6 – ESB Link Road being constructed and open at year of opening. The layout of the scheme is set out in the figure below.



Figure 4: Scheme 6 Layout

5. Committed Development Trip Generation

Resultant traffic flows were derived for the 2021 opening year with the road network as currently in place as well as for 2031 – 10 years after opening. For the latter scenario it is assumed that the ESB link road, which has planning permission, will be completed and open. The traffic movements for each of the various committed developments for sites 1, 2 and 3 will be impacted by the construction of the ESB Link Road.

The figures for the traffic movements for each of the committed development sites are shown in Appendix B as follows:

1. Avid site – (D16A/0158) – Figure 4
2. Wexele site (D15A/0827) – Figure 5;
3. Febvre site (D15A/0827) – Figure 6;
4. Ulster Bank Site (D15A/0560) – Figure 7;
5. Microsoft Site (South County Business Park) (D14A/0351) Figure 8;
6. South County Gateway site (South County Business Park) Figure 9;
7. Tivway site (ABP-301428-18) Figure 10
8. Rockbrook (Sentinel) Office Block - Figures 12 & 13

The resultant combined traffic flows for the committed development are shown in Figures 14 for the peak hours.

6. Background Traffic Growth

It is considered reasonable to use central growth figures for the background traffic in deriving the 2021 and 2031 traffic flows. The TII document Unit 5.3 PAG –for National Roads Unit 5.3 – Travel Demand Projections October 2016 Figure 5.3.2 – Central Growth gives a figure of 1.0134 for the 2016 – 2030 period and 1.0038 for the 2030-2031 period.

TII Publications
Project Appraisal Guidelines for National Roads Unit 5.3 - Travel Demand Projections

PE-PAG-02017
October 2016

Table 5.3.2: Link-Based Growth Rates: Annual Growth Factors

Region	Low Sensitivity Growth				Central Growth				High Sensitivity Growth			
	2013 - 2030		2030 - 2050		2013 - 2030		2030 - 2050		2013 - 2030		2030 - 2050	
	LV	HV	LV	HV	LV	HV	LV	HV	LV	HV	LV	HV
1 Dublin	1.0089	1.0221	1.0004	1.0135	1.0134	1.0237	1.0038	1.0176	1.0149	1.0242	1.0054	1.0195
2 Mid-East Kildare Meath Wicklow	1.0109	1.0221	1.0018	1.0135	1.0140	1.0237	1.0048	1.0176	1.0154	1.0242	1.0054	1.0195
3 Midland Laois Longford	1.0088	1.0221	0.9997	1.0135	1.0120	1.0237	1.0030	1.0176	1.0131	1.0242	1.0018	1.0195

Extract from Unit 5.3 Link-Based Traffic Growth Forecasting Figure 5.3.2

Using this growth rate the following factors will be used:

2021 - 1.069 (6.9%)

2031 - 1.209 (20.9%)

The resultant background traffic flows for the 2021 and 2031 are set out in Appendix B Figures 2 and 3.

7. Trip Generation

The trip generation at the existing site was measured to determine the split between the retail and residential elements of the existing scheme. It was important to establish this as the proposals for the scheme are that the existing residential traffic and also the new residential element will be routed via the Carmanhall access. The recorded trips for the existing 419 units is set out below, together with relevant new trip generation for the new 428 apartment development.

		In	Out
AM	Existing trips	21	58
	trip rate / apartment	0.050	0.138
	New Trips	21	59
PM	Existing trips	38	17
	trip rate / apartment	0.091	0.041
	New Trips	39	17

Table 1: Trip Generation

It is worth noting that these trip rates are considerably lower than those used for the original planning application for the site (by up to 75%). These significant reductions are reflective of the high uptake of alternative means of transport – refer to Baseline Travel Plan survey results.

The turning proportions for the development traffic from Rockbrook as proposed under the original Transportation Assessment D07A/0975 for the scheme have been used:

- 10% of arrivals from Stillorgan/Goatstown – via St Raphael’s Road;
- 10% of arrivals from Brewery Road via Burton Hall Road;
- 20% of arrivals from Leopardstown Road via Burton Hall Road;
- 40% of arrivals from M50 via Blackthorn Drive;
- 10% of arrivals via Drumartin Link Road via Benildus Avenue. (Note under the 2005 application this traffic was routed via Drumartin Link and Blackthorn Drive – but Benildus Avenue was constructed in the interim);
- 10% from Sandyford Road via Blackthorn Drive.

These proportions compared well with the turning proportions to and from the existing site access on Blackthorn Drive and so it is considered appropriate to use the same for this study. The resultant turning proportions and volumes are set out in Appendix B Figures 15 and 16 respectively.

As the existing residential (419 apartments) will enter and leave the basement car park via the new Carmanhall Road access it is necessary to reroute associated traffic from the existing access on Blackthorn Road. The resultant turning volumes are set out in Appendix B Figure 17.

The combined traffic turning numbers for the rerouted existing residential traffic and new residential traffic are set out in Appendix B Figure 18.

Assessments for the following scenarios were carried out:

- 2016 Existing Flows
- 2021 (Year of Opening) – Do Nothing – Grown 2016 traffic flows + development flows from existing permitted/committed developments which will impact the traffic in the vicinity of the development, but excluding the proposed Rockbrook Apartment Development (resultant traffic flows are set out in Appendix B Figure 19);
- 2021– Do Nothing as above but including proposed RB Central Apartment Development (resultant traffic flows are set out in Appendix B Figure 20);
- 2031 – Do Nothing (resultant traffic flows are set out in Appendix B Figure 21);
- 2031 – Do Something (resultant traffic flows are set out in Appendix B Figure 22).

The traffic generated for this development includes for the rerouting of the existing occupied apartments via the Carmanhall Road/Site junction.

8. Impact of the Proposed Development Traffic on the Junctions

The percentage uplift of traffic on existing junctions was established by calculating the total additional traffic at the junction due to the development as a percentage of the total traffic on the junction in 2021. This was used to assess the relative impact of the works on the traffic flows and is set out in Table 2 below.

Year/ Peak	Junction 1 Blackthorn Dr/Carmanhall Rd/Birch Ave	Junction 2 Carmanhall Rd/Site Access (new)	Junction 3 Carmanhall Rd/Corrig Rd	Junction 4 Carmanhall Rd/Blackthorn Rd	Junction 5 Blackthorn Dr/Site Access
2021 AM	4.3%	16.4%	5.9%	3.3%	0.0%
2031 AM	3.8%	15.1%	5.3%	3.0%	0.0%
2021 PM	2.5%	10.8%	3.7%	1.9%	2.3%
2031 PM	2.3%	10.0%	3.3%	1.7%	2.1%

Table 2: Additional Traffic at junctions due to the development

Under the requirements of National Roads Authority's (now TII) Traffic and Transport Assessment Guidelines 2014 if the impact of a new development amounts more than 10% additional traffic on the local network the impact is considered material even if the local network is not experiencing prolonged congestion. Where the network is experiencing prolonged congestion during peak period this threshold is reduced to 5%.

The table above shows the additional traffic added to the junctions due to the development, even assuming all junctions are congested, would not be considered to have a material impact for Junctions 1, 4 and 5.

However, for completeness, quantitative assessments of all junctions have been carried out.

9. Junction Capacity Assessments

The operational assessment of the local road network has been undertaken using LinSig software for the signalised junction (Junction 1) and TRL PICADY software for the priority junctions – Junctions 2 - 5.

All junction analysis output is set out in Appendix C. Discussion of the results is set out in the EIAR Chapter 14.

9.1 Junction 1 Blackthorn Dr/Carmanhall Rd/Birch Ave

When considering signalised junctions a positive Percentage Residual Capacity (PRC) would indicate that a junction has sufficient spare capacity.

This four arm signalised junction was assessed using LinSig software. The results are set out in Table 3 below:

	PRC (%)	Ave Queue (pcu's)
2016 AM Existing	71.4	8.2
2021 AM Do Nothing	5.2	15.9
2021 AM Do Something	0.8	18.6
2031 AM Do Nothing	-11.3	33.7
2031 AM Do Something	-16.2	52.4
2016 PM Existing	75.1	12.3
2021 PM Do Nothing	25.6	16.8
2021 PM Do Something	20.5	21.0
2031 PM Do Nothing	1.3	31.8
2031 PM Do Something	2.9	34.2

Table 3: Junction 1 PRC and Queue

9.2 Junction 2 Carmanhall Rd/Site Access

This priority junction was analysed using PICADY software. When considering priority controlled junctions a Ratio of Flow to Capacity (RFC) of greater than 85% (0.850) would indicate that is junction is nearing capacity.

The results of the operational assessment of this priority junction during the weekday morning and evening peaks is summarised in Table 4 below.

The arms are labelled as below:

Arm A: Carmanhall Rd West

Arm B: Development

Arm C: Carmanhall Rd East

	Arm	RFC (Max)	Max. Queue (pcu's)
2016 AM Existing	B-AC	-	-
	C-AB	-	-
2021 AM Do Nothing	B-AC	0.139	0.1
	C-AB	0.221	0.2
2021 AM Do Something	B-AC	0.540	1.1
	C-AB	0.260	0.4
2031 AM Do Nothing	B-AC	0.146	0.2
	C-AB	0.228	0.3
2031 AM Do Something	B-AC	0.571	1.3
	C-AB	0.268	0.4
2016 PM Existing	B-AC	-	-
	C-AB	-	-
2021 PM Do Nothing	B-AC	0.683	2.0
	C-AB	0.026	0.0
2021 PM Do Something	B-AC	0.803	3.7
	C-AB	0.077	0.1
2031 PM Do Nothing	B-AC	0.708	2.3
	C-AB	0.026	0.0
2031 PM Do Something	B-AC	0.834	1.8
	C-AB	0.062	0.1

Table 4: Junction 2 RFC and Queue

9.3 Junction 3 Carmanhall Rd/Corrig Rd

The results of the operational assessment of this priority junction during the weekday morning and evening peaks is summarised in Table 5 below:

The arms are labelled as below:

Arm A: Carmanhall Rd East

Arm B: Corrig Road

Arm C: Carmanhall Rd West

	Arm	RFC (Max)	Max. Queue (pcu's)
2016 AM Existing	B-AC	0.515	1.0
	C-AB	0.147	1.5
2021 AM Do Nothing	B-AC	0.614	1.5
	C-AB	0.180	0.3
2021 AM Do Something	B-AC	0.630	1.7
	C-AB	0.181	0.3
2031 AM Do Nothing	B-AC	0.723	2.4
	C-AB	0.203	0.3
2031 AM Do Something	B-AC	0.743	2.7
	C-AB	0.205	0.3
2016 PM Existing	B-AC	0.439	0.8
	C-AB	0.066	0.1
2021 PM Do Nothing	B-AC	0.501	1.0
	C-AB	0.078	0.1
2021 PM Do Something	B-AC	0.509	1.0
	C-AB	0.078	0.1
2031 PM Do Nothing	B-AC	0.580	1.3
	C-AB	0.089	0.1
2031 PM Do Something	B-AC	0.590	0.9
	C-AB	0.071	0.1

Table 5: Junction 3 RFC and Queue

9.4 Junction 4 Carmanhall Rd/Blackthorn Rd

The results of the operational assessment of this priority junction during the weekday morning and evening peaks is summarised in Table 6 below.

The arms are labelled as below:

Arm A: Blackthorn Rd South

Arm B: Carmanhall Road

Arm C: Blackthorn Rd North

	Arm	RFC (Max)	Max. Queue (pcu's)
2016 AM Existing	B-AC	0.416	0.7
	C-AB	0.262	0.4
2021 AM Do Nothing	B-AC	0.715	2.3
	C-AB	0.374	0.6
2021 AM Do Something	B-AC	0.833	3.9
	C-AB	0.350	0.6
2031 AM Do Nothing	B-AC	0.855	4.9
	C-AB	0.471	0.9
2031 AM Do Something	B-AC	0.985	12
	C-AB	0.482	0.9
2016 PM Existing	B-AC	0.875	5.7
	C-AB	0.106	0.1
2021 PM Do Nothing	B-AC	1.690	83
	C-AB	0.194	0.2
2021 PM Do Something	B-AC	1.758	176
	C-AB	0.201	0.3
2031 PM Do Nothing	B-AC	2.089	248
	C-AB	0.247	0.3
2031 PM Do Something	B-AC	2.171	227
	C-AB	0.257	0.2

Table 6: Junction 2 RFC and Queue

9.5 Junction 5 Blackthorn Dr/Site Access

The results of the operational assessment of this priority junction during the weekday morning and evening peaks is summarised in Table 8 below.

The arms are labelled as below:

Arm A: Blackthorn Drive East

Arm B: Site Access

Arm C: Blackthorn Drive West

	Arm	RFC (Max)	Max. Queue (pcu's)
2016 AM Existing	B-AC	0.142	0.2
	C-AB	0.088	0.1
2021 AM Do Nothing	B-AC	0.158	0.2
	C-AB	0.096	0.1
2021 AM Do Something	B-AC	0.043	0.0
	C-AB	0.119	0.1
2031 AM Do Nothing	B-AC	0.185	0.2
	C-AB	0.111	0.1
2031 AM Do Something	B-AC	0.064	0.1
	C-AB	0.134	0.2
2016 PM Existing	B-AC	0.222	0.3
	C-AB	0.079	0.1
2021 PM Do Nothing	B-AC	0.250	0.3
	C-AB	0.088	0.1
2021 PM Do Something	B-AC	0.305	0.4
	C-AB	0.088	0.1
2031 PM Do Nothing	B-AC	0.300	0.4
	C-AB	0.102	0.1
2031 PM Do Something	B-AC	0.350	0.5
	C-AB	0.102	0.1

Table 8: Junction 5 RFC and Queue

APPENDIX A

SURVEY DATA

Client: CST Group
 Project: 3142-IRE
 Site: Site 1
 Date: 08/12/2016

Weather AM: Rainy
 Weather PM: Cloudy & Clear

Notes: -



Entry : Arm A - Blackthorn Drive

	Destination : Arm A - Blackthorn Drive								Destination : Arm B - Carmanhall Road								Destination : Arm C - Blackthorn Drive								Destination : Arm D - Birch Avenue								Arm Totals				
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS		LTAX	MC	PC	Total
07:00	0	0	0	0	0	0	0	0	0	6	0	0	0	0	0	0	0	6	10	1	0	0	0	1	0	0	12	5	0	0	0	0	0	1	0	6	24
07:15	0	0	0	0	0	0	0	0	0	11	2	0	0	0	0	1	0	14	12	1	0	0	4	0	0	0	17	4	0	0	0	0	0	0	0	4	35
07:30	0	0	0	0	0	0	0	0	0	14	1	0	0	0	0	0	1	16	31	1	0	0	2	0	0	0	34	9	0	0	0	0	0	0	0	9	59
07:45	0	0	0	0	0	0	0	0	0	23	0	0	0	0	0	0	0	23	37	4	0	0	0	0	0	0	41	11	0	1	0	0	0	0	0	12	76
1 Hr	0	0	0	0	0	0	0	0	0	54	3	0	0	0	0	1	1	59	90	7	0	0	6	1	0	0	104	29	0	1	0	0	0	1	0	31	194
08:00	0	0	0	0	0	0	0	0	0	19	4	0	0	0	2	1	0	26	46	0	0	0	3	2	0	1	52	6	0	0	0	0	0	0	0	6	84
08:15	0	0	0	0	0	0	0	0	0	29	2	0	0	0	0	1	0	32	54	1	0	0	0	0	0	1	56	17	2	0	0	0	0	0	0	19	107
08:30	0	0	0	0	0	0	0	0	0	36	2	0	0	0	0	1	0	39	43	2	0	0	2	2	1	0	50	15	0	0	0	0	0	0	0	15	104
08:45	0	0	0	0	0	0	0	0	0	55	3	0	0	0	2	0	2	62	52	2	0	0	1	1	0	2	58	20	2	0	0	0	0	0	0	22	142
1 Hr	0	0	0	0	0	0	0	0	0	139	11	0	0	0	4	3	2	159	195	5	0	0	6	5	1	4	216	58	4	0	0	0	0	0	0	62	437
09:00	0	0	0	0	0	0	0	0	0	41	2	1	0	0	0	0	1	45	44	2	2	1	1	1	1	0	52	18	0	0	0	0	2	0	20	117	
09:15	0	0	0	0	0	0	0	0	0	36	4	0	0	0	0	0	0	40	54	2	0	0	2	2	0	0	60	20	7	0	0	0	0	0	0	27	127
09:30	0	0	0	0	0	0	0	0	0	19	3	0	0	0	2	0	0	24	38	4	0	0	2	1	0	0	45	12	0	1	0	0	0	0	0	13	82
09:45	0	0	0	0	0	0	0	0	0	21	1	0	0	0	2	0	0	24	23	4	1	0	0	1	0	0	29	11	1	0	0	0	0	0	0	12	65
1 Hr	0	0	0	0	0	0	0	0	0	117	10	1	0	0	4	0	1	133	159	12	3	1	5	5	1	0	186	61	8	1	0	0	0	2	0	72	391
3 Hrs	0	0	0	0	0	0	0	0	0	310	24	1	0	0	8	4	4	351	444	24	3	1	17	11	2	4	506	148	12	2	0	0	0	3	0	165	1022

Entry : Arm A - Blackthorn Drive

	Destination : Arm A - Blackthorn Drive								Destination : Arm B - Carmanhall Road								Destination : Arm C - Blackthorn Drive								Destination : Arm D - Birch Avenue								Arm Totals				
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS		LTAX	MC	PC	Total
16:00	0	0	0	0	0	0	0	0	0	14	1	0	0	0	0	0	0	15	51	4	1	1	2	1	1	0	61	5	4	0	0	0	0	0	0	9	85
16:15	0	0	0	0	0	0	0	0	0	15	1	0	0	0	1	0	0	17	48	5	0	0	0	0	0	0	53	4	1	0	0	0	1	1	0	7	77
16:30	0	0	0	0	0	0	0	0	0	19	2	0	0	0	0	0	0	21	44	5	2	0	1	1	0	0	53	10	0	0	0	0	1	1	0	12	86
16:45	0	0	0	0	0	0	0	0	0	23	0	0	0	0	0	0	2	25	37	2	0	0	1	2	0	0	42	11	3	0	0	0	0	0	0	14	81
1 Hr	0	0	0	0	0	0	0	0	0	71	4	0	0	0	1	0	2	78	180	16	3	1	4	4	1	0	209	30	8	0	0	0	2	2	0	42	329
17:00	0	0	0	0	0	0	0	0	0	17	1	0	0	0	1	0	0	19	37	3	0	0	0	2	0	2	44	11	4	0	0	0	0	0	0	15	78
17:15	0	0	0	0	0	0	0	0	0	24	0	0	0	0	1	0	0	25	24	5	0	0	3	0	0	1	33	6	2	0	0	0	0	0	0	8	66
17:30	0	0	0	0	0	0	0	0	0	12	1	0	0	0	0	1	0	14	39	4	0	0	1	0	0	1	45	5	0	0	0	0	0	0	0	5	64
17:45	0	0	0	0	0	0	0	0	0	20	0	0	0	0	0	0	0	20	47	0	0	0	1	0	0	1	49	3	2	0	0	0	0	0	0	5	74
1 Hr	0	0	0	0	0	0	0	0	0	73	2	0	0	0	2	1	0	78	147	12	0	0	5	2	0	5	171	25	8	0	0	0	0	0	0	33	282
18:00	0	0	0	0	0	0	0	0	0	11	2	0	0	0	0	0	0	13	37	3	0	1	1	0	0	3	45	4	0	0	0	0	0	0	0	4	62
18:15	0	0	0	0	0	0	0	0	0	11	2	0	0	0	0	0	0	13	51	1	0	0	1	1	1	0	55	6	0	0	0	0	0	0	0	6	74
18:30	0	0	0	0	0	0	0	0	0	18	1	0	0	0	0	0	1	20	51	0	0	0	2	1	0	0	54	3	0	0	0	0	0	0	0	3	77
18:45	0	0	0	0	0	0	0	0	0	10	0	0	0	0	0	0	0	10	39	2	0	0	1	2	0	0	44	6	2	0	0	0	0	0	0	8	62
1 Hr	0	0	0	0	0	0	0	0	0	50	5	0	0	0	0	0	1	56	178	6	0	1	5	4	1	3	198	19	2	0	0	0	0	0	0	21	275
3 Hrs	0	0	0	0	0	0	0	0	0	194	11	0	0	0	3	1	3	212	505	34	3	2	14	10	2	8	578	74	18	0	0	0	2	2	0	96	886
Total	0	0	0	0	0	0	0	0	0	504	35	1	0	0	11	5	7	563	949	58	6	3	31	21	4	12	1084	222	30	2	0	0	2	5	0	261	1908

Client: CST Group
 Project: 3142-IRE
 Site: Site 1
 Date: 08/12/2016

Weather AM: Rainy
 Weather PM: Cloudy & Clear

Notes: -



Entry: Arm C - Blackthorn Drive

	Destination : Arm A - Blackthorn Drive								Total	Destination : Arm B - Carmanhall Road								Total	Destination : Arm C - Blackthorn Drive								Total	Destination : Arm D - Birch Avenue								Total	Arm Totals				
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC		CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC		CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC		CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC						
07:00	45	1	1	0	0	0	0	1	48	31	8	0	0	0	0	0	0	0	39	0	0	0	0	0	0	0	0	0	0	0	0	15	2	0	0	0	0	0	0	17	104
07:15	79	8	0	0	0	1	1	0	89	42	1	0	0	0	0	0	0	0	43	0	0	0	0	0	0	0	0	0	0	0	18	3	0	0	0	0	0	0	21	153	
07:30	117	6	0	0	1	2	1	0	127	38	2	3	0	0	2	0	0	45	0	0	0	0	0	0	0	0	0	0	0	19	3	0	0	0	0	0	0	22	194		
07:45	126	11	0	0	0	2	0	2	141	61	3	0	0	0	0	0	1	65	0	0	0	0	0	0	0	0	0	0	18	3	0	0	0	0	0	0	21	227			
1 Hr	367	26	1	0	1	5	2	3	405	172	14	3	0	0	2	0	1	192	0	0	0	0	0	0	0	0	0	0	70	11	0	0	0	0	0	0	81	678			
08:00	129	8	0	0	0	2	0	1	140	53	3	0	0	0	0	0	1	57	0	0	0	0	0	0	0	0	0	0	26	3	0	0	0	0	0	0	29	226			
08:15	110	8	2	0	0	2	0	3	125	78	3	0	0	0	2	1	1	85	0	0	0	0	0	0	0	0	0	0	28	3	0	0	0	0	0	1	32	242			
08:30	109	8	4	1	0	3	1	1	127	76	5	0	0	0	0	2	2	85	0	0	0	0	0	0	0	0	0	0	27	0	0	0	0	0	0	0	27	239			
08:45	87	5	1	0	0	4	0	3	100	73	3	2	0	0	0	0	2	80	0	0	0	0	0	0	0	0	0	0	26	3	0	0	0	0	0	1	30	210			
1 Hr	435	29	7	1	0	11	1	8	492	280	14	2	0	0	2	3	6	307	0	0	0	0	0	0	0	0	0	0	107	9	0	0	0	0	0	2	118	917			
09:00	79	9	2	0	0	1	0	1	92	77	3	0	0	0	1	0	1	82	0	0	0	0	0	0	0	0	0	0	29	1	0	1	0	0	0	0	31	205			
09:15	70	6	1	0	1	1	0	0	79	81	3	1	0	0	1	0	0	86	0	0	0	0	0	0	0	0	0	0	25	6	0	0	0	0	0	0	31	196			
09:30	89	7	2	1	1	3	0	0	103	59	6	0	0	0	1	1	1	68	0	0	0	0	0	0	0	0	0	0	38	8	1	0	0	0	0	0	47	218			
09:45	59	4	0	1	0	4	0	1	69	38	8	1	0	0	1	0	1	49	0	0	0	0	0	0	0	0	0	0	13	2	2	0	0	0	0	0	17	135			
1 Hr	297	26	5	2	2	9	0	2	343	255	20	2	0	0	4	1	3	285	0	0	0	0	0	0	0	0	0	0	105	17	3	1	0	0	0	0	126	754			
3 Hrs	1099	81	13	3	3	25	3	13	1240	707	48	7	0	0	8	4	10	784	0	0	0	0	0	0	0	0	0	0	282	37	3	1	0	0	0	0	2	325	2349		

Entry: Arm C - Blackthorn Drive

	Destination : Arm A - Blackthorn Drive								Total	Destination : Arm B - Carmanhall Road								Total	Destination : Arm C - Blackthorn Drive								Total	Destination : Arm D - Birch Avenue								Total	Arm Totals	
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC		CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC		CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC		CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			
16:00	61	2	1	0	0	0	0	1	65	27	3	0	0	0	3	0	1	34	0	0	0	0	0	0	0	0	0	7	2	1	0	0	0	0	0	10	109	
16:15	82	4	1	0	0	1	0	2	90	25	2	0	0	0	0	1	0	28	0	0	0	0	0	0	0	0	0	12	1	0	0	0	0	0	0	13	131	
16:30	70	5	1	0	0	0	0	1	77	19	3	0	0	0	1	1	0	24	0	0	0	0	0	0	0	0	0	5	2	0	0	0	0	0	0	7	108	
16:45	66	5	0	0	0	1	0	2	74	24	6	1	0	0	0	0	1	32	0	0	0	0	0	0	0	0	0	7	0	0	0	0	0	0	0	7	113	
1 Hr	279	16	3	0	0	2	0	6	306	95	14	1	0	0	4	2	2	118	0	0	0	0	0	0	0	0	0	31	5	1	0	0	0	0	0	37	461	
17:00	82	7	0	1	0	1	1	2	94	30	3	1	0	0	1	1	0	36	0	0	0	0	0	0	0	0	0	8	0	0	0	0	0	0	0	8	138	
17:15	64	7	0	0	0	2	0	1	74	20	3	0	0	0	0	1	1	25	0	0	0	0	0	0	0	0	0	10	0	0	0	0	0	0	0	10	109	
17:30	77	0	1	0	0	1	1	2	82	28	1	0	0	0	1	0	0	30	0	0	0	0	0	0	0	0	0	4	1	0	0	0	0	0	0	5	117	
17:45	67	7	0	0	0	2	0	1	77	22	1	0	0	0	0	0	0	23	0	0	0	0	0	0	0	0	0	6	0	0	0	0	0	0	0	6	106	
1 Hr	290	21	1	1	0	6	2	6	327	100	8	1	0	0	2	2	1	114	0	0	0	0	0	0	0	0	0	28	1	0	0	0	0	0	0	29	470	
18:00	61	3	0	0	0	0	0	2	66	28	4	0	0	0	0	0	1	33	0	0	0	0	0	0	0	0	0	2	2	0	0	0	0	0	0	4	103	
18:15	68	5	0	0	0	2	0	1	76	26	0	0	0	0	0	0	1	27	0	0	0	0	0	0	0	0	0	5	0	0	0	0	0	0	0	5	108	
18:30	56	4	0	0	1	0	1	1	63	32	0	0	0	0	0	0	0	32	0	0	0	0	0	0	0	0	0	7	0	0	0	0	0	0	0	7	102	
18:45	62	3	0	0	0	1	2	1	69	25	0	0	0	0	0	0	0	25	0	0	0	0	0	0	0	0	0	3	0	0	0	0	0	0	0	3	97	
1 Hr	247	15	0	0	1	3	3	5	274	111	4	0	0	0	0	0	2	117	0	0	0	0	0	0	0	0	0	17	2	0	0	0	0	0	0	19	410	
3 Hrs	816	52	4	1	1	11	5	17	907	306	26	2	0	0	6	4	5	349	0	0	0	0	0	0	0	0	0	76	8	1	0	0	0	0	0	85	1341	
Total	1915	133	17	4	4	36	8	30	2147	1013	74	9	0	0	14	8	15	1133	0	0	0	0	0	0	0	0	0	358	45	4	1	0	0	0	0	2	410	3690

Client: CST Group
Project: 3142-IRE
Site: Site 1
Date: 08/12/2016

Weather AM: Rainy
Weather PM: Cloudy & Clear

Notes: -



Entry: Arm D - Birch Avenue

	Destination : Arm A - Blackthorn Drive									Destination : Arm B - Carmanhall Road									Destination : Arm C - Blackthorn Drive									Destination : Arm D - Birch Avenue									Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	
07:00	4	0	0	0	0	0	0	0	4	1	0	0	0	0	0	0	0	1	2	1	0	0	0	0	0	0	0	0	0	0	0	0	0	12			
07:15	3	2	0	0	0	0	0	0	5	0	0	0	0	0	0	0	0	0	2	1	0	0	0	0	0	0	0	0	0	0	0	0	8				
07:30	5	0	0	0	0	0	0	0	5	2	0	0	0	0	0	0	0	0	7	1	0	0	0	0	0	0	0	0	0	0	0	0	15				
07:45	4	1	0	0	0	0	1	0	6	0	1	0	0	0	0	0	0	0	3	1	1	0	0	0	0	0	0	0	0	0	0	0	12				
1 Hr	16	3	0	0	0	1	0	0	20	3	1	0	0	0	0	0	0	0	16	5	2	0	0	0	0	0	0	0	0	0	0	0	47				
08:00	2	1	1	0	0	0	0	0	4	2	0	0	0	0	0	0	0	0	3	2	0	1	0	0	0	0	0	0	0	0	0	0	12				
08:15	3	0	0	0	0	0	0	0	3	4	0	0	0	0	0	0	0	0	5	3	1	0	0	0	0	0	0	0	0	0	0	0	16				
08:30	3	0	0	0	0	0	0	0	3	3	1	0	0	0	0	0	0	0	3	1	0	0	0	0	0	0	0	0	0	0	0	0	11				
08:45	5	1	0	0	0	0	0	0	6	7	0	1	0	0	0	0	0	0	7	2	1	0	0	0	1	0	0	0	0	0	0	0	25				
1 Hr	13	2	1	0	0	0	0	0	16	16	1	1	0	0	0	0	0	0	18	8	2	1	0	0	1	0	0	0	0	0	0	0	64				
09:00	3	3	0	0	0	0	0	0	6	1	1	0	0	0	0	0	0	0	1	4	1	0	0	0	0	0	0	0	0	0	0	0	14				
09:15	7	5	0	0	0	0	0	0	12	7	3	0	0	0	0	0	0	0	6	1	2	1	0	0	0	0	0	0	0	0	0	0	32				
09:30	18	4	0	0	0	0	0	0	22	7	1	0	0	0	0	2	0	0	11	4	0	0	0	0	0	0	0	0	0	0	0	0	47				
09:45	10	1	0	0	0	0	0	0	11	6	1	0	0	0	0	0	0	0	12	5	0	0	0	1	0	0	0	0	0	0	0	0	36				
1 Hr	38	13	0	0	0	0	0	0	51	21	6	0	0	0	2	0	0	0	30	14	3	1	0	1	0	0	0	0	0	0	0	0	129				
3 Hrs	67	18	1	0	0	1	0	0	87	40	8	1	0	0	0	2	0	0	64	27	7	2	0	2	0	0	0	0	0	0	0	0	240				

Entry: Arm D - Birch Avenue

	Destination : Arm A - Blackthorn Drive									Destination : Arm B - Carmanhall Road									Destination : Arm C - Blackthorn Drive									Destination : Arm D - Birch Avenue									Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	
16:00	10	3	0	0	0	0	0	0	13	4	4	2	0	0	0	0	0	0	30	5	0	0	0	1	0	0	0	0	0	0	0	0	59				
16:15	21	3	0	0	0	0	1	0	25	8	0	2	0	0	0	0	0	0	10	4	0	0	0	0	1	0	0	0	0	0	0	0	50				
16:30	25	2	0	0	0	0	0	0	27	4	2	0	0	0	0	0	0	0	6	1	0	0	0	0	1	0	0	0	0	0	0	0	48				
16:45	18	1	0	0	0	0	0	0	19	4	0	0	0	0	0	0	0	0	4	2	0	0	0	0	0	0	0	0	0	0	0	0	41				
1 Hr	74	9	0	0	0	0	1	0	84	20	6	4	0	0	0	0	0	0	69	12	0	0	0	1	2	0	0	0	0	0	0	0	198				
17:00	43	1	0	0	0	0	0	0	44	5	0	0	0	0	0	0	0	0	5	2	0	0	0	0	1	0	0	0	0	0	0	0	85				
17:15	30	3	0	0	0	0	0	0	34	2	0	0	0	0	0	0	0	0	2	1	0	0	0	0	0	0	0	0	0	0	0	0	63				
17:30	49	3	0	0	0	0	1	1	54	6	0	0	0	0	0	0	0	0	6	2	0	0	0	0	0	0	0	0	0	0	0	0	91				
17:45	31	0	0	0	0	0	0	0	31	7	1	0	0	0	0	0	0	0	8	1	0	0	0	0	0	0	0	0	0	0	0	0	61				
1 Hr	153	7	0	0	0	0	1	1	163	20	1	0	0	0	0	0	0	0	109	6	0	0	0	0	1	0	0	0	0	0	0	0	300				
18:00	17	1	0	0	0	0	0	0	18	5	0	0	0	0	0	0	0	0	5	2	0	0	0	0	0	0	0	0	0	0	0	0	45				
18:15	23	0	0	0	0	0	0	0	23	1	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0	0	0	40				
18:30	14	0	0	0	0	0	0	0	14	4	0	0	0	0	0	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	36				
18:45	3	0	0	0	0	0	0	0	3	4	0	0	0	0	0	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	28				
1 Hr	57	1	0	0	0	0	0	0	58	14	0	0	0	0	0	0	0	0	74	3	0	0	0	0	0	0	0	0	0	0	0	0	149				
3 Hrs	284	17	0	0	0	0	2	1	305	54	7	4	0	0	0	0	0	0	252	21	0	0	0	1	3	0	0	0	0	0	0	0	647				
Total	351	35	1	0	0	3	1	1	392	94	15	5	0	0	0	2	0	0	316	48	7	2	0	3	3	0	0	0	0	0	0	0	887				

Client: CST Group
Project: 3142-IRE
Site: Site 1
Date: 08/12/2016

Weather AM: Rainy
Weather PM: Cloudy & Clear

Notes: -



Origin : Arm A - Blackthorn Drive									Origin : Arm B - Carmanhall Road									Origin : Arm C - Blackthorn Drive									Origin : Arm D - Birch Avenue									Origin Totals	
CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total		
07:00	21	1	0	0	0	1	1	0	24	12	5	0	0	0	1	0	1	19	91	11	1	0	0	0	0	1	104	9	2	1	0	0	0	0	0	12	159
07:15	27	3	0	0	4	0	1	0	35	23	5	0	0	0	0	0	0	28	139	12	0	0	0	1	1	0	153	5	3	0	0	0	0	0	0	8	224
07:30	54	2	0	0	2	0	0	1	59	28	3	2	0	0	0	0	0	33	174	11	3	0	1	4	1	0	194	14	1	0	0	0	0	0	0	15	301
07:45	71	4	1	0	0	0	0	0	76	39	5	1	0	0	1	0	2	48	205	17	0	0	0	2	0	3	227	7	3	1	0	0	1	0	0	12	363
1 Hr	173	10	1	0	6	1	2	1	194	102	18	3	0	0	2	0	3	128	609	51	4	0	1	7	2	4	678	35	9	2	0	0	1	0	0	47	1047
08:00	71	4	0	0	3	4	1	1	84	34	2	2	0	0	0	0	0	38	208	14	0	0	0	2	0	2	226	7	3	1	1	0	0	0	0	12	360
08:15	100	5	0	0	0	0	1	1	107	34	4	1	0	0	0	1	0	40	216	14	2	0	0	4	1	5	242	12	3	1	0	0	0	0	0	16	405
08:30	94	4	0	0	2	2	2	0	104	42	6	1	0	0	2	1	0	52	212	13	4	1	0	3	3	3	239	9	2	0	0	0	0	0	0	11	406
08:45	127	7	0	0	1	3	0	4	142	49	7	3	1	0	1	0	0	61	186	11	3	0	0	4	0	6	210	19	3	2	0	0	1	0	0	25	438
1 Hr	392	20	0	0	6	9	4	6	437	159	19	7	1	0	3	2	0	191	822	52	9	1	0	13	4	16	917	47	11	4	1	0	1	0	0	64	1609
09:00	103	4	3	1	1	1	3	1	117	41	7	1	0	0	1	3	0	53	185	13	2	1	0	2	0	2	205	5	8	1	0	0	0	0	0	14	389
09:15	110	13	0	0	2	2	0	0	127	47	9	3	0	0	0	0	0	59	176	15	2	0	1	2	0	0	196	20	9	2	1	0	0	0	0	32	414
09:30	69	7	1	0	2	3	0	0	82	54	11	1	0	0	2	0	1	69	186	21	3	1	1	4	1	1	218	36	9	0	0	0	0	2	0	47	416
09:45	55	6	1	0	0	3	0	0	65	36	8	0	0	0	1	0	0	45	110	14	3	1	0	5	0	2	135	28	7	0	0	0	1	0	0	36	281
1 Hr	337	30	5	1	5	9	3	1	391	178	35	5	0	0	4	3	1	226	657	63	10	3	2	13	1	5	754	89	33	3	1	0	1	2	0	129	1500
3 Hrs	902	60	6	1	17	19	9	8	1022	439	72	15	1	0	9	5	4	545	2088	166	23	4	3	33	7	25	2349	171	53	9	2	0	3	2	0	240	4156

ORIGIN SUMMARY

Origin : Arm A - Blackthorn Drive									Origin : Arm B - Carmanhall Road									Origin : Arm C - Blackthorn Drive									Origin : Arm D - Birch Avenue									Origin Totals	
CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total		
16:00	70	9	1	1	2	1	1	0	85	121	13	1	0	0	2	3	0	140	95	7	2	0	0	3	0	2	109	44	12	2	0	0	1	0	0	59	393
16:15	67	7	0	0	0	2	1	0	77	107	7	0	0	0	2	2	2	120	119	7	1	0	0	1	1	2	131	39	7	2	0	0	1	1	0	50	378
16:30	73	7	2	0	1	2	1	0	86	165	13	0	0	0	1	1	0	180	94	10	1	0	0	1	1	1	108	42	5	0	0	0	0	1	0	48	422
16:45	71	5	0	0	1	2	0	2	81	143	10	2	0	0	2	1	3	161	97	11	1	0	0	1	0	3	113	38	3	0	0	0	0	0	0	41	396
1 Hr	281	28	3	1	4	7	3	2	329	536	43	3	0	0	7	7	5	601	405	35	5	0	0	6	2	8	461	163	27	4	0	0	2	2	0	198	1589
17:00	65	8	0	0	0	3	0	2	78	145	6	0	0	0	3	1	2	157	120	10	1	1	0	2	2	2	138	81	3	0	0	0	0	1	0	85	458
17:15	54	7	0	0	3	1	0	1	66	137	5	1	0	0	1	1	1	146	94	10	0	0	0	2	1	2	109	58	4	0	0	0	0	0	1	63	384
17:30	56	5	0	0	1	0	1	1	64	139	2	1	0	0	0	0	3	145	109	2	1	0	0	2	1	2	117	84	5	0	0	0	1	1	0	91	417
17:45	70	2	0	0	1	0	0	1	74	153	6	0	0	0	2	0	1	162	95	8	0	0	0	2	0	1	106	59	2	0	0	0	0	0	0	61	403
1 Hr	245	22	0	0	5	4	1	5	282	574	19	2	0	0	6	2	7	610	418	30	2	1	0	8	4	7	470	282	14	0	0	0	1	2	1	300	1662
18:00	52	5	0	1	1	0	0	3	62	114	2	0	0	0	1	3	2	122	91	9	0	0	0	0	0	3	103	42	3	0	0	0	0	0	0	45	332
18:15	68	3	0	0	1	1	1	0	74	120	3	0	0	0	1	1	2	127	99	5	0	0	0	2	0	2	108	39	1	0	0	0	0	0	0	40	349
18:30	72	1	0	0	2	1	0	1	77	93	4	0	0	0	1	0	1	99	95	4	0	0	0	1	0	1	102	36	0	0	0	0	0	0	0	36	314
18:45	55	4	0	0	1	2	0	0	62	104	4	0	0	0	0	1	1	110	90	3	0	0	0	1	2	1	97	28	0	0	0	0	0	0	0	28	297
1 Hr	247	13	0	1	5	4	1	4	275	431	13	0	0	0	3	5	6	458	375	21	0	0	1	3	3	7	410	145	4	0	0	0	0	0	0	149	1292
3 Hrs	773	63	3	2	14	15	5	11	886	1541	75	5	0	0	16	14	18	1669	1198	86	7	1	1	17	9	22	1341	590	45	4	0	0	3	4	1	647	4543
Total	1675	123	9	3	31	34	14	19	1908	1980	147	20	1	0	25	19	22	2214	3286	252	30	5	4	50	16	47	3690	761	98	13	2	0	6	6	1	887	8699

Check
DESTINATION SUMMARY

1908

2214

3690

887

8699

Client: CST Group
 Project: 3142-IRE
 Site: Site 1
 Date: 08/12/2016

Weather AM: Rainy
 Weather PM: Cloudy & Clear

Notes: -



Destination : Arm A - Blackthorn Drive										Destination : Arm B - Carmanhall Road										Destination : Arm C - Blackthorn Drive										Destination : Arm D - Birch Avenue										Dest
CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	Total				
07:00	55	3	1	0	0	1	0	1	61	38	8	0	0	0	0	0	0	46	19	5	1	0	0	1	0	1	27	21	3	0	0	0	0	1	0	25	159			
07:15	86	13	0	0	0	1	1	0	101	53	3	0	0	0	0	1	0	57	26	3	0	0	4	0	0	0	33	29	4	0	0	0	0	0	0	33	224			
07:30	133	9	0	0	1	2	1	0	146	54	3	3	0	0	2	0	1	63	50	2	2	0	2	0	0	0	56	33	3	0	0	0	0	0	0	36	301			
07:45	140	14	0	0	0	3	0	3	160	84	4	0	0	0	0	0	1	89	59	8	2	0	0	1	0	1	71	39	3	1	0	0	0	0	0	43	363			
1 Hr	414	39	1	0	1	7	2	4	468	229	18	3	0	0	2	1	2	255	154	18	5	0	6	2	0	2	187	122	13	1	0	0	0	1	0	137	1047			
08:00	144	10	1	0	0	2	0	1	158	74	7	0	0	0	2	1	1	85	62	2	2	1	3	2	0	1	73	40	4	0	0	0	0	0	0	44	360			
08:15	118	9	2	0	0	2	0	3	134	111	5	0	0	0	2	2	1	121	72	6	2	0	0	0	1	1	82	61	6	0	0	0	0	0	1	68	405			
08:30	128	10	4	1	0	4	1	1	149	115	8	0	0	0	0	3	2	128	60	7	0	0	2	3	2	0	74	54	0	1	0	0	0	0	0	55	406			
08:45	102	9	1	0	0	5	0	3	120	135	6	3	0	0	2	0	4	150	81	8	4	1	1	2	0	2	99	63	5	0	0	0	0	0	1	69	438			
1 Hr	492	38	8	1	0	13	1	8	561	435	26	3	0	0	6	6	8	484	275	23	8	2	6	7	3	4	328	218	15	1	0	0	0	0	2	236	1609			
09:00	100	15	3	0	0	1	1	1	121	119	6	1	0	0	1	0	2	129	58	9	3	1	1	2	1	0	75	57	2	0	1	0	0	4	0	64	389			
09:15	89	12	1	0	1	1	0	0	104	124	10	1	0	0	1	0	0	136	80	7	5	1	2	2	0	0	97	60	17	0	0	0	0	0	0	77	414			
09:30	118	16	3	1	1	4	0	1	144	85	10	0	0	0	3	3	1	102	74	12	0	0	2	2	0	0	90	68	10	2	0	0	0	0	0	80	416			
09:45	78	9	0	1	0	4	0	1	93	65	10	1	0	0	3	0	1	80	56	12	1	0	0	3	0	0	72	30	4	2	0	0	0	0	0	36	281			
1 Hr	385	52	7	2	2	10	1	3	462	393	36	3	0	0	8	3	4	447	268	40	9	2	5	9	1	0	334	215	33	4	1	0	0	4	0	257	1500			
3 Hrs	1291	129	16	3	3	30	4	15	1491	1057	80	9	0	0	16	10	14	1186	697	81	22	4	17	18	4	6	849	555	61	6	1	0	0	5	2	630	4156			

DESTINATION SUMMARY

Destination : Arm A - Blackthorn Drive										Destination : Arm B - Carmanhall Road										Destination : Arm C - Blackthorn Drive										Destination : Arm D - Birch Avenue										Dest
CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	Total				
16:00	98	8	1	0	0	0	1	1	109	45	8	2	0	0	3	0	1	59	170	13	2	1	2	4	3	0	195	17	12	1	0	0	0	0	0	30	393			
16:15	127	9	1	0	0	3	1	3	144	48	3	2	0	0	1	1	0	55	137	14	0	0	0	1	2	1	155	20	2	0	0	0	1	1	0	24	378			
16:30	146	11	1	0	0	0	1	1	160	42	7	0	0	0	1	1	0	51	166	15	2	0	1	2	1	0	187	20	2	0	0	0	1	1	0	24	422			
16:45	135	8	0	0	0	1	0	4	148	51	6	1	0	0	0	0	3	61	140	12	2	0	1	4	1	1	161	23	3	0	0	0	0	0	0	26	396			
1 Hr	506	36	3	0	0	4	3	9	561	186	24	5	0	0	5	2	4	226	613	54	6	1	4	11	7	2	698	80	19	1	0	0	2	2	0	104	1589			
17:00	183	9	0	1	0	3	1	3	200	52	4	1	0	0	2	1	0	60	152	10	0	0	0	3	2	3	170	24	4	0	0	0	0	0	0	28	458			
17:15	150	11	0	0	0	2	1	2	166	46	3	0	0	0	1	1	1	52	121	9	1	0	3	1	0	2	137	26	3	0	0	0	0	0	0	29	384			
17:30	179	3	1	0	0	2	2	2	189	46	2	0	0	0	1	1	0	50	144	8	1	0	1	0	0	2	156	19	1	0	0	0	0	0	2	22	417			
17:45	163	10	0	0	0	2	0	1	176	49	2	0	0	0	0	0	0	51	145	2	0	0	1	2	0	1	151	20	4	0	0	0	0	0	1	25	403			
1 Hr	675	33	1	1	0	9	4	8	731	193	11	1	0	0	4	3	1	213	562	29	2	0	5	6	2	8	614	89	12	0	0	0	0	0	3	104	1662			
18:00	111	4	0	0	0	1	2	3	121	44	6	0	0	0	0	0	1	51	131	7	0	1	1	0	1	4	145	13	2	0	0	0	0	0	0	15	332			
18:15	124	5	0	0	0	2	0	1	132	38	2	0	0	0	0	0	1	41	146	4	0	0	1	2	2	1	157	18	1	0	0	0	0	0	0	19	349			
18:30	104	5	0	0	1	0	1	1	112	54	1	0	0	0	0	0	1	56	126	3	0	0	2	2	0	1	134	12	0	0	0	0	0	0	0	12	314			
18:45	90	4	0	0	0	1	2	2	99	39	0	0	0	0	0	0	0	39	131	5	0	0	1	2	1	0	140	17	2	0	0	0	0	0	0	19	297			
1 Hr	429	18	0	0	1	4	5	7	464	175	9	0	0	0	0	0	3	187	534	19	0	1	5	6	4	7	576	60	5	0	0	0	0	0	0	65	1292			
3 Hrs	1610	87	4	1	1	17	12	24	1756	554	44	6	0	0	9	5	8	626	1709	102	8	2	14	23	13	17	1888	229	36	1	0	0	2	2	3	273	4543			
Total	2901	216	20	4	4	47	16	39	3247	1611	124	15	0	0	25	15	22	1812	2406	183	30	6	31	41	17	23	2737	784	97	7	1	0	2	7	5	903	8699			



Entry : Arm A - Burton Hall Road

	Destination : Arm A - Burton Hall Road									Destination : Arm B - Burton Hall Road									Destination : Arm C - Carmanhall Road									Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	
07:00	0	0	0	0	0	0	0	0	0	3	0	0	0	0	0	0	0	2	3	0	1	0	0	1	0	0	5	8
07:15	0	0	0	0	0	0	0	0	0	1	0	0	0	0	1	0	0	2	1	2	0	0	0	0	0	0	3	5
07:30	0	0	0	0	0	0	0	0	0	5	0	0	0	0	1	0	0	6	7	0	0	0	0	0	0	0	7	13
07:45	0	0	0	0	0	0	0	0	0	10	1	1	0	0	1	0	0	13	13	0	0	0	0	1	0	1	15	28
1 Hr	0	0	0	0	0	0	0	0	0	19	1	1	0	0	3	0	0	24	24	2	1	0	0	2	0	1	30	54
08:00	0	0	0	0	0	0	0	0	0	19	1	1	0	0	1	0	2	24	14	1	0	0	0	0	1	0	16	40
08:15	0	0	0	0	0	0	0	0	0	15	3	0	0	0	0	0	1	19	22	1	0	0	0	0	0	0	23	42
08:30	0	0	0	0	0	0	0	0	0	15	2	0	0	0	1	1	2	21	17	1	0	0	0	1	0	0	19	40
08:45	0	0	0	0	0	0	0	0	0	20	2	0	0	0	1	0	3	26	22	3	1	0	0	1	0	0	27	53
1 Hr	0	0	0	0	0	0	0	0	0	69	8	1	0	0	3	1	8	90	75	6	1	0	0	2	1	0	85	175
09:00	0	0	0	0	0	0	0	0	0	15	1	0	0	0	0	0	1	17	22	2	1	0	0	1	0	0	26	43
09:15	0	0	0	0	0	1	0	0	1	12	1	0	0	0	0	0	0	13	22	1	0	0	0	0	0	0	23	37
09:30	0	0	0	0	0	0	0	0	0	10	1	1	0	0	0	0	0	12	11	2	0	0	0	0	0	0	13	25
09:45	0	0	0	0	0	0	0	0	0	9	1	0	0	0	1	0	0	11	8	0	0	0	0	0	0	0	8	19
1 Hr	0	0	0	0	0	1	0	0	1	46	4	1	0	0	1	0	1	53	63	5	1	0	0	1	0	0	70	124
3 Hrs	0	0	0	0	0	1	0	0	1	134	13	3	0	0	7	1	9	167	162	13	3	0	0	5	1	1	185	353

Entry : Arm A - Burton Hall Road

	Destination : Arm A - Burton Hall Road									Destination : Arm B - Burton Hall Road									Destination : Arm C - Carmanhall Road									Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	
16:00	0	0	0	0	0	0	0	0	0	22	1	0	0	0	0	0	0	23	12	4	0	0	0	1	0	0	17	40
16:15	0	0	0	0	0	0	0	0	0	8	3	0	0	0	0	0	0	11	9	3	0	0	0	1	0	0	13	24
16:30	0	0	0	0	0	0	0	0	0	4	1	0	0	0	0	0	0	5	10	0	1	0	0	0	0	0	11	16
16:45	0	0	0	0	0	0	0	0	0	9	1	0	0	0	0	0	0	10	11	1	0	0	0	1	0	0	13	23
1 Hr	0	0	0	0	0	0	0	0	0	43	6	0	0	0	0	0	0	49	42	8	1	0	0	3	0	0	54	103
17:00	0	0	0	0	0	0	0	0	0	3	0	0	0	0	0	0	0	3	8	2	0	0	0	0	0	0	10	13
17:15	0	0	0	0	0	0	0	0	0	13	0	0	0	0	0	0	1	14	7	1	0	0	0	0	0	0	8	22
17:30	0	0	0	0	0	0	0	0	0	10	2	0	0	0	0	0	1	13	8	0	0	0	0	0	0	1	9	22
17:45	0	0	0	0	0	0	0	0	0	8	2	0	0	1	0	0	0	11	9	1	0	0	0	0	0	0	10	21
1 Hr	0	0	0	0	0	0	0	0	0	34	4	0	0	1	0	0	2	41	32	4	0	0	0	0	0	1	37	78
18:00	0	0	0	0	0	0	0	0	0	12	1	0	0	0	0	0	0	13	4	0	0	0	0	0	1	0	5	18
18:15	0	0	0	0	0	0	0	0	0	3	0	0	0	0	0	0	1	4	8	0	0	0	0	1	0	0	9	13
18:30	0	0	0	0	0	0	0	0	0	7	0	0	0	1	0	0	0	8	5	1	0	0	0	1	0	0	7	15
18:45	0	0	0	0	0	0	0	0	0	3	0	0	0	0	0	0	0	3	4	0	0	0	0	0	0	0	4	7
1 Hr	0	0	0	0	0	0	0	0	0	25	1	0	0	1	0	0	1	28	21	1	0	0	0	2	1	0	25	53
3 Hrs	0	0	0	0	0	0	0	0	0	102	11	0	0	2	0	0	3	118	95	13	1	0	0	5	1	1	116	234
Total	0	0	0	0	0	1	0	0	1	236	24	3	0	2	7	1	12	285	257	26	4	0	0	10	2	2	301	587

Entry : Arm B - Burton Hall Road

	Destination : Arm A - Burton Hall Road									Destination : Arm B - Burton Hall Road									Destination : Arm C - Carmanhall Road									Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	
07:00	54	5	2	0	3	2	1	0	67	0	0	0	0	0	0	0	0	0	41	4	1	0	0	1	1	1	49	116
07:15	99	14	2	0	6	1	0	3	125	0	0	0	0	0	0	0	0	0	56	10	2	0	0	1	0	0	69	194
07:30	150	9	2	0	3	2	0	0	166	0	0	0	0	0	0	0	0	0	58	5	0	0	0	1	0	0	64	230
07:45	170	5	2	0	3	2	0	0	182	0	0	0	0	0	0	0	0	0	85	2	2	0	0	0	1	1	91	273
1 Hr	473	33	8	0	15	7	1	3	540	0	0	0	0	0	0	0	0	0	240	21	5	0	0	3	2	2	273	813
08:00	169	16	4	1	5	6	0	1	202	0	0	0	0	0	0	0	0	0	63	5	0	0	0	2	0	0	70	272
08:15	163	6	1	0	5	7	0	1	183	0	0	0	0	0	0	0	0	0	78	8	1	0	0	4	1	1	93	276
08:30	159	10	2	0	2	7	1	0	181	0	0	0	0	0	0	0	0	0	91	8	2	0	0	1	2	2	106	287
08:45	139	7	1	1	4	2	0	3	157	0	0	0	0	0	0	0	0	0	84	7	1	1	0	0	1	3	97	254
1 Hr	630	39	8	2	16	22	1	5	723	0	0	0	0	0	0	0	0	0	316	28	4	1	0	7	4	6	366	1089
09:00	136	16	0	1	3	7	0	0	163	0	0	0	0	0	0	0	0	0	81	13	2	0	0	2	0	1	99	262
09:15	123	16	3	0	3	3	1	1	150	0	0	0	0	0	0	0	0	0	82	11	0	0	1	3	0	0	97	247
09:30	119	17	0	0	2	7	1	0	146	0	0	0	0	0	0	0	0	0	65	6	1	0	0	1	0	2	75	221
09:45	115	21	4	0	3	6	2	0	151	0	0	0	0	0	0	0	0	0	54	10	0	0	0	3	0	0	67	218
1 Hr	493	70	7	1	11	23	4	1	610	0	0	0	0	0	0	0	0	0	282	40	3	0	1	9	0	3	338	948

Client: CST Group
 Project: 3142-IRE
 Site: Site 2
 Date: 08/12/2016

Weather AM: Rainy
 Weather PM: Cloudy & Clear

Notes: -



09:00	168	26	2	1	3	8	0	1	209	15	2	0	0	0	0	0	1	18	103	15	3	0	0	3	0	1	125	352
09:15	152	24	5	0	3	8	1	1	194	12	3	0	0	0	1	0	2	18	104	12	0	0	1	3	0	0	120	332
09:30	139	29	1	0	2	8	1	1	181	12	1	1	0	0	0	0	0	14	76	8	1	0	0	1	0	2	88	283
09:45	146	34	6	0	3	7	3	1	200	10	1	1	0	0	1	0	0	13	62	10	0	0	0	3	0	0	75	288
1 Hr	605	113	14	1	11	31	5	4	784	49	7	2	0	0	2	0	3	63	345	45	4	0	1	10	0	3	408	1255
3 Hrs	1906	242	37	4	42	73	8	12	2324	148	22	4	0	0	9	1	16	200	1000	103	15	1	1	24	7	12	1163	3687

DESTINATION SUMMARY

	Destination : Arm A - Burton Hall Road									Destination : Arm B - Burton Hall Road									Destination : Arm C - Carmanhall Road									Dest Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	
16:00	261	38	1	0	2	9	4	5	320	25	2	0	0	0	1	0	0	28	41	10	1	0	0	5	1	0	58	406
16:15	250	28	3	0	2	6	2	2	293	11	3	0	0	0	0	0	0	14	45	11	0	0	0	1	1	1	59	366
16:30	261	13	5	0	4	6	6	3	298	6	1	0	0	0	0	0	0	7	32	2	1	0	0	2	1	0	38	343
16:45	255	22	4	0	4	12	2	2	301	12	1	0	0	0	0	0	0	13	48	6	2	0	0	3	1	1	61	375
1 Hr	1027	101	13	0	12	33	14	12	1212	54	7	0	0	0	1	0	0	62	166	29	4	0	0	11	4	2	216	1490
17:00	302	13	1	0	4	4	0	3	327	4	0	0	0	0	0	0	0	4	48	6	0	0	0	2	0	0	56	387
17:15	298	12	1	0	3	8	1	6	329	15	0	0	0	0	0	0	2	17	42	4	1	0	0	1	2	3	53	399
17:30	289	11	0	0	5	4	1	10	320	11	2	0	0	0	0	0	1	14	49	2	1	0	0	1	0	3	56	390
17:45	306	8	1	0	3	3	4	3	328	8	2	0	0	1	0	0	0	11	55	4	0	0	0	2	0	1	62	401
1 Hr	1195	44	3	0	15	19	6	22	1304	38	4	0	0	1	0	0	3	46	194	16	2	0	0	6	2	7	227	1577
18:00	256	12	1	1	3	4	4	4	285	15	2	0	0	0	0	0	0	17	37	1	0	0	0	0	2	2	42	344
18:15	240	5	0	0	3	3	2	5	258	3	0	0	0	0	0	0	1	4	50	2	0	0	0	1	0	0	53	315
18:30	211	3	0	0	5	3	0	5	227	8	0	0	0	1	0	0	1	10	37	4	0	0	0	4	0	1	46	283
18:45	188	6	0	0	3	3	1	3	204	4	0	0	0	0	0	0	0	4	29	1	0	0	0	0	0	1	31	239
1 Hr	895	26	1	1	14	13	7	17	974	30	2	0	0	1	0	0	2	35	153	8	0	0	0	5	2	4	172	1181
3 Hrs	3117	171	17	1	41	65	27	51	3490	122	13	0	0	2	1	0	5	143	513	53	6	0	0	22	8	13	615	4248
Total	5023	413	54	5	83	138	35	63	5814	270	35	4	0	2	10	1	21	343	1513	156	21	1	1	46	15	25	1778	7935



Entry : Arm A - Carmanhall Road

	Destination : Arm A - Carmanhall Road									Destination : Arm B - Carmanhall Road									Destination : Arm C - Corrig Road									Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	
07:00	0	0	0	0	0	0	0	0	0	21	3	0	0	0	0	0	0	24	3	1	0	0	0	0	0	4	28	
07:15	0	0	0	0	0	0	0	0	0	35	1	0	0	0	0	0	0	36	5	1	0	0	0	0	0	6	42	
07:30	0	0	0	0	0	0	0	0	0	38	3	0	0	0	0	0	0	41	9	1	0	0	0	0	1	11	52	
07:45	1	0	0	0	0	0	0	0	1	53	0	0	0	0	0	0	1	54	10	1	0	0	0	0	1	12	67	
1 Hr	1	0	0	0	0	0	0	0	1	147	7	0	0	0	0	0	1	155	27	4	0	0	0	0	2	33	189	
08:00	0	0	0	0	0	0	0	0	0	59	5	0	0	0	0	0	0	64	11	0	0	0	0	1	1	13	77	
08:15	0	0	0	0	0	0	0	0	0	81	5	0	0	0	0	1	4	91	17	1	0	0	0	0	0	18	109	
08:30	1	0	0	0	0	0	0	0	1	72	3	0	0	0	0	1	1	77	11	4	0	0	0	0	1	16	94	
08:45	0	0	0	0	0	0	0	0	0	68	3	1	0	0	1	0	3	76	30	0	1	0	0	1	0	32	108	
1 Hr	1	0	0	0	0	0	0	0	1	280	16	1	0	0	1	2	8	308	69	5	1	0	0	2	2	79	388	
09:00	0	0	0	0	0	0	0	0	0	69	3	2	0	0	0	0	1	75	14	2	0	0	0	1	0	17	92	
09:15	0	0	0	0	0	0	0	0	0	69	5	0	0	0	1	0	2	77	18	1	0	0	0	0	0	19	96	
09:30	0	0	0	0	0	0	0	0	0	38	6	0	0	0	1	2	1	48	10	1	0	0	0	0	0	11	59	
09:45	0	0	0	0	0	0	0	0	0	29	6	0	0	0	0	1	1	37	8	1	1	0	0	2	0	12	49	
1 Hr	0	0	0	0	0	0	0	0	0	205	20	2	0	0	2	3	5	237	50	5	1	0	0	3	0	59	296	
3 Hrs	2	0	0	0	0	0	0	0	2	632	43	3	0	0	3	5	14	700	146	14	2	0	0	5	2	171	873	

Entry : Arm A - Carmanhall Road

	Destination : Arm A - Carmanhall Road									Destination : Arm B - Carmanhall Road									Destination : Arm C - Corrig Road									Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	
16:00	0	0	0	0	0	0	0	0	0	16	7	0	0	0	1	0	3	27	6	3	2	0	0	1	0	12	39	
16:15	0	0	0	0	0	0	0	0	0	29	1	1	0	0	0	1	0	32	11	1	1	0	0	1	0	14	46	
16:30	0	0	0	0	0	0	0	0	0	19	2	0	0	0	0	0	0	21	8	3	0	0	0	0	0	11	32	
16:45	1	0	0	0	0	0	0	0	1	23	5	1	0	0	0	0	2	31	8	0	0	0	0	0	0	8	40	
1 Hr	1	0	0	0	0	0	0	0	1	87	15	2	0	0	1	1	5	111	33	7	3	0	0	2	0	45	157	
17:00	0	0	0	0	0	0	0	0	0	20	0	1	0	0	0	0	0	21	7	1	0	0	0	1	0	9	30	
17:15	0	0	0	0	0	0	0	0	0	26	5	0	0	0	0	0	0	31	10	1	0	0	0	0	0	11	42	
17:30	0	0	0	0	0	0	0	0	0	18	2	0	0	0	0	0	0	20	6	0	0	0	0	0	1	7	27	
17:45	0	0	0	0	0	0	0	0	0	21	2	0	0	0	0	0	0	23	6	1	0	0	0	0	0	7	30	
1 Hr	0	0	0	0	0	0	0	0	0	85	9	1	0	0	0	0	0	95	29	3	0	0	0	1	1	34	129	
18:00	1	0	0	0	0	0	0	0	1	22	1	0	0	0	0	0	1	24	4	3	0	0	0	0	0	7	32	
18:15	0	0	0	0	0	0	0	0	0	22	0	0	0	0	0	0	0	22	4	0	0	0	0	0	0	4	26	
18:30	0	0	0	0	0	0	0	0	0	17	0	0	0	0	0	0	0	17	6	1	0	0	0	0	0	7	24	
18:45	1	0	0	0	0	0	0	0	1	16	0	0	0	0	0	0	0	16	6	0	0	0	0	0	0	6	23	
1 Hr	2	0	0	0	0	0	0	0	2	77	1	0	0	0	0	0	1	79	20	4	0	0	0	0	0	24	105	
3 Hrs	3	0	0	0	0	0	0	0	3	249	25	3	0	0	1	1	6	285	82	14	3	0	0	3	1	103	391	
Total	5	0	0	0	0	0	0	0	5	881	68	6	0	0	4	6	20	985	228	28	5	0	0	8	3	274	1264	

Check

5

985

274

1264

Entry : Arm B - Carmanhall Road

	Destination : Arm A - Carmanhall Road									Destination : Arm B - Carmanhall Road									Destination : Arm C - Corrig Road									Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	



08:45	98	3	2	0	0	2	0	3	108	44	4	2	1	0	0	0	1	52	22	6	1	0	0	1	1	1	32	192
1 Hr	350	21	2	0	0	3	4	8	388	130	13	4	1	0	1	2	3	154	107	14	5	0	0	1	2	2	131	673
09:00	83	5	2	0	0	1	0	1	92	32	6	2	0	0	1	0	2	43	31	3	0	0	0	2	1	2	39	174
09:15	87	6	0	0	0	1	0	2	96	43	7	0	0	1	1	0	0	52	27	2	1	0	0	1	0	0	31	179
09:30	48	7	0	0	0	1	2	1	59	54	7	0	0	0	0	0	0	61	24	3	3	0	0	0	0	0	30	150
09:45	37	7	1	0	0	2	1	1	49	28	5	0	0	0	1	0	1	35	17	3	1	0	0	1	0	1	23	107
1 Hr	255	25	3	0	0	5	3	5	296	157	25	2	0	1	3	0	3	191	99	11	5	0	0	4	1	3	123	610
3 Hrs	780	57	5	0	0	8	7	16	873	375	48	9	1	1	4	3	8	449	259	36	10	0	0	6	3	6	320	1642

ORIGIN SUMMARY

	Origin : Arm A - Carmanhall Road									Origin : Arm B - Carmanhall Road									Origin : Arm C - Corrig Road									Origin Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	
16:00	22	10	2	0	0	2	0	3	39	74	11	0	0	0	1	4	1	91	36	6	1	0	0	3	1	0	47	177
16:15	40	2	2	0	0	1	1	0	46	60	7	0	0	0	0	1	3	71	33	3	2	0	0	2	3	1	44	161
16:30	27	5	0	0	0	0	0	0	32	92	8	1	0	0	0	1	1	103	51	7	0	0	0	1	0	0	59	194
16:45	32	5	1	0	0	0	0	2	40	79	4	3	0	0	2	1	3	92	49	5	0	0	1	0	0	2	57	189
1 Hr	121	22	5	0	0	3	1	5	157	305	30	4	0	0	3	7	8	357	169	21	3	0	1	6	4	3	207	721
17:00	27	1	1	0	0	1	0	0	30	86	0	0	0	0	2	0	2	90	65	2	0	0	0	2	1	1	71	191
17:15	36	6	0	0	0	0	0	0	42	85	4	1	0	0	0	1	2	93	34	3	0	0	0	3	0	3	43	178
17:30	24	2	0	0	0	0	1	0	27	89	3	1	0	0	1	0	1	95	61	0	0	0	0	0	1	1	63	185
17:45	27	3	0	0	0	0	0	0	30	80	3	0	0	0	2	0	4	89	55	4	0	0	0	1	0	2	62	181
1 Hr	114	12	1	0	0	1	1	0	129	340	10	2	0	0	5	1	9	367	215	9	0	0	0	6	2	7	239	735
18:00	27	4	0	0	0	0	0	1	32	63	1	0	0	0	0	1	1	66	22	1	0	0	0	1	2	0	26	124
18:15	26	0	0	0	0	0	0	0	26	53	3	0	0	0	1	0	2	59	31	0	0	0	0	1	1	2	35	120
18:30	23	1	0	0	0	0	0	0	24	53	1	0	0	0	0	1	2	57	19	1	0	0	0	0	0	0	20	101
18:45	23	0	0	0	0	0	0	0	23	53	0	0	0	0	0	0	1	54	19	0	0	0	0	0	1	0	20	97
1 Hr	99	5	0	0	0	0	0	1	105	222	5	0	0	0	1	2	6	236	91	2	0	0	0	2	4	2	101	442
3 Hrs	334	39	6	0	0	4	2	6	391	867	45	6	0	0	9	10	23	960	475	32	3	0	1	14	10	12	547	1898
Total	1114	96	11	0	0	12	9	22	1264	1242	93	15	1	1	13	13	31	1409	734	68	13	0	1	20	13	18	867	3540

Check

1264

1409

867

3540

DESTINATION SUMMARY

	Destination : Arm A - Carmanhall Road									Destination : Arm B - Carmanhall Road									Destination : Arm C - Corrig Road									Dest Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	
07:00	11	2	0	0	0	0	0	1	14	24	3	0	0	0	0	0	0	27	8	1	0	0	0	0	1	1	11	52
07:15	16	6	0	0	0	0	0	0	22	43	3	0	0	0	1	0	0	47	8	2	0	0	0	0	0	0	10	79
07:30	28	3	2	0	0	0	0	0	33	48	3	0	0	0	0	0	1	52	14	1	0	0	0	0	0	1	16	101
07:45	41	4	1	0	0	0	0	0	46	64	3	0	0	0	0	0	1	68	11	1	0	0	0	0	0	1	13	127
1 Hr	96	15	3	0	0	0	0	1	115	179	12	0	0	0	1	0	2	194	41	5	0	0	0	0	1	3	50	359
08:00	36	1	2	0	0	0	0	0	39	71	7	0	0	0	0	0	0	78	14	0	0	0	0	1	1	0	16	133
08:15	37	3	0	0	0	0	1	0	41	94	5	1	0	0	0	2	5	107	25	1	0	0	0	0	0	0	26	174
08:30	40	8	2	0	0	1	1	0	52	88	5	1	0	0	0	1	1	96	18	5	0	0	0	0	1	2	26	174
08:45	49	8	1	1	0	1	0	1	61	78	5	2	0	0	1	1	4	91	37	0	2	0	0	1	0	0	40	192
1 Hr	162	20	5	1	0	2	2	1	193	331	22	4	0	0	1	4	10	372	94	6	2	0	0	2	2	2	108	673
09:00	44	7	2	0	0	2	1	3	59	82	4	2	0	0	1	0	1	90	20	3	0	0	0	1	0	1	25	174
09:15	47	7	1	0	0	2	0	0	57	84	7	0	0	0	1	0	2	94	26	1	0	0	1	0	0	0	28	179

Client: CST Group
Project: 3142-IRE
Site: Site 3
Date: 08/12/2016

Weather AM: Rainy
Weather PM: Cloudy & Clear

Notes: -



09:30	56	6	1	0	0	0	0	0	63	51	9	2	0	0	1	2	1	66	19	2	0	0	0	0	0	0	21	150
09:45	32	5	0	0	0	2	0	1	40	39	8	1	0	0	0	1	2	51	11	2	1	0	0	2	0	0	16	107
1 Hr	179	25	4	0	0	6	1	4	219	256	28	5	0	0	3	3	6	301	76	8	1	0	1	3	0	1	90	610
3 Hrs	437	60	12	1	0	8	3	6	527	766	62	9	0	0	5	7	18	867	211	19	3	0	1	5	3	6	248	1642

DESTINATION SUMMARY

	Destination : Arm A - Carmanhall Road									Destination : Arm B - Carmanhall Road									Destination : Arm C - Corrig Road									Dest Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	
16:00	87	12	0	0	0	2	3	0	104	30	9	1	0	0	2	0	3	45	15	6	2	0	0	2	2	1	28	177
16:15	80	8	0	0	0	1	1	3	93	38	1	3	0	0	1	3	1	47	15	3	1	0	0	1	1	0	21	161
16:30	134	13	0	0	0	0	1	0	148	25	4	0	0	0	1	0	0	30	11	3	1	0	0	0	0	1	16	194
16:45	112	9	2	0	0	2	1	4	130	34	5	2	0	1	0	0	3	45	14	0	0	0	0	0	0	0	14	189
1 Hr	413	42	2	0	0	5	6	7	475	127	19	6	0	1	4	3	7	167	55	12	4	0	0	3	3	2	79	721
17:00	135	2	0	0	0	3	1	2	143	31	0	1	0	0	1	0	0	33	12	1	0	0	0	1	0	1	15	191
17:15	103	6	1	0	0	1	1	4	116	34	5	0	0	0	2	0	1	42	18	2	0	0	0	0	0	0	20	178
17:30	136	3	1	0	0	1	0	2	143	28	2	0	0	0	0	1	0	31	10	0	0	0	0	0	1	0	11	185
17:45	123	6	0	0	0	3	0	4	136	27	3	0	0	0	0	0	2	32	12	1	0	0	0	0	0	0	13	181
1 Hr	497	17	2	0	0	8	2	12	538	120	10	1	0	0	3	1	3	138	52	4	0	0	0	1	1	1	59	735
18:00	76	2	0	0	0	1	2	0	81	28	1	0	0	0	0	1	1	31	8	3	0	0	0	0	0	1	12	124
18:15	71	3	0	0	0	1	0	2	77	33	0	0	0	0	1	1	2	37	6	0	0	0	0	0	0	0	6	120
18:30	67	2	0	0	0	0	0	2	71	22	0	0	0	0	0	0	0	22	6	1	0	0	0	0	1	0	8	101
18:45	64	0	0	0	0	0	1	1	66	24	0	0	0	0	0	0	0	24	7	0	0	0	0	0	0	0	7	97
1 Hr	278	7	0	0	0	2	3	5	295	107	1	0	0	0	1	2	3	114	27	4	0	0	0	0	1	1	33	442
3 Hrs	1188	66	4	0	0	15	11	24	1308	354	30	7	0	1	8	6	13	419	134	20	4	0	0	4	5	4	171	1898
Total	1625	126	16	1	0	23	14	30	1835	1120	92	16	0	1	13	13	31	1286	345	39	7	0	1	9	8	10	419	3540



Notes:

Entry : Arm A - Blackthorn Drive											Destination : Arm B - Blackthorn Drive											Destination : Arm C - Rockbrook Entrance											Arm Totals
Destination : Arm A - Blackthorn Drive											Destination : Arm B - Blackthorn Drive											Destination : Arm C - Rockbrook Entrance											
CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total							
07:00	0	0	0	0	0	0	0	0	49	3	1	0	0	1	0	2	56	4	0	0	0	0	0	0	0	4	60						
07:15	0	0	0	0	0	0	0	0	98	12	1	0	0	2	1	3	117	1	1	0	0	0	0	0	0	2	119						
07:30	0	0	0	0	0	0	0	0	125	4	1	0	1	2	1	5	139	7	0	0	0	0	0	0	0	7	146						
07:45	2	0	0	0	0	0	0	2	143	8	0	0	0	2	2	3	158	9	0	0	0	0	0	0	0	9	169						
1 Hr	2	0	0	0	0	0	0	2	415	27	3	0	1	7	4	13	470	21	1	0	0	0	0	0	0	22	494						
08:00	0	0	0	0	0	0	0	0	169	12	1	0	0	1	0	2	185	8	0	0	0	0	0	0	0	8	193						
08:15	0	0	0	0	0	0	0	0	141	6	3	0	0	1	1	6	158	7	0	0	0	0	0	0	0	7	165						
08:30	0	0	0	0	0	0	0	0	157	8	3	2	0	0	0	11	181	14	2	0	0	0	0	0	0	16	197						
08:45	0	0	0	0	0	0	0	0	113	7	1	0	0	4	3	14	142	17	0	0	0	0	0	0	0	17	159						
1 Hr	0	0	0	0	0	0	0	0	580	33	8	2	0	6	4	33	666	46	2	0	0	0	0	0	0	48	714						
09:00	0	0	0	0	0	0	0	0	108	11	1	0	0	7	1	7	135	16	0	0	0	0	0	0	0	16	151						
09:15	0	0	0	0	0	0	0	0	104	9	2	0	1	2	0	3	121	12	1	0	0	0	0	0	1	14	135						
09:30	1	0	0	0	0	0	0	1	97	11	2	1	0	3	1	2	117	17	4	0	0	0	0	0	0	21	139						
09:45	0	0	0	0	0	0	0	0	96	9	0	0	0	8	1	0	114	11	0	0	0	0	1	0	0	12	126						
1 Hr	1	0	0	0	0	0	0	1	405	40	5	1	1	20	3	12	487	56	5	0	0	0	1	0	1	63	551						
3 Hrs	3	0	0	0	0	0	0	3	1400	100	16	3	2	33	11	58	1623	123	8	0	0	0	1	0	1	133	1759						

Entry : Arm A - Blackthorn Drive											Destination : Arm B - Blackthorn Drive											Destination : Arm C - Rockbrook Entrance											Arm Totals
Destination : Arm A - Blackthorn Drive											Destination : Arm B - Blackthorn Drive											Destination : Arm C - Rockbrook Entrance											
CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC	Total							
16:00	0	0	0	0	0	0	0	0	80	6	1	0	0	1	2	1	91	12	0	0	0	0	0	0	0	12	103						
16:15	0	0	0	0	0	0	0	0	106	5	2	0	0	1	1	2	117	8	0	0	0	0	0	0	0	8	125						
16:30	2	0	0	0	0	0	0	2	81	7	0	0	0	0	1	2	91	11	0	0	0	0	0	0	0	11	104						
16:45	0	0	0	0	0	0	0	0	91	4	0	0	0	0	0	2	97	6	0	0	0	0	0	0	0	6	103						
1 Hr	2	0	0	0	0	0	0	2	358	22	3	0	0	2	4	7	396	37	0	0	0	0	0	0	0	37	435						
17:00	0	0	0	0	0	0	0	0	114	4	0	0	0	1	1	1	121	13	0	0	0	0	0	0	1	14	135						
17:15	0	0	0	0	0	1	0	1	119	4	0	1	0	1	1	3	129	10	0	0	0	0	0	0	0	10	140						
17:30	0	0	0	0	0	0	0	0	114	0	0	0	0	0	2	1	117	11	1	0	0	0	0	0	0	12	129						
17:45	1	1	0	0	0	0	0	2	129	6	1	0	0	1	0	1	138	12	0	0	0	0	0	0	1	13	153						
1 Hr	1	1	0	0	0	1	0	3	476	14	1	1	0	3	4	6	505	46	1	0	0	0	0	0	2	49	557						
18:00	0	0	0	0	0	0	0	0	90	3	0	0	0	0	1	3	97	12	0	0	0	0	0	0	0	12	109						
18:15	2	0	0	0	0	0	0	2	123	6	0	0	0	0	0	1	130	12	0	0	0	0	0	0	0	12	144						
18:30	0	0	0	0	0	0	0	0	88	1	0	0	1	0	0	1	91	10	0	0	0	1	0	1	1	12	103						
18:45	0	0	0	0	0	0	0	0	84	5	0	0	0	1	0	0	90	10	0	0	0	0	0	0	0	10	100						
1 Hr	2	0	0	0	0	0	0	2	385	15	0	0	1	1	1	5	408	44	0	0	0	0	1	0	1	46	456						
3 Hrs	5	1	0	0	0	1	0	7	1219	51	4	1	1	6	9	18	1309	127	1	0	0	0	1	0	3	132	1448						

Total	8	1	0	0	0	1	0	10	2619	151	20	4	3	39	20	76	2932	250	9	0	0	0	2	0	4	265	3207
--------------	---	---	---	---	---	---	---	----	------	-----	----	---	---	----	----	----	------	-----	---	---	---	---	---	---	---	-----	------

Client: CST Group Weather AM: Rainy
 Project: 3142-IRE Weather PM: Cloudy & Clear
 Site: Site 4
 Date: 08/12/2016



Entry : Arm B - Blackthorn Drive

	Destination : Arm A - Blackthorn Drive									Total	Destination : Arm B - Blackthorn Drive									Total	Destination : Arm C - Rockbrook Entrance									Total	Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			
07:00	19	1	0	0	0	0	1	0	21	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	0	1	22			
07:15	21	3	0	0	4	0	1	1	30	0	0	0	0	0	0	0	0	0	0	2	0	0	0	0	0	0	2	32			
07:30	35	0	0	0	2	0	0	2	39	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	0	1	40			
07:45	40	4	1	1	1	1	0	0	48	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	48			
1 Hr	115	8	1	1	7	1	2	3	138	0	0	0	0	0	0	0	0	0	0	4	0	0	0	0	0	0	4	142			
08:00	65	2	0	0	2	1	0	2	72	2	0	0	0	0	0	0	0	0	0	5	0	0	0	0	0	0	5	79			
08:15	68	8	0	0	0	1	0	1	78	0	0	0	0	0	0	0	0	0	0	5	0	0	0	0	0	0	5	83			
08:30	64	3	0	0	2	2	1	0	72	0	0	0	0	0	0	0	0	0	0	10	0	0	0	0	0	1	11	83			
08:45	74	2	2	0	1	4	0	3	86	0	0	0	0	0	0	0	0	0	0	15	0	0	0	0	0	0	1	16	102		
1 Hr	271	15	2	0	5	8	1	6	308	2	0	0	0	0	0	0	0	0	2	33	2	0	0	0	0	2	37	347			
09:00	70	6	1	1	1	1	2	0	82	0	0	0	0	0	0	0	0	0	0	24	0	0	0	0	0	1	25	107			
09:15	88	10	1	0	2	2	0	2	105	0	0	0	0	0	0	0	0	0	0	17	0	0	0	0	0	1	18	123			
09:30	48	2	1	0	2	2	0	0	55	0	0	0	0	0	0	0	0	0	0	17	0	0	0	0	0	0	17	72			
09:45	58	8	1	0	0	3	1	0	71	0	0	0	0	0	0	0	0	0	0	18	1	0	0	0	0	1	20	91			
1 Hr	264	26	4	1	5	8	3	2	313	0	0	0	0	0	0	0	0	0	0	76	1	0	0	0	0	3	80	393			
3 Hrs	650	49	7	2	17	17	6	11	759	2	0	0	0	0	0	0	0	0	2	113	3	0	0	0	0	5	121	882			

Entry : Arm B - Blackthorn Drive

	Destination : Arm A - Blackthorn Drive									Total	Destination : Arm B - Blackthorn Drive									Total	Destination : Arm C - Rockbrook Entrance									Total	Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			
16:00	92	12	1	0	2	3	1	2	113	0	0	0	0	0	0	0	0	0	0	17	1	0	0	0	0	0	1	19	132		
16:15	75	10	0	0	0	2	0	0	87	0	0	0	0	0	0	0	0	0	0	14	0	0	0	0	0	0	14	101			
16:30	79	11	1	0	1	2	1	1	96	0	0	0	0	0	0	0	0	0	0	11	0	0	0	0	0	2	13	109			
16:45	83	3	0	0	1	0	0	5	92	0	0	0	0	0	0	0	0	0	0	19	2	0	0	0	0	2	23	115			
1 Hr	329	36	2	0	4	7	2	8	388	0	0	0	0	0	0	0	0	0	0	61	3	0	0	0	0	5	69	457			
17:00	87	7	0	0	0	1	0	7	102	0	0	0	0	0	0	0	0	0	0	11	1	0	0	0	0	2	14	116			
17:15	80	4	0	0	3	0	0	3	90	1	0	0	0	0	0	0	0	0	1	15	2	0	0	0	0	2	19	110			
17:30	73	6	0	0	1	2	0	10	92	1	0	0	0	0	0	0	0	0	1	12	0	0	0	0	0	0	12	105			
17:45	108	2	0	0	1	0	0	4	115	3	0	0	0	0	0	0	0	0	3	16	0	0	0	0	0	0	16	134			
1 Hr	348	19	0	0	5	3	0	24	399	5	0	0	0	0	0	0	0	0	5	54	3	0	0	0	0	4	61	465			
18:00	62	6	0	1	1	0	0	5	75	1	0	0	0	0	0	0	0	0	1	13	0	0	0	0	0	3	16	92			
18:15	79	2	0	0	2	0	1	3	87	0	0	0	0	0	0	0	0	0	0	20	1	0	0	0	0	0	21	108			
18:30	78	0	0	0	1	1	0	2	82	0	0	0	0	0	0	0	0	0	0	10	0	0	0	0	0	1	11	93			
18:45	63	3	0	0	1	0	0	6	73	0	0	0	0	0	0	0	0	0	0	12	0	0	0	0	1	0	13	86			
1 Hr	282	11	0	1	5	1	1	16	317	1	0	0	0	0	0	0	0	0	1	55	1	0	0	0	1	0	4	61	379		
3 Hrs	959	66	2	1	14	11	3	48	1104	6	0	0	0	0	0	0	0	0	6	170	7	0	0	0	1	0	13	191	1301		

Total	1609	115	9	3	31	28	9	59	1863	8	0	0	0	0	0	0	0	0	8	283	10	0	0	0	0	1	0	18	312	2183
--------------	------	-----	---	---	----	----	---	----	------	---	---	---	---	---	---	---	---	---	---	-----	----	---	---	---	---	---	---	----	-----	------

Client: CST Group Weather AM: Rainy
 Project: 3142-IRE Weather PM: Cloudy & Clear
 Site: Site 4
 Date: 08/12/2016



Notes:

Entry : Arm C - Rockbrook Entrance

	Destination : Arm A - Blackthorn Drive									Total	Destination : Arm B - Blackthorn Drive									Total	Destination : Arm C - Rockbrook Entrance									Total	Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			
07:00	2	0	0	0	0	0	0	0	0	2	3	0	0	0	0	0	0	0	3	0	0	0	0	0	0	0	0	0	5		
07:15	3	1	0	0	0	0	0	0	0	4	2	0	0	0	0	0	0	0	2	0	0	0	0	0	0	0	0	0	6		
07:30	5	1	0	0	0	0	0	0	0	6	9	1	0	0	0	0	0	0	10	0	0	0	0	0	0	0	0	0	16		
07:45	12	0	0	0	0	0	0	0	0	12	6	0	0	0	0	0	0	0	6	0	0	0	0	0	0	0	0	0	18		
1 Hr	22	2	0	0	0	0	0	0	0	24	20	1	0	0	0	0	0	0	21	0	0	0	0	0	0	0	0	0	45		
08:00	6	0	0	0	0	0	0	0	0	6	5	0	0	0	0	0	0	0	5	0	0	0	0	0	0	0	0	0	11		
08:15	9	0	0	0	0	0	0	0	2	11	6	0	0	0	0	0	0	0	6	0	0	0	0	0	0	0	0	0	17		
08:30	9	2	0	0	0	0	0	0	1	12	9	0	0	0	0	0	0	0	9	0	0	0	0	0	0	0	0	0	21		
08:45	12	1	0	0	0	0	0	0	1	14	6	0	0	0	0	0	0	1	7	0	0	0	0	0	0	0	0	0	21		
1 Hr	36	3	0	0	0	0	0	0	4	43	26	0	0	0	0	0	0	1	27	0	0	0	0	0	0	0	0	0	70		
09:00	6	1	0	0	0	0	0	0	0	7	5	0	0	0	0	0	0	0	5	0	0	0	0	0	0	0	0	0	12		
09:15	20	0	0	0	0	0	0	0	0	20	4	1	0	0	0	0	0	0	5	0	0	0	0	0	0	0	0	0	25		
09:30	17	1	0	0	0	0	0	0	0	18	10	0	0	0	0	0	0	0	10	0	0	0	0	0	0	0	0	0	28		
09:45	9	1	0	0	0	0	0	0	0	10	13	1	0	0	0	0	0	1	15	0	0	0	0	0	0	0	0	0	25		
1 Hr	52	3	0	0	0	0	0	0	0	55	32	2	0	0	0	0	0	1	35	0	0	0	0	0	0	0	0	0	90		
3 Hrs	110	8	0	0	0	0	0	0	4	122	78	3	0	0	0	0	0	2	83	0	0	0	0	0	0	0	0	0	205		

Entry : Arm C - Rockbrook Entrance

	Destination : Arm A - Blackthorn Drive									Total	Destination : Arm B - Blackthorn Drive									Total	Destination : Arm C - Rockbrook Entrance									Total	Arm Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			
16:00	17	2	0	1	0	0	1	0	0	21	10	0	0	0	0	1	0	0	11	0	0	1	0	0	0	0	0	0	33		
16:15	20	1	0	0	0	0	0	0	0	21	14	0	0	0	0	0	0	0	14	0	0	1	0	0	0	0	0	1	36		
16:30	17	0	1	0	0	0	1	0	0	19	10	0	0	0	0	0	0	0	10	0	0	0	0	0	0	0	0	0	29		
16:45	18	0	0	0	0	0	0	0	1	19	17	0	0	0	0	0	0	1	18	0	0	0	0	0	0	0	0	0	37		
1 Hr	72	3	1	1	0	1	1	1	1	80	51	0	0	0	0	1	0	1	53	0	0	2	0	0	0	0	0	2	135		
17:00	6	0	0	0	0	0	0	0	0	6	12	2	0	0	0	0	0	0	14	0	0	0	0	0	0	0	0	0	20		
17:15	12	1	0	0	0	0	0	0	0	13	10	0	0	0	0	0	0	0	10	0	0	0	0	0	0	0	0	0	23		
17:30	19	0	0	0	0	0	0	0	1	20	13	0	0	0	0	0	0	0	13	0	0	0	0	0	0	0	0	0	33		
17:45	14	0	0	0	0	0	0	0	0	14	14	0	0	0	0	0	0	1	15	0	0	0	0	0	0	0	0	0	29		
1 Hr	51	1	0	0	0	0	0	0	1	53	49	2	0	0	0	0	0	1	52	0	0	0	0	0	0	0	0	0	105		
18:00	16	1	0	0	0	0	0	0	0	17	15	0	0	0	0	1	0	0	16	0	0	0	0	0	0	0	0	0	33		
18:15	17	1	0	0	0	0	0	0	0	18	3	0	0	0	0	0	0	1	4	0	0	0	0	0	0	0	0	0	22		
18:30	18	0	0	0	0	0	0	0	0	18	16	0	0	0	0	0	0	0	16	0	0	0	0	0	0	0	0	0	34		
18:45	14	0	0	0	0	0	0	0	0	14	10	0	0	0	0	0	0	0	10	0	0	0	0	0	0	0	0	0	24		
1 Hr	65	2	0	0	0	0	0	0	0	67	44	0	0	0	0	1	0	1	46	0	0	0	0	0	0	0	0	0	113		
3 Hrs	188	6	1	1	0	1	1	1	2	200	144	2	0	0	0	2	0	3	151	0	0	2	0	0	0	0	0	2	353		
Total	298	14	1	1	0	1	1	1	6	322	222	5	0	0	0	2	0	5	234	0	0	2	0	0	0	0	0	2	558		



ORIGIN SUMMARY

	Origin : Arm A - Blackthorn Drive									Total	Origin : Arm B - Blackthorn Drive									Total	Origin : Arm C - Rockbrook Entrance									Total	Origin Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			
07:00	53	3	1	0	0	1	0	2	60	20	1	0	0	0	0	1	0	22	5	0	0	0	0	0	0	0	5	87			
07:15	99	13	1	0	0	2	1	3	119	23	3	0	0	4	0	1	1	32	5	1	0	0	0	0	0	0	6	157			
07:30	132	4	1	0	1	2	1	5	146	36	0	0	0	2	0	0	2	40	14	2	0	0	0	0	0	0	16	202			
07:45	154	8	0	0	0	2	2	3	169	40	4	1	1	1	1	0	0	48	18	0	0	0	0	0	0	0	18	235			
1 Hr	438	28	3	0	1	7	4	13	494	119	8	1	1	7	1	2	3	142	42	3	0	0	0	0	0	0	45	681			
08:00	177	12	1	0	0	1	0	2	193	70	4	0	0	2	1	0	2	79	11	0	0	0	0	0	0	0	11	283			
08:15	148	6	3	0	0	1	1	6	165	73	8	0	0	0	1	0	1	83	15	0	0	0	0	0	0	2	17	265			
08:30	171	10	3	2	0	0	0	11	197	74	3	0	0	2	2	1	1	83	18	2	0	0	0	0	0	1	21	301			
08:45	130	7	1	0	0	4	3	14	159	89	2	2	0	1	4	0	4	102	18	1	0	0	0	0	0	2	21	282			
1 Hr	626	35	8	2	0	6	4	33	714	306	17	2	0	5	8	1	8	347	62	3	0	0	0	0	0	5	70	1131			
09:00	124	11	1	0	0	7	1	7	151	94	6	1	1	1	1	2	1	107	11	1	0	0	0	0	0	0	12	270			
09:15	116	10	2	0	1	2	0	4	135	105	10	1	0	2	2	0	3	123	24	1	0	0	0	0	0	0	25	283			
09:30	115	15	2	1	0	3	1	2	139	65	2	1	0	2	2	0	0	72	27	1	0	0	0	0	0	0	28	239			
09:45	107	9	0	0	0	9	1	0	126	76	9	1	0	0	3	1	1	91	22	2	0	0	0	0	0	1	25	242			
1 Hr	462	45	5	1	1	21	3	13	551	340	27	4	1	5	8	3	5	393	84	5	0	0	0	0	0	1	90	1034			
3 Hrs	1526	108	16	3	2	34	11	59	1759	765	52	7	2	17	17	6	16	882	188	11	0	0	0	0	0	6	205	2846			

ORIGIN SUMMARY

	Origin : Arm A - Blackthorn Drive									Total	Origin : Arm B - Blackthorn Drive									Total	Origin : Arm C - Rockbrook Entrance									Total	Origin Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			
16:00	92	6	1	0	0	1	2	1	103	109	13	1	0	2	3	1	3	132	27	2	1	1	0	1	1	0	33	268			
16:15	114	5	2	0	0	1	1	2	125	89	10	0	0	0	2	0	0	101	34	1	1	0	0	0	0	0	36	262			
16:30	94	7	0	0	0	0	1	2	104	90	11	1	0	1	2	1	3	109	27	0	1	0	0	1	0	0	29	242			
16:45	97	4	0	0	0	0	0	2	103	102	5	0	0	1	0	0	7	115	35	0	0	0	0	0	0	2	37	255			
1 Hr	397	22	3	0	0	2	4	7	435	390	39	2	0	4	7	2	13	457	123	3	3	1	0	2	1	2	135	1027			
17:00	127	4	0	0	0	1	1	2	135	98	8	0	0	0	1	0	9	116	18	2	0	0	0	0	0	0	20	271			
17:15	129	4	0	1	0	2	1	3	140	96	6	0	0	3	0	0	5	110	22	1	0	0	0	0	0	0	23	273			
17:30	125	1	0	0	0	0	2	1	129	86	6	0	0	1	2	0	10	105	32	0	0	0	0	0	0	1	33	267			
17:45	142	7	1	0	0	1	0	2	153	127	2	0	0	1	0	0	4	134	28	0	0	0	0	0	0	1	29	316			
1 Hr	523	16	1	1	0	4	4	8	557	407	22	0	0	5	3	0	28	465	100	3	0	0	0	0	0	2	105	1127			
18:00	102	3	0	0	0	0	1	3	109	76	6	0	1	1	0	0	8	92	31	1	0	0	0	1	0	0	33	234			
18:15	137	6	0	0	0	0	0	1	144	99	3	0	0	2	0	1	3	108	20	1	0	0	0	0	0	1	22	274			
18:30	98	1	0	0	1	1	0	2	103	88	0	0	0	1	1	0	3	93	34	0	0	0	0	0	0	0	34	230			
18:45	94	5	0	0	0	1	0	0	100	75	3	0	0	1	1	0	6	86	24	0	0	0	0	0	0	0	24	210			
1 Hr	431	15	0	0	1	2	1	6	456	338	12	0	1	5	2	1	20	379	109	2	0	0	0	1	0	1	113	948			
3 Hrs	1351	53	4	1	1	8	9	21	1448	1135	73	2	1	14	12	3	61	1301	332	8	3	1	0	3	1	5	353	3102			

Total	2877	161	20	4	3	42	20	80	3207	1900	125	9	3	31	29	9	77	2183	520	19	3	1	0	3	1	11	558	5948
--------------	------	-----	----	---	---	----	----	----	------	------	-----	---	---	----	----	---	----	------	-----	----	---	---	---	---	---	----	-----	------



DESTINATION SUMMARY

	Destination : Arm A - Blackthorn Drive									Total	Destination : Arm B - Blackthorn Drive									Total	Destination : Arm C - Rockbrook Entrance									Total	Dest Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			
07:00	21	1	0	0	0	0	1	0	23	52	3	1	0	0	1	0	2	59	5	0	0	0	0	0	0	0	5	87			
07:15	24	4	0	0	4	0	1	1	34	100	12	1	0	0	2	1	3	119	3	1	0	0	0	0	0	0	4	157			
07:30	40	1	0	0	2	0	0	2	45	134	5	1	0	1	2	1	5	149	8	0	0	0	0	0	0	0	8	202			
07:45	54	4	1	1	1	1	0	0	62	149	8	0	0	0	2	2	3	164	9	0	0	0	0	0	0	0	9	235			
1 Hr	139	10	1	1	7	1	2	3	164	435	28	3	0	1	7	4	13	491	25	1	0	0	0	0	0	0	26	681			
08:00	71	2	0	0	2	1	0	2	78	176	12	1	0	0	1	0	2	192	11	2	0	0	0	0	0	0	13	283			
08:15	77	8	0	0	0	1	0	3	89	147	6	3	0	0	1	1	6	164	12	0	0	0	0	0	0	0	12	265			
08:30	73	5	0	0	2	2	1	1	84	166	8	3	2	0	0	0	11	190	24	2	0	0	0	0	0	1	27	301			
08:45	86	3	2	0	1	4	0	4	100	119	7	1	0	0	4	3	15	149	32	0	0	0	0	0	0	1	33	282			
1 Hr	307	18	2	0	5	8	1	10	351	608	33	8	2	0	6	4	34	695	79	4	0	0	0	0	0	2	85	1131			
09:00	76	7	1	1	1	1	2	0	89	113	11	1	0	0	7	1	7	140	40	0	0	0	0	0	0	1	41	270			
09:15	108	10	1	0	2	2	0	2	125	108	10	2	0	1	2	0	3	126	29	1	0	0	0	0	0	2	32	283			
09:30	66	3	1	0	2	2	0	0	74	107	11	2	1	0	3	1	2	127	34	4	0	0	0	0	0	0	38	239			
09:45	67	9	1	0	0	3	1	0	81	109	10	0	0	0	8	1	1	129	29	1	0	0	0	1	0	1	32	242			
1 Hr	317	29	4	1	5	8	3	2	369	437	42	5	1	1	20	3	13	522	132	6	0	0	0	1	0	4	143	1034			
3 Hrs	763	57	7	2	17	17	6	15	884	1480	103	16	3	2	33	11	60	1708	236	11	0	0	0	1	0	6	254	2846			

DESTINATION SUMMARY

	Destination : Arm A - Blackthorn Drive									Total	Destination : Arm B - Blackthorn Drive									Total	Destination : Arm C - Rockbrook Entrance									Total	Dest Totals
	CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			CAR	LGV	OGV1	OGV2	BUS	LTAX	MC	PC			
16:00	109	14	1	1	2	3	2	2	134	90	6	1	0	0	2	2	1	102	29	1	1	0	0	0	0	1	32	268			
16:15	95	11	0	0	0	2	0	0	108	120	5	2	0	0	1	1	2	131	22	0	1	0	0	0	0	0	23	262			
16:30	98	11	2	0	1	3	1	1	117	91	7	0	0	0	0	1	2	101	22	0	0	0	0	0	0	2	24	242			
16:45	101	3	0	0	1	0	0	0	111	108	4	0	0	0	0	0	3	115	25	2	0	0	0	0	0	2	29	255			
1 Hr	403	39	3	1	4	8	3	9	470	409	22	3	0	0	3	4	8	449	98	3	2	0	0	0	0	5	108	1027			
17:00	93	7	0	0	0	1	0	7	108	126	6	0	0	0	1	1	1	135	24	1	0	0	0	0	0	3	28	271			
17:15	92	5	0	0	3	1	0	3	104	130	4	0	1	0	1	1	3	140	25	2	0	0	0	0	0	2	29	273			
17:30	92	6	0	0	1	2	0	11	112	128	0	0	0	0	0	2	1	131	23	1	0	0	0	0	0	0	24	267			
17:45	123	3	0	0	1	0	0	4	131	146	6	1	0	0	1	0	2	156	28	0	0	0	0	0	0	1	29	316			
1 Hr	400	21	0	0	5	4	0	25	455	530	16	1	1	0	3	4	7	562	100	4	0	0	0	0	0	6	110	1127			
18:00	78	7	0	1	1	0	0	5	92	106	3	0	0	0	1	1	3	114	25	0	0	0	0	0	0	3	28	234			
18:15	98	3	0	0	2	0	1	3	107	126	6	0	0	0	0	0	2	134	32	1	0	0	0	0	0	0	33	274			
18:30	96	0	0	0	1	1	0	2	100	104	1	0	0	1	0	0	1	107	20	0	0	0	0	1	0	2	23	230			
18:45	77	3	0	0	1	0	0	6	87	94	5	0	0	0	1	0	0	100	22	0	0	0	0	1	0	0	23	210			
1 Hr	349	13	0	1	5	1	1	16	386	430	15	0	0	1	2	1	6	455	99	1	0	0	0	2	0	5	107	948			
3 Hrs	1152	73	3	2	14	13	4	50	1311	1369	53	4	1	1	8	9	21	1466	297	8	2	0	0	2	0	16	325	3102			
Total	1915	130	10	4	31	30	10	65	2195	2849	156	20	4	3	41	20	81	3174	533	19	2	0	0	3	0	22	579	5948			

Check

Checks

Arms Tot 5948 5948
Origin Tot 5948 5948
Dest Tot 5948 5948

2195

3174

579

5948



Client: CST Group
 Project: 3142-IRE Rockbrook Apartments, Sandyford
 Site: 1
 Date: 08/12/2016

	Entry								Total	Exit								Total
	CAR	LGV	OGV1	OGV2	PSV	TAXI	MC	PC		CAR	LGV	OGV1	OGV2	PSV	TAXI	MC	PC	
07:00	4	0	0	0	0	0	0	0	4	4	0	0	0	0	0	0	0	4
07:15	1	0	0	0	0	0	0	0	1	4	0	0	0	0	0	0	4	
07:30	3	0	0	0	0	0	0	0	3	15	1	0	0	0	0	0	16	
07:45	1	1	0	0	0	0	0	0	2	18	0	0	0	0	0	0	18	
1 Hr	9	1	0	0	0	0	0	0	10	41	1	0	0	0	0	0	42	
08:00	6	1	0	0	0	0	0	0	7	9	0	0	0	0	0	0	9	
08:15	2	0	0	0	0	0	0	0	2	14	0	0	0	0	0	2	16	
08:30	1	1	0	0	0	0	0	0	2	20	0	0	0	0	0	0	20	
08:45	9	1	0	0	0	0	0	0	10	13	2	0	0	0	0	0	15	
1 Hr	18	3	0	0	0	0	0	0	21	56	2	0	0	0	0	2	60	
09:00	7	0	0	0	0	0	0	0	7	5	2	0	0	0	0	0	7	
09:15	6	1	0	0	0	0	0	1	8	5	0	0	0	0	0	0	5	
09:30	3	0	0	0	0	0	0	0	3	2	0	0	0	0	0	0	2	
09:45	4	0	0	0	0	0	0	1	5	7	0	0	0	0	0	0	7	
1 Hr	20	1	0	0	0	0	0	2	23	19	2	0	0	0	0	0	21	
3 Hr Total	47	5	0	0	0	0	0	2	54	116	5	0	0	0	0	2	123	
16:00	3	0	0	0	0	0	0	0	3	2	0	1	0	0	0	0	3	
16:15	4	0	1	0	0	0	0	0	5	2	0	1	0	0	0	0	3	
16:30	5	0	1	0	0	0	0	0	6	5	0	1	0	0	0	0	6	
16:45	4	0	0	0	0	0	0	0	4	4	0	0	0	0	0	0	4	
1 Hr	16	0	2	0	0	0	0	0	18	13	0	3	0	0	0	0	16	
17:00	8	0	0	0	0	0	0	0	8	1	0	0	0	0	0	0	1	
17:15	9	1	0	0	0	0	0	0	10	5	0	0	0	0	0	0	5	
17:30	9	0	0	0	0	0	0	0	9	3	0	0	0	0	0	1	4	
17:45	10	0	0	0	0	0	0	1	11	6	0	0	0	0	0	1	7	
1 Hr	36	1	0	0	0	0	0	1	38	15	0	0	0	0	0	2	17	
18:00	6	0	0	0	0	1	0	1	8	4	0	0	0	0	1	0	5	
18:15	12	0	0	0	0	0	0	0	12	4	0	0	0	0	0	0	4	
18:30	9	0	0	0	0	0	0	1	10	3	0	0	0	0	0	0	3	
18:45	5	0	0	0	0	0	0	0	5	5	0	0	0	0	0	0	5	
1 Hr	32	0	0	0	0	1	0	2	35	16	0	0	0	0	1	0	17	
3 Hr Total	84	1	2	0	0	1	0	3	91	44	0	3	0	0	1	2	50	
Total	131	6	2	0	0	1	0	5	145	160	5	3	0	0	1	4	173	


APPENDIX B

TRAFFIC FLOW FIGURES

Figure

- 1 Existing Traffic 2016
- 2 Existing Traffic 2021
- 3 Existing Traffic 2031
- 4 Site 1 Development Traffic
- 5 Site 2 Development Traffic
- 6 Site 3 Development Traffic
- 7 Site 4 Development Traffic
- 8 Site 5 Development Traffic
- 9 Site 6 Development Traffic
- 10 Site 7 Development Traffic
- 11 Total Other Development Traffic
- 12 Rockbrook Office Development Traffic (%)
- 13 Rockbrook Office Development Traffic
- 14 Other Developments with Rockbrook Office
- 15 RB Central New Development Traffic (%)
- 16 RB Central New Development Traffic
- 17 Rerouted Residential Traffic (Existing)
- 18 Existing Rockbrook Residential & New Development Traffic
- 19 Do Nothing 2021
- 20 Do Something 2021
- 21 Do Nothing 2031
- 22 Do Something 2031


AM
PM



Job No: 118139
Job Title: Rockbrook

Existing Traffic 2016 - Figure 1


AM
PM



Job No: 118139
Job Title: Rockbrook

Existing Traffic 2021 - Figure 2


AM
PM



Job No: 118139
Job Title: Rockbrook

Existing Traffic 2031 - Figure 3


AM
PM



Job No: 118139
Job Title: Rockbrook

Site 1 Development Traffic - Figure 4


AM
PM



Job No: 118139
Job Title: Rockbrook

Site 2 Development Traffic 2031 - Figure 5


AM
PM



Job No: 118139
Job Title: Rockbrook

Site 3 Development Traffic 2031 - Figure 6


AM
PM



Job No: 118139
Job Title: Rockbrook

Site 4 Development Traffic - Figure 7


AM
PM



Job No: 118139
Job Title: Rockbrook

Site 5 Development Traffic - Figure 8


AM
PM



Job No: 118139
Job Title: Rockbrook

Site 6 Development Traffic - Figure 9


AM
PM



Job No: 118139
Job Title: Rockbrook

Site 7 Development Traffic - Figure 10


AM
PM



Job No: 118139
Job Title: Rockbrook

Total Other Development Traffic - Figure 11


AM
PM



Job No: 118139
Job Title: Rockbrook

Rockbrook Office Development Traffic (%) - Figure 12


	in	out
AM	297	45
PM	42	263



Job No: 118139
 Job Title: Rockbrook

Rockbrook Office Development Traffic - Figure 13


AM
PM



Job No: 118139
Job Title: Rockbrook


Rockbrook new Residential Development Traffic (%) - Figure 15

	in	out
AM	21	59
PM	39	18



Job No: 118139
 Job Title: Rockbrook


Rockbrook New Development Traffic - Figure 16



Job No: 118139
Job Title: Rockbrook

Rerouted Residential Traffic (Existing) Figure 17


AM
PM



Job No: 118139
Job Title: Rockbrook

Existing Rockbrook Residential & New Development Traffic
Figure 18


AM
PM



Job No: 118139
Job Title: Rockbrook

Do Nothing 2021 - Figure 19


AM
PM



Job No: 118139
Job Title: Rockbrook

Do Something 2021 - Figure 20


AM
PM



Job No: 118139
Job Title: Rockbrook

Do Nothing 2031 - Figure 21

AM
PM



Job No: 118139
Job Title: Rockbrook

Do Something 2031 - Figure 22

APPENDIX C


JUNCTION ANALYSIS OUTPUTS

Full Input Data And Results
Full Input Data And Results


User and Project Details

Project:	118139 Rockbrook
Title:	Rockbrook
Location:	
File name:	118139 Blackthorn Dr_Carmanhall Rd Junction 2018 10 11.lsg3x
Author:	J Noone
Company:	CST Group
Address:	1 O'Connell Street, Sligo
Notes:	

Network Layout Diagram



Phase Diagram



Phase Input Data


Phase Name	Phase type	Assoc Phase	Street Min	Cont Min
A	Traffic		7	7
B	Traffic		7	7
C	Traffic		7	7
D	Ind. Arrow	C	4	4
E	Traffic		7	7
F	Traffic		7	7
G	Pedestrian		10	10
H	Pedestrian		10	10
I	Pedestrian		10	10
J	Pedestrian		10	10

Full Input Data And Results

Phase Intergreens Matrix

Terminating Phase	Starting Phase										
	A	B	C	D	E	F	G	H	I	J	
A	-	5	5	-	5	5	-	5	5		
B	-	-	-	-	-	-	-	5	-	-	
C	5	-	-	5	-	5	-	5	5		
D	5	-	-	5	-	5	-	5	5		
E	-	-	5	5	-	5	5	-	5	5	
F	5	-	-	5	-	5	-	5	5		
G	11	-	11	11	11	11	-	-	-		
H	-	7	-	-	-	-	-	-	-		
I	9	-	9	9	9	9	-	-	-		
J	15	-	15	15	15	15	-	-	-		

Stage Diagram



Traffic Flow Groups

Flow Group	Start Time	End Time	Duration	Formula
1: '2016 AM Do Nothing - Existing Flows'	08:00	09:00	01:00	
2: '2021 AM Do Nothing - Existing Flows + Permitted Dev'	08:00	09:00	01:00	
3: '2021 AM Do Something - Existing Flows+Permitted Dev+New Dev'	08:00	09:00	01:00	
4: '2031 AM Do Nothing - Existing Flows + Permitted Dev'	08:00	09:00	01:00	
5: '2031 AM Do Something - Existing Flows+Permitted Dev+New Dev'	08:00	09:00	01:00	
6: '2016 PM Do Nothing - Existing Flows'	17:00	18:00	01:00	
7: '2021 PM Do Nothing - Existing Flows + Permitted Dev'	17:00	18:00	01:00	
8: '2021 PM Do Something - Existing Flows+Permitted Dev+New Dev'	17:00	18:00	01:00	
9: '2031 PM Do Nothing - Existing Flows + Permitted Dev'	17:00	18:00	01:00	
10: '2031 PM Do Something - Existing Flows+Permitted Dev+New Dev'	17:00	18:00	01:00	

Full Input Data And Results

Scenario 1: '2016 AM Existing Flows' (FG1: '2016 AM Do Nothing - Existing Flows', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

		Destination				
		A	B	C	D	Tot.
Origin	A	0	84	60	62	206
	B	332	0	120	444	896
	C	18	30	0	18	66
	D	178	216	76	0	470
	Tot.	528	330	256	524	1638

Full Input Data And Results

Traffic Lane Flows

Junction: Blackthorn Drive_Carmanhall Rd Junction							
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat flow (PCU/Hr)
1/1 (Carmanhall Rd)	2.65	0.00	Y	Arm 6 Left	12.00	100.0 %	1671
1/2 (Carmanhall Rd)	3.15	0.00	Y	Arm 7 Ahead	Inf	49.2 %	1815
				Arm 8 Right	12.00	50.8 %	
2/1 (Blackthorn Drive South)	3.00	0.00	Y	Arm 7 Left	9.00	30.4 %	1823
				Arm 8 Ahead	Inf	69.6 %	
2/2 (Blackthorn Drive South)	3.00	0.00	N	Arm 8 Ahead	Inf	100.0 %	2055
2/3 (Blackthorn Drive South)	3.00	0.00	N	Arm 5 Right	12.00	100.0 %	1827
3/1 (Birch Avenue)	3.25	0.00	Y	Arm 5 Ahead	Inf	27.3 %	1760
				Arm 6 Right	12.00	45.5 %	
				Arm 8 Left	9.00	27.3 %	
4/1 (Blackthorn Drive North)	3.00	0.00	Y	Arm 5 Left	9.00	82.8 %	1683
				Arm 6 Ahead	Inf	17.2 %	
4/2 (Blackthorn Drive North)	3.00	0.00	N	Arm 6 Ahead	Inf	100.0 %	2055
4/3 (Blackthorn Drive North)	3.00	0.00	N	Arm 7 Right	12.00	100.0 %	1827
5/1 (Carmanhall Rd Lane 1)	Infinite Saturation Flow						Inf
6/1 (Blackthorn Dr South Lane 1)	Infinite Saturation Flow						Inf
6/2 (Blackthorn Dr South Lane 2)	Infinite Saturation Flow						Inf
7/1 (Birch Avenue Lane 1)	Infinite Saturation Flow						Inf
8/1 (Blackthorn Dr North Lane 1)	Infinite Saturation Flow						Inf
8/2 (Blackthorn Dr North Lane 2)	Infinite Saturation Flow						Inf

Scenario 2: '2021 AM Do Nothing' (FG2: '2021 AM Do Nothing - Existing Flows + Permitted Dev', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
		A	B	C	D	Tot.
Origin	A	0	146	64	94	304
	B	488	0	128	475	1091
	C	19	32	0	19	70
	D	268	231	81	0	580
	Tot.	775	409	273	588	2045

Full Input Data And Results

Traffic Lane Flows

Junction: Blackthorn Drive_Carmanhall Rd Junction							
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat flow (PCU/Hr)
1/1 (Carmanhall Rd)	2.65	0.00	Y	Arm 6 Left	12.00	100.0 %	1671
1/2 (Carmanhall Rd)	3.15	0.00	Y	Arm 7 Ahead	Inf	40.5 %	1796
				Arm 8 Right	12.00	59.5 %	
2/1 (Blackthorn Drive South)	3.00	0.00	Y	Arm 7 Left	9.00	21.4 %	1849
				Arm 8 Ahead	Inf	78.6 %	
2/2 (Blackthorn Drive South)	3.00	0.00	N	Arm 8 Ahead	Inf	100.0 %	2055
2/3 (Blackthorn Drive South)	3.00	0.00	N	Arm 5 Right	12.00	100.0 %	1827
3/1 (Birch Avenue)	3.25	0.00	Y	Arm 5 Ahead	Inf	27.1 %	1760
				Arm 6 Right	12.00	45.7 %	
				Arm 8 Left	9.00	27.1 %	
4/1 (Blackthorn Drive North)	3.00	0.00	Y	Arm 5 Left	9.00	93.4 %	1657
				Arm 6 Ahead	Inf	6.6 %	
4/2 (Blackthorn Drive North)	3.00	0.00	N	Arm 6 Ahead	Inf	100.0 %	2055
4/3 (Blackthorn Drive North)	3.00	0.00	N	Arm 7 Right	12.00	100.0 %	1827
5/1 (Carmanhall Rd Lane 1)	Infinite Saturation Flow						Inf
6/1 (Blackthorn Dr South Lane 1)	Infinite Saturation Flow						Inf
6/2 (Blackthorn Dr South Lane 2)	Infinite Saturation Flow						Inf
7/1 (Birch Avenue Lane 1)	Infinite Saturation Flow						Inf
8/1 (Blackthorn Dr North Lane 1)	Infinite Saturation Flow						Inf
8/2 (Blackthorn Dr North Lane 2)	Infinite Saturation Flow						Inf

Scenario 3: '2021 AM Do Something' (FG3: '2021 AM Do Something - Existing Flows+Permitted Dev+New Dev', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
		A	B	C	D	Tot.
Origin	A	0	196	64	125	385
	B	497	0	128	484	1109
	C	19	32	0	19	70
	D	280	206	81	0	567
	Tot.	796	434	273	628	2131

Full Input Data And Results

Traffic Lane Flows

Junction: Blackthorn Drive_Carmanhall Rd Junction							
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat flow (PCU/Hr)
1/1 (Carmanhall Rd)	2.65	0.00	Y	Arm 6 Left	12.00	100.0 %	1671
1/2 (Carmanhall Rd)	3.15	0.00	Y	Arm 7 Ahead	Inf	33.9 %	1783
				Arm 8 Right	12.00	66.1 %	
2/1 (Blackthorn Drive South)	3.00	0.00	Y	Arm 7 Left	9.00	21.1 %	1850
				Arm 8 Ahead	Inf	78.9 %	
2/2 (Blackthorn Drive South)	3.00	0.00	N	Arm 8 Ahead	Inf	100.0 %	2055
2/3 (Blackthorn Drive South)	3.00	0.00	N	Arm 5 Right	12.00	100.0 %	1827
3/1 (Birch Avenue)	3.25	0.00	Y	Arm 5 Ahead	Inf	27.1 %	1760
				Arm 6 Right	12.00	45.7 %	
				Arm 8 Left	9.00	27.1 %	
4/1 (Blackthorn Drive North)	3.00	0.00	Y	Arm 5 Left	9.00	94.6 %	1654
				Arm 6 Ahead	Inf	5.4 %	
4/2 (Blackthorn Drive North)	3.00	0.00	N	Arm 6 Ahead	Inf	100.0 %	2055
4/3 (Blackthorn Drive North)	3.00	0.00	N	Arm 7 Right	12.00	100.0 %	1827
5/1 (Carmanhall Rd Lane 1)	Infinite Saturation Flow						Inf
6/1 (Blackthorn Dr South Lane 1)	Infinite Saturation Flow						Inf
6/2 (Blackthorn Dr South Lane 2)	Infinite Saturation Flow						Inf
7/1 (Birch Avenue Lane 1)	Infinite Saturation Flow						Inf
8/1 (Blackthorn Dr North Lane 1)	Infinite Saturation Flow						Inf
8/2 (Blackthorn Dr North Lane 2)	Infinite Saturation Flow						Inf

Scenario 4: '2031 AM Do Nothing' (FG4: '2031 AM Do Nothing - Existing Flows + Permitted Dev', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
		A	B	C	D	Tot.
Origin	A	0	158	73	102	333
	B	534	0	145	537	1216
	C	22	36	0	22	80
	D	294	261	92	0	647
	Tot.	850	455	310	661	2276

Full Input Data And Results

Traffic Lane Flows

Junction: Blackthorn Drive_Carmanhall Rd Junction							
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat flow (PCU/Hr)
1/1 (Carmanhall Rd)	2.65	0.00	Y	Arm 6 Left	12.00	100.0 %	1671
1/2 (Carmanhall Rd)	3.15	0.00	Y	Arm 7 Ahead	Inf	41.7 %	1799
				Arm 8 Right	12.00	58.3 %	
2/1 (Blackthorn Drive South)	3.00	0.00	Y	Arm 7 Left	9.00	21.4 %	1849
				Arm 8 Ahead	Inf	78.6 %	
2/2 (Blackthorn Drive South)	3.00	0.00	N	Arm 8 Ahead	Inf	100.0 %	2055
2/3 (Blackthorn Drive South)	3.00	0.00	N	Arm 5 Right	12.00	100.0 %	1827
3/1 (Birch Avenue)	3.25	0.00	Y	Arm 5 Ahead	Inf	27.5 %	1760
				Arm 6 Right	12.00	45.0 %	
				Arm 8 Left	9.00	27.5 %	
4/1 (Blackthorn Drive North)	3.00	0.00	Y	Arm 5 Left	9.00	92.7 %	1659
				Arm 6 Ahead	Inf	7.3 %	
4/2 (Blackthorn Drive North)	3.00	0.00	N	Arm 6 Ahead	Inf	100.0 %	2055
4/3 (Blackthorn Drive North)	3.00	0.00	N	Arm 7 Right	12.00	100.0 %	1827
5/1 (Carmanhall Rd Lane 1)	Infinite Saturation Flow						Inf
6/1 (Blackthorn Dr South Lane 1)	Infinite Saturation Flow						Inf
6/2 (Blackthorn Dr South Lane 2)	Infinite Saturation Flow						Inf
7/1 (Birch Avenue Lane 1)	Infinite Saturation Flow						Inf
8/1 (Blackthorn Dr North Lane 1)	Infinite Saturation Flow						Inf
8/2 (Blackthorn Dr North Lane 2)	Infinite Saturation Flow						Inf

Scenario 5: '2031 AM Do Something' (FG5: '2031 AM Do Something - Existing Flows+Permitted Dev+New Dev', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
		A	B	C	D	Tot.
Origin	A	0	208	73	134	415
	B	544	0	145	547	1236
	C	22	36	0	22	80
	D	305	236	92	0	633
	Tot.	871	480	310	703	2364

Full Input Data And Results

Traffic Lane Flows

Junction: Blackthorn Drive_Carmanhall Rd Junction							
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat flow (PCU/Hr)
1/1 (Carmanhall Rd)	2.65	0.00	Y	Arm 6 Left	12.00	100.0 %	1671
1/2 (Carmanhall Rd)	3.15	0.00	Y	Arm 7 Ahead	Inf	35.3 %	1786
				Arm 8 Right	12.00	64.7 %	
2/1 (Blackthorn Drive South)	3.00	0.00	Y	Arm 7 Left	9.00	21.1 %	1850
				Arm 8 Ahead	Inf	78.9 %	
2/2 (Blackthorn Drive South)	3.00	0.00	N	Arm 8 Ahead	Inf	100.0 %	2055
2/3 (Blackthorn Drive South)	3.00	0.00	N	Arm 5 Right	12.00	100.0 %	1827
3/1 (Birch Avenue)	3.25	0.00	Y	Arm 5 Ahead	Inf	27.5 %	1760
				Arm 6 Right	12.00	45.0 %	
				Arm 8 Left	9.00	27.5 %	
4/1 (Blackthorn Drive North)	3.00	0.00	Y	Arm 5 Left	9.00	93.3 %	1657
				Arm 6 Ahead	Inf	6.7 %	
4/2 (Blackthorn Drive North)	3.00	0.00	N	Arm 6 Ahead	Inf	100.0 %	2055
4/3 (Blackthorn Drive North)	3.00	0.00	N	Arm 7 Right	12.00	100.0 %	1827
5/1 (Carmanhall Rd Lane 1)	Infinite Saturation Flow						Inf
6/1 (Blackthorn Dr South Lane 1)	Infinite Saturation Flow						Inf
6/2 (Blackthorn Dr South Lane 2)	Infinite Saturation Flow						Inf
7/1 (Birch Avenue Lane 1)	Infinite Saturation Flow						Inf
8/1 (Blackthorn Dr North Lane 1)	Infinite Saturation Flow						Inf
8/2 (Blackthorn Dr North Lane 2)	Infinite Saturation Flow						Inf

Scenario 6: '2016 PM Existing Flows' (FG6: '2016 PM Do Nothing - Existing Flows', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
		A	B	C	D	Tot.
Origin	A	0	327	42	241	610
	B	114	0	29	327	470
	C	21	116	0	163	300
	D	78	171	33	0	282
	Tot.	213	614	104	731	1662

Full Input Data And Results

Traffic Lane Flows

Junction: Blackthorn Drive_Carmanhall Rd Junction							
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat flow (PCU/Hr)
1/1 (Carmanhall Rd)	2.65	0.00	Y	Arm 6 Left	12.00	100.0 %	1671
1/2 (Carmanhall Rd)	3.15	0.00	Y	Arm 7 Ahead	Inf	14.8 %	1744
				Arm 8 Right	12.00	85.2 %	
2/1 (Blackthorn Drive South)	3.00	0.00	Y	Arm 7 Left	9.00	18.1 %	1859
				Arm 8 Ahead	Inf	81.9 %	
2/2 (Blackthorn Drive South)	3.00	0.00	N	Arm 8 Ahead	Inf	100.0 %	2055
2/3 (Blackthorn Drive South)	3.00	0.00	N	Arm 5 Right	12.00	100.0 %	1827
3/1 (Birch Avenue)	3.25	0.00	Y	Arm 5 Ahead	Inf	7.0 %	1703
				Arm 6 Right	12.00	38.7 %	
				Arm 8 Left	9.00	54.3 %	
4/1 (Blackthorn Drive North)	3.00	0.00	Y	Arm 5 Left	9.00	66.1 %	1725
				Arm 6 Ahead	Inf	33.9 %	
4/2 (Blackthorn Drive North)	3.00	0.00	N	Arm 6 Ahead	Inf	100.0 %	2055
4/3 (Blackthorn Drive North)	3.00	0.00	N	Arm 7 Right	12.00	100.0 %	1827
5/1 (Carmanhall Rd Lane 1)	Infinite Saturation Flow						Inf
6/1 (Blackthorn Dr South Lane 1)	Infinite Saturation Flow						Inf
6/2 (Blackthorn Dr South Lane 2)	Infinite Saturation Flow						Inf
7/1 (Birch Avenue Lane 1)	Infinite Saturation Flow						Inf
8/1 (Blackthorn Dr North Lane 1)	Infinite Saturation Flow						Inf
8/2 (Blackthorn Dr North Lane 2)	Infinite Saturation Flow						Inf

Scenario 7: '2021 PM Do Nothing' (FG7: '2021 PM Do Nothing - Existing Flows + Permitted Dev', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
		A	B	C	D	Tot.
Origin	A	0	473	45	331	849
	B	175	0	31	350	556
	C	22	124	0	174	320
	D	109	183	35	0	327
	Tot.	306	780	111	855	2052

Full Input Data And Results

Traffic Lane Flows

Junction: Blackthorn Drive_Carmanhall Rd Junction							
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat flow (PCU/Hr)
1/1 (Carmanhall Rd)	2.65	0.00	Y	Arm 6 Left	12.00	100.0 %	1671
1/2 (Carmanhall Rd)	3.15	0.00	Y	Arm 7 Ahead	Inf	12.0 %	1739
				Arm 8 Right	12.00	88.0 %	
2/1 (Blackthorn Drive South)	3.00	0.00	Y	Arm 7 Left	9.00	14.0 %	1871
				Arm 8 Ahead	Inf	86.0 %	
2/2 (Blackthorn Drive South)	3.00	0.00	N	Arm 8 Ahead	Inf	100.0 %	2055
2/3 (Blackthorn Drive South)	3.00	0.00	N	Arm 5 Right	12.00	100.0 %	1827
3/1 (Birch Avenue)	3.25	0.00	Y	Arm 5 Ahead	Inf	6.9 %	1703
				Arm 6 Right	12.00	38.8 %	
				Arm 8 Left	9.00	54.4 %	
4/1 (Blackthorn Drive North)	3.00	0.00	Y	Arm 5 Left	9.00	80.7 %	1688
				Arm 6 Ahead	Inf	19.3 %	
4/2 (Blackthorn Drive North)	3.00	0.00	N	Arm 6 Ahead	Inf	100.0 %	2055
4/3 (Blackthorn Drive North)	3.00	0.00	N	Arm 7 Right	12.00	100.0 %	1827
5/1 (Carmanhall Rd Lane 1)	Infinite Saturation Flow						Inf
6/1 (Blackthorn Dr South Lane 1)	Infinite Saturation Flow						Inf
6/2 (Blackthorn Dr South Lane 2)	Infinite Saturation Flow						Inf
7/1 (Birch Avenue Lane 1)	Infinite Saturation Flow						Inf
8/1 (Blackthorn Dr North Lane 1)	Infinite Saturation Flow						Inf
8/2 (Blackthorn Dr North Lane 2)	Infinite Saturation Flow						Inf

Scenario 8: '2021 PM Do Something' (FG8: '2021 PM Do Something - Existing Flows+Permitted Dev+New Dev', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
		A	B	C	D	Tot.
Origin	A	0	487	45	340	872
	B	191	0	31	348	570
	C	22	124	0	174	320
	D	129	176	35	0	340
	Tot.	342	787	111	862	2102

Full Input Data And Results

Traffic Lane Flows

Junction: Blackthorn Drive_Carmanhall Rd Junction							
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat flow (PCU/Hr)
1/1 (Carmanhall Rd)	2.65	0.00	Y	Arm 6 Left	12.00	100.0 %	1671
1/2 (Carmanhall Rd)	3.15	0.00	Y	Arm 7 Ahead	Inf	11.7 %	1738
				Arm 8 Right	12.00	88.3 %	
2/1 (Blackthorn Drive South)	3.00	0.00	Y	Arm 7 Left	9.00	10.7 %	1882
				Arm 8 Ahead	Inf	89.3 %	
2/2 (Blackthorn Drive South)	3.00	0.00	N	Arm 8 Ahead	Inf	100.0 %	2055
2/3 (Blackthorn Drive South)	3.00	0.00	N	Arm 5 Right	12.00	100.0 %	1827
3/1 (Birch Avenue)	3.25	0.00	Y	Arm 5 Ahead	Inf	6.9 %	1703
				Arm 6 Right	12.00	38.8 %	
				Arm 8 Left	9.00	54.4 %	
4/1 (Blackthorn Drive North)	3.00	0.00	Y	Arm 5 Left	9.00	89.0 %	1668
				Arm 6 Ahead	Inf	11.0 %	
4/2 (Blackthorn Drive North)	3.00	0.00	N	Arm 6 Ahead	Inf	100.0 %	2055
4/3 (Blackthorn Drive North)	3.00	0.00	N	Arm 7 Right	12.00	100.0 %	1827
5/1 (Carmanhall Rd Lane 1)	Infinite Saturation Flow						Inf
6/1 (Blackthorn Dr South Lane 1)	Infinite Saturation Flow						Inf
6/2 (Blackthorn Dr South Lane 2)	Infinite Saturation Flow						Inf
7/1 (Birch Avenue Lane 1)	Infinite Saturation Flow						Inf
8/1 (Blackthorn Dr North Lane 1)	Infinite Saturation Flow						Inf
8/2 (Blackthorn Dr North Lane 2)	Infinite Saturation Flow						Inf

Scenario 9: '2031 PM Do Nothing' (FG9: '2031 PM Do Nothing - Existing Flows + Permitted Dev', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :

	Destination					
		A	B	C	D	Tot.
Origin	A	0	519	51	365	935
	B	191	0	35	395	621
	C	25	140	0	197	362
	D	120	207	40	0	367
	Tot.	336	866	126	957	2285

Full Input Data And Results

Traffic Lane Flows

Junction: Blackthorn Drive_Carmanhall Rd Junction							
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat flow (PCU/Hr)
1/1 (Carmanhall Rd)	2.65	0.00	Y	Arm 6 Left	12.00	100.0 %	1671
1/2 (Carmanhall Rd)	3.15	0.00	Y	Arm 7 Ahead	Inf	12.3 %	1739
				Arm 8 Right	12.00	87.7 %	
2/1 (Blackthorn Drive South)	3.00	0.00	Y	Arm 7 Left	9.00	8.2 %	1889
				Arm 8 Ahead	Inf	91.8 %	
2/2 (Blackthorn Drive South)	3.00	0.00	N	Arm 8 Ahead	Inf	100.0 %	2055
2/3 (Blackthorn Drive South)	3.00	0.00	N	Arm 5 Right	12.00	100.0 %	1827
3/1 (Birch Avenue)	3.25	0.00	Y	Arm 5 Ahead	Inf	6.9 %	1703
				Arm 6 Right	12.00	38.7 %	
				Arm 8 Left	9.00	54.4 %	
4/1 (Blackthorn Drive North)	3.00	0.00	Y	Arm 5 Left	9.00	38.3 %	1800
				Arm 6 Ahead	Inf	61.7 %	
4/2 (Blackthorn Drive North)	3.00	0.00	N	Arm 6 Ahead	Inf	100.0 %	2055
4/3 (Blackthorn Drive North)	3.00	0.00	N	Arm 7 Right	12.00	100.0 %	1827
5/1 (Carmanhall Rd Lane 1)	Infinite Saturation Flow						Inf
6/1 (Blackthorn Dr South Lane 1)	Infinite Saturation Flow						Inf
6/2 (Blackthorn Dr South Lane 2)	Infinite Saturation Flow						Inf
7/1 (Birch Avenue Lane 1)	Infinite Saturation Flow						Inf
8/1 (Blackthorn Dr North Lane 1)	Infinite Saturation Flow						Inf
8/2 (Blackthorn Dr North Lane 2)	Infinite Saturation Flow						Inf

Scenario 10: '2031 PM Do Something' (FG10: '2031 PM Do Something - Existing Flows+Permitted Dev+New Dev', Plan 1: 'Network Control Plan 1')

Traffic Flows, Desired

Desired Flow :


	Destination					
		A	B	C	D	Tot.
Origin	A	0	533	51	374	958
	B	207	0	35	394	636
	C	25	140	0	197	362
	D	140	200	40	0	380
	Tot.	372	873	126	965	2336

Traffic Lane Flows


Junction: Blackthorn Drive_Carmanhall Rd Junction							
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat flow (PCU/Hr)
1/1 (Carmanhall Rd)	2.65	0.00	Y	Arm 6 Left	12.00	100.0 %	1671
1/2 (Carmanhall Rd)	3.15	0.00	Y	Arm 7 Ahead	Inf	12.0 %	1739
				Arm 8 Right	12.00	88.0 %	
2/1 (Blackthorn Drive South)	3.00	0.00	Y	Arm 7 Left	9.00	8.3 %	1889
				Arm 8 Ahead	Inf	91.7 %	
2/2 (Blackthorn Drive South)	3.00	0.00	N	Arm 8 Ahead	Inf	100.0 %	2055
2/3 (Blackthorn Drive South)	3.00	0.00	N	Arm 5 Right	12.00	100.0 %	1827
3/1 (Birch Avenue)	3.25	0.00	Y	Arm 5 Ahead	Inf	6.9 %	1703
				Arm 6 Right	12.00	38.7 %	
				Arm 8 Left	9.00	54.4 %	
4/1 (Blackthorn Drive North)	3.00	0.00	Y	Arm 5 Left	9.00	67.3 %	1722
				Arm 6 Ahead	Inf	32.7 %	
4/2 (Blackthorn Drive North)	3.00	0.00	N	Arm 6 Ahead	Inf	100.0 %	2055
4/3 (Blackthorn Drive North)	3.00	0.00	N	Arm 7 Right	12.00	100.0 %	1827
5/1 (Carmanhall Rd Lane 1)	Infinite Saturation Flow						Inf
6/1 (Blackthorn Dr South Lane 1)	Infinite Saturation Flow						Inf
6/2 (Blackthorn Dr South Lane 2)	Infinite Saturation Flow						Inf
7/1 (Birch Avenue Lane 1)	Infinite Saturation Flow						Inf
8/1 (Blackthorn Dr North Lane 1)	Infinite Saturation Flow						Inf
8/2 (Blackthorn Dr North Lane 2)	Infinite Saturation Flow						Inf

Scenario 1: '2016 AM Existing Flows' (FG1: '2016 AM Do Nothing - Existing Flows', Plan 1: 'Network Control Plan 1')

Stage Sequence Diagram




Full Input Data And Results




Stage Timings

Stage	1	2	3	1	2	3	4
Duration	72	3	26	70	3	14	10
Change Point	0	87	90	118	193	196	212

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results


Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Rockbrook	-	-	-	-	-	-	-	-	-	-	-	-	52.5%
Blackthorn Drive_Carmanhall Rd Junction	-	-	-	-	-	-	-	-	-	-	-	-	52.5%
1/2+1/1	Carmanhall Rd Left Ahead Right	O	N/A	N/A	A B		2:1	40:205		206	1815:1671	392	52.5%
2/1	Blackthorn Drive South Left Ahead	U	N/A	N/A	C		2	142	-	395	1823	1156	34.2%
2/2+2/3	Blackthorn Drive South Right Ahead	U+O	N/A	N/A	C	- D	2	142		501	2055:1827	954	52.5%
3/1	Birch Avenue Ahead Right Left	O	N/A	N/A	E		2	40	-	66	1760	326	20.3%
4/1	Blackthorn Drive North Left Ahead	U	N/A	N/A	F		2	142	-	215	1683	1068	20.1%
4/2+4/3	Blackthorn Drive North Ahead Right	U+O	N/A	N/A	F		2	142		255	2055:1827	1336	19.1%
5/1	Carmanhall Rd	U	N/A	N/A	-		-	-	-	528	1	Inf	0.0%
6/1	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	121	1	Inf	0.0%
6/2	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	209	1	Inf	0.0%
7/1	Birch Avenue	U	N/A	N/A	-		-	-	-	256	1	Inf	0.0%
8/1	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	293	1	Inf	0.0%
8/2	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	231	1	Inf	0.0%

Full Input Data And Results

Scenario 2: '2021 AM Do Nothing' (FG2: '2021 AM Do Nothing - Existing Flows + Permitted Dev', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3	1	2	3	4
Duration	70	3	16	77	3	19	10
Change Point	0	85	88	106	188	191	212

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results


Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Rockbrook	-	-	-	-	-	-	-	-	-	-	-	-	85.5%
Blackthorn Drive_Carmanhall Rd Junction	-	-	-	-	-	-	-	-	-	-	-	-	85.5%
1/2+1/1	Carmanhall Rd Left Ahead Right	O	N/A	N/A	A B		2:1	35:205		304	1796:1671	367	82.8%
2/1	Blackthorn Drive South Left Ahead	U	N/A	N/A	C		2	147	-	597	1849	1214	49.2%
2/2+2/3	Blackthorn Drive South Right Ahead	U+O	N/A	N/A	C	- D	2	147		494	2055:1827	577	85.5%
3/1	Birch Avenue Ahead Right Left	O	N/A	N/A	E		2	35	-	70	1760	287	24.4%
4/1	Blackthorn Drive North Left Ahead	U	N/A	N/A	F		2	147	-	287	1657	1088	26.4%
4/2+4/3	Blackthorn Drive North Ahead Right	U+O	N/A	N/A	F		2	147		293	2055:1827	1374	21.3%
5/1	Carmanhall Rd	U	N/A	N/A	-		-	-	-	775	1	Inf	0.0%
6/1	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	165	1	Inf	0.0%
6/2	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	244	1	Inf	0.0%
7/1	Birch Avenue	U	N/A	N/A	-		-	-	-	273	1	Inf	0.0%
8/1	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	488	1	Inf	0.0%
8/2	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	100	1	Inf	0.0%

Full Input Data And Results

Scenario 3: '2021 AM Do Something' (FG3: '2021 AM Do Something - Existing Flows+Permitted Dev+New Dev', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3	1	2	3	4
Duration	70	3	23	73	3	16	10
Change Point	0	85	88	113	191	194	212

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results


Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Rockbrook	-	-	-	-	-	-	-	-	-	-	-	-	89.3%
Blackthorn Drive_Carmanhall Rd Junction	-	-	-	-	-	-	-	-	-	-	-	-	89.3%
1/2+1/1	Carmanhall Rd Left Ahead Right	O	N/A	N/A	A B		2:1	39:205		385	1783:1671	435	88.5%
2/1	Blackthorn Drive South Left Ahead	U	N/A	N/A	C		2	143	-	607	1850	1182	51.4%
2/2+2/3	Blackthorn Drive South Right Ahead	U+O	N/A	N/A	C	- D	2	143		502	2055:1827	562	89.3%
3/1	Birch Avenue Ahead Right Left	O	N/A	N/A	E		2	39	-	70	1760	318	22.0%
4/1	Blackthorn Drive North Left Ahead	U	N/A	N/A	F		2	143	-	296	1654	1057	28.0%
4/2+4/3	Blackthorn Drive North Ahead Right	U+O	N/A	N/A	F		2	143		271	2055:1827	1345	20.2%
5/1	Carmanhall Rd	U	N/A	N/A	-		-	-	-	796	1	Inf	0.0%
6/1	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	212	1	Inf	0.0%
6/2	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	222	1	Inf	0.0%
7/1	Birch Avenue	U	N/A	N/A	-		-	-	-	273	1	Inf	0.0%
8/1	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	498	1	Inf	0.0%
8/2	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	130	1	Inf	0.0%

Full Input Data And Results

Scenario 4: '2031 AM Do Nothing' (FG4: '2031 AM Do Nothing - Existing Flows + Permitted Dev', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3	1	2	3	4
Duration	81	3	17	67	3	17	10
Change Point	0	96	99	118	190	193	212

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results


Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Rockbrook	-	-	-	-	-	-	-	-	-	-	-	-	100.2%
Blackthorn Drive_Carmanhall Rd Junction	-	-	-	-	-	-	-	-	-	-	-	-	100.2%
1/2+1/1	Carmanhall Rd Left Ahead Right	O	N/A	N/A	A B		2:1	34:205		333	1799:1671	340	98.0%
2/1	Blackthorn Drive South Left Ahead	U	N/A	N/A	C		2	148	-	677	1849	1222	55.4%
2/2+2/3	Blackthorn Drive South Right Ahead	U+O	N/A	N/A	C	- D	2	148		539	2055:1827	538	100.2%
3/1	Birch Avenue Ahead Right Left	O	N/A	N/A	E		2	34	-	80	1760	279	28.7%
4/1	Blackthorn Drive North Left Ahead	U	N/A	N/A	F		2	148	-	317	1659	1096	28.9%
4/2+4/3	Blackthorn Drive North Ahead Right	U+O	N/A	N/A	F		2	148		330	2055:1827	1339	24.6%
5/1	Carmanhall Rd	U	N/A	N/A	-		-	-	-	850	1	Inf	0.0%
6/1	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	181	1	Inf	0.0%
6/2	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	274	1	Inf	0.0%
7/1	Birch Avenue	U	N/A	N/A	-		-	-	-	310	1	Inf	0.0%
8/1	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	554	1	Inf	0.0%
8/2	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	107	1	Inf	0.0%

Full Input Data And Results

Scenario 5: '2031 AM Do Something' (FG5: '2031 AM Do Something - Existing Flows+Permitted Dev+New Dev', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3	1	2	3	4
Duration	78	3	15	66	3	23	10
Change Point	0	93	96	113	184	187	212

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Rockbrook	-	-	-	-	-	-	-	-	-	-	-	-	104.5%
Blackthorn Drive_Carmanhall Rd Junction	-	-	-	-	-	-	-	-	-	-	-	-	104.5%
1/2+1/1	Carmanhall Rd Left Ahead Right	O	N/A	N/A	A B		2:1	38:205		415	1786:1671	404	102.7%
2/1	Blackthorn Drive South Left Ahead	U	N/A	N/A	C		2	144	-	687	1850	1190	57.7%
2/2+2/3	Blackthorn Drive South Right Ahead	U+O	N/A	N/A	C	- D	2	144		549	2055:1827	525	104.5%
3/1	Birch Avenue Ahead Right Left	O	N/A	N/A	E		2	38	-	80	1760	310	25.8%
4/1	Blackthorn Drive North Left Ahead	U	N/A	N/A	F		2	144	-	327	1657	1066	30.7%
4/2+4/3	Blackthorn Drive North Ahead Right	U+O	N/A	N/A	F		2	144		306	2055:1827	1149	26.6%
5/1	Carmanhall Rd	U	N/A	N/A	-		-	-	-	871	1	Inf	0.0%
6/1	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	230	1	Inf	0.0%
6/2	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	250	1	Inf	0.0%
7/1	Birch Avenue	U	N/A	N/A	-		-	-	-	310	1	Inf	0.0%
8/1	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	564	1	Inf	0.0%
8/2	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	139	1	Inf	0.0%


Full Input Data And Results

Item	Entering (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per Veh (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network: Rockbrook	-	-	894	31	56	17.3	33.7	1.4	52.4	-	-	-	-
Blackthorn Drive_Carmanhall Rd Junction	-	-	894	31	56	17.3	33.7	1.4	52.4	-	-	-	-
1/2+1/1	415	404	294	31	8	5.0	13.3	0.0	18.4	159.2	12.3	13.3	25.6
2/1	687	687	-	-	-	2.6	0.7	-	3.2	17.0	17.2	0.7	17.9
2/2+2/3	549	525	472	0	48	7.1	19.1	1.0	27.2	178.2	22.0	19.1	41.2
3/1	80	80	36	0	0	0.9	0.2	0.0	1.1	49.8	2.6	0.2	2.8
4/1	327	327	-	-	-	1.0	0.2	-	1.2	12.9	6.4	0.2	6.7
4/2+4/3	306	306	92	0	0	0.8	0.2	0.4	1.4	16.2	3.7	0.2	3.9
5/1	847	847	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/1	225	225	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/2	250	250	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
7/1	308	308	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	564	564	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/2	135	135	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
C1			PRC for Signalled Lanes (%):	-16.2	Total Delay for Signalled Lanes (pcuHr):	52.42	PRC Over All Lanes (%):	-16.2	Total Delay Over All Lanes(pcuHr):	52.42	Cycle Time (s):	227	

Full Input Data And Results

Scenario 6: '2016 PM Existing Flows' (FG6: '2016 PM Do Nothing - Existing Flows', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3	1	2	3	4
Duration	15	3	77	37	3	53	10
Change Point	0	30	33	112	154	157	212

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Rockbrook	-	-	-	-	-	-	-	-	-	-	-	-	51.4%
Blackthorn Drive_Carmanhall Rd Junction	-	-	-	-	-	-	-	-	-	-	-	-	51.4%
1/2+1/1	Carmanhall Rd Left Ahead Right	O	N/A	N/A	A B		2:1	130:205		610	1744:1671	1187	51.4%
2/1	Blackthorn Drive South Left Ahead	U	N/A	N/A	C		2	52	-	160	1859	442	36.2%
2/2+2/3	Blackthorn Drive South Right Ahead	U+O	N/A	N/A	C	- D	2	52		310	2055:1827	611	50.8%
3/1	Birch Avenue Ahead Right Left	O	N/A	N/A	E		2	130	-	300	1703	990	30.3%
4/1	Blackthorn Drive North Left Ahead	U	N/A	N/A	F		2	52	-	118	1725	410	28.8%
4/2+4/3	Blackthorn Drive North Ahead Right	U+O	N/A	N/A	F		2	52		164	2055:1827	521	31.5%
5/1	Carmanhall Rd	U	N/A	N/A	-		-	-	-	213	1	Inf	0.0%
6/1	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	367	1	Inf	0.0%
6/2	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	247	1	Inf	0.0%
7/1	Birch Avenue	U	N/A	N/A	-		-	-	-	104	1	Inf	0.0%
8/1	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	294	1	Inf	0.0%
8/2	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	437	1	Inf	0.0%


Full Input Data And Results

Item	Entering (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per Veh (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network: Rockbrook	-	-	780	45	6	10.0	2.0	0.3	12.3	-	-	-	-
Blackthorn Drive_Carmanhall Rd Junction	-	-	780	45	6	10.0	2.0	0.3	12.3	-	-	-	-
1/2+1/1	610	610	520	45	3	1.5	0.5	0.0	2.1	12.3	5.9	0.5	6.4
2/1	160	160	-	-	-	1.6	0.3	-	1.9	42.4	4.2	0.3	4.5
2/2+2/3	310	310	111	0	3	3.2	0.5	0.2	3.8	44.5	5.2	0.5	5.7
3/1	300	300	116	0	0	1.0	0.2	0.0	1.2	14.7	4.9	0.2	5.1
4/1	118	118	-	-	-	1.2	0.2	-	1.4	41.5	3.0	0.2	3.2
4/2+4/3	164	164	33	0	0	1.6	0.2	0.1	1.9	41.6	3.3	0.2	3.6
5/1	213	213	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/1	367	367	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/2	247	247	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
7/1	104	104	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	294	294	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/2	437	437	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
C1			PRC for Signalled Lanes (%):		75.1	Total Delay for Signalled Lanes (pcuHr):		12.28					
			PRC Over All Lanes (%):		75.1	Total Delay Over All Lanes(pcuHr):		12.28	Cycle Time (s): 227				

Full Input Data And Results

Scenario 7: '2021 PM Do Nothing' (FG7: '2021 PM Do Nothing - Existing Flows + Permitted Dev', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3	1	2	3	4
Duration	16	3	83	38	3	45	10
Change Point	0	31	34	119	162	165	212

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Rockbrook	-	-	-	-	-	-	-	-	-	-	-	-	71.7%
Blackthorn Drive_Carmanhall Rd Junction	-	-	-	-	-	-	-	-	-	-	-	-	71.7%
1/2+1/1	Carmanhall Rd Left Ahead Right	O	N/A	N/A	A B		2:1	128:205		849	1739:1671	1184	71.7%
2/1	Blackthorn Drive South Left Ahead	U	N/A	N/A	C		2	54	-	222	1871	462	48.1%
2/2+2/3	Blackthorn Drive South Right Ahead	U+O	N/A	N/A	C	- D	2	54		334	2055:1827	470	71.1%
3/1	Birch Avenue Ahead Right Left	O	N/A	N/A	E		2	128	-	320	1703	975	32.8%
4/1	Blackthorn Drive North Left Ahead	U	N/A	N/A	F		2	54	-	135	1688	416	32.4%
4/2+4/3	Blackthorn Drive North Ahead Right	U+O	N/A	N/A	F		2	54		192	2055:1827	534	36.0%
5/1	Carmanhall Rd	U	N/A	N/A	-		-	-	-	306	1	Inf	0.0%
6/1	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	499	1	Inf	0.0%
6/2	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	281	1	Inf	0.0%
7/1	Birch Avenue	U	N/A	N/A	-		-	-	-	111	1	Inf	0.0%
8/1	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	365	1	Inf	0.0%
8/2	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	490	1	Inf	0.0%


Full Input Data And Results

Item	Entering (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per Veh (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network: Rockbrook	-	-	1059	53	26	12.6	3.7	0.5	16.8	-	-	-	-
Blackthorn Drive_Carmanhall Rd Junction	-	-	1059	53	26	12.6	3.7	0.5	16.8	-	-	-	-
1/2+1/1	849	849	747	53	4	2.4	1.3	0.1	3.8	16.2	9.5	1.3	10.8
2/1	222	222	-	-	-	2.3	0.5	-	2.7	44.2	6.4	0.5	6.9
2/2+2/3	334	334	153	0	22	3.6	1.2	0.3	5.0	54.4	5.7	1.2	6.9
3/1	320	320	124	0	0	1.1	0.2	0.0	1.4	15.5	5.4	0.2	5.7
4/1	135	135	-	-	-	1.3	0.2	-	1.6	41.6	3.7	0.2	4.0
4/2+4/3	192	192	35	0	0	1.9	0.3	0.1	2.2	41.9	4.3	0.3	4.6
5/1	306	306	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/1	499	499	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/2	281	281	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
7/1	111	111	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	365	365	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/2	490	490	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
C1			PRC for Signalled Lanes (%):	25.6	Total Delay for Signalled Lanes (pcuHr):			16.77					
			PRC Over All Lanes (%):	25.6	Total Delay Over All Lanes(pcuHr):			16.77	Cycle Time (s): 227				

Full Input Data And Results

Scenario 8: '2021 PM Do Something' (FG8: '2021 PM Do Something - Existing Flows+Permitted Dev+New Dev', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3	1	2	3	4
Duration	8	3	68	48	3	58	10
Change Point	0	23	26	96	149	152	212

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Rockbrook	-	-	-	-	-	-	-	-	-	-	-	-	74.7%
Blackthorn Drive_Carmanhall Rd Junction	-	-	-	-	-	-	-	-	-	-	-	-	74.7%
1/2+1/1	Carmanhall Rd Left Ahead Right	O	N/A	N/A	A B		2:1	126:205		872	1738:1671	1167	74.7%
2/1	Blackthorn Drive South Left Ahead	U	N/A	N/A	C		2	56	-	291	1882	481	60.5%
2/2+2/3	Blackthorn Drive South Right Ahead	U+O	N/A	N/A	C	- D	2	56		279	2055:1827	374	74.6%
3/1	Birch Avenue Ahead Right Left	O	N/A	N/A	E		2	126	-	320	1703	960	33.3%
4/1	Blackthorn Drive North Left Ahead	U	N/A	N/A	F		2	56	-	145	1668	426	34.0%
4/2+4/3	Blackthorn Drive North Ahead Right	U+O	N/A	N/A	F		2	56		195	2055:1827	552	35.3%
5/1	Carmanhall Rd	U	N/A	N/A	-		-	-	-	342	1	Inf	0.0%
6/1	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	503	1	Inf	0.0%
6/2	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	284	1	Inf	0.0%
7/1	Birch Avenue	U	N/A	N/A	-		-	-	-	111	1	Inf	0.0%
8/1	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	434	1	Inf	0.0%
8/2	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	428	1	Inf	0.0%


Full Input Data And Results

Item	Entering (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per Veh (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network: Rockbrook	-	-	1062	63	52	16.0	4.4	0.6	21.0	-	-	-	-
Blackthorn Drive_Carmanhall Rd Junction	-	-	1062	63	52	16.0	4.4	0.6	21.0	-	-	-	-
1/2+1/1	872	872	760	63	4	2.8	1.5	0.2	4.4	18.3	14.2	1.5	15.7
2/1	291	291	-	-	-	4.4	0.8	-	5.2	64.1	11.4	0.8	12.1
2/2+2/3	279	279	159	0	32	4.4	1.4	0.3	6.1	78.4	9.1	1.4	10.6
3/1	320	320	124	0	0	1.2	0.2	0.0	1.5	16.4	6.2	0.2	6.5
4/1	145	145	-	-	-	1.4	0.3	-	1.7	41.1	4.0	0.3	4.3
4/2+4/3	195	195	19	0	16	1.8	0.3	0.1	2.2	41.4	4.4	0.3	4.7
5/1	342	342	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/1	503	503	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/2	284	284	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
7/1	111	111	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	434	434	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/2	428	428	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
C1			PRC for Signalled Lanes (%):	20.5	Total Delay for Signalled Lanes (pcuHr):			21.04					
			PRC Over All Lanes (%):	20.5	Total Delay Over All Lanes(pcuHr):			21.04	Cycle Time (s): 227				

Full Input Data And Results

Scenario 9: '2031 PM Do Nothing' (FG9: '2031 PM Do Nothing - Existing Flows + Permitted Dev', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3	1	2	3	4
Duration	49	3	76	17	3	40	10
Change Point	0	64	67	145	167	170	212

Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results


Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Rockbrook	-	-	-	-	-	-	-	-	-	-	-	-	88.9%
Blackthorn Drive_Carmanhall Rd Junction	-	-	-	-	-	-	-	-	-	-	-	-	88.9%
1/2+1/1	Carmanhall Rd Left Ahead Right	O	N/A	N/A	A B		2:1	116:205		935	1739:1671	1052	88.9%
2/1	Blackthorn Drive South Left Ahead	U	N/A	N/A	C		2	66	-	426	1889	566	75.3%
2/2+2/3	Blackthorn Drive South Right Ahead	U+O	N/A	N/A	C	- D	2	66		195	2055:1827	221	88.1%
3/1	Birch Avenue Ahead Right Left	O	N/A	N/A	E		2	116	-	362	1703	885	40.9%
4/1	Blackthorn Drive North Left Ahead	U	N/A	N/A	F		2	66	-	313	1800	539	58.0%
4/2+4/3	Blackthorn Drive North Ahead Right	U+O	N/A	N/A	F		2	66		54	2055:1827	198	27.2%
5/1	Carmanhall Rd	U	N/A	N/A	-		-	-	-	336	1	Inf	0.0%
6/1	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	712	1	Inf	0.0%
6/2	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	154	1	Inf	0.0%
7/1	Birch Avenue	U	N/A	N/A	-		-	-	-	126	1	Inf	0.0%
8/1	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	588	1	Inf	0.0%
8/2	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	369	1	Inf	0.0%

Full Input Data And Results

Scenario 10: '2031 PM Do Something' (FG10: '2031 PM Do Something - Existing Flows+Permitted Dev+New Dev', Plan 1: 'Network Control Plan 1')


Stage Sequence Diagram




Stage Timings

Stage	1	2	3	1	2	3	4
Duration	51	3	62	9	3	60	10
Change Point	0	66	69	133	147	150	212

Signal Timings Diagram




Full Input Data And Results
Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network: Rockbrook	-	-	-	-	-	-	-	-	-	-	-	-	87.4%
Blackthorn Drive_Carmanhall Rd Junction	-	-	-	-	-	-	-	-	-	-	-	-	87.4%
1/2+1/1	Carmanhall Rd Left Ahead Right	O	N/A	N/A	A B		2:1	122:205		958	1739:1671	1096	87.4%
2/1	Blackthorn Drive South Left Ahead	U	N/A	N/A	C		2	60	-	422	1889	516	81.8%
2/2+2/3	Blackthorn Drive South Right Ahead	U+O	N/A	N/A	C	- D	2	60		214	2055:1827	246	87.1%
3/1	Birch Avenue Ahead Right Left	O	N/A	N/A	E		2	122	-	362	1703	930	38.9%
4/1	Blackthorn Drive North Left Ahead	U	N/A	N/A	F		2	60	-	208	1722	470	44.2%
4/2+4/3	Blackthorn Drive North Ahead Right	U+O	N/A	N/A	F		2	60		172	2055:1827	498	34.5%
5/1	Carmanhall Rd	U	N/A	N/A	-		-	-	-	372	1	Inf	0.0%
6/1	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	601	1	Inf	0.0%
6/2	Blackthorn Dr South	U	N/A	N/A	-		-	-	-	272	1	Inf	0.0%
7/1	Birch Avenue	U	N/A	N/A	-		-	-	-	126	1	Inf	0.0%
8/1	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	584	1	Inf	0.0%
8/2	Blackthorn Dr North	U	N/A	N/A	-		-	-	-	381	1	Inf	0.0%

PICADY		
GUI Version: 5.1 AD Analysis Program Release: 4.0 (SEPT 2008)		
© Copyright TRL Limited, 2008 Adapted from PICADY/3 which is Crown Copyright by permission of the controller of HMSO		
For sales and distribution information, program advice and maintenance, contact:		
TRL Limited Crowthorne House Nine Mile Ride Wokingham, Berks. RG40 3GA, UK		Tel: +44 (0)1344 770758 Fax: +44 (0)1344 770864 E-mail: software@trl.co.uk Web: www.trlsoftware.co.uk
The user of this computer program for the solution of an engineering problem is in no way relieved of their responsibility for the correctness of the solution		

Run Analysis

Parameter	Values
File Run	I:\..\Carmanhall Rd_Development\118139 Carmanhall Rd_Development T-Junction 2018 10 11.vpi
Date Run	16 October 2018
Time Run	16:22:12
Driving Side	Drive On The Left

Arm Names and Flow Scaling Factors

Arm	Arm Name	Flow Scaling Factor (%)
Arm A	Carmanhall Rd West	100
Arm B	Development	100
Arm C	Carmanhall Rd East	100

Stream Labelling Convention

Stream A-B contains traffic going from A to B etc.

Run Information

Parameter	Values
Run Title	Carmanhall Rd/Development T-Junction
Location	Sandyford, Dublin 18
Date	11 October 2018
Enumerator	J Noone
Job Number	118139
Status	TIA
Client	IRES Residential Properties Ltd
Description	-

Geometric Data

Geometric Parameters


Parameter	Minor Arm B
Major Road Carriageway Width (m)	7.30
Major Road Kerbed Central Reserve Width (m)	0.00
Major Road Right Turning Lane Width (m)	2.20
Minor Road First Lane Width (m)	3.50
Minor Road Visibility To Right (m)	10
Minor Road Visibility To Left (m)	10
Major Road Right Turn Visibility (m)	200
Major Road Right Turn Blocks Traffic	Yes

Slope and Intercept Values

Stream	Intercept for Stream B-A	Slope for A-B	Slope for A-C	Slope for C-A	Slope for C-B
B-A	510.177	0.088	0.222	0.139	0.317
B-C	661.780	0.096	0.242	-	-
C-B	689.785	0.252	0.252	-	-

Note: Streams may be combined in which case capacity will be adjusted
 These values do not allow for any site-specific corrections

Junction Diagram



Demand Data

Modelling Periods

Parameter	Period	Duration (min)	Segment Length (min)
First Modelling Period	07:45-09:15	90	15
Second Modelling Period	16:45-18:15	90	15

ODTAB Turning Counts

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	174.0	448.0
Arm B	29.0	0.0	16.0
Arm C	281.0	104.0	0.0

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	25.0	189.0
Arm B	171.0	0.0	92.0
Arm C	601.0	15.0	0.0

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	204.0	448.0
Arm B	111.0	0.0	60.0
Arm C	281.0	120.0	0.0

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	78.0	189.0
Arm B	194.0	0.0	105.0
Arm C	601.0	43.0	0.0

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	174.0	504.0
Arm B	29.0	0.0	16.0
Arm C	310.0	104.0	0.0

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	204.0	504.0
Arm B	111.0	0.0	60.0
Arm C	310.0	120.0	0.0

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	25.0	207.0
Arm B	171.0	0.0	92.0
Arm C	677.0	15.0	0.0

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	78.0	207.0
Arm B	194.0	0.0	105.0
Arm C	677.0	43.0	0.0

ODTAB Synthesised Flows

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

Arm	Rising Time	Rising Flow (veh/min)	Peak Time	Peak Flow (veh/min)	Falling Time	Falling Flow (veh/min)
Arm A	08:00	7.775	08:30	11.663	09:00	7.775
Arm B	08:00	0.563	08:30	0.844	09:00	0.563
Arm C	08:00	4.813	08:30	7.219	09:00	4.813

Heavy Vehicles Percentages

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Queues & Delays

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	0.56	7.03	0.080	-	0.00	0.09	-	1.2	0.15
	C-AB	1.30	9.53	0.137	-	0.00	0.16	-	2.4	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.18	-	-	-	-	-	-	-	-
	A-C	5.62	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	0.67	6.59	0.102	-	0.09	0.11	-	1.6	0.17
	C-AB	1.56	9.15	0.170	-	0.16	0.22	-	3.3	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.61	-	-	-	-	-	-	-	-
	A-C	6.71	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	0.83	5.96	0.138	-	0.11	0.16	-	2.3	0.19
	C-AB	1.91	8.62	0.221	-	0.22	0.32	-	4.7	0.15
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.19	-	-	-	-	-	-	-	-
	A-C	8.22	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	0.83	5.96	0.139	-	0.16	0.16	-	2.4	0.19
	C-AB	1.91	8.62	0.221	-	0.32	0.32	-	4.8	0.15
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.19	-	-	-	-	-	-	-	-
	A-C	8.22	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	0.67	6.58	0.102	-	0.16	0.12	-	1.8	0.17
	C-AB	1.56	9.15	0.170	-	0.32	0.22	-	3.4	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.61	-	-	-	-	-	-	-	-
	A-C	6.71	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	0.56	7.03	0.080	-	0.12	0.09	-	1.4	0.15
	C-AB	1.30	9.53	0.137	-	0.22	0.17	-	2.5	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.18	-	-	-	-	-	-	-	-
	A-C	5.62	-	-	-	-	-	-	-	-

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	3.30	7.77	0.424	-	0.00	0.72	-	10.1	0.22
	C-AB	0.19	10.82	0.017	-	0.00	0.02	-	0.3	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.31	-	-	-	-	-	-	-	-
	A-C	2.37	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	3.94	7.48	0.527	-	0.72	1.07	-	15.2	0.28
	C-AB	0.22	10.69	0.021	-	0.02	0.02	-	0.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.37	-	-	-	-	-	-	-	-

	A-C	2.83	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	4.83	7.06	0.683	-	1.07	1.99	-	26.9	0.42
	C-AB	0.28	10.51	0.026	-	0.02	0.03	-	0.4	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.46	-	-	-	-	-	-	-	-
	A-C	3.47	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	4.83	7.06	0.683	-	1.99	2.07	-	30.5	0.44
	C-AB	0.28	10.51	0.026	-	0.03	0.03	-	0.4	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.46	-	-	-	-	-	-	-	-
	A-C	3.47	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	3.94	7.48	0.527	-	2.07	1.16	-	18.7	0.29
	C-AB	0.22	10.69	0.021	-	0.03	0.02	-	0.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.37	-	-	-	-	-	-	-	-
	A-C	2.83	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	3.30	7.77	0.424	-	1.16	0.76	-	11.9	0.23
	C-AB	0.19	10.82	0.017	-	0.02	0.02	-	0.3	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.31	-	-	-	-	-	-	-	-
	A-C	2.37	-	-	-	-	-	-	-	-

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	2.15	6.93	0.310	-	0.00	0.44	-	6.2	0.21
	C-AB	1.51	9.43	0.160	-	0.00	0.20	-	3.0	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.56	-	-	-	-	-	-	-	-
	A-C	5.62	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	2.56	6.47	0.396	-	0.44	0.64	-	9.1	0.25
	C-AB	1.80	9.03	0.199	-	0.20	0.27	-	4.0	0.14
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.06	-	-	-	-	-	-	-	-
	A-C	6.71	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	3.14	5.81	0.540	-	0.64	1.12	-	15.5	0.37
	C-AB	2.20	8.48	0.260	-	0.27	0.40	-	6.0	0.16
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.74	-	-	-	-	-	-	-	-
	A-C	8.22	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	3.14	5.81	0.540	-	1.12	1.14	-	17.0	0.37
	C-AB	2.20	8.48	0.260	-	0.40	0.40	-	6.1	0.16
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.74	-	-	-	-	-	-	-	-
	A-C	8.22	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	2.56	6.46	0.397	-	1.14	0.67	-	10.7	0.26
	C-AB	1.80	9.03	0.199	-	0.40	0.28	-	4.2	0.14
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.06	-	-	-	-	-	-	-	-
	A-C	6.71	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	2.15	6.93	0.310	-	0.67	0.46	-	7.2	0.21
	C-AB	1.51	9.43	0.160	-	0.28	0.20	-	3.1	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.56	-	-	-	-	-	-	-	-

	A-C	5.62	-	-	-	-	-	-	-	-
--	-----	------	---	---	---	---	---	---	---	---

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	3.75	7.62	0.492	-	0.00	0.94	-	13.0	0.25
	C-AB	0.54	10.65	0.051	-	0.00	0.05	-	0.8	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.98	-	-	-	-	-	-	-	-
	A-C	2.37	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	4.48	7.29	0.614	-	0.94	1.51	-	20.9	0.35
	C-AB	0.64	10.49	0.061	-	0.05	0.07	-	1.0	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.17	-	-	-	-	-	-	-	-
	A-C	2.83	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	5.49	6.83	0.803	-	1.51	3.39	-	43.2	0.63
	C-AB	0.79	10.26	0.077	-	0.07	0.09	-	1.3	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.43	-	-	-	-	-	-	-	-
	A-C	3.47	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	5.49	6.83	0.803	-	3.39	3.67	-	53.4	0.71
	C-AB	0.79	10.26	0.077	-	0.09	0.09	-	1.4	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.43	-	-	-	-	-	-	-	-
	A-C	3.47	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	4.48	7.29	0.614	-	3.67	1.68	-	28.3	0.39
	C-AB	0.64	10.49	0.061	-	0.09	0.07	-	1.0	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.17	-	-	-	-	-	-	-	-
	A-C	2.83	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	3.75	7.62	0.492	-	1.68	1.00	-	16.0	0.26
	C-AB	0.54	10.65	0.051	-	0.07	0.06	-	0.8	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.98	-	-	-	-	-	-	-	-
	A-C	2.37	-	-	-	-	-	-	-	-

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	0.56	6.83	0.083	-	0.00	0.09	-	1.3	0.16
	C-AB	1.30	9.35	0.140	-	0.00	0.17	-	2.5	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.18	-	-	-	-	-	-	-	-
	A-C	6.32	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	0.67	6.34	0.106	-	0.09	0.12	-	1.7	0.18
	C-AB	1.56	8.94	0.174	-	0.17	0.23	-	3.4	0.14
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.61	-	-	-	-	-	-	-	-
	A-C	7.55	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	0.83	5.65	0.146	-	0.12	0.17	-	2.4	0.21
	C-AB	1.91	8.36	0.228	-	0.23	0.34	-	5.0	0.15
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.19	-	-	-	-	-	-	-	-
	A-C	9.25	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	0.83	5.65	0.146	-	0.17	0.17	-	2.5	0.21
	C-AB	1.91	8.36	0.228	-	0.34	0.34	-	5.1	0.16
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.19	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
	A-C	9.25	-	-	-	-	-	-	-	-
08:45-09:00	B-AC	0.67	6.33	0.106	-	0.17	0.12	-	1.9	0.18
	C-AB	1.56	8.94	0.174	-	0.34	0.23	-	3.5	0.14
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.61	-	-	-	-	-	-	-	-
	A-C	7.55	-	-	-	-	-	-	-	-
09:00-09:15	B-AC	0.56	6.82	0.083	-	0.12	0.09	-	1.4	0.16
	C-AB	1.30	9.35	0.140	-	0.23	0.17	-	2.6	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.18	-	-	-	-	-	-	-	-
	A-C	6.32	-	-	-	-	-	-	-	-

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	2.15	6.72	0.319	-	0.00	0.46	-	6.5	0.22
	C-AB	1.51	9.26	0.163	-	0.00	0.21	-	3.0	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.56	-	-	-	-	-	-	-	-
	A-C	6.32	-	-	-	-	-	-	-	-
08:00-08:15	B-AC	2.56	6.21	0.412	-	0.46	0.68	-	9.7	0.27
	C-AB	1.80	8.82	0.204	-	0.21	0.28	-	4.2	0.14
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.06	-	-	-	-	-	-	-	-
	A-C	7.55	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	3.14	5.50	0.571	-	0.68	1.25	-	17.2	0.41
	C-AB	2.20	8.22	0.268	-	0.28	0.42	-	6.3	0.17
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.74	-	-	-	-	-	-	-	-
	A-C	9.25	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	3.14	5.50	0.571	-	1.25	1.29	-	19.1	0.42
	C-AB	2.20	8.22	0.268	-	0.42	0.43	-	6.5	0.17
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.74	-	-	-	-	-	-	-	-
	A-C	9.25	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	2.56	6.21	0.413	-	1.29	0.72	-	11.6	0.28
	C-AB	1.80	8.82	0.204	-	0.43	0.29	-	4.3	0.14
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.06	-	-	-	-	-	-	-	-
	A-C	7.55	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	2.15	6.72	0.319	-	0.72	0.48	-	7.5	0.22
	C-AB	1.51	9.26	0.163	-	0.29	0.21	-	3.2	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.56	-	-	-	-	-	-	-	-
	A-C	6.32	-	-	-	-	-	-	-	-

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	3.30	7.61	0.434	-	0.00	0.75	-	10.4	0.23
	C-AB	0.19	10.76	0.017	-	0.00	0.02	-	0.3	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.31	-	-	-	-	-	-	-	-
	A-C	2.60	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	3.94	7.28	0.541	-	0.75	1.13	-	16.0	0.29
	C-AB	0.22	10.62	0.021	-	0.02	0.02	-	0.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.37	-	-	-	-	-	-	-	-

	A-C	3.10	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	4.83	6.81	0.709	-	1.13	2.21	-	29.5	0.47
	C-AB	0.28	10.42	0.026	-	0.02	0.03	-	0.4	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.46	-	-	-	-	-	-	-	-
	A-C	3.80	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	4.83	6.81	0.709	-	2.21	2.31	-	34.0	0.50
	C-AB	0.28	10.42	0.026	-	0.03	0.03	-	0.4	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.46	-	-	-	-	-	-	-	-
	A-C	3.80	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	3.94	7.28	0.541	-	2.31	1.23	-	20.0	0.31
	C-AB	0.22	10.62	0.021	-	0.03	0.02	-	0.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.37	-	-	-	-	-	-	-	-
	A-C	3.10	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	3.30	7.61	0.434	-	1.23	0.79	-	12.4	0.24
	C-AB	0.19	10.76	0.017	-	0.02	0.02	-	0.3	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.31	-	-	-	-	-	-	-	-
	A-C	2.60	-	-	-	-	-	-	-	-

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	3.75	7.46	0.503	-	0.00	0.98	-	13.5	0.26
	C-AB	0.54	10.59	0.051	-	0.00	0.06	-	0.8	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.98	-	-	-	-	-	-	-	-
	A-C	2.60	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	4.48	7.09	0.632	-	0.98	1.61	-	22.3	0.37
	C-AB	0.64	10.42	0.062	-	0.06	0.07	-	1.0	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.17	-	-	-	-	-	-	-	-
	A-C	3.10	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	5.49	6.58	0.834	-	1.61	3.93	-	48.8	0.72
	C-AB	0.79	10.18	0.078	-	0.07	0.09	-	1.4	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.43	-	-	-	-	-	-	-	-
	A-C	3.80	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	5.49	6.58	0.834	-	3.93	4.35	-	62.6	0.85
	C-AB	0.79	10.18	0.078	-	0.09	0.09	-	1.4	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.43	-	-	-	-	-	-	-	-
	A-C	3.80	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	4.48	7.09	0.632	-	4.35	1.83	-	31.6	0.43
	C-AB	0.64	10.42	0.062	-	0.09	0.07	-	1.1	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.17	-	-	-	-	-	-	-	-
	A-C	3.10	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	3.75	7.46	0.503	-	1.83	1.05	-	16.8	0.28
	C-AB	0.54	10.59	0.051	-	0.07	0.06	-	0.8	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.98	-	-	-	-	-	-	-	-

	A-C	2.60	-	-	-	-	-	-	-	-
--	-----	------	---	---	---	---	---	---	---	---

Entry capacities marked with an '(X)' are dominated by a pedestrian crossing in that time segment.

In time segments marked with a '(B)', traffic leaving the junction may block back from a crossing so impairing normal operation of the junction.

Delays marked with '##' could not be calculated.

Overall Queues & Delays

Queueing Delay Information Over Whole Period

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	61.9	41.3	10.7	0.2	10.7	0.2
C-AB	143.1	95.4	21.2	0.1	21.2	0.1
C-A	-	-	-	-	-	-
A-B	239.5	159.7	-	-	-	-
A-C	616.6	411.1	-	-	-	-
All	1448.0	965.3	31.9	0.0	31.9	0.0

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	362.0	241.3	113.4	0.3	113.4	0.3
C-AB	20.6	13.8	2.0	0.1	2.0	0.1
C-A	-	-	-	-	-	-
A-B	34.4	22.9	-	-	-	-
A-C	260.1	173.4	-	-	-	-
All	1504.4	1003.0	115.4	0.1	115.4	0.1

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	235.4	156.9	65.8	0.3	65.8	0.3
C-AB	165.2	110.1	26.2	0.2	26.2	0.2
C-A	-	-	-	-	-	-
A-B	280.8	187.2	-	-	-	-
A-C	616.6	411.1	-	-	-	-
All	1684.7	1123.2	92.0	0.1	92.0	0.1

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	411.6	274.4	174.8	0.4	174.9	0.4
C-AB	59.2	39.5	6.4	0.1	6.4	0.1
C-A	-	-	-	-	-	-
A-B	107.4	71.6	-	-	-	-
A-C	260.1	173.4	-	-	-	-
All	1665.5	1110.3	181.2	0.1	181.3	0.1

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	61.9	41.3	11.3	0.2	11.3	0.2
C-AB	143.1	95.4	22.2	0.2	22.2	0.2
C-A	-	-	-	-	-	-
A-B	239.5	159.7	-	-	-	-
A-C	693.7	462.5	-	-	-	-
All	1565.0	1043.3	33.5	0.0	33.5	0.0

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	235.4	156.9	71.6	0.3	71.6	0.3
C-AB	165.2	110.1	27.6	0.2	27.6	0.2
C-A	-	-	-	-	-	-
A-B	280.8	187.2	-	-	-	-
A-C	693.7	462.5	-	-	-	-
All	1801.7	1201.2	99.2	0.1	99.2	0.1

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	362.0	241.3	122.3	0.3	122.4	0.3
C-AB	20.6	13.8	2.0	0.1	2.0	0.1
C-A	-	-	-	-	-	-
A-B	34.4	22.9	-	-	-	-
A-C	284.9	189.9	-	-	-	-
All	1633.8	1089.2	124.4	0.1	124.4	0.1

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 16:45-18:15


Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	411.6	274.4	195.6	0.5	195.7	0.5
C-AB	59.2	39.5	6.5	0.1	6.5	0.1
C-A	-	-	-	-	-	-
A-B	107.4	71.6	-	-	-	-
A-C	284.9	189.9	-	-	-	-
All	1794.9	1196.6	202.1	0.1	202.2	0.1

Delay is that occurring only within the time period.

Inclusive delay includes delay suffered by vehicles which are still queuing after the end of the time period.

These will only be significantly different if there is a large queue remaining at the end of the time period.

PICADY 5 Run Successful

PICADY		
GUI Version: 5.1 AD Analysis Program Release: 4.0 (SEPT 2008)		
© Copyright TRL Limited, 2008 Adapted from PICADY/3 which is Crown Copyright by permission of the controller of HMSO		
For sales and distribution information, program advice and maintenance, contact:		
TRL Limited Crowthorne House Nine Mile Ride Wokingham, Berks. RG40 3GA, UK		Tel: +44 (0)1344 770758 Fax: +44 (0)1344 770864 E-mail: software@trl.co.uk Web: www.trlsoftware.co.uk
The user of this computer program for the solution of an engineering problem is in no way relieved of their responsibility for the correctness of the solution		

Run Analysis

Parameter	Values
File Run	I:\..\Carmanhall Rd_Corrig Rd\118139 Carmanhall Rd_Corrig Rd T-Junction 2018 10 11.vpi
Date Run	16 October 2018
Time Run	16:06:09
Driving Side	Drive On The Left

Arm Names and Flow Scaling Factors

Arm	Arm Name	Flow Scaling Factor (%)
Arm A	Carmanhall Rd East	100
Arm B	Corrig Rd	100
Arm C	Carmanhall Rd West	100

Stream Labelling Convention

Stream A-B contains traffic going from A to B etc.

Run Information

Parameter	Values
Run Title	Carmanhall Rd/Corrig Rd T-Junction
Location	Sandyford, Dublin 18
Date	11 October 2018
Enumerator	J Noone
Job Number	118139
Status	TIA
Client	IRES Residential Properties Ltd
Description	-

Geometric Data

Geometric Parameters



Parameter	Minor Arm B
Major Road Carriageway Width (m)	7.30
Major Road Kerbed Central Reserve Width (m)	0.00
Major Road Right Turning Lane Width (m)	2.20
Minor Road First Lane Width (m)	4.50
Minor Road Visibility To Right (m)	40
Minor Road Visibility To Left (m)	40
Major Road Right Turn Visibility (m)	160
Major Road Right Turn Blocks Traffic	Yes

Slope and Intercept Values

Stream	Intercept for Stream B-A	Slope for A-B	Slope for A-C	Slope for C-A	Slope for C-B
B-A	586.875	0.101	0.255	0.160	0.364
B-C	746.600	0.108	0.273	-	-
C-B	666.621	0.244	0.244	-	-

Note: Streams may be combined in which case capacity will be adjusted
These values do not allow for any site-specific corrections

Junction Diagram



Demand Data

Modelling Periods

Parameter	Period	Duration (min)	Segment Length (min)
First Modelling Period	07:45-09:15	90	15
Second Modelling Period	16:45-18:15	90	15

ODTAB Turning Counts

Demand Set: 2016 AM Existing Traffic

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	34.0	139.0
Arm B	165.0	0.0	73.0
Arm C	319.0	83.0	0.0

Demand Set: 2016 PM Existing Traffic

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	25.0	341.0
Arm B	42.0	0.0	197.0
Arm C	95.0	34.0	0.0

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	39.0	259.0
Arm B	177.0	0.0	80.0
Arm C	373.0	96.0	0.0

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	27.0	379.0
Arm B	47.0	0.0	217.0
Arm C	202.0	39.0	0.0

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	39.0	275.0
Arm B	177.0	0.0	80.0
Arm C	417.0	96.0	0.0

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	27.0	408.0
Arm B	47.0	0.0	217.0
Arm C	214.0	39.0	0.0

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	44.0	278.0
Arm B	201.0	0.0	90.0
Arm C	418.0	107.0	0.0

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	44.0	294.0
Arm B	201.0	0.0	90.0
Arm C	462.0	107.0	0.0

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	30.0	427.0
Arm B	53.0	0.0	244.0
Arm C	215.0	44.0	0.0

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	30.0	456.0
Arm B	53.0	0.0	244.0
Arm C	228.0	44.0	0.0

ODTAB Synthesised Flows

Demand Set: 2016 AM Existing Traffic

Modelling Period: 07:45-09:15

Arm	Rising Time	Rising Flow (veh/min)	Peak Time	Peak Flow (veh/min)	Falling Time	Falling Flow (veh/min)
Arm A	08:00	2.162	08:30	3.244	09:00	2.162
Arm B	08:00	2.975	08:30	4.462	09:00	2.975
Arm C	08:00	5.025	08:30	7.538	09:00	5.025

Heavy Vehicles Percentages

Demand Set: 2016 AM Existing Traffic

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2016 PM Existing Traffic

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Queues & Delays

Demand Set: 2016 AM Existing Traffic
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	2.99	9.13	0.327	-	0.00	0.48	-	6.8	0.16
	C-AB	1.04	10.58	0.098	-	0.00	0.11	-	1.7	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.43	-	-	-	-	-	-	-	-
	A-C	1.74	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	3.57	8.86	0.402	-	0.48	0.66	-	9.5	0.19
	C-AB	1.24	10.48	0.119	-	0.11	0.14	-	2.1	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.51	-	-	-	-	-	-	-	-
	A-C	2.08	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	4.37	8.49	0.515	-	0.66	1.03	-	14.6	0.24
	C-AB	1.52	10.34	0.147	-	0.14	0.19	-	2.8	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.62	-	-	-	-	-	-	-	-
	A-C	2.55	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	4.37	8.49	0.515	-	1.03	1.04	-	15.6	0.24
	C-AB	1.52	10.34	0.147	-	0.19	0.19	-	2.8	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.62	-	-	-	-	-	-	-	-
	A-C	2.55	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	3.57	8.86	0.403	-	1.04	0.69	-	10.8	0.19
	C-AB	1.24	10.48	0.119	-	0.19	0.14	-	2.1	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.51	-	-	-	-	-	-	-	-
	A-C	2.08	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	2.99	9.13	0.327	-	0.69	0.49	-	7.7	0.16
	C-AB	1.04	10.58	0.098	-	0.14	0.11	-	1.7	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.43	-	-	-	-	-	-	-	-
	A-C	1.74	-	-	-	-	-	-	-	-

Demand Set: 2016 PM Existing Traffic
Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	3.00	10.59	0.283	-	0.00	0.39	-	5.6	0.13
	C-AB	0.43	9.99	0.043	-	0.00	0.04	-	0.7	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.31	-	-	-	-	-	-	-	-
	A-C	4.28	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	3.58	10.33	0.347	-	0.39	0.52	-	7.6	0.15
	C-AB	0.51	9.77	0.052	-	0.04	0.06	-	0.8	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.37	-	-	-	-	-	-	-	-
	A-C	5.11	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	4.39	9.98	0.439	-	0.52	0.77	-	11.1	0.18
	C-AB	0.62	9.47	0.066	-	0.06	0.07	-	1.1	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.46	-	-	-	-	-	-	-	-
	A-C	6.26	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	4.39	9.98	0.439	-	0.77	0.78	-	11.6	0.18
	C-AB	0.62	9.47	0.066	-	0.07	0.07	-	1.1	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.46	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
	A-C	6.26	-	-	-	-	-	-	-	-
17:45-18:00	B-AC	3.58	10.33	0.347	-	0.78	0.54	-	8.4	0.15
	C-AB	0.51	9.77	0.052	-	0.07	0.06	-	0.8	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.37	-	-	-	-	-	-	-	-
	A-C	5.11	-	-	-	-	-	-	-	-
18:00-18:15	B-AC	3.00	10.59	0.283	-	0.54	0.40	-	6.2	0.13
	C-AB	0.43	9.99	0.043	-	0.06	0.05	-	0.7	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.31	-	-	-	-	-	-	-	-
	A-C	4.28	-	-	-	-	-	-	-	-

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	3.22	8.60	0.375	-	0.00	0.59	-	8.3	0.18
	C-AB	1.20	10.20	0.118	-	0.00	0.14	-	2.1	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.49	-	-	-	-	-	-	-	-
	A-C	3.25	-	-	-	-	-	-	-	-
08:00-08:15	B-AC	3.85	8.22	0.469	-	0.59	0.86	-	12.3	0.23
	C-AB	1.44	10.02	0.144	-	0.14	0.18	-	2.7	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.58	-	-	-	-	-	-	-	-
	A-C	3.88	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	4.72	7.69	0.614	-	0.86	1.51	-	20.9	0.33
	C-AB	1.76	9.78	0.180	-	0.18	0.24	-	3.7	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.72	-	-	-	-	-	-	-	-
	A-C	4.75	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	4.72	7.69	0.614	-	1.51	1.54	-	22.9	0.34
	C-AB	1.76	9.78	0.180	-	0.24	0.25	-	3.7	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.72	-	-	-	-	-	-	-	-
	A-C	4.75	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	3.85	8.21	0.469	-	1.54	0.91	-	14.4	0.23
	C-AB	1.44	10.02	0.144	-	0.25	0.18	-	2.7	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.58	-	-	-	-	-	-	-	-
	A-C	3.88	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	3.22	8.59	0.375	-	0.91	0.61	-	9.6	0.19
	C-AB	1.20	10.20	0.118	-	0.18	0.14	-	2.1	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.49	-	-	-	-	-	-	-	-
	A-C	3.25	-	-	-	-	-	-	-	-

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	3.31	10.38	0.319	-	0.00	0.46	-	6.6	0.14
	C-AB	0.49	9.87	0.050	-	0.00	0.05	-	0.8	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.34	-	-	-	-	-	-	-	-
	A-C	4.76	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	3.96	10.08	0.392	-	0.46	0.63	-	9.2	0.16
	C-AB	0.58	9.63	0.061	-	0.05	0.07	-	1.0	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.40	-	-	-	-	-	-	-	-

	A-C	5.68	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	4.84	9.67	0.501	-	0.63	0.98	-	14.0	0.21
	C-AB	0.72	9.29	0.077	-	0.07	0.09	-	1.3	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.50	-	-	-	-	-	-	-	-
	A-C	6.95	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	4.84	9.67	0.501	-	0.98	0.99	-	14.8	0.21
	C-AB	0.72	9.29	0.077	-	0.09	0.09	-	1.3	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.50	-	-	-	-	-	-	-	-
	A-C	6.95	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	3.96	10.08	0.392	-	0.99	0.66	-	10.3	0.16
	C-AB	0.58	9.63	0.061	-	0.09	0.07	-	1.0	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.40	-	-	-	-	-	-	-	-
	A-C	5.68	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	3.31	10.37	0.319	-	0.66	0.48	-	7.4	0.14
	C-AB	0.49	9.87	0.050	-	0.07	0.05	-	0.8	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.34	-	-	-	-	-	-	-	-
	A-C	4.76	-	-	-	-	-	-	-	-

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	3.22	8.47	0.381	-	0.00	0.60	-	8.5	0.19
	C-AB	1.20	10.15	0.119	-	0.00	0.14	-	2.1	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.49	-	-	-	-	-	-	-	-
	A-C	3.45	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	3.85	8.06	0.478	-	0.60	0.89	-	12.7	0.24
	C-AB	1.44	9.96	0.144	-	0.14	0.18	-	2.7	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.58	-	-	-	-	-	-	-	-
	A-C	4.12	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	4.72	7.49	0.629	-	0.89	1.60	-	22.1	0.35
	C-AB	1.76	9.71	0.181	-	0.18	0.25	-	3.7	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.72	-	-	-	-	-	-	-	-
	A-C	5.05	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	4.72	7.49	0.630	-	1.60	1.65	-	24.5	0.36
	C-AB	1.76	9.71	0.181	-	0.25	0.25	-	3.8	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.72	-	-	-	-	-	-	-	-
	A-C	5.05	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	3.85	8.06	0.478	-	1.65	0.94	-	15.1	0.24
	C-AB	1.44	9.96	0.144	-	0.25	0.19	-	2.8	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.58	-	-	-	-	-	-	-	-
	A-C	4.12	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	3.22	8.46	0.381	-	0.94	0.63	-	9.8	0.19
	C-AB	1.20	10.15	0.119	-	0.19	0.14	-	2.2	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.49	-	-	-	-	-	-	-	-

	A-C	3.45	-	-	-	-	-	-	-	-
--	-----	------	---	---	---	---	---	---	---	---

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	3.31	10.27	0.323	-	0.00	0.47	-	6.7	0.14
	C-AB	0.49	9.78	0.050	-	0.00	0.05	-	0.8	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.34	-	-	-	-	-	-	-	-
	A-C	5.12	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	3.96	9.95	0.397	-	0.47	0.65	-	9.4	0.17
	C-AB	0.58	9.52	0.061	-	0.05	0.07	-	1.0	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.40	-	-	-	-	-	-	-	-
	A-C	6.11	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	4.84	9.51	0.509	-	0.65	1.01	-	14.4	0.21
	C-AB	0.72	9.17	0.078	-	0.07	0.09	-	1.3	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.50	-	-	-	-	-	-	-	-
	A-C	7.49	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	4.84	9.51	0.509	-	1.01	1.02	-	15.3	0.21
	C-AB	0.72	9.17	0.078	-	0.09	0.09	-	1.3	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.50	-	-	-	-	-	-	-	-
	A-C	7.49	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	3.96	9.95	0.397	-	1.02	0.67	-	10.5	0.17
	C-AB	0.58	9.52	0.061	-	0.09	0.07	-	1.0	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.40	-	-	-	-	-	-	-	-
	A-C	6.11	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	3.31	10.27	0.323	-	0.67	0.48	-	7.5	0.14
	C-AB	0.49	9.78	0.050	-	0.07	0.05	-	0.8	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.34	-	-	-	-	-	-	-	-
	A-C	5.12	-	-	-	-	-	-	-	-

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	3.65	8.40	0.435	-	0.00	0.75	-	10.5	0.21
	C-AB	1.34	10.13	0.133	-	0.00	0.16	-	2.4	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.55	-	-	-	-	-	-	-	-
	A-C	3.49	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	4.36	7.98	0.547	-	0.75	1.16	-	16.4	0.27
	C-AB	1.60	9.93	0.161	-	0.16	0.21	-	3.1	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.66	-	-	-	-	-	-	-	-
	A-C	4.17	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	5.34	7.39	0.723	-	1.16	2.36	-	31.4	0.45
	C-AB	1.96	9.67	0.203	-	0.21	0.29	-	4.4	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.81	-	-	-	-	-	-	-	-
	A-C	5.10	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	5.34	7.39	0.723	-	2.36	2.47	-	36.4	0.48
	C-AB	1.96	9.67	0.203	-	0.29	0.29	-	4.4	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.81	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
	A-C	5.10	-	-	-	-	-	-	-	-
08:45-09:00	B-AC	4.36	7.97	0.547	-	2.47	1.25	-	20.3	0.29
	C-AB	1.60	9.93	0.161	-	0.29	0.21	-	3.2	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.66	-	-	-	-	-	-	-	-
	A-C	4.17	-	-	-	-	-	-	-	-
09:00-09:15	B-AC	3.65	8.39	0.435	-	1.25	0.79	-	12.5	0.21
	C-AB	1.34	10.13	0.133	-	0.21	0.16	-	2.5	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.55	-	-	-	-	-	-	-	-
	A-C	3.49	-	-	-	-	-	-	-	-

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	3.65	8.27	0.442	-	0.00	0.77	-	10.8	0.21
	C-AB	1.34	10.08	0.133	-	0.00	0.16	-	2.4	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.55	-	-	-	-	-	-	-	-
	A-C	3.69	-	-	-	-	-	-	-	-
08:00-08:15	B-AC	4.36	7.82	0.558	-	0.77	1.21	-	17.0	0.28
	C-AB	1.60	9.88	0.162	-	0.16	0.21	-	3.2	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.66	-	-	-	-	-	-	-	-
	A-C	4.40	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	5.34	7.19	0.742	-	1.21	2.57	-	33.8	0.49
	C-AB	1.96	9.60	0.205	-	0.21	0.30	-	4.5	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.81	-	-	-	-	-	-	-	-
	A-C	5.40	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	5.34	7.19	0.743	-	2.57	2.71	-	39.8	0.53
	C-AB	1.96	9.60	0.205	-	0.30	0.30	-	4.6	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.81	-	-	-	-	-	-	-	-
	A-C	5.40	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	4.36	7.82	0.558	-	2.71	1.31	-	21.5	0.30
	C-AB	1.60	9.88	0.162	-	0.30	0.22	-	3.3	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.66	-	-	-	-	-	-	-	-
	A-C	4.40	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	3.65	8.26	0.442	-	1.31	0.81	-	12.9	0.22
	C-AB	1.34	10.08	0.133	-	0.22	0.17	-	2.5	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.55	-	-	-	-	-	-	-	-
	A-C	3.69	-	-	-	-	-	-	-	-

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	3.73	10.19	0.366	-	0.00	0.57	-	8.1	0.15
	C-AB	0.55	9.71	0.057	-	0.00	0.06	-	0.9	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.38	-	-	-	-	-	-	-	-
	A-C	5.36	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	4.45	9.86	0.451	-	0.57	0.81	-	11.6	0.18
	C-AB	0.66	9.44	0.070	-	0.06	0.08	-	1.1	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.45	-	-	-	-	-	-	-	-

	A-C	6.40	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	5.45	9.40	0.580	-	0.81	1.33	-	18.7	0.25
	C-AB	0.81	9.07	0.089	-	0.08	0.10	-	1.5	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.55	-	-	-	-	-	-	-	-
	A-C	7.84	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	5.45	9.40	0.580	-	1.33	1.35	-	20.2	0.25
	C-AB	0.81	9.07	0.089	-	0.10	0.10	-	1.5	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.55	-	-	-	-	-	-	-	-
	A-C	7.84	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	4.45	9.86	0.451	-	1.35	0.84	-	13.3	0.19
	C-AB	0.66	9.44	0.070	-	0.10	0.08	-	1.2	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.45	-	-	-	-	-	-	-	-
	A-C	6.40	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	3.73	10.19	0.366	-	0.84	0.59	-	9.1	0.16
	C-AB	0.55	9.71	0.057	-	0.08	0.06	-	0.9	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.38	-	-	-	-	-	-	-	-
	A-C	5.36	-	-	-	-	-	-	-	-

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	3.73	10.08	0.370	-	0.00	0.58	-	8.2	0.16
	C-AB	0.55	9.62	0.057	-	0.00	0.06	-	0.9	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.38	-	-	-	-	-	-	-	-
	A-C	5.72	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	4.45	9.73	0.457	-	0.58	0.82	-	11.9	0.19
	C-AB	0.66	9.34	0.071	-	0.06	0.08	-	1.2	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.45	-	-	-	-	-	-	-	-
	A-C	6.83	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	5.45	9.24	0.590	-	0.82	1.38	-	19.4	0.26
	C-AB	0.81	8.94	0.090	-	0.08	0.10	-	1.5	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.55	-	-	-	-	-	-	-	-
	A-C	8.37	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	5.45	9.24	0.590	-	1.38	1.41	-	21.0	0.26
	C-AB	0.81	8.94	0.090	-	0.10	0.10	-	1.6	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.55	-	-	-	-	-	-	-	-
	A-C	8.37	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	4.45	9.73	0.457	-	1.41	0.86	-	13.6	0.19
	C-AB	0.66	9.34	0.071	-	0.10	0.08	-	1.2	0.12
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.45	-	-	-	-	-	-	-	-
	A-C	6.83	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	3.73	10.08	0.370	-	0.86	0.60	-	9.3	0.16
	C-AB	0.55	9.62	0.057	-	0.08	0.06	-	0.9	0.11
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.38	-	-	-	-	-	-	-	-

	A-C	5.72	-	-	-	-	-	-	-	-
--	-----	------	---	---	---	---	---	---	---	---

Entry capacities marked with an '(X)' are dominated by a pedestrian crossing in that time segment.
 In time segments marked with a '(B)', traffic leaving the junction may block back from a crossing so impairing normal operation of the junction.
 Delays marked with '##' could not be calculated.

Overall Queues & Delays

Queueing Delay Information Over Whole Period

Demand Set: 2016 AM Existing Traffic
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	327.6	218.4	65.0	0.2	65.0	0.2
C-AB	114.2	76.2	13.2	0.1	13.2	0.1
C-A	-	-	-	-	-	-
A-B	46.8	31.2	-	-	-	-
A-C	191.3	127.5	-	-	-	-
All	1119.0	746.0	78.2	0.1	78.2	0.1

Demand Set: 2016 PM Existing Traffic
Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	329.0	219.3	50.4	0.2	50.4	0.2
C-AB	46.8	31.2	5.1	0.1	5.1	0.1
C-A	-	-	-	-	-	-
A-B	34.4	22.9	-	-	-	-
A-C	469.4	312.9	-	-	-	-
All	1010.3	673.5	55.5	0.1	55.6	0.1

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	353.7	235.8	88.5	0.3	88.5	0.3
C-AB	132.1	88.1	17.0	0.1	17.0	0.1
C-A	-	-	-	-	-	-
A-B	53.7	35.8	-	-	-	-
A-C	356.5	237.7	-	-	-	-
All	1409.5	939.6	105.5	0.1	105.5	0.1

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	363.4	242.3	62.2	0.2	62.2	0.2
C-AB	53.7	35.8	6.1	0.1	6.1	0.1
C-A	-	-	-	-	-	-
A-B	37.2	24.8	-	-	-	-
A-C	521.7	347.8	-	-	-	-
All	1253.9	835.9	68.3	0.1	68.4	0.1

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	353.7	235.8	92.6	0.3	92.7	0.3
C-AB	132.1	88.1	17.3	0.1	17.3	0.1
C-A	-	-	-	-	-	-
A-B	53.7	35.8	-	-	-	-
A-C	378.5	252.3	-	-	-	-
All	1492.0	994.7	110.0	0.1	110.0	0.1

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	363.4	242.3	63.8	0.2	63.8	0.2
C-AB	53.7	35.8	6.2	0.1	6.2	0.1
C-A	-	-	-	-	-	-
A-B	37.2	24.8	-	-	-	-
A-C	561.6	374.4	-	-	-	-
All	1310.4	873.6	70.0	0.1	70.0	0.1

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	400.5	267.0	127.5	0.3	127.6	0.3
C-AB	147.3	98.2	20.1	0.1	20.1	0.1
C-A	-	-	-	-	-	-
A-B	60.6	40.4	-	-	-	-
A-C	382.6	255.1	-	-	-	-
All	1566.4	1044.2	147.6	0.1	147.6	0.1

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	400.5	267.0	135.8	0.3	135.8	0.3
C-AB	147.3	98.2	20.5	0.1	20.5	0.1
C-A	-	-	-	-	-	-
A-B	60.6	40.4	-	-	-	-
A-C	404.7	269.8	-	-	-	-
All	1649.0	1099.3	156.3	0.1	156.3	0.1

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	408.8	272.5	81.0	0.2	81.0	0.2
C-AB	60.6	40.4	7.2	0.1	7.2	0.1
C-A	-	-	-	-	-	-
A-B	41.3	27.5	-	-	-	-
A-C	587.7	391.8	-	-	-	-
All	1394.3	929.5	88.2	0.1	88.2	0.1

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15


Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	408.8	272.5	83.4	0.2	83.4	0.2
C-AB	60.6	40.4	7.3	0.1	7.3	0.1
C-A	-	-	-	-	-	-
A-B	41.3	27.5	-	-	-	-
A-C	627.7	418.4	-	-	-	-
All	1452.1	968.1	90.7	0.1	90.7	0.1

Delay is that occurring only within the time period.

Inclusive delay includes delay suffered by vehicles which are still queuing after the end of the time period.

These will only be significantly different if there is a large queue remaining at the end of the time period.

PICADY 5 Run Successful

PICADY		
GUI Version: 5.1 AD Analysis Program Release: 4.0 (SEPT 2008)		
© Copyright TRL Limited, 2008 Adapted from PICADY/3 which is Crown Copyright by permission of the controller of HMSO		
For sales and distribution information, program advice and maintenance, contact:		
TRL Limited Crowthorne House Nine Mile Ride Wokingham, Berks. RG40 3GA, UK		Tel: +44 (0)1344 770758 Fax: +44 (0)1344 770864 E-mail: software@trl.co.uk Web: www.trlsoftware.co.uk
The user of this computer program for the solution of an engineering problem is in no way relieved of their responsibility for the correctness of the solution		

Run Analysis

Parameter	Values
File Run	I:\..\Blackthorn Rd_Carmanhall Rd\118139 Blackthorn Rd_Carmanhall Rd T-Junction 2018 10 11.vpi
Date Run	16 October 2018
Time Run	16:03:24
Driving Side	Drive On The Left

Arm Names and Flow Scaling Factors

Arm	Arm Name	Flow Scaling Factor (%)
Arm A	Blackthorn Rd South	100
Arm B	Carmanhall Rd	100
Arm C	Blackthorn Rd North	100

Stream Labelling Convention

Stream A-B contains traffic going from A to B etc.

Run Information

Parameter	Values
Run Title	Blackthorn Rd/Carmanhall Rd T-Junction
Location	Sandyford, Dublin 18
Date	11 October 2018
Enumerator	J Noone
Job Number	118139
Status	TIA
Client	IRES Residential Properties Ltd
Description	-

Geometric Data

Geometric Parameters


Parameter	Minor Arm B
Major Road Carriageway Width (m)	9.00
Major Road Kerbed Central Reserve Width (m)	0.00
Major Road Right Turning Lane Width (m)	2.20
Minor Road First Lane Width (m)	4.10
Minor Road Visibility To Right (m)	55
Minor Road Visibility To Left (m)	40
Major Road Right Turn Visibility (m)	160
Major Road Right Turn Blocks Traffic	Yes

Slope and Intercept Values

Stream	Intercept for Stream B-A	Slope for A-B	Slope for A-C	Slope for C-A	Slope for C-B
B-A	574.682	0.091	0.230	0.145	0.329
B-C	731.087	0.097	0.246	-	-
C-B	666.621	0.225	0.225	-	-

Note: Streams may be combined in which case capacity will be adjusted
 These values do not allow for any site-specific corrections

Junction Diagram



Demand Data

Modelling Periods

Parameter	Period	Duration (min)	Segment Length (min)
First Modelling Period	07:45-09:15	90	15
Second Modelling Period	16:45-18:15	90	15

ODTAB Turning Counts

Demand Set: 2016 AM Existing Traffic

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	395.0	684.0
Arm B	12.0	0.0	171.0
Arm C	83.0	95.0	0.0

Demand Set: 2016 PM Existing Traffic

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	190.0	952.0
Arm B	5.0	0.0	352.0
Arm C	41.0	37.0	0.0

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	527.0	835.0
Arm B	29.0	0.0	240.0
Arm C	89.0	112.0	0.0

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	253.0	1274.0
Arm B	22.0	0.0	511.0
Arm C	44.0	51.0	0.0

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	544.0	847.0
Arm B	29.0	0.0	284.0
Arm C	89.0	112.0	0.0

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	281.0	1283.0
Arm B	22.0	0.0	524.0
Arm C	44.0	51.0	0.0

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	583.0	931.0
Arm B	31.0	0.0	264.0
Arm C	100.0	125.0	0.0

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	599.0	943.0
Arm B	31.0	0.0	308.0
Arm C	100.0	125.0	0.0

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	279.0	1407.0
Arm B	23.0	0.0	561.0
Arm C	50.0	56.0	0.0

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	308.0	1416.0
Arm B	23.0	0.0	573.0
Arm C	50.0	56.0	0.0

ODTAB Synthesised Flows

Demand Set: 2016 AM Existing Traffic

Modelling Period: 07:45-09:15

Arm	Rising Time	Rising Flow (veh/min)	Peak Time	Peak Flow (veh/min)	Falling Time	Falling Flow (veh/min)
Arm A	08:00	13.488	08:30	20.231	09:00	13.488
Arm B	08:00	2.287	08:30	3.431	09:00	2.287
Arm C	08:00	2.225	08:30	3.337	09:00	2.225

Heavy Vehicles Percentages

Demand Set: 2016 AM Existing Traffic

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2016 PM Existing Traffic

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Queues & Delays

Demand Set: 2016 AM Existing Traffic
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	2.30	9.31	0.247	-	0.00	0.32	-	4.6	0.14
	C-AB	1.19	8.07	0.148	-	0.00	0.17	-	2.5	0.14
	C-A	-	-	-	-	-	-	-	-	-
	A-B	4.96	-	-	-	-	-	-	-	-
	A-C	8.58	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	2.74	8.79	0.312	-	0.32	0.45	-	6.5	0.16
	C-AB	1.42	7.48	0.190	-	0.17	0.23	-	3.5	0.16
	C-A	-	-	-	-	-	-	-	-	-
	A-B	5.92	-	-	-	-	-	-	-	-
	A-C	10.25	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	3.36	8.07	0.416	-	0.45	0.70	-	10.0	0.21
	C-AB	1.74	6.66	0.262	-	0.23	0.35	-	5.2	0.20
	C-A	-	-	-	-	-	-	-	-	-
	A-B	7.25	-	-	-	-	-	-	-	-
	A-C	12.55	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	3.36	8.07	0.416	-	0.70	0.70	-	10.5	0.21
	C-AB	1.74	6.66	0.262	-	0.35	0.35	-	5.3	0.20
	C-A	-	-	-	-	-	-	-	-	-
	A-B	7.25	-	-	-	-	-	-	-	-
	A-C	12.55	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	2.74	8.79	0.312	-	0.70	0.46	-	7.2	0.17
	C-AB	1.42	7.48	0.190	-	0.35	0.24	-	3.6	0.17
	C-A	-	-	-	-	-	-	-	-	-
	A-B	5.92	-	-	-	-	-	-	-	-
	A-C	10.25	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	2.30	9.31	0.247	-	0.46	0.33	-	5.1	0.14
	C-AB	1.19	8.07	0.148	-	0.24	0.18	-	2.6	0.15
	C-A	-	-	-	-	-	-	-	-	-
	A-B	4.96	-	-	-	-	-	-	-	-
	A-C	8.58	-	-	-	-	-	-	-	-

Demand Set: 2016 PM Existing Traffic
Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	4.48	8.96	0.500	-	0.00	0.97	-	13.5	0.22
	C-AB	0.46	7.89	0.059	-	0.00	0.06	-	0.9	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.38	-	-	-	-	-	-	-	-
	A-C	11.95	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	5.35	8.34	0.641	-	0.97	1.69	-	23.4	0.32
	C-AB	0.55	7.27	0.076	-	0.06	0.08	-	1.2	0.15
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.85	-	-	-	-	-	-	-	-
	A-C	14.26	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	6.55	7.49	0.875	-	1.69	4.99	-	59.8	0.75
	C-AB	0.68	6.40	0.106	-	0.08	0.12	-	1.8	0.17
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.49	-	-	-	-	-	-	-	-
	A-C	17.47	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	6.55	7.49	0.875	-	4.99	5.69	-	80.9	0.93
	C-AB	0.68	6.40	0.106	-	0.12	0.12	-	1.8	0.17
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.49	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
	A-C	17.47	-	-	-	-	-	-	-	-
17:45-18:00	B-AC	5.35	8.34	0.641	-	5.69	1.90	-	34.4	0.39
	C-AB	0.55	7.27	0.076	-	0.12	0.08	-	1.3	0.15
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.85	-	-	-	-	-	-	-	-
	A-C	14.26	-	-	-	-	-	-	-	-
18:00-18:15	B-AC	4.48	8.96	0.500	-	1.90	1.03	-	16.5	0.23
	C-AB	0.46	7.89	0.059	-	0.08	0.06	-	0.9	0.13
	C-A	-	-	-	-	-	-	-	-	-
	A-B	2.38	-	-	-	-	-	-	-	-
	A-C	11.95	-	-	-	-	-	-	-	-

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	3.38	8.50	0.397	-	0.00	0.65	-	9.1	0.19
	C-AB	1.41	7.27	0.193	-	0.00	0.24	-	3.5	0.17
	C-A	-	-	-	-	-	-	-	-	-
	A-B	6.61	-	-	-	-	-	-	-	-
	A-C	10.48	-	-	-	-	-	-	-	-
08:00-08:15	B-AC	4.03	7.83	0.515	-	0.65	1.02	-	14.5	0.26
	C-AB	1.68	6.53	0.257	-	0.24	0.34	-	5.1	0.21
	C-A	-	-	-	-	-	-	-	-	-
	A-B	7.90	-	-	-	-	-	-	-	-
	A-C	12.51	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	4.94	6.91	0.715	-	1.02	2.27	-	30.0	0.47
	C-AB	2.06	5.50	0.374	-	0.34	0.58	-	8.7	0.29
	C-A	-	-	-	-	-	-	-	-	-
	A-B	9.67	-	-	-	-	-	-	-	-
	A-C	15.32	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	4.94	6.90	0.715	-	2.27	2.37	-	35.0	0.50
	C-AB	2.06	5.50	0.374	-	0.58	0.59	-	9.0	0.29
	C-A	-	-	-	-	-	-	-	-	-
	A-B	9.67	-	-	-	-	-	-	-	-
	A-C	15.32	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	4.03	7.83	0.515	-	2.37	1.10	-	17.9	0.28
	C-AB	1.68	6.53	0.257	-	0.59	0.35	-	5.4	0.21
	C-A	-	-	-	-	-	-	-	-	-
	A-B	7.90	-	-	-	-	-	-	-	-
	A-C	12.51	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	3.38	8.49	0.397	-	1.10	0.67	-	10.6	0.20
	C-AB	1.41	7.27	0.193	-	0.35	0.24	-	3.7	0.17
	C-A	-	-	-	-	-	-	-	-	-
	A-B	6.61	-	-	-	-	-	-	-	-
	A-C	10.48	-	-	-	-	-	-	-	-

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	6.69	7.78	0.860	-	0.00	4.57	-	53.1	0.62
	C-AB	0.64	6.81	0.094	-	0.00	0.10	-	1.5	0.16
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.17	-	-	-	-	-	-	-	-
	A-C	15.99	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	7.99	6.95	1.150	-	4.57	22.65	-	210.6	2.45
	C-AB	0.76	5.97	0.128	-	0.10	0.14	-	2.2	0.19
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.79	-	-	-	-	-	-	-	-

	A-C	19.09	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	9.78	5.79	1.690	-	22.65	82.65	-	790.1	9.40
	C-AB	0.94	4.82	0.194	-	0.14	0.24	-	3.5	0.26
	C-A	-	-	-	-	-	-	-	-	-
	A-B	4.64	-	-	-	-	-	-	-	-
	A-C	23.38	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	9.78	5.79	1.690	-	82.65	142.57	-	1689.2	17.58
	C-AB	0.94	4.82	0.194	-	0.24	0.24	-	3.6	0.26
	C-A	-	-	-	-	-	-	-	-	-
	A-B	4.64	-	-	-	-	-	-	-	-
	A-C	23.38	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	7.99	6.95	1.150	-	142.57	158.20	-	2255.8	21.10
	C-AB	0.76	5.97	0.128	-	0.24	0.15	-	2.2	0.19
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.79	-	-	-	-	-	-	-	-
	A-C	19.09	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	6.69	7.78	0.860	-	158.20	142.54	-	2255.5	19.46
	C-AB	0.64	6.81	0.094	-	0.15	0.11	-	1.6	0.16
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.17	-	-	-	-	-	-	-	-
	A-C	15.99	-	-	-	-	-	-	-	-

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	3.93	8.50	0.462	-	0.00	0.84	-	11.7	0.21
	C-AB	1.41	7.19	0.195	-	0.00	0.24	-	3.5	0.17
	C-A	-	-	-	-	-	-	-	-	-
	A-B	6.83	-	-	-	-	-	-	-	-
	A-C	10.63	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	4.69	7.83	0.599	-	0.84	1.42	-	19.8	0.31
	C-AB	1.68	6.43	0.261	-	0.24	0.35	-	5.2	0.21
	C-A	-	-	-	-	-	-	-	-	-
	A-B	8.15	-	-	-	-	-	-	-	-
	A-C	12.69	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	5.74	6.89	0.833	-	1.42	3.93	-	48.5	0.69
	C-AB	2.06	5.38	0.382	-	0.35	0.60	-	9.0	0.30
	C-A	-	-	-	-	-	-	-	-	-
	A-B	9.98	-	-	-	-	-	-	-	-
	A-C	15.54	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	5.74	6.89	0.833	-	3.93	4.35	-	62.6	0.81
	C-AB	2.06	5.38	0.382	-	0.60	0.61	-	9.3	0.30
	C-A	-	-	-	-	-	-	-	-	-
	A-B	9.98	-	-	-	-	-	-	-	-
	A-C	15.54	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	4.69	7.83	0.599	-	4.35	1.57	-	27.3	0.36
	C-AB	1.68	6.43	0.261	-	0.61	0.36	-	5.5	0.21
	C-A	-	-	-	-	-	-	-	-	-
	A-B	8.15	-	-	-	-	-	-	-	-
	A-C	12.69	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	3.93	8.50	0.462	-	1.57	0.88	-	14.0	0.22
	C-AB	1.41	7.19	0.195	-	0.36	0.25	-	3.7	0.17
	C-A	-	-	-	-	-	-	-	-	-
	A-B	6.83	-	-	-	-	-	-	-	-

	A-C	10.63	-	-	-	-	-	-	-	-
--	-----	-------	---	---	---	---	---	---	---	---

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	6.85	7.72	0.887	-	0.00	5.31	-	59.9	0.69
	C-AB	0.64	6.70	0.095	-	0.00	0.10	-	1.5	0.16
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.53	-	-	-	-	-	-	-	-
	A-C	16.10	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	8.18	6.88	1.190	-	5.31	26.73	-	245.4	2.84
	C-AB	0.76	5.85	0.131	-	0.10	0.15	-	2.2	0.20
	C-A	-	-	-	-	-	-	-	-	-
	A-B	4.21	-	-	-	-	-	-	-	-
	A-C	19.22	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	10.02	5.70	1.758	-	26.73	91.59	-	887.6	10.67
	C-AB	0.94	4.67	0.201	-	0.15	0.25	-	3.7	0.27
	C-A	-	-	-	-	-	-	-	-	-
	A-B	5.16	-	-	-	-	-	-	-	-
	A-C	23.54	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	10.02	5.70	1.758	-	91.59	156.40	-	1860.0	21.99
	C-AB	0.94	4.67	0.201	-	0.25	0.25	-	3.8	0.27
	C-A	-	-	-	-	-	-	-	-	-
	A-B	5.16	-	-	-	-	-	-	-	-
	A-C	23.54	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	8.18	6.88	1.190	-	156.40	176.00	-	2493.0	23.33
	C-AB	0.76	5.85	0.131	-	0.25	0.15	-	2.3	0.20
	C-A	-	-	-	-	-	-	-	-	-
	A-B	4.21	-	-	-	-	-	-	-	-
	A-C	19.22	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	6.85	7.72	0.887	-	176.00	163.59	-	2546.9	22.12
	C-AB	0.64	6.70	0.095	-	0.15	0.11	-	1.6	0.17
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.53	-	-	-	-	-	-	-	-
	A-C	16.10	-	-	-	-	-	-	-	-

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	3.70	8.12	0.456	-	0.00	0.82	-	11.4	0.22
	C-AB	1.57	6.84	0.229	-	0.00	0.29	-	4.3	0.19
	C-A	-	-	-	-	-	-	-	-	-
	A-B	7.32	-	-	-	-	-	-	-	-
	A-C	11.68	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	4.42	7.38	0.599	-	0.82	1.42	-	19.7	0.33
	C-AB	1.87	6.02	0.311	-	0.29	0.44	-	6.6	0.24
	C-A	-	-	-	-	-	-	-	-	-
	A-B	8.74	-	-	-	-	-	-	-	-
	A-C	13.95	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	5.41	6.33	0.855	-	1.42	4.31	-	51.8	0.79
	C-AB	2.29	4.87	0.471	-	0.44	0.86	-	12.7	0.38
	C-A	-	-	-	-	-	-	-	-	-
	A-B	10.70	-	-	-	-	-	-	-	-
	A-C	17.08	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	5.41	6.33	0.855	-	4.31	4.88	-	69.6	0.97
	C-AB	2.29	4.87	0.471	-	0.86	0.88	-	13.5	0.39
	C-A	-	-	-	-	-	-	-	-	-
	A-B	10.70	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
	A-C	17.08	-	-	-	-	-	-	-	-
08:45-09:00	B-AC	4.42	7.38	0.599	-	4.88	1.58	-	28.4	0.39
	C-AB	1.87	6.02	0.311	-	0.88	0.46	-	7.1	0.24
	C-A	-	-	-	-	-	-	-	-	-
	A-B	8.74	-	-	-	-	-	-	-	-
	A-C	13.95	-	-	-	-	-	-	-	-
09:00-09:15	B-AC	3.70	8.12	0.456	-	1.58	0.86	-	13.7	0.23
	C-AB	1.57	6.84	0.229	-	0.46	0.30	-	4.6	0.19
	C-A	-	-	-	-	-	-	-	-	-
	A-B	7.32	-	-	-	-	-	-	-	-
	A-C	11.68	-	-	-	-	-	-	-	-

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	4.25	8.12	0.524	-	0.00	1.06	-	14.6	0.25
	C-AB	1.57	6.77	0.232	-	0.00	0.30	-	4.4	0.19
	C-A	-	-	-	-	-	-	-	-	-
	A-B	7.52	-	-	-	-	-	-	-	-
	A-C	11.83	-	-	-	-	-	-	-	-
08:00-08:15	B-AC	5.08	7.37	0.689	-	1.06	2.04	-	27.6	0.41
	C-AB	1.87	5.92	0.316	-	0.30	0.45	-	6.8	0.25
	C-A	-	-	-	-	-	-	-	-	-
	A-B	8.97	-	-	-	-	-	-	-	-
	A-C	14.13	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	6.22	6.32	0.984	-	2.04	8.78	-	92.1	1.28
	C-AB	2.29	4.76	0.482	-	0.45	0.90	-	13.2	0.40
	C-A	-	-	-	-	-	-	-	-	-
	A-B	10.99	-	-	-	-	-	-	-	-
	A-C	17.30	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	6.22	6.32	0.985	-	8.78	12.03	-	157.6	2.00
	C-AB	2.29	4.76	0.482	-	0.90	0.93	-	14.2	0.40
	C-A	-	-	-	-	-	-	-	-	-
	A-B	10.99	-	-	-	-	-	-	-	-
	A-C	17.30	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	5.08	7.37	0.689	-	12.03	2.46	-	65.5	0.77
	C-AB	1.87	5.92	0.316	-	0.93	0.47	-	7.3	0.25
	C-A	-	-	-	-	-	-	-	-	-
	A-B	8.97	-	-	-	-	-	-	-	-
	A-C	14.13	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	4.25	8.12	0.524	-	2.46	1.14	-	18.6	0.27
	C-AB	1.57	6.77	0.232	-	0.47	0.31	-	4.6	0.19
	C-A	-	-	-	-	-	-	-	-	-
	A-B	7.52	-	-	-	-	-	-	-	-
	A-C	11.83	-	-	-	-	-	-	-	-

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	7.33	7.34	0.998	-	0.00	9.91	-	97.0	1.08
	C-AB	0.70	6.36	0.110	-	0.00	0.12	-	1.8	0.18
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.50	-	-	-	-	-	-	-	-
	A-C	17.65	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	8.75	6.42	1.363	-	9.91	45.43	-	416.7	5.00
	C-AB	0.84	5.44	0.154	-	0.12	0.18	-	2.7	0.22
	C-A	-	-	-	-	-	-	-	-	-
	A-B	4.18	-	-	-	-	-	-	-	-

	A-C	21.08	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	10.72	5.13	2.089	-	45.43	129.25	-	1310.2	16.95
	C-AB	1.03	4.16	0.247	-	0.18	0.32	-	4.8	0.32
	C-A	-	-	-	-	-	-	-	-	-
	A-B	5.12	-	-	-	-	-	-	-	-
	A-C	25.82	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	10.72	5.13	2.089	-	129.25	213.06	-	2567.4	33.60
	C-AB	1.03	4.16	0.247	-	0.32	0.32	-	4.9	0.32
	C-A	-	-	-	-	-	-	-	-	-
	A-B	5.12	-	-	-	-	-	-	-	-
	A-C	25.82	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	8.75	6.42	1.363	-	213.06	248.06	-	3458.4	33.46
	C-AB	0.84	5.44	0.154	-	0.32	0.19	-	2.8	0.22
	C-A	-	-	-	-	-	-	-	-	-
	A-B	4.18	-	-	-	-	-	-	-	-
	A-C	21.08	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	7.33	7.34	0.998	-	248.06	248.15	-	3721.6	33.95
	C-AB	0.70	6.36	0.110	-	0.19	0.13	-	1.9	0.18
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.50	-	-	-	-	-	-	-	-
	A-C	17.65	-	-	-	-	-	-	-	-

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	7.48	7.28	1.027	-	0.00	11.63	-	109.8	1.21
	C-AB	0.70	6.25	0.112	-	0.00	0.12	-	1.8	0.18
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.86	-	-	-	-	-	-	-	-
	A-C	17.77	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	8.93	6.35	1.407	-	11.63	50.80	-	469.5	5.69
	C-AB	0.84	5.31	0.158	-	0.12	0.18	-	2.8	0.22
	C-A	-	-	-	-	-	-	-	-	-
	A-B	4.61	-	-	-	-	-	-	-	-
	A-C	21.22	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	10.94	5.04	2.170	-	50.80	139.29	-	1425.7	18.60
	C-AB	1.03	4.01	0.257	-	0.18	0.34	-	5.0	0.33
	C-A	-	-	-	-	-	-	-	-	-
	A-B	5.65	-	-	-	-	-	-	-	-
	A-C	25.98	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	10.94	5.04	2.171	-	139.29	227.76	-	2752.9	36.66
	C-AB	1.03	4.01	0.257	-	0.34	0.34	-	5.2	0.34
	C-A	-	-	-	-	-	-	-	-	-
	A-B	5.65	-	-	-	-	-	-	-	-
	A-C	25.98	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	8.93	6.34	1.407	-	227.76	266.55	-	3707.3	36.05
	C-AB	0.84	5.31	0.158	-	0.34	0.19	-	2.9	0.22
	C-A	-	-	-	-	-	-	-	-	-
	A-B	4.61	-	-	-	-	-	-	-	-
	A-C	21.22	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	7.48	7.28	1.027	-	266.55	269.58	-	4020.9	36.98
	C-AB	0.70	6.25	0.112	-	0.19	0.13	-	1.9	0.18
	C-A	-	-	-	-	-	-	-	-	-
	A-B	3.86	-	-	-	-	-	-	-	-

	A-C	17.77	-	-	-	-	-	-	-	-
--	-----	-------	---	---	---	---	---	---	---	---

Entry capacities marked with an '(X)' are dominated by a pedestrian crossing in that time segment.
 In time segments marked with a '(B)', traffic leaving the junction may block back from a crossing so impairing normal operation of the junction.
 Delays marked with '##' could not be calculated.

Overall Queues & Delays

Queueing Delay Information Over Whole Period

Demand Set: 2016 AM Existing Traffic
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	251.9	167.9	43.9	0.2	43.9	0.2
C-AB	130.8	87.2	22.8	0.2	22.8	0.2
C-A	-	-	-	-	-	-
A-B	543.7	362.5	-	-	-	-
A-C	941.5	627.7	-	-	-	-
All	1982.1	1321.4	66.7	0.0	66.7	0.0

Demand Set: 2016 PM Existing Traffic
Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	491.4	327.6	228.4	0.5	228.4	0.5
C-AB	50.9	34.0	7.9	0.2	7.9	0.2
C-A	-	-	-	-	-	-
A-B	261.5	174.3	-	-	-	-
A-C	1310.4	873.6	-	-	-	-
All	2170.6	1447.1	236.3	0.1	236.3	0.1

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	370.3	246.8	117.1	0.3	117.1	0.3
C-AB	154.2	102.8	35.3	0.2	35.3	0.2
C-A	-	-	-	-	-	-
A-B	725.4	483.6	-	-	-	-
A-C	1149.3	766.2	-	-	-	-
All	2521.6	1681.1	152.3	0.1	152.4	0.1

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	733.6	489.1	7254.3	9.9	8560.1	11.7
C-AB	70.2	46.8	14.7	0.2	14.7	0.2
C-A	-	-	-	-	-	-
A-B	348.2	232.2	-	-	-	-
A-C	1753.6	1169.0	-	-	-	-
All	2966.2	1977.5	7269.0	2.5	8574.8	2.9

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	430.8	287.2	183.9	0.4	184.0	0.4
C-AB	154.2	102.8	36.2	0.2	36.2	0.2
C-A	-	-	-	-	-	-
A-B	748.8	499.2	-	-	-	-
A-C	1165.8	777.2	-	-	-	-
All	2622.1	1748.1	220.1	0.1	220.2	0.1

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	751.5	501.0	8092.8	10.8	9825.8	13.1
C-AB	70.2	46.8	15.1	0.2	15.1	0.2
C-A	-	-	-	-	-	-
A-B	386.8	257.9	-	-	-	-
A-C	1766.0	1177.3	-	-	-	-
All	3035.0	2023.3	8107.9	2.7	9840.9	3.2

Demand Set: 2031 AM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	406.0	270.7	194.5	0.5	194.6	0.5
C-AB	172.1	114.7	48.8	0.3	48.8	0.3
C-A	-	-	-	-	-	-
A-B	802.5	535.0	-	-	-	-
A-C	1281.5	854.3	-	-	-	-
All	2799.7	1866.4	243.4	0.1	243.4	0.1

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	466.6	311.1	376.0	0.8	376.1	0.8
C-AB	172.1	114.7	50.5	0.3	50.5	0.3
C-A	-	-	-	-	-	-
A-B	824.5	549.7	-	-	-	-
A-C	1298.0	865.3	-	-	-	-
All	2898.8	1932.5	426.4	0.1	426.5	0.1

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	803.8	535.9	11571.4	14.4	15766.2	19.6
C-AB	77.1	51.4	18.9	0.2	18.9	0.2
C-A	-	-	-	-	-	-
A-B	384.0	256.0	-	-	-	-
A-C	1936.6	1291.1	-	-	-	-
All	3270.4	2180.3	11590.2	3.5	15785.1	4.8

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15


Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	820.3	546.9	12486.2	15.2	17477.7	21.3
C-AB	77.1	51.4	19.6	0.3	19.6	0.3
C-A	-	-	-	-	-	-
A-B	423.9	282.6	-	-	-	-
A-C	1949.0	1299.3	-	-	-	-
All	3339.2	2226.1	12505.8	3.7	17497.3	5.2

Delay is that occurring only within the time period.

Inclusive delay includes delay suffered by vehicles which are still queuing after the end of the time period.

These will only be significantly different if there is a large queue remaining at the end of the time period.

PICADY 5 Run Successful

PICADY		
GUI Version: 5.1 AD Analysis Program Release: 4.0 (SEPT 2008)		
© Copyright TRL Limited, 2008 Adapted from PICADY/3 which is Crown Copyright by permission of the controller of HMSO		
For sales and distribution information, program advice and maintenance, contact:		
TRL Limited Crowthorne House Nine Mile Ride Wokingham, Berks. RG40 3GA, UK		Tel: +44 (0)1344 770758 Fax: +44 (0)1344 770864 E-mail: software@trl.co.uk Web: www.trlsoftware.co.uk
The user of this computer program for the solution of an engineering problem is in no way relieved of their responsibility for the correctness of the solution		

Run Analysis

Parameter	Values
File Run	I:\..\Blackthorn Dr_Development\118139 Blackthorn Dr_Development T-Junction 2018 10 11.vpi
Date Run	16 October 2018
Time Run	14:44:23
Driving Side	Drive On The Left

Arm Names and Flow Scaling Factors

Arm	Arm Name	Flow Scaling Factor (%)
Arm A	Blackthorn Dr East	100
Arm B	Development	100
Arm C	Blackthorn Dr West	100

Stream Labelling Convention

Stream A-B contains traffic going from A to B etc.

Run Information

Parameter	Values
Run Title	Blackthorn Dr/Development T-Junction
Location	Sandyford, Dublin 18
Date	11 October 2018
Enumerator	J Noone
Job Number	118139
Status	TIA
Client	IRES Residential Properties Ltd
Description	-

Geometric Data

Geometric Parameters


Parameter	Minor Arm B
Major Road Carriageway Width (m)	15.00
Major Road Kerbed Central Reserve Width (m)	0.00
Major Road Right Turning Lane Width (m)	3.30
Minor Road First Lane Width (m)	4.40
Minor Road Visibility To Right (m)	31
Minor Road Visibility To Left (m)	32
Major Road Right Turn Visibility (m)	200
Major Road Right Turn Blocks Traffic	Yes

Slope and Intercept Values

Stream	Intercept for Stream B-A	Slope for A-B	Slope for A-C	Slope for C-A	Slope for C-B
B-A	573.725	0.064	0.161	0.101	0.230
B-C	733.641	0.068	0.173	-	-
C-B	772.365	0.182	0.182	-	-

Note: Streams may be combined in which case capacity will be adjusted
 These values do not allow for any site-specific corrections

Junction Diagram



Demand Data

Modelling Periods

Parameter	Period	Duration (min)	Segment Length (min)
First Modelling Period	07:45-09:15	90	15
Second Modelling Period	16:45-18:15	90	15

ODTAB Turning Counts

Demand Set: 2016 AM Existing Traffic

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	57.0	319.0
Arm B	27.0	0.0	44.0
Arm C	616.0	56.0	0.0

Demand Set: 2016 PM Existing Traffic

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	61.0	399.0
Arm B	52.0	0.0	53.0
Arm C	505.0	49.0	0.0

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	61.0	368.0
Arm B	29.0	0.0	47.0
Arm C	784.0	60.0	0.0

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	65.0	531.0
Arm B	56.0	0.0	57.0
Arm C	602.0	52.0	0.0

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	67.0	381.0
Arm B	2.0	0.0	22.0
Arm C	803.0	74.0	0.0

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	59.0	540.0
Arm B	63.0	0.0	73.0
Arm C	608.0	52.0	0.0

Demand Set: 2031 AM Do Nothing - Existing Traffic+Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	69.0	413.0
Arm B	33.0	0.0	53.0
Arm C	871.0	68.0	0.0

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	75.0	426.0
Arm B	6.0	0.0	28.0
Arm C	890.0	82.0	0.0

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	74.0	588.0
Arm B	63.0	0.0	64.0
Arm C	673.0	59.0	0.0

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	0.0	68.0	596.0
Arm B	70.0	0.0	80.0
Arm C	679.0	59.0	0.0

ODTAB Synthesised Flows

Demand Set: 2016 AM Existing Traffic

Modelling Period: 07:45-09:15

Arm	Rising Time	Rising Flow (veh/min)	Peak Time	Peak Flow (veh/min)	Falling Time	Falling Flow (veh/min)
Arm A	08:00	4.700	08:30	7.050	09:00	4.700
Arm B	08:00	0.887	08:30	1.331	09:00	0.887
Arm C	08:00	8.400	08:30	12.600	09:00	8.400

Heavy Vehicles Percentages

Demand Set: 2016 AM Existing Traffic

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2016 PM Existing Traffic

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 AM Do Nothing - Existing Traffic+Permitted Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

From/To	Arm A	Arm B	Arm C
Arm A	-	0.0	0.0
Arm B	0.0	-	0.0
Arm C	0.0	0.0	-

Queues & Delays

Demand Set: 2016 AM Existing Traffic
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	0.89	9.81	0.091	-	0.00	0.10	-	1.4	0.11
	C-AB	0.70	12.01	0.058	-	0.00	0.06	-	0.9	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.72	-	-	-	-	-	-	-	-
	A-C	4.00	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	1.06	9.56	0.111	-	0.10	0.12	-	1.8	0.12
	C-AB	0.84	11.85	0.071	-	0.06	0.08	-	1.1	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.85	-	-	-	-	-	-	-	-
	A-C	4.78	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	1.30	9.21	0.142	-	0.12	0.16	-	2.4	0.13
	C-AB	1.03	11.62	0.088	-	0.08	0.10	-	1.4	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.05	-	-	-	-	-	-	-	-
	A-C	5.85	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	1.30	9.21	0.142	-	0.16	0.16	-	2.5	0.13
	C-AB	1.03	11.62	0.088	-	0.10	0.10	-	1.5	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.05	-	-	-	-	-	-	-	-
	A-C	5.85	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	1.06	9.56	0.111	-	0.16	0.13	-	1.9	0.12
	C-AB	0.84	11.85	0.071	-	0.10	0.08	-	1.2	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.85	-	-	-	-	-	-	-	-
	A-C	4.78	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	0.89	9.81	0.091	-	0.13	0.10	-	1.5	0.11
	C-AB	0.70	12.01	0.058	-	0.08	0.06	-	0.9	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.72	-	-	-	-	-	-	-	-
	A-C	4.00	-	-	-	-	-	-	-	-

Demand Set: 2016 PM Existing Traffic
Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	1.32	9.34	0.141	-	0.00	0.16	-	2.4	0.12
	C-AB	0.61	11.82	0.052	-	0.00	0.05	-	0.8	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.77	-	-	-	-	-	-	-	-
	A-C	5.01	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	1.57	9.06	0.174	-	0.16	0.21	-	3.0	0.13
	C-AB	0.73	11.62	0.063	-	0.05	0.07	-	1.0	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.91	-	-	-	-	-	-	-	-
	A-C	5.98	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	1.93	8.66	0.222	-	0.21	0.28	-	4.1	0.15
	C-AB	0.90	11.34	0.079	-	0.07	0.09	-	1.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.12	-	-	-	-	-	-	-	-
	A-C	7.32	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	1.93	8.66	0.222	-	0.28	0.28	-	4.3	0.15
	C-AB	0.90	11.34	0.079	-	0.09	0.09	-	1.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.12	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
	A-C	7.32	-	-	-	-	-	-	-	-
17:45-18:00	B-AC	1.57	9.05	0.174	-	0.28	0.21	-	3.3	0.13
	C-AB	0.73	11.62	0.063	-	0.09	0.07	-	1.0	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.91	-	-	-	-	-	-	-	-
	A-C	5.98	-	-	-	-	-	-	-	-
18:00-18:15	B-AC	1.32	9.34	0.141	-	0.21	0.17	-	2.5	0.12
	C-AB	0.61	11.82	0.052	-	0.07	0.06	-	0.8	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.77	-	-	-	-	-	-	-	-
	A-C	5.01	-	-	-	-	-	-	-	-

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	0.95	9.57	0.100	-	0.00	0.11	-	1.6	0.12
	C-AB	0.75	11.89	0.063	-	0.00	0.07	-	1.0	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.77	-	-	-	-	-	-	-	-
	A-C	4.62	-	-	-	-	-	-	-	-
08:00-08:15	B-AC	1.14	9.26	0.123	-	0.11	0.14	-	2.0	0.12
	C-AB	0.90	11.70	0.077	-	0.07	0.08	-	1.2	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.91	-	-	-	-	-	-	-	-
	A-C	5.51	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	1.39	8.83	0.158	-	0.14	0.19	-	2.7	0.13
	C-AB	1.10	11.44	0.096	-	0.08	0.11	-	1.6	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.12	-	-	-	-	-	-	-	-
	A-C	6.75	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	1.39	8.83	0.158	-	0.19	0.19	-	2.8	0.13
	C-AB	1.10	11.44	0.096	-	0.11	0.11	-	1.6	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.12	-	-	-	-	-	-	-	-
	A-C	6.75	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	1.14	9.26	0.123	-	0.19	0.14	-	2.2	0.12
	C-AB	0.90	11.70	0.077	-	0.11	0.08	-	1.3	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.91	-	-	-	-	-	-	-	-
	A-C	5.51	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	0.95	9.56	0.100	-	0.14	0.11	-	1.7	0.12
	C-AB	0.75	11.89	0.063	-	0.08	0.07	-	1.0	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.77	-	-	-	-	-	-	-	-
	A-C	4.62	-	-	-	-	-	-	-	-

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	1.42	8.96	0.158	-	0.00	0.19	-	2.7	0.13
	C-AB	0.65	11.51	0.057	-	0.00	0.06	-	0.9	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.82	-	-	-	-	-	-	-	-
	A-C	6.66	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	1.69	8.60	0.197	-	0.19	0.24	-	3.5	0.14
	C-AB	0.78	11.25	0.069	-	0.06	0.07	-	1.1	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.97	-	-	-	-	-	-	-	-

	A-C	7.96	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	2.07	8.10	0.256	-	0.24	0.34	-	4.9	0.17
	C-AB	0.95	10.88	0.088	-	0.07	0.10	-	1.4	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.19	-	-	-	-	-	-	-	-
	A-C	9.74	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	2.07	8.10	0.256	-	0.34	0.34	-	5.1	0.17
	C-AB	0.95	10.88	0.088	-	0.10	0.10	-	1.4	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.19	-	-	-	-	-	-	-	-
	A-C	9.74	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	1.69	8.60	0.197	-	0.34	0.25	-	3.8	0.15
	C-AB	0.78	11.25	0.069	-	0.10	0.07	-	1.1	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.97	-	-	-	-	-	-	-	-
	A-C	7.96	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	1.42	8.96	0.158	-	0.25	0.19	-	2.9	0.13
	C-AB	0.65	11.51	0.057	-	0.07	0.06	-	0.9	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.82	-	-	-	-	-	-	-	-
	A-C	6.66	-	-	-	-	-	-	-	-

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	0.30	10.88	0.028	-	0.00	0.03	-	0.4	0.09
	C-AB	0.93	11.85	0.078	-	0.00	0.08	-	1.3	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.84	-	-	-	-	-	-	-	-
	A-C	4.78	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	0.36	10.66	0.034	-	0.03	0.03	-	0.5	0.10
	C-AB	1.11	11.65	0.095	-	0.08	0.10	-	1.6	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.00	-	-	-	-	-	-	-	-
	A-C	5.71	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	0.44	10.36	0.043	-	0.03	0.04	-	0.6	0.10
	C-AB	1.36	11.38	0.119	-	0.10	0.13	-	2.0	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.23	-	-	-	-	-	-	-	-
	A-C	6.99	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	0.44	10.36	0.043	-	0.04	0.04	-	0.7	0.10
	C-AB	1.36	11.38	0.119	-	0.13	0.14	-	2.0	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.23	-	-	-	-	-	-	-	-
	A-C	6.99	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	0.36	10.66	0.034	-	0.04	0.04	-	0.5	0.10
	C-AB	1.11	11.65	0.095	-	0.14	0.11	-	1.6	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.00	-	-	-	-	-	-	-	-
	A-C	5.71	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	0.30	10.88	0.028	-	0.04	0.03	-	0.4	0.09
	C-AB	0.93	11.85	0.078	-	0.11	0.09	-	1.3	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.84	-	-	-	-	-	-	-	-

	A-C	4.78	-	-	-	-	-	-	-	-
--	-----	------	---	---	---	---	---	---	---	---

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	1.71	9.05	0.189	-	0.00	0.23	-	3.3	0.14
	C-AB	0.65	11.50	0.057	-	0.00	0.06	-	0.9	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.74	-	-	-	-	-	-	-	-
	A-C	6.78	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	2.04	8.69	0.234	-	0.23	0.30	-	4.4	0.15
	C-AB	0.78	11.24	0.069	-	0.06	0.07	-	1.1	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.88	-	-	-	-	-	-	-	-
	A-C	8.09	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	2.50	8.19	0.305	-	0.30	0.43	-	6.2	0.18
	C-AB	0.95	10.87	0.088	-	0.07	0.10	-	1.4	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.08	-	-	-	-	-	-	-	-
	A-C	9.91	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	2.50	8.19	0.305	-	0.43	0.43	-	6.5	0.18
	C-AB	0.95	10.87	0.088	-	0.10	0.10	-	1.4	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.08	-	-	-	-	-	-	-	-
	A-C	9.91	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	2.04	8.69	0.234	-	0.43	0.31	-	4.8	0.15
	C-AB	0.78	11.24	0.069	-	0.10	0.07	-	1.1	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.88	-	-	-	-	-	-	-	-
	A-C	8.09	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	1.71	9.05	0.189	-	0.31	0.23	-	3.6	0.14
	C-AB	0.65	11.50	0.057	-	0.07	0.06	-	0.9	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.74	-	-	-	-	-	-	-	-
	A-C	6.78	-	-	-	-	-	-	-	-

Demand Set: 2031 AM Do Nothing - Existing Traffic+Permitted Dev
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	1.08	9.37	0.115	-	0.00	0.13	-	1.9	0.12
	C-AB	0.85	11.77	0.072	-	0.00	0.08	-	1.2	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.87	-	-	-	-	-	-	-	-
	A-C	5.18	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:00-08:15	B-AC	1.29	9.02	0.143	-	0.13	0.16	-	2.4	0.13
	C-AB	1.02	11.56	0.088	-	0.08	0.10	-	1.4	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.03	-	-	-	-	-	-	-	-
	A-C	6.19	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	1.58	8.53	0.185	-	0.16	0.22	-	3.3	0.14
	C-AB	1.25	11.26	0.111	-	0.10	0.12	-	1.9	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.27	-	-	-	-	-	-	-	-
	A-C	7.58	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	1.58	8.53	0.185	-	0.22	0.23	-	3.4	0.14
	C-AB	1.25	11.26	0.111	-	0.12	0.12	-	1.9	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.27	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
	A-C	7.58	-	-	-	-	-	-	-	-
08:45-09:00	B-AC	1.29	9.02	0.143	-	0.23	0.17	-	2.6	0.13
	C-AB	1.02	11.56	0.088	-	0.12	0.10	-	1.5	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.03	-	-	-	-	-	-	-	-
	A-C	6.19	-	-	-	-	-	-	-	-
09:00-09:15	B-AC	1.08	9.37	0.115	-	0.17	0.13	-	2.0	0.12
	C-AB	0.85	11.77	0.072	-	0.10	0.08	-	1.2	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.87	-	-	-	-	-	-	-	-
	A-C	5.18	-	-	-	-	-	-	-	-

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev
Modelling Period: 07:45-09:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
07:45-08:00	B-AC	0.43	10.25	0.042	-	0.00	0.04	-	0.6	0.10
	C-AB	1.03	11.73	0.088	-	0.00	0.10	-	1.4	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.94	-	-	-	-	-	-	-	-
	A-C	5.35	-	-	-	-	-	-	-	-
08:00-08:15	B-AC	0.51	9.96	0.051	-	0.04	0.05	-	0.8	0.11
	C-AB	1.23	11.51	0.107	-	0.10	0.12	-	1.8	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.12	-	-	-	-	-	-	-	-
	A-C	6.38	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:15-08:30	B-AC	0.62	9.55	0.065	-	0.05	0.07	-	1.0	0.11
	C-AB	1.50	11.20	0.134	-	0.12	0.15	-	2.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.38	-	-	-	-	-	-	-	-
	A-C	7.82	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:30-08:45	B-AC	0.62	9.55	0.065	-	0.07	0.07	-	1.0	0.11
	C-AB	1.50	11.20	0.134	-	0.15	0.15	-	2.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.38	-	-	-	-	-	-	-	-
	A-C	7.82	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
08:45-09:00	B-AC	0.51	9.96	0.051	-	0.07	0.05	-	0.8	0.11
	C-AB	1.23	11.51	0.107	-	0.15	0.12	-	1.8	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.12	-	-	-	-	-	-	-	-
	A-C	6.38	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
09:00-09:15	B-AC	0.43	10.25	0.042	-	0.05	0.04	-	0.7	0.10
	C-AB	1.03	11.73	0.088	-	0.12	0.10	-	1.5	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.94	-	-	-	-	-	-	-	-
	A-C	5.35	-	-	-	-	-	-	-	-

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	1.59	8.75	0.182	-	0.00	0.22	-	3.2	0.14
	C-AB	0.74	11.36	0.065	-	0.00	0.07	-	1.0	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.93	-	-	-	-	-	-	-	-
	A-C	7.38	-	-	-	-	-	-	-	-

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	1.90	8.35	0.228	-	0.22	0.29	-	4.3	0.15
	C-AB	0.88	11.07	0.080	-	0.07	0.09	-	1.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.11	-	-	-	-	-	-	-	-

	A-C	8.81	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	2.33	7.78	0.300	-	0.29	0.42	-	6.1	0.18
	C-AB	1.08	10.66	0.102	-	0.09	0.11	-	1.7	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.36	-	-	-	-	-	-	-	-
	A-C	10.79	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	2.33	7.78	0.300	-	0.42	0.42	-	6.3	0.18
	C-AB	1.08	10.66	0.102	-	0.11	0.11	-	1.7	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.36	-	-	-	-	-	-	-	-
	A-C	10.79	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	1.90	8.35	0.228	-	0.42	0.30	-	4.6	0.16
	C-AB	0.88	11.07	0.080	-	0.11	0.09	-	1.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.11	-	-	-	-	-	-	-	-
	A-C	8.81	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	1.59	8.75	0.182	-	0.30	0.23	-	3.5	0.14
	C-AB	0.74	11.36	0.065	-	0.09	0.07	-	1.1	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.93	-	-	-	-	-	-	-	-
	A-C	7.38	-	-	-	-	-	-	-	-

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
16:45-17:00	B-AC	1.88	8.83	0.213	-	0.00	0.27	-	3.8	0.14
	C-AB	0.74	11.36	0.065	-	0.00	0.07	-	1.0	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.85	-	-	-	-	-	-	-	-
	A-C	7.48	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:00-17:15	B-AC	2.25	8.43	0.267	-	0.27	0.36	-	5.2	0.16
	C-AB	0.88	11.06	0.080	-	0.07	0.09	-	1.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.02	-	-	-	-	-	-	-	-
	A-C	8.93	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:15-17:30	B-AC	2.75	7.87	0.350	-	0.36	0.53	-	7.6	0.19
	C-AB	1.08	10.65	0.102	-	0.09	0.11	-	1.7	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.25	-	-	-	-	-	-	-	-
	A-C	10.94	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:30-17:45	B-AC	2.75	7.87	0.350	-	0.53	0.53	-	8.0	0.20
	C-AB	1.08	10.65	0.102	-	0.11	0.11	-	1.7	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.25	-	-	-	-	-	-	-	-
	A-C	10.94	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
17:45-18:00	B-AC	2.25	8.43	0.267	-	0.53	0.37	-	5.7	0.16
	C-AB	0.88	11.06	0.080	-	0.11	0.09	-	1.3	0.10
	C-A	-	-	-	-	-	-	-	-	-
	A-B	1.02	-	-	-	-	-	-	-	-
	A-C	8.93	-	-	-	-	-	-	-	-
Segment	Stream	Demand (veh/min)	Capacity (veh/min)	RFC	Ped. Flow (ped/min)	Start Queue (veh)	End Queue (veh)	Geometric Delay (veh.min/segment)	Delay (veh.min/segment)	Mean Arriving Vehicle Delay (min)
18:00-18:15	B-AC	1.88	8.83	0.213	-	0.37	0.27	-	4.2	0.14
	C-AB	0.74	11.36	0.065	-	0.09	0.07	-	1.1	0.09
	C-A	-	-	-	-	-	-	-	-	-
	A-B	0.85	-	-	-	-	-	-	-	-

	A-C	7.48	-	-	-	-	-	-	-	-
--	-----	------	---	---	---	---	---	---	---	---

Entry capacities marked with an '(X)' are dominated by a pedestrian crossing in that time segment.
 In time segments marked with a '(B)', traffic leaving the junction may block back from a crossing so impairing normal operation of the junction.
 Delays marked with '##' could not be calculated.

Overall Queues & Delays

Queueing Delay Information Over Whole Period

Demand Set: 2016 AM Existing Traffic
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	97.7	65.2	11.6	0.1	11.6	0.1
C-AB	77.1	51.4	7.0	0.1	7.0	0.1
C-A	-	-	-	-	-	-
A-B	78.5	52.3	-	-	-	-
A-C	439.1	292.7	-	-	-	-
All	1540.2	1026.8	18.6	0.0	18.6	0.0

Demand Set: 2016 PM Existing Traffic
Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	144.5	96.3	19.6	0.1	19.6	0.1
C-AB	67.4	45.0	6.2	0.1	6.2	0.1
C-A	-	-	-	-	-	-
A-B	84.0	56.0	-	-	-	-
A-C	549.2	366.1	-	-	-	-
All	1540.2	1026.8	25.8	0.0	25.8	0.0

Demand Set: 2021 AM Do Nothing - Existing Traffic + Permitted Dev
Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	104.6	69.7	13.0	0.1	13.0	0.1
C-AB	82.6	55.1	7.7	0.1	7.7	0.1
C-A	-	-	-	-	-	-
A-B	84.0	56.0	-	-	-	-
A-C	506.5	337.7	-	-	-	-
All	1856.8	1237.9	20.7	0.0	20.7	0.0

Demand Set: 2021 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	155.5	103.7	23.0	0.1	23.0	0.1
C-AB	71.6	47.7	6.9	0.1	6.9	0.1
C-A	-	-	-	-	-	-
A-B	89.5	59.6	-	-	-	-
A-C	730.9	487.3	-	-	-	-
All	1876.1	1250.7	29.9	0.0	29.9	0.0

Demand Set: 2021 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	33.0	22.0	3.2	0.1	3.2	0.1
C-AB	101.9	67.9	9.8	0.1	9.8	0.1
C-A	-	-	-	-	-	-
A-B	92.2	61.5	-	-	-	-
A-C	524.4	349.6	-	-	-	-
All	1856.8	1237.9	13.0	0.0	13.0	0.0

Demand Set: 2021 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	187.2	124.8	28.9	0.2	28.9	0.2
C-AB	71.6	47.7	6.9	0.1	6.9	0.1
C-A	-	-	-	-	-	-
A-B	81.2	54.1	-	-	-	-
A-C	743.3	495.5	-	-	-	-
All	1920.1	1280.1	35.8	0.0	35.8	0.0

Demand Set: 2031 AM Do Nothing - Existing Traffic+Permitted Dev

Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	118.4	78.9	15.5	0.1	15.5	0.1
C-AB	93.6	62.4	9.0	0.1	9.0	0.1
C-A	-	-	-	-	-	-
A-B	95.0	63.3	-	-	-	-
A-C	568.5	379.0	-	-	-	-
All	2074.3	1382.8	24.5	0.0	24.5	0.0

Demand Set: 2031 AM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 07:45-09:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	46.8	31.2	5.0	0.1	5.0	0.1
C-AB	112.9	75.2	11.1	0.1	11.1	0.1
C-A	-	-	-	-	-	-
A-B	103.2	68.8	-	-	-	-
A-C	586.4	390.9	-	-	-	-
All	2074.3	1382.8	16.1	0.0	16.1	0.0

Demand Set: 2031 PM Do Nothing - Existing Traffic + Permitted Dev

Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	174.8	116.5	28.0	0.2	28.0	0.2
C-AB	81.2	54.1	8.1	0.1	8.1	0.1
C-A	-	-	-	-	-	-
A-B	101.9	67.9	-	-	-	-
A-C	809.3	539.6	-	-	-	-
All	2093.5	1395.7	36.0	0.0	36.0	0.0

Demand Set: 2031 PM Do Something - Existing Traffic+Permitted Dev+New Dev

Modelling Period: 16:45-18:15

Stream	Total Demand (veh)	Total Demand (veh/h)	Queueing Delay (min)	Queueing Delay (min/veh)	Inclusive Delay (min)	Inclusive Delay (min/veh)
B-AC	206.5	137.6	34.6	0.2	34.6	0.2
C-AB	81.2	54.1	8.1	0.1	8.1	0.1
C-A	-	-	-	-	-	-
A-B	93.6	62.4	-	-	-	-
A-C	820.3	546.9	-	-	-	-
All	2136.2	1424.1	42.7	0.0	42.7	0.0

Delay is that occurring only within the time period.

Inclusive delay includes delay suffered by vehicles which are still queuing after the end of the time period.

These will only be significantly different if there is a large queue remaining at the end of the time period.

PICADY 5 Run Successful