



**183106 - Crown Square Development
Phase 2, Galway City**

Engineering Planning Report Stage 3

July 2019

Document Control

Document Number: 183-106-PL2-SHD

| Revision | Description | Date | Prepared | Checked | Approved |
|----------|---------------|------------|-----------|------------|------------|
| PRO | Draft Review | 08/03/2019 | F. Timlin | D. Gallery | R. Stokes |
| PL0 | Stage 2 Issue | 13/03/2019 | F. Timlin | D. Gallery | R. Stokes |
| PL1 | Stage 3 Issue | 23/05/2019 | F. Timlin | D. Gallery | R. Stokes |
| PL2 | Stage 3 Issue | 09/07/2019 | F. Timlin | D. Gallery | C. O'Brien |

Table of Contents

| | |
|--|----|
| Document Control | i |
| Table of Contents..... | ii |
| 1 Introduction | 1 |
| 2 Foul Water Drainage Design | 3 |
| 2.1 Existing Foul Water Drainage..... | 3 |
| 2.2 Proposed Foul Water Drainage | 4 |
| 2.2.1 Foul Water Reduction Measures | 5 |
| 2.2.2 External Foul Water Drainage System | 5 |
| 2.2.3 Proposed Foul Water Drainage System | 5 |
| 2.2.4 Foul Water Drainage Suspended from Underside of Ground Floor Slab | 6 |
| 2.3 Phasing | 6 |
| 3 Surface Water Drainage Design | 7 |
| 3.1 Existing Surface Water Drainage..... | 7 |
| 3.2 Existing Site | 7 |
| 3.3 Proposed Surface Water Drainage | 8 |
| 3.3.1 Proposed Development Drainage Network | 8 |
| 3.3.2 General..... | 9 |
| 3.3.3 Attenuation Tanks..... | 9 |
| 3.3.4 Rainwater Harvesting | 9 |
| 3.3.5 Green Roofs | 9 |
| 3.3.6 Bypass Separators | 9 |
| 3.3.7 Green Areas | 9 |
| 3.4 Compliance with the GDSDS | 10 |
| 4 Watermain Design | 11 |
| 4.1 Existing Water Infrastructure..... | 11 |
| 4.2 Proposed Water Infrastructure..... | 12 |
| 4.2.1 Water Supply Demand | 12 |
| 4.2.2 Water Supply Demand | 12 |
| 4.2.3 Water demand Reduction Measures..... | 13 |
| 4.3 Phasing | 13 |
| 5 Flood Risk Assessment | 13 |
| 6 Traffic and Transportation Assessment | 14 |
| 7 Road Safety Audit | 15 |
| 8 Mobility Management Plan..... | 16 |

| | | |
|------------|---|--------|
| Appendix A | - Existing Services Record Drawings..... | A-XVII |
| Appendix B | - Foul Water Calculations - Micro Drainage | B-I |
| Appendix C | - Irish Water Letter of Feasibility | C-II |
| Appendix D | - Statement of Design Acceptance | D-III |
| Appendix E | - Rainfall Supporting Data | E-IV |
| Appendix F | - Surface Water Calculations - Micro Drainage | F-V |
| Appendix G | - Correspondence with Galway City Council..... | G-VI |
| Appendix H | - CFRAM Mapping | H-VII |

1 Introduction

This report was prepared to accompany a planning application for a proposed development on a site located at the junction of the Monivea & Joyce's Road, Mervue, Galway City. This report deals specifically with the surface water drainage, foul water drainage, watermain design and flood protection measures for this application.

The planning application has been divided into two phases. Phase 1, which relates to the office and hotel development on the western half of the site, was submitted to Galway City Council in November 2018. Phase 2, which relates to the residential development at the eastern half of the site, is the subject of this report, and this report forms part of the SHD application for Phase 2.

The Phase 2 development will consist of a residential scheme comprising 288 no. apartments and amenity accommodation with a gross floor area of circa 32,379 sqm; a commercial scheme with a cumulative gross floor area of 4,096 sqm; public realm and landscaping works, including pedestrian and cyclist linkages; and a double basement with pedestrian, cyclist and vehicular access.

Following discussions with Galway City Council, it was agreed that best approach to take to describe the engineering design - traffic, roads, drainage, water and flooding - would be to describe the design for the entire development. Therefore, the figures used in this report relating to the drainage and water design are based on the total load to be carried from the entire development, with the figures broken down into their contributing parts for clarity.

The mixed-use development project commenced on site in 2008. In late 2008, it was halted during the construction phase due to the sharp downturn in the economy and has remained in a partially-constructed phase since that time.

The site has been stripped to create a double basement area over the entire site footprint, and this has been partially infilled with a two-storey concrete frame in one area of the site adjacent to Monivea Road. This existing structure is a significant element. There are also a large number of foundations poured in other areas of the site, and sections of basement slab.

The development has a plan area of approximately 5.117 hectares in total. Access to the development will be via the Monivea Road and Joyce's Road. Figure 1 below indicates the proposed development within the surrounding development.




Figure 1 - Site Location of the Proposed Development

The Layout of the proposed scheme is detailed in the series of planning drawings by Henry J Lyons Architects accompanying this planning submission.

In preparation of this report and design of the development, PUNCH Consulting Engineers have liaised with the following parties:

1. Frank Clancy, Senior Executive Engineer, Water services, Galway City Council
2. John Sheehan, Executive Technician, Water services, Galway City Council
3. Brian Day, Senior Design Engineer, Irish Water
4. James O'Malley, Design Engineer, Irish Water

2 Foul Water Drainage Design

2.1 Existing Foul Water Drainage

On the basis of available records, the following foul water drainage exists adjacent to the site of the proposed development.

- A 675mm Concrete sewer is located on the Monivea Road, which falls in a south-westerly direction.
- A 225mm Concrete sewer is located on the Tuam Road, which falls in a south-westerly direction.

It should be noted that diversion works of the 675mm concrete sewer on the Monivea Road were undertaken in 2008, please refer to Figure 2 below and Appendix A for illustration of the existing sewer network.




Figure 2 - Existing Foul Drainage Surrounding Site (Source: Irish Water Record Drawing)

2.2 Proposed Foul Water Drainage

Foul water drainage has been designed using WinDes Microdrainage software with reference to the following documentation:

1. "Recommendations for Site Development Works for Housing Areas" published by DOE
2. "Code of Practice for Wastewater Infrastructure" published by Irish Water - particularly Appendix D - Wastewater Flow Rates for Design
3. "Wastewater Engineers Treatment & Reuse" by Metcalf & Eddy

On the basis of the documentation referenced above, the following wastewater characteristics have been taken:

1. 165 litres/ person/ day for residential units
2. 250 litres/ guest/ day for hotel rooms (assuming 2 no. guests per room)
3. 300 litres/100sq.m/day for hotel amenity area
4. 300 litres/100sq.m/day for retail area
5. 300 litres/100sq.m/day for fitness/ leisure area
6. 300 litres/100sq.m/day for restaurant/ coffee shop area
7. 300 litres/100sq.m/day for medical centre/ pharmacy/ other area
8. 400 litres/100sq.m/day for convenience store area
9. 750 litres/100sq.m/day for ancillary residential accommodation (Concierge, Games Room, Movie Room etc.)
10. 750 litres/100sq.m/day for office area

Table 1 below shows the foul flows for the development, indicating proposed dry weather flow, as well as the peak flows. The total increase in dry weather flow (DWF) associated with the site was calculated as 6.74 l/s with an increase in peak flow of 40.44 l/s. The daily foul loading is 582.177m³. The sewers will be designed for the peak flow.

Table 1: Calculation of Peak Daily Foul Flow

| Building Use | Quantity | Rate per day | Daily Foul Loading (l/day) | DWF (l/s) | Design Flow (6DWF) (l/s) |
|---|------------------------|------------------------|----------------------------|-----------|--------------------------|
| Total Commercial Floor Area | 39,445 m ² | 750l/100m ² | 295,838 | 3.42 | 20.52 |
| Total Residential Units | 288 units/1030 persons | 165l/person | 169,950 | 1.97 | 11.82 |
| Total Hotel Rooms | 175 rooms | 500l/room | 87,500 | 1.01 | 6.06 |
| Total Hotel Amenities Area | 2,490 m ² | 300l/100m ² | 7,470 | 0.09 | 0.54 |
| Total Ancillary Residential Accommodation | 1,275 m ² | 750l/100m ² | 9,563 | 0.11 | 0.66 |

| | | | | | |
|------------------------------------|----------------------|------------------------|----------------|-------------|--------------|
| Total Fitness/Leisure Area | 1,140 m ² | 300l/100m ² | 3,420 | 0.04 | 0.24 |
| Total Medical /Pharmacy/Other Area | 1,962 m ² | 300l/100m ² | 5,886 | 0.07 | 0.42 |
| Total Restaurant/Coffee Shop Area | 550 m ² | 300l/100m ² | 1,650 | 0.02 | 0.12 |
| Total Convenience Store Area | 225 m ² | 400l/100m ² | 900 | 0.01 | 0.06 |
| TOTAL | | | 582,177 | 6.74 | 40.44 |

The general approach taken for the design of the proposed foul water drainage system is to collect all foul water from ground level upwards and discharge to the public foul water sewer network by gravity via an external below ground drainage system. This will minimise the volume of foul water which will need to be pumped from the development and, furthermore, reduce the volume of emergency storage required in the pumping station.

It is proposed to make two connections to the public foul water sewer system on the 675mm diameter concrete foul sewer on the Monivea Road, one at the West of the site and one to the East.

2.2.1 Foul Water Reduction Measures

It is noted that the development will incorporate water conservation measures in the sanitary facilities. These will include low flow dual flush toilets, and monobloc low volume push taps. These will reduce the foul discharge from the development.

2.2.2 External Foul Water Drainage System

A below ground drainage system will be provided for the site. This will deal with foul water from both the residential/commercial developments and the suspended drainage system in the basement. It is proposed to connect this drainage system to the 675mm diameter public foul water sewer located in the Monivea Road.

2.2.3 Proposed Foul Water Drainage System

The proposed foul sewers have been designed using MicroDrainage software in accordance with the “Irish Water Code of Practice for Wastewater Infrastructure” design guide. Please refer to Appendix B for details of Foul Water Calculations.

In the basement, it is proposed that a pumping station will be provided to pump effluent from showers and toilets being provided for staff that walk or cycle to the proposed development. The effluent will be pumped to a decompression manhole in the courtyard and flow by gravity to the proposed foul drainage network.

In accordance with the GDSDS, any surface water that is generated within the -1 & -2 basement will run through a bypass interceptor prior to being pumped to the foul water system, this figure is estimated at 0.04l/s based upon approximately 1600 parking bays (Refer to Architects site layout drawings for more details) at 2l/ bay/ day, in accordance with the “Design Recommendations for Multi Storey and Underground Car Parks” published by the Institute of Structural Engineers.

A pre-connection enquiry form was issued to Irish Water and a response was received stating “subject to a valid connection agreement being put in place, your proposed connection to the Irish Water network can be facilitated.” Please refer to Appendix C for details of the letter of feasibility from Irish Water.

Please refer to Appendix D for “Statement of Design Acceptance” issued by Irish Water.

2.2.4 Foul Water Drainage Suspended from Underside of Ground Floor Slab

Vertical stacks collecting foul water from the above storeys will enter the basement level at service riser locations. These will be connected to drainage pipes suspended from the underside of the ground floor slab and where necessary, strapped to the basement wall. These will penetrate the basement wall at various locations and connect to the external drainage system. Adequate protection will be provided to all drainage strapped to the basement wall face to ensure damage is not caused from moving vehicles.

2.3 Phasing

It is proposed that the residential units are to be constructed concurrently. The number of units and the total wastewater demand for the residential units is outlined below.

Table 2: Wastewater demand

| Item | No. units | Total design demand |
|-------------------------|-----------|---------------------|
| Total residential units | 288 | 11.82 l/s |

3 Surface Water Drainage Design

3.1 Existing Surface Water Drainage

On the basis of available records, the following public surface water drainage exists adjacent to the development site:

- A 450mm Concrete sewer is located on the Monivea Road, which falls in a south-westerly direction.
- A 600mm Concrete sewer is located on the Tuam Road, which falls in a south-westerly direction.

The existing site is currently impermeable with significant excavation works having been previously undertaken. Refer to Figure 3 below and Appendix A for illustration of the existing sewer network.




Figure 3 - Existing Storm Drainage Surrounding Site (Source: Irish Water Record Drawing)

3.2 Existing Site

The existing permitted development commenced construction in 2008. However, due to the economic downturn it was abandoned in late 2008. Currently there is a large excavation with parts of the impermeable concrete frame car park installed on site. The general Topography of the site excluding the excavation is largely flat with a gentle slope falling towards the West of the site. Levels vary on Joyce's Rd from 28-29mAOD, and rise to approx. 30mAOD on Monivea Road at the eastern extremity of the site. The excavated site area has been reduced to formation level for the original basement which was at an FFL of 23.3mAOD. The proposed basement level under this planning application is also to be at 23.3mAOD.

3.3 Proposed Surface Water Drainage

The proposed surface water drainage system has been designed with reference to the following documents:

1. "Recommendations for Site Development Works for Housing Areas" - DOE
2. "Greater Dublin Strategic Drainage Study" (GDSDS)
3. CIRIA Publications C753 - "The SuDS Manual"
4. Galway City Development Plan 2017-2023

The drainage system has been designed with the aim of providing a sustainable drainage solution ensuring, in so far as feasible, that the development has a minimal impact on the existing public surface water sewer system. This is achieved with the incorporation of Sustainable urban Drainage Systems (SuDS).

The Galway City Development Plan 2017-2023 in conjunction with the Greater Dublin Strategic Drainage Study (GDSDS) requires that the site discharge is reduced. The runoff is to be reduced for the 1% AEP (1:100-year storm return period), with an additional 10% to be added to rainfall to allow for climate change.

Similar to the design of foul water drainage, the general approach taken for the design of the proposed surface water drainage system is to collect all surface water from ground level upwards and discharge to the public surface water sewer network by gravity via an external below ground drainage system. This will minimise the volume of surface water which will need to be pumped from the development, hence reducing the whole life cost and impact for the development.

3.3.1 Proposed Development Drainage Network

The proposed development has been designed using MicroDrainage software.

An M5-60 of 17.5mm and a Ratio (R) of 0.300 was utilised in the model.

The model has analysed a range of storms at the 1% AEP (1 in 100-year return period storm), with a 10% additional rainfall to allow for climate change.

A value for the SAAR for the site has been obtained from the HR Wallingford website. This value is 1281mm. A copy of these results is included in Appendix E.

The surface water runoff from the proposed development is to be entirely separate from the development's foul sewerage network development drainage.

All surface water run-off from roof areas and hardstanding areas shall be collected in the gravity pipe network. The surface water from any open deck parking areas or pavements shall be collected via a series of gullies and channels.

Any surface water that is generated within the -1 & -2 basement will run through a bypass interceptor prior to being pumped to the foul water system, this figure is estimated at 0.04l/s based upon approximately 1600 parking bays at 2l/ bay/ day.

New surface water connections will be designed to connect by gravity to the existing public drainage network, with 70% of limited forward flow discharging to the Tuam Road located north of the site and the remainder discharging to the Monivea Road located south of the development.

A detailed utility survey is currently being undertaken, to ascertain which services could be utilised as part of the new network.

On the eastern half of the site, a portion of the external podium level drops down to Basement -1 level. Therefore, it will not be possible to discharge surface water from this area by gravity to the public sewer. Surface water from the proposed reduced podium area on site will be attenuated and then pumped via rising main to the North of the site where it will connect into the main line of the proposed surface water drainage network.

Please refer to Appendix F for MicroDrainage calculations related to proposed surface water drainage.

3.3.2 General

The proposed development has been assessed in relation to Sustainable Urban Drainage Systems (SuDS).

Please note discussions have been held with Galway City Council Water services Department as regards the surface water strategy. Please refer to Appendix G for memorandum in regard to discussions.

3.3.3 Attenuation Tanks

The proposed attenuation tanks will be sized to reduce the runoff from the site to 2l/ha/s for the 1% AEP (1:100 year storm return period) storm, with 10% additional rainfall to allow for climate change in accordance with the recommendations set out in the Greater Dublin Strategic Drainage Study. The result of this analysis requires 4 no. Attenuation tanks with a combined liquid storage of 2056 cu.m. Most of the attenuation tanks will be located outside the footprint of the basement structure.

Gullies and linear drainage channels will be provided as required to prevent surface water ponding on site and to ensure that no surface water discharges on to the public road and footpath surface.

3.3.4 Rainwater Harvesting

It is proposed to utilise rainwater recovered from the apartment rooftops for flushing of toilets, wash down of car park and bin stores, watering of green areas, and perhaps topping up of the sprinkler tanks which are all a waste of potable water.

The grey-water recovered on the site would normally go directly to the storm water drain. By recycling this rain water, less drawdown will occur from the existing watermains and has the added benefit of limiting rainwater entering the storm sewer.

3.3.5 Green Roofs

It is proposed to provide a large extent of extensive green roofs within the proposed development. This shall be provided at roof level and at podium level. Green roofs are widely recognised as an effective SuDS solution and an important tool in mitigating the adverse effects of development on rainfall run-off and for managing urban flood risk.

Research in the UK by Kellagher and Lauchlan (2005)¹ and CIRIA C753 (The SuDS Manual) indicates that green roofs are effective in providing both attenuation and volume reduction in runoff for minor rainfall events.

3.3.6 Bypass Separators

All surface water generated by the development will be passed through a class 1 bypass separator to capture and remove harmful material before the surface water discharges into the attenuation tanks.

Any surface water that is generated within the -1 & -2 basement will run through a bypass interceptor prior to being pumped to the foul water system, this figure is estimated at 0.04l/s based upon approximately 1600 parking bays at 2l/ bay/ day.

3.3.7 Green Areas

The proposed development will include several planted areas. These will be installed to reduce the surface water runoff on the site and to act as a SUDS measure for the development.

3.4 Compliance with the GDSDS

There are 4 sub criteria for level of services as set out in the GDSDS-RDP Volume 2 Section 6.3.4 (table 6.3).

- 1) No flooding on site, except where planned (30-year high estimated rainfall).
- 2) No internal property flooding (100-year high intensity rainfall event).
- 3) No internal flooding (100-year river event and critical duration for site).
- 4) No flooding off site except where specifically planned (100-year high intensity rainfall event).

The mitigation measures proposed as part of the surface water network and the treatment train as outlined above will allow the development to comply with the items, 1 - 4 noted above with regards to compliance with the GDSDS.

4 Watermain Design

4.1 Existing Water Infrastructure

The following existing public watermain infrastructure exists adjacent to the development

- 9 inch nominal diameter asbestos watermain located on Joyce's Road with a 150mm diameter Cast Iron connection to the proposed development.
- 300mm nominal diameter asbestos watermain located on Monivea Road.
- 300mm nominal diameter asbestos watermain located on the Tuam Road.

Refer to Figure 4 below and Appendix A for illustration of the existing sewer network.




Figure 4 - Existing Watermain Surrounding Site (Source: Irish Water Record Drawing)

4.2 Proposed Water Infrastructure

4.2.1 Water Supply Demand

The existing water supply connection is to be retained. The extent of the existing connection within the site is not known. This is intended to be confirmed through a utility survey currently being undertaken.

The residential units will be constructed concurrently, as such, the demand will be as outlined below.

4.2.2 Water Supply Demand

The design loading for foul drainage is used to evaluate an approximation of the water demand on the site, without additional flow to allow for surface water infiltration. On the basis of this, the following flow rates are to be used:

1. 150 litres/ unit/ day for residential units
2. 250 litres/ guest/ day for hotel rooms (assuming 2 no. guests per room)
3. 300 litres/100sq.m/day for hotel amenity area
4. 300 litres/100sq.m/day for retail area
5. 300 litres/100sq.m/day for fitness/ leisure area
6. 300 litres/100sq.m/day for restaurant/ coffee shop area
7. 300 litres/100sq.m/day for medical centre/ pharmacy/ other area
8. 400 litres/100sq.m/day for convenience store area
9. 750 litres/100sq.m/day for ancillary residential accommodation (Concierge, Games Room, Movie Room etc.)
10. 750 litres/100sq.m/day for office area

With reference to Irish Water's "Water Code of Practice," the average daily flow is calculated as the number of persons multiplied by the flow rate per person. The average day peak week flow is taken to be $1.25 \times$ the average flow, and the peak demand is taken to be the average day peak week flow multiplied by a peaking factor of 5.

This is demonstrated in Table 3 below. On the basis of this table, the development will have an average day peak drawdown of 8.18l/s and a peak demand flow of 41.01l/s.

Table 3: Water Average Day Peak Flow

| Component | Quantity | Rate per Day | Dry Weather Flow | Design Flow (5 DWF) (l/s) |
|---|------------------------|------------------------|------------------------------------|---------------------------|
| Total Commercial Floor Area | 39,445 m ² | 750l/100sqm | 369.80 cu.m/day or 4.28 l/s | 21.40 |
| Total Residential Units | 288 units/1030 persons | 150l/person | 193.13 cu.m/day or 2.24 l/s | 11.20 |
| Total Hotel Rooms | 175 Rooms | 500l/room | 109.4 cu.m/day or 1.27 l/s | 6.35 |
| Total Hotel Amenities Area | 2,490 m ² | 300l/100sqm | 9.34 cu.m/day or 0.11 l/s | 0.55 |
| Total Ancillary Residential Accommodation | 1,275 m ² | 750l/100m ² | 9.56 cu.m/day or 0.11 l/s | 0.66 |

| | | | | |
|--|----------------------|-------------|--------------------------------------|------------------|
| Total Fitness/Leisure Area | 1,140 m ² | 300l/100sqm | 4.28 cu.m/day or 0.05l/s | 0.25 |
| Total Medical/ Pharmacy/ Other Area | 1,962 m ² | 300l/100sqm | 7.36 cu.m/day or 0.09 l/s | 0.45 |
| Total Restaurant/ Coffee Shop Area | 550 m ² | 300l/100sqm | 2.06 cu.m/day or 0.02 l/s | 0.10 |
| Total Convenience Store Area | 225 m ² | 400l/100sqm | 1.13 cu.m/day or 0.01 l/s | 0.05 |
| Total | | | 8.18 l/s | 41.01 l/s |

A pre-connection enquiry form was issued to Irish Water and a response was received stating “subject to a valid connection agreement being put in place, your proposed connection to the Irish Water network can be facilitated. Please refer to Appendix C for details of the letter of feasibility from Irish Water.

Please refer to Appendix D for “Statement of Design Acceptance” issued by Irish Water.

4.2.3 Water demand Reduction Measures

To further reduce the water demand on Irish Water, water supplies and to reduce the foul discharge from the development, water conservation measures will be incorporated in the sanitary facilities throughout the development, e.g. dual flush toilets, Monobloc low volume push taps and waterless urinals.

4.3 Phasing

It is proposed that the residential units are to be constructed concurrently. The number of units and the total water demand for the residential units is outlined below.

Table 4: Water demand

| Item | No. units | Total design demand |
|-------------------------|-----------|---------------------|
| Total residential units | 288 | 11.20 l/s |

5 Flood Risk Assessment

A Flood Risk Assessment has been undertaken by PUNCH Consulting Engineers for the development which accompanies this planning submission.

6 Traffic and Transportation Assessment

The Traffic and Transport Assessment prepared for planning application 18/363 Crown Square included for the whole Crown Square development as envisaged at that date. As part of the design development, there have been minor amendments to the number of parking spaces and the various building areas and uses but the change in overall number of vehicle trips generated is inconsequential. The total car parking numbers is 1377, this is a small reduction of 25 no. parking spaces from those submitted with the Phase 1 planning application. Therefore, the TTA produced on 31/10/18 and previously submitted to GCC on 09/11/18 for Phase 1 is proposed to be included as part of the Phase 2 documentation with the updated parking numbers.


7 Road Safety Audit


A Road Safety Audit has been undertaken by CST Consulting Engineers for the development which accompanies this planning submission.


8 Mobility Management Plan

A Mobility Management Plan has been undertaken by PUNCH Consulting Engineers for the development which accompanies this planning submission. The Mobility Management Plan (MMP) prepared for planning application 18/363 Crown Square included for the whole Crown Square development as envisaged at that date. Following receipt of a further information (FI) request from Galway City Council on 11/01/19, the MMP was revised and resubmitted to GCC on 18/02/19. As part of the design development, there have been minor amendments to the number of parking spaces and various building areas and uses but the scope and content of the MMP is unchanged. The total car parking numbers submitted as part of the FI response have reduced slightly from those submitted with the Phase 1 planning application. Therefore, the revised MMP previously submitted to GCC on 18/02/19 is proposed to be included as part of the Phase 2 documentation with the updated parking numbers.

Appendix A - Existing Services Record Drawings








WARNING

THE MAP INDICATES THE APPROXIMATE LOCATION OF ESB TRANSMISSION AND DISTRIBUTION LINES. ONLY APPROXIMATE INFORMATION CAN BE PROVIDED. ESB IS NOT RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF THIS MAP. IT IS THE RESPONSIBILITY OF THE USER TO TAKE APPROPRIATE SAFETY MEASURES WHEN WORKING IN THE AREA OF THESE LINES. ESB IS NOT RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION CONTAINED IN THIS MAP. THE INFORMATION IS PROVIDED AS A GUIDE ONLY AND SHOULD NOT BE RELIED UPON AS A SOURCE OF DESIGN INFORMATION. ESB IS NOT RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION CONTAINED IN THIS MAP. THE INFORMATION IS PROVIDED AS A GUIDE ONLY AND SHOULD NOT BE RELIED UPON AS A SOURCE OF DESIGN INFORMATION. ESB IS NOT RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION CONTAINED IN THIS MAP. THE INFORMATION IS PROVIDED AS A GUIDE ONLY AND SHOULD NOT BE RELIED UPON AS A SOURCE OF DESIGN INFORMATION. ESB IS NOT RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION CONTAINED IN THIS MAP. THE INFORMATION IS PROVIDED AS A GUIDE ONLY AND SHOULD NOT BE RELIED UPON AS A SOURCE OF DESIGN INFORMATION. ESB IS NOT RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION CONTAINED IN THIS MAP. THE INFORMATION IS PROVIDED AS A GUIDE ONLY AND SHOULD NOT BE RELIED UPON AS A SOURCE OF DESIGN INFORMATION. ESB IS NOT RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION CONTAINED IN THIS MAP. THE INFORMATION IS PROVIDED AS A GUIDE ONLY AND SHOULD NOT BE RELIED UPON AS A SOURCE OF DESIGN INFORMATION. ESB IS NOT RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION CONTAINED IN THIS MAP. THE INFORMATION IS PROVIDED AS A GUIDE ONLY AND SHOULD NOT BE RELIED UPON AS A SOURCE OF DESIGN INFORMATION.

DATE: 19-Jun-2018

** SCALE: 1:1500



PLEASE NOTE THAT THERE ARE HIGH VOLTAGE (38KV AND HIGHER VOLTAGES) OVERHEAD LINES AND UNDERGROUND CABLES ON THIS MAP. IF YOU INTEND WORKING, OR UNDERTAKING DEVELOPMENT WITHIN A CORRIDOR EXTENDING 40 METRES ON EITHER SIDE OF ANY HIGH VOLTAGE OVERHEAD LINES OR WITHIN A CORRIDOR EXTENDING 5 METRES ON EITHER SIDE OF ANY HIGH VOLTAGE UNDERGROUND CABLES, YOU MUST CONTACT THE DESIGNATED PARTIES (PLEASE SEE ENCLOSED SHEET) IN ADVANCE OF THE WORKS.

Important Safety Notice:

Damage to gas pipelines can result in serious injury or death. Gas network information is provided as a general guide. The exact location and depth of medium or low pressure distribution gas pipes must be verified on site by carrying out necessary investigations, including, for example, hand digging test holes along the route of the pipe. Service pipes are not generally shown but their presence should always be anticipated.

High pressure transmission pipelines are shown in red. If a transmission pipeline is identified within 10m of any intended excavations then work must not proceed before GNi has been consulted. The true location and depth of a transmission pipeline must be verified on site by a representative of GNi. Contact can be made through 1850-427-747.

All work in the vicinity of the gas network must be conducted in accordance with the current edition of the Health & Safety Authority publication, *Code of Practice For Avoiding Danger From Underground Services* which is available from the Health and Safety Authority (1850 289 389) or can be downloaded at www.hsa.ie.

Legal Notice:

Gas Networks Ireland (GNI) and its affiliates, except for the accuracy of any information contained in this document concerning location and technical designation of the gas distribution and transmission network (the "Information"), measurements.

Any representations and warranties, express or implied, are excluded to the fullest extent permitted by law. No liability shall be accepted for any loss or damage including, without limitation, direct, indirect or consequential losses, arising out of or in connection with the use or release of the Information.

Aurora Telecom Fibre Optic Cable
Aurora Telecom Duct
Aurora Telecom Sub-duct
Aurora Telecom Inserted Gas Pipe

Contact Aurora Telecom on 1850-427-399 or (01)203-0120.

Transmission Pipe (High Pressure)
Transmission Pipe (Construction Issue)
Distribution Pipe (Medium Pressure)
Service Pipe (Low Pressure)
Service Pipe (Medium Pressure)
Strategic Pipe (Low Pressure)
Strategic Pipe (Medium Pressure)
Inserted Pipe (Medium Pressure)
Inserted Pipe (Low Pressure)
Distribution Pipe (Abandoned)

Pressure Monitor
Protection (Steel)
Protection (Stabbing)
Reducer
Service Terminator
Tee
Transition
C-C? Cover (depth in meters)
C-T Test Point
D End Cap
H-Hot Tap
X Installation Valve
Mains Verification **

Please contact GNI on 1850-427-747 for specific information.



Design Department - DUBLIN

GAS NETWORK INFORMATION

Punch Consulting Engineers


Manresa Rd, Merrion Co. Dublin

Contact: C Fallon

Plot Date: 19/06/2018

Printed By: KOC

Scale: 1:2500



0 0.02 0.04 0.08 Km

Coordinate System: TM65 Irish Grid
Projection Transverse Mercator

Scale @ A2: 1:2,000
Drawing No.: Crown p/FW

Drawn By: J Sheahan
Checked By: -
Approved By: -

Drawn Date: 19/06/2018
Checked Date: -
Approved Date: -



Water Services Crown Site Monivea Road

Info Barometric Design | karan.karan@water.ie

- No part of this drawing may be reproduced or transmitted in any form or stored in any retrieval system of any nature without the written permission of Irish Water as copyright holder except as agreed for use on the project for which the document was originally issued.
- Whilst every care has been taken in its compilation, Irish Water makes no guarantee as to the position of its underground network as a general guide only on the strict understanding that it is based on the best available information provided by each Local Authority in relation to Irish Water. Irish Water can assume no responsibility for any guarantee, undertaken or warranty concerning the accuracy, completeness or up-to-date status of the information provided and does not accept any liability whatever arising from any error or omission. This information should not be relied upon in the event of excavation or other works being carried out. Service connection pipes are not generally shown but their presence should be anticipated.

Legend

| Water Mains(Irish Water Owned) | Liquid Type |
|--------------------------------|---------------|
| Unreated | Potable Water |
| Potable Water | Unreated |

| Water Mains(Non Irish Water Owned) | Liquid Type |
|------------------------------------|---------------|
| Unreated | Potable Water |
| Potable Water | Unreated |

Boundary Valves

| Valve Normal Position |
|-----------------------|
| Open |
| Closed |
| Part Closed |

Non Boundary Valves


| Valve Normal Position |
|-----------------------|
| Open |
| Closed |
| Part Closed |

Coordinate System: TM65 Irish Grid
Projection: Transverse Mercator

Scale @ A2: 1:2,000
Drawing No.: Crown pW

Drawn By: J Sheahan
Checked By: .
Approved By: .

Drawn Date: 19/06/2018
Checked Date: .
Approved Date: .



Water Services Crown Site Monivea Road

- No part of this drawing may be reproduced or transmitted in any form or stored in any retrieval system of any nature without the written permission of Irish Water as copyright holder except as agreed for use on the project for which the document was originally issued.
 - Whilst every care has been taken in its compilation, Irish Water gives no guarantee that it is based on the best available information provided by each Local Authority in Ireland to Irish Water. Irish Water can assume no responsibility for any guarantees undertaken or warranties concerning the accuracy, completeness or up-to-date status of the information provided and does not accept any liability which may arise from any use of or reliance on this information. This information should not be relied upon in the event of excavations or other works being carried out. The underground network is identified prior to excavations or any other works being carried out. Service connection pipes are not generally shown but their presence should be anticipated.
- © Copyright Irish Water
Reproduced from the Ordnance Survey Of Ireland by Permission of the Government. Licence No. 3-3-34



Legend

| Liquid Type | Surface |
|-------------|---------|
| | |

Liquid Type

| Cascade | Catchpit | Hatchbox | Lamphole | Standard | Other: Unknown |
|---------|----------|----------|----------|----------|----------------|
| | | | | | |

Storm Manholes

| Manhole Type |
|--------------|
| |

Coordinate System: TM65 Irish Grid
Projection: Transverse Mercator

Scale @ A2: 1:2,000
Drawing No.: Crown p.e SW

Drawn By: J Sheahan
Checked By: -
Approved By: -

Drawn Date: 19/06/2018
Checked Date: -
Approved Date: -




**Water Services
Crown Site
Monivea Road**

1. No part of this drawing may be reproduced or transmitted in any form or stored in any retrieval system of any nature without the written permission of Irish Water as copyright holder except as agreed for use on the project for which the document was originally issued.
 2. Whilst every care has been taken in its compilation, Irish Water makes no guarantee as to the position of its underground network as a general guide only. It is based on the best information available and is provided by each Local Authority in Ireland to Irish Water. Irish Water can assume no responsibility for any guarantee, undertaken or warranty concerning the accuracy, completeness or up-to-date nature of the information provided and does not accept any liability whatever arising from any error or omission. This information should not be relied upon in the event of excavation or other works being carried out. Service connection pipes are not generally shown but their presence should be anticipated.

© Copyright Irish Water

Reproduced from the Ordnance Survey Of Ireland by Permission of the Government. Licence No. 3-3-34





Ordnance Survey Ireland Licence No. EN002385
© Ordnance Survey of Ireland and Government of Ireland

Produced on: 19/06/2018

PROJECT NAME:
Virgin Media
Unit 6 & 7
Broomhill Business Park
Tallow 24
DESIGNED BY:



Important Safety Notice:
Damage to gas pipelines can result in serious injury or death. Gas network information provided is a general guide. The exact location and depth of medium or low pressure distribution gas pipes must be verified on site by carrying out necessary investigations, for example, hand digging trial holes along the route of the pipe.

Service pipes are not generally known but their presence should always be anticipated.
High pressure transmission pipelines are shown in red. If a transmission pipeline is identified within 10m of any intended excavations then work must not proceed before a GN has been consulted. This is to ensure the location and depth of a transmission pipeline must be verified on site by a representative of GN. Contact can be made through 1850-427-747.

Legal Notice:
All work in the vicinity of the gas network must be completed in accordance with the current edition of the Health & Safety Authority publication, Code of Practice for Avoiding Danger from Underground Services which is available from the Health and Safety Authority (090) 249-3869 or can be downloaded at www.hsa.ie.

Any representations, warranties, express or implied, are excluded to the fullest extent permitted by law. No liability shall be accepted for any loss or damage including, without limitation, direct or consequential losses, arising out of or in connection with the use or misuse of the information.

Aurora Telecom Fiber Optic-Cable
Aurora Telecom Duct
Aurora Telecom Sub-duct
Aurora Telecom Inserted Gas Pipe

Contact Aurora Telecom on 1850-427-399 or (0)1203-0120.

Transmission Pipe (High Pressure)
Distribution Pipe (Construction Joint)
Distribution Pipe (Medium Pressure)
Service Pipe (Low Pressure)
Service Pipe (Medium Pressure)
Strategic Pipe (Low Pressure)
Strategic Pipe (Medium Pressure)
Inserted Pipe (Medium Pressure)
Inserted Pipe (Low Pressure)
Distribution Pipe (Abandoned)


C-2 Cover (depth in meters)
C-T Test Point
D End Cap
H Hot Tap
X Installation Valve
M Mains Verification #

Pressure Monitor
Protective (Sleeve)
Protection (Slabbing)
Reducer
Service Terminator
Tee
Transition



| GAS NETWORK INFORMATION | | |
|--------------------------------|-----------------------------|-------------------|
| Issue: | Punch Consulting Engineers | |
| Location: | Mantra Rd, Menlo Co. Galway | |
| Plot Date: | 19/06/2018 | Contact: C Fallon |
| Printed By: | KOC | Scale: 1:2500 |

Design Department - DUBLIN



0 0.02 0.04 0.08 Km

Coordinate System: TM65 Irish Grid
Projection Transverse Mercator

Scale @ A2: 1:2,000
Drawing No.: Crown p/FW

Drawn By: J Sheahan
Checked By: -
Approved By: -

Drawn Date: 19/06/2018
Checked Date: -
Approved Date: -



Water Services Crown Site Monivea Road

1. No part of the drawing may be reproduced or transmitted in any form or stored in any retrieval system of any nature without the written permission of Irish Water as copyright holder except as agreed for use on the project for which the document was originally issued.
2. Whilst every care has been taken in its compilation, Irish Water takes no responsibility for the position of its underground network as a general guide only on the stated understanding that it is based on the best available information provided by each Local Authority in Ireland to Irish Water. Irish Water can assume no responsibility for any inaccuracies, understandings or warranties concerning the accuracy, completeness or up-to-date status of the information provided and does not accept any liability whatever for any loss or damage resulting from any use of this information. This information should not be relied upon in the event of any work being carried out. Service connection pipes are not generally shown but their presence should be anticipated.

Map Bureau Design: karen@bwater.ie

Reproduced from the Ordnance Survey Of Ireland by Permission of the Government. License No. 3-3-34





| |
|------------------------------------|
| Coordinate System: TM65 Irish Grid |
| Projection: Transverse Mercator |
| Scale @ A2: 1:2,000 |
| Drawing No.: Crown pW |
| Drawn By: J Sheahan |
| Checked By: . |
| Approved By: . |
| Drawn Date: 19/06/2018 |
| Checked Date: . |
| Approved Date: . |



Water Services
Crown Site
Monivea Road


- No part of this drawing may be reproduced or transmitted in any form or stored in any retrieval system of any nature without the written permission of Irish Water as copyright holder except as agreed for use on the project for which the document was originally issued.
- Whilst every care has been taken in its compilation, Irish Water gives this information as a general guide only on the state of the underground network as it is based on the best available information provided by each Local Authority in Ireland to Irish Water. Irish Water can assume no responsibility for any inaccuracies, omissions, or variations concerning the accuracy, completeness, or up-to-date status of the information provided and does not accept liability whichever the source of any errors or omissions. This information should not be relied upon in the event of excavation. It is the responsibility of the excavator to call upon the services of a professional surveyor to determine the exact position of any underground services before carrying out any work or excavation.
- Irish Water and the Ordnance Survey of Ireland have made every effort to ensure the accuracy of the information contained in this drawing. However, due to the nature of the underground environment, it is important to note that the location and condition of the pipes shown on the drawing may not necessarily reflect the actual state of the network in the field. It is the responsibility of the user to verify the correctness of the information and to take appropriate safety measures when carrying out any work or excavation.
- Reproduced from the Ordnance Survey Of Ireland by Permission of the Government. License No. 3-3-34



Legend

| | | |
|-----------------------|--|----------------|
| Liquid Type | | Surface |
| Liquid Type | | Surface |
| Storm Manholes | | |
| Manhole Type | | Cascade |
| | | Catchpit |
| | | Hatchbox |
| | | Lamphole |
| | | Standard |
| | | Other: Unknown |


| | |
|------------------------------------|--------------------|
| Scale @ A2: | 0.002 0.04 0.08 Km |
| Coordinate System: TM65 Irish Grid | |
| Projection: Transverse Mercator | |
| Checked By: | J Sheahan |
| Approved By: | . |
| Drawn Date: | 19/06/2018 |
| Checked Date: | . |
| Approved Date: | . |



**Water Services
Crown Site
Monivea Road**

1. No part of this drawing may be reproduced or transmitted in any form or stored in any retrieval system of any nature without the written permission of Irish Water as copyright holder except as agreed for use on the project for which the document was originally issued.
2. Whilst every care has been taken in its compilation, Irish Water makes no guarantee as to the position of its underground network as a general guide only on the stated understanding that it is based on the best available information provided by each Local Authority in Ireland and Irish Water can assume no responsibility for any inaccuracies, understandings or warranties concerning the accuracy, completeness or up-to-date status of the information provided. It is the responsibility of the user to check the information against the actual ground conditions. This information should not be relied upon in the event of any work being carried out. Service connection pipes are not generally shown but their presence should be anticipated.
- © Copyright Irish Water





PROJECT NAME
Virgin Media
Unit 6 & 7
Broombhill Business Park
Tallaght 24

DESIGNED BY:
Vigil media

Ordnance Survey Ireland Licence No. EN002385
(c) Ordnance Survey of Ireland and Government of Ireland
Produced on: 19/06/2018



Appendix B - Foul Water Calculations - Micro Drainage

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 1 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

FOUL SEWERAGE DESIGN

Design Criteria for Foul Phase 1

Pipe Sizes Standard Manhole Sizes Standard

| | | | |
|-----------------------------|--------|---------------------------------------|-------|
| Industrial Flow (l/s/ha) | 0.00 | Add Flow / Climate Change (%) | 0 |
| Industrial Peak Flow Factor | 0.00 | Minimum Backdrop Height (m) | 0.000 |
| Flow Per Person (l/per/day) | 165.00 | Maximum Backdrop Height (m) | 0.000 |
| Persons per House | 2.70 | Min Design Depth for Optimisation (m) | 1.200 |
| Domestic (l/s/ha) | 0.00 | Min Vel for Auto Design only (m/s) | 0.75 |
| Domestic Peak Flow Factor | 6.00 | Min Slope for Optimisation (1:X) | 500 |

Designed with Level Soffits

Network Design Table for Foul Phase 1

| PN | Length (m) | Fall (m) | Slope (1:X) | Area (ha) | Houses | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|--------|---------------|-------------|----------------|--------------|--------|--------------------|-----------|-------------|-------------|----------------|
| 20.000 | 10.000 | 0.050 | 200.0 | 0.000 | 238 | 0.0 | 1.500 | o | 225 | 🔒 |
| 20.001 | 64.381 | 0.322 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | 🔓 |
| 20.002 | 14.483 | 0.072 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | 🔓 |
| 20.003 | 22.874 | 0.114 | 200.6 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | 🔓 |
| 20.004 | 32.344 | 0.162 | 199.7 | 0.000 | 134 | 0.0 | 1.500 | o | 225 | 🔓 |
| 20.005 | 5.870 | 0.029 | 202.4 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | 🔓 |
| 20.006 | 49.923 | 0.250 | 199.7 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | 🔓 |
| 20.007 | 5.689 | 0.028 | 203.2 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | 🔓 |
| 20.008 | 27.245 | 0.136 | 200.3 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | 🔓 |
| 20.009 | 12.851 | 0.064 | 200.8 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | 🔓 |
| 20.010 | 65.606 | 0.328 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | 🔓 |
| 21.000 | 43.074 | 0.215 | 200.3 | 0.000 | 109 | 0.0 | 1.500 | o | 225 | 🔒 |

Network Results Table

| PN | US/IL (m) | Σ Area (ha) | Σ Base Flow (l/s) | Σ Hse | Add Flow (l/s) | P.Dep (mm) | P.Vel (m/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|--------|--------------|----------------|----------------------|-------|-------------------|---------------|----------------|--------------|--------------|---------------|
| 20.000 | 29.800 | 0.000 | 0.0 | 238 | 0.0 | 73 | 0.66 | 0.81 | 32.2 | 7.4 |
| 20.001 | 29.750 | 0.000 | 0.0 | 238 | 0.0 | 73 | 0.66 | 0.81 | 32.2 | 7.4 |
| 20.002 | 29.428 | 0.000 | 0.0 | 238 | 0.0 | 73 | 0.66 | 0.81 | 32.2 | 7.4 |
| 20.003 | 29.356 | 0.000 | 0.0 | 238 | 0.0 | 73 | 0.66 | 0.81 | 32.2 | 7.4 |
| 20.004 | 29.242 | 0.000 | 0.0 | 372 | 0.0 | 93 | 0.74 | 0.81 | 32.2 | 11.5 |
| 20.005 | 29.080 | 0.000 | 0.0 | 372 | 0.0 | 93 | 0.74 | 0.81 | 32.0 | 11.5 |
| 20.006 | 29.051 | 0.000 | 0.0 | 372 | 0.0 | 93 | 0.74 | 0.81 | 32.2 | 11.5 |
| 20.007 | 28.801 | 0.000 | 0.0 | 372 | 0.0 | 93 | 0.74 | 0.80 | 32.0 | 11.5 |
| 20.008 | 28.773 | 0.000 | 0.0 | 372 | 0.0 | 93 | 0.74 | 0.81 | 32.2 | 11.5 |
| 20.009 | 28.637 | 0.000 | 0.0 | 372 | 0.0 | 93 | 0.74 | 0.81 | 32.1 | 11.5 |
| 20.010 | 28.573 | 0.000 | 0.0 | 372 | 0.0 | 93 | 0.74 | 0.81 | 32.2 | 11.5 |
| 21.000 | 29.675 | 0.000 | 0.0 | 109 | 0.0 | 49 | 0.52 | 0.81 | 32.2 | 3.4 |

| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | | | | | | | | | | Page 2 |
|--|---------------|-----------------------|-----------------------------|--------------|-------------------|--------------------|---------------|--------------|--------------|---|---|
| Crown Square Developments | | | | | | | | | | |  |
| Date 2018-10-18 File 181018_Overall Networks... | | | | | | | | | | | Designed by F. Timlin Checked by D. Gallery |
| Micro Drainage Network 2014.1 | | | | | | | | | | | |
| <u>Network Design Table for Foul Phase 1</u> | | | | | | | | | | | |
| PN | Length (m) | Fall (1:X) | Slope | Area (ha) | Houses | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design | |
| 22.000 | 9.490 | 0.047 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |  |
| 22.001 | 4.566 | 0.023 | 198.5 | 0.000 | 103 | 0.0 | 1.500 | o | 225 |  |  |
| 23.000 | 14.192 | 0.071 | 199.9 | 0.000 | 103 | 0.0 | 1.500 | o | 225 |  |  |
| 22.002 | 9.491 | 0.047 | 201.9 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |  |
| 24.000 | 23.448 | 0.117 | 200.4 | 0.000 | 109 | 0.0 | 1.500 | o | 225 |  |  |
| 25.000 | 23.649 | 0.118 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |  |
| 22.003 | 51.186 | 0.256 | 199.9 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |  |
| 21.001 | 39.470 | 0.197 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |  |
| 26.000 | 25.299 | 0.126 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |  |
| 26.001 | 51.453 | 0.257 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |  |
| 21.002 | 65.355 | 0.327 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |  |
| 21.003 | 12.814 | 0.064 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |  |
| 27.000 | 22.879 | 0.114 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  | |
| <u>Network Results Table</u> | | | | | | | | | | | |
| PN | US/IL (m) | Σ Area (ha) | Σ Base Flow (l/s) | Σ Hse | Add Flow (l/s) | P.Dep (l/s) | P.Vel (mm) | Vel (m/s) | Cap (l/s) | Flow (l/s) | |
| 22.000 | 29.950 | 0.000 | 0.0 | 0 | 0.0 | 0 | 0.00 | 0.81 | 32.2 | 0.0 | |
| 22.001 | 29.903 | 0.000 | 0.0 | 103 | 0.0 | 48 | 0.52 | 0.81 | 32.3 | 3.2 | |
| 23.000 | 29.950 | 0.000 | 0.0 | 103 | 0.0 | 48 | 0.51 | 0.81 | 32.2 | 3.2 | |
| 22.002 | 29.879 | 0.000 | 0.0 | 206 | 0.0 | 68 | 0.63 | 0.81 | 32.1 | 6.4 | |
| 24.000 | 29.950 | 0.000 | 0.0 | 109 | 0.0 | 49 | 0.52 | 0.81 | 32.2 | 3.4 | |
| 25.000 | 29.950 | 0.000 | 0.0 | 0 | 0.0 | 0 | 0.00 | 0.81 | 32.2 | 0.0 | |
| 22.003 | 29.832 | 0.000 | 0.0 | 315 | 0.0 | 85 | 0.71 | 0.81 | 32.2 | 9.7 | |
| 21.001 | 29.460 | 0.000 | 0.0 | 424 | 0.0 | 100 | 0.77 | 0.81 | 32.2 | 13.1 | |
| 26.000 | 29.950 | 0.000 | 0.0 | 0 | 0.0 | 0 | 0.00 | 0.81 | 32.2 | 0.0 | |
| 26.001 | 29.824 | 0.000 | 0.0 | 0 | 0.0 | 0 | 0.00 | 0.81 | 32.2 | 0.0 | |
| 21.002 | 29.263 | 0.000 | 0.0 | 424 | 0.0 | 100 | 0.77 | 0.81 | 32.2 | 13.1 | |
| 21.003 | 28.936 | 0.000 | 0.0 | 424 | 0.0 | 100 | 0.77 | 0.81 | 32.2 | 13.1 | |
| 27.000 | 29.950 | 0.000 | 0.0 | 0 | 0.0 | 0 | 0.00 | 0.81 | 32.2 | 0.0 | |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 3 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Network Design Table for Foul Phase 1

| PN | Length (m) | Fall (1:X) | Slope (ha) | Area (ha) | Houses | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|--------|---------------|---------------|---------------|--------------|--------|--------------------|-----------|-------------|-------------|---|
| 28.000 | 22.862 | 0.114 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |
| 27.001 | 52.955 | 0.265 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |
| 21.004 | 86.040 | 1.076 | 80.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |
| 20.011 | 18.924 | 0.237 | 79.8 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |

Network Results Table

| PN | US/IL (m) | Σ Area (ha) | Σ Base Flow (l/s) | Σ Hse | Add Flow (l/s) | P.Dep (mm) | P.Vel (m/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|--------|---------------|-----------------------|-----------------------------|--------------|-------------------|---------------|----------------|--------------|--------------|---------------|
| 28.000 | 29.950 | 0.000 | 0.0 | 0 | 0.0 | 0 | 0.00 | 0.81 | 32.2 | 0.0 |
| 27.001 | 29.836 | 0.000 | 0.0 | 0 | 0.0 | 0 | 0.00 | 0.81 | 32.2 | 0.0 |
| 21.004 | 27.860 | 0.000 | 0.0 | 424 | 0.0 | 78 | 1.08 | 1.28 | 51.1 | 13.1 |
| 20.011 | 26.785 | 0.000 | 0.0 | 796 | 0.0 | 110 | 1.27 | 1.29 | 51.1 | 24.6 |

Surcharged Outfall Details for Foul Phase 1

| Outfall Pipe Number | Outfall Name | C. Level (m) | I. Level (m) | Min I. Level (mm) | D,L (mm) | W (m) |
|------------------------|-----------------|-----------------|-----------------|-------------------------|-------------|----------|
| 20.011 | EX-F1 | 28.090 | 26.548 | 0.000 | 0 | 0 |

Input Hydrograph Type: User Defined

No Input Hydrograph data used for analysis due to offset specified.

Simulation Criteria for Foul Phase 1

| | | | |
|---------------------------------|-------|-------------------------------------|-------|
| Volumetric Runoff Coeff | 0.750 | Additional Flow - % of Total Flow | 0.000 |
| Areal Reduction Factor | 1.000 | MADD Factor * 10m³/ha Storage | 2.000 |
| Hot Start (mins) | 0 | Inlet Coeffiecient | 0.800 |
| Hot Start Level (mm) | 0 | Flow per Person per Day (l/per/day) | 0.000 |
| Manhole Headloss Coeff (Global) | 0.500 | Run Time (mins) | 60 |
| Foul Sewage per hectare (l/s) | 0.000 | Output Interval (mins) | 1 |

Number of Input Hydrographs 0 Number of Storage Structures 0
 Number of Online Controls 0 Number of Time/Area Diagrams 0
 Number of Offline Controls 0 Number of Real Time Controls 0

| | | |
|--|---|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 4 |
| Date 2018-10-18 File 181018_Overall Networks... | Crown Square Developments Designed by F. Timlin Checked by D. Gallery | |
| Micro Drainage | Network 2014.1 |  |
| | | |

Simulation Criteria for Foul Phase 1

Synthetic Rainfall Details

| | | | |
|-----------------------|----------------------|-----------------------|--------|
| Rainfall Model | FSR | Profile Type | Summer |
| Return Period (years) | 5 | Cv (Summer) | 0.750 |
| Region | Scotland and Ireland | Cv (Winter) | 0.840 |
| M5-60 (mm) | 17.500 | Storm Duration (mins) | 30 |
| Ratio R | 0.300 | | |

| | | |
|--|-----------------------|--------|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 1 |
| Crown Square Developments | | |
| Date 2018-10-18 | Designed by F. Timlin | |
| File 181018_Overall Networks... | Checked by D. Gallery | |



Micro Drainage Network 2014.1

FOUL SEWERAGE DESIGN

Design Criteria for Foul Phase 2

Pipe Sizes Standard Manhole Sizes Standard

| | | | |
|-----------------------------|--------|---------------------------------------|-------|
| Industrial Flow (l/s/ha) | 0.00 | Add Flow / Climate Change (%) | 0 |
| Industrial Peak Flow Factor | 0.00 | Minimum Backdrop Height (m) | 0.000 |
| Flow Per Person (l/per/day) | 165.00 | Maximum Backdrop Height (m) | 0.000 |
| Persons per House | 2.70 | Min Design Depth for Optimisation (m) | 1.200 |
| Domestic (l/s/ha) | 0.00 | Min Vel for Auto Design only (m/s) | 0.75 |
| Domestic Peak Flow Factor | 6.00 | Min Slope for Optimisation (1:X) | 500 |

Designed with Level Soffits

Network Design Table for Foul Phase 2

| PN | Length (m) | Fall (m) | Slope (1:X) | Area (ha) | Houses | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|-------|---------------|-------------|----------------|--------------|--------|--------------------|-----------|-------------|-------------|----------------|
| 1.000 | 21.138 | 0.106 | 200.0 | 0.000 | 96 | 0.0 | 1.500 | o | 225 | |
| 1.001 | 22.507 | 0.113 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | |
| 1.002 | 23.985 | 0.120 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | |
| 1.003 | 6.661 | 0.033 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | |
| 1.004 | 39.338 | 0.197 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | |
| 2.000 | 19.958 | 0.100 | 200.0 | 0.000 | 144 | 0.0 | 1.500 | o | 225 | |
| 2.001 | 22.106 | 0.111 | 199.2 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | |
| 2.002 | 31.940 | 0.160 | 199.6 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | |
| 1.005 | 44.160 | 0.221 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 | |
| 3.000 | 36.914 | 0.185 | 200.0 | 0.000 | 480 | 0.0 | 1.500 | o | 225 | |

Network Results Table

| PN | US/IL | Σ Area (ha) | Σ Base Flow (l/s) | Σ Hse | Add Flow (l/s) | P.Dep (mm) | P.Vel (m/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|--------|----------------|----------------------|-------|-------------------|---------------|----------------|--------------|--------------|---------------|
| 1.000 | 30.000 | 0.000 | 0.0 | 96 | 0.0 | 46 | 0.50 | 0.81 | 32.2 | 3.0 |
| 1.001 | 29.894 | 0.000 | 0.0 | 96 | 0.0 | 46 | 0.50 | 0.81 | 32.2 | 3.0 |
| 1.002 | 29.782 | 0.000 | 0.0 | 96 | 0.0 | 46 | 0.50 | 0.81 | 32.2 | 3.0 |
| 1.003 | 29.662 | 0.000 | 0.0 | 96 | 0.0 | 46 | 0.50 | 0.81 | 32.2 | 3.0 |
| 1.004 | 29.629 | 0.000 | 0.0 | 96 | 0.0 | 46 | 0.50 | 0.81 | 32.2 | 3.0 |
| 2.000 | 30.000 | 0.000 | 0.0 | 144 | 0.0 | 57 | 0.57 | 0.81 | 32.2 | 4.5 |
| 2.001 | 29.900 | 0.000 | 0.0 | 144 | 0.0 | 57 | 0.57 | 0.81 | 32.3 | 4.5 |
| 2.002 | 29.789 | 0.000 | 0.0 | 144 | 0.0 | 57 | 0.57 | 0.81 | 32.2 | 4.5 |
| 1.005 | 29.432 | 0.000 | 0.0 | 240 | 0.0 | 73 | 0.66 | 0.81 | 32.2 | 7.4 |
| 3.000 | 30.000 | 0.000 | 0.0 | 480 | 0.0 | 107 | 0.79 | 0.81 | 32.2 | 14.9 |

| | | | | | | | | |
|--|--|--|--|--|--|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | | | | | | | Page 2 |
| Date 2018-10-18 File 181018_Overall Networks... | | | | | | | |  |
| Micro Drainage | | | | | | | | Network 2014.1 |

Network Design Table for Foul Phase 2

| PN | Length (m) | Fall (m) | Slope (1:X) | Area (ha) | Houses | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|-------|---------------|-------------|----------------|--------------|--------|--------------------|-----------|-------------|-------------|---|
| 1.006 | 56.395 | 0.282 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |
| 4.000 | 24.844 | 0.124 | 200.0 | 0.000 | 120 | 0.0 | 1.500 | o | 225 |  |
| 4.001 | 47.911 | 0.240 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |
| 1.007 | 5.342 | 0.027 | 200.0 | 0.000 | 0 | 0.0 | 1.500 | o | 225 |  |

Network Results Table

| PN | US/IL (m) | Σ Area (ha) | Σ Base Flow (l/s) | Σ Hse | Add Flow (l/s) | P.Dep (mm) | P.Vel (m/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|--------------|-----------------------|-----------------------------|--------------|-------------------|---------------|----------------|--------------|--------------|---------------|
| 1.006 | 29.211 | 0.000 | 0.0 | 720 | 0.0 | 138 | 0.87 | 0.81 | 32.2 | 22.3 |
| 4.000 | 29.970 | 0.000 | 0.0 | 120 | 0.0 | 52 | 0.54 | 0.81 | 32.2 | 3.7 |
| 4.001 | 29.846 | 0.000 | 0.0 | 120 | 0.0 | 52 | 0.54 | 0.81 | 32.2 | 3.7 |
| 1.007 | 28.929 | 0.000 | 0.0 | 840 | 0.0 | 153 | 0.90 | 0.81 | 32.2 | 26.0 |

Surcharged Outfall Details for Foul Phase 2

| Outfall Pipe Number | Outfall Name | C. Level (m) | I. Level (m) | Min I. Level (mm) | D,L (mm) | W (mm) |
|------------------------|-----------------|-----------------|-----------------|-------------------------|-------------|-----------|
| 1.007 | EX-F2 | 30.315 | 28.902 | 0.000 | 0 | 0 |

Input Hydrograph Type: User Defined

No Input Hydrograph data used for analysis due to offset specified.

Simulation Criteria for Foul Phase 2

| | | | |
|---------------------------------|-------|-------------------------------------|-------|
| Volumetric Runoff Coeff | 0.750 | Additional Flow - % of Total Flow | 0.000 |
| Areal Reduction Factor | 1.000 | MADD Factor * 10m³/ha Storage | 2.000 |
| Hot Start (mins) | 0 | Inlet Coeffiecient | 0.800 |
| Hot Start Level (mm) | 0 | Flow per Person per Day (l/per/day) | 0.000 |
| Manhole Headloss Coeff (Global) | 0.500 | Run Time (mins) | 60 |
| Foul Sewage per hectare (l/s) | 0.000 | Output Interval (mins) | 1 |

Number of Input Hydrographs 0 Number of Storage Structures 0

Number of Online Controls 0 Number of Time/Area Diagrams 0

Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

| | | |
|--|---------------------------|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 3 |
| Date 2018-10-18 File 181018_Overall Networks... | Crown Square Developments | |
| Designed by F. Timlin Checked by D. Gallery | |  |
| Micro Drainage | Network 2014.1 | |

Synthetic Rainfall Details

| | | |
|-----------------------------|--------|--------------------------|
| Rainfall Model | FSR | Profile Type Summer |
| Return Period (years) | 5 | Cv (Summer) 0.750 |
| Region Scotland and Ireland | | Cv (Winter) 0.840 |
| M5-60 (mm) | 17.500 | Storm Duration (mins) 30 |
| Ratio R | 0.300 | |

Appendix C - Irish Water Letter of Feasibility



LUXOR INVESTMENTS LIMITED
C/O DONNAGH MURPHY

PUNCH CONSULTING, 97 HENRY STREET, LIMERICK

Uisce Éireann
Bosca OP 6000
Baile Átha Cliath 1
Éire

Irish Water
PO Box 6000
Dublin 1
Ireland

T: +353 1 89 25000
F: +353 1 89 25001
www.water.ie

12th March 2019

Dear Sir/Madam,

Re: Customer Reference No 953699652 pre-connection enquiry - Subject to contract | Contract denied
Connection for mixed use development comprising of 300 residential units and ancillary residential accommodation, offices, hotel, retail units, medical centre, pharmacy and leisure centre

Irish Water has reviewed your pre-connection enquiry in relation to water and wastewater connections at CROWN SQUARE DEVELOPMENT, MONIVEA ROAD, GALWAY.

Based upon the details that you have provided with your pre-connection enquiry and on the capacity currently available in the network(s), as assessed by Irish Water, we wish to advise you that, subject to a valid connection agreement being put in place, your proposed connection to the Irish Water network(s) can be facilitated.

An existing Irish Water 675mm diameter wastewater sewer runs along the southern boundary of the development site. A connection can be facilitated to the Irish Water wastewater network. The structural integrity of the existing Irish Water sewer running to the south of the development site should not be compromised during the course of any construction works. The proposed discharge may require a Trade Effluent to Sewer Discharge Licence to be in place prior to connection being made. The applicant is advised to visit <https://www.water.ie/for-business/trade-effluent/> in this regard.

The existing Irish Water watermain network has capacity to cater for the proposed development. We understand that the development site has an existing watermain connection from the 9 inch AC watermain on Connolly Avenue. This is the preferred connection location. You will be responsible for assessing the suitability of this existing connection and the existing private side watermain network in catering for the proposed development demands. The existing water meter arrangement may require to be upgraded to ensure it satisfies IW requirements and that it is right sized to suit the development supply demands. This will be confirmed at connection application stage. Please note that the confirmation of feasibility to connect to the Irish Water water infrastructure does not extend to your fire flow requirements. To guarantee a flow to meet the Fire Authority requirements you should provide adequate fire storage capacity within your development.

Strategic Housing Development

Irish Water notes that the residential element of this development may dictate that this element is subject to the Strategic Housing Development planning process. Therefore in advance of submitting your full application to An Bord Pleanala for assessment, you must have reviewed this development with Irish Water and received a Statement of Design Acceptance in relation to the layout of water and wastewater services. The water and wastewater layouts can be submitted to cdsdesignqa@water.ie.

All infrastructure should be designed and installed in accordance with the Irish Water Codes of Practice and Standard Details.

You are advised that this correspondence does not constitute an offer in whole or in part to provide a connection to any Irish Water infrastructure and is provided subject to a connection agreement being signed at a later date.

A connection agreement can be applied for by completing the connection application form available at www.water.ie/connections. Irish Water's current charges for water and wastewater connections are set out in the Water Charges Plan as approved by the Commission for Regulation of Utilities.

If you have any further questions, please contact James O Malley from the design team at jomalley@water.ie. For further information, visit www.water.ie/connections

Yours sincerely,

Maria O'Dwyer
Connections and Developer Services

Stiúrthóiri / Directors: Mike Quinn (Chairman), Jerry Grant, Cathal Marley, Brendan Murphy, Michael G. O'Sullivan
Oifig Chláraithe / Registered Office: Teach Colvill, 24-26 Sráid Thalbóid, Baile Átha Cliath 1, D01 NP86 / Colvill House, 24-26 Talbot Street, Dublin 1, D01 NP86
Is cuideachta ghníomhaiochta ainmnithe atá faoi theorainn scaireanna é Uisce Éireann / Irish Water is a designated activity company, limited by shares.
Uimhir Chláraithe in Éirinn / Registered in Ireland No.: 530363

Appendix D – Statement of Design Acceptance

Luxor Investments Limited c/o Fergal Timlin,
Punch Consulting,
97 Henry Street,
Limerick

23 May 2019

Uisce Éireann
Bosca OP 448
Oifig Sheachadta
na Cathrach Theas
Cathair Chorcaí

**Re: Design Submission for Housing Development at Crown Square Development,
Monivea Road, Galway (the “Development”) (the “Design Submission”) / 953699652.**

Irish Water
PO Box 448
South City
Delivery Office
Cork City

www.water.ie

Dear Fergal,

Many thanks for your recent Design Submission.

We have reviewed your proposal for the connection(s) at the Development. Based on the information provided, which included the documents outlined in Appendix A to this letter, Irish Water has no objection to your proposals.

This letter does not constitute an offer, in whole or in part, to provide a connection to any Irish Water infrastructure. Before you can connect to our network you must sign a connection agreement with Irish Water. This can be applied for by completing the connection application form at www.water.ie/connections. Irish Water's current charges for water and wastewater connections are set out in the Water Charges Plan as approved by the Commission for Regulation of Utilities (CRU) (https://www.cru.ie/document_group/irish-waters-water-charges-plan-2018/).

You the Customer (including any designers/contractors or other related parties appointed by you) is entirely responsible for the design and construction of all water and/or wastewater infrastructure within the Development which is necessary to facilitate connection(s) from the boundary of the Development to Irish Water's network(s) (the “**Self-Lay Works**”), as reflected in your Design Submission. Acceptance of the Design Submission by Irish Water does not, in any way, render Irish Water liable for any elements of the design and/or construction of the Self-Lay Works.

If you have any further questions, please contact your Irish Water Representative

Name: James O’Malley
Email: jomalley@water.ie

Yours sincerely,



Maria O'Dwyer

Connections and Developer Services

Appendix A

Document Title & Revision

- 183-106-051-PL1 Proposed Ground Floor Drainage Layout – Phase 2
- 183-106-053-PL1 Basement Floor Drainage – Phase 2
- 183-106-054-PL1 Watermain Layout – Phase 2
- 183-106-057-PL0 Drainage Longitudinal Sections – Sheet 3 of 6
- 183-106-058-PL0 Drainage Longitudinal Sections – Sheet 4 of 6
- 183-106-060-PL0 Drainage Longitudinal Sections – Sheet 6 of 6



Standard Details/Code of Practice Exemption: N/A

*** Statement of Design Acceptance conditional that minimum cover to FC20-10 is increased to 500mm as per section 3.9.1 of the Wastewater Code of Practice**


For further information, visit www.water.ie/connections

Notwithstanding any matters listed above, the Customer (including any appointed designers/contractors, etc.) is entirely responsible for the design and construction of the Self-Lay Works. Acceptance of the Design Submission by Irish Water will not, in any way, render Irish Water liable for any elements of the design and/or construction of the Self-Lay Works.


| NOTE | |
|---|--|
| PROPOSED DRAINAGE TO BE IN ACCORDANCE WITH THE IRISH WATER CODE OF PRACTICE | |
| IRISH WATER WASTEWATER DETAILS | |
| Drawing No. | Drawing Title |
| STD-WW-01 | Waste water service connection responsibility |
| STD-WW-02 | Typical layout for sewer within new developments |
| STD-WW-03 | Drain & service connection pipework |
| STD-WW-04 | Typical sewer / service pipe connection |
| STD-WW-05 | Typical service layout indicating separation distances |
| STD-WW-06 | Restrictions on wastewater infrastructure adjacent to trees |
| STD-WW-06a | Restrictions on new trees/shrubs planting adjacent to sewers |
| STD-WW-07 | Trench backfill & bedding |
| STD-WW-08 | Concrete bed, haunch & surround to wastewater pipes |
| STD-WW-09 | Blockwork manhole (450mm dia.) |
| STD-WW-12 | Backdrop manholes |
| STD-WW-13 | Private side inspection chamber |
| STD-WW-34 | Vent stack |




Ordnance Survey Ireland Licence No EN 0003719
© Ordnance Survey Ireland/Government of Ireland




- SEWERS GENERAL:**
1. ALL SEWERS SHALL COMPLY WITH SECTION 3.13 OF THE IRISH WATER WASTEWATER CODE OF PRACTICE AS DESCRIBED BELOW;
 2. ALL FOUL SEWERS TO BE THERMOPLASTIC STRUCTURED WALL PIPES, UNPLASTIC PVC PIPES OR WITH THE RELEVANT PROVISIONS OF WS-13-01, I.E. POLYSEWER BY PONDITE CYLINDRICAL EQUIVALENT APPROVED;
 3. GRAVITY SEWER PIPE MATERIAL, TYPE, SIZE, LENGTH AND FITTINGS SHALL NOT CHANGE DURING THE CONSTRUCTION OF THE GRAVITY SEWERS. PIPE MATERIAL SHOULD NOT CHANGE BETWEEN MANHOLES. THE LIST BELOW DOES NOT APPLY TO PIPES INSTALLED IN CONCRETE DRAINS, DRAINS AND ATTENUATION TANKS;
 4. CONCRETE: CONCRETE SEWER PIPES WITH SPIGOT AND SOCKET JOINTS AND RUBBER RING FITTINGS SHALL COMPLY WITH EN 1916 (2002), BS 5911, PART 1 (2002) - 2010 AND 5 & 6 (2004) OR EQUIVALENT APPROVED. PIPE SIZE, LENGTH AND FITTINGS SHALL NOT CHANGE DURING THE CONSTRUCTION OF THE GRAVITY SEWERS. PIPE MATERIAL SHOULD NOT CHANGE BETWEEN MANHOLES. THE LIST BELOW DOES NOT APPLY TO PIPES INSTALLED IN CONCRETE DRAINS, DRAINS AND ATTENUATION TANKS;
 5. THERMOPLASTIC STRUCTURED WALL PIPES: THERMOPLASTIC UNPLASTIC PVC, UNPLASTIC PVC PIPES AND FITTINGS SHALL COMPLY WITH THE PROVISIONS OF EN 1401 AND EQUIVALENT APPROVED. PIPE SIZE, LENGTH AND FITTINGS SHALL NOT CHANGE DURING THE CONSTRUCTION OF THE GRAVITY SEWER. PIPE MATERIAL SHOULD NOT CHANGE BETWEEN MANHOLES. THE LIST BELOW DOES NOT APPLY TO PIPES INSTALLED IN CONCRETE DRAINS, DRAINS AND ATTENUATION TANKS;
 6. UNPLASTIC PVC: UNPLASTIC PVC PIPES AND FITTINGS SHALL COMPLY WITH THE PROVISIONS OF EN 1401 AND EQUIVALENT APPROVED. PIPE SIZE, LENGTH AND FITTINGS SHALL NOT CHANGE DURING THE CONSTRUCTION OF THE GRAVITY SEWER. PIPE MATERIAL SHOULD NOT CHANGE BETWEEN MANHOLES. THE LIST BELOW DOES NOT APPLY TO PIPES INSTALLED IN CONCRETE DRAINS, DRAINS AND ATTENUATION TANKS;
 7. OTHER: THE USE OF ALTERNATIVE PIPE TYPES AND MATERIALS WILL REQUIRE THE PRIOR WRITTEN AGREEMENT OF IRISH WATER.
 8. ALL RISING MAINS SHALL COMPLY WITH SECTION 3.14 OF THE IRISH WATER WASTEWATER CODE OF PRACTICE.



DRAINAGE LEGEND



PHASING LEGEND




IRISH WATER WATERMAIN DETAILS

| Drawing No. | Drawing Title |
|-------------|--|
| STD-W-01 | Water service connection responsibility |
| STD-W-02 | Typical layout for water mains within developments |
| STD-W-03 | Customer connection & boundary box |
| STD-W-04 | General pipe connections (sheet 1 of 7) |
| STD-W-05 | General pipe connections (sheet 2 of 7) |
| STD-W-06 | General pipe connections (sheet 3 of 7) |
| STD-W-07 | General pipe connections (sheet 4 of 7) |
| STD-W-08 | General pipe connections (sheet 5 of 7) |
| STD-W-09 | General pipe connections (sheet 6 of 7) |
| STD-W-11 | Typical service layout indicating separation distances |
| STD-W-12 | Restrictions on water infrastructure works adjacent to existing trees |
| STD-W-12A | Restrictions on new trees / shrubs planting adjacent to watermains |
| STD-W-13 | Trench backfill & bedding |
| STD-W-15 | Sluice valve for polyethylene (P.E.) pipe (<350mm dia.) (sheet 2 of 2) |
| STD-W-18 | On-line hydrant for polyethylene (P.E.) pipe (sheet 3 of 4) |
| STD-W-19 | Off-line hydrant for polyethylene (P.E.) pipe (sheet 4 of 4) |
| STD-W-22 | On-line air valve for polyethylene (P.E.) pipe (sheet 3 of 4) |
| STD-W-26 | Non mech meter chamber (40-250mm dia.) |
| STD-W-27 | Marker posts / plates |
| STD-W-28 | Water main thrust & support blocks |
| STD-W-30 | Scour chamber & head wall arrangements |

NOTE

PROPOSED WATERMAIN TO BE IN ACCORDANCE WITH THE IRISH WATER CODE OF PRACTICE











WATERMAIN LEGEND





| | |
|--|--|
| EXISTING WATERMAIN | |
| PROPOSED WATERMAIN (110mm OD PE100 SDR11 PIPE) | |
| PROPOSED SUSPENDED WATERMAIN (LEVEL B1) DN100 DUCTILE IRON | |
| PROPOSED SUSPENDED WATERMAIN (LEVEL B2) DN100 DUCTILE IRON | |
| PROPOSED FIRE HYDRANT | |
| PROPOSED SLUICE VALVE | |
| PROPOSED SCOUR VALVE | |
| BOUNDARY BOX MANIFOLD (FOR MULTIPLE PROPERTIES) | |
| PROPERTY BOUNDARY BOX | |
| EXISTING WATERMETER | |
| AIR VALVE | |








PHASING LEGEND

| | |
|------------------------|--|
| PHASE 1 WORKS BOUNDARY | |
| PHASE 2 WORKS BOUNDARY | |









Appendix E – Rainfall Supporting Data



| | |
|----------------|--------------------------|
| Calculated by: | Fergal Timlin |
| Site name: | Crown Square Development |
| Site location: | Monivea Road, Galway |

Site coordinates

| | |
|------------|-------------|
| Latitude: | 53.28796° N |
| Longitude: | 9.02134° W |

| | |
|------------|---------------------|
| Reference: | 6484561 |
| Date: | 2018-10-25T10:07:56 |

| | |
|-------------|-------|
| Methodology | IH124 |
|-------------|-------|

Site characteristics

| | |
|----------------------|-----|
| Total site area (ha) | 5.4 |
|----------------------|-----|

Methodology

| | | |
|------------------------|-----------------------------|--------|
| Qbar estimation method | Calculate from SPR and SAAR | |
| SPR estimation method | Calculate from SOIL type | |
| | Default | Edited |
| SOIL type | 1 | 1 |
| HOST class | --- | --- |
| SPR/SPRHOST | 0.1 | 0.1 |

Hydrological characteristics

| | Default | Edited |
|-------------------------------|---------|--------|
| SAAR (mm) | 1281 | 1281 |
| Hydrological region | 13 | 13 |
| Growth curve factor: 1 year | 0.85 | 0.85 |
| Growth curve factor: 30 year | 1.65 | 1.65 |
| Growth curve factor: 100 year | 1.95 | 1.95 |

Notes:

| |
|--|
| (1) Is $Q_{BAR} < 2.0 \text{ l/s/ha}$? |
| Normally limiting discharge rates which are less than 2.0 l/s/ha are set at 2.0 l/s/ha. |
| (2) Are flow rates $< 5.0 \text{ l/s}$? |
| Where flow rates are less than 5.0 l/s consents are usually set at 5.0 l/s if blockage from vegetation and other materials is possible. Lower consent flow rates may be set in which case blockage work must be addressed by using appropriate drainage elements |
| (3) Is $SPR/SPRHOST \leq 0.3$? |
| Where groundwater levels are low enough the use of soakaways to avoid discharge offsite may be a requirement for disposal of surface water runoff. |

Greenfield runoff rates

| | Default | Edited |
|----------------------|---------|--------|
| Qbar (l/s) | 1.84 | 1.84 |
| 1 in 1 year (l/s) | 1.56 | 1.56 |
| 1 in 30 years (l/s) | 3.04 | 3.04 |
| 1 in 100 years (l/s) | 3.59 | 3.59 |

Appendix F - Surface Water Calculations - Micro Drainage

| | | |
|--|--|--------|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 1 |
| Crown Square Developments | | |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery | |
| Micro Drainage | Network 2014.1 | |



STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm Blocks 2-4

Pipe Sizes Standard Manhole Sizes Standard

FSR Rainfall Model - Scotland and Ireland

| | | | |
|--------------------------------------|--------|---------------------------------------|-------|
| Return Period (years) | 5 | Add Flow / Climate Change (%) | 0 |
| M5-60 (mm) | 17.500 | Minimum Backdrop Height (m) | 0.000 |
| Ratio R | 0.300 | Maximum Backdrop Height (m) | 0.000 |
| Maximum Rainfall (mm/hr) | 50 | Min Design Depth for Optimisation (m) | 1.200 |
| Maximum Time of Concentration (mins) | 30 | Min Vel for Auto Design only (m/s) | 1.00 |
| Foul Sewage (l/s/ha) | 0.000 | Min Slope for Optimisation (1:X) | 500 |
| Volumetric Runoff Coeff. | 0.750 | | |

Designed with Level Inverts

Time Area Diagram for Storm Blocks 2-4

| Time (mins) | Area (ha) | Time (mins) | Area (ha) | Time (mins) | Area (ha) |
|-------------|-----------|-------------|-----------|-------------|-----------|
| 0-4 | 0.511 | 4-8 | 1.183 | 8-12 | 0.059 |

Total Area Contributing (ha) = 1.754

Total Pipe Volume (m³) = 295.877

Network Design Table for Storm Blocks 2-4

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|--------|------------|----------|-------------|-------------|-------------|-----------------|--------|----------|----------|-------------|
| 21.000 | 66.008 | 0.330 | 200.0 | 0.096 | 5.00 | 0.0 | 0.600 | o | 300 | |
| 21.001 | 12.195 | 0.061 | 200.0 | 0.049 | 0.00 | 0.0 | 0.600 | o | 300 | |
| 21.002 | 69.239 | 0.346 | 200.0 | 0.216 | 0.00 | 0.0 | 0.600 | o | 300 | |
| 22.000 | 45.550 | 0.228 | 200.0 | 0.155 | 5.00 | 0.0 | 0.600 | o | 225 | |
| 21.003 | 39.461 | 0.197 | 200.0 | 0.108 | 0.00 | 0.0 | 0.600 | o | 375 | |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|--------|--------------|-------------|-----------|----------------------|--------------------------|------------|----------------|-----------|-----------|------------|
| 21.000 | 50.00 | 5.99 | 29.925 | 0.096 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 13.0 |
| 21.001 | 50.00 | 6.18 | 29.595 | 0.145 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 19.6 |
| 21.002 | 50.00 | 7.22 | 29.349 | 0.361 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 48.9 |
| 22.000 | 50.00 | 5.82 | 29.925 | 0.155 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 21.0 |
| 21.003 | 50.00 | 7.73 | 29.003 | 0.624 | 0.0 | 0.0 | 0.0 | 1.28 | 141.1 | 84.5 |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 2 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Network Design Table for Storm Blocks 2-4

| PN | Length (m) | Fall (1:X) | Slope (ha) | I.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|--------|---------------|---------------|---------------|----------------|--------------------|-----------|-------------|-------------|---|
| 23.000 | 73.703 | 0.369 | 199.7 | 0.286 | 5.00 | 0.0 | 0.600 | o 300 |  |
| 21.004 | 73.227 | 0.366 | 200.0 | 0.220 | 0.00 | 0.0 | 0.600 | o 450 |  |
| 24.000 | 45.116 | 0.226 | 199.6 | 0.304 | 5.00 | 0.0 | 0.600 | o 300 |  |
| 21.005 | 80.759 | 0.200 | 403.8 | 0.000 | 0.00 | 0.0 | 0.600 | o 2000 |  |
| 25.000 | 56.239 | 0.281 | 200.1 | 0.320 | 5.00 | 0.0 | 0.600 | o 300 |  |
| 21.006 | 7.898 | 0.039 | 200.0 | 0.000 | 0.00 | 0.0 | 0.600 | o 225 |  |
| 21.007 | 31.157 | 0.156 | 200.0 | 0.000 | 0.00 | 0.0 | 0.600 | o 225 |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|--------|-----------------|----------------|--------------|----------------------------|--------------------------------|---------------|-------------------|--------------|--------------|---------------|
| 23.000 | 50.00 | 6.11 | 29.925 | 0.286 | 0.0 | 0.0 | 0.0 | 1.11 | 78.4 | 38.7 |
| 21.004 | 50.00 | 8.58 | 28.806 | 1.130 | 0.0 | 0.0 | 0.0 | 1.43 | 228.1 | 153.0 |
| 24.000 | 50.00 | 5.68 | 30.000 | 0.304 | 0.0 | 0.0 | 0.0 | 1.11 | 78.4 | 41.2 |
| 21.005 | 50.00 | 9.11 | 26.100 | 1.434 | 0.0 | 0.0 | 0.0 | 2.54 | 7971.9 | 194.2 |
| 25.000 | 50.00 | 5.85 | 27.000 | 0.320 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 43.3 |
| 21.006 | 50.00 | 5.14 | 25.900 | 0.000 | 3.1 | 0.0 | 0.0 | 0.92 | 36.6 | 3.1 |
| 21.007 | 50.00 | 5.71 | 25.861 | 0.000 | 3.1 | 0.0 | 0.0 | 0.92 | 36.6 | 3.1 |

Free Flowing Outfall Details for Storm Blocks 2-4

| Outfall Pipe Number | Outfall Name | C. Level (m) | I. Level (m) | Min I. Level (mm) | D,L (mm) | W (m) |
|------------------------|-----------------|-----------------|-----------------|-------------------------|-------------|----------|
| 21.007 | EX-S2 | 28.030 | 25.705 | 0.000 | 0 | 0 |

| | | |
|--|---|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 3 |
| Date 2018-10-18 File 181018_Overall Networks... | Crown Square Developments Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Simulation Criteria for Storm Blocks 2-4

| | | | |
|---------------------------------|-------|-------------------------------------|-------|
| Volumetric Runoff Coeff | 0.750 | Additional Flow - % of Total Flow | 0.000 |
| Areal Reduction Factor | 1.000 | MADD Factor * 10m³/ha Storage | 2.000 |
| Hot Start (mins) | 0 | Inlet Coeffiecient | 0.800 |
| Hot Start Level (mm) | 0 | Flow per Person per Day (l/per/day) | 0.000 |
| Manhole Headloss Coeff (Global) | 0.500 | Run Time (mins) | 60 |
| Foul Sewage per hectare (l/s) | 0.000 | Output Interval (mins) | 1 |

| | | | |
|-----------------------------|---|------------------------------|---|
| Number of Input Hydrographs | 0 | Number of Storage Structures | 1 |
| Number of Online Controls | 1 | Number of Time/Area Diagrams | 0 |
| Number of Offline Controls | 0 | Number of Real Time Controls | 0 |

Synthetic Rainfall Details

| | | | |
|-----------------------|----------------------|-----------------------|--------|
| Rainfall Model | FSR | Profile Type | Summer |
| Return Period (years) | 5 | Cv (Summer) | 0.750 |
| Region | Scotland and Ireland | Cv (Winter) | 0.840 |
| M5-60 (mm) | 17.500 | Storm Duration (mins) | 30 |
| Ratio R | 0.300 | | |

| | | |
|--|---|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 4 |
| Date 2018-10-18 File 181018_Overall Networks... | Crown Square Developments Designed by F. Timlin Checked by D. Gallery | |
| Micro Drainage | Network 2014.1 |  |

Online Controls for Storm Blocks 2-4

Hydro-Brake Optimum® Manhole: S21-6, DS/PN: 21.006, Volume (m³): 260.2

| | |
|-----------------------------------|----------------------------|
| Unit Reference | MD-SHE-0071-3100-2000-3100 |
| Design Head (m) | 2.000 |
| Design Flow (l/s) | 3.1 |
| Flush-Flo™ | Calculated |
| Objective | Minimise upstream storage |
| Diameter (mm) | 71 |
| Invert Level (m) | 25.900 |
| Minimum Outlet Pipe Diameter (mm) | 100 |
| Suggested Manhole Diameter (mm) | 1200 |

| Control Points | Head (m) | Flow (l/s) |
|---------------------------|----------|------------|
| Design Point (Calculated) | 2.000 | 3.1 |
| Flush-Flo™ | 0.313 | 2.3 |
| Kick-Flo® | 0.640 | 1.8 |
| Mean Flow over Head Range | - | 2.4 |

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

| Depth (m) | Flow (l/s) |
|-----------|------------|-----------|------------|-----------|------------|-----------|------------|
| 0.100 | 1.9 | 1.200 | 2.4 | 3.000 | 3.7 | 7.000 | 5.6 |
| 0.200 | 2.2 | 1.400 | 2.6 | 3.500 | 4.0 | 7.500 | 5.7 |
| 0.300 | 2.3 | 1.600 | 2.8 | 4.000 | 4.3 | 8.000 | 5.9 |
| 0.400 | 2.3 | 1.800 | 2.9 | 4.500 | 4.5 | 8.500 | 6.1 |
| 0.500 | 2.2 | 2.000 | 3.1 | 5.000 | 4.7 | 9.000 | 6.3 |
| 0.600 | 2.0 | 2.200 | 3.2 | 5.500 | 5.0 | 9.500 | 6.4 |
| 0.800 | 2.0 | 2.400 | 3.4 | 6.000 | 5.2 | | |
| 1.000 | 2.3 | 2.600 | 3.5 | 6.500 | 5.4 | | |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 5 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Storage Structures for Storm Blocks 2-4

Tank or Pond Manhole: S21-6, DS/PN: 21.006

Invert Level (m) 25.900

| Depth (m) | Area (m ²) | Depth (m) | Area (m ²) | Depth (m) | Area (m ²) |
|-----------|------------------------|-----------|------------------------|-----------|------------------------|
| 0.000 | 450.0 | 2.200 | 450.0 | 2.201 | 0.0 |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 6 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Summary of Critical Results by Maximum Level (Rank 1) for Storm Blocks 2-4

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coeffiecient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1
 Number of Online Controls 1 Number of Time/Area Diagrams 0
 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.300
 Region Scotland and Ireland Cv (Summer) 0.750
 M5-60 (mm) 17.500 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 100.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status ON
 DVD Status ON
 Inertia Status ON

Profile(s)

Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
 720, 960, 1440, 2160, 2880, 4320, 5760,
 7200, 8640, 10080

Return Period(s) (years) 100
 Climate Change (%) 10

| PN | Storm | Return Period | Climate Change | First X Surcharge | First Y Flood | First Z Overflow | O/F Act. | Lvl Exc. |
|---------------|------------------|---------------|----------------|-------------------|---------------|------------------|----------|----------|
| 21.000 | 15 Winter | 100 | +10% | 100/15 | Summer | | | |
| 21.001 | 15 Winter | 100 | +10% | 100/15 | Summer | | | |
| 21.002 | 15 Winter | 100 | +10% | 100/15 | Summer | | | |
| 22.000 | 15 Winter | 100 | +10% | 100/15 | Summer | | | |
| 21.003 | 15 Winter | 100 | +10% | 100/15 | Summer | | | |
| 23.000 | 15 Winter | 100 | +10% | 100/15 | Summer | | | |
| 21.004 | 15 Winter | 100 | +10% | 100/15 | Summer | | | |
| 24.000 | 15 Winter | 100 | +10% | 100/15 | Summer | | | |
| 21.005 | 2880 Winter | 100 | +10% | 100/2880 | Winter | | | |
| 25.000 | 2880 Winter | 100 | +10% | 100/15 | Summer | | | |
| 21.006 | 2880 Winter | 100 | +10% | 100/15 | Summer | | | |
| 21.007 | 2880 Winter | 100 | +10% | | | | | |

| PN | Name | Water | | Flooded | | Pipe | |
|---------------|--------------|---------------|--------------|---------------------|-------------|-------------------|------------------------|
| | | US/MH | Level (m) | Surch'ded Depth (m) | Volume (m³) | Flow / Cap. (l/s) | Flow (l/s) |
| 21.000 | S21-0 | 30.731 | 0.506 | 0.000 | 0.38 | 0.0 | 28.1 SURCHARGED |
| 21.001 | S21-1 | 30.627 | 0.732 | 0.000 | 0.83 | 0.0 | 51.4 SURCHARGED |
| 21.002 | S21-2 | 30.554 | 0.905 | 0.000 | 1.19 | 0.0 | 88.9 SURCHARGED |

| | | | | | | | | |
|--|--|--|--|--|--|--|--|--------|
| Punch Consulting Engineers | | | | | | | | Page 7 |
| 97 Henry Street Limerick Ireland | | Crown Square Developments | | | | | | |
| Date 2018-10-18 File 181018_Overall Networks... | | Designed by F. Timlin Checked by D. Gallery | | | | | | |
| Micro Drainage | | Network 2014.1 | | | | | | |



Summary of Critical Results by Maximum Level (Rank 1) for Storm Blocks 2-4

| PN | US/MH | Water | | Flooded | | Pipe | | Status |
|--------|-------|--------|-----------|--------------------|-------------|--------------------------|------------|------------------|
| | | Name | Level (m) | Surch'ed Depth (m) | Volume (m³) | Flow / O'flow Cap. (l/s) | Flow (l/s) | |
| 22.000 | S22-0 | 30.515 | | 0.365 | 0.000 | 1.49 | 0.0 | 52.0 SURCHARGED |
| 21.003 | S21-3 | 30.020 | | 0.642 | 0.000 | 1.31 | 0.0 | 167.7 SURCHARGED |
| 23.000 | S23-0 | 30.531 | | 0.306 | 0.000 | 1.32 | 0.0 | 99.2 SURCHARGED |
| 21.004 | S21-4 | 29.698 | | 0.443 | 0.000 | 1.49 | 0.0 | 318.1 SURCHARGED |
| 24.000 | S24-0 | 30.579 | | 0.279 | 0.000 | 1.51 | 0.0 | 110.6 SURCHARGED |
| 21.005 | S21-5 | 28.474 | | 0.374 | 0.000 | 0.00 | 0.0 | 19.9 SURCHARGED |
| 25.000 | S25-0 | 28.474 | | 1.174 | 0.000 | 0.06 | 0.0 | 4.4 SURCHARGED |
| 21.006 | S21-6 | 28.474 | | 2.349 | 0.000 | 0.12 | 0.0 | 3.5 SURCHARGED |
| 21.007 | S21-7 | 25.908 | | -0.177 | 0.000 | 0.10 | 0.0 | 3.5 OK |

| | | |
|--|--|--------|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 1 |
| Crown Square Developments | | |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery | |
| Micro Drainage | Network 2014.1 | |



STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm Blocks 2-4

Pipe Sizes Standard Manhole Sizes Standard

FSR Rainfall Model - Scotland and Ireland

| | | | |
|--------------------------------------|--------|---------------------------------------|-------|
| Return Period (years) | 5 | Add Flow / Climate Change (%) | 0 |
| M5-60 (mm) | 17.500 | Minimum Backdrop Height (m) | 0.000 |
| Ratio R | 0.300 | Maximum Backdrop Height (m) | 0.000 |
| Maximum Rainfall (mm/hr) | 50 | Min Design Depth for Optimisation (m) | 1.200 |
| Maximum Time of Concentration (mins) | 30 | Min Vel for Auto Design only (m/s) | 1.00 |
| Foul Sewage (l/s/ha) | 0.000 | Min Slope for Optimisation (1:X) | 500 |
| Volumetric Runoff Coeff. | 0.750 | | |

Designed with Level Inverts

Time Area Diagram for Storm Blocks 2-4

| Time (mins) | Area (ha) | Time (mins) | Area (ha) | Time (mins) | Area (ha) |
|-------------|-----------|-------------|-----------|-------------|-----------|
| 0-4 | 0.511 | 4-8 | 1.183 | 8-12 | 0.059 |

Total Area Contributing (ha) = 1.754

Total Pipe Volume (m³) = 295.877

Network Design Table for Storm Blocks 2-4

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|--------|------------|----------|-------------|-------------|-------------|-----------------|--------|----------|----------|-------------|
| 21.000 | 66.008 | 0.330 | 200.0 | 0.096 | 5.00 | 0.0 | 0.600 | o | 300 | |
| 21.001 | 12.195 | 0.061 | 200.0 | 0.049 | 0.00 | 0.0 | 0.600 | o | 300 | |
| 21.002 | 69.239 | 0.346 | 200.0 | 0.216 | 0.00 | 0.0 | 0.600 | o | 300 | |
| 22.000 | 45.550 | 0.228 | 200.0 | 0.155 | 5.00 | 0.0 | 0.600 | o | 225 | |
| 21.003 | 39.461 | 0.197 | 200.0 | 0.108 | 0.00 | 0.0 | 0.600 | o | 375 | |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|--------|--------------|-------------|-----------|----------------------|--------------------------|------------|----------------|-----------|-----------|------------|
| 21.000 | 50.00 | 5.99 | 29.925 | 0.096 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 13.0 |
| 21.001 | 50.00 | 6.18 | 29.595 | 0.145 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 19.6 |
| 21.002 | 50.00 | 7.22 | 29.349 | 0.361 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 48.9 |
| 22.000 | 50.00 | 5.82 | 29.925 | 0.155 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 21.0 |
| 21.003 | 50.00 | 7.73 | 29.003 | 0.624 | 0.0 | 0.0 | 0.0 | 1.28 | 141.1 | 84.5 |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 2 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Network Design Table for Storm Blocks 2-4

| PN | Length (m) | Fall (1:X) | Slope (ha) | I.Area (mins) | T.E. 5.00 | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|--------|---------------|---------------|---------------|------------------|--------------|--------------------|-----------|-------------|-------------|--|
| 23.000 | 73.703 | 0.369 | 199.7 | 0.286 | | 0.0 | 0.600 | o | 300 |  |
| 21.004 | 73.227 | 0.366 | 200.0 | 0.220 | 0.00 | | 0.0 | 0.600 | o | 450  |
| 24.000 | 45.116 | 0.226 | 199.6 | 0.304 | 5.00 | | 0.0 | 0.600 | o | 300  |
| 21.005 | 80.759 | 0.200 | 403.8 | 0.000 | 0.00 | | 0.0 | 0.600 | o | 2000  |
| 25.000 | 56.239 | 0.281 | 200.1 | 0.320 | 5.00 | | 0.0 | 0.600 | o | 300  |
| 21.006 | 7.898 | 0.039 | 200.0 | 0.000 | 0.00 | | 0.0 | 0.600 | o | 225  |
| 21.007 | 31.157 | 0.156 | 200.0 | 0.000 | 0.00 | | 0.0 | 0.600 | o | 225  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|--------|-----------------|----------------|--------------|----------------------------|--------------------------------|---------------|-------------------|--------------|--------------|---------------|
| 23.000 | 50.00 | 6.11 | 29.925 | 0.286 | 0.0 | 0.0 | 0.0 | 1.11 | 78.4 | 38.7 |
| 21.004 | 50.00 | 8.58 | 28.806 | 1.130 | 0.0 | 0.0 | 0.0 | 1.43 | 228.1 | 153.0 |
| 24.000 | 50.00 | 5.68 | 30.000 | 0.304 | 0.0 | 0.0 | 0.0 | 1.11 | 78.4 | 41.2 |
| 21.005 | 50.00 | 9.11 | 26.100 | 1.434 | 0.0 | 0.0 | 0.0 | 2.54 | 7971.9 | 194.2 |
| 25.000 | 50.00 | 5.85 | 27.000 | 0.320 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 43.3 |
| 21.006 | 50.00 | 5.14 | 25.900 | 0.000 | 3.1 | 0.0 | 0.0 | 0.92 | 36.6 | 3.1 |
| 21.007 | 50.00 | 5.71 | 25.861 | 0.000 | 3.1 | 0.0 | 0.0 | 0.92 | 36.6 | 3.1 |

Free Flowing Outfall Details for Storm Blocks 2-4

| Outfall Pipe Number | Outfall Name | C. Level (m) | I. Level (m) | Min I. Level (mm) | D,L (mm) | W (m) |
|------------------------|-----------------|-----------------|-----------------|-------------------------|-------------|----------|
| 21.007 | EX-S2 | 28.030 | 25.705 | 0.000 | 0 | 0 |

| | | |
|--|---|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 3 |
| Date 2018-10-18 File 181018_Overall Networks... | Crown Square Developments Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Simulation Criteria for Storm Blocks 2-4

| | | | |
|---------------------------------|-------|-------------------------------------|-------|
| Volumetric Runoff Coeff | 0.750 | Additional Flow - % of Total Flow | 0.000 |
| Areal Reduction Factor | 1.000 | MADD Factor * 10m³/ha Storage | 2.000 |
| Hot Start (mins) | 0 | Inlet Coeffiecient | 0.800 |
| Hot Start Level (mm) | 0 | Flow per Person per Day (l/per/day) | 0.000 |
| Manhole Headloss Coeff (Global) | 0.500 | Run Time (mins) | 60 |
| Foul Sewage per hectare (l/s) | 0.000 | Output Interval (mins) | 1 |

| | | | |
|-----------------------------|---|------------------------------|---|
| Number of Input Hydrographs | 0 | Number of Storage Structures | 1 |
| Number of Online Controls | 1 | Number of Time/Area Diagrams | 0 |
| Number of Offline Controls | 0 | Number of Real Time Controls | 0 |

Synthetic Rainfall Details

| | | | |
|-----------------------|----------------------|-----------------------|--------|
| Rainfall Model | FSR | Profile Type | Summer |
| Return Period (years) | 5 | Cv (Summer) | 0.750 |
| Region | Scotland and Ireland | Cv (Winter) | 0.840 |
| M5-60 (mm) | 17.500 | Storm Duration (mins) | 30 |
| Ratio R | 0.300 | | |

| | | |
|--|---|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 4 |
| Date 2018-10-18 File 181018_Overall Networks... | Crown Square Developments Designed by F. Timlin Checked by D. Gallery | |
| Micro Drainage | Network 2014.1 |  |
| <u>Online Controls for Storm Blocks 2-4</u> | | |

Hydro-Brake Optimum® Manhole: S21-6, DS/PN: 21.006, Volume (m³): 260.2

| | |
|-----------------------------------|----------------------------|
| Unit Reference | MD-SHE-0071-3100-2000-3100 |
| Design Head (m) | 2.000 |
| Design Flow (l/s) | 3.1 |
| Flush-Flo™ | Calculated |
| Objective | Minimise upstream storage |
| Diameter (mm) | 71 |
| Invert Level (m) | 25.900 |
| Minimum Outlet Pipe Diameter (mm) | 100 |
| Suggested Manhole Diameter (mm) | 1200 |

| Control Points | Head (m) | Flow (l/s) |
|---------------------------|----------|------------|
| Design Point (Calculated) | 2.000 | 3.1 |
| Flush-Flo™ | 0.313 | 2.3 |
| Kick-Flo® | 0.640 | 1.8 |
| Mean Flow over Head Range | - | 2.4 |

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

| Depth (m) | Flow (l/s) |
|-----------|------------|-----------|------------|-----------|------------|-----------|------------|
| 0.100 | 1.9 | 1.200 | 2.4 | 3.000 | 3.7 | 7.000 | 5.6 |
| 0.200 | 2.2 | 1.400 | 2.6 | 3.500 | 4.0 | 7.500 | 5.7 |
| 0.300 | 2.3 | 1.600 | 2.8 | 4.000 | 4.3 | 8.000 | 5.9 |
| 0.400 | 2.3 | 1.800 | 2.9 | 4.500 | 4.5 | 8.500 | 6.1 |
| 0.500 | 2.2 | 2.000 | 3.1 | 5.000 | 4.7 | 9.000 | 6.3 |
| 0.600 | 2.0 | 2.200 | 3.2 | 5.500 | 5.0 | 9.500 | 6.4 |
| 0.800 | 2.0 | 2.400 | 3.4 | 6.000 | 5.2 | | |
| 1.000 | 2.3 | 2.600 | 3.5 | 6.500 | 5.4 | | |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 5 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Storage Structures for Storm Blocks 2-4

Tank or Pond Manhole: S21-6, DS/PN: 21.006

Invert Level (m) 25.900

| Depth (m) | Area (m ²) | Depth (m) | Area (m ²) | Depth (m) | Area (m ²) |
|-----------|------------------------|-----------|------------------------|-----------|------------------------|
| 0.000 | 450.0 | 2.200 | 450.0 | 2.201 | 0.0 |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 6 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Summary of Critical Results by Maximum Level (Rank 1) for Storm Blocks 2-4

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coeffiecient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1
 Number of Online Controls 1 Number of Time/Area Diagrams 0
 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.300
 Region Scotland and Ireland Cv (Summer) 0.750
 M5-60 (mm) 17.500 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 100.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status ON
 DVD Status ON
 Inertia Status ON

Profile(s)

Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
 720, 960, 1440, 2160, 2880, 4320, 5760,
 7200, 8640, 10080

Return Period(s) (years) 30
 Climate Change (%) 0

| PN | Storm | Return Period | Climate Change | First X Surcharge | First Y Flood | First Z Overflow | O/F Act. | Lvl Exc. |
|--------|-------------|---------------|----------------|-------------------|---------------|------------------|----------|----------|
| 21.000 | 15 Winter | 30 | 0% | | | | | |
| 21.001 | 15 Winter | 30 | 0% | 30/15 | Winter | | | |
| 21.002 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 22.000 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 21.003 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 23.000 | 15 Winter | 30 | 0% | | | | | |
| 21.004 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 24.000 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 21.005 | 2880 Winter | 30 | 0% | | | | | |
| 25.000 | 2880 Winter | 30 | 0% | 30/15 | Summer | | | |
| 21.006 | 2880 Winter | 30 | 0% | 30/15 | Summer | | | |
| 21.007 | 2880 Winter | 30 | 0% | | | | | |

Water Flooded Pipe

| US/MH | Level | Surch'ed Depth (m) | Volume (m³) | Flow / Cap. (l/s) | O'flow (l/s) | Flow Status |
|--------|-------|--------------------|-------------|-------------------|--------------|---------------------|
| PN | Name | (m) | | | | |
| 21.000 | S21-0 | 30.048 | -0.177 | 0.000 | 0.33 | 0.0 25.0 OK |
| 21.001 | S21-1 | 29.920 | 0.025 | 0.000 | 0.71 | 0.0 43.7 SURCHARGED |
| 21.002 | S21-2 | 29.861 | 0.212 | 0.000 | 1.00 | 0.0 74.8 SURCHARGED |

| | | |
|--|----------------|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 7 |
| Date 2018-10-18 File 181018_Overall Networks... | | Crown Square Developments |
| Designed by F. Timlin Checked by D. Gallery | |  |
| Micro Drainage | Network 2014.1 | |

Summary of Critical Results by Maximum Level (Rank 1) for Storm Blocks 2-4

| PN | US/MH | Water | | Flooded | | Pipe | | Status |
|--------|-------|--------|-----------|--------------------|-------------|--------------------------|------------|------------|
| | | Name | Level (m) | Surch'ed Depth (m) | Volume (m³) | Flow / O'flow Cap. (l/s) | Flow (l/s) | |
| 22.000 | S22-0 | 30.212 | 0.062 | 0.000 | 1.15 | 0.0 | 40.1 | SURCHARGED |
| 21.003 | S21-3 | 29.575 | 0.197 | 0.000 | 1.02 | 0.0 | 130.5 | SURCHARGED |
| 23.000 | S23-0 | 30.188 | -0.037 | 0.000 | 1.00 | 0.0 | 75.2 | OK |
| 21.004 | S21-4 | 29.366 | 0.111 | 0.000 | 1.15 | 0.0 | 245.5 | SURCHARGED |
| 24.000 | S24-0 | 30.320 | 0.020 | 0.000 | 1.07 | 0.0 | 78.4 | SURCHARGED |
| 21.005 | S21-5 | 27.448 | -0.652 | 0.000 | 0.00 | 0.0 | 14.9 | OK |
| 25.000 | S25-0 | 27.448 | 0.148 | 0.000 | 0.04 | 0.0 | 3.3 | SURCHARGED |
| 21.006 | S21-6 | 27.448 | 1.323 | 0.000 | 0.09 | 0.0 | 2.7 | SURCHARGED |
| 21.007 | S21-7 | 25.903 | -0.183 | 0.000 | 0.08 | 0.0 | 2.7 | OK |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 1 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm Phase 1+2

Pipe Sizes Standard Manhole Sizes Standard

FSR Rainfall Model - Scotland and Ireland
 Return Period (years) 5 Add Flow / Climate Change (%) 0
 M5-60 (mm) 17.500 Minimum Backdrop Height (m) 0.000
 Ratio R 0.300 Maximum Backdrop Height (m) 0.000
 Maximum Rainfall (mm/hr) 50 Min Design Depth for Optimisation (m) 1.200
 Maximum Time of Concentration (mins) 30 Min Vel for Auto Design only (m/s) 1.00
 Foul Sewage (l/s/ha) 0.000 Min Slope for Optimisation (1:X) 500
 Volumetric Runoff Coeff. 0.750

Designed with Level Inverts

Time Area Diagram for Storm Phase 1+2

| Time (mins) | Area (ha) | Time (mins) | Area (ha) | Time (mins) | Area (ha) |
|-------------|-----------|-------------|-----------|-------------|-----------|
| 0-4 | 0.587 | 4-8 | 2.049 | 8-12 | 0.245 |

Total Area Contributing (ha) = 2.881

Total Pipe Volume (m³) = 413.862

Network Design Table for Storm Phase 1+2

< - Indicates pipe capacity < flow

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|-------|------------|----------|-------------|-------------|-------------|-----------------|--------|----------|----------|---|
| 1.000 | 21.407 | 0.107 | 200.0 | 0.241 | 5.00 | 0.0 | 0.600 | o | 300 |  |
| 1.001 | 32.110 | 0.161 | 200.0 | 0.095 | 0.00 | 0.0 | 0.600 | o | 300 |  |
| 2.000 | 16.500 | 0.083 | 200.0 | 0.095 | 5.00 | 0.0 | 0.600 | o | 225 |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|--------------|-------------|-----------|----------------------|--------------------------|------------|----------------|-----------|-----------|------------|
| 1.000 | 50.00 | 5.32 | 29.925 | 0.241 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 32.6 |
| 1.001 | 50.00 | 5.80 | 29.818 | 0.336 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 45.5 |
| 2.000 | 50.00 | 5.30 | 29.925 | 0.095 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 12.9 |

| | | | | | | | | | | |
|--|--|--|--|--|--|--|--|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | | | | | | | | | Page 2 |
| Crown Square Developments | | | | | | | | | |  |
| Date 2018-10-18 File 181018_Overall Networks... | | | | | | | | | | Designed by F. Timlin Checked by D. Gallery |
| Micro Drainage | | | | | | | | | | Network 2014.1 |

Network Design Table for Storm Phase 1+2

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|---|
| 1.002 | 18.366 | 0.092 | 200.0 | 0.020 | 0.00 | 0.0 | 0.600 | o | 300 |  |
| 1.003 | 43.895 | 0.219 | 200.0 | 0.244 | 0.00 | 0.0 | 0.600 | o | 450 |  |
| 3.000 | 20.860 | 0.104 | 200.0 | 0.098 | 5.00 | 0.0 | 0.600 | o | 300 |  |
| 3.001 | 22.473 | 0.112 | 200.0 | 0.098 | 0.00 | 0.0 | 0.600 | o | 300 |  |
| 3.002 | 30.792 | 0.154 | 200.0 | 0.187 | 0.00 | 0.0 | 0.600 | o | 300 |  |
| 1.004 | 38.676 | 0.193 | 200.4 | 0.034 | 0.00 | 0.0 | 0.600 | o | 525 |  |
| 1.005 | 32.619 | 0.163 | 200.1 | 0.000 | 0.00 | 0.0 | 0.600 | o | 525 |  |
| 1.006 | 68.566 | 0.343 | 199.9 | 0.185 | 0.00 | 0.0 | 0.600 | o | 525 |  |
| 1.007 | 27.883 | 0.139 | 200.6 | 0.136 | 0.00 | 0.0 | 0.600 | o | 2000 |  |
| 4.000 | 56.923 | 0.285 | 200.0 | 0.210 | 5.00 | 0.0 | 0.600 | o | 300 |  |
| 5.000 | 55.052 | 0.275 | 200.2 | 0.233 | 5.00 | 0.0 | 0.600 | o | 300 |  |
| 4.001 | 6.196 | 0.031 | 199.9 | 0.100 | 0.00 | 0.0 | 0.600 | o | 300 |  |
| 4.002 | 8.212 | 0.027 | 300.0 | 0.295 | 0.00 | 0.0 | 0.600 | o | 600 |  |
| 4.003 | 4.463 | 0.015 | 300.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 600 |  |
| 1.008 | 38.789 | 0.200 | 193.9 | 0.118 | 0.00 | 0.0 | 0.600 | o | 2300 |  |
| 1.009 | 40.482 | 0.202 | 200.4 | 0.046 | 0.00 | 0.0 | 0.600 | o | 300 |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add (l/s) | Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|-----------------|----------------|--------------|-------------------------|-----------------------------|---------------|--------------|---------------|--------------|--------------|---------------|
| 1.002 | 50.00 | 6.08 | 29.657 | 0.451 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 61.1 | |
| 1.003 | 50.00 | 6.59 | 28.900 | 0.695 | 0.0 | 0.0 | 0.0 | 1.43 | 228.1 | 94.1 | |
| 3.000 | 50.00 | 5.31 | 29.925 | 0.098 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 13.3 | |
| 3.001 | 50.00 | 5.65 | 29.821 | 0.196 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 26.5 | |
| 3.002 | 50.00 | 6.11 | 29.708 | 0.383 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 51.9 | |
| 1.004 | 50.00 | 7.00 | 28.681 | 1.112 | 0.0 | 0.0 | 0.0 | 1.58 | 341.7 | 150.6 | |
| 1.005 | 50.00 | 7.34 | 28.488 | 1.112 | 0.0 | 0.0 | 0.0 | 1.58 | 342.0 | 150.6 | |
| 1.006 | 50.00 | 8.07 | 28.325 | 1.297 | 0.0 | 0.0 | 0.0 | 1.58 | 342.2 | 175.6 | |
| 1.007 | 50.00 | 5.13 | 27.982 | 0.000 | 40.0 | 0.0 | 0.0 | 3.61 | 11327.4 | 40.0 | |
| 4.000 | 50.00 | 5.86 | 29.925 | 0.210 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 28.4 | |
| 5.000 | 50.00 | 5.83 | 29.925 | 0.233 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 31.6 | |
| 4.001 | 50.00 | 5.95 | 29.640 | 0.543 | 0.0 | 0.0 | 0.0 | 1.11 | 78.4 | 73.5 | |
| 4.002 | 50.00 | 6.05 | 29.609 | 0.838 | 0.0 | 0.0 | 0.0 | 1.40 | 396.0 | 113.5 | |
| 4.003 | 50.00 | 6.10 | 29.582 | 0.838 | 0.0 | 0.0 | 0.0 | 1.40 | 396.0 | 113.5 | |
| 1.008 | 50.00 | 6.26 | 27.843 | 0.956 | 40.0 | 0.0 | 0.0 | 3.99 | 16586.2 | 169.5 | |
| 1.009 | 50.00 | 6.87 | 27.642 | 1.002 | 40.0 | 0.0 | 0.0 | 1.11 | 78.2 | 175.7 | |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 3 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Network Design Table for Storm Phase 1+2

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|----------------|
| 6.000 | 42.734 | 0.214 | 199.7 | 0.040 | 5.00 | 0.0 | 0.600 | o | 225 | 🔒 |
| 7.000 | 42.486 | 0.212 | 200.4 | 0.035 | 5.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 6.001 | 17.068 | 0.085 | 200.8 | 0.027 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 6.002 | 11.971 | 0.060 | 199.5 | 0.026 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 8.000 | 37.699 | 0.188 | 200.5 | 0.020 | 5.00 | 0.0 | 0.600 | o | 225 | 🔒 |
| 8.001 | 26.414 | 0.132 | 200.1 | 0.020 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 8.002 | 10.975 | 0.055 | 199.5 | 0.030 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 8.003 | 38.380 | 0.192 | 199.9 | 0.089 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 8.004 | 6.550 | 0.033 | 198.5 | 0.034 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 9.000 | 44.150 | 0.200 | 220.8 | 0.050 | 5.00 | 0.0 | 0.600 | o | 1500 | 🔒 |
| 8.005 | 33.826 | 0.169 | 200.2 | 0.075 | 0.00 | 0.0 | 0.600 | o | 375 | 🔓 |
| 6.003 | 8.078 | 0.040 | 202.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 375 | 🔓 |
| 6.004 | 22.501 | 0.075 | 300.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 600 | 🔓 |
| 6.005 | 2.811 | 0.009 | 312.3 | 0.000 | 0.00 | 0.0 | 0.600 | o | 600 | 🔓 |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|-----------------|----------------|--------------|-------------------------|-----------------------------|---------------|-------------------|--------------|--------------|---------------|
| 6.000 | 50.00 | 5.77 | 29.925 | 0.040 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 5.4 |
| 7.000 | 50.00 | 5.77 | 29.925 | 0.035 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 4.7 |
| 6.001 | 50.00 | 6.08 | 29.711 | 0.102 | 0.0 | 0.0 | 0.0 | 0.92 | 36.5 | 13.8 |
| 6.002 | 50.00 | 6.30 | 27.860 | 0.128 | 0.0 | 0.0 | 0.0 | 0.92 | 36.7 | 17.3 |
| 8.000 | 50.00 | 5.68 | 30.000 | 0.020 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 2.7 |
| 8.001 | 50.00 | 6.16 | 29.812 | 0.040 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 5.4 |
| 8.002 | 50.00 | 6.36 | 28.000 | 0.070 | 0.0 | 0.0 | 0.0 | 0.92 | 36.7 | 9.5 |
| 8.003 | 50.00 | 7.05 | 27.945 | 0.159 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 21.5 |
| 8.004 | 50.00 | 7.17 | 27.753 | 0.193 | 0.0 | 0.0 | 0.0 | 0.92 | 36.8 | 26.1 |
| 9.000 | 50.00 | 5.26 | 26.700 | 0.050 | 0.0 | 0.0 | 0.0 | 2.88 | 5094.9 | 6.8 |
| 8.005 | 50.00 | 7.61 | 26.500 | 0.318 | 0.0 | 0.0 | 0.0 | 1.28 | 141.0 | 43.1 |
| 6.003 | 50.00 | 7.72 | 26.331 | 0.446 | 0.0 | 0.0 | 0.0 | 1.27 | 140.4 | 60.4 |
| 6.004 | 50.00 | 5.27 | 26.291 | 0.000 | 50.0 | 0.0 | 0.0 | 1.40 | 396.0 | 50.0 |
| 6.005 | 50.00 | 5.30 | 26.216 | 0.000 | 50.0 | 0.0 | 0.0 | 1.37 | 388.1 | 50.0 |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 4 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Network Design Table for Storm Phase 1+2

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|---|
| 1.010 | 5.489 | 0.018 | 304.9 | 0.000 | 0.00 | 0.0 | 0.600 | o | 225 |  |
| 1.011 | 4.584 | 0.100 | 45.8 | 0.000 | 0.00 | 0.0 | 0.600 | o | 225 |  |
| 1.012 | 11.556 | 0.039 | 300.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 225 |  |
| 1.013 | 52.654 | 0.320 | 164.5 | 0.000 | 0.00 | 0.0 | 0.600 | o | 225 |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul Flow (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|-----------------|----------------|--------------|----------------------------|--------------------------------|--------------------|----------------------|--------------|--------------|---------------|
| 1.010 | 50.00 | 5.12 | 26.207 | 0.000 | 7.1 | 0.0 | 0.0 | 0.74 | 29.6 | 7.1 |
| 1.011 | 50.00 | 5.16 | 26.189 | 0.000 | 7.1 | 0.0 | 0.0 | 1.94 | 77.0 | 7.1 |
| 1.012 | 50.00 | 5.42 | 26.089 | 0.000 | 7.1 | 0.0 | 0.0 | 0.75 | 29.8 | 7.1 |
| 1.013 | 50.00 | 6.28 | 26.050 | 0.000 | 7.1 | 0.0 | 0.0 | 1.02 | 40.4 | 7.1 |

Free Flowing Outfall Details for Storm Phase 1+2

| Outfall Pipe Number | Outfall Name | C. Level (m) | I. Level (m) | Min I. Level (mm) | D,L (mm) | W (m) |
|------------------------|-----------------|-----------------|-----------------|-------------------------|-------------|----------|
| 1.013 | EX-S1 | 26.790 | 25.730 | 0.000 | 0 | 0 |

Simulation Criteria for Storm Phase 1+2

Volumetric Runoff Coeff 0.750 Additional Flow - % of Total Flow 0.000
Areal Reduction Factor 1.000 MADD Factor * 10m³/ha Storage 2.000
Hot Start (mins) 0 Inlet Coeffiecient 0.800
Hot Start Level (mm) 0 Flow per Person per Day (l/per/day) 0.000
Manhole Headloss Coeff (Global) 0.500 Run Time (mins) 60
Foul Sewage per hectare (l/s) 0.000 Output Interval (mins) 1

Number of Input Hydrographs 0 Number of Storage Structures 3
Number of Online Controls 4 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

| | | | |
|-----------------------------|--------|-----------------------|--------|
| Rainfall Model | FSR | Profile Type | Summer |
| Return Period (years) | 5 | Cv (Summer) | 0.750 |
| Region Scotland and Ireland | | Cv (Winter) | 0.840 |
| M5-60 (mm) | 17.500 | Storm Duration (mins) | 30 |
| Ratio R | 0.300 | | |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 5 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Online Controls for Storm Phase 1+2

Hydro-Brake Optimum® Manhole: S1-7, DS/PN: 1.007, Volume (m³): 21.8

| | |
|-----------------------------------|----------------------------|
| Unit Reference | MD-SHE-0254-4000-2000-4000 |
| Design Head (m) | 2.000 |
| Design Flow (l/s) | 40.0 |
| Flush-Flo™ | Calculated |
| Objective | Minimise upstream storage |
| Diameter (mm) | 254 |
| Invert Level (m) | 27.982 |
| Minimum Outlet Pipe Diameter (mm) | 300 |
| Suggested Manhole Diameter (mm) | 2100 |

| Control Points | Head (m) | Flow (l/s) |
|---------------------------|----------|------------|
| Design Point (Calculated) | 2.000 | 40.0 |
| Flush-Flo™ | 0.599 | 39.8 |
| Kick-Flo® | 1.297 | 32.5 |
| Mean Flow over Head Range | - | 34.5 |

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

| Depth (m) | Flow (l/s) |
|-----------|------------|-----------|------------|-----------|------------|-----------|------------|
| 0.100 | 8.2 | 1.200 | 35.2 | 3.000 | 48.6 | 7.000 | 73.3 |
| 0.200 | 26.1 | 1.400 | 33.7 | 3.500 | 52.4 | 7.500 | 75.8 |
| 0.300 | 36.8 | 1.600 | 35.9 | 4.000 | 55.8 | 8.000 | 78.2 |
| 0.400 | 38.7 | 1.800 | 38.0 | 4.500 | 59.1 | 8.500 | 80.5 |
| 0.500 | 39.6 | 2.000 | 40.0 | 5.000 | 62.2 | 9.000 | 82.8 |
| 0.600 | 39.8 | 2.200 | 41.8 | 5.500 | 65.2 | 9.500 | 85.0 |
| 0.800 | 39.3 | 2.400 | 43.6 | 6.000 | 68.0 | | |
| 1.000 | 38.0 | 2.600 | 45.4 | 6.500 | 70.7 | | |

Hydro-Brake Optimum® Manhole: S6-4, DS/PN: 6.004, Volume (m³): 4.0

| | |
|-----------------------------------|----------------------------|
| Unit Reference | MD-SHE-0284-5000-1800-5000 |
| Design Head (m) | 1.800 |
| Design Flow (l/s) | 50.0 |
| Flush-Flo™ | Calculated |
| Objective | Minimise upstream storage |
| Diameter (mm) | 284 |
| Invert Level (m) | 26.291 |
| Minimum Outlet Pipe Diameter (mm) | 300 |
| Suggested Manhole Diameter (mm) | 2100 |

| Control Points | Head (m) | Flow (l/s) |
|---------------------------|----------|------------|
| Design Point (Calculated) | 1.800 | 50.0 |
| Flush-Flo™ | 0.559 | 49.9 |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 6 |
| Date 2018-10-18 File 181018_Overall Networks... | | Crown Square Developments |
| Designed by F. Timlin Checked by D. Gallery | |  |
| Micro Drainage Network 2014.1 | | |

Hydro-Brake Optimum® Manhole: S6-4, DS/PN: 6.004, Volume (m³): 4.0

| Control Points | Head (m) | Flow (l/s) |
|---------------------------|----------|------------|
| Kick-Flo® | 1.224 | 41.5 |
| Mean Flow over Head Range | - | 42.7 |

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

| Depth (m) | Flow (l/s) |
|-----------|------------|-----------|------------|-----------|------------|-----------|------------|
| 0.100 | 8.9 | 1.200 | 42.5 | 3.000 | 63.9 | 7.000 | 96.5 |
| 0.200 | 29.3 | 1.400 | 44.3 | 3.500 | 68.9 | 7.500 | 99.8 |
| 0.300 | 46.8 | 1.600 | 47.2 | 4.000 | 73.5 | 8.000 | 103.0 |
| 0.400 | 49.0 | 1.800 | 50.0 | 4.500 | 77.8 | 8.500 | 106.1 |
| 0.500 | 49.8 | 2.000 | 52.6 | 5.000 | 81.9 | 9.000 | 109.1 |
| 0.600 | 49.9 | 2.200 | 55.0 | 5.500 | 85.8 | 9.500 | 112.0 |
| 0.800 | 48.9 | 2.400 | 57.4 | 6.000 | 89.5 | | |
| 1.000 | 47.1 | 2.600 | 59.7 | 6.500 | 93.1 | | |

Non Return Valve Manhole: S6-5, DS/PN: 6.005, Volume (m³): 10.9

Hydro-Brake Optimum® Manhole: S1-10, DS/PN: 1.010, Volume (m³): 9.8

| | |
|-----------------------------------|----------------------------|
| Unit Reference | MD-SHE-0110-7100-2000-7100 |
| Design Head (m) | 2.000 |
| Design Flow (l/s) | 7.1 |
| Flush-Flo™ | Calculated |
| Objective | Minimise upstream storage |
| Diameter (mm) | 110 |
| Invert Level (m) | 26.207 |
| Minimum Outlet Pipe Diameter (mm) | 150 |
| Suggested Manhole Diameter (mm) | 1200 |

| Control Points | Head (m) | Flow (l/s) |
|---------------------------|----------|------------|
| Design Point (Calculated) | 2.000 | 7.1 |
| Flush-Flo™ | 0.479 | 6.4 |
| Kick-Flo® | 0.979 | 5.1 |
| Mean Flow over Head Range | - | 5.8 |

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

| Depth (m) | Flow (l/s) |
|-----------|------------|-----------|------------|-----------|------------|-----------|------------|
| 0.100 | 3.8 | 0.300 | 6.1 | 0.500 | 6.4 | 0.800 | 6.0 |
| 0.200 | 5.6 | 0.400 | 6.3 | 0.600 | 6.3 | 1.000 | 5.1 |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 7 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Hydro-Brake Optimum® Manhole: S1-10, DS/PN: 1.010, Volume (m³): 9.8

| Depth (m) | Flow (l/s) |
|-----------|------------|-----------|------------|-----------|------------|-----------|------------|
| 1.200 | 5.6 | 2.400 | 7.7 | 5.000 | 10.9 | 8.000 | 13.7 |
| 1.400 | 6.0 | 2.600 | 8.0 | 5.500 | 11.4 | 8.500 | 14.1 |
| 1.600 | 6.4 | 3.000 | 8.6 | 6.000 | 11.9 | 9.000 | 14.5 |
| 1.800 | 6.8 | 3.500 | 9.2 | 6.500 | 12.4 | 9.500 | 14.9 |
| 2.000 | 7.1 | 4.000 | 9.8 | 7.000 | 12.8 | | |
| 2.200 | 7.4 | 4.500 | 10.4 | 7.500 | 13.3 | | |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 8 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Storage Structures for Storm Phase 1+2

Tank or Pond Manhole: S1-7, DS/PN: 1.007

Invert Level (m) 27.982

| Depth (m) | Area (m ²) | Depth (m) | Area (m ²) | Depth (m) | Area (m ²) |
|-----------|------------------------|-----------|------------------------|-----------|------------------------|
| 0.000 | 320.0 | 2.000 | 320.0 | 2.001 | 0.0 |

Tank or Pond Manhole: S1-9, DS/PN: 1.009

Invert Level (m) 27.642

| Depth (m) | Area (m ²) | Depth (m) | Area (m ²) | Depth (m) | Area (m ²) |
|-----------|------------------------|-----------|------------------------|-----------|------------------------|
| 0.000 | 250.0 | 2.300 | 250.0 | 2.301 | 0.0 |

Tank or Pond Manhole: S8-5, DS/PN: 8.005

Invert Level (m) 26.500

| Depth (m) | Area (m ²) | Depth (m) | Area (m ²) | Depth (m) | Area (m ²) |
|-----------|------------------------|-----------|------------------------|-----------|------------------------|
| 0.000 | 230.0 | 1.700 | 230.0 | 1.701 | 0.0 |

| | | |
|--|---|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 9 |
| Date 2018-10-18 File 181018_Overall Networks... | Crown Square Developments Designed by F. Timlin Checked by D. Gallery | |
| Micro Drainage | Network 2014.1 |  |

Summary of Critical Results by Maximum Level (Rank 1) for Storm Phase 1+2

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coeffiecient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 3
 Number of Online Controls 4 Number of Time/Area Diagrams 0
 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.300
 Region Scotland and Ireland Cv (Summer) 0.750
 M5-60 (mm) 17.500 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 100.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status ON
 DVD Status ON
 Inertia Status ON

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
 720, 960, 1440, 2160, 2880, 4320, 5760,
 7200, 8640, 10080

Return Period(s) (years) 100
 Climate Change (%) 10

| PN | Storm | Return Climate Period | First X Surcharge | First Y Flood | First Z Overflow | O/F Act. | Lvl Exc. |
|-------|-------------|-----------------------|-------------------|---------------|------------------|----------|----------|
| 1.000 | 15 Winter | 100 | +10% | 100/15 | Summer | | |
| 1.001 | 15 Winter | 100 | +10% | 100/15 | Summer | | |
| 2.000 | 15 Winter | 100 | +10% | 100/15 | Summer | | |
| 1.002 | 15 Winter | 100 | +10% | 100/15 | Summer | | |
| 1.003 | 1440 Winter | 100 | +10% | 100/15 | Summer | | |
| 3.000 | 15 Winter | 100 | +10% | 100/15 | Summer | | |
| 3.001 | 15 Winter | 100 | +10% | 100/15 | Summer | | |
| 3.002 | 15 Winter | 100 | +10% | 100/15 | Summer | | |
| 1.004 | 1440 Winter | 100 | +10% | 100/15 | Summer | | |
| 1.005 | 1440 Winter | 100 | +10% | 100/15 | Summer | | |
| 1.006 | 1440 Winter | 100 | +10% | 100/15 | Summer | | |
| 1.007 | 1440 Winter | 100 | +10% | | | | |
| 4.000 | 15 Winter | 100 | +10% | 100/15 | Summer | | |
| 5.000 | 15 Winter | 100 | +10% | 100/15 | Summer | | |
| 4.001 | 15 Winter | 100 | +10% | 100/15 | Summer | | |
| 4.002 | 15 Winter | 100 | +10% | 100/15 | Summer | | |
| 4.003 | 15 Summer | 100 | +10% | | | | |
| 1.008 | 1440 Winter | 100 | +10% | | | | |
| 1.009 | 1440 Winter | 100 | +10% | 100/15 | Summer | | |
| 6.000 | 15 Winter | 100 | +10% | | | | |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 10 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Summary of Critical Results by Maximum Level (Rank 1) for Storm Phase 1+2

| PN | Storm | Return Period | Climate Change | First X Surcharge | First Y Flood | First Z Overflow | O/F Act. | Lvl Exc. |
|-------|-------------|---------------|----------------|-------------------|---------------|------------------|----------|----------|
| 7.000 | 15 Winter | 100 | +10% | | | | | |
| 6.001 | 15 Winter | 100 | +10% | 100/15 Winter | | | | |
| 6.002 | 15 Summer | 100 | +10% | 100/15 Summer | | | | |
| 8.000 | 15 Winter | 100 | +10% | | | | | |
| 8.001 | 15 Winter | 100 | +10% | | | | | |
| 8.002 | 15 Winter | 100 | +10% | 100/15 Summer | | | | |
| 8.003 | 15 Winter | 100 | +10% | 100/15 Summer | | | | |
| 8.004 | 15 Winter | 100 | +10% | 100/15 Summer | | | | |
| 9.000 | 8640 Winter | 100 | +10% | | | | | |
| 8.005 | 8640 Winter | 100 | +10% | 100/30 Winter | | | | |
| 6.003 | 8640 Winter | 100 | +10% | 100/15 Summer | | | | |
| 6.004 | 8640 Winter | 100 | +10% | 100/60 Summer | | | | |
| 6.005 | 8640 Winter | 100 | +10% | 100/15 Winter | | | | |
| 1.010 | 1440 Winter | 100 | +10% | 100/15 Summer | | | | |
| 1.011 | 1440 Winter | 100 | +10% | | | | | |
| 1.012 | 1440 Winter | 100 | +10% | | | | | |
| 1.013 | 1440 Winter | 100 | +10% | | | | | |

| PN | Name | Water | | Flooded | | Pipe | | |
|-------|-------|--------|-----------|-------------------|-------------|-------------------|--------------|------------------|
| | | US/MH | Level (m) | Surched Depth (m) | Volume (m³) | Flow / Cap. (l/s) | O'flow (l/s) | Flow (l/s) |
| 1.000 | S1-0 | 30.787 | | 0.562 | 0.000 | 1.16 | 0.0 | 79.8 FLOOD RISK |
| 1.001 | S1-1 | 30.644 | | 0.526 | 0.000 | 1.49 | 0.0 | 106.6 SURCHARGED |
| 2.000 | S2-0 | 30.356 | | 0.206 | 0.000 | 0.99 | 0.0 | 32.2 SURCHARGED |
| 1.002 | S1-2 | 30.272 | | 0.315 | 0.000 | 2.13 | 0.0 | 143.6 SURCHARGED |
| 1.003 | S1-3 | 29.720 | | 0.370 | 0.000 | 0.08 | 0.0 | 16.0 SURCHARGED |
| 3.000 | S3-0 | 30.582 | | 0.357 | 0.000 | 0.51 | 0.0 | 34.8 SURCHARGED |
| 3.001 | S3-1 | 30.493 | | 0.373 | 0.000 | 0.98 | 0.0 | 67.8 SURCHARGED |
| 3.002 | S3-2 | 30.385 | | 0.377 | 0.000 | 1.86 | 0.0 | 132.5 SURCHARGED |
| 1.004 | S1-4 | 29.718 | | 0.513 | 0.000 | 0.09 | 0.0 | 25.6 SURCHARGED |
| 1.005 | S1-5 | 29.717 | | 0.704 | 0.000 | 0.09 | 0.0 | 25.5 SURCHARGED |
| 1.006 | TANK1 | 29.716 | | 0.866 | 0.000 | 0.09 | 0.0 | 29.6 SURCHARGED |
| 1.007 | S1-7 | 29.714 | | -0.268 | 0.000 | 0.00 | 0.0 | 10.3 OK |
| 4.000 | S4-0 | 30.846 | | 0.621 | 0.000 | 0.89 | 0.0 | 66.4 FLOOD RISK |
| 5.000 | S5-0 | 30.847 | | 0.622 | 0.000 | 0.94 | 0.0 | 69.4 FLOOD RISK |
| 4.001 | S4-1 | 30.641 | | 0.700 | 0.000 | 2.89 | 0.0 | 158.7 SURCHARGED |
| 4.002 | S4-2 | 30.221 | | 0.012 | 0.000 | 1.11 | 0.0 | 260.3 SURCHARGED |
| 4.003 | S4-3 | 30.182 | | 0.000 | 0.000 | 1.13 | 0.0 | 247.2 OK |
| 1.008 | TANK2 | 29.613 | | -0.529 | 0.000 | 0.00 | 0.0 | 29.5 OK |
| 1.009 | S1-9 | 29.612 | | 1.670 | 0.000 | 0.18 | 0.0 | 12.8 SURCHARGED |
| 6.000 | S6-0 | 30.031 | | -0.119 | 0.000 | 0.44 | 0.0 | 15.2 OK |
| 7.000 | S7-0 | 30.023 | | -0.127 | 0.000 | 0.38 | 0.0 | 13.3 OK |
| 6.001 | S6-1 | 29.938 | | 0.002 | 0.000 | 1.05 | 0.0 | 34.4 SURCHARGED |
| 6.002 | S6-2 | 28.135 | | 0.050 | 0.000 | 1.35 | 0.0 | 42.2 SURCHARGED |
| 8.000 | S8-0 | 30.073 | | -0.152 | 0.000 | 0.22 | 0.0 | 7.6 OK |
| 8.001 | S8-1 | 29.920 | | -0.117 | 0.000 | 0.46 | 0.0 | 15.5 OK |
| 8.002 | S8-2 | 28.732 | | 0.507 | 0.000 | 0.83 | 0.0 | 25.6 SURCHARGED |
| 8.003 | S8-3 | 28.667 | | 0.497 | 0.000 | 1.59 | 0.0 | 55.0 SURCHARGED |
| 8.004 | S8-4 | 28.160 | | 0.182 | 0.000 | 2.31 | 0.0 | 65.5 SURCHARGED |
| 9.000 | TANK3 | 28.116 | | -0.084 | 0.000 | 0.00 | 0.0 | 0.3 OK |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 11 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Summary of Critical Results by Maximum Level (Rank 1) for Storm Phase 1+2

| PN | US/MH Name | Water | | Flooded | | Pipe | | Status |
|-------|---------------|--------------|-----------------------|----------------|-----------------------------|------------|------|------------|
| | | Level (m) | Surch'ed Depth (m) | Volume (m³) | Flow / O'flow Cap. (l/s) | Flow (l/s) | | |
| 8.005 | S8-5 | 28.116 | 1.241 | 0.000 | 0.07 | 0.0 | 8.7 | SURCHARGED |
| 6.003 | S6-3 | 28.121 | 1.415 | 0.000 | 0.08 | 0.0 | 8.3 | FLOOD RISK |
| 6.004 | S6-4 | 28.121 | 1.230 | 0.000 | 0.02 | 0.0 | 7.1 | FLOOD RISK |
| 6.005 | S6-5 | 28.119 | 1.303 | 0.000 | 0.05 | 0.0 | 11.2 | SURCHARGED |
| 1.010 | S1-10 | 29.655 | 3.223 | 0.000 | 0.39 | 0.0 | 9.0 | SURCHARGED |
| 1.011 | PI | 26.258 | -0.156 | 0.000 | 0.20 | 0.0 | 9.0 | OK |
| 1.012 | S1-12 | 26.182 | -0.132 | 0.000 | 0.36 | 0.0 | 9.0 | OK |
| 1.013 | S1-13 | 26.124 | -0.152 | 0.000 | 0.23 | 0.0 | 9.0 | OK |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 1 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm Phase 1+2

Pipe Sizes Standard Manhole Sizes Standard

FSR Rainfall Model - Scotland and Ireland

| | | | |
|--------------------------------------|--------|---------------------------------------|-------|
| Return Period (years) | 5 | Add Flow / Climate Change (%) | 0 |
| M5-60 (mm) | 17.500 | Minimum Backdrop Height (m) | 0.000 |
| Ratio R | 0.300 | Maximum Backdrop Height (m) | 0.000 |
| Maximum Rainfall (mm/hr) | 50 | Min Design Depth for Optimisation (m) | 1.200 |
| Maximum Time of Concentration (mins) | 30 | Min Vel for Auto Design only (m/s) | 1.00 |
| Foul Sewage (l/s/ha) | 0.000 | Min Slope for Optimisation (1:X) | 500 |
| Volumetric Runoff Coeff. | 0.750 | | |

Designed with Level Inverts

Time Area Diagram for Storm Phase 1+2

| Time (mins) | Area (ha) | Time (mins) | Area (ha) | Time (mins) | Area (ha) |
|-------------|-----------|-------------|-----------|-------------|-----------|
| 0-4 | 0.587 | 4-8 | 2.049 | 8-12 | 0.245 |

Total Area Contributing (ha) = 2.881

Total Pipe Volume (m³) = 413.862

Network Design Table for Storm Phase 1+2

< - Indicates pipe capacity < flow

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|-------|------------|----------|-------------|-------------|-------------|-----------------|--------|----------|----------|---|
| 1.000 | 21.407 | 0.107 | 200.0 | 0.241 | 5.00 | 0.0 | 0.600 | o | 300 |  |
| 1.001 | 32.110 | 0.161 | 200.0 | 0.095 | 0.00 | 0.0 | 0.600 | o | 300 |  |
| 2.000 | 16.500 | 0.083 | 200.0 | 0.095 | 5.00 | 0.0 | 0.600 | o | 225 |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|--------------|-------------|-----------|----------------------|--------------------------|------------|----------------|-----------|-----------|------------|
| 1.000 | 50.00 | 5.32 | 29.925 | 0.241 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 32.6 |
| 1.001 | 50.00 | 5.80 | 29.818 | 0.336 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 45.5 |
| 2.000 | 50.00 | 5.30 | 29.925 | 0.095 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 12.9 |

| | | | | | | | | | | | |
|--|--|--|--|--|--|--|--|--|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | | | | | | | | | | Page 2 |
| Crown Square Developments | | | | | | | | | | |  |
| Date 2018-10-18 File 181018_Overall Networks... | | | | | | | | | | | Designed by F. Timlin Checked by D. Gallery |
| Micro Drainage Network 2014.1 | | | | | | | | | | | |

Network Design Table for Storm Phase 1+2

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|---|
| 1.002 | 18.366 | 0.092 | 200.0 | 0.020 | 0.00 | 0.0 | 0.600 | o | 300 |  |
| 1.003 | 43.895 | 0.219 | 200.0 | 0.244 | 0.00 | 0.0 | 0.600 | o | 450 |  |
| 3.000 | 20.860 | 0.104 | 200.0 | 0.098 | 5.00 | 0.0 | 0.600 | o | 300 |  |
| 3.001 | 22.473 | 0.112 | 200.0 | 0.098 | 0.00 | 0.0 | 0.600 | o | 300 |  |
| 3.002 | 30.792 | 0.154 | 200.0 | 0.187 | 0.00 | 0.0 | 0.600 | o | 300 |  |
| 1.004 | 38.676 | 0.193 | 200.4 | 0.034 | 0.00 | 0.0 | 0.600 | o | 525 |  |
| 1.005 | 32.619 | 0.163 | 200.1 | 0.000 | 0.00 | 0.0 | 0.600 | o | 525 |  |
| 1.006 | 68.566 | 0.343 | 199.9 | 0.185 | 0.00 | 0.0 | 0.600 | o | 525 |  |
| 1.007 | 27.883 | 0.139 | 200.6 | 0.136 | 0.00 | 0.0 | 0.600 | o | 2000 |  |
| 4.000 | 56.923 | 0.285 | 200.0 | 0.210 | 5.00 | 0.0 | 0.600 | o | 300 |  |
| 5.000 | 55.052 | 0.275 | 200.2 | 0.233 | 5.00 | 0.0 | 0.600 | o | 300 |  |
| 4.001 | 6.196 | 0.031 | 199.9 | 0.100 | 0.00 | 0.0 | 0.600 | o | 300 |  |
| 4.002 | 8.212 | 0.027 | 300.0 | 0.295 | 0.00 | 0.0 | 0.600 | o | 600 |  |
| 4.003 | 4.463 | 0.015 | 300.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 600 |  |
| 1.008 | 38.789 | 0.200 | 193.9 | 0.118 | 0.00 | 0.0 | 0.600 | o | 2300 |  |
| 1.009 | 40.482 | 0.202 | 200.4 | 0.046 | 0.00 | 0.0 | 0.600 | o | 300 |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add (l/s) | Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|-----------------|----------------|--------------|-------------------------|-----------------------------|---------------|--------------|---------------|--------------|--------------|---------------|
| 1.002 | 50.00 | 6.08 | 29.657 | 0.451 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 61.1 | |
| 1.003 | 50.00 | 6.59 | 28.900 | 0.695 | 0.0 | 0.0 | 0.0 | 1.43 | 228.1 | 94.1 | |
| 3.000 | 50.00 | 5.31 | 29.925 | 0.098 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 13.3 | |
| 3.001 | 50.00 | 5.65 | 29.821 | 0.196 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 26.5 | |
| 3.002 | 50.00 | 6.11 | 29.708 | 0.383 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 51.9 | |
| 1.004 | 50.00 | 7.00 | 28.681 | 1.112 | 0.0 | 0.0 | 0.0 | 1.58 | 341.7 | 150.6 | |
| 1.005 | 50.00 | 7.34 | 28.488 | 1.112 | 0.0 | 0.0 | 0.0 | 1.58 | 342.0 | 150.6 | |
| 1.006 | 50.00 | 8.07 | 28.325 | 1.297 | 0.0 | 0.0 | 0.0 | 1.58 | 342.2 | 175.6 | |
| 1.007 | 50.00 | 5.13 | 27.982 | 0.000 | 40.0 | 0.0 | 0.0 | 3.61 | 11327.4 | 40.0 | |
| 4.000 | 50.00 | 5.86 | 29.925 | 0.210 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 28.4 | |
| 5.000 | 50.00 | 5.83 | 29.925 | 0.233 | 0.0 | 0.0 | 0.0 | 1.11 | 78.3 | 31.6 | |
| 4.001 | 50.00 | 5.95 | 29.640 | 0.543 | 0.0 | 0.0 | 0.0 | 1.11 | 78.4 | 73.5 | |
| 4.002 | 50.00 | 6.05 | 29.609 | 0.838 | 0.0 | 0.0 | 0.0 | 1.40 | 396.0 | 113.5 | |
| 4.003 | 50.00 | 6.10 | 29.582 | 0.838 | 0.0 | 0.0 | 0.0 | 1.40 | 396.0 | 113.5 | |
| 1.008 | 50.00 | 6.26 | 27.843 | 0.956 | 40.0 | 0.0 | 0.0 | 3.99 | 16586.2 | 169.5 | |
| 1.009 | 50.00 | 6.87 | 27.642 | 1.002 | 40.0 | 0.0 | 0.0 | 1.11 | 78.2 | 175.7 | |

97 Henry Street
Limerick
Ireland

Crown Square Developments

Date 2018-10-18
File 181018_Overall Networks...

Designed by F. Timlin
Checked by D. Gallery



Micro Drainage

Network 2014.1

Network Design Table for Storm Phase 1+2

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|----------------|
| 6.000 | 42.734 | 0.214 | 199.7 | 0.040 | 5.00 | 0.0 | 0.600 | o | 225 | 🔒 |
| 7.000 | 42.486 | 0.212 | 200.4 | 0.035 | 5.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 6.001 | 17.068 | 0.085 | 200.8 | 0.027 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 6.002 | 11.971 | 0.060 | 199.5 | 0.026 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 8.000 | 37.699 | 0.188 | 200.5 | 0.020 | 5.00 | 0.0 | 0.600 | o | 225 | 🔒 |
| 8.001 | 26.414 | 0.132 | 200.1 | 0.020 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 8.002 | 10.975 | 0.055 | 199.5 | 0.030 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 8.003 | 38.380 | 0.192 | 199.9 | 0.089 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 8.004 | 6.550 | 0.033 | 198.5 | 0.034 | 0.00 | 0.0 | 0.600 | o | 225 | 🔓 |
| 9.000 | 44.150 | 0.200 | 220.8 | 0.050 | 5.00 | 0.0 | 0.600 | o | 1500 | 🔒 |
| 8.005 | 33.826 | 0.169 | 200.2 | 0.075 | 0.00 | 0.0 | 0.600 | o | 375 | 🔓 |
| 6.003 | 8.078 | 0.040 | 202.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 375 | 🔓 |
| 6.004 | 22.501 | 0.075 | 300.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 600 | 🔓 |
| 6.005 | 2.811 | 0.009 | 312.3 | 0.000 | 0.00 | 0.0 | 0.600 | o | 600 | 🔓 |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|-----------------|----------------|--------------|-------------------------|-----------------------------|---------------|-------------------|--------------|--------------|---------------|
| 6.000 | 50.00 | 5.77 | 29.925 | 0.040 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 5.4 |
| 7.000 | 50.00 | 5.77 | 29.925 | 0.035 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 4.7 |
| 6.001 | 50.00 | 6.08 | 29.711 | 0.102 | 0.0 | 0.0 | 0.0 | 0.92 | 36.5 | 13.8 |
| 6.002 | 50.00 | 6.30 | 27.860 | 0.128 | 0.0 | 0.0 | 0.0 | 0.92 | 36.7 | 17.3 |
| 8.000 | 50.00 | 5.68 | 30.000 | 0.020 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 2.7 |
| 8.001 | 50.00 | 6.16 | 29.812 | 0.040 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 5.4 |
| 8.002 | 50.00 | 6.36 | 28.000 | 0.070 | 0.0 | 0.0 | 0.0 | 0.92 | 36.7 | 9.5 |
| 8.003 | 50.00 | 7.05 | 27.945 | 0.159 | 0.0 | 0.0 | 0.0 | 0.92 | 36.6 | 21.5 |
| 8.004 | 50.00 | 7.17 | 27.753 | 0.193 | 0.0 | 0.0 | 0.0 | 0.92 | 36.8 | 26.1 |
| 9.000 | 50.00 | 5.26 | 26.700 | 0.050 | 0.0 | 0.0 | 0.0 | 2.88 | 5094.9 | 6.8 |
| 8.005 | 50.00 | 7.61 | 26.500 | 0.318 | 0.0 | 0.0 | 0.0 | 1.28 | 141.0 | 43.1 |
| 6.003 | 50.00 | 7.72 | 26.331 | 0.446 | 0.0 | 0.0 | 0.0 | 1.27 | 140.4 | 60.4 |
| 6.004 | 50.00 | 5.27 | 26.291 | 0.000 | 50.0 | 0.0 | 0.0 | 1.40 | 396.0 | 50.0 |
| 6.005 | 50.00 | 5.30 | 26.216 | 0.000 | 50.0 | 0.0 | 0.0 | 1.37 | 388.1 | 50.0 |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 4 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Network Design Table for Storm Phase 1+2

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Auto Design |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|---|
| 1.010 | 5.489 | 0.018 | 304.9 | 0.000 | 0.00 | 0.0 | 0.600 | o | 225 |  |
| 1.011 | 4.584 | 0.100 | 45.8 | 0.000 | 0.00 | 0.0 | 0.600 | o | 225 |  |
| 1.012 | 11.556 | 0.039 | 300.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 225 |  |
| 1.013 | 52.654 | 0.320 | 164.5 | 0.000 | 0.00 | 0.0 | 0.600 | o | 225 |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul Flow (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|-----------------|----------------|--------------|----------------------------|--------------------------------|--------------------|----------------------|--------------|--------------|---------------|
| 1.010 | 50.00 | 5.12 | 26.207 | 0.000 | 7.1 | 0.0 | 0.0 | 0.74 | 29.6 | 7.1 |
| 1.011 | 50.00 | 5.16 | 26.189 | 0.000 | 7.1 | 0.0 | 0.0 | 1.94 | 77.0 | 7.1 |
| 1.012 | 50.00 | 5.42 | 26.089 | 0.000 | 7.1 | 0.0 | 0.0 | 0.75 | 29.8 | 7.1 |
| 1.013 | 50.00 | 6.28 | 26.050 | 0.000 | 7.1 | 0.0 | 0.0 | 1.02 | 40.4 | 7.1 |

Free Flowing Outfall Details for Storm Phase 1+2

| Outfall Pipe Number | Outfall Name | C. Level (m) | I. Level (m) | Min I. Level (mm) | D,L (mm) | W (m) |
|------------------------|-----------------|-----------------|-----------------|-------------------------|-------------|----------|
| 1.013 | EX-S1 | 26.790 | 25.730 | 0.000 | 0 | 0 |

Simulation Criteria for Storm Phase 1+2

Volumetric Runoff Coeff 0.750 Additional Flow - % of Total Flow 0.000
Areal Reduction Factor 1.000 MADD Factor * 10m³/ha Storage 2.000
Hot Start (mins) 0 Inlet Coeffiecient 0.800
Hot Start Level (mm) 0 Flow per Person per Day (l/per/day) 0.000
Manhole Headloss Coeff (Global) 0.500 Run Time (mins) 60
Foul Sewage per hectare (l/s) 0.000 Output Interval (mins) 1

Number of Input Hydrographs 0 Number of Storage Structures 3
Number of Online Controls 4 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

| | | | |
|-----------------------------|--------|-----------------------|--------|
| Rainfall Model | FSR | Profile Type | Summer |
| Return Period (years) | 5 | Cv (Summer) | 0.750 |
| Region Scotland and Ireland | | Cv (Winter) | 0.840 |
| M5-60 (mm) | 17.500 | Storm Duration (mins) | 30 |
| Ratio R | 0.300 | | |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 5 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Online Controls for Storm Phase 1+2

Hydro-Brake Optimum® Manhole: S1-7, DS/PN: 1.007, Volume (m³): 21.8

| | |
|-----------------------------------|----------------------------|
| Unit Reference | MD-SHE-0254-4000-2000-4000 |
| Design Head (m) | 2.000 |
| Design Flow (l/s) | 40.0 |
| Flush-Flo™ | Calculated |
| Objective | Minimise upstream storage |
| Diameter (mm) | 254 |
| Invert Level (m) | 27.982 |
| Minimum Outlet Pipe Diameter (mm) | 300 |
| Suggested Manhole Diameter (mm) | 2100 |

| Control Points | Head (m) | Flow (l/s) |
|---------------------------|----------|------------|
| Design Point (Calculated) | 2.000 | 40.0 |
| Flush-Flo™ | 0.599 | 39.8 |
| Kick-Flo® | 1.297 | 32.5 |
| Mean Flow over Head Range | - | 34.5 |

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

| Depth (m) | Flow (l/s) |
|-----------|------------|-----------|------------|-----------|------------|-----------|------------|
| 0.100 | 8.2 | 1.200 | 35.2 | 3.000 | 48.6 | 7.000 | 73.3 |
| 0.200 | 26.1 | 1.400 | 33.7 | 3.500 | 52.4 | 7.500 | 75.8 |
| 0.300 | 36.8 | 1.600 | 35.9 | 4.000 | 55.8 | 8.000 | 78.2 |
| 0.400 | 38.7 | 1.800 | 38.0 | 4.500 | 59.1 | 8.500 | 80.5 |
| 0.500 | 39.6 | 2.000 | 40.0 | 5.000 | 62.2 | 9.000 | 82.8 |
| 0.600 | 39.8 | 2.200 | 41.8 | 5.500 | 65.2 | 9.500 | 85.0 |
| 0.800 | 39.3 | 2.400 | 43.6 | 6.000 | 68.0 | | |
| 1.000 | 38.0 | 2.600 | 45.4 | 6.500 | 70.7 | | |

Hydro-Brake Optimum® Manhole: S6-4, DS/PN: 6.004, Volume (m³): 4.0

| | |
|-----------------------------------|----------------------------|
| Unit Reference | MD-SHE-0284-5000-1800-5000 |
| Design Head (m) | 1.800 |
| Design Flow (l/s) | 50.0 |
| Flush-Flo™ | Calculated |
| Objective | Minimise upstream storage |
| Diameter (mm) | 284 |
| Invert Level (m) | 26.291 |
| Minimum Outlet Pipe Diameter (mm) | 300 |
| Suggested Manhole Diameter (mm) | 2100 |

| Control Points | Head (m) | Flow (l/s) |
|---------------------------|----------|------------|
| Design Point (Calculated) | 1.800 | 50.0 |
| Flush-Flo™ | 0.559 | 49.9 |

| | | |
|--|----------------|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | | Page 6 |
| Date 2018-10-18 File 181018_Overall Networks... | | Crown Square Developments |
| Designed by F. Timlin Checked by D. Gallery | |  |
| Micro Drainage | Network 2014.1 | |

Hydro-Brake Optimum® Manhole: S6-4, DS/PN: 6.004, Volume (m³): 4.0

| Control Points | Head (m) | Flow (l/s) |
|---------------------------|----------|------------|
| Kick-Flo® | 1.224 | 41.5 |
| Mean Flow over Head Range | - | 42.7 |

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

| Depth (m) | Flow (l/s) |
|-----------|------------|-----------|------------|-----------|------------|-----------|------------|
| 0.100 | 8.9 | 1.200 | 42.5 | 3.000 | 63.9 | 7.000 | 96.5 |
| 0.200 | 29.3 | 1.400 | 44.3 | 3.500 | 68.9 | 7.500 | 99.8 |
| 0.300 | 46.8 | 1.600 | 47.2 | 4.000 | 73.5 | 8.000 | 103.0 |
| 0.400 | 49.0 | 1.800 | 50.0 | 4.500 | 77.8 | 8.500 | 106.1 |
| 0.500 | 49.8 | 2.000 | 52.6 | 5.000 | 81.9 | 9.000 | 109.1 |
| 0.600 | 49.9 | 2.200 | 55.0 | 5.500 | 85.8 | 9.500 | 112.0 |
| 0.800 | 48.9 | 2.400 | 57.4 | 6.000 | 89.5 | | |
| 1.000 | 47.1 | 2.600 | 59.7 | 6.500 | 93.1 | | |

Non Return Valve Manhole: S6-5, DS/PN: 6.005, Volume (m³): 10.9

Hydro-Brake Optimum® Manhole: S1-10, DS/PN: 1.010, Volume (m³): 9.8

| | |
|-----------------------------------|----------------------------|
| Unit Reference | MD-SHE-0110-7100-2000-7100 |
| Design Head (m) | 2.000 |
| Design Flow (l/s) | 7.1 |
| Flush-Flo™ | Calculated |
| Objective | Minimise upstream storage |
| Diameter (mm) | 110 |
| Invert Level (m) | 26.207 |
| Minimum Outlet Pipe Diameter (mm) | 150 |
| Suggested Manhole Diameter (mm) | 1200 |

| Control Points | Head (m) | Flow (l/s) |
|---------------------------|----------|------------|
| Design Point (Calculated) | 2.000 | 7.1 |
| Flush-Flo™ | 0.479 | 6.4 |
| Kick-Flo® | 0.979 | 5.1 |
| Mean Flow over Head Range | - | 5.8 |

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

| Depth (m) | Flow (l/s) |
|-----------|------------|-----------|------------|-----------|------------|-----------|------------|
| 0.100 | 3.8 | 0.300 | 6.1 | 0.500 | 6.4 | 0.800 | 6.0 |
| 0.200 | 5.6 | 0.400 | 6.3 | 0.600 | 6.3 | 1.000 | 5.1 |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 7 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Hydro-Brake Optimum® Manhole: S1-10, DS/PN: 1.010, Volume (m³): 9.8

| Depth (m) | Flow (l/s) |
|-----------|------------|-----------|------------|-----------|------------|-----------|------------|
| 1.200 | 5.6 | 2.400 | 7.7 | 5.000 | 10.9 | 8.000 | 13.7 |
| 1.400 | 6.0 | 2.600 | 8.0 | 5.500 | 11.4 | 8.500 | 14.1 |
| 1.600 | 6.4 | 3.000 | 8.6 | 6.000 | 11.9 | 9.000 | 14.5 |
| 1.800 | 6.8 | 3.500 | 9.2 | 6.500 | 12.4 | 9.500 | 14.9 |
| 2.000 | 7.1 | 4.000 | 9.8 | 7.000 | 12.8 | | |
| 2.200 | 7.4 | 4.500 | 10.4 | 7.500 | 13.3 | | |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 8 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Storage Structures for Storm Phase 1+2

Tank or Pond Manhole: S1-7, DS/PN: 1.007

Invert Level (m) 27.982

| Depth (m) | Area (m ²) | Depth (m) | Area (m ²) | Depth (m) | Area (m ²) |
|-----------|------------------------|-----------|------------------------|-----------|------------------------|
| 0.000 | 320.0 | 2.000 | 320.0 | 2.001 | 0.0 |

Tank or Pond Manhole: S1-9, DS/PN: 1.009

Invert Level (m) 27.642

| Depth (m) | Area (m ²) | Depth (m) | Area (m ²) | Depth (m) | Area (m ²) |
|-----------|------------------------|-----------|------------------------|-----------|------------------------|
| 0.000 | 250.0 | 2.300 | 250.0 | 2.301 | 0.0 |

Tank or Pond Manhole: S8-5, DS/PN: 8.005

Invert Level (m) 26.500

| Depth (m) | Area (m ²) | Depth (m) | Area (m ²) | Depth (m) | Area (m ²) |
|-----------|------------------------|-----------|------------------------|-----------|------------------------|
| 0.000 | 230.0 | 1.700 | 230.0 | 1.701 | 0.0 |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 9 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Summary of Critical Results by Maximum Level (Rank 1) for Storm Phase 1+2

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coeffiecient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 3
 Number of Online Controls 4 Number of Time/Area Diagrams 0
 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.300
 Region Scotland and Ireland Cv (Summer) 0.750
 M5-60 (mm) 17.500 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 100.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status ON
 DVD Status ON
 Inertia Status ON

Profile(s)

Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
 720, 960, 1440, 2160, 2880, 4320, 5760,
 7200, 8640, 10080

Return Period(s) (years) 30
 Climate Change (%) 0

| PN | Storm | Return Climate Period | Change | First X Surcharge | First Y Flood | First Z Overflow | O/F Act. | Lvl Exc. |
|-------|------------|-----------------------|--------|-------------------|---------------|------------------|----------|----------|
| 1.000 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 1.001 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 2.000 | 15 Winter | 30 | 0% | | | | | |
| 1.002 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 1.003 | 15 Winter | 30 | 0% | | | | | |
| 3.000 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 3.001 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 3.002 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 1.004 | 960 Winter | 30 | 0% | | | | | |
| 1.005 | 960 Winter | 30 | 0% | 30/240 | Winter | | | |
| 1.006 | 960 Winter | 30 | 0% | 30/180 | Winter | | | |
| 1.007 | 960 Winter | 30 | 0% | | | | | |
| 4.000 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 5.000 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 4.001 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 4.002 | 15 Winter | 30 | 0% | | | | | |
| 4.003 | 15 Winter | 30 | 0% | | | | | |
| 1.008 | 960 Winter | 30 | 0% | | | | | |
| 1.009 | 960 Winter | 30 | 0% | 30/15 | Summer | | | |
| 6.000 | 15 Winter | 30 | 0% | | | | | |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 10 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Summary of Critical Results by Maximum Level (Rank 1) for Storm Phase 1+2

| PN | Storm | Return Period | Climate Change | First X Surcharge | First Y Flood | First Z Overflow | O/F Act. | Lvl Exc. |
|--------------|------------------|---------------|----------------|-------------------|---------------|------------------|----------|----------|
| 7.000 | 15 Winter | 30 | 0% | | | | | |
| 6.001 | 15 Winter | 30 | 0% | | | | | |
| 6.002 | 15 Winter | 30 | 0% | | | | | |
| 8.000 | 15 Winter | 30 | 0% | | | | | |
| 8.001 | 15 Winter | 30 | 0% | | | | | |
| 8.002 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 8.003 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 8.004 | 15 Winter | 30 | 0% | 30/15 | Summer | | | |
| 9.000 | 7200 Winter | 30 | 0% | | | | | |
| 8.005 | 7200 Winter | 30 | 0% | 30/120 | Summer | | | |
| 6.003 | 7200 Winter | 30 | 0% | 30/15 | Winter | | | |
| 6.004 | 7200 Winter | 30 | 0% | 30/120 | Winter | | | |
| 6.005 | 7200 Winter | 30 | 0% | 30/60 | Winter | | | |
| 1.010 | 960 Winter | 30 | 0% | 30/15 | Summer | | | |
| 1.011 | 960 Winter | 30 | 0% | | | | | |
| 1.012 | 960 Winter | 30 | 0% | | | | | |
| 1.013 | 960 Winter | 30 | 0% | | | | | |

| PN | US/MH Name | Water Level (m) | Flooded | | | Pipe | | |
|--------------|-------------|-----------------|-------------------|--------------|-------------------|--------------|--------------|-------------------|
| | | | Surched Depth (m) | Volume (m³) | Flow / Cap. (l/s) | O'flow (l/s) | Flow | Status |
| 1.000 | S1-0 | 30.355 | 0.130 | 0.000 | 0.82 | 0.0 | 56.5 | SURCHARGED |
| 1.001 | S1-1 | 30.273 | 0.155 | 0.000 | 1.08 | 0.0 | 77.1 | SURCHARGED |
| 2.000 | S2-0 | 30.119 | -0.031 | 0.000 | 0.77 | 0.0 | 24.9 | OK |
| 1.002 | S1-2 | 30.074 | 0.117 | 0.000 | 1.55 | 0.0 | 104.4 | SURCHARGED |
| 1.003 | S1-3 | 29.208 | -0.142 | 0.000 | 0.78 | 0.0 | 159.1 | OK |
| 3.000 | S3-0 | 30.274 | 0.049 | 0.000 | 0.35 | 0.0 | 24.1 | SURCHARGED |
| 3.001 | S3-1 | 30.191 | 0.070 | 0.000 | 0.67 | 0.0 | 46.1 | SURCHARGED |
| 3.002 | S3-2 | 30.098 | 0.090 | 0.000 | 1.27 | 0.0 | 90.6 | SURCHARGED |
| 1.004 | S1-4 | 29.123 | -0.082 | 0.000 | 0.09 | 0.0 | 25.3 | OK |
| 1.005 | S1-5 | 29.121 | 0.108 | 0.000 | 0.09 | 0.0 | 24.8 | SURCHARGED |
| 1.006 | TANK1 | 29.120 | 0.270 | 0.000 | 0.09 | 0.0 | 27.7 | SURCHARGED |
| 1.007 | S1-7 | 29.118 | -0.864 | 0.000 | 0.00 | 0.0 | 12.3 | OK |
| 4.000 | S4-0 | 30.405 | 0.180 | 0.000 | 0.65 | 0.0 | 48.0 | SURCHARGED |
| 5.000 | S5-0 | 30.428 | 0.203 | 0.000 | 0.72 | 0.0 | 53.2 | SURCHARGED |
| 4.001 | S4-1 | 30.278 | 0.338 | 0.000 | 2.20 | 0.0 | 120.8 | SURCHARGED |
| 4.002 | S4-2 | 30.040 | -0.170 | 0.000 | 0.80 | 0.0 | 187.6 | OK |
| 4.003 | S4-3 | 30.015 | -0.167 | 0.000 | 0.85 | 0.0 | 186.0 | OK |
| 1.008 | TANK2 | 29.021 | -1.121 | 0.000 | 0.00 | 0.0 | 28.1 | OK |
| 1.009 | S1-9 | 29.021 | 1.079 | 0.000 | 0.17 | 0.0 | 12.1 | SURCHARGED |
| 6.000 | S6-0 | 30.012 | -0.138 | 0.000 | 0.30 | 0.0 | 10.6 | OK |
| 7.000 | S7-0 | 30.005 | -0.145 | 0.000 | 0.27 | 0.0 | 9.3 | OK |
| 6.001 | S6-1 | 29.865 | -0.071 | 0.000 | 0.80 | 0.0 | 26.0 | OK |
| 6.002 | S6-2 | 28.085 | 0.000 | 0.000 | 1.00 | 0.0 | 31.4 | OK |
| 8.000 | S8-0 | 30.060 | -0.165 | 0.000 | 0.15 | 0.0 | 5.3 | OK |
| 8.001 | S8-1 | 29.900 | -0.137 | 0.000 | 0.32 | 0.0 | 10.9 | OK |
| 8.002 | S8-2 | 28.347 | 0.122 | 0.000 | 0.59 | 0.0 | 18.1 | SURCHARGED |
| 8.003 | S8-3 | 28.310 | 0.140 | 0.000 | 1.13 | 0.0 | 39.2 | SURCHARGED |
| 8.004 | S8-4 | 28.050 | 0.072 | 0.000 | 1.66 | 0.0 | 47.2 | SURCHARGED |
| 9.000 | TANK3 | 27.659 | -0.541 | 0.000 | 0.00 | 0.0 | 0.3 | OK |

| | | |
|--|--|---|
| Punch Consulting Engineers 97 Henry Street Limerick Ireland | Crown Square Developments | Page 11 |
| Date 2018-10-18 File 181018_Overall Networks... | Designed by F. Timlin Checked by D. Gallery |  |
| Micro Drainage | Network 2014.1 | |

Summary of Critical Results by Maximum Level (Rank 1) for Storm Phase 1+2

| PN | US/MH Name | Water | | Flooded | | Pipe | | Status |
|-------|---------------|--------------|-----------------------|----------------|-----------------------------|------------|-----|------------|
| | | Level (m) | Surch'ed Depth (m) | Volume (m³) | Flow / O'flow Cap. (l/s) | Flow (l/s) | | |
| 8.005 | S8-5 | 27.659 | 0.784 | 0.000 | 0.07 | 0.0 | 8.6 | SURCHARGED |
| 6.003 | S6-3 | 27.693 | 0.987 | 0.000 | 0.08 | 0.0 | 8.2 | SURCHARGED |
| 6.004 | S6-4 | 27.694 | 0.803 | 0.000 | 0.03 | 0.0 | 7.9 | SURCHARGED |
| 6.005 | S6-5 | 27.662 | 0.846 | 0.000 | 0.04 | 0.0 | 9.3 | SURCHARGED |
| 1.010 | S1-10 | 29.066 | 2.634 | 0.000 | 0.35 | 0.0 | 8.2 | SURCHARGED |
| 1.011 | PI | 26.254 | -0.160 | 0.000 | 0.18 | 0.0 | 8.2 | OK |
| 1.012 | S1-12 | 26.177 | -0.137 | 0.000 | 0.32 | 0.0 | 8.2 | OK |
| 1.013 | S1-13 | 26.120 | -0.155 | 0.000 | 0.21 | 0.0 | 8.2 | OK |

Appendix G - Correspondence with Galway City Council

Memorandum

Project Title Crown Square Development

From Fergal Timlin

Project No 183106

To Frank Clancy, John Sheehan

Subject Surface Water Sewers Strategy High Level Overview

Cc Joe McGuire

Date 11am 30th July 2018

Notes:

Meeting Location: Galway City Council Headquarters, Forster Street, Galway City

Meeting Attendees: Frank Clancy (FC) (Senior Executive Engineer) GCC, John Sheehan (JS) (Executive Technician) GCC, Fergal Timlin (FT) PUNCH, Emma Tarpey (ET) PUNCH

Meeting Agenda: Surface Water Sewers Strategy High Level Overview


- 1) Following introductions with JS & FC, during which they welcomed the development, FT began the meeting by providing an overview of the previous drainage construction drawings and identifying the locations of the 3 previously proposed attenuation tanks.
- 2) JS had a copy of the original planning drawings and noted that the locations of the attenuation tanks had changed from that submitted with the original planning application (061102-004PL2 attached). However JS acknowledged that the attenuation tank locations as shown on the drainage construction drawing (mpp-sw-00-03-003 C2) may have been agreed between PUNCH and GCC post planning.
- 3) The previous drainage construction drawing notes that surface water discharge from the site is 30l/s (which equates to 6l/s/ha)
 - a) FC and JS noted that surface water discharge from the site of 30l/s (which equates to 6l/s/ha) appears not to be in compliance with Galway City Council general requirements and the Greater Dublin Strategic Drainage Strategy (GDSDS)
 - b) JS noted that the 450mm surface water pipe (that the previously proposed development outfalls to) downsizes to a 375mm pipe downstream of the site on the Monivea Road. JS has concerns that the existing surface water sewers may not have capacity to accept 30l/s. A figure closer to 2l/s/ha was noted by JS.
 - c) JS/FC noted that they will undertake a capacity assessment of the existing surface water network
 - d) FT noted that prior to the development of the Crown site, there was no form of surface water control on site and peak flows from the site were estimated at 170 l/s. FT also noted that surface water currently being pumped from the site is likely to be greater than 30l/s. JS agreed that the flow from the site was currently greater than 2l/s/ha but this is a temporary arrangement.
 - e) JS/FC noted that for GCC to consider a surface water discharge greater than 2l/s/ha, justification for same would be required and that a number of SuDS measures will be required to be utilised on the site (green roofs, rainwater harvesting etc.). JS/FC noted that proposed surface water discharge rate and SuDS proposals require to be agreed with GCC
- 4) JS noted that there is an existing 600mm surface water pipe located to the north of the site. JS noted that GCC have a preference for discharging the outflow from the site to this sewer

-
- a) FT noted that attenuation tank 2 was already constructed and that it was proposed to maintain the tank as constructed, with an outflow to the 450mm surface water pipe on the Monivea Road.
 - b) FC/JS noted that the surface water outfall from the site may be split between the existing 450mm and 600mm surface water pipes
 - 5) FT noted the route of the proposed surface water outfall is subject to location of existing services etc. A GPR survey is due to commence shortly to confirm location of services.
 - 6) FC/JS noted that they are happy to liaise with the design team as the overall design is developed

Signed: _____
Fergal D. Timlin

Date: 2nd August 2018


Appendix H - CFRAM Mapping



AFA Boundary
Modelled River Centreline

Grey squares have no extent shown for this suite of flood maps so no maps have been produced.

10% AEP





IMPORTANT USER NOTE:
THE VIEWER OF THIS MAP SHOULD REFER TO THE DISCLAIMER, GUIDANCE NOTES AND CONDITIONS OF USE THAT ACCOMPANY THIS MAP.



WESTERN CFRAM STUDY
CATCHMENT FLOOD RISK ASSESSMENT AND MANAGEMENT

| | |
|---------------------------------|-----------------------------------|
| Map No.: W3/GWLW_DPFCD100_F1 | Sheet: 7 of 21 |
| Map Type: Flood Depth (10% AEP) | |
| Map Area: HPW | Source: Fluvial Scenario: Current |
| Drawn By: KF | Date: May 2017 Scale: |
| Checked By: TS | Date: May 2017 |
| Approved By: JC | Date: May 2017 |
| Original @ A3 | |





IMPORTANT USER NOTE:
THE VIEWER OF THIS MAP SHOULD REFER TO THE DISCLAIMER, GUIDANCE NOTES AND CONDITIONS OF USE THAT ACCOMPANY THIS MAP.




JBA Consulting
24 Grove Island
Cobh
Limerick
Ireland




WESTERN
CFRAM
STUDY

CATCHMENT FLOOD RISK
ASSESSMENT AND MANAGEMENT


| | |
|----------------------------------|-----------------|
| Map No.: W3/GWLW_DPF/C0001_F1 | Sheet: 7 of 21 |
| Map Type: Flood Depth (0.1% AEP) | Final |
| Map Area: HPW | Source: Fluvial |
| Drawn By: KF | Date: May 2017 |
| Checked By: TS | Date: May 2017 |
| Approved By: JC | Date: May 2017 |
| Map No.: W3/GWLW_DPF/C0001_F1 | 1:5,000 |
| Original @ A3 | Sheet: |





AFA Boundary
Modelled River
Centreline

1% AEP




IMPORTANT USER NOTE:
THE VIEWER OF THIS MAP SHOULD REFER TO THE
DISCLAIMER, GUIDANCE NOTES AND CONDITIONS
OF USE THAT ACCOMPANY THIS MAP.






The Office of Public Works
Jonathan Swift Street
Trimm, Co. Meath






| Map No.: W3/GWLW_DPF/C010_01 | Sheet: 7 of 21 |
|-------------------------------|----------------|
| Map Type: Flood Depth (% AEP) | Final |
| Map Area: HPW | |
| Drawn By: KF | Date: May 2017 |
| Checked By: TS | Date: May 2017 |
| Approved By: JC | Date: May 2017 |
| Scale: 1:5,000 | |
| Original @ A3 | |












AFA Boundary
Modelled River Centreline

0.1% AEP


Inhabitants (No / Ha)




IMPORTANT USER NOTE:
THE VIEWER OF THIS MAP SHOULD REFER TO THE DISCLAIMER, GUIDANCE NOTES AND CONDITIONS OF USE THAT ACCOMPANY THIS MAP.



| | |
|--|---------------------|
| Map Galway City No. Inhabitants (0.1% AEP) | Final |
| Map Type: | HPW |
| Map Area: | KF |
| Drawn by: | Date: Jun 2017 |
| Checked by: | Date: Jun 2017 |
| Approved by: | Date: Jun 2017 |
| Map No: | W30GW_RIFC001_F1_07 |
| Sheet: | 7 of 21 |






IMPORTANT USER NOTE:
THE VIEWER OF THIS MAP SHOULD REFER TO THE
DISCLAIMER, GUIDANCE NOTES AND CONDITIONS
OF USE THAT ACCOMPANY THIS MAP.



JBA Consulting
24 Grove Island
Cobh
Limerick
Ireland

WESTERN CFRAM STUDY
CATCHMENT FLOOD RISK ASSESSMENT AND MANAGEMENT

| Map No: | W30GW_RIFCD010_F1_07 | Sheet: | 7 of 21 |
|----------------|--|---------|----------|
| Map Type: | Specific Risk - No inhabitants (% AEP) | Final | |
| Map Area: | HPW | Source: | |
| Drawn by: | KF | Date: | Jun 2017 |
| Checked by: | TS | Date: | Jun 2017 |
| Approved by: | JC | Date: | Jun 2017 |
| Original @ A3: | 1:5,000 | Scale: | |





Risk Map: Type of Economic Activity
UoM 30 Corrib

**Fluvial 0.1% AEP
Economic Activity**

| | |
|--|----------------|
| | Property |
| | Infrastructure |
| | Rural |
| | Economic |

| | |
|--|----------------------|
| | Risk |
| | Activity Not At Risk |

IMPORTANT USER NOTE:
THE VIEWER OF THIS MAP SHOULD REFER TO THE
DISCLAIMER, GUIDANCE NOTES AND CONDITIONS
OF USE THAT ACCOMPANY THIS MAP.



JBA Consulting
The Office of Public Works
Jonathan Swift Street
Trim Co. Meath

WESTERN

CFRAM
STUDY
CATCHMENT FLOOD RISK
ASSESSMENT AND MANAGEMENT

| Map No: | W30_RTFCD001_F1-01 | Sheet: | 1 of 1 |
|--------------|---------------------------|---------|-----------|
| Map Type: | Type of Economic Activity | Final | |
| Map Area: | UoM 30 | Source: | Flood |
| Drawn by: | DR | Date: | Aug 2016 |
| Checked by: | JC | Date: | Aug 2016 |
| Approved by: | SPW | Date: | Aug 2016 |
| Map No: | W30_RTFCD001_F1-01 | Scale: | 1:300,000 |

