RKD	NUMBER	APPENDIX 2
	REVISION	A
	DATE	22/07/2019
RESIDENTIAL QUALITY AUDIT	ISSUE	PLANNING
RESIDENTIAL QUALITY AUDIT	Page 1	

			Page 1							
UNIT TYPE	UNIT SIZE	TYPE VARIANT	FOOTPRINT INDIVIDUAL	FOOTPRINT TOTAL	UNIT NUMBER	TOTAL UNIT NUMBER	%	UNIT DESCRIPTION		
		A1	70	3080	44			SEMI-DETACHED (Gable Fronted)		
	3 BED	A1a	70	1400	20	76	20.3%	SEMI-DETACHED		
Α	2 PED	A2	70	280	4	76	20.5%	SEMI-DETACHED (Gable Fronted / Side Access)		
		A3	72	576	8			SEMI-DETACHED (Bay Window)		
		B1	70	140	2			TERRACE (Gable Fronted / Side Access)		
В	3 BED	B2	70	1120	16	42	11.2%	TERRACE		
B	3 860	В3	72	1584	22	42	11.270	TERRACE (End Terrace / Bay Window)		
		B4	72	144	2			TERRACE (End Terrace / Side Access)		
		C1	70	3640	52			SEMI-DETACHED (Gable Fronted)		
С	4 BED	C1A	70	560	8	67	17.9%	SEMI-DETACHED (Gable Fronted / Side Access)		
		C2	70	490	7			DETACHED (Side Access)		
D	1 BED	D1	N/A		16	16	4.3%	APARTMENT (First floor)		
E	2 BED	E1	101		26	34	9.1%	DUPLEX (Ground Level - Front Access)		
_	Z DLD	E2	101	3421	8	34	5.170	DUPLEX (Ground Level - Side Access)		
F	3 BED	F1	N/A		10	18 4.8%	4.8%	DUPLEX (2 Storey - Front Access)		
•	3 525	F2	N/A		8	10	4.070	DUPLEX (2 Storey - Side Access)		
		1A			14					
	1 BED Apt.	1B			4	30	8.0%	1 Bed Apartment		
		1C			12					
		2A			14					
G		2B	COMBINED FOOTPRINT FOR APARTMENT BLOCKS	2904	14					
		2C			14					
	2 BED Apt.	2D			14	92	24.5%	2 Bed Apartment		
		2E			28					
		2F			4					
		2G		40000	4					
TOTAL				19339	375					

SITE AREA (DENSITY)	SQM	95139
SITE AREA (DENSITY)	Hectares	9.51
DENSITY		39.42

PUBLIC OPEN SPACE					
SITE AREA (REDLINE EXCL. HOSPITAL ST.)	SQM	109252			
OPEN SPACE	SQM	18024			
OPEN SPACE	Hectares	1.80			
	% Provided	16.5%			

Overall Mix					
	No.	%			
1 Bed	46	12.3%			
2 Bed	126	33.6%			
3 Bed	136	36.3%			
4 Bed	67	17.9%			
Total	375				

	Notes & References
*	Housing Areas Based on 'Sustainable Residential Developments in Urban Areas' - May 2009
**	Apartment Areas Based on 'Sustainable Urban Housing: Design Standards for New Apartments' - March 2018
***	Masterplan refers to Quality Housing for Sustainable Communities - 2007
***	Amenity space figures based on Kildare County Council Development Plan

Refer to Communal Amenity Section of RKD Design Statement for clarification on nature and layout of Communal Amenity spaces.
64.2% Dual Aspect figure achieved, higher than minimum allowance of 50% as per SPPR4 in 'Design Standards for New Apartments'
Maximum of 7 units per floor per core achieved, lower than maximum requirement of 12 in SPPR6 in 'Design Standards for New Apartments'

age 2

UNIT TYPE	UNIT SIZE	TYPE VARIANT	PARKING REQUIRED	PARKING PROVIDED	UNIT AREA REQUIRED GROSS (m2)	UNIT AREA ACHIEVED GROSS (m2)	UNIT AREA ACHIEVED NET (m2)	FLOOR AREA ABOVE MINIMUM REQUIRED	% FLOOR AREA ABOVE MINIMUM REQUIRED	TOTAL AREA
		A1			92	117	117	25	27.2%	5148
Α	3 BED	A1a	2 / unit	152	92	117	117	25	27.2%	2340
A	3 BED	A2	2 / unit	132	92	121	121	29	31.5%	484
		A3			92	121	121	29	31.5%	968
		B1			92	121	121	29	31.5%	242
В	3 BED	B2	2 / unit	84	92	117	117	25	27.2%	1872
ь	3 DLD	В3	2 / unit	04	92	121	121	29	31.5%	2662
		B4			92	125	125	33	35.9%	250
		C1			110	151	151	41	37.3%	7852
С	4 BED	C1A	2 / unit	134	110	153	153	43	39.1%	1224
		C2			110	153	153	43	39.1%	1071
D	1 BED	D1	1 / unit + 1 visitor / 4 units		45	59	59	14	31.1%	944
E	2 BED	E1	1 / unit + 1 visitor / 4 units	85	73	82	82	9	12.3%	2132
-	2 020	E2	17 41111.7 1 11311.01 7 4 41111.5		73	82	82	9	12.3%	656
F	3 BED	F1	1 / unit + 1 visitor / 4 units		90	115	115	25	27.8%	1150
	3 525	F2	17 dilit / 1 visitor / 4 dilits		90	115	115	25	27.8%	920
		1A				53.2	51.7	8.2	18.2%	745
	1 BED Apt.	1B	1 / unit + 1 visitor / 4 units		45	56.5	55.2	11.5	25.6%	226
		1C				51.3	50	6.3	14.0%	616
		2A				86.3	84.6	13.3	18.2%	1208
G		2B		156		89.2	87.9	16.2	22.2%	1249
		2C		255		85.6	84	12.6	17.3%	1198
	2 BED Apt.	2D	1 / unit + 1 visitor / 4 units		73	84.4	82.9	11.4	15.6%	1182
		2E				86.8	85.1	13.8	18.9%	2430
		2F				93.6	91.7	20.6	28.2%	374
		2G				85	83.7	12	16.4%	340
TOTAL				611						39483

Page 3

						Page 3		AGGREGATE KITCHEN	
UNIT TYPE	UNIT SIZE	TYPE VARIANT	ASPECT	NUMBER OF BEDROOMS	NUMBER OF BEDSPACES	AGGREGATE BEDROOM AREA REQUIRED (m2)	AGGREGATE BEDROOM AREA ACHIEVED (m2)	LIVING DINING AREA REQUIRED (m2)	AGGREGATE KITCHEN LIVING DINING AREA ACHIEVED (m2)
		A1	Dual	3	5	32	32.4	34	39.3
Α	3 BED	A1a	Dual	3	5	32	32.4	34	39.3
^	3 000	A2	Dual	3	5	32	32.4	34	41.8
		A3	Dual	3	5	32	34.3	34	41.2
		B1	Dual	3	5	32	32.4	34	41.8
В	3 BED	B2	Dual	3	5	32	32.4	34	39.3
ь	3 000	В3	Dual	3	5	32	34.3	34	41.2
		B4	Dual	3	5	32	34.3	34	43.7
		C1	Dual	4	7	43	44.7	40	40
С	4 BED	C1A	Dual	4	7	43	44.7	40	42.5
		C2	Dual	4	7	43	44.7	40	42.5
D	1 BED	D1	Dual	1	2	11.4	13	23	23.3
E	2 BED	E1	Dual	2	4	24.4	24.4	30	30.9
-	Z DLD	E2	Dual	2	4	24.4	24.5	30	30.5
F	3 BED	F1	Dual	3	5	31.5	32.2	34	34.4
•	3 525	F2	Dual	3	5	31.5	32.2	34	34.4
		1A	Single	1	2	11.4	12.4	23	23.8
	1 BED Apt.	1B	Single	1	2	11.4	14.4	23	23.5
		1C	Varies	1	2	11.4	11.4	23	25.5
		2A	Single	2	4	24.4	25.7	30	30.6
G		2B	Dual	2	4	24.4	28.1	30	32
Ğ		2C	Single	2	4	24.4	26.8	30	30.1
	2 BED Apt.	2D	Varies	2	4	24.4	25.1	30	30.6
		2 E	Varies	2	4	24.4	25.7	30	30.6
		2F	Dual	2	4	24.4	25.6	30	34.4
		2G	Dual	2	4	24.4	26.7	30	30.7
TOTAL									

Dual Aspect Apartments							
Unit Type Variants	Unit No.	Dual Aspect No.	Dual Aspect %	Dual Aspect % Total			
D1	16	16	100.0%				
E1 / E2	34	34	100.0%				
F1 / F2	18	18	100.0%	64.20/			
1A / 1B / 1C	30	4	13.3%	64.2%			
2A / 2B / 2C / 2D / 2E / 2F / 2G	92	50	54.3%				
Total	190	122	64.2%				

Page 4

UNIT TYPE	UNIT SIZE	TYPE VARIANT	AGGREGATE STORAGE AREA REQUIRED (m2)	AGGREGATE STORAGE AREA ACHIEVED (m2)	PRIVATE AMENITY SPACE REQURED PER UNIT (m2)	PRIVATE AMENITY SPACE ACHIEVED (m2)	PRIVATE AMENITY SPACE TOTAL (m2)
		A1	9	9	60	varies / minimum 60	varies
Α	3 BED	A1a	9	9	60	varies / minimum 60	varies
A	2 PED	A2	9	9	60	varies / minimum 60	varies
		A3	9	9	60	varies / minimum 60	varies
		B1	9	9	60	varies / minimum 60	varies
В	3 BED	B2	9	9	60	varies / minimum 60	varies
ь	2 PED	В3	9	9	60	varies / minimum 60	varies
		B4	9	9	60	varies / minimum 60	varies
		C1	10	10.3	75	varies / minimum 75	varies
С	4 BED	C1A	10	10.3	75	varies / minimum 75	varies
		C2	10	10.3	75	varies / minimum 75	varies
D	1 BED	D1	3	3.7	5	7	112
Е	2 BED	E1	6	6	7	varies / minimum 16.9	varies
<u> </u>	Z BED	E2	6	6	7	varies / minimum 16.9	varies
F	3 BED	F1	9	9	9	12.1	121
Г	3 DLD	F2	9	9	9	12.1	96.8
		1A	3	3	5	varies / minimum 5	varies
	1 BED Apt.	1B	3	3.4	5	varies / minimum 5	varies
		1C	3	3.3	5	varies / minimum 5	varies
		2A	6	6.3	7	varies / minimum 7	varies
G		2B	6	6.8	7	varies / minimum 7	varies
J		2C	6	6	7	varies / minimum 7	varies
	2 BED Apt.	2D	6	6.2	7	varies / minimum 7	varies
		2E	6	6.1	7	varies / minimum 7	varies
		2F	6	6.1	7	varies / minimum 7	varies
		2G	6	6.6	7	varies / minimum 7	varies
TOTAL							

age 5

UNIT TYPE	UNIT SIZE	TYPE VARIANT	Page 5 COMMUNAL AMENITY SPACE REQUIRED (m2)	COMMUNAL AMENITY SPACE ACHIEVED (m2)	COMMUNAL AMENITY SPACE TOTAL (m2)	CEILING HEIGHT / M
		A1	N/A	N/A	N/A	2.45
		A1a	N/A	N/A	N/A	2.45
Α	3 BED	A2	N/A	N/A	N/A	2.45
		A3	N/A	N/A	N/A	2.45
		B1	N/A	N/A	N/A	2.45
		B2	N/A	N/A	N/A	2.45
В	3 BED	B3	N/A	N/A	N/A	2.45
		B4	N/A	N/A	N/A	2.45
		C1	N/A	, N/A	N/A	2.45
С	4 BED	C1A	N/A	N/A	N/A	2.45
		C2	N/A	N/A	N/A	2.45
D	1 BED	D1	5	varies / minimum 5		2.45
E	2 050	E1	7	varies / minimum 7		2.7
E	2 BED	E2	7	varies / minimum 7	675	2.7
F	3 BED	F1	9	varies / minimum 9		2.45
Г	3 BED	F2	9	varies / minimum 9		2.45
		1A	5	varies / minimum 5		2.7
	1 BED Apt.	1B	5	varies / minimum 5		2.7
		1C	5	varies / minimum 5		2.7
		2A	7	varies / minimum 7		2.7
G		2B	7	varies / minimum 7	1934	2.7
•		2C	7	varies / minimum 7	1334	2.7
	2 BED Apt.	2D	7	varies / minimum 7		2.7
		2E	7	varies / minimum 7		2.7
		2F	7	varies / minimum 7		2.7
		2G	7	varies / minimum 7		2.7
TOTAL			1274		2609	

	Bike Parking Requirements (Apartments) - 1 per Bed Space & 1 Guest per 2 Units	Car Parking Requirements (Apartments) - 1 Per Unit & 1 Guest per 4 Units
Total	275	153
Resident	214	122
Guest	61	31
No. Of Total V	Which Are Required To Be Accessible for People with Disabilities	8

	Bike Parking Requirements (Duplexes) - 1 per Bed Space & 1 Guest per 2 Units	Car Parking Requirements (Duplexes) - 1 Per Unit & 1 Guest per 4 Units
Total	172	85
Resident	138	68
Guest	34	17
No. Of Total	Which Are Required To Be Accessible for People with Disabilities	4

	Bike Parking Provided (Apartments)	Car Parking Provided (Apartments)
Total	275 (of which 196 are in basement)	156 (of which 16 are on Grade)
Resident	214 (of which 196 are in basement)	122
Guest	61	34 (of which 11 are on Grade)
No. Of	Total Which Are Accessible for People with Disabilities	9 (of which 5 are on Grade)

	Bike Parking Provided (Duplexes) - Provided within both Private and Communal Amenity Spaces	Car Parking Provided (Duplexes) - Provided in front of / adjacent to units
Total	172	85
Resident	138	68
Guest	34	17
No. Of Total Which Are Accessible for People with Disabilities		4