



Pathway
---------


## Proposed Development Buildings

MATERIALS KEY

- 1 Retaining Walls: Concrete retaining wall with Random Rubble finish with reference to local stone typologies 2 Solid Walls to Buildings: Reconstituted Stone/Concrete
- 3
- <u>Glazing System:</u> Anodised/Tiger coated proprietary glazing system 4
- Metal Rain Screen: Laser cut translucent metal feature panels
- 5 Glazing System: Feature panel over glazing

6

- Canopy: Projecting Aluminium Canopy Colour to match metal feature panels 7
- Ballasted Roof: Proprietary bitumen flat roof warm roof const on precast concrete supports
- NOTE: ALL MATERIALS FOR AGREEMENT WITH CORK COUNTY COUNCIL PRIOR TO CONSTRUCTION



E.I.A.R. Dursey Island Cable Car & Visitor Centre Development Figure 4.6 Mainland Station - Building 3 Originator | Volume | Location Type | Role | DCCVC - ROD - STR - SW\_AE - DR - CH - 4.6 Scale (A1) AS SHOWN Date: May 2019 Job No: 18.148 Rev: -