



RETENTION

Existing Hedgerows to be Retained: 1,015 Linear Metres

EXISTING VEGETATION
Existing hedgerows to be retained and protected during the course of construction.

Existing Regenerative Woodland to be Retained: 945 Sq.m

EXISTING VEGETATION
Remedial Works: Crown Raising to produce a 2m clear stem

Existing Trees and Understorey to be Retained: 4268 Sq.m

EXISTING VEGETATION
Remedial Works: Crown Raising to produce a 2m clear stem

EXISTING TREES
Existing trees to be retained and protected during the course of construction.

REPLACEMENT

Proposed Hedgerow Planting: 1865 Linear Metres

ALL HEDGEROW PLANTING TYPES:
Hedgerow Planting:
Prunus lusitanica, 60-90cm cg at 250mm centres:

Native Hedgerow Planting:
15% Crataegus monogyna, 60-90cm br at 250mm centres.
10% Euonymus europaeus, 60-90cm br at 250mm centres
15% Malus sylvestris, 60-90cm br at 250mm centres
20% Prunus spinosa, 60-90cm br at 250mm centres
15% Prunus avium, 60-90cm br at 250mm centres
15% Sorbus aucuparia, 60-90cm br at 250mm centres
5% Sambucus nigra, 60-90cm br at 250mm centres
5% Salix caprea, 60-90cm br at 250mm centres

Thornless Hedgerow Planting:
35% Acer campestre, 60-90cm br at 250mm centres.
20% Corylus avellana, 60-90cm br at 250mm centres
10% Ilex aquifolium, 2L cg at 250mm centres
20% Euonymus europaeus, 60-90cm br at 250mm centres.
15% Sorbus aucuparia, 60-90cm br at 250mm centres

Proposed Tree Planting: 855 No.

PROPOSED MIXED SPECIES

REMOVAL

Existing Hedgerows to be Removed: 590 Linear Metres

EXISTING VEGETATION
Existing hedgerows to be removed.



Landscape Plan
Scale 1:1000

No.	Revision	Date	By	PROPOSED DEVELOPMENT ON LANDS AT CAPDOO AND ABBEYLANDS, CLANE, CO. KILDARE. LANDSCAPE DETAILS-HEDGEROW REMOVAL, RETENTION AND REPLACEMENT
Landmark Designs Ltd. BALLINAFAGH PROSPEROUS NAAS CO. KILDARE M: 086 851 9294 LANDSCAPE DESIGN & CONSULTANCY E: gwen@landmarkdesigns@gmail.com				Date: 01.11.2019 Job No: P356 Scale: 1:1000 Drawn: GT
Designed: GWEN TIERNEY Landscape Architect. Status: SPD PLANNING 201905				Drawing No: 02 Rev: