



Pyrus calleryana 'Chanticleer'



Acer platanoides 'Drummondii'



Acer platanoides 'Deborah'



Tilia cordata 'Greenspire'



Quercus petraea

- LANDSCAPE NOTES:
1. ALL PLANTS ARE TO BE OF HEALTHY STOCK AND PRODUCED LOCALLY WHERE POSSIBLE
 2. ALL PLANT FAILURES ARE TO BE REPLACED WITH IN THE FIRST PLANTING SEASON
 3. TOP SOIL TO BE OF GOOD QUALITY ENRICHED WITH ORGANIC MATTER.
 4. LAWNS TO HAVE A MINIMUM OF 200MM OF TOP SOIL OVER 300MM OF SUB SOIL.
 5. SHRUB AREAS ARE TO HAVE A MINIMUM OF 450MM TOP SOIL.
 6. TREE PITS ARE TO BE .900MM * 900MM LOOSE FORKED WITH FREE DRAINING GRANULAR STONE .100 DEEP TO THE BASE. WHERE TREES ARE IN CLOSE PROXIMITY TO SERVICES AND BUILDINGS ROOT BARRIER MEMBRANE IS TO BE USED TO PROTECT STRUCTURES
 7. ALL TREES ARE TO BE STAKED AND TIED WITH RABBIT PROTECTION GUARDS FITTED.
 8. WILDFLOWER MEADOW SEED TO BE NATIVE SPECIES WITH NATIVE PROVINANCE
 9. ALL LANDSCAPE WORKS SHOULD BE CARRIED OUT BY QUALIFIED LANDSCAPE CONTRACTORS TO ENSURE THE STANDARD OF WORKS COMPLY WITH BEST WORKS PRACTICE.

REFERENCE NOTES SCHEDULE AREA4

SYMBOL	DESCRIPTION	QTY	DETAIL
1	PRIVATE AMENITY SPACE	4,799 m ²	
2	PUBLIC SPACE	1,104 m ²	
3	SCRUB SCREENING RETAINED	7,586 m ²	
4	RUSHES	3,324 m ²	
7	EXISTING VEGETATION	2,248 m ²	
9	LOW NATURAL GROUND COVER TO RAIL EMBANKMENT	2,484 m ²	
10	EXISTING TREE SCREENING ADJACENT TO SITE	1,788 m ²	
15	ROCK OUT CROP	9	
17	BENCH GABION BASKE T- SPLIT STONE INFILL - WITH TIMBER SEAT.	3	
20	DECORATIVE GRAVEL PATH	54.0 m ²	
21	PAVING FLAGS	33.7 m ²	

PLANT SCHEDULE AREA4

TREES	BOTANICAL NAME / COMMON NAME	CONT	QTY	
	ACER PLATANOIDES 'COLUMNARE' / COLUMNAR NORWAY MAPLE	10-12CM BR	23	
	ACER PLATANOIDES 'DEBORAH' / DEBORAH MAPLE	14-16CM RB	11	
	ACER PLATANOIDES 'DRUMMONDII' / NORWAY MAPLE	10-12CM BR	3	
	ACER SACCHARINUM / SILVER MAPLE	10-12CM BR	3	
	BETULA JACQUEMONTII / JACQUEMONTII BIRCH	12-14CM BR	25	
	BETULA JACQUEMONTII / JACQUEMONTII BIRCH	16-18CM RB	16	
	BETULA NIGRA / RIVER BIRCH	12-14CM BR	18	
	BETULA PENDULA / EUROPEAN WHITE BIRCH	14-16CM RB	7	
	BETULA PUBESCENS / DOWNY BIRCH	160-200CM	57	
	BETULA UTILIS JACQUEMONTII / WHITEBARKED HIMALAYAN BIRCH	14-16CM RB	6	
	CRATAEGUS LAEVIGATA PAULS SCARLET / RED HAWTHORN	12-14CM BR	7	
	PINUS SYLVESTRIS / SCOTCH PINE	10L	7	
	PYRUS CALLERYANA 'CHANTICLEER' / CHANTICLEER PEAR	10-12CM BR	17	
	QUERCUS PETRAEA / DURMAST OAK	18-20CM RB	12	
	SALIX CAPREA / FRENCH PUSSY WILLOW	10-12CM BR	8	
	SALIX CINEREA / LARGE GREY WILLOW	12-14CM BR	2	
	SORBUS ARIA LUTEOCENS / CHESS APPLE	12-14CM BR	1	
	SORBUS X THURINGIACA 'FASTIGIATA' / OAKLEAF MOUNTAIN ASH	14-16CM RB	4	
	TILIA CORDATA 'GREENSPIRE' / GREENSPIRE LITTLELEAF LINDEN	12-14CMRB	4	
SHRUBS	BOTANICAL NAME / COMMON NAME	CONT	QTY	
	CRATAEGUS MONOGYNA / ONESEED HAWTHORN	60-90 CM BR	40	
	LIGUSTRUM VULGARE / PRIVET	60-90 CM BR	126	
GROUND COVERS	BOTANICAL NAME / COMMON NAME	CONT	SPACING	QTY
	GRASS PO SEED / LAWN	SEED		714.7 m ²

- DRAWING NOTES
1. See architects drawing and sections for all internal boundary details
 2. See Engineers details for road surfaces, pathways and tactile surfaces.
 3. Item 18 refers to Otter protection fence see details on Sheet 02

LANDSCAPE - DESIGN - PLANNING - CONSULTANCY
DESIGN & BUILD - ARBORICULTURE

UNIT 5 C CLONARD VILLAGE, WEXFORD
landscapeplanning@btinternet.com

Client: William Neville Construction
Project: CARCUR PARK
CARCUR
WEXFORD

Drawn By: PN
Scale: 1:500
Status: PLANTING PLAN

Date: June 2018
Drg. No. Sheet 05
Rev.
Drawing Title: SITE LAYOUT PLAN