





-  Pedestrian Circulation & Connectivity
-  Pedestrian Circulation & Connectivity through public linear park
-  Future Potential Pedestrian links Greenway Linkage (Indicative) North & South
-  Traffic Circulation

PLEASE NOTE:

THIS DRAWING, THE DESIGN AND ITS CONTENTS ARE COPYRIGHT, ALL RIGHTS RESERVED.
 NO PART OF THIS DRAWING CAN BE COPIED OR REPRODUCED IN ANY FORM WHATSOEVER, PARTLY OR COMPLETELY WITHOUT PRIOR WRITTEN CONSENT OF THE COPYRIGHT OWNERS RADHARC LANDSCAPING LTD.
 THIS DRAWING HAS BEEN PREPARED SOLELY FOR THE PURPOSE OF PLANNING PERMISSION.
 THIS DRAWING IS NOT TO BE RELIED UPON FOR CONSTRUCTION AND NO GUARANTEE IS GIVEN AS TO ITS SUITABILITY FOR CONSTRUCTION.
 ALL CONTRACTORS, WHETHER MAIN OR SUBCONTRACTORS MUST VISIT THE SITE AND ARE RESPONSIBLE FOR TAKING AND CHECKING ANY AND ALL DIMENSIONS AND LEVELS THAT RELATE TO THE WORKS. ALL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR.

GENERAL NOTES:

- All soil movement should take place during dry weather (when topsoil is not wet);
- Topsoil should be stripped first & stored separately from subsoil. All topsoil to be good quality medium loam and free from deleterious material;
- Organic matter to be added when necessary to create a good friable structure;
- Soil depths for trees 1000mm (40% free draining subsoil, 60% topsoil); for general planting 700mm;
- All grass levels to be raised 100mm above kerb level;
- All landscape treatment subject to engineers' approval for structural, moisture and drainage considerations;
- Gravel or hard surface line between all planting and buildings, approx width 300mm;
- 1m high black shelter fencing should be erected for the first two seasons in wind vulnerable areas;
- Bark mulch dress to 50mm depth should be added to all ornamental planting and replenished annually to maintain depth.

HATCH NOTE:

The drawing hatch is graphic indication & not intended as an accurate representation of finished work. Paving and other hard/soft finishes will vary on completion. Please discuss further with Radharc regarding material finishes.

TREES & SHRUBS (PLANTING, CARE & MAINTENANCE):


- Trees to be supported by staking depending on size: 1.4-1.5m trees planted in prepared tree pits, 900 x 900 x 1000mm. Secured with double stake and cross bar; 16-18 cm girth - Secured with double stake and cross bar;
- Containerised shrubs to be planted at any time of the year but avoiding periods of frost, water logging or drought;
- Bareroot trees to be planted in the period of Nov-March;
- Shelter Fencing to be erected during establishment phase.

MAINTENANCE:

- Weed control by residual chemical and by regular spot treatment with translocated herbicide (e.g. Glyphosate) during the growing season. Weeds among plants to be hand weeded where necessary;
- Pruning of all plants to be carried out by a competent horticulturist in accordance with good practice;
- Watering: all planting to be kept well watered during dry weather, especially during establishment phase.

Radharc
 landscape design
 Private Commercial Residential

Ballinahalla, Moycullen, Co. Galway, H91 KAK3
 Tel: (091) 555078 Fax: (091) 555954
 e-mail: info@radharclandscaping.com
 www.radharclandscaping.com

Stage 3 - SHD	Rev. Date_By_Description	
Drawing Purpose: FOR_PLANNING		
Project:	Beama SHD, Beama, Co Galway	
Client:	Burkeway Homes	
Drawing title:	Circulation & Connectivity	
Drawing No:	924_Rad_1973_03_Circulation & Connectivity	
Scale:	1:500@A1	Drawn by: SG
Date:	13/07/2020	Checked by: BW

Do not scale from this drawing. All dimensions to be checked on site. Discrepancies between this drawing and information given elsewhere must be reported to this office for clarification before proceeding