Landscape Plan 1:1000

N

3 *Tilia sp.* removed due to works. 3 replacement *Tilia cordata 'Greenspire'* (rb 20-25cm girth) to be incorporated into grass verge . Planting positions to be agreed on site.

160 meters of mixed hedgerow impacted by works. Approximately 20 semi mature to mature trees impacted. Replacement native hedgerow mix to be planted along boundary.
10 replacement trees to be incorporated into grass verge . 10 to be replanted into hedgerow. Planting positions to be agreed on site.

Group of 10 *Pinus sp.* to be removed due to work. Replacement planting to be incorporated into grass verge. Planting position to be agreed on site. 5 no. *Pinus sylvestris* (rb 4m h) in nearest available space. 3 no. *Betula pendula* (rb 16-18cm girth)
2 no.*Tilia cordata 'Greenspire'* (rb 20-25cm girth)

3 young *Acer campestre* to be removed due to works. Replacement *3 Tilia cordata 'Greenspire'* (rb 20-25cm girth) in nearest available space. Space at appropriate distance to create avenue effect. Planting position to be agreed on site.

3 *Salix sp.* and *Betula sp*. to be removed due to works. Replacement 3 Salix alba (rb 20-25cm girth) in nearest available space. Planting position to be agreed on site.
35m2 of shrub mix to replace shrubs removed during works.

3 *Betula nigra* to be removed due to works. Replacement 4 *Betula nigra* (rb 16-18cm girth) in nearest available space. Planting position to be agreed on site.
35m2 of shrub ground cover mix to replace shrubs removed during works.

Mature hedgerow including mature *Fraxinus excelsior,Crataegus monogyna, Sorbus aucuparia.* Replacement tree planting in nearest available space. Planting positions to be agreed on site. To include 2 no. *Fagus sylvatica* (RB 20-25cm girth) 2no. *Prunus avium* (RB 20-25cm girth)

Legend

- Existing Tree
- Removed Tree
- Removed Hedge
- Proposed Tree

FS- *Fagus sylvatica* (rb20-25cmg)
PA - Prunus avium (rb20-25cmg)
SA - Salix alba (rb20-25cmg)
TC- *Tilia cordata* 'Greenspire' (rb20-25cmg)
BP- *Betula pendula* (rb16-18cmg)
SAp - *Sorbus aucuparia* (rb16-18cmg)
PS - *Pinus sylvestris* (rb4-5m H)
BN - *Betula nigra* (rb16-18cmg)

Grass Mix 30g per m².
Area- 1598m²
20% Festuca ovina
15% Poa pratensis
30% Festuca rubra
20% Festuca rubra subsp.
10% Agrostis capillaris
5% Trifolium repens

Hedgerow Mix

180 meters. 4 plants per linear meter. Rootballed container grown to be used To vary between 90cm -1.5m height

45% Crataegus monogyna
10% Corylus avellana
5% Euonymus europaeus
10% Ilex aquifolium
7% Prunus spinosa
5% Rosa canina
3% Salix caprea
3% Sambucus nigra
5% Viburnum opulus
5% Cornus sanguinea

Shrub Mix m2 area
3-7 plants per m² dependent on species
15% Symphoricarpus x chenaultii 'Hancock'
15% Lonicera pileata
15% Hypericum calycinum
40% Hedera helix 'Hibernica'
15% Mahonia aquifolium

- Planning Boundary
- Boundary of Permitted Development
- Proposed 110KV Clutterland to Kilmahud Grid Connection
- Proposed HDD Under Nangor Road

Rev	Date	By	Details
B	04/11/20	-	PLANNING

AUSTEN ASSOCIATES
One Salt House, South Quay, Wicklow Town, Co. Wicklow
T: 0404 66827
Email: designdesk@austenassociates.ie | Web: www.austenassociates.ie
landscape architecture design | arboriculture project management

Copyright Austen Associates, 2020

Project title: Clutterland 110 kV GIS Substation

Drawing title: Landscape Plan

Drawn by: LJ
Approved by: TA
Status: Planning
Scale: 1:1000 on A1
Date: October 2020
Drawing no: CLDHV-AA-XX-XX-DR-L-0111
Revision: B