














DISCLAIMER
 1. This drawing is the property of Cameo & Partners Ltd.
 2. It must not be copied or reproduced without written consent.
 3. Do not scale from this drawing.
 4. Check all dimensions on site before setting out.

PROPOSED HARD LANDSCAPE

-  **Paving Type 1:** Buff Coloured Granite Slabs
Size: 100x200, 200x400, 400x600, depth 80mm.
Colour: 3 shades of light buff.
Supplier: Stonepave or Similar Approved
-  **Paving Type 3:** Buff Coloured Granite Setts
Size: 100x200, depth 80mm.
Colour: 3 shades of light buff.
Supplier: Stonepave or Similar Approved
-  **Paving Type 5:** Wet Pour Safety Surface
Colour: 4 shades of yellow and orange.
Supplier: Soft Surfaces or Similar Approved
-  **Paving Type 15:** Slate chipping
Size: 20-30mm
Supplier: Kilsaran or Similar Approved/TBC
-  **Edge Type 2:** High Performance Concrete Edges and Walls
Height: various. Colour: White with etched surface.
Supplier: Cassidy Brothers or Similar Approved
-  **Edge Type 4:** Metal Planter Edge
Height/Colour: 500mm / To match architectural metalwork.
Supplier: CMOS or Similar Approved
-  **Edge Type 5:** Aluminium Edge
Height: 100mm. Width: 50mm/100mm
Supplier: EverEdge or Similar Approved
-  **Furniture Type 8:** Bespoke Metal Trellis System
Powder coated metal tubes with tension wires as a plant support for climber plants.
Colour to match architectural metalwork.
Supplier: Jakob Systems or Similar Approved
-  **Furniture Type 10:**
Table with chairs. Notional only.
Client to confirm preferred product.
-  **Insects hotel**
Stage beetle loggery
-  **Floor finish level / Level proposed**
± 31.00 FFL
± 31.000
-  **Water Feature**
Bespoke water feature with to be developed with water feature specialist.
-  **Bespoke metal structure**

PROPOSED SOFT LANDSCAPE

-  **Proposed Mature Tree**
Size/Colour: 35-40cm girth, RB, 2m clear stem.
Product: Refer to Planting Schedule
Supplier: Van den Berk/Tully Nurseries or Similar Approved
-  **Proposed Semi-Mature Multi-stem Tree**
Product: Refer to Planting Schedule
Supplier: Van den Berk/Tully Nurseries or Similar Approved
-  **Proposed Shrub Planting**
Product: Refer to Planting Schedule
Supplier: Tully Nurseries or Similar Approved
-  **Proposed Herbaceous Planting**
Product: Refer to Planting Schedule
Supplier: Tully Nurseries or Similar Approved
-  **Proposed Green Wall**
Supplier: ANS Global or Similar Approved

