

DISCLAIMER
 1. This drawing is the property of Camco & Partners Ltd.
 2. It must not be copied or reproduced without written consent.
 3. Do not scale from this drawing.
 4. Check all dimensions on site before setting out.



SITE OF CONCURRENT PLANNING APPLICATION AS INDICATED ON PLAN No. C0096 L1000 SDZ REV P05.
 Note: Footprints of buildings on this adjoining site are for indicative purposes only and are subject to a separate SDZ planning application

PROPOSED HARD LANDSCAPE		PROPOSED SOFT LANDSCAPE	
	Site Ownership Boundary		Proposed Mature Tree Size/Colour: 35-50cm girth, RB, 2m clear stem. Product: Refer to Planting Schedule Supplier: Van den Bergh/Tully Nurseries or Similar Approved
	Planning Lodgment Boundary		Proposed Semi-Mature Tree Size/Colour: 25-30cm girth, RB Product: Refer to Planting Schedule Supplier: Van den Bergh/Tully Nurseries or Similar Approved
	Paving Type 1: Buff Coloured Granite Slabs Size: 100x200, 200x400, 400x800, depth 80mm. Colour: 3 shades of light buff. Supplier: Stonepave or Similar Approved		Proposed Semi-Mature Multi-stem Tree Product: Refer to Planting Schedule Supplier: Van den Bergh/Tully Nurseries or Similar Approved
	Paving Type 2: Granite Slabs Size: 800x800mm, depth 80mm. Colour: Silver Grey to DCC standard Supplier: Stonepave or Similar Approved		Proposed Semi-Mature Specimen Shrub Product: Refer to Planting Schedule Supplier: Tully Nurseries or Similar Approved
	Paving Type 3: Buff Coloured Granite Slabs Size: 100x200, depth 80mm. Colour: 3 shades of light buff. Supplier: Stonepave or Similar Approved		Proposed Hedge Product: Refer to Planting Schedule Supplier: Tully Nurseries or Similar Approved Size/Colour: 100-150cm high, branched, shr, no. per lin. m.
	Paving Type 4: Buff Coloured Granite Slabs Size: 800x800mm, depth 80mm. Colour: 3 shades of light buff. Supplier: Stonepave or Similar Approved		Proposed Shrub Planting Product: Refer to Planting Schedule Supplier: Tully Nurseries or Similar Approved
	Paving Type 5: Wet Pour Safety Surface Colour: 4 shades of yellow and orange. Supplier: Soft Surfaces or Similar Approved		Proposed Herbaceous Planting Product: Refer to Planting Schedule Supplier: Tully Nurseries or Similar Approved
	Paving Type 6: Coloured Tarmac (Cycle Lane) Colour: to DCC Standards Supplier: SIAC Construction or Similar Approved		Proposed Green Wall Supplier: ANS Global or Similar Approved
	Paving Type 7: Buff Coloured Granite Slabs Size/Colour: 100x200, depth 80mm / to meet DCC standards. Supplier: Stonepave or Similar Approved		Furniture Type 1: Recessed Tree Grille Supplier: OMCOS or Similar Approved Size/Material: 1200x1200mm/Galvanised Steel
	Paving Type 8: Buff Coloured Granite Slabs Size/Colour: 100x200, depth 80mm. Supplier: Stonepave or Similar Approved		Furniture Type 2: Cycle Stand Product: Sheffield type Supplier: Hancock or Similar Approved Size/Material: 750x750x48.3mm (HxLxW)/Galvanised Steel
	Paving Type 9: Granite Slabs Size: 100x200, depth 80mm. Colour: Silver grey to meet DCC standards. Supplier: Stonepave or Similar Approved		Furniture Type 3: Seats & Benches on Top of Wall Solid concrete deck board Size/Colour: Plan deck, 21x148 mm, 6m / Grey/brown. Supplier: SAGEC, Compost Decking Board or Similar Approved
	Paving Type 10: Granite Slabs Size: Various, larger than 800x800. Colour: 2 shades buff. Supplier: Stonepave or Similar Approved		Furniture Type 4: Handrail Supplier: OMCOS or Similar Approved Size: 800mm, Material: Stainless Steel, Finish: Brushed.
	Edge Type 1: Granite Road Kerb Size/Colour: 400mm width to meet DCC requirements. Supplier: Stonepave or Similar Approved		Furniture Type 5: Benches, A - fixed, B - removable Product: Flat top bollard Supplier: Hancock or Similar Approved Size/Material: 114x1100 mm, 316 stainless steel body and cap.
	Edge Type 2: High Performance Concrete Edges and Walls Height: various, Colour: White with ribbed surface. Supplier: Casasly Brothers or Similar Approved		Furniture Type 6: Glass Balustrade Product: Frameless Glass Balustrade Supplier: TBC Height: 1100mm.
	Edge Type 3: Conservation Fix Kerb Size/Colour: 150x200x150mm/Concrete/Textured. Supplier: Doranconcrete or Similar Approved		Furniture Type 7: Glass Balustrade Product: Frameless Glass Balustrade Supplier: TBC Height: 1100mm.
	Step Type 1: Granite Slabs Colour: To match P11 Finish Sand blasted Black sand. Supplier: Stonepave or Similar Approved		Floor finish level / Level existing / Level proposed
	Furniture Type 8: Recessed Tree Grille Supplier: OMCOS or Similar Approved Size/Material: 1200x1200mm/Galvanised Steel		Ventilation Grille To Architect's details.