

© COPYRIGHT OF THIS DRAWING IS RESERVED BY DBFL CONSULTING ENGINEERS. NO PART SHALL BE REPRODUCED OR TRANSMITTED WITHOUT THEIR WRITTEN PERMISSION.

15 25 0 5 10 20 30 40 50mm

NOTE

- C20/25 CONCRETE TO HAVE A MINIMUM CEMENT CONTENT OF 260Kg/m³, MAXIMUM WATER/CEMENT RATIO OF 0.65 AND SLUMP CLASS S2.
- C25/30 CONCRETE TO HAVE A MINIMUM CEMENT CONTENT OF 280Kg/m³, MAXIMUM WATER/CEMENT RATIO OF 0.65 AND SLUMP CLASS S2.
- 3. C40/50 CONCRETE TO HAVE A MINIMUM CEMENT CONTENT OF 400Kg/m³, MAXIMUM WATER/CEMENT RATIO OF 0.45 AND SLUMP CLASS S3.
- WHERE CLASS 6F1/6F2 CAPPING MATERIAL IS PROPOSED WITHIN 500mm OF CONCRETE OR STEEL, CLASS 6N TO BE USED INSTEAD.

NOTE:

ALL WORKS & SPECIFICATIONS TO BE UNDERTAKEN IN ACCORDANCE WITH

• TII SPECIFICATION FOR

ROADWORKS

• GREATER DUBLIN CODE OF

P01 25/01/21 ISSUED FOR PLANNING

client approval

S2 - INFORMATION

A - Approved

DUBLIN OFFICE: Ormond House, Upper Ormond Quay, Dublin 7. D07 W704 PHONE +353 1 400 4000

WATERFORD OFFICE: Suite 8b The Atrium, Maritana Gate, Canada Street, Waterford. X91 W028 PHONE +353 51 309 500

STANDARD DETAILS SHEET 2 OF 4

180176-DBFL-XX-XX-DR-C-5003

CORK OFFICE: Phoenix House, Monahan Road, Cork. T12 H1XY PHONE +353 (0) 21 2024538

LISSYWOLLEN RESIDENTIAL

WESTMEATH

DEVELOPMENT AT BRAWNY ROAD, LISSYWOLLEN, ATHLONE, CO.

DELPHI ARCHITECTS

B - Approved with comments

issue purpose

DBFL Consulting Engineers

PLANNING

- PRACTICE FOR DRAINAGE WORKS
- RECOMMENDATIONS FOR SITE

 PENEL ORMENTATIONS
- DEVELOPMENT WORKS

 IRISH WATER CODE OF PRACTICE
- AND STANDARD DETAILS