GENERAL NOTES

"All taking down and removals to be carefully undertaken in accordance with Conservation Specifications by David Slattery Conservation Architects."

"Surviving original multi-pane sash windows to link building to be carefully conserved, retaining single panes of glass in accordance with Conservation Specifications by David Slattery Conservation Architects."

"Non-original 20th Century sash windows to Seminary to be spliced where beads and half cills are
decayed. New slimglaze double glazed units to be fitted into existing sashes. All in accordance with detail
drawings showing glazing bar profile impact and Conservation Specifications by David Slattery
Conservation Architects."

"All services to Seminary to reuse existing routes where possible with any new routes and installarions to

be carried out in accordance with Conservation Specifications by David Slattery Conservation Architects."

"Minor repairs to leaded and stained glass in Assembly Hall are limited to repair of opening sections and glass replacement where panes are broken. No storm or secondary glazing proposed. All to be carried out in accordance with Conservation Specifications by David Slattery Conservation Architects."

"Stained glass over front entrance to chapel is set in a timber frame and is to be carefully removed to agreed location in accordance with Conservation Specifications by David Slattery Conservation Architects."

"Slate roofs to Seminary and Chapel to be restored using Blue Bangor slate and stepped lead valleys in accordance with Conservation Specifications by David Slattery Conservation Architects."

"All cast-iron rainwater goods to be retained and renewed with any replacements where goods are beyond repair to be in cast iron. All in accordance with Conservation Specifications by David Slattery Conservation Architects."


"Render to be lightly cleaned with dilute biocide in accordance with Conservation Specifications by David Slattery Conservation Architects."

"Limestone strings and cills to be carefully cleaned using Doff or similar steam cleaning - no abrasive or chemical cleaning. All in accordance with Conservation Specifications by David Slattery Conservation

Architects." "Granite cills, cappings etc to be carefully cleaned using a light calcium carbonate abrasive in


in accordance with Conservation Specifications by David Slattery Conservation Architects."


accordance with Conservation Specifications by David Slattery Conservation Architects." "Wholesale repointing is not required and localised pointing where necessary will be carried out using a lime (NHL3.5) mortar and aggregate and lime mix to match existing bedding mortar tone and texture. All





Sections Proposed H-H Scale - 1:100


3 Proposed Section I-I Scale - 1 : 100













O'Donnell+Tuomey



 PROJECT NUMBER
 DATE

 CLN-MCM-00-ZZ-M3-A-C0003
 10/06/20

 SCALE@ A0:
 DRAWN/CHECKED:

 As indicated
 IB/ ROC

 STATUS CODE:
 DRAWING NUMBER

 A1
 CLN-MCM-E1-ZZ-DR-A-P-123

DRAWING Cloister North Elevation

Holy Cross College, Clonliffe Road, Dublin 3 and Drumcondra Road Lower, Drumcondra, Dublin 9

Holy Cross College SHD

PROJECT NAME

CWTC Multi Family ICAV acting on behalf of its sub-fund DBTR DR1 Fund

APPLICANT NAME

STATUS CODE DESCRIPTION ISSUED FOR PLANNING APPROVAL

