



**LEGEND**

**TREE PROTECTION**

- TREES TO BE RETAINED
- SITE BOUNDARY
- TREE PROTECTION

ROLA-TRAC  
Protective matting to be used during the initial construction phase. Removed during landscaping phase.

Proposed wall bridging sections  
After preliminary investigation using hand tools/AirSpade will be undertaken to identify root systems extents

TREE PROTECTION TO REMAIN IN PLACE UNTIL PRIMARY CONSTRUCTION PHASE IS COMPLETED AND REMOVED AS NECESSARY FOR LANDSCAPING PHASE. Drawing to be interpreted with reference to the Arboricultural Assessment, Impact & Tree Protection document.

REV	DATE	DESCRIPTION
B	24-06-20	Modified impacts for attenuation tanks and related services.
C	04-08-20	Modified impacts for attenuation tanks and related services.
D	05-08-20	Amended client and address titleblock details, updated underground services reference.
E	06-01-21	Adjusted position of underground services tank east of building A.
F	07-04-21	New survey information from update report.
G	11-08-21	New landscaping inputs

**CMK**  
Consultants & Architects Ltd

Client: SANDFORD LIVING LIMITED	PROJECT: MILLTOWN PARK, SANDFORD ROAD, DUBLIN 6	JOB NO. TSAN001
DRAWING: Tree Protection (1 of 2)	DATE: 11-08-21	SCALE: 1:400 @ A1
DRAWN BY: Neil McBride	NMB INITIALS	REVISION: 0
STATUS: PLANNING		

NOTES: This drawing is copyright of CMK Horticulture & Arboriculture Ltd. All rights reserved. No part of this drawing may be reproduced without the prior written consent of CMK Horticulture & Arboriculture Ltd.