

## Appendix A16.4 Recorded Built Heritage Sites Within the Receiving Environment

The County Development Plan lists a number of RMPs within the protected structures list. Those listings have not been repeated within this section (BH 26-33).

BH No.:	1
RPS No.:	694
NIAH No.:	11354004
Townland:	Castleknock
Parish:	Castleknock
Barony:	Castleknock
Classification:	Canal Bridge
Dist. from development:	c. 415m south (Orbital Sewer)
Description:	Single-arch humpback road bridge over Royal Canal, c.1810, now pedestrianised.
Rating:	Regional
Categories of special interest:	Architectural, technical
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	2
RPS No.:	684
NIAH No.:	11354005
Townland:	Abbotstown
Parish:	Castleknock
Barony:	Castleknock



BH No.:	2
Classification:	Graveyard
Dist. from development:	Partially within Orbital Sewer (tunnel)
Description:	Graveyard and ruined Church dating from pre-1700, now overgrown with vegetation.
Rating:	National
Categories of special interest:	Archaeological, social
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	3
RPS No.:	686
NIAH No.:	11354007
Townland:	Dunsink
Parish:	Castleknock
Barony:	Castleknock
Classification:	Elm Green House and outbuildings
Dist. from development:	c. 440m southeast (Orbital Sewer)
Description:	Detached five-bay two-storey over basement house, c.1850, with recessed bay to north and recessed central bay having single-storey projecting entrance porch. Limestone entrance gates, derelict gate lodge and farmyard complex to site. ROOF: Hipped asbestos cement roof with nap rendered chimney stacks; clay pots; cast-iron rainwater goods. WALLS: Rough-cast rendered with red brick corbel cornice. OPENINGS: Square headed with nap rendered reveals; granite cills; 1/1 timber sash windows; segmental headed porch opening with brick dressing; timber and glazed door, c.1990, granite steps. INTERIOR: Raised and fielded timber shutters, lugged architraves, raised and fielded timber doors, run moulded cornice ramped dado rail, mahogany staircase with tapered balusters.



BH No.:	3
Rating:	Regional
Categories of special interest:	Architectural, artistic
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	4
RPS No.:	683
NIAH No.:	11354006
Townland:	Sheephill
Parish:	Castleknock
Barony:	Castleknock
Classification:	Abbotstown House
Dist. from development:	c. 310m northwest (Orbital Sewer)
Description:	Detached five-bay two-storey former house, c.1860, with advanced central entrance bay to ground floor. Two-storey return to rear and six-bay two- storey wing to north-east. Extended to north, c.1930 and c.1970. Farmyard complex to north. Now in use as laboratories and offices. ROOF: Hidden behind parapet wall; double pitched slate roof to right wing, nap rendered chimney stacks with terracotta pots. WALLS: Nap rendered with a moulded cornice; OPENINGS: Square headed window opening with nap rendered architraves and cornice stone cills; cill course; 6/6 and 1/1 timber sash windows; nap rendered porch with Doric pilasters; wreaths, cornice and balustrade; flat panelled timber door flanked by timber side windows to porch.
Rating:	Regional
Categories of special interest:	Architectural, artistic
Reference:	NIAH survey for County Fingal



BH No.:	4
	County Fingal Development Plan 2017-2023

BH No.:	5
RPS No.:	604
NIAH No.:	11349003
Townland:	Collinstown
Parish:	Santry
Barony:	Coolock
Classification:	Thatched cottage
Dist. from development:	c. 60m south (Orbital Sewer)
Description:	Detached three-bay single-storey thatched house, c.1800, with central projecting entrance porch. Single-bay single-storey extension to right side, c.1980. ROOF: Double pitched thatched roof with a red brick and a nap rendered chimney stack; concrete tiles to extension also having rendered chimney stack. WALLS: Nap rendered; pebble dashed extension. OPENINGS:S quare headed with stone cills; nap rendered reveals and uPVC castments and door.
Rating:	Regional
Categories of special interest:	Architectural, social, technical
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023



BH No.:	6
RPS No.:	N/a
NIAH No.:	11349004
Townland:	Dardistown
Parish:	Santry
Barony:	Coolock
Classification:	Thatched cottage
Dist. from development:	c. 60m south (Orbital Sewer)
Description:	Detached three-bay single-storey thatched house, c.1800, on a L-shaped plan with gable-fronted projecting entrance porch. ROOF: Double pitched thatch roof; decorative thatched ridging with two nap rendered chimney stacks; timber barge boards to porch. WALLS: Nap rendered. OPENINGS: Square headed windows with nap rendered reveals; stone cills and uPVC casements; round headed door opening.
Rating:	Regional
Categories of special interest:	Architectural, social, technical
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	7
RPS No.:	1907 & 1908
NIAH No.:	N/a
Townland:	Clonshagh
Parish:	Cloghran
Barony:	Coolock
Classification:	Woodlands House & green house



BH No.:	7
Dist. from development:	c. 400m south (Orbital Sewer)
	c. 610m southwest of WwTP
Description:	The house is a square, brick, two storey building with a high basement and a pyramidal roof, from the centre of which rises a gazebo. It has four chimney stacks and a five bay entrance front. The interior is divided by a long vaulted corridor-hall running from front to back. Craig considers it the most interesting early 18th-century house in Ireland
Rating:	Not specified
Categories of special interest:	Not specified
Reference:	Dublin City Development Plan 2017-2023

BH No.:	8
RPS No.:	N/a
NIAH No.:	11349005
Townland:	Belcamp
Parish:	Cloghran
Barony:	Coolock
Classification:	Belcamp
Dist. from development:	c. 400m south of WwTP
Description:	Detached three-bay two-storey house, c.1840, with central portico. ROOF: M-profile double pitched slate roof; rendered chimney stacks; terracotta pots. WALLS: Pebble dashed; nap rendered plinth coourse. OPENINGS: lonic columns to portico; square headed openings; stone cills; uPVC casements. The house was damaged by fire before 2002 and was demolished in between 2008 and 2009.
Rating:	Regional



BH No.:	8
Categories of special interest:	Architectural
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	9
RPS No.:	463
NIAH No.:	11350024
Townland:	Belcamp
Parish:	Cloghran
Barony:	Coolock
Classification:	Belcamp House
Dist. from development:	c. 880m southeast of WwTP
Description:	Attached seven-bay three-storey over basement red brick former house, c.1785, originally detached. Three-bay full-height central breakfront with rusticated ashlar granite to ground floor. Three-bay full height central bow to rear façade. Now in use as ecclesiastical residence and school. Detached eight-bay subterranean cellar range c.1785 at basement level to west of entrance façade. ROOF: Flat-roofed, originally pitched. Red brick chimneys with clayware pots. Cast-iron rainwater goods. WALLS: Red brick Flemish bond, with rusticated granite ashlar to ground floor central breakfront. Carved granite stringcourse to ground floor. Red brick parapet. OPENINGS: Timber sash windows with granite sills, set in round headed openings to ground floor, with square headed openings above. Timber panelled door with fanlight above. Venetian windows to side elevations. Glazed timber doors to rear. INTERIOR: Very fine oval entrance hall. Damaged by fire in 2011.
Rating:	National
Categories of special interest:	Architectural, artistic, historical



BH No.:	9
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	10
RPS No.:	463
NIAH No.:	11350035
Townland:	Belcamp
Parish:	Cloghran
Barony:	Coolock
Classification:	Belcamp chapel
Dist. from development:	c. 875m southeast of WwTP
Description:	Attached red brick Gothic Revival style chapel, built 1903, on a cruciform plan. Four-bay side elevation to nave with single-bay transepts attached to east and west, and having apse to north. Designed by architect George Coppinger Ashlin. Stained glass windows by Harry Clarke. Single-bay projecting porch to south-west. ROOF: Double pitched slate, half conical to apse, with decorative clay ridge tiles, lead flashings and cast-iron rainwater goods. Celtic cross style finials to gables. WALLS: Red brick English garden bond, with Flemish bond plinth having limestone copings. Limestone ashlar stringcourse, red brick moulded cornice and red brick pilasters. Scalloped features over window openings. Limestone ashlar plaque to apse. OPENINGS: Lead framed stained glass windows set in round headed opening, paired and tripartite, with limestone block-and-start archivolts, sill course and hood mouldings. Timber tongue and groove door, c.1980, with limestone ashlar block-and-start surround.
Rating:	Regional
Categories of special interest:	Architectural, artistic, historical
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023



BH No.:	11
RPS No.:	463
NIAH No.:	11350036 & 11350037
Townland:	Belcamp
Parish:	Cloghran
Barony:	Coolock
Classification:	Belcamp college dormitory buildings
Dist. from development:	c. 895m southeast of WwTP
Description:	<ul> <li>11350036 - Attached eleven-bay two-storey over basement dormitory wing, c.1900, with single-bay full-height central stairway breakfront. ROOF: Double-pitched slate, hipped to breakfront. Red brick chimneys, clay ridge tiles and cast-iron rainwater goods. WALLS: Red brick Flemish bond, with string courses to each floor and moulded brick cornice. OPENINGS: Timber sash windows and replacement uPVC casement windows with stone sills, set in square headed openings to basement and ground floor, in round headed openings to first floor. Venetian style window to breakfront. Replacement timber panelled and glazed door.</li> <li>11350037 - Attached thirteen-bay three-storey red brick wing with dormer attic, c.1925, with pair of gabled advanced bays. Set at right angles to an earlier wing. ROOF: Double pitched slate with concrete ridge tiles,</li> </ul>
	rooflights and cast-iron rainwater goods. Limestone copings to gables with cross finials. WALLS: Red brick Flemish bond with moulded red brick cornice. OPENINGS: Timber sash and replacement uPVC windows with concrete sills, set in square headed openings to ground floor and second floor, in round headed openings to first floor. Sandstone ashlar block-and-start door surround.
Rating:	Regional
Categories of special interest:	Architectural, artistic, social
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023



BH No.:	12
RPS No.:	463
NIAH No.:	11350040
Townland:	Belcamp
Parish:	Cloghran
Barony:	Coolock
Classification:	Belcamp college bridge
Dist. from development:	c. 955m southeast of WwTP
Description:	Single-arch concrete road bridge over river, c.1850. Balustraded parapet with cast-iron balusters.
Rating:	Regional
Categories of special interest:	Architectural, technical
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	13
RPS No.:	463
NIAH No.:	11350025
Townland:	Belcamp
Parish:	Cloghran
Barony:	Coolock
Classification:	Washington Memorial Tower, Belcamp Hall
Dist. from development:	c. 1km southeast of WwTP
Description:	Detached two-stage square-plan memorial, built 1778, with corner towers and crenellated parapet. Date given on plaque with inscription 'Washington



BH No.:	13
	memorial tower built by Edw. Newenham in 1778 in honour of American Independence restored 1984'. WALLS: Red brick partly rendered; rough cast render. OPENINGS: Pointed arched openings with random stone surrounds.
Rating:	Regional
Categories of special interest:	Architectural, artistic, historical
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	14
RPS No.:	792
NIAH No.:	11350013
Townland:	Springhill
Parish:	Cloghran
Barony:	Coolock
Classification:	Springhill House
Dist. from development:	c. 400m east of WwTP
Description:	Detached five-bay two-storey house, c.1800, on a U-shaped plan. Three- bay two-storey return to north-east and two-bay two-storey return to north- west. Outbuilding c.1850 attached to rear. Detached stable building c.1800 to north.
Rating:	Regional
Categories of special interest:	Architectural, artistic
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023



BH No.:	15
RPS No.:	N/a
NIAH No.:	11350014
Townland:	Saintdoolaghs
Parish:	Balgriffin
Barony:	Coolock
Classification:	Water pump
Dist. from development:	c. 770m east of WwTP
Description:	Cast-iron water pump, c.1870. Marked at incorrect location of the NIAH mapping.
Rating:	Regional
Categories of special interest:	Social, artistic
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	16
RPS No.:	789
NIAH No.:	N/a
Townland:	Belcamp
Parish:	Cloghran
Barony:	Coolock
Classification:	Belcamp Hutchinson (house)
Dist. from development:	c. 1km southeast of WwTP
Description:	Three storey, five bay country house built in 1786. Retains its gate lodge



BH No.:	16
	and entrance.
Rating:	Not specified
Categories of special interest:	Not specified
Reference:	County Fingal Development Plan 2017-2023

BH No.:	17
RPS No.:	N/a
NIAH No.:	11350015
Townland:	Saintdoolaghs
Parish:	Balgriffin
Barony:	Coolock
Classification:	Limehill House
Dist. from development:	c. 875m east of WwTP
Description:	Detached double-pile three-bay two-storey over basement house, c.1790, with projecting central bow to rear elevation. Single-storey addition to west elevation, converted to conservatory c.1995. ROOF: M-profile; hipped; slate roof with terracotta ridge tiles. WALLS: Pebble dashed. OPENINGS: Square-headed; rendered reveals; limestone cills; original sash windows; 6/6 pane and tri-partite windows; door set in depressed segmental headed doorcase with timber consoles on pilasters; sidelights; original timber panelled door.
Rating:	Regional
Categories of special interest:	Architectural, artistic
Reference:	NIAH survey for County Fingal



BH No.:	18
RPS No.:	458
NIAH No.:	11350010
Townland:	Saintdoolaghs
Parish:	Balgriffin
Barony:	Coolock
Classification:	Emsworth (house)
Dist. from development:	c. 30m south (Outfall Pipeline – land-based)
Description:	Detached five-bay two-storey house, 1794, with pedimented three-bay two- storey central bay flanked by single-bay, single-storey, overlapping wings. Fanlighted doorway under porch of engaged Doric columns and entablature. Ground floor centre windows and windows of wings set in arched recesses. Coach house and stable yard to rear. The only one of James Gandon's villas to survive intact. Drawing for Emsworth initialled 'J.G. March 94' and inscribed ' Erected for J. Woodmason Esqr. Stemworth' is in National Library, Dublin.
Rating:	National
Categories of special interest:	Architectural, artistic
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	19
RPS No.:	464
NIAH No.:	11350009
Townland:	Kinsaley
Parish:	Kinsaley
Barony:	Coolock



BH No.:	19
Classification:	Kinsaley House
Dist. from development:	c. 155m NNE (Outfall Pipeline – land-based)
Description:	Detached five-bay two-storey over basement red brick house with dormer attic, built 1736, with flanking screen walls. Single- and two-storey returns to rear. Farmyard complex to north and west. ROOF: Hidden behind parapet; slate; rendered chimney stacks with clay pots; cast-iron rainwater goods. WALLS: Original Georgian red brick, Flemish bond; nap rendered to side and rear; rendered quoins; early twentieth century single-storey extension. OPENINGS: Square-headed; rendered reveals; stone cills; original 6/6 timber sash windows; replacement timber sash windows to basement; block and start stone doorcase; original timber panelled door; fanlight over. INTERIOR: Interior almost entirely intact; lugged architraves and window surrounds; rococo plasterwork; original joinery.
Rating:	National
Categories of special interest:	Architectural, artistic
Reference:	NIAH survey for County Fingal County Fingal Development Plan 2017-2023

BH No.:	20
RPS No.:	455
NIAH No.:	11350033
Townland:	Kinsaley
Parish:	Kinsaley
Barony:	Coolock
Classification:	Graveyard
Dist. from development:	c. 255m north (Outfall Pipeline – land-based)
Description:	Graveyard with various cut stone grave markers from c.1800 to present. Medieval church, now in ruins, with an attached mausoleum.



BH No.:	20
Rating:	Regional
Categories of special interest:	Architectural, artistic, social, archaeological
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	21
RPS No.:	454
NIAH No.:	11350003
Townland:	Kinsaley
Parish:	Kinsaley
Barony:	Coolock
Classification:	Catholic Church
Dist. from development:	c. 355m north (Outfall Pipeline – land-based)
Description:	Detached gabled-fronted Roman Catholic church, c.1840, on a cruciform plan with two-bay side elevation to nave. Single-bay transepts which have gabled porches attached to west elevations, and single-bay sacristy with gabled porch attached to south elevation. Tower and spire to east. ROOF: Double-pitched; slate with granite ridge tiles and coping; pyramidal slate roof to tower crowned by wrought iron cross; some original cast-iron rainwater goods. WALLS: Nap rendered front wall with raised lettering within pediment and having statue of the Virgin contained within a niche; stone cross crowns gable; pebbledash side walls. OPENINGS: Square headed granite surround to main door; timber panelled door; round and square headed; rendered reveals; stone cill; timber sash windows with coloured glass margin panes. Kinsaley National School located to the immediate south of the church and included as a 'local' record within the NIAH survey (Ref.: 11350004).
Rating:	Regional



BH No.:	21
Categories of special interest:	Architectural, artistic, social
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	22
RPS No.:	N/a
NIAH No.:	11350005
Townland:	Kinsaley
Parish:	Kinsaley
Barony:	Coolock
Classification:	Post box
Dist. from development:	c. 360m north (Outfall Pipeline – land-based)
Description:	Wall-mounted cast-iron post box, c.1885, with 'VR' monogram, set into wall of Saint Nicholas' Boys National school. Manufacturer's name, 'T. Allen & Co., London'.
Rating:	Regional
Categories of special interest:	Artistic, social
Reference:	NIAH survey for County Fingal



BH No.:	23
RPS No.:	N/a
NIAH No.:	11350006
Townland:	Kinsaley
Parish:	Kinsaley
Barony:	Coolock
Classification:	Bridge
Dist. from development:	c. 400m NNW (Outfall Pipeline – land-based)
Description:	Single-span red brick bridge with cast-iron lintels, rebuilt 1897, replacing earlier bridge.
Rating:	Regional
Categories of special interest:	Architectural, technical
Reference:	NIAH survey for County Fingal

BH No.:	24
RPS No.:	456
NIAH No.:	11350008
Townland:	Kinsaley
Parish:	Kinsaley
Barony:	Coolock
Classification:	Gate lodge to Kinsaley Hall
Dist. from development:	c. 355m NNW (Outfall Pipeline – land-based)
Description:	Detached three-bay single-storey gate lodge, c.1860, with gable-fronted projecting porch. ROOF: Hipped; slate roof; two nap rendered brick chimney stacks; decorative timber barge boards to gabled porch. WALLS: Nap rendered. OPENINGS: Square-headed; nap rendered reveals; small



BH No.:	24
	openings; square headed replacement timber casements; replacement timber panelled door.
Rating:	Regional
Categories of special interest:	Architectural
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	25
RPS No.:	460
NIAH No.:	11350019
Townland:	Saintdoolaghs
Parish:	Balgriffin
Barony:	Coolock
Classification:	St. Doolaghs Park (house)
Dist. from development:	c. 515m west (Outfall Pipeline – land-based)
Description:	Detached five-bay two-storey over basement house, c.1850, with advanced central bay having projecting entrance porch. Pierced balustrade conceals the basement and continues to the walled garden. Curved corridor to rear right-hand side leading to former conservatory, c.1890, now demolished. Former home of the painter Nathaniel Hone the Younger. ROOF: Hidden behind parapet wall with two nap rendered corniced chimney stacks. WALLS: Nap rendered with quoins and granite entrance porch; cornice and string course; central three bays to rear in a shallow bow. OPENINGS: Square headed openings with nap rendered architrave and bracket cornice; granite cills; timber sash windows.
Rating:	Regional
Categories of special interest:	Architectural, artistic



BH No.:	25
Reference:	NIAH survey for County Fingal
	County Fingal Development Plan 2017-2023

BH No.:	26
RPS No.:	617
NIAH No.:	N/a
Townland:	Dubber
Parish:	Santry
Barony:	Coolock
Classification:	Dubber House
Dist. from development:	c. 95m north (Orbital Sewer)
Description:	Two storey farm house of reasonable size with ground floor entrance porch on the main SSW facing elevation and extension to NNE elevation at rear. In good condition.
Rating:	Regional
Categories of special interest:	Not specified
Reference:	County Fingal Development Plan 2017-2023

BH No.:	27
RPS No.:	685
NIAH No.:	N/a
Townland:	Dunsink
Parish:	Castleknock



BH No.:	27
Barony:	Castleknock
Classification:	Earhtwork
Dist. from development:	c. 210m south-east (Orbital Sewer)
Description:	On a knoll. Comprises a large irregularly shaped mound (diam c. 20m, H 3m). A curvilinear feature attached to this mound was investigated in 1991 and proved to be of modern construction (Keeley 1995; Healy 1975, 27).
Rating:	Not specified
Categories of special interest:	Not specified
Reference:	County Fingal Development Plan 2017-2023

BH No.:	28
RPS No.:	914
NIAH No.:	N/a
Townland:	Kinsaley
Parish:	Kinsaley
Barony:	Coolock
Classification:	Former research building
Dist. from development:	c. 20m north (Outfall Pipeline – land-based)
Description:	20 <sup>th</sup> century former research building in the International style
Rating:	Not specified
Categories of special interest:	Not specified
Reference:	County Fingal Development Plan 2017-2023

Page left intentionally blank