

Environmental Impact Assessment Report

Slieveacurry Renewable Energy Development, Co. Clare

Volume 1

Non-Technical Summary and Main Report







Client: Slieveacurry Ltd

Project Title: Slieveacurry Renewable Energy

Development, Co. Clare

Project Number: 170224c

Document Title: Volume 1 - Non-Technical Summary and

Main Report

Document File Name: **EIAR F - 2021.11.18 - 170224c**

Prepared By: MKO

Tuam Road Galway Ireland H91 VW84



Rev	Status	Date	Author(s)	Approved By
01	Final	18/11/2021	EOS	MW



Table of Contents

Non-Technical Summary

1.	INTRODUCTION	1-1
	1.1 Introduction	1-1
	1.2 Project History	1-2
	1.3 Legislative Context of Environmental Impact Assessment	1-2
	1.3.1 EIAR Guidance	
	1.3.2 Wind Energy Development Guideline for Planning Authorities	1-4
	1.4 The Applicant	
	1.5 Brief Description of the Proposed Development	1_/L
	1.5.1 References to Proposed Development Site	
	1.6 Need for the Proposed Development	
	1.6.1 Overview	
	1.6.3 Energy Security	1 0
	1.6.7 Increasing Energy Consumption	
	1.6.9 Economic Benefits	
	1.7 Purpose and Scope of the EIAR	
	1.8 Structure and Content of the EIAR	
	1.8.1 General Structure	
	1.8.2 Description of Likely Significant Effects and Impacts	
	1.9 Project Team	
	1.9.1 Project Team Responsibilities	
	1.9.2 Project Team Members	1-22
	1.9.2.1 MKO 1-22 1.9.2.2 Hydro Environmental Services Ltd	1 20
	1.9.2.2 Hydro Environmental Services Ltd	
	1.9.2.4 AWN Consulting Ltd	
	1.9.2.5 Tobar Archaeological Services	
	1.9.2.6 Alan Lipscombe Traffic and Transport Consultants	1-29
	1.10 Difficulties Encountered	1-30
	1.11 Viewing and Purchasing of the EIAR	1-30
2.	BACKGROUND TO THE PROPOSED DEVELOPMENT	2-1
	2.1 Introduction	2-1
	2.1.1 Renewable Energy Resources	2-1
	2.1.2 EU Policy	
	2.1.2.1 2030 Climate Change and Energy Framework	2-3
	2.2 Climate Change Policy and Targets	2-3
	2.2.1 Introduction	
	2.2.2 International Policy	
	2.2.2.1 United Nations Framework Convention on Climate Change	2-4
	2.2.2.2 Intergovernmental Panel on Climate Change	
	2.2.3 National Policy	
	2.2.3.2 Climate Action and Low Carbon Development (Amendment) Act 2021	
	2.2.4 Renewable Energy Policy and Targets	
	2.2.4.1 EU Legislation	
	2.2.4.3 Progress on Targets	
	2.3 Planning Policy Context	
	2.3.1 National Policy	
	Traditional Tolloy	2 13



	2.3.1.1 National Planning Framework (2018)	2-15
	2.3.1.2 Key Sustainability Elements of the NPF	2-16
	2.3.2 Regional Policy	
	2.3.2.1 Southern Regional Assembly Regional Spatial & Economic Strategy (2020)	2-18
	· · · · · · · · · · · · · · · · · · ·	
	2.3.3.1 Clare County Development Plan 2017-2023 (as varied)	
	2.3.4 Relevant Guidelines	
	2.3.4.1 Draft Guidelines	2-33
	2.4 Planning History Review	2-34
	2.4.1 Proposed Development Site and its Environs	
	2.5 Scoping and Consultations	2-50
	2.5.1 Scoping Replies	2-50
	2.5.2 Other Consultations - Telecommunications	2-64
	2.5.3 Community Engagement	
	2.5.4 Previous Planning Applications	
	2.5.5 Pre-Planning Meetings	2-67
	2.5.5.1 An Bord Pleanála	2-67
	2.5.5.2 Clare County Council	
	2.6 Cumulative Impact Assessment	
	2.6.1 Methodology for Cumulative Assessment of Projects	
	2.6.2 Projects Considered in Cumulative Assessment	2-69
	2.6.2.1 Forestry and Replanting	2-69
	2.6.2.2 Other Wind Turbines	
	2.6.2.3 Other Developments/Land uses	
	2.0.2.5 Other Developments, Luna uses	2 70
3.	SITE SELECTION AND REASONABLE ALTERNATIVES	3-1
	3.1 Introduction	3-1
	3.2.1 Strategic Site Selection	
	3.2.1.1 Clare Wind Energy Strategy	3-2
	3.2.1.2 Underground Cable Connection	3-4
	3.2.1.3 Designated Sites	3-4
	3.2.1.4 Wind Speeds	
	3.2.1.5 Population Density	
	3.2.1.6 Summary	
	3.3 Consideration of Alternatives	
	3.3.1 Methodology	3-6
	3.3.2 'Do-Nothing' Option	3-7
	3.3.3 Alternative Renewable Energy Technologies	
	3.3.4 Alternative Turbine Numbers and Model	
	3.3.5 Alternative Turbine Layout and Design	3-8
	3.3.5.1 Constraints Mapping	3-9
	3.3.5.2 Turbine Layout	3-11
	3.3.5.3 Road Layout	
	3.3.5.4 Location of Ancillary Structures	
	3.3.5.5 Assessment	
	3.3.6 Alternative Transport Route and Site Access	
	3.3.6.1 Port of Entry	
	3.3.6.2 Delivery to Site	
	3.3.7 Alternative Mitigation Measures	3-19
_		
1.	DESCRIPTION OF THE PROPOSED DEVELOPMENT	4-1
	4.1 Introduction	4-1
	4.2 Development Layout	4-1
	4.3 Development Components	
	4.3.1 Wind Turbines	
	4.3.1.1 Turbine Locations	4-3
	4.3.1.2 Turbine Type	
	4.3.1.3 Turbine Foundations	
	4 3 1 4 Hard Standing Areas	4.7
	4.3.1.4 Hard Standing Areas	
	4.3.1.5 Assembly Area	4-7
	5 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	4-7 4-7



	.1 Road Construction Types	
4.3.3	Rock Extraction	4-15
4.3.3	3.1 Description	4-15
	3.2 Rock Extraction Methods	
4.3.4	Peat and Spoil Management Plan	
	1 Quantities	
1.3.7	2 Peat and Spoil Usage in Restoration of Borrow Pits	4-10 مل ⁻⁴
4.3.5	Substation Extension	
	5.1 Substation Control Building	
4.3.6	Site Underground Cabling	
4.3.7	Meteorological Mast	4-24
4.3.8	Temporary Construction Compounds	4-25
4.3.9	Tree Felling and Replanting	
	2.1 Tree Felling	
	2.2 Tree Planting	
4.3.10		
	Site Activities	
	0.1 Environmental Management	
	0.2 Refuelling	
	0.3 Concrete Deliveries	
	0.4 Concrete Pouring	
4.3.1	0.5 Dust Suppression	4-33
4.3.1	0.6 Vehicle Washing	4-33
	0.7 Waste Management	
4.4 Ac	cess and Transportation	
4.4.1	Site Entrance	4-34
4.4.2	Turbine and Construction Materials Transport Route	4-34
	Accommodation Works	
4.4.3	Traffic Management	
	mmunity Gain Proposal	
4.5.1	Background	
4.5.2	The Proposal	4-39
4.5.2	.1 Financial Contributions	4-39
4.5.3	Community and Voluntary Group Fund	4-39
4 - 4		
4.5.4	Renewable Energy Fund for Local Residents	4-39
	Renewable Energy Fund for Local Residents	
4.6 Site	e Drainage	4-40
4.6 Site	e DrainageIntroduction	4-40 4-40
4.6.1 4.6.2	e DrainageIntroductionExisting Drainage Features	4-40 4-40 4-40
4.6.1 4.6.2 4.6.3	e Drainage	4-40 4-40 4-40 4-40
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4	e Drainage	4-40 4-40 4-40 4-40 4-42
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4	e Drainage	4-40 4-40 4-40 4-40 4-42
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4	e Drainage	4-40 4-40 4-40 4-42 4-43
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4	e Drainage	4-40 4-40 4-40 4-42 4-43
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4	E Drainage	4-40 4-40 4-40 4-42 4-43 4-43
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4	E Drainage	4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4	e Drainage	4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4	e Drainage	4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6	Porainage	4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6	Prainage	4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-47 4-48
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4	Prainage	4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-47 4-48 4-49
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4	e Drainage	4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-47 4-48 4-49
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4	e Drainage	4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-48 4-49 4-49
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4	e Drainage	4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-47 4-48 4-49 4-49 4-49
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4	e Drainage	4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-48 4-49 4-49 4-50 4-50
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.5	e Drainage	4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-48 4-49 4-49 4-50 4-50 4-52
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.5 4.6.5 4.6.6	Introduction Existing Drainage Features Drainage Design Principles Drainage Design L1 Interceptor Drains L2 Swales L3 Check Dams L4 Level Spreaders L5 Piped Slope Drains L6 Vegetation Filters L7 Stilling Ponds (Settlement Ponds) L8 Siltbuster L9 Silt Bags L10 Sedimats L11 Culverts L12 Silt Fences L13 Forestry Felling Drainage Borrow Pit Drainage Cable Trench Drainage	4-40 4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-47 4-47 4-49 4-49 4-50 4-50 4-52
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.6 4.6.5 4.6.6 4.6.7	Introduction Existing Drainage Features Drainage Design Principles Drainage Design L1 Interceptor Drains L2 Swales L3 Check Dams L4 Level Spreaders L5 Piped Slope Drains L6 Vegetation Filters L7 Stilling Ponds (Settlement Ponds) L8 Siltbuster L9 Silt Bags L10 Sedimats L11 Culverts L12 Silt Fences L13 Forestry Felling Drainage Borrow Pit Drainage Cable Trench Drainage Management	4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-47 4-47 4-48 4-49 4-49 4-50 4-50 4-52 4-52 4-53
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.5 4.6.6 4.6.7	E Drainage	4-40 4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-47 4-47 4-49 4-49 4-50 4-52 4-53
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.6 4.6.7 4.6.7	Introduction Existing Drainage Features Drainage Design Principles Drainage Design Interceptor Drains Swales Check Dams Level Spreaders Spiped Slope Drains Vegetation Filters Stilling Ponds (Settlement Ponds) Silt Bags Silt Bags Cluverts Silt Fences Silt Fences Silt Fences Silt Prestry Felling Drainage Cable Trench Drainage Management Preparative Site Drainage Management Pre-emptive Site Drainage Management	4-40 4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-47 4-47 4-49 4-49 4-50 4-52 4-53 4-53
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.6 4.6.7 4.6.7	Introduction Existing Drainage Features Drainage Design Principles Drainage Design Interceptor Drains Swales Check Dams Level Spreaders Spiped Slope Drains Vegetation Filters Stilling Ponds (Settlement Ponds) Silt Bags In Culverts Silt Fences Silt Fences Silt Fences Site and Drainage Management Preperative Site Drainage Management Pre-emptive Site Drainage Management Pre-emptive Site Drainage Management Reactive Site Drainage Management Reactive Site Drainage Management	4-40 4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-48 4-49 4-49 4-50 4-50 4-52 4-53 4-53
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.6 4.6.7 4.6.7 4.6.7 4.6.7 4.6.7 4.6.7	Introduction Existing Drainage Features Drainage Design Principles Drainage Design Interceptor Drains Swales Check Dams Level Spreaders Spiped Slope Drains Vegetation Filters Stilling Ponds (Settlement Ponds) Silt Bags In Culverts Silt Fences Silt Fences Silt Fences Site and Drainage Management Preperative Site Drainage Management Pre-emptive Site Drainage Management Reactive Site Drainage Management Drainage Maintenance	4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-48 4-49 4-49 4-50 4-52 4-52 4-53 4-53 4-53
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.5 4.6.6 4.6.7 4.6.7 4.6.7 4.6.8 4.6.9	e Drainage Introduction Existing Drainage Features. Drainage Design Principles. Drainage Design. 1 Interceptor Drains. 2 Swales 3 Check Dams 4 Level Spreaders. 5 Piped Slope Drains. 6 Vegetation Filters. 7 Stilling Ponds (Settlement Ponds). 8 Siltbuster. 9 Silt Bags. 10 Sedimats. 11 Culverts. 12 Silt Fences. 13 Forestry Felling Drainage. Borrow Pit Drainage. Cable Trench Drainage. Site and Drainage Management. 1 Preparative Site Drainage Management. 2 Pre-emptive Site Drainage Management. Drainage Maintenance. Construction Phasing and Timing.	4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-47 4-49 4-49 4-50 4-52 4-52 4-53 4-53 4-53 4-53 4-53
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.6 4.6.7 4.6.7 4.6.7 4.6.7 4.6.7 4.6.7	e Drainage Introduction Existing Drainage Features. Drainage Design Principles. Drainage Design. 1 Interceptor Drains. 2 Swales 3 Check Dams 4 Level Spreaders. 5 Piped Slope Drains. 6 Vegetation Filters. 7 Stilling Ponds (Settlement Ponds). 8 Siltbuster. 9 Silt Bags. 10 Sedimats. 11 Culverts. 12 Silt Fences. 13 Forestry Felling Drainage. Borrow Pit Drainage. Cable Trench Drainage. Site and Drainage Management. 1 Preparative Site Drainage Management. 2 Pre-emptive Site Drainage Management. 3 Reactive Site Drainage Management. Drainage Maintenance. Construction Phasing and Timing. Construction Sequencing.	4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-49 4-50 4-52 4-52 4-53 4-53 4-53 4-53 4-54 4-54
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.5 4.6.6 4.6.7 4.6.7 4.6.7 4.6.8 4.6.9	e Drainage Introduction Existing Drainage Features. Drainage Design Principles. Drainage Design. 1 Interceptor Drains. 2 Swales 3 Check Dams 4 Level Spreaders. 5 Piped Slope Drains. 6 Vegetation Filters. 7 Stilling Ponds (Settlement Ponds). 8 Siltbuster. 9 Silt Bags. 10 Sedimats. 11 Culverts. 12 Silt Fences. 13 Forestry Felling Drainage. Borrow Pit Drainage. Cable Trench Drainage. Site and Drainage Management. 1 Preparative Site Drainage Management. 2 Pre-emptive Site Drainage Management. Drainage Maintenance. Construction Phasing and Timing.	4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-49 4-50 4-52 4-52 4-53 4-53 4-53 4-53 4-54 4-54
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.5 4.6.6 4.6.7 4.6.7 4.6.7 4.6.7 4.6.8 4.6.9 4.6.10 4.6.11	e Drainage Introduction Existing Drainage Features Drainage Design Principles Drainage Design Interceptor Drains Swales Check Dams Level Spreaders Fiped Slope Drains Siltbuster Silt Bags In Sedimats Culverts Silt Fences Borrow Pit Drainage Borrow Pit Drainage Borrow Pit Drainage Cable Trench Drainage Management Preparative Site Drainage Management Pre-emptive Site Drainage Management Drainage Maintenance Construction Phasing and Timing Construction Phase Monitoring and Oversight.	4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-47 4-49 4-50 4-50 4-52 4-53 4-53 4-53 4-53 4-54 4-54 4-54
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.6 4.6.7 4.6.7 4.6.7 4.6.7 4.6.8 4.6.9 4.6.10 4.6.11 4.7 Co	e Drainage Introduction Existing Drainage Features Drainage Design Principles Drainage Design Interceptor Drains Swales Check Dams Level Spreaders Fiped Slope Drains Silting Ponds (Settlement Ponds) Silt Bags In Sedimats Culverts Silt Fences Borrow Pit Drainage Borrow Pit Drainage Cable Trench Drainage Site and Drainage Management Preparative Site Drainage Management Preperment Ponds Management Preperment Ponds Management Preperment Ponds Management Preperment Ponds Management Preparative Site Drainage Management Drainage Maintenance Construction Phasing and Timing Construction Phase Monitoring and Oversight Instruction Methodologies	4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-47 4-49 4-50 4-50 4-52 4-53 4-53 4-53 4-53 4-54 4-54 4-56
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.6 4.6.7 4.6.7 4.6.7 4.6.8 4.6.9 4.6.10 4.6.11 4.7 Co 4.7.1	e Drainage	4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-47 4-49 4-49 4-50 4-50 4-52 4-53 4-53 4-53 4-53 4-53 4-54 4-56
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.6 4.6.7 4.6.7 4.6.7 4.6.7 4.6.8 4.6.9 4.6.10 4.6.11 4.7 Co 4.7.1 4.7.2	Introduction Existing Drainage Features Drainage Design Principles Drainage Design	4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-47 4-49 4-49 4-50 4-52 4-53 4-53 4-53 4-53 4-53 4-54 4-56 4-56 4-56
4.6 Site 4.6.1 4.6.2 4.6.3 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.4 4.6.5 4.6.6 4.6.7 4.6.7 4.6.7 4.6.8 4.6.9 4.6.10 4.6.11 4.7 Co 4.7.1	e Drainage	4-40 4-40 4-40 4-40 4-40 4-42 4-43 4-43 4-44 4-46 4-46 4-47 4-47 4-49 4-49 4-50 4-52 4-52 4-53 4-53 4-53 4-53 4-54 4-54 4-56 4-56 4-56 4-56 4-57 4-57



	4.7.5 Underground Cable Trench	
	4.7.5.1 Existing Underground Services	
	4.7.5.2 Joint Bays	4-60
	4.7.5.3 Underground Cable Watercourse/Culvert Crossings	
	4.8 Operation	
	4.8.1 Maintenance	
	4.8.2 Monitoring	4-68
	4.9 Decommissioning	4-68
5.	POPULATION AND HUMAN HEALTH	
J.		
	5.1 Introduction	
	5.1.1 Statement of Authority	
	5.2 Population	
	5.2.1 Receiving Environment	
	5.2.2 Population Trends	
	5.2.3 Population Density	
	5.2.4 Household Statistics	
	5.2.5 Age Structure	
	5.2.6 Employment and Economic Activity	5-6
	5.2.6.1 Economic Status of the Study Area	5-6
	5.2.6.2 Employment by Socio-Economic Group	
	5.2.6.3 Employment and Investment Potential in the Irish Wind Energy Industry	
	5.2.7 Land-Use	
	5.2.7.1 Equine Industry	
	5.2.8 Services	
	5.2.8.2 Access and Public Transport	
	5.2.8.3 Amenities and Community Facilities	
	5.3 Tourism	
	5.3.1 Tourism Numbers and Revenue	
	5.3.2 Tourist Attractions	
	5.3.3 Tourist Attitudes to Wind Farms	
	5.3.3.1 Scottish Tourism Survey 2016	
	5.3.3.2 Fáilte Ireland Surveys 2007 and 2012	
	5.4 Public Perception of Wind Energy	
	5.4.1 Sustainable Energy Ireland Survey 2003	
	5.4.1.1 Background	
	5.4.1.2 Findings	
	5.4.1.3 Survey Update 2017	
	5.4.1.4 Conclusions	
	5.4.2 Public Perceptions of Wind Power in Scotland and Ireland Survey 2005	
	5.4.2.1 Background	5-17
	5.4.2.3 Study Area	
	5.4.2.4 Conclusions	
	5.4.3 IWEA Interactions Opinion Poll on Wind Energy	
	5.5 Health Impacts of Wind Farms	
	5.5.1 Health Impact Studies	
	5.5.2 Turbine Safety	
	5.5.3 Electromagnetic Interference	
	5.5.4 Assessment of Effects on Human Health	
	5.5.5 Vulnerability of the Project to Natural Disasters and Major Accidents	
	5.6 Property Values	
	5.7 Shadow Flicker	
	5.7.1 Background	
	5.7.2 Guidance	
	5.7.3 Scoping	
	5.7.4 Shadow Flicker Prediction Methodology	
	5.7.5 Shadow Flicker Assessment Criteria	
	5.7.5.1 Turbine Dimensions	
	5.7.5.2 Study Area	
	5.7.6 Shadow Flicker Assessment Results	
	5.7.6.1 Daily and Annual Shadow Flicker	
	on the first of th	



	5.7.6.2 Comparative Shadow Flicker Assessment	5-41
	5.7.6.3 Cumulative Shadow Flicker	5-42
	5.8 Residential Amenity	5-46
	5.9.1 'Do-Nothing' Scenario	
	5.9.2 Construction Phase	
	5.9.2.1 Health and Safety	5-46
	5.9.2.2 Employment and Investment	5-47
	5.9.2.3 Population	
	5.9.2.4 Land-use	
	5.9.2.5 Tourism and Amenity	
	5.9.2.6 Noise 5-49	
	5.9.2.7 Air (Dust)	5 50
	5.9.2.8 Traffic	
	5.9.2.9 Shadow Flicker	
	5.9.3 Operational Phase	
	5.9.3.1 Health and Safety	
	5.9.3.2 Employment and Investment	
	5.9.3.3 Population	5-54
	5.9.3.4 Property Values	
	5.9.3.5 Land-use	5-54
	5.9.3.6 Noise 5-54	
	5.9.3.7 Traffic	5-55
	5.9.3.8 Tourism	
	5.9.3.9 Shadow Flicker	
	5.9.3.10 Interference with Communication Systems	
	5.9.3.11 Residential Amenity	
	5.9.4 Decommissioning Phase	
	5.9.5 Cumulative Effects	
	5.9.5.1 Employment and Economic Activity	
	5.9.5.2 Tourism and Amenity	5-66
	5.9.5.3 Traffic	
	5.9.5.4 Air (Dust)	5-67
	5.9.5.5 Health and Safety	5-67
	5.9.5.6 Property Values	5-67
	5.9.5.7 Services	5-67
	5.9.5.8 Shadow Flicker	5-68
	5.9.5.9 Residential Amenity	
	5.10 Summary	
	3.10 Julillary	
6.	BIODIVERSITY	6-1
	6.1 Introduction	6-1
	6.2 Requirements for Ecological Impact Assessment	6-3
	6.3 Scoping/Review of Relevant Guidance and Sources of Consultation	6.5
	3.5 Scoping/Neview of Nelevant duluance and Sources of Consultation	0-3
	6.3.1 Statement of Authority	
	6.4 Methodology	6-6
	6.4.1 Desk Study	6-6
	6.4.2 Scoping and Consultation	
	6.4.3 Field Surveys	
	6.4.3.1 Multi-disciplinary Walkover Surveys (as per NRA Guidelines, 2009)	
	6.4.3.2 Dedicated Habitat and Vegetation Composition Surveys	
	6.4.3.3 Terrestrial Fauna Surveys	
	6.4.4 Methodology for Assessment of Impacts and Effects	
	6.4.4.1 Identification of Target Receptors and Key Ecological Receptors	
	6.4.4.2 Determining Importance of Ecological Receptors	
	6.4.4.3 Characterisation of Impacts and Effects	
	6.4.4.4 Determining the Significance of Effects	
	6.4.4.5 Incorporation of Mitigation	6-22
	6.5 Establishing the Ecological Baseline	
	6.5.1 Desk Study	
	6.5.1.1 Designated Sites	
	6.5.1.2 NPWS Article 17 Reporting	
	6.5.1.3 Vascular plants	
	6.5.1.4 Bryophytes	
	6.5.1.5 National Biodiversity Data Centre (NBDC) Records	
	6.5.1.6 Bat Records	
	6.5.1.1 NPWS Protected Species Records	6-30



	6.5.1.2 Inland Fisheries Ireland Data	6-31
	6.5.1.3 Invasive Species	
	6.5.1.4 Freshwater Pearl Mussel (Margaritifera margaritifera)	6-33
	6.5.1.5 Marsh Fritillary (Euphydryas aurinia)	
	6.5.1.6 Conclusions of the Desktop Study	6-33
	6.6 Ecological Walkover Survey Results	
	6.6.1 Description of Habitats, Flora & Fauna within the Ecological Survey Area	
	6.6.1.1 Habitats within the EIAR Study Area Boundary	
	6.6.1.2 Habitats Along the Haul Route	
	6.6.1.4 Fauna in the Existing Environment	
	6.6.2 Importance of Ecological Receptors	
	6.7 Ecological Impact Assessment	
	6.7.1 Do-Nothing Effect	6-71
	6.7.2 Effects on Designated Sites	6-71
	6.7.3 Likely Significant Effects During Construction Phase	
	6.7.3.1 Effects on Habitats During Construction	
	6.7.3.2 Effects on Fauna During Construction	
	6.7.4 Likely Significant Effects During Operational Phase	
	6.7.4.1 Effects on Habitats during Operation	
	6.7.4.2 Effects on Fauna during Operation	
	6.7.5 Likely Significant Effects During Decommissioning phase	
	6.7.6 Monitoring Proposals	6-85
	6.8 Cumulative impacts	6-85
	6.8.1 Assessment of Plans	6-85
	6.8.2 Assessment of Projects	
	6.8.3 Existing Habitats and Land Uses	
	6.8.4 Assessment of Cumulative Effects	
	6.9 Conclusion	6-91
_		
/ <u>.</u>	ORNITHOLOGY	/-1
	7.1 Introduction	7_1
	7.1.1 Decayintian of the Dyen acad Davidenment	7 2
	7.1.1 Description of the Proposed Development	
	7.1.2 Legislation, Guidance and Policy Context	7-2
	7.1.2 Legislation, Guidance and Policy Context	7-2 7-3
	7.1.2 Legislation, Guidance and Policy Context	7-2 7-3
	7.1.2 Legislation, Guidance and Policy Context	7-2 7-3 7-3
	7.1.2 Legislation, Guidance and Policy Context	7-2 7-3 7-3 7-3
	7.1.2 Legislation, Guidance and Policy Context	7-2 7-3 7-3 7-3
	7.1.2 Legislation, Guidance and Policy Context	7-2 7-3 7-3 7-3 7-4
	7.1.2 Legislation, Guidance and Policy Context	7-2 7-3 7-3 7-3 7-4 7-4
	7.1.2 Legislation, Guidance and Policy Context	7-2 7-3 7-3 7-3 7-4 7-4 7-5
	7.1.2 Legislation, Guidance and Policy Context	7-2 7-3 7-3 7-4 7-4 7-5 7-5
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-5
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-57-5
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-20
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-20
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-20
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-207-20
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-207-207-207-207-20
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-207-207-207-207-20
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-207-207-207-23
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-237-23
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-237-23
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-237-23
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-207-207-207-24
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-207-207-217-237-24
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-207-207-247-24
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-207-247-247-24
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-207-217-237-247-24
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-207-207-207-207-217-237-247-24
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-57-207-207-207-207-217-237-247-247-337-33
	7.1.2 Legislation, Guidance and Policy Context. 7.1.3 Statement of Authority and Competence. 7.2 Assessment Approach and Methodology. 7.2.1 Desk Study	7-27-37-47-57-57-57-207-207-207-207-207-247-247-247-337-33
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-57-207-207-237-247-247-247-337-337-347-35
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-57-207-207-207-237-247-247-317-337-337-357-35
	7.1.2 Legislation, Guidance and Policy Context	7-27-37-37-47-57-57-57-57-207-207-207-237-247-247-317-337-337-357-35



	7.4.3	Merlin	/-38
	7.4.4	Peregrine Falcon	7-38
	7.4.5	Osprey	7-38
	7.4.6	Common Snipe	
	7.4.7	Kestrel	
	7.4.8	Red Grouse	
	7.4.9	Woodcock	
	7.4.10	Buzzard	
	7.4.10	Sparrowhawk	
	7.4.12	Passerines (Red-listed)	
1.5	5 Ev	aluation	
	7.5.1	Golden Plover	
	7.5.2	Hen Harrier	
	7.5.3	Merlin	
	7.5.4	Peregrine Falcon	7-45
	7.5.5	Osprey	7-45
	7.5.6	Curlew	
	7.5.7	Common Snipe	
	7.5.8	Kestrel	
	7.5.9	Red Grouse	
	7.5.10	Woodcock	
	7.5.10	Buzzard	
	7.5.11	Sparrowhawk	
	7.5.12		
- <i>-</i>		Passerines (Red-listed)	
		entification of Key Ornithological Receptors	
7.7		OR Sensitivity Determination	
7.8	3 Lik	cely and Significant Effects	7-53
	7.8.1	Do-Nothing Effect	7-53
	7.8.2	Effects on Key Ornithological Receptors during Construction and Operation	7-55
		2.1 Hen Harrier (All Seasons)	
	7.8.	2.2 Golden Plover (Wintering)	
	7.8.	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	
	7.8.		
	7.8.		
	7.8.		
	7.8.		
	7.8 7.8.	2.8 Red Grouse (Breeding)	
	7.8.3	2.9 Sparrowhawk (All Seasons) Effects on Key Ornithological Receptors during Decommissioning	
		3.1 All Species	7 - / 1. 7 71
	7.8.4	Effects Associated with the Cable Route	
	7.8.5	Effects on Designated Areas	
7.9			
/.5		tigation and Best Practice Measures	
	7.9.1	Mitigation by Design	
	7.9.2	Mitigation During Construction, Operation and Decommissioning	
		2.1 Construction Phase Mitigation	
		2.2 Operational Phase Mitigation	
7 1		2.3 Decommissioning Phase Mitigation	
7.1		hancement Plan	
7.1	.1 M o	onitoring	
	7.11.1	Commencement and Pre-Construction Monitoring	
	7.11.2	Post-Construction Monitoring	
7.1	.2 Re	sidual Effects	7-76
7.1		sessment of Cumulative Effects	
	7.13.1	Plans Considered in the Cumulative Impact Assessment	
	7.13.1	Projects Considered in the Cumulative Impact Assessment	
		2.2. Cumulative Assessment per Key Ornithological Receptor	
7 1		onclusion	
		71 N 41 A 41 N 41 L	, -(, /



8.	LAND SOILS AND GEOLOGY	8-1
	8.1 Introduction	8-1
	8.1.1 Background and Objectives	8-1
	8.1.2 Statement of Authority	8-1
	8.1.3 Relevant Legislation	8-2
	8.1.4 Relevant Guidance	8-2
	8.2 Assessment Methodology	8-3
	8.2.1 Desk Study	
	8.2.2 Baseline Monitoring and Site Investigations	
	8.2.3 Scope and Consultation	
	8.2.4 Impact Assessment Methodology	
	8.2.5 Limitations and Difficulties Encountered	
	8.3 Existing Environment	
	8.3.1 Site Description and Topography	
	8.3.2 Peat/Soils and Subsoils	
	8.3.3 Bedrock Geology	
	8.3.4 Geological Resource Importance	
	8.3.5 Geological Heritage Sites	
	8.3.6 Soil Contamination	
	8.3.7 Economic Geology	
	8.3.8 Peat Stability Assessment	
	8.3.8.1 Peat Stability Assessment Results	
	8.4 Characteristics of the Proposed Development	
	8.5 Likely Significant Effects on Land, Soils and Geology	
	8.5.1 Do Nothing Scenario	
	8.5.2 Construction Stage - Likely Significant Effects and Mitigation Measures	
	8.5.2.1 Peat, Subsoil Excavation and Bedrock Excavation	
	21 8.5.2.3 Erosion of Exposed Subsoils and Peat During Tree Felling, Access Road and Turbi	
	Construction Work	
	8.5.2.4 Peat Instability and Failure	
	8.5.2.5 Slievecallan Wind Farm Substation Extension Works	
	8.5.2.6 Turbine Delivery Route Works	
	8.5.3 Operational Stage - Likely Significant Effects and Mitigation Measures	
	8.5.3.1 Site Road Maintenance during the Operational Stage	
	8.5.3.3 Use of Oils in Turbine Transformers During Operational Stage	
	8.5.4 Decommissioning Stage - Likely Significant Effects and Mitigation Measure	
	8.5.5 Risk of Major Accidents and Disasters	
	8.5.6 Post Construction Monitoring	
	8.5.7 Potential Cumulative Impacts	
	8.5.8 Summary	
9.	HYDROLOGY AND HYDROGEOLOGY	9-1
	9.1 Introduction	9-1
	9.1.1 Background and Objectives	
	9.1.2 Statement of Authority	9-1
	9.1.3 Scoping and Consultation	
	9.1.4 Relevant Legislation	9-2
	9.1.5 Relevant Guidance	
	9.2 Methodology	9-4
	9.2.1 Desk Study	
	9.2.2 Baseline Monitoring and Site Investigations	
	9.2.3 Impact Assessment Methodology	
	9.2.4 Overview of Impact Assessment Process	
	9.2.5 Limitations and Difficulties Encountered	9-7
	9.3 Receiving Environment	
	9.3.1 Site Description and Topography	
	9.3.2 Water Balance	
	9.3.3 Regional Hydrology	9-8



	9.3.4 Proposed Development Site Drainage	9-9
	9.3.5 Baseline Assessment of Development Site Runoff	
	9.3.6 Flood Risk Assessment	
	9.3.7 Surface Water Quality	
	9.3.8 Hydrogeology	
	9.3.9 Groundwater Vulnerability	
	9.3.10 Groundwater Hydrochemistry	
	9.3.11 Groundwater Body Status	
	9.3.12 Surface Water Body Status	
	9.3.13 Designated Sites and Habitats	
	9.3.14 Water Resources	
	9.3.15 Receptor Sensitivity	9-22
	9.4 Characteristics of the Proposed Development	
	9.4.1 Proposed Drainage Management	
	9.5 Likely Significant Effects and Mitigation Measures	
	9.5.1 Do Nothing Scenario	
	9.5.2 Construction Phase – Likely Significant Effects and Mitigation Measures	
	9.5.2.1 Clear Felling of Coniferous Plantation	
	9.5.2.2 Earthworks (Removal of Vegetation Cover, Excavations and Stock Piling) Resulting in	
	Suspended Solids Entrainment in Surface Waters	
	9.5.2.3 Potential Impacts on Groundwater Levels and Local Well Supplies During Excavation	
	Borrow Pits	
	9.5.2.4 Excavation Dewatering and Potential Impacts on Surface Water Quality	
	9.5.2.6 Groundwater and Surface Water Contamination from Wastewater Disposal	9-36
	9.5.2.7 Release of Cement-Based Products	
	9.5.2.8 Morphological Changes to Surface Water Courses & Drainage Patterns	
	9.5.2.9 Potential Hydrological Impacts on Designated Sites	9-39
	9.5.2.10 Potential Effects on Local Groundwater Well Supplies	
	9.5.2.11 Turbine Delivery Route Works	9-41
	9.5.2.12 Effects of Tree Felling and Construction Works on the WFD Status of Downstream Waterbodies	0.42
	9.5.2.13 Potential for Increased Surface Water Runoff	
	9.5.3 Operational Phase – Likely Significant Effects and Mitigation Measures	
	9.5.3.1 Increased Surface Water Runoff Rates due to Road and Hardstand Emplacement	9-43
	9.5.3.2 Effects on Hydrology during Operational PhasePhase	
	9.5.4 Decommissioning Phase - Likely Significant Effects and Mitigation Measures	
	9.5.5 Risk of Major Accidents and Disasters	9-47
	9.5.6 Cumulative Impacts	
	9.5.7 Conclusion	9-49
10.	AIR AND CLIMATE	10-1
	10.1 Introduction	10 1
	10.1.1 Background	
	10.1.2 Statement of Authority	
	10.2.1 Air Quality Standards	
	10.2.2 Air Quality Zones	
	10.2.3 Existing Air Quality	
	10.2.3.1 Sulphur Dioxide (SO ₂)	
	10.2.3.2 Particulate Matter (PM ₁₀)	
	10.2.3.3 Nitrogen Dioxide (NO ₂)	10-7
	10.2.3.4 Carbon Monoxide (CO)	
	10.2.3.5 Ozone (0 ₃)	10-8
	10.2.3.6 Dust 10-9	10.0
	10.2.4 Likely Significant Effects and Associated Mitigation Measures	
	10.2.4.2 Construction Phase	
	10.2.4.3 Operational Phase	
	10.2.4.4 Decommissioning Phase	
	10.3 Climate	
	10.3.1 Climate Change and Greenhouse Gases	10-14
	10.3.1.1 Greenhouse Gas Emission Targets	
	10.3.2 Climate and Weather in the Existing Environment	10-24



	10.3.3 Calculating Carbon Losses and Savings from the Proposed Development	
	10.3.3.1 Background	10-26
	10.3.3.2 Methodology for Calculating Losses	
	10.3.3.3 Calculating Carbon Losses and Savings	
	10.3.3.5 Carbon Savings	
	10.3.4 Likely Significant Effects and Associated Mitigation Measures	
	10.3.4.1 'Do-Nothing' Effect	
	10.3.4.2 Construction Phase	10-30
	10.3.4.3 Operational Phase	
	10.3.4.4 Greenhouse Gas Emissions	10-31
	10.3.4.5 Decommissioning Phase	
	10.4 Cumulative Assessment	10-32
11.	NOISE AND VIBRATION	11-1
	11.1 Introduction	11-1
	11.1.1 Background and Objectives	
	11.1.2 Statement of Authority	
	11.2 Fundamentals of Acoustics	
	11.3 Assessment Methodology	
	11.3.1 EPA Description of Effects	
	11.3.2 Guidance Documents and Assessment Criteria	
	11.3.2.1 Construction and Decommissioning Phase	
	11.3.2.2 Operational Phase	
	11.3.3 Special Characteristics of Turbine Noise	
	11.3.3.1 Infrasound/Low Frequency Noise	11-11
	11.3.3.2 Amplitude Modulation	
	11.3.4 Comments on Human Health Impacts	11-15
	11.3.4.1 The National Health and Medical Research Council	
	11.3.4.2 Health Canada	
	11.3.4.3 New South Wales Health Department	11-15
	11.3.4.4 The Australian Medical Association	
	11.3.4.5 Journal of Occupational and Environmental Medicine	
	11.3.5 Vibration	
	11.3.6 Background Noise Assessment	
	11.3.6.1 Choice of Measurement Locations	11-16
	11.3.6.2 Measurement Period	11-22
	11.3.6.3 Personnel and Instrumentation	11-22
	11.3.6.4 Procedure	11-23
	11.3.6.5 Analysis of Background Noise Data	11-23
	11.3.7 Turbine Noise Calculations	
	11.3.7.1 Noise Modelling Software	
	11.3.7.2 Input Data and Assumptions	
	11.3.7.3 Consideration of Wind Direction and Noise Propagation	
	11.3.8 Assessment of Construction Impacts	
	11.4 Receiving Environment	
	11.4.1 Background Noise Levels	
	11.4.1 Background Noise Leveis	
	11.4.1.1 Location A	
	11.4.1.3 Location C	
	11.4.1.4 Location D	
	11.4.1.5 Location E	
	11.4.1.6 Summary of Background Noise Levels	11-39
	11.4.2 Wind Turbine Noise Criteria	
	11.4.2.1 Assigning Turbine Noise Limits	
	Likely Significant Effects and Associated Mitigation Measures	
	11.5.1 Do-Nothing Scenario	
	11.5.2 Construction Phase Potential Impacts	
	11.5.2.1 Turbines, Hardstands, Substation, Underground cabling and Access Roads	
	11.5.2.2 Construction Traffic	
	11.5.2.3 Borrow Pits and Rock Extraction Methods	
	11.5.3 Operational Phase Potential Impacts	
	11.5.3.2 Internal Roads	
	11.5.3.3 Substation	



	11.5.4 Decommissioning Phase Potential Impacts	11-54
	11.5.4.1 Description of Effects	11-55
	11.5.5 Construction Phase Mitigation	
	11.5.5.1 Construction Phase Mitigation Measures – Noise	
	11.5.5.2 Construction Phase Mitigation Measures – Vibration	
	11.5.6 Operational Phase Mitigation Measures	
	11.5.6.2 Curtailment 11.5.6.2 Low Frequency Noise	
	11.5.6.3 Amplitude Modulation	
	11.5.6.4 Monitoring	
	11.5.7 Decommissioning Phase Mitigation Measures	
	11.5.8 Description of Residual Effects	
	11.5.8.1 Construction and Decommissioning Phase	
	11.5.8.2 General Construction – Turbines and Hardstands Substation and Grid Connection	
	11.5.8.3 Internal Roads Construction	
	11.5.8.4 Junction Upgrade Works	11-61
	11.5.8.5 Borrow Pits and Rock Extraction Methods	
	11.5.8.6 Construction Traffic	
	11.5.8.7 Operational Phase	
	11.5.9 Cumulative Effects	
	11.5.9.1 Construction Phase	
	11.5.9.2 Operational Phase	
	11.6 Conclusion	
10	LANDCOADE AND VICUAL	10.1
12.	LANDSCAPE AND VISUAL	12-1
	12.1 Introduction	12-1
	12.1.1 Statement of Authority	
	12.1.2 'Do-Nothing' Scenario	
	12.1.3 Proposed Development Description	
	12.1.4 Mitigation by Design	
	12.1.5 Scoping Replies/Pre-Planning Meetings	
	12.2 Brief Methodology and Assessment Criteria	
	12.2.1 Scope and Definition of Landscape and Visual Impact (LVIA) Study Area	
	12.2.2 Guidelines	
	12.2.3 Baseline Landscape and Visual Information	
	12.2.4 Assessment of Potential Impacts	
	12.3 Landscape Policy Context	
	12.3.1 Clare Wind Energy Strategy	
	12.3.2 Clare County Development Plan 2017-2023	
	12.3.2.2 Scenic Routes	
	12.3.2.3 Settlements	
	12.3.2.4 Landscape Character Assessment	
	12.3.3 DoEHLG 'Wind Energy Development Guidelines' (2006)	
	12.4 Visibility of the Proposed Development	
	12.4.1 ZTV Mapping: Theoretical Visibility of the Proposed Development	
	12.5 Landscape Baseline	
	12.5.1 Landscape of the Proposed Development Site	
	12.5.1.2 Landscape Value and Sensitivity of the Proposed Development Site	
	12.5.2 Landscape Receptors in the Wider LVIA Study Area	
	12.5.2.1 Landscape Character Areas	
	12.5.2.2 Landscapes of National and International Renown	
	12.5.3 Landscape Receptor Preliminary Assessment	12-32
	12.6 Visual Baseline	12-36
	12.6.1 Visual Receptors	
	12.6.1.1 Designated Scenic Routes	
	12.6.1.2 Settlements	12-37
	12.6.1.3 Recreation and Tourist Destinations	
	12.6.1.4 Viewing Areas	
	12.6.1.5 Transport Routes	
	12.6.1.6 Recreational Routes	
	12.7 Cumulative Baseline	
	12.7.1 Comparative Cumulative Visibility – Half Blade 7TV	レーカリ



	12.8 Likely or Significant Landscape and Visual Effects	12-53
	12.8.1 'Do-Nothing' Scenario	
	12.8.2 Construction Phase Effects	12-53
	12.8.2.1 Landscape Effects	
	12.8.2.2 Visual Effects	
	12.8.3 Operational Phase Effects	
	12.8.3.1 Landscape Effects	
	12.8.3.3 Visual Effects	
	12.8.3.4 Cumulative Visual Effects	
	12.8.4 Ancillary Project Elements	
	12.8.5 Decommissioning Phase Effects	
	12.9 Additional LVIA Commentary Regarding Clare County Council Decision	
	Ref. 21/370	
	12.9.1 Previous Reason for Refusal No. 1	
	12.9.1.1 Response to Refusal Reason No. 1	
	12.9.1.2 Photomontages – Turbine Tip Height Comparison	
	12.9.1.3 Summary Conclusion on Refusal Reason no. 1	
	12.10 Conclusion	
13.	ARCHAEOLOGY AND CULTURAL HERITAGE	13-1
	13.1 Introduction	
	13.1.1 Proposed Development	
	13.1.2 Statement of Authority	
	13.1.3 Legislation and Guidelines	
	13.1.3.1 Current Legislation	
	13.1.3.2 Clare County Development Plan 2017-2023	
	13.1.4 Location and Topography	
	13.2 Methodology	
	13.2.1 Geographical Information Systems	
	13.2.2 Desktop Assessment	
	13.2.2.1 Record of Monuments and Places	
	13.2.2.2 Cartographic Sources and Aerial Photography	
	13.2.2.3 Topographical Files - National Museum of Ireland	
	13.2.2.5 Clare County Development Plans	
	13.2.2.6 Excavations Database	
	13.2.2.7 National Inventory of Architectural Heritage (NIAH)	13-9
	13.2.3 Field Inspection	13-9
	13.2.3.1 Limitations Associated with Fieldwork	
	13.2.4 Assessment of Likely Significant Effects	
	13.2.4.1 Types of Impact	
	13.2.5 Methodology for the assessment of impacts on visual setting (indirect e	
	13.3 Existing Environment	
	13.3.1 Description of the proposed EIAR study area	
	13.3.2 Archaeological Heritage	
	13.3.2.1 National Monuments	13-49
	13.3.2.2 Recorded Monuments within the EIAR site boundary	
	13.3.2.4 Archaeological Investigations undertaken within or adjacent to the proposed E	
	boundary	
	13.3.2.5 Townlands and administrative boundaries	
	13.3.2.6 Topographical Museum Files	13-96
	13.3.2.7 Cartographic Evidence	
	13.3.2.8 Lewis Topographical Dictionary of Ireland	
	13.3.3 Architectural and Cultural Heritage	
	13.3.3.1 Protected Structures within the EIAR site boundary	
	13.3.3.2 Protected Structures within 5km of the nearest proposed turbines	
	13.3.3.4 Local Cultural Heritage	
	13.3.4 Archaeological and Architectural Heritage along the Proposed Delivery	
	13.3.4.1 Named Bridges along the Delivery Route	
	13.3.4.2 Junction Accommodation Areas	
	13.4 Likely Significant Effects and Associated Mitigation Measures	
	13.4.1 Construction Phase Potential Impacts (Indirect)	
	13.4.2 Construction Phase Potential Impacts (Direct)	



	13.4.2.1 National Monuments	13-107
	13.4.2.2 Recorded Monuments within the EIAR Boundary	
	13.4.2.3 Sub-surface archaeology	13-109
	13.4.2.4 Protected Structures within the EIAR Site Boundary	
	13.4.2.5 Local Cultural / Built Heritage	
	13.4.3 Operational Phase Potential Impacts (Indirect)	
	13.4.3.1 Impact on National Monuments in State Care / Guardianship	
	13.4.3.2 Impact on Recorded Monument within the EIAR boundary	
	13.4.3.4 Impact on RPS structures within the EIAR boundary	
	13.4.3.5 Impact on NIAH/RPS structures within 5km of the nearest proposed turbine	
	13.4.4 Operational Phase Potential Impacts (Direct)	
	13.5 Cumulative Impacts	13-120
	13.5.1 Cumulative Impacts (Direct Impacts)	
	13.5.2 Cumulative Impacts (Indirect Impact on Setting)	
	13.5.2.1 National Monuments	13-121
	13.5.3 Cultural Heritage Assets within 5km of the proposed Slieveacurry turbines	13-125
	13.6 Decommissioning Phase	13-125
	13.7 Conclusion	13-125
1.4	MATERIAL ASSETS	14.1
14.		
	14.1 Traffic and Transport	
	14.1.1 Introduction	
	14.1.1.1 Background and Objectives	
	14.1.1.2 Statement of Authority	
	14.1.1.3 Guidance and Legislation	
	14.1.1.5 Methodology and Section Structure	
	14.1.2 Receiving Environment	
	14.1.2.1 Site Location	
	14.1.2.2 Proposed Abnormal Size Load Delivery Route	14-3
	14.1.2.3 Proposed Construction Traffic Haul Route	
	14.1.2.4 Site Entrance	
	14.1.3 Existing Traffic Volumes	
	14.1.3.1 Background Traffic Flows	
	14.1.4 Proposed Development and Traffic Generation	14-0
	14.1.4.1 Development Trip Generation – During Construction	14-10
	14.1.4.2 Development Trip Generation – During Operation	14-14
	14.1.5 Construction Traffic Design Vehicles	
	14.1.5.1 Construction Traffic Vehicle Types	14-14
	14.1.6 Traffic Effects During Construction and During Operation	
	14.1.7 Traffic Management of Large Deliveries	
	14.1.8 Route Assessment	
	14.1.9 Provision for Sustainable Modes of Travel	
	14.19.1 Walking and Cycling	
	14.19.2 Public Transport	
	14.1.10 Likely and Significant Effects and Associated Mitigation Measures	
	14.1.10.1 "Do Nothing" Scenario	
	14.110.3 Operational Phase	
	14.1.10.4 Decommissioning Phase	
	14.1.10.5 Cumulative Effects	14-56
	14.1.10.6 Mitigation Measures	
	14.1.10.7 Residual Impacts	
	14.2 Telecommunications and Aviation	
	14.2.1 Introduction	
	14.2.1 Statement of Authority	
	14.2.3 Background	
	14.2.3.1 Broadcast Communications	
	14.2.3.2 Domestic Receivers	
	14.2.3.3 Other Signal Types	
	14.2.4 Preventing Electromagnetic Interference	
	14.2.4.1 National Guidelines	14-62
	14.2.4.2. Scoping and Consultation	14-62



	14.2.5 Likely Significant Effects and Associated Mitigation Measures	14-65
	14.2.5.1 'Do-Nothing' Scenario	14-65
	14.2.5.2 Construction Phase	14-65
	14.2.5.3 Operational Phase	14-65
	14.2.5.4 Cumulative Effect	14-66
15.	INTERACTION OF EFFECTS	15-1
	15.1 Introduction	15-1
	15.1.1 Statement of Authority	15-3
	15.2 Impact Interactions	15-3
	15.2.1 Population and Human Health	15-3
	15.2.2 Biodiversity	15-4
	15.2.3 Ornithology	15_5
	15.2.4 Land, Soils and Geology	15 6
	15.2.5 Air and Climate	15 6
	2011000p0 0110 11000	15-0
	15.3 Mitigation and Residual Impacts	15-7
16.	SCHEDULE OF MITIGATION AND MONITORING PROPOSALS	16-1
	16.1 Introduction	16-1
	16.2 EIAR Mitigation Measures	16-2
	16.3 EIAR Monitoring Measures	
	±0.0 En 11 110 III O III	

BIBLIOGRAPHY

Volume 2 – Photomontage Booklet

Volume 3 – Appendices 2-1 to 14-2