



1 PROPOSED Children play area - Detail 2  
1 : 250

**LEGEND**

	INDICATES EXISTING TREES IN GRASSSED VERGE
	INDICATES TREE PLANTING WITH SEMI MATURE MEDIUM GROWING TREES - SET INTO PREPARED PLANTING PITS WITH 5 CM OF SOIL AND ROOT PROTECTION BARRIER
	TREE PLANTING WITH LOW GROWING MULTI STEM SPECIA SET INTO PLANTER WITH DEAD MAN ANCHOR TREE SUPPORT
	TALL SHRUB WITH BAMBOO SUPPORT
	MATURE BAMBOO PLANT 5.0 M HIGH IN CORRTEN STEEL POT
	SHRUB PLANTING WITH MATURE PLANT SET INTO POT
	INDICATES HEDGE PLANTING WITH SEMI MATURE PLANTS
	SHRUB PLANTING WITH MIXED SPECIES INTO RAISED PLANTIE
	PERMEABLE TARMAC
	all cycle lanes
	SELECTED BRICK / COMPOSITE STONE PAVING Circular areas/intenal shared surface areas courtyards
	SMOOTH CONCRETE WITH BRUSH FINISH (anti slip finish) Normal footpaths
	COLORLED TARMAC all parking spaces
	PAVING BLOCKS WITH POROU SURFACE
	BENCH SEAT WITH STAINLESS STEEL FRAME AND TIMBER SEAT
	INDICATES LED UP LIGHTERS IN PAVING
	BOLLARDS WITH STAINLESS STEEL UNITS SET INTO LOOKABLE SOCKETS
	VISITOR BICYCLE PARKING AT PODIUM LEVEL
	PAVING WITH 400 WIDE GRANITE SLABS
	PAVING WITH NON SLIP GLAZING SLABS WITH LED LIGHTS UNDER

**PLANT LEGEND**

symbol	plant description	size in cm	comment
EE	Elaeagnus Ebingei	2.5 LT	CG 2.0 PER m2
LS	Lavandula Stoechas	2.0 LT	CG 2.5 PER m2
PM	Phyllostachys Mitis	3.0 LT	1.0 PER m2 PLANTED IN BOTTOMLESS POTS

**PLANTS PLANTED IN MIXED GROUPS AT 100 PER M2**  
 ANEMONE NEMEROSA  
 CROCUS TOMMASINIANUS  
 NARCISUS FEBRUARY SILVER  
 NARCISUS FEBRUARY GOLD  
 NARCISUS MT HOOD

**NOTES:**  
 ALL PLANTING TO BE UNDERTAKEN IN FIRST SEASON FOLLOWING COMPLETION OF SITE AND DEVELOPMENT WORKS TO EACH PHASE OF THE WORKS  
 NOTES ON SPECIFICATION:  
 ALL PLANTS TO SET INTO PREPARED PITS WITH MIXED WITH MOST MOSS PEAT AND SLOW RELEASING FERTILIZED PLANTING PITS TO BE 350 WIDER THAN ROOTBALL WITH BOTTOM 350 OF PIT DUG OVER TO ASSIST DRAINAGE  
 TREES TO HAVE 2 No. 70 DIA. TREATED TIMBER STAKES WITH CROSS RAIL AND THE SHRUB PLANTED AREAS IN GARDENS TO HAVE MIN 450 DEEP TOP SOIL ON SUB SOIL DUG OVER  
 SHRUB PLANTED AREAS IN OPEN SPACE TO HAVE MIN 450 DEEP TOP SOIL ON SUBSOIL DUG OVER GRASSING GRADE 2 SEED SPREAD ON CULTIVATED TOP SOIL 200 DEEP TO EVEN FLOWING LEVELS  
 WHERE NOTED OPEN SPACE AREAS TO HAVE MIX OF 2 CLOVER SPECIES AND NATIVE WILDFLOWERS AND EARLY FLOWERING BULBS  
 MAINTENANCE PERIOD TO BE 18 MONTHS TO INCLUDE WATERING, WEEDING AND REPLACEMENT AF FAILED PLANTS

**PROJECT** ■ Proposed Residential Development at Ballykeefe, Raheen, Co Limerick.  
**CLIENT** ■ DW Raheen Developments Ltd.  
**TITLE** ■ PROPOSED Children play area  
**SCALE:** 1:250 @A3 **DATE:** NOV. 2021 **DRWG. No.** PCR -01-09-03 **DRN. BY** Cass Roche  
**PC ROCHE + associates**  
 urban planners, environmental designers, landscape architects and site planners  
 1, 016337242  
 t, 08725922298  
 e, cass@pcroche.com

Use figured dimensions only. This data is supplied electronically for convenience only. No liability is accepted for any inference taken or effect on any system, however caused.  
 © This drawing and any design hereon is copyright and may not be altered, reproduced or otherwise used without express permission of PC ROCHE & Associates Limited.