



Area of Temporary Tree Protection and Controlled, Low Impact Works

Temporary Tree Protection Hoarding



This Drawing Must Be Read in Conjunction with the "Arboricultural Method Statement" at "Appendix 1" of the Associated Arboricultural Report

Ashgrove House
26 Foxrock Court
Dublin 18
D18 R2K1



Colour Coding of Tree Retention or Removal

- Trees Intended for Retention - Solid Green Crown Outline
- Trees Intended for Removal in Conjunction With Development Works - Broken Pink Crown Outline

Colour Coding of Tree Protection Measures

- Location Of Primary Construction Exclusion Fencing
- Area Of Primary Construction Exclusion Fencing
- Location of known works within "Construction Exclusion Zone", to be undertaken using low-impact methodologies and under the guidance of the Project Arborist

Tree Line

Colour Coding of Tree Categories

- Category "A" Trees (Green Button) Excellent Quality Trees
- Category "B" Trees (Blue Button) Good Quality Trees
- Category "C" Trees (Gray Button) Mediocre to Poor Quality Trees
- Category "U" Trees (Red Button) Dead, Dying or Otherwise Compromised Trees that are Unsalvageable.

Graphic Representation of Tree Form, Balance and Protection Zone

Canopy Extent
Cardinal Radii
Category Code
Stem Circumference

Canopy is drawn to account for any natural asymmetry or imbalance. Crown Representation is scaled to account for north, east, west and south radii.

Root Protection Area (RPA)
This area relates the "RPA" radius as defined in the Tree Survey Table and is measured from the tree centre.

Construction Exclusion Zone (CEZ)
This area defines the preliminary Construction Exclusion Zone (CEZ) that must be protected by fencing from the potentially damaging effects of construction activity.

Client : Balscadden GP3 LTD.
Scale : 1:500 @ A1 Date : March 2022
Project : Tree Survey, Balscadden, Howth, Co Dublin
Description : Tree Protection Plan
Drawing Title : Balscadden Tree Protection Plan

Mob. 086-3819011
e-mail - thetreefile@eircom.net