



# **Contents**

19.	Material Assets	. 1
19.1	Introduction	. 1
19.2	Methodology	. 2
19.2.1	Study Area	. 2
19.2.2	Relevant Guidelines, Policy and Legislation	. 3
19.2.3	Data Collection and Collation	. 3
19.2.4	Appraisal Method for the Assessment of Impacts	. 3
19.3	Baseline Environment	. 6
19.3.1	Major Infrastructure and Existing Utilities	. 6
19.3.2	Imported Material	. 7
19.4	Potential Impacts	. 8
19.4.1	Characteristics of the Proposed Scheme	. 8
19.4.2	'Do Nothing' Scenario	. 8
19.4.3	Construction Phase	. 8
19.4.4	Operational Phase	13
19.5	Mitigation and Monitoring Measures	16
19.5.1	Construction Phase	16
19.5.2	Operational Phase	17
19.6	Residual Impacts	18
19.6.1	Construction Phase	18
19.6.2	Operational Phase	18
19.7	References	19



# 19. Material Assets

# 19.1 Introduction

This Chapter of the Environmental Impact Assessment Report (EIAR) has considered the potential impacts on material assets associated with the Construction and Operational Phases of the Clongriffin to City Centre Core Bus Corridor Scheme (hereafter referred to as the Proposed Scheme).

The design of the Proposed Scheme has been developed to a stage where all potential environmental impacts can be identified, and a fully informed environmental impact assessment can be carried out. It is likely that the Proposed Scheme will be constructed by a contractor appointed under a Design and Build form of Contract. The contractor engaged will be responsible for finalising the design of the Proposed Scheme in compliance with the Employer's Requirements, including compliance with the requirements of the EIAR and Natura Impact Statement (NIS) (including all mitigation measures) and any development consent conditions. Minor modifications may be made to the current design at the detailed design stage to avail of opportunities to improve the design in the light of experience on the ground or other innovations. Any such minor modifications, however, will not give rise to any impacts which are more significant than those already identified and assessed in this EIAR.

During the Construction Phase, the potential impacts on material assets arising from the Proposed Scheme have been assessed, including potential impacts on utilities and potential impacts arising from the importation of construction materials, which result from construction activities such as utility diversions, road resurfacing and road realignments.

During the Operational Phase, the potential impacts on material assets associated with changes in utility demand from new infrastructure associated with the Proposed Scheme have been assessed. The assessment has been carried out according to best practice and guidelines relating to material asset assessment as outlined in Section 19.2.

The aim of the Proposed Scheme when in operation is to provide enhanced walking, cycling and bus infrastructure on this key access corridor in the Dublin region, which will enable and deliver efficient, safe, and integrated sustainable transport movement along the corridor. The objectives of the Proposed Scheme are described in Chapter 1 (Introduction). The Proposed Scheme which is described in Chapter 4 (Proposed Scheme Description) has been designed to meet these objectives.

The design of the Proposed Scheme has evolved through comprehensive design iteration, with particular emphasis on minimising the potential for environmental impacts, where practicable, whilst ensuring the objectives of the Proposed Scheme are attained. In addition, feedback received from the comprehensive consultation programme undertaken throughout the option selection and design development process have been incorporated, where appropriate.



# 19.2 Methodology

Material assets are resources of both natural and human origin that have intrinsic value. The Environmental Protection Agency (EPA) Draft Guidelines on the Information to be Contained in Environmental Impacts Assessment Reports (hereafter referred to as the Draft EPA EIAR Guidelines) (EPA 2017) discuss material assets as follows:

'The meaning of this factor is less clear than others. In Directive 2011/92/EU it included architectural and archaeological heritage. Directive 2014/52/EU includes those heritage aspects as components of cultural heritage. Material assets can now be taken to mean built services and infrastructure. Sealing of agricultural land and effects on mining or quarrying potential come under the factors of land and soils.'

The Draft EPA EIAR Guidelines specifically list built services, roads and traffic, and waste management as topics which fall into the category of material assets. Further to this, the Guidance on the Preparation of the Environmental Impact Assessment Report (European Commission 2017) references buildings, other structures, mineral resources, and water resources as material assets. The Proposed Scheme will not have any impacts on buildings and other structures. This EIAR includes separate chapters covering a number of those listed material assets and other material assets as follows:

- Roads and traffic Chapter 6 (Traffic & Transport);
- Employment and land-use assets Chapter 10 (Population);
- Ecological assets Chapter 12 (Biodiversity);
- Waterways, rivers, and streams Chapter 13 (Water);
- Soils, lands, and mining or quarrying potential Chapter 14 (Land, Soils, Geology & Hydrogeology);
- Cultural heritage assets Chapter 15 (Archaeological & Cultural Heritage) and Chapter 16 (Architectural Heritage);
- Visual amenity assets Chapter 17 (Landscape (Townscape) & Visual); and
- Waste management Chapter 18 (Waste & Resources).

The focus of this Chapter is on built services, specifically:

- Major infrastructure and utilities; and
- Imported material, excluding the materials which will be covered in Chapter 18 (Waste & Resources).

Major infrastructure includes items such as canals, railway lines and Luas lines interacting with the Proposed Scheme. Existing utility information has been collated from the utility service providers and utility (ground penetrating radar (GPR)) surveys have been carried out, as required. In addition, as part of the design development, the diversions and changes required to existing utilities infrastructure have been considered.

Conservative estimates have been prepared of the quantities of materials that may be needed for construction to inform the impact assessment of the Proposed Scheme. For the purpose of this Chapter, imported materials includes materials which are sourced from outside the Proposed Scheme, namely the major construction materials (concrete granular fill / aggregate, asphalt, and structural steel). The impacts associated with the transportation of the material to the site have been considered within the assessments of construction traffic in Chapter 6 (Traffic & Transport), Chapter 7 (Air Quality) and Chapter 9 (Noise & Vibration).

### 19.2.1 Study Area

The study area with regard to major infrastructure and utilities comprises all areas within the Proposed Scheme, including both permanent and temporary land take boundaries.



# 19.2.2 Relevant Guidelines, Policy and Legislation

This Chapter has been prepared in accordance with the following guidance:

- Draft Guidelines on the Information to be Contained in Environmental Impacts Assessment Reports (EPA 2017);
- Environmental Impact Assessment of Projects Guidance on the Preparation of the Environmental Impact Assessment Report (European Commission 2017); and
- Institute of Environmental Management and Assessment (IEMA) Guide to: Materials and Waste in Environmental Impact Assessment Guidance for a Proportionate Approach (IEMA 2020).

#### 19.2.3 Data Collection and Collation

All major infrastructure and utilities which may be impacted by the Proposed Scheme have been assessed including:

- Aviation Fuel Pipeline;
- Electricity;
- Water / Wastewater;
- Surface Water Drainage;
- Gas: and
- Telecommunications.

Existing utility information was requested from utility companies and service providers. The following service providers provided utility information for the study area of the Proposed Scheme:

- Dublin City Council (DCC);
- Electricity Supply Board (ESB) Networks / EirGrid;
- Gas Networks Ireland (GNI);
- · Irish Water; and
- Telecommunications providers.

The types and quantities of the major materials which will need to be imported for the construction of the Proposed Scheme have also been established.

### 19.2.4 Appraisal Method for the Assessment of Impacts

The assessment of the potential impact of the Proposed Scheme on material assets has been undertaken having regard to the Draft EPA EIAR Guidelines (EPA 2017). The following issues have been considered as part of the assessment of impacts:

- Potential for impacts on major infrastructure and public utilities and the need to adequately protect them during the Construction Phase;
- Requirement for connections to public utilities by the Proposed Scheme during both the Construction and Operational Phases; and
- Use of imported materials required for the construction of the Proposed Scheme.

Each impact has been categorised based on:

- Quality of the impact;
- · Significance of the impact; and
- Duration of the impact.

The definition of these impact characteristics as per the Draft EPA EIAR Guidelines is provided in Table 1.4 in Chapter 1 (Introduction). These characteristics have been used to assess the quality and duration of all impacts.



Table 19.1 provides the significance criteria used to identify the significance of impacts on major infrastructure and utilities. For the purposes of assessing the impacts on major infrastructure and utilities, an impact is deemed to be not significant from a rating of Imperceptible to Moderate, and significant from Significant to Profound.

Table 19.1: Significance Criteria for Major Infrastructure and Utilities

Significance Level	Criteria	
Profound	Where there is a continuous utility interruption of more than a week; Where additional demand on a utility would consume all remaining capacity; or Where there is a permanent disruption* of a major piece of infrastructure.	
Very Significant	Where there is a continuous utility interruption of more than 48 hours;  Where additional demand on a utility would significantly reduce the available capacity of that utility; or  Where there is long-term disruption* of a major piece of infrastructure.	
Significant	Where there is a continuous utility interruption of more than 24 hours; Where there is significant additional demand on a utility; or Where there is a medium-term disruption* of a major piece of infrastructure.	
Moderate	Where there are discrete utility interruptions of no more than eight hours for up to seven consecutive days; Where the additional demand on a utility is relatively large; or Where there is a short-term disruption* of a major piece of infrastructure.	
Slight  Where there are discrete utility interruptions of no more than eight hours for up to three days;  Where additional demand on a utility is relatively small; or  Where there is a temporary disruption* of a major piece of infrastructure.		
Not Significant  Where there is a utility interruption of no more than eight hours on a single day;  Where additional demand on a utility is quantifiable but is too small to have any impact on capacity  Where there is a brief disruption* of a major piece of infrastructure.		
Imperceptible	Where there is no utility interruption during diversion works; Where additional demand on a utility has no material change; or Where there are minor changes on a major piece of infrastructure which has no material impact on its usability.	
* Disruption with respe	ect to major infrastructure refers to the closure or significant reduction in usability of the infrastructure.	

For the significance of the impacts associated with imported materials, in addition to the Draft EPA EIAR Guidelines (EPA 2017), the IEMA Guide to: Materials and Waste in Environmental Impact Assessment (IEMA 2020) (hereafter referred to as the IEMA Guidance) has been used. For materials, the sensitivity of the receptor (Table 19.2) and the magnitude of the impact (Table 19.3) are assigned and used to determine the significance of the impact (Table 19.4).

Table 19.2: Sensitivity Criteria for Materials (IEMA 2020)

Value	Description			
	On balance, the key materials required for construction of a development			
Very high	Are known to be insufficient in terms of production, supply and/or stock; and/or Comprise no sustainable features and benefits compared to industry-standard materials*.			
High	Are forecast (through trend analysis and other information) to suffer from known issues regarding supply and stock; and/or Comprise little or no sustainable features and benefits compared to industry-standard materials*.			
Medium	Are forecast (through trend analysis and other information) to suffer from some potential issues regarding supply and stock; and/or  Are available comprising some sustainable features and benefits compared to industry-standard materials*.			
Low	Are forecast (through trend analysis and other information) to be generally free from known issues regarding supply and stock; and/or			
	Are available comprising a high proportion of sustainable features and benefits compared to industry-standard materials*.			
Negligible	Are forecast (through trend analysis and other information) to be free from known issues regarding supply and stock; and/or			
	Are available comprising a very high proportion of sustainable features and benefits compared to industry-standard materials.*			



Table 19.3: Assessing Magnitude for Materials (IEMA 2020)

Value	Description		
	The assessment is made by determining whether through a development, the consumption of		
Major	one or more materials is >10% by volume of the regional* baseline availability;		
Moderate	one or more materials is between 6-10% by volume of the regional* baseline availability;		
Minor	one or more materials is between 1-5% by volume of the regional* baseline availability		
Negligible	no individual material type is equal to or greater than 1% by volume of the regional* baseline availability.		
No change	lo changeno materials are required.		
* or where justified, national.			

Table 19.4: Determining Significance for Materials (IEMA 2020)

5		N	Magnitude of impact			
of Receptor		No change	Negligible	Minor	Moderate	Major
	Very High	Neutral	Slight	Moderate or Large	Large or Very Large	Very Large
Value) o	High	Neutral	Slight	Slight or Moderate	Moderate or Large	Large or Very Large
Sensitivity (or Va	Medium	Neutral	Neutral or Slight	Slight	Moderate	Moderate or Large
	Low	Neutral	Neutral or Slight	Neutral or Slight	Slight	Sight or Moderate
	Negligible	Neutral	Neutral	Neutral or Slight	Neutral or Slight	Slight

In accordance with the IEMA Guidance an impact is deemed to be significant if it has a significance level of Moderate, Large or Very Large, while Neutral or Slight are deemed to be not significant.



### 19.3 Baseline Environment

The Proposed Scheme has an overall length of approximately 5.7km, and is routed along the R107 Malahide Road from Mayne River Avenue – R107 Malahide Road Junction to the junction with Marino Mart - Fairview and also routed for cyclists via the junction with Malahide Road-Brian Road along Carleton Road, St Aidan's Park, Haverty Road and Marglann Marino, all in the County of Dublin and within the DCC administrative area. From here the Proposed Scheme ties into a separate project, the Clontarf to City Centre Cycle & Bus Priority Project, currently being developed by DCC. The Clontarf to City Centre Cycle & Bus Priority Project will provide segregated cycling facilities and bus priority infrastructure along a 2.7km route that extends from Clontarf Road at the junction with Alfie Byrne Road, to Amiens Street at the junction with Talbot Street in the City Centre. The start of the scheme ties into a separate project being developed by DCC namely, The Belmayne Main Street and Belmayne Avenue Scheme, which provides bus and cycle linkages to Clongriffin Dart Station.

There are several utilities in place along and crossing the Proposed Scheme roads, the majority of which are buried within and along the roadways. These utilities include:

- ESB electricity lines (high, medium, and low voltage) and associated infrastructure;
- Gas Networks Ireland gas mains (high, medium, and low pressure) and associated infrastructure;
- Irish Water potable water mains and associated infrastructure;
- Irish Water sewer lines (foul and combined sewers) and associated infrastructure;
- Local Authority surface water drainage network and associated infrastructure;
- Eir, Enet and Virgin Media telecommunications lines and associated infrastructure;
- · Local Authority traffic signal ducting; and
- The Aviation Fuel Pipeline between Dublin Port and Dublin Airport (not yet fully constructed at the time of preparation of this EIAR).

The following outlines the baseline environment with respect to material assets.

# 19.3.1 Major Infrastructure and Existing Utilities

Table 19.5 lists the types of major infrastructure and utilities within the study area of the Proposed Scheme, along or crossing the Proposed Scheme. Most utilities are buried beneath the roads or footpaths, with a mixture of main trunk routes as well as branches off these main routes existing along the entire length of the Proposed Scheme. Aside from the listed utilities, there are no other major infrastructure items such as railway lines or canals within the Proposed Scheme.

Table 19.5: Utilities Within the Proposed Scheme Study Area

Utility Provider	Service Type	Description
		Underground 110kV (kilovolt) lines
	High Voltage Electricity	Underground 38kV lines
		Overhead 38kV lines
ESB	Madium Valtaga Flactricity	Underground lines
ESB	Medium Voltage Electricity	Overhead three phase lines
	Low Voltage Electricity	Underground lines
		Overhead single-phase lines
		Overhead three phase lines
	High Pressure Gas	300mm steel main at 19 bar
	vorks  Medium Pressure Gas	32mm polyethylene main at 4 bar
		63mm polyethylene main at 4 bar
Gas Networks Ireland		90mm polyethylene main at 4 bar
		125mm polyethylene main at 4 bar
		180mm polyethylene main at 4 bar
		250mm polyethylene main at 4 bar



Utility Provider	Service Type	Description
	Low Pressure Gas	Numerous sizes of polyethylene and steel mains at 25 mbar along entire route
	Potable Water	Trunk and distribution mains of various diameters and materials, with supporting infrastructure such as valves and hydrants
Irish Water	Sewer Lines	Foul sewer lines and associated infrastructure
	Sewer Lines	Combined sewer lines and associated infrastructure
Local Authorities	Surface Water Sewer Network	Surface water sewer network and associated infrastructure
	Traffic Signals	Ducting for traffic signals and associated infrastructure
	Virgin Media	Underground cables and associated infrastructure
Telecommunications	Eir	Underground cables and associated infrastructure
	Enet	Enet cables on R107 Malahide Road between Danieli Road and Kilmore Road
Independent Aviation Fuel Pipeline Company Ltd.		The Aviation Fuel Pipeline is currently under construction and once completed, will connect Dublin Airport and Dublin Port, allowing aviation fuel to be piped from the port to the airport. The Proposed Scheme will overlap with the pipeline along much of its length, from the start of the Proposed Scheme at the R139 (Northern Cross) / R107 junction on the Malahide Road to the R139 Malahide Road / Copeland Avenue junction where the pipeline will leave the Malahide Road and continue down Copeland Avenue away from the Proposed Scheme.

## 19.3.2 Imported Material

The quantities of material which are currently imported to the area covered by the Proposed Scheme under baseline conditions are low. Currently material is only imported as part of maintenance activities which are undertaken on the existing roadways, cycle lanes, footpaths, utilities, and verges. These activities would largely involve repair of road, cycle lane and footpath surfaces, repainting of road markings, drainage maintenance and repair, utility works, landscaping, and winter maintenance.

A report entitled Essential Aggregates: Providing for Ireland's Needs to 2040 (Irish Concrete Federation 2019) was published in 2019 which details and quantifies Ireland's natural aggregate reserves. At the time of publication of that report, Ireland had approximately 500 active large commercial quarries, approximately 220 ready mixed concrete plants, 20 large scale precast concrete plants and 40 plants producing bitumen bound road surfacing materials.

The Irish Concrete Federation quantifies the annual production of these materials in Ireland on their website, with the 2019 figures (the most recent available) being as follows:

- Five million cubic metres of ready-mixed concrete;
- 135 million concrete blocks;
- 38 million tonnes of aggregates;
- Two million tonnes of bituminous road surfacing materials; and
- Two million square metres of paving products.



# 19.4 Potential Impacts

This section presents potential impacts that may occur due to the Proposed Scheme, in the absence of mitigation. The informs the need for mitigation or monitoring to be proposed (refer to Section 19.5). Predicted residual impacts taking into account any proposed mitigation is then presented in Section 19.6.

## 19.4.1 Characteristics of the Proposed Scheme

#### 19.4.1.1 Major Infrastructure and Utilities

Construction of the Proposed Scheme has the potential to have an impact on existing infrastructure and utilities in order to accommodate changes to junction layouts or changes to carriageway widths. Where protection of utilities in place is not an option, this will involve realignment, upgrade, or replacement of this infrastructure as part of works within those areas. Each proposed modification to the existing infrastructure or utilities is outlined in this Chapter. Where utility diversions are proposed, the approximate length of the diversions is provided in Table 19.6 to Table 19.9. The potential impacts would occur predominantly during the Construction Phase.

During the Operational Phase, some utilities will be required for the Proposed Scheme. This will include electricity connections for such elements as new street lighting, junction signalling, and real time passenger information (RTPI) displays at bus stops. There will also be some amendments to existing surface water drainage to control and/or attenuate surface water runoff from any additional paved surfaces.

#### 19.4.1.2 Imported Material

Material will be required to construct the Proposed Scheme. These materials will be comprised of standard construction materials, paving materials, landscaping materials, street furniture, paints, lighting, junction infrastructure materials and fill materials, as required. This Chapter covers the major materials needing to be imported to the site for the purposes of construction of the Proposed Scheme (i.e., concrete, granular fill / aggregate, asphalt, and structural steel). Any materials arising from within the site which are to be reused within the Proposed Scheme (e.g., excavated soils) are assessed in Chapter 18 (Waste & Resources).

# 19.4.2 'Do Nothing' Scenario

In the Do Nothing scenario, the Proposed Scheme would not be implemented and there would be no changes to existing infrastructure or utilities as a result of the Proposed Scheme. Therefore, there would be a Neutral impact on infrastructure and utilities under the 'Do Nothing' scenario.

Similarly, with respect to imported material, the 'Do Nothing' scenario means that there is no requirement to import material for the construction of the Proposed Scheme. Therefore, this material is not consumed by the Proposed Scheme, and the impact under the 'Do Nothing' scenario is Neutral.

#### 19.4.3 Construction Phase

#### 19.4.3.1 Major Infrastructure and Utilities

The following outlines the key potential impacts on major infrastructure and utilities as a result of the Construction Phase of the Proposed Scheme. Major utilities include the Aviation Fuel Pipeline (not yet fully constructed at the time of writing this EIAR), major electricity overhead lines and underground cables, water distribution and foul and surface water infrastructure, gas mains and telecommunications infrastructure. Please refer to Chapter 20 (Risk of Major Accidents and / or Disasters) for an assessment of the impacts associated with major accidents involving utilities. Additionally, there will be some demand on existing utilities by the construction activities (i.e., by the Construction Compound or equipment), which is also addressed as relevant in the following sections. Chapter 5 (Construction) should also be referenced for additional detail on the Construction Phase of the Proposed Scheme.

The main Construction Phase impacts will arise from the requirement to divert utilities. The proposed utility diversions are listed in Table 19.6 to Table 19.9. To the best of the engineering experience and judgement available and based on the available records and preliminary reasonable site investigations, it is expected that



the utility diversion will be to the stated length. It is likely however that modifications to these proposed measures may be required at the detailed design / construction stage, and any such modifications (if required) will not give rise to any impacts which are any more significant than those already identified and assessed in this Chapter and will not alter the summary of potential Construction Phase impacts presented in Table 19.13.

### 19.4.3.1.1 Aviation Fuel Pipeline

The Proposed Scheme will overlap with the aviation fuel pipeline (assuming that its construction is completed prior to the Proposed Scheme) along much of its length, from the R139 (Northern Cross) / R107 Malahide Road Junction to the R107 Malahide Road / Copeland Avenue Junction where the pipeline will leave the Malahide Road and continue down Copeland Avenue away from the Proposed Scheme. Construction of the Proposed Scheme will not require any diversion of the Aviation Fuel Pipeline as it will be constructed at a depth greater than the excavation depths required for the construction of the Proposed Scheme and will therefore have no likely significant impact on the pipeline.

### 19.4.3.1.2 Electricity

The Construction Compound will require electricity to power temporary office and welfare facilities during the Construction Phase. Power for the Construction Compound will be supplied through a connection into the electricity network, or where this is unavailable, via generators. Temporary electricity provision for works areas along the Proposed Scheme to power items such as temporary lighting, temporary traffic signals and other construction equipment will be provided through generators, as required.

The electricity demand during the Construction Phase is considered to be a Negative, Not Significant, Short-Term impact.

A number of interfaces between the existing electricity infrastructure and the Proposed Scheme have been identified, some of which will require diversion of the infrastructure as outlined in Table 19.6 and shown in ESB Asset Alterations Drawings (BCIDA-ACM-UTL\_UE-0001\_XX\_00-DR-CU-9001) in Volume 3 of this EIAR. As a result of these diversions there may be temporary local interruptions to the electricity provision during works on that infrastructure.

**Table 19.6: Potential Major Electricity Infrastructure Diversions** 

Approximate Chainage	Description	Proposed Measure (Approximate)	Figure Sheet Reference			
	Mayne River Avenue to Gracefield Road – Malahide Road					
A6010 – A6060	Medium voltage underground cables	75m diversion	Sheet 13 of 21			
Gracefield Road	to Marino Mart / Fairview - Malahide Road					
A6060	Medium voltage underground cables	90m diversion	Sheet 14 of 21			
A6380	Low voltage overhead lines	25m diversion	Sheet 14 of 21			
A6360 – A6520	Low voltage overhead lines	160m diversion	Sheet 15 of 21			
A6500 – A6520	Low voltage overhead lines	35m diversion	Sheet 15 of 21			
A6535 – A6545	Low voltage overhead lines	35m diversion	Sheet 15 of 21			
A6520 – A6540	Low voltage overhead lines	27m diversion	Sheet 15 of 21			
A6530 – A6500	Low voltage overhead lines	25m diversion	Sheet 15 of 21			
A6540 – A6590	Low voltage overhead lines	30m diversion	Sheet 15 of 21			
A6590 – A6600	Low voltage overhead lines	60m diversion	Sheet 15 of 21			
A7090 – A7120	Low voltage overhead lines	40m diversion	Sheet 16 of 21			
A7160 – A7180	Low voltage overhead lines	25m diversion	Sheet 17 of 21			
A7210	Low voltage overhead lines	20m diversion	Sheet 17 of 21			

While electricity interruptions, if required, will generally only occur for a set number of hours per day (no more than eight hours where reasonably practicable), the exact number of interruption days for particular customers for each diversion cannot be ascertained at this stage, so a worst-case scenario of up to a week has been assessed. Using the criteria as outlined in Section 19.2.4 and Table 19.1, where diversion of an electricity line is required



which will result in the planned interruption of electricity provision, the worst-case potential impact will be Negative, Moderate and Temporary.

#### 19.4.3.1.3 Water

The Construction Compound and construction areas will require a water supply for welfare facilities within the Construction Compound, as well as for dust suppression at certain construction areas where the conditions require it. The Construction Compound will be connected into the local mains water supply where possible. Where a connection is not possible, water tankers will be used.

The potable water demand during the Construction Phase is considered to be a Negative, Not Significant and Short-Term impact.

A number of interfaces between the existing water infrastructure and the Proposed Scheme have been identified, some of which will require diversion of the infrastructure as outlined in Table 19.7 and shown in IW Water Asset Alterations Drawings (BCIDA-ACM-UTL\_UW-0001\_XX\_00-DR-CU-9001) in Volume 3 of this EIAR. As a result of these diversions there may be temporary local interruptions to water provision during works on that infrastructure.

**Table 19.7: Potential Major Water Infrastructure Diversions** 

Approximate Chainage	Description	Proposed Measure (Approximate)	Figure Sheet Reference
Mayne River Ave	nue to Gracefield Road – Malahide Road		
A3060 – A3170	125mm moPVC watermain	106m diversion	Sheet 6 of 21
A3370 – A3400	250mm ductile iron watermain	30m diversion	Sheet 6 of 21
A3970 – A4010	304.8mm asbestos cement watermain	87m diversion	Sheet 8 of 21
A5970 – A6110	457.2mm cast iron (CI) watermain	137m diversion	Sheet 13 of 21
A5990 – A6110	160mm HDPE watermain	26m diversion	Sheet 13 of 21
A6030	457.2mm CI watermain	48m diversion	Sheet 14 of 21
Gracefield Road	to Marino Mart / Fairview – Malahide Road		
A6390 – A6520	152.4mm CI watermain	127m diversion	Sheet 15 of 21
A6580 – A6740	152.4mm CI watermain	158m diversion	Sheet 15 of 21
A7230 – A7250	101mm CI watermain	20m diversion	Sheet 17 of 21
A7900 – A7980	228.6mm CI watermain	80m diversion	Sheet 19 of 21
A8190 – A8210	228.6mm CI watermain	21m diversion	Sheet 19 of 21

While water interruptions, if required, will generally only occur for a set number of hours per day (no more than eight hours where reasonably practicable), the total number of interruption days for particular customers for each diversion cannot be ascertained at this stage, so a worst-case scenario of up to a week has been assessed. Using the criteria as outlined in Section 19.2.4 and Table 19.1, where diversion of a water main is required which will result in the planned interruption of water provision, the worst-case potential impact will be Negative, Moderate and Temporary.

#### 19.4.3.1.4 Wastewater and Surface Water Runoff

There will be wastewater and surface water runoff created by the Construction Compound and construction areas. Wastewater will be created by welfare facilities within the Construction Compound and construction areas, and surface water run-off will emanate from any areas of the Construction Compound and construction areas which are paved. The Construction Compound will be connected into the local foul / combined sewers where possible, or where not possible, will have on-site tanks for the collection of foul water which will be emptied by means of a suction tanker and the wastewater shall be disposed of to a licensed wastewater treatment plant. Where required, temporary welfare facilities (for example portable toilets) will be used, which will be collected as required for offsite disposal of the wastewater to a suitably licensed facility.

The potential impact as a result of the demand on the foul water network during the Construction Phase will be a Negative, Not Significant, Short-Term impact.



There have been no major interfaces identified between the Proposed Scheme and the existing foul sewer network which will require any diversion works. Therefore, it is predicted that there will be no significant impact to the foul sewer network as a result of the construction of the Proposed Scheme.

There will be limited upgrade works required to the surface water drainage network to facilitate the changes to the road alignment and the impermeable surface area. Much of this work will involve the construction of new road gullies to align with the new kerb line. There will also be several Sustainable Drainage System (SuDS) measures installed, namely filter drains and bioretention systems, to control the flow of surface water. All surface water will continue to drain into existing networks and outfalls. Refer to Chapter 13 (Water) for further information on surface water drainage during the Construction Phase of the Proposed Scheme.

#### 19.4.3.1.5 Gas

There will be no requirement for a connection to existing gas infrastructure during the Construction Phase of the Proposed Scheme. Therefore, it is predicted that there will be no significant impact associated with gas demand during the Construction Phase.

A number of interfaces between the existing gas infrastructure and the Proposed Scheme have been identified, some of which will require diversion of the infrastructure as outlined in Table 19.8 and shown in GNI Asset Alterations Drawings (BCIDA-ACM-UTL\_UG-0001\_XX\_00-DR-CU-9001) in Volume 3 of this EIAR. As a result of these diversions there may be temporary local interruptions to the gas provision during works on that infrastructure.

**Table 19.8: Potential Major Gas Infrastructure Diversions** 

Approximate Chainage	Description	Proposed Measure (Approximate)	Figure Sheet Reference		
Mayne River Avenu	ue to Gracefield Road – Malahide Road				
A5670 – A5730	Low pressure gas main	80m diversion	Sheet 13 of 21		
A5800 – A5830	Low pressure gas main	35m diversion	Sheet 13 of 21		
A5980	High pressure District Regulating Installation	Localised diversion	Sheet 13 of 21		
Gracefield Road to Marino Mart / Fairview – Malahide Road					
A6390 – A6470	Low pressure gas main	80m diversion	Sheet 15 of 21		
A7240 – A7270	Low pressure gas main	30m diversion	Sheet 17 of 21		
A8360 – A8420	Low pressure gas main	55m diversion	Sheet 20 of 21		
A8500 – A8650	Low pressure gas main	150m diversion	Sheet 20 of 21		

While gas interruptions, if required, will generally only occur for a set number of hours per day (no more than eight hours where reasonably practicable), the total number of interruption days for particular customers for each diversion cannot be ascertained at this stage so a worst-case scenario of up to a week has been assessed. Using the criteria as outlined in Section 19.2.4 and Table 19.1, where diversion of a gas main is required which will result in the planned interruption of gas provision, the worst-case potential impact will be Negative, Moderate and Temporary.

#### 19.4.3.1.6 Telecommunications

Telecommunications access will be required at the Construction Compound. The potential impact as a result of the demand on the telecommunications network during the Construction Phase will be a Negative, Not Significant, Short-Term impact.

A number of interfaces between the existing telecommunications infrastructure and the Proposed Scheme have been identified, some of which will require diversion of the infrastructure as outlined in Table 19.9 and shown in Telecommunications Asset Alterations (BCIDA-ACM-UTL\_UL-0001\_XX\_00-DR-CU-9001) in Volume 3 of this EIAR. As a result of these diversions there may be temporary local interruptions to the telecommunications provision during works on that infrastructure.



Table 19.9: Potential Telecommunications Infrastructure Diversions

Approximate Chainage	Description	Proposed Measure (Approximate)	Figure Sheet Reference
Mayne River Ave	nue to Gracefield Road – Malahide Road		
A3070 – A3150	6 No. 100mm Eir ducts including chambers	80m diversion	Sheet 6 of 21
A3230 – A3330	15 No. 100mm Eir ducts including chambers	190m diversion	Sheet 6 of 21
A4030 – A4060	Virgin Media ducts and chambers	30m diversion	Sheet 8 of 21
A5090 – A5920	Eir ducts and chambers	30m diversion	Sheet 11 of 21
A5660 – A5900	2 No. 100mm Eir ducts including chambers	245m diversion	Sheet 13 of 21
Gracefield Road	o Marino Mart / Fairview – Malahide Road		
A6090 – A6110	Eir ducts and chambers	20m diversion	Sheet 14 of 21
A6360 – A6520	6 No. 100mm Eir ducts including chambers	160m diversion	Sheet 15 of 21
A6540 – A6730	16 No. 100mm Eir ducts including chambers	265m diversion	Sheet 15 of 21
A7040 – A7260	10 No. 100mm Eir ducts including chambers	225m diversion	Sheet 16 of 21
A7230 – A7270	Virgin Media ducts and chambers	45m diversion	Sheet 17 of 21

While telecommunications interruptions, if required, will generally only occur for a set number of hours per day (no more than eight hours where reasonably practicable), the total number of interruption days for particular customers for each diversion cannot be ascertained at this stage so a worst-case scenario of up to a week has been assessed. Using the criteria as outlined in Section 19.2.4 and Table 19.1, where diversion of a telecommunications line is required which will result in the planned interruption of telecommunications provision, the worst-case potential impact will be Negative, Moderate and Temporary.

## 19.4.3.2 Imported Material

The Construction Phase will require the importation of a number of key construction materials for the Proposed Scheme works. This material will include items such as concrete, granular fill / aggregate, asphalt, and structural steel. For a full description of the Construction Phase, please refer to Chapter 5 (Construction). An assessment of the climate impact from the carbon associated with these materials is included in Chapter 8 (Climate). Table 19.10 provides a conservative estimate of the quantities of the major materials required to complete the Construction Phase of the Proposed Scheme.

Table 19.10: Conservative Quantity Estimates of Major Construction Materials Required by the Proposed Scheme

Material	Estimated Quantity
Asphalt	28,600 tonnes
Concrete	9,400 tonnes
Precast Concrete	10,900 tonnes
Aggregates	37,600 tonnes
Structural Steel	5 tonnes
Brickwork & Blockwork	160 tonnes

The quantities of material listed in Table 19.10 represents a very small proportion of the Irish quantities manufactured per year as outlined in Section 19.3.2. The estimated quantity of concrete required represents less than one percent of the total quantity produced in Ireland per annum. Similarly, assuming the aggregate composition of asphalt is 90-95% and concrete is 60-80%, the total estimated aggregate quantity required by the Proposed Scheme represents less than one percent of the total aggregate quantity produced in Ireland per annum.

Importation of material to the Proposed Scheme site will be carried out throughout the Construction Phase, with different materials being required at different times. The main direct impacts associated with the importation of construction materials arises from the gathering / manufacture of the materials, as well as the fact that once the materials are used within the Proposed Scheme, they are no longer available for other uses. There will also be impacts associated with the importation of materials through the requirement of heavy goods vehicles for delivery



of the material and the use of materials. Impacts are covered in more detail in Chapter 6 (Traffic & Transport), Chapter 7 (Air Quality), Chapter 8 (Climate) and Chapter 9 (Noise & Vibration) where relevant.

As the materials required for the Construction Phase of the Proposed Scheme are generally readily available, the sensitivity of the material will be Low. As the quantities of the material required constitute less than one percent of the quantities produced per annum in Ireland, the magnitude of the impact will be Negligible. Therefore, the potential impact associated with the imported materials will be Negative, Slight and Long-Term.

#### 19.4.3.3 Construction Phase Impact Summary

Table 19.11 provides a summary of the potential impacts on material assets associated with the Construction Phase of the Proposed Scheme.

**Table 19.11: Summary of Potential Construction Phase Impacts** 

Assessment Topic	Potential Impact
Major Infrastructure and Utilities	
Aviation Fuel Pipeline	No significant impact
Electricity Demand	Negative, Not Significant, Short-Term
Electricity Interruption	Negative, Moderate, Temporary
Water Demand	Negative, Not Significant, Short-Term
Water Interruption	Negative, Moderate, Temporary
Wastewater Demand	Negative, Not Significant, Short-Term
Wastewater Interruption	No significant impact
Gas Demand	No significant impact
Gas Interruption	Negative, Moderate, Temporary
Telecommunications Demand	Negative, Not Significant, Short-Term
Telecommunications Interruption	Negative, Moderate, Temporary
Imported Material	
Use of Imported Material	Negative, Slight, Long-Term

### 19.4.4 Operational Phase

## 19.4.4.1 Major Infrastructure and Utilities

The main impacts on major infrastructure and utilities will be associated with the Construction Phase. However, there will be some demand on utilities by the Proposed Scheme once operational. These impacts are outlined in the following sections.

#### 19.4.4.1.1 Aviation Fuel Pipeline

Upon completion of the Construction Phase, there will be no interaction between the operation of the Proposed Scheme and the Aviation Fuel Pipeline. There will therefore be no significant Operational Phase impacts on this infrastructure asset as a result of the Proposed Scheme.

## 19.4.4.1.2 Electricity

Once the Proposed Scheme is operational, electricity will be required to power such elements as street lighting, junction signalling and RTPI displays. Power for these types of equipment will be supplied via power cables which connect the equipment to an electricity supply cabinet. The anticipated impact on electricity demand during the Operational Phase will be Negative, Imperceptible and Long-Term.



#### 19.4.4.1.3 Water Usage

The Proposed Scheme will not result in any additional water provision being required after the Construction Phase is completed. Therefore, there is no significant Operational Phase impact anticipated on water infrastructure as a result of the Proposed Scheme.

#### 19.4.4.1.4 Wastewater and Surface Water Runoff

Once the Proposed Scheme is constructed, the hardstanding surface area will be larger in some places than before construction due to the construction of wider carriageways, cycle infrastructure and footpaths. This larger surface area will result in additional surface water runoff. Drainage upgrades and SuDS measures have been included as part of the design of the Proposed Scheme to attenuate any additional runoff. There will therefore be no significant Operational Phase impacts anticipated on surface water drainage infrastructure. Impacts on water courses and water quality as a result of any potential increases in surface water runoff through existing outfalls is assessed in Chapter 13 (Water).

The Proposed Scheme will not require any foul sewer connection to operate. Therefore, there is no significant Operational Phase impact anticipated on foul sewer infrastructure as a result of the Proposed Scheme.

#### 19.4.4.1.5 Gas

The Proposed Scheme will not require any gas connection to operate. Therefore, there is no significant Operational Phase impact anticipated on gas infrastructure as a result of the Proposed Scheme.

#### 19.4.4.1.6 Telecommunications

Once the Proposed Scheme is operational, telecommunications links will be required for such equipment as traffic signal controllers, and for RPTI displays at bus stops and on bus information apps. Generally, this equipment will be connected to the local fibre optic cable network via ducting connected to fibre cabinets. In the case of the real time bus information, cellular communications (3G/4G/5G) will be provided. This type of infrastructure is already in operation along the Proposed Scheme route. Therefore, any additional telecommunications requirements by any new infrastructure will be minimal.

Therefore, the anticipated impact on telecommunications demand during the Operational Phase will be Negative, Imperceptible and Long-Term.

#### 19.4.4.2 Imported Material

Materials will be required during the Operational Phase for maintenance of the infrastructure. This will include repair of roadway, cycleway, and footway surfaces, as well as repair of street furniture (including bus shelters and poles), and landscaping. However, as the Proposed Scheme largely involves the upgrade and alteration of existing roadways, most of the material required for maintenance of the Proposed Scheme would have already been required for the maintenance of the existing roadways in the absence of the Proposed Scheme. The Proposed Scheme will result in an overall narrowing of the carriageway, resulting in a marginal decrease in maintenance needs over the lifetime of the Proposed Scheme when compared to the Do Nothing scenario. Therefore there will be a small reduction in material requirements for the Operational Phase.

As the materials required for the Operational Phase of the Proposed Scheme are generally readily available, the sensitivity of the material will be Low. As the quantities of the material required for maintenance will be lower than the quantities required for the Construction Phase and therefore constitute less than one percent of the quantities produced per annum in Ireland, the magnitude of the impact will be Negligible. Therefore, the potential impact associated with the imported materials will be Neutral and Long-Term.

#### 19.4.4.3 Operational Phase Impact Summary

Table 19.12 provides a summary of the potential impacts on material assets associated with the Operational Phase of the Proposed Scheme.



Table 19.12: Summary of Potential Operational Phase Impacts

Assessment Topic	Potential Impact	
Major Infrastructure and Utilities		
Aviation Fuel Pipeline	No significant impact	
Electricity	Negative, Imperceptible, Long-Term	
Water Usage	No significant impact	
Wastewater	No significant impact	
Surface Water Runoff	No significant impact	
Gas	No significant impact	
Telecommunications	Negative, Imperceptible, Long-Term	
Imported Material		
Use of Imported Material	Neutral, Long-Term	



# 19.5 Mitigation and Monitoring Measures

The following Section outlines the measures which will be adhered to in order to ensure that there are no significant impacts on material assets as a result of the construction and operation of the Proposed Scheme. No monitoring measures are considered to be required for material assets.

#### 19.5.1 Construction Phase

#### 19.5.1.1 Major Infrastructure and Utilities

The Proposed Scheme has been designed to minimise the impact on major infrastructure. This includes the avoidance of interactions with major utility infrastructure as far as possible. Where there are interfaces with existing utility infrastructure, protection in place or diversion as necessary is proposed to prevent long-term interruption to the provision of the affected services.

All possible precautions will be taken by the appointed contractor to avoid unplanned interruptions to any services during the Construction Phase of the Proposed Scheme. Proposed utility works are based on available records, and preliminary site investigations. Prior to excavation works being commenced, localised confirmatory surveys will be undertaken by the appointed contractor to verify the results of the pre-construction assessments undertaken and reported in this EIAR. Where works are required in and around known utility infrastructure, precautions will be implemented by the appointed contractor to protect the infrastructure from damage, in accordance with best practice methodologies and the requirements of the utility companies, where practicable. Protection measures during construction will include warning signs and markings indicating the location of utility infrastructure, safe digging techniques in the vicinity of known utilities, and in certain circumstances where possible, isolation of the section of infrastructure during works in the immediate vicinity.

Consultation has been undertaken with the major utility companies regarding the design, potential interfaces and measures required to protect or divert the infrastructure which is interfacing with the Proposed Scheme design. All utility companies for which diversions are proposed will continue to be consulted with NTA oversight when designing any diversions to ensure that proposed diversions conform to the utility provider's requirements, where practicable and acceptable to the NTA, and to ensure that service interruptions are kept to a minimum.

Where diversions, or modifications, are required to utility infrastructure (as listed in Section 19.4.3), service interruptions and disturbance to the surrounding residential, commercial and/or community property may be unavoidable. Where this is the case, it will be planned in advance by the appointed contractor.. Required service interruptions will generally only occur for a set period of time per day (a set number of hours not exceeding eight hours where reasonably practicable) and will generally not be continuous for full days at a time. Prior notification will be given to all impacted properties. This notification will include information on when interruptions and works are scheduled to occur and the duration of such interruption. Any required works will be carefully planned by the appointed contractor to ensure that the duration of interruptions is minimised in so far as is practicable.

#### 19.5.1.2 Imported Materials

The Proposed Scheme has been designed to minimise the amount and extent of major construction works required, and therefore minimise the quantities of construction materials required. The majority of the Proposed Scheme will require minimal intervention, being comprised of lane reconfigurations, road marking layout changes, resurfacing works, and the construction of segregated cycle tracks.

Consideration will be given by the appointed contractor to the sustainability of material being sourced for the construction of the Proposed Scheme. In so far as is reasonably practicable, materials required for the construction of the Proposed Scheme will be sourced locally to reduce the amount of travelling required to get the material to the site. Key issues to be considered when sourcing materials for the Construction Phase will include the source, the material specification, production and transport costs, and the availability of the material. For quarried material sourced within the State, only quarries which are included in local authority quarry registers will be used by the appointed contractor to source any quarried material.



Construction materials will be managed on-site by the appointed contractor in such a way as to prevent overordering and waste. Materials will be stored in appropriate storage areas or receptacles to reduce the potential for damage requiring replacement. 'Just-In-Time' ordering principles will be implemented by the appointed contractor where practicable to reduce the potential for over-ordering.

## 19.5.1.3 Summary of Construction Phase Impacts After Mitigation

Due to the fact that impacts are anticipated to be minimal and mitigation measures are largely inherent in the design of the Proposed Scheme, the predicted post mitigation impacts are unchanged as summarised in Table 19.13.

Table 19.13: Summary of Predicted Construction Phase Impacts Following the Implementation of Mitigation Measures

Assessment Topic	Potential Impact (Pre-Mitigation)	Predicted Impact (Post Mitigation)		
Major Infrastructure and Utilities				
Aviation Fuel Pipeline	No significant impact	No significant impact		
Electricity Demand	Negative, Not Significant, Short-Term	Negative, Not Significant, Short-Term		
Electricity Interruption	Negative, Moderate, Temporary	Negative, Moderate, Temporary		
Water Demand	Negative, Not Significant, Short-Term	Negative, Not Significant, Short-Term		
Water Interruption	Negative, Moderate, Temporary	Negative, Moderate, Temporary		
Wastewater Demand	Negative, Not Significant, Short-Term	Negative, Not Significant, Short-Term		
Wastewater Interruption	No significant impact	No significant impact		
Gas Demand	No significant impact	No significant impact		
Gas Interruption	Negative, Moderate, Temporary	Negative, Moderate, Temporary		
Telecommunications Demand	Negative, Not Significant, Short-Term	Negative, Not Significant, Short-Term		
Telecommunications Interruption	Negative, Moderate, Temporary	Negative, Moderate, Temporary		
Imported Material				
Use of Imported Material	Negative, Slight, Long-Term	Negative, Slight, Long-Term		

# 19.5.2 Operational Phase

Due to the measures which are included within the design and the fact that impacts are anticipated to be minimal, there are no specific mitigation measures necessary during the Operational Phase. The predicted post mitigation impact is therefore unchanged as summarised in Table 19.14.

Table 19.14: Summary of Predicted Operational Phase Impacts Following the Implementation of Mitigation Measures

Assessment Topic	Potential Impact (Pre-Mitigation)	Predicted Impact (Post Mitigation)		
Major Infrastructure and Utilities				
Aviation Fuel Pipeline	No significant impact	No significant impact		
Electricity	Negative, Imperceptible, Long-Term	Negative, Imperceptible, Long-Term		
Water Usage	No significant impact	No significant impact		
Wastewater	No significant impact	No significant impact		
Surface Water Runoff	No significant impact	No significant impact		
Gas	No significant impact	No significant impact		
Telecommunications	Negative, Imperceptible, Long-Term	Negative, Imperceptible, Long-Term		
Imported Materials				
Use of Imported Material	Neutral, Long-Term	Neutral, Long-Term		



# 19.6 Residual Impacts

## 19.6.1 Construction Phase

There will be no significant residual impacts on major infrastructure and utilities or as a result of imported material during the Construction Phase.

# 19.6.2 Operational Phase

There will be no significant residual impacts on major infrastructure and utilities or as a result of imported material during the Operational Phase.

No significant residual impacts have been identified either in the Construction or Operational Phases of the Proposed Scheme, whilst meeting the scheme objectives set out in Chapter 1 (Introduction).



### 19.7 References

Environmental Protection Agency (EPA) (2017). Guidelines on the Information to be Contained in Environmental Impact Assessment Reports (Draft)

European Commission (EC) (2017). Environmental Impact Assessment of Projects - Guidance on the Preparation of the Environmental Impact Assessment Report

Institute of Environmental Management and Assessment (IEMA) (2020). IEMA Guide to: Materials and Waste in Environmental Impact Assessment - Guidance for a Proportionate Approach

Irish Concrete Federation (2019). Essential Aggregates Providing for Ireland's Needs to 2040

#### **Directives and Legislation**

Directive 2011/92/EU of the European Parliament and of the Council of 13 December 2011 on the assessment of the effects of certain public and private projects on the environment

Directive 2014/52/EU of the European Parliament and of the Council of 16 April 2014 amending Directive 2011/92/EU on the assessment of the effects of certain public and private projects on the environment.