



LEGEND

Soft Landscape

- Existing Trees to be removed
Due to development Per Arborist Advice (Cat U)
- Existing Trees
To be retained as per detailed site investigation
- Existing Trees
Retained only subject to BS5837:2012
- Tree Root Protection Fencing
In accordance with BS5837:2012
- Boundary Buffer Trees
Species: *Acer campestre* 'Elegant', *Betula pendula*, *Pinus nigra var maritima*, *Pinus sylvestris*, *Populus tremula*, *Sorbus aria*, *Alnus glutinosa*
- Street Trees and Feature Shrubs
Species: *Tilia cordata*, *Carpinus betulus* 'Fastigiata', *Alnus glutinosa* 'Imperialis'
- Courtyard Trees
Species: *Alnus glutinosa* 'Imperialis', *Amelanchier lamarckii*, *Betula pendula*, *Corylus avellana*, *Crataegus monogyna*, *Sorbus aucuparia*
- Compensatory Tree Planting
Semi-mature trees 25-30cm girth
Species: *Alnus glutinosa*, *Quercus robur*, *Acer campestre*, *Tilia cordata*
- Perimeter Buffer Planting
Species: *Barbarea fibrata* 'Amstelveen', *Cornus sanguinea*, *Crataegus monogyna*, *Elaeagnus x ebbingei*, *Hebe alpicans*, *Mahonia aquifolium*, *Ilex aquifolium*, *Viburnum opulus*
- Residential Buffer Planting
Species: *Arbutus unedo*, *Cornus sanguinea*, *Forsythia spectabilis*, *Hieracium mollis*, *Ilex aquifolium*, *Mahonia aquifolium*, *Carex oshimensis* 'Evergold', *Hypericum 'hidcote'*, *Lavandula 'hidcote'*, *Sarcococca humilis*, *Viburnum davidii*, *Liriope muscari*
- Native Hedgerow Mix - Boundary with Regional Park
Crataegus monogyna [40%], *Prunus spinosa* [30%], *Euonymus europaeus* [10%], *Corylus avellana* [10%], *Viburnum opulus* [5%], *Rosa pimpinellifolia* [4%], *Lonicera periclymenum* [1%]
- Courtyard Planting
Species: *Carex oshimensis* 'Evergold', *Erica sp.*, *Hypericum 'hidcote'*, *Lavandula 'hidcote'*, *Lonicera pileata*, *Luzula sylvatica*, *Mahonia aquifolium*, *Penstemon 'Kariel Rose'*, *Rosmarinus officinalis*, *Salvia nemorosa* 'Ostfriesland', *Sarcococca humilis*, *Viburnum davidii*, *Vinca minor*
- Street Planting for SuDs / Bioattenuation
Species: Marsh marigold (*Caltha palustris*), Purple loosestrife (*Lythrum salicaria*), Brooklime (*Veronica beccabunga*), Meadowsweet (*Filipendula ulmaria*), Meadow Rue (*Thalictrum flavum*), Tufted Vetch (*Vicia cracca*), Water Avens (*Geum rivale*), Wild Angelica (*Angelica sylvestris*), Wild Valerian (*Valeriana officinalis*), Yarrow (*Achillea millefolium*), Yellow flag (*Iris pseudacorus*), Purple Willow (*Salix purpurea*)
- Stone Pebbles & Ornamental Grass Planting
Stones of various sizes and coastal grass planting.
Species: *Leymus arenarius*, *Limonium bellifolium*, *Miscanthus sinensis*, *Santolina chamaecyparissus*, *Stipa tenuissima* 'Pony tails'
- Sedum Green Roof
Living Roof Mix: Moy Materials Irish Native Biodiverse Extensive Green Roof System - see 1819_PL_D_01 for more information
- Bioswale
Planted with native wild flora seed mix suited to seasonal inundation - subject to Ecologist Input
- Wildflower Meadow
Native Wildflower Seed mix suited to coastal location - subject to Ecologist Input
- Amenity Lawn
150mm min Topsoil depth, Coburn's Low Maintenance seed, or similar and approved. Amenity grass seed mix.
- Mounded Amenity Grass
Max. 1.5m height, 150mm min. Topsoil depth, Coburn's Low Maintenance seed, or similar and approved.
- Bank
- Bio-retention Tree Pit
Coordinated with Civil Engineering Proposals

Hard Landscape

- Courtyard Footpaths
Resin Bound Aggregate - quartzite, buff colour
- Courtyard Paving
Resin Bound Aggregate - granite, light/dark grey colour
- Entrance Feature Paving
High quality Concrete Block Paving, stretcher bond pattern
- Play Safe Surface
Wetpour Safety Surface
- Footpath
Brushed concrete, non-slip finish
- Surface to All the Path Leading to Park
Feature Paving, e.g. Resin-Bound Aggregate Surfacing
- Road
with in-situ concrete kerbs, to engineer's specification.
- Car Parking
Standard material for taking in charge to be agreed
- Decking
- Tactile
Blister Concrete Tactile - Buff Colour

Furniture/Elements

- Natural Play Elements
Tree stumps, logs, boulders, and other elements that encourage natural, imaginative play. Made of natural materials. Play opportunities for different age groups.
- Seating
Seating integrated on the walls of raised planters. 2000mm length.
- Seating
Self-standing park benches, 2000mm length.
- Raised Planter
450mm high, 100mm thick concrete walls.
- Visitor Cycle Parking
Stainless steel standard Sheffield Bicycle stands, or similar and approved. One stand capacity two bikes. 496 No.
- Resident Cycle Parking
Two Tier Cycle Shelter, or similar and approved. 426 No.

Lighting

- EX1 8m Pole Mounted Street Light
- EX2 4m Pole Mounted
- EX3 Bollard Light
- EX4 Floor Light
- EX5 Recessed Wall Fitting
- MP Lighting Mini-Pillar

Boundary Treatment

- Site Boundary
- Apartment Building Entrance Points
- Basement Line
- Entrance to proposed Racecourse Park
As proposed by Fingal County Council
- Potential Additional Link to Racecourse Park
Subject to agreement with FCC Parks Dept
- Existing Boundary Wall & Railing to be removed
- Proposed 1.2m Railing with Native Hedgerow
Boundary with Racecourse Regional Park, consistent with GA03, Standard Bowtop Railing*
- Courtyard Boundary Railing and Gate
To Architects' Detail
- Creche Railing
To Architects' Detail
- Step Handrail
Please see Detail xx/xx on Sheet No. 1819_PL_D_0X.
- Kerb
Slipform Concrete Kerb, and/or similar approved
- Retaining Wall
Concrete Retaining Wall

1. This drawing is intended to show landscape architectural proposals only. Please refer to Architects and Engineer's drawings for relevant details of buildings, structures, roads, parking, etc.
 2. The copyright of this drawing is vested with Murray & Associates. This drawing may not be copied or reproduced without written consent.
 3. All materials referred to on this drawing, including plant species, are indicative and subject to change following detailed site investigation. Significant changes, if any are required, will be referred to the relevant authority for agreement.
 4. This drawing is not suitable for use for construction purposes.
 5. Discrepancies to be referred to Murray & Associates for clarification.

murray & associates
landscape architecture

14 The Seapoint Building, mcall@murray-associates.com
 44-45 Convent Road, www.murray-associates.com
 Dublin 3, D03 RF63, +353 (0)1 854 0990

REV	DATE	REVISION	DRAWN	CHECKED

0 16/03/22 IFF HT MB
 REV DATE REVISION DRAWN CHECKED

CLIENT
Lismore Homes Ltd.

PROJECT TITLE
GA2 Baldoyle

SHEET TITLE
Landscape Plan 4 of 4

SHEET NO.
1819_PL_P_04_IFP

SCALE
1:200

STAGE
Planning

DATE
16/03/22