




- Site Boundary
- Proposed Amenity grass areas with public ownership and to public open space: grass seed sown on 150mm clean topsoil (imported if necessary), over 250mm subsoil, all subsoil to be punctured and consolidated to aid natural drainage: (to receive the following amenity seed mix 2):
  - 50% Dwarf ryegrass
  - 45% Strong creeping red fescue
  - 5% Chewings fescue
- Grass areas within private ownership.
- Proposed shrub planting within private ownership: positioned within 450mm clean topsoil (imported if necessary) to areas shown.
- Proposed shrub planting areas within public open space, positioned within 450mm clean topsoil (imported if necessary) to areas shown. See drawing PP-01-PP for Planting Strategy & LD-01-PP for details.
- Existing Hedgerow to be retained or infilled as necessary with similar species where possible; see drawing PP-01-PP for Planting Strategy & LD-01-PP for details.
- Proposed native hedgerow to areas shown; Part Native Hedgerow: below should be planted at 5/linear metre (double staggered row with temporary post and wire fencing) see drawing PP-01-PP for Planting Strategy & LD-01-PP for details.
- Proposed herb layer, Hedgerow Wild Flower Mixture (Code ECD4)
- Proposed Meadow Zone
- Proposed naturalised bulb planting; (Planted as shown or included in shrub areas). See drawing PP-01-PP for Planting Strategy and LD-01-PP for details.
- Proposed open space tree planting; see drawing PP-01-PP for Planting Strategy and LD-01-PP for details.
- Proposed Street tree planting; see drawing PP-01-PP for Planting Strategy and LD-01-PP for details. All Street tree planting or tree planting within constrained hardcape zones shall receive constructed tree pits to ensure 16M3 of growing medium is provided quality establishment.
- Existing Tree planting to be retained.
- Proposed bitmac footpath surface with concrete pencil kerb edging.
- Proposed brushed concrete surface.
- Proposed concrete block paving.
- Proposed feature paving to plaza area, Bush Hammered granite paving (rectangular form); to Engineers details.
- Proposed feature paving to plaza area, Tegula Tobermore paving or similar and approved in grey with banding in charcoal (80mm depth); to Engineers details.
- Proposed feature paving to plaza area, Manhattan paving by Tobermore or similar and approved (rectangular form) with a random mix of 30% Charcoal and 70% Silver (80mm depth); to Engineers details.
- Proposed Tree planting to plaza zone to be set in tree grate; The Castle Paving stone Tree Grate; Supplied by Green Blue Urban or similar and approved; see Detail 06 drawing LD-02-PP for information.
- Proposed concrete feature paving to raised tables and pedestrian areas shown, to Engineers details.
- Proposed bitmac road surface to Engineers details.
- Proposed Duracolor Beige SMA 10 surf Mex C; suited to vehicular traffic situations, in Homezone areas as shown, to Engineers details.
- Proposed Resin bound gravel surface within Plaza Zone.
- Proposed Tiger mulch surface to play areas.
- Proposed wetpour safety surfacing.
- Proposed MUGA(Multi-Use Games Area) with cross play (size 800m2) and associated fencing (Refer to detail 04 drawing reference LD-02-PP)
- Proposed rubberised grass to play zones.
- Proposed position of light pole showing 7m dia. no tree planting zone.
- Table tennis, see drawing PG-04-PP for details.
- Proposed bench, see Detail 02, LD-02-PP for details.
- Proposed Litter Bin, see Detail 01, LD-02-PP for details.
- Proposed freestanding Medilith Interpretive display signage, see Detail 05 on drawing LD-02-PP for details.
- Omox S21 raised planters (aluminium and powder coated) with timber seeping in accordance with details on drawing no. LD-04-PP.

| Rev. | Date | Note |
|------|------|------|
|      |      |      |
|      |      |      |
|      |      |      |
|      |      |      |
|      |      |      |
|      |      |      |
|      |      |      |
|      |      |      |
|      |      |      |



General Notes

Doyle & O'Troithigh  
Landscape Architecture

|                                                                              |                                                                                      |                                                       |                                                            |
|------------------------------------------------------------------------------|--------------------------------------------------------------------------------------|-------------------------------------------------------|------------------------------------------------------------|
| Project Name                                                                 | Mooretown Phase 3 (SHD)                                                              | Drawing Name                                          | Landscape Plan - Open Spaces<br>Western Park<br>(Aof 4)    |
| Status                                                                       | Planning                                                                             | Drawing No                                            | LP-09-PP                                                   |
| Project No                                                                   | 21-003                                                                               | Revision No                                           | 00                                                         |
| Scale                                                                        | 1:250                                                                                | Drawn By                                              | AD                                                         |
| Date                                                                         | 06/04/2022                                                                           | Checked By                                            | LD                                                         |
| Linda Doyle<br>Director<br>+353 (0)87 267 4196<br>linda@doyle-otroithigh.com | Dalith O'Troithigh<br>Director<br>+353 (0)86 300 3469<br>dalith@doyle-otroithigh.com | Office Address<br>28-29 Upper Pembroke St<br>Dublin 2 | Contact<br>mail@doyle-otroithigh.com<br>+353 (0)1 608 7782 |