

C Classification Selection

Project NameRatoath South SHD ~ Outer Relief RoadProject Number21068From Table 3 - Parameters for the selection of lighting class C CEN/TR 13201-1:2014

Parameter	Options	Description ^a	Weighting Value V _w ^a	Designer Selection
Design speed or speed limit	Very high	v ≥ 100km/h	3	
	High	70< V <100 km/h	2	
	Moderate	40 < v ≤ 70 km/h	0	0
	Low	v ≤ 40 km/h	-1	
Traffic volume	High		1	
	Moderate		0	0
	Low		-1	
Traffic composition	Mixed with high percentage of non-motorised		2	
	Mixed		1	
	Motorised only		0	0
Separation of	No		1	1
carriageway	Yes		0	
Parked	Present		1	
vehicles	Not present		0	0
Ambient Iuminosity	High	Shopping windows, advertisement expressions, sports fields, station areas, storage areas	1	
	Moderate	Normal situation	0	0
Navigational task	Low		-1	
	Very difficult		2	
	Difficult		1	1
	Easy		0	

^a The values stated in the column are an example. Any adaption of the method or more appropriate weighting values can be used instead, on the national level.

Number of lighting classes 6

- Weighting value V_w 2
- Lighting class selected 4

