



**Main 4m Wide walking and Bicycle trail connects from Whitechurch Road through the development site open space zoned area and provides future access to additional open space zoned areas further up stream along the Glenamought River.**  
**Total Open Space zoned area including existing sports pitches is 21.3ha. Portion within site application area is 5.11ha. or 24% of the total area.**

**Amenity Turfed Areas** regularly mown grass/turfed areas are proposed along proposed pedestrian and Bicycle Paths and on any spaces where the gradients allow for recreational use. These include the terrace created by the installation of the underground attenuation tanks within the open space area. Bench seating is to be provided along paths at strategic points especially to capitalise on views to the west down the valley & in locations where passive surveillance from the apartment buildings overlooking the area. Paths are designed to have minimised gradients to promote access to the open space area for all. The sloped areas are to be retained as existing managed as woodland or meadows per the management plan to be determined by the ecologist.

**short / long meadow grass pollinator OPEN MEADOW area**

**43 No. Tilia cordata 'Green Spire' / Lime standard, bareroot 14/16cm girth, staked**

**Retain Wet Meadow as existing**

**WET MEADOW AREA**  
Retain Wet Meadow as existing

**WOODLAND AS EXISTING**

**CONNECTION TO IDA LANDS**

**WOODLAND AS EXISTING**

**Mown Amenity Turf Area**

**Mown Amenity Turf Area**

**WOODLAND AS EXISTING**

**PUBLIC PARK**

**Mown Amenity Turf Area**

**OPEN MEADOW AREA**

**WOODLAND AS EXISTING**

**WOODLAND AS EXISTING**

**WOODLAND AS EXISTING**

**WOODLAND AS EXISTING**

**WOODLAND AS EXISTING**

**WOODLAND AS EXISTING**

**retain meadow grass pollinator biodiversity area**

**retain meadow grass pollinator biodiversity area**

**OPEN MEADOW AREA**

**Mown Amenity Turf Area**

**Active Amenity Outdoor Gym Area**

**OUTDOOR GYM**

**APARTMENT BLOCK G**

09No. Prunus avium 'Plena' Standard WRB 14/16cm girth, staked

09No. Prunus avium 'Plena' Standard WRB 14/16cm girth, staked

12No. Quercus robur 'Fastigiata' standard, RB 14/16cm girth, staked

242-262

**Active Amenity Kick About Area**

**KICK ABOUT AREA**

**Mown Amenity Turf Area**

**APARTMENT BLOCK F**

05No. Quercus robur 'Fastigiata' standard, RB 14/16cm girth, staked

183-203

20No. Acer campestre 'Elsrijk' standard, WRB 14/16cm girth, staked

**Enclosed Fritillary Habitat Meadow Area**

**ENCLOSED MEADOW AREA**

*Crataegus mongyna* / Hawthorn, bareroot, 90-120cm height at 30cm centres double staggered row 30cm apart, prune post planting by 50%.

*Crataegus mongyna* / Hawthorn, bareroot, 90-120cm height at 30cm centres double staggered row 30cm apart, prune post planting by 50%.

**IMPORTANT TO BE READ**  
 THIS DRAWING IS COPYRIGHT © DOYLE McDONOUGH NASH ARCHITECTS. ALL RIGHTS RESERVED. THIS DRAWING IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM DOYLE McDONOUGH NASH ARCHITECTS. ANY REPRODUCTION OR TRANSMISSION OF THIS DRAWING WITHOUT PERMISSION IS STRICTLY PROHIBITED.

|     |                                 |          |    |
|-----|---------------------------------|----------|----|
| 1   | ISSUED FOR PLANNING APPLICATION | 26.06.22 | SD |
| Rev | DATE                            | BY       |    |

**DMNA** Doyle McDonough Nash Architects  
 21 Patrick's Hill, Cork. T: 0214518371 E: info@dmnarchitects.ie

**CORK COUNTY GAA BOARD**

**RESIDENTIAL DEVELOPMENT AT KILBARRARY, CORK**

**LANDSCAPE MASTERPLAN SHEET 2**

Scale: 1:500@A1

Sheet No: 19012

Revision: 4002

Date: 1 PA