

Legend

- Site Boundary
- Proposed Amenity grass areas with public ownership and to public open space: grass seed sown on 250mm clean topsoil (imported if necessary), over 250mm subsoil, all subsoil to be punctured and consolidated to aid natural drainage: (to receive the following amenity seed mix 2):
 - 50% Dwarf ryegrass
 - 45% Strong creeping red fescue
 - 5% Chewings fescue
- Existing hedgerow/vegetation retained to areas shown; reduction of height and width required.
- Proposed native hedgerow to areas shown; to be planted at 5/linear metre (double staggered row with temporary post and wire fencing, see drawing LD-01-PP for details).
- Proposed open space tree planting; specimen species; See drawings PP-01-02-TS for species information & LD-01-TS for details.
- Proposed Street tree planting.
- Existing Tree planting to be retained.
- Proposed concrete raised footpath.
- Proposed Barlestone permeable paving; Colour: Walnut (or colour to be agreed), to Engineers details.
- Proposed concrete paving; to Engineers details.
- Proposed bitmac footpath surface with pin kerb edging, within public open space, to Engineers details.
- Proposed standard black bitmac roadway, to Engineers details.
- Proposed stone mastic asphalt course (SMA) with Red coloured chippings suited to vehicle traffic situations, in homezone areas as shown, to Engineers details.
- Proposed combined cycleway/footpath, to be surface with bitmac, red coloured, to Engineers details.
- Proposed Tiger mulch surface to play areas.
- Proposed position of light pole showing 5m dia. no treea planting zone.
- Proposed bench, see LD-02-TS for details.
- Proposed Litter Bin, see LD-02-TS for details.
- Existing NRA fence (replaced locally where necessary to allow for adjoining works).
- Proposed 1.1m high black bow top fence to enclosed play areas. (See Detail 04 on Dwg BD-01-PP).
- Timber steppers within play zones
- Proposed rounded boulders.
- Proposed climbing net, set into slope.
- Refer to Arboricultural Impact Assessment as prepared by Arborcare Ltd. for detailed reference with regard to tree/hedgerow protection and removal.



5 10 073 0110 0
playo swing Kendor with nest seat Ø 100

Scope of delivery:
4x seat with seat base, 20x galvanized steel
2x wooden beam, galvanized steel
2x horizontal bar, galvanized steel
2x rear seat Ø100 cm, galvanized steel, polyurethane coated steel eye

Name	509 p2
Foundation level	FL 3
Foundation space	800x500x300 cm
Free falling height	140 cm
Height playground set	242,0 m
Foundation	4x Ø12 x 16 PSt + 4x CF
Assembly	2 persons/2 h
Loggia surface	238x640x3 cm
Weight surface	45 kg

5 55 310 5
balance step 40

Scope of delivery:
1x step Ø1, 20x galvanized steel
1x rear step, galvanized steel

Name	509 p2
Foundation level	FL 3
Foundation space	Ø14x200 cm
Free falling height	30 cm
Height playground set	14 CF
Foundation	1 person/2 h
Loggia surface	20xØ10 cm
Weight surface	10 kg

5 55 311 5
balance step 60

Scope of delivery:
1x step Ø2, 20x galvanized steel
1x rear step, galvanized steel

Name	509 p2
Foundation level	FL 3
Foundation space	Ø14x200 cm
Free falling height	30 cm
Height playground set	14 CF
Foundation	1 person/2 h
Loggia surface	20xØ10 cm
Weight surface	10 kg

5 56 084 0
Basis Pendulum carousel 7Janus Ø 320 cm

Scope of delivery:
1x post Ø 133 cm, steel hot-dip galvanized
2x crossbars Ø 8,5 cm, steel hot-dip galvanized
4x pendulum seat with chain, rubber, stainless steel (3x)

Name	Freibahn Ø320, rubber
Foundation level	FL 3
Foundation space	Ø 115x800 cm
Free falling height	120 cm
Height playground set	88,5 m
Foundation	1x CF
Assembly	2 persons/3 h
Loggia surface	300x300x3 cm
Weight surface	90 kg

5 45 012 0630 0
paradiso play unit Winja

Scope of delivery:
1x platform, rubber
1x slide, rubber, PE
1x top entrance, rubber, PE
1x diagonal sliding ramp, stainless steel
1x window, rubber
1x ladder, rubber
2x bench, rubber
2x space with sliding balls, stainless steel, PE

Name	Freibahn rubber
Foundation level	FL 3
Foundation space	530x470x225 cm
Free falling height	60 cm
Height playground set	21,0 m
Foundation	1x CF
Assembly	2 persons/3 h
Loggia surface	140x80x3 cm
Weight surface	310 kg

5 55 316 5
balance Samba net footbridge

Scope of delivery:
1x rope, plastic-coated steel cable
1x steel structure, Ø10
4x post, steel, galvanized steel

Name	509 p2
Foundation level	FL 3
Foundation space	220x170x225 cm
Free falling height	45 cm
Height playground set	45 cm
Foundation	4x Ø12 x 16 PSt
Assembly	1 person/2 h
Loggia surface	220x170 cm
Weight surface	12,5 kg

5 55 090 5
unique two-seater seesaw

Scope of delivery:
1x seat, rubber, Ø10
2x seat, steel, Ø10
2x handle, galvanized steel
2x frame, rubber
post, steel, galvanized steel

Name	509 p2
Foundation level	FL 3
Foundation space	600x500x300 cm
Free falling height	130 cm
Height playground set	132,0 m
Foundation	1x CF
Assembly	2 persons/2 h
Loggia surface	Ø 10x400 cm
Weight surface	40 kg

5 45 355 0630 0
paradiso spring rocker Turtle

Scope of delivery:
1x spring, rubber, Ø10
1x spring, spring steel
1x handle, stainless steel

Name	Freibahn rubber
Foundation level	FL 3
Foundation space	300x500x40 cm
Free falling height	60 cm
Height playground set	7,5 m
Foundation	1x Ø8x200 + 1x CF

5 45 360 0630 0
paradiso spring rocker Lamb

Scope of delivery:
1x spring, rubber, Ø10
1x spring, spring steel
1x handle, stainless steel

Name	Freibahn rubber
Foundation level	FL 3
Foundation space	300x500x40 cm
Free falling height	60 cm
Height playground set	7,5 m
Foundation	1x Ø8x200 + 1x CF

5 45 357 0630 0
paradiso spring rocker Mouse

Scope of delivery:
1x spring, rubber, Ø10
1x spring, spring steel
1x handle, stainless steel

Name	Freibahn rubber
Foundation level	FL 3
Foundation space	300x500x40 cm
Free falling height	60 cm
Height playground set	7,5 m
Foundation	1x Ø8x200 + 1x CF

5 62 085 0
fit Table tennis unit Outdoor green

Scope of delivery:
1x table, rubber table, 270x120x2,25 cm, Polymer concrete
1x table, rubber table, 270x120x2,25 cm, Polymer concrete
4x ground, galvanized
1x net with holder, aluminum

Name	Freibahn concrete
Foundation level	FL 3
Foundation space	Ø17x6x2x200 cm
Free falling height	2,50 m
Height playground set	2,50 m
Foundation	
Assembly	
Loggia surface	
Weight surface	

5 54 034 0
fit active-station crosstrainer

Scope of delivery:
1x active-station, VA, PE, HPE


Name	VA, HPE
Foundation level	FL 3
Foundation space	470x370x300 cm
Free falling height	47 cm
Height playground set	1,5 m
Foundation	1x CF

5 54 032 0
fit active-station pull down

Scope of delivery:
1x active-station, VA, PE, HPE

Name	VA, HPE
Foundation level	FL 3
Foundation space	480x370x300 cm
Free falling height	72 cm
Height playground set	1,5 m
Foundation	1x CF

Rev.	Date	Note



General Notes

Doyle & O'Troighth
Landscape
Architecture

Project Name: Residential Development, Ennis, Co. Claire
Drawing Name: Play Area Plan (2 / 3)

Status: Planning
Project No: 21-048
Scale: 1:250
Date: 12/08/2022

Drawing No: PG-02-PP
Revision No: 00
Drawn By: AD
Checked By: LD

Linda Doyle
Director
+353 (0)87 287 4196
linda@doyle-o'troighth.com

Daini O'Troighth
Director
+353 (0)86 300 3499
doini@doyle-o'troighth.com

Office Address
Pheonix House
29-31 Upper Pembroke St
Dublin 2

Contact
mail@doyle-o'troighth.com
+353 (0)1 608 7762