Legend

- Site Boundary
- Proposed Amenity **grass areas with public ownership and to public open space**: grass seed sown on 150mm clean topsoil (imported if necessary), over 250mm subsoil, all subsoil to be punctured and consolidated to aid natural drainage: (to receive the following amenity seed mix 2):
  50% Dwarf ryegrass
  45% Strong creeping red fescue
  5% Chewings fescue
- Grass areas within private ownership.
- Proposed shrub planting within private ownership, positioned within 450mm clean topsoil (imported if necessary) to areas shown.
- Proposed shrub planting areas within public open space, positioned within 450mm clean topsoil (imported if necessary) to areas shown. See drawing LD-01-PP for details.
- Proposed woodland and native infill hedgerow to areas shown.
- Existing hedgerow/vegetation retained to areas shown; reduction of height and width required.
- Proposed native hedgerow to areas shown; to be planted at 5/linear metre (double staggered row with temporary post and wire fencing, see drawing LD-01-PP for details.
- Proposed naturalised bulb planting; planted as shown. See drawing PP-01-PP for species information.
- Proposed Meadow Zone
- Proposed open space tree planting; specimen species; See drawings PP-01-02-TS for species information & LD-01-TS for details.
- Proposed Street tree planting.
- Existing Tree planting to be retained.
- Proposed brushed concrete surface.
- Proposed concrete block (permeable) paving (colour to be agreed), to Engineers details.
- Proposed concrete block paving; to Engineers details.
- Proposed bitmac footpath surface with pin kerb edging, within public open space, to Engineers details.
- Proposed standard black bitmac roadway, to Engineers details.
- Proposed stone mastic asphalt course (SMA) with Red coloured chippings suited to vehicle traffic situations, in homezone areas as shown, to Engineers details.
- Proposed combined cycleway/footpath, to be surface with bitmac, red coloured, to Engineers details.
- Proposed Tiger mulch surface to play areas.
- Proposed rubberised grass matting
- Proposed grassritter
- Existing dry stone wall with hedgerow to be retained. Reducing the height and width of the hedgerow to be carried out to improve longevity. Localised upgrading works to dry stone walling to be carried out as necessary.
- Existing dry stone wall to be lifted and relayed along with the planting out of a new infill of native hedgerow following completion of attenuation works.
- Existing NRA fence (replaced locally where necessary to allow for adjoining works).
- Proposed 1.1m high black bow top fence to enclosed play areas. (See Detail 03 on Dwg BD-01-PP).
- Proposed pedestrian guard rail to Engineers details.
- Proposed part retaining plinth with powder coated (black) railings (handrails where applicable to steps). (See Detail 05 on Dwg BD-01-PP).
- Proposed 1.8M high black paladin fence. (See Detail 07 on Dwg BD-02-PP).
- Proposed 2M high concrete post and concrete panel fence. (See Detail 08 on Dwg BD-02-PP).
- Proposed position of light pole showing 7m diameter radius referencing the 'no tree planting zone'.
- Proposed bench, see LD-02-PP for details.
- Proposed Litter Bin, see LD-02-PP for details.
- Proposed rounded boulders.

Refer to Arboricultural Impact Assessment as prepared by Arborcare Ltd. for detailed reference with regard to tree/hedgerow protection and removal.

Rev.	Date	Note

North

General Notes

Doyle & O'Troithigh Landscape Architecture

Project Name	Residential Development, Ennis, Co. Claire	Drawing Name	Landscape Plan (3 / 4)
Status	Planning	Drawing No	LP-04-PP
Project No	21-048	Revision No	00
Scale	1:500	Drawn By	AD
Date	12/08/2022	Checked By	LD

Linda Doyle
Director
+353 (0)87 267 4196
linda@doyle-otroithigh.com

Daithi O'Troithigh
Director
+353 (0)86 300 3499
daithi@doyle-otroithigh.com

Office Address
Pembroke House
28-23 Upper Pembroke St
Dublin 2

Contact
mail@doyle-otroithigh.com
+353 (0)1 608 7782