




- Legend**
- Site Boundary
  - Proposed Amenity grass areas with public ownership and to public open space: grass seed sown on 150mm clean topsoil (imported if necessary), over 250mm subsoil, all subsoil to be punctured and consolidated to aid natural drainage: (to receive the following amenity seed mix 2):  
50% Dwarf ryegrass  
45% Strong creeping red fescue  
5% Chewings fescue
  - Grass areas within private ownership.
  - Proposed shrub planting within private ownership, positioned within 450mm clean topsoil (imported if necessary) to areas shown.
  - Proposed shrub planting areas within public open space, positioned within 450mm clean topsoil (imported if necessary) to areas shown. See drawing LD-01-PP for details.
  - Proposed woodland and native infill hedgerow to areas shown.
  - Existing hedgerow/vegetation retained to areas shown; reduction of height and width required.
  - Proposed native hedgerow to areas shown; to be planted at 5/linear metre (double staggered row with temporary post and wire fencing, see drawing LD-01-PP for details).
  - Proposed naturalised bulb planting; planted as shown. See drawing PP-01-PP for species information.
  - Proposed Meadow Zone
  - Proposed open space tree planting; specimen species; See drawings PP-01-02-TS for species information & LD-01-TS for details.
  - Proposed Street tree planting.
  - Existing Tree planting to be retained.
  - Proposed brushed concrete surface.
  - Proposed concrete block (permeable) paving (colour to be agreed), to Engineers details.
  - Proposed concrete block paving; to Engineers details.
  - Proposed bitmac footpath surface with pin kerb edging, within public open space, to Engineers details.
  - Proposed standard black bitmac roadway, to Engineers details.
  - Proposed stone mastic asphalt course (SMA) with Red coloured chippings suited to vehicle traffic situations, in homezone areas as shown, to Engineers details.
  - Proposed combined cycleway/footpath, to be surface with bitmac, red coloured, to Engineers details.
  - Proposed Tiger mulch surface to play areas.
  - Existing dry stone wall with hedgerow to be retained. Reducing the height and width of the hedgerow to be carried out to improve longevity. Localised upgrading works to dry stone walling to be carried out as necessary.
  - Existing NRA Fence (replaced locally where necessary to allow for adjoining works).
  - Proposed 1.1m high black bow top fence to enclosed play areas. (See Detail 03 on Dwg BD-01-PP).
  - Proposed low retaining dry stone walls to retain local levels. (See Detail 04 on Dwg BD-01-PP).
  - Proposed 2M high stone wall. (See Detail 06 on Dwg BD-01-PP).
  - Proposed position of light pole showing 7m diameter radius referencing the 'no tree planting zone'.
  - Proposed bench, see LD-02-PP for details.
  - Proposed Litter Bin, see LD-02-PP for details.
  - Timber steppers within play zones
  - Proposed sleepers set into surface as informal pathways and on slopes as step units.
  - Proposed rounded boulders.
  - Proposed climbing net, set into slope. See PG-01-03-PP for example details.
  - Proposed woodland playzone, with climbing boulders and informal sleeper pathway. Planting in the area will be light canopy woodland with newly planted understorey including ferns and Ivy, all set on a bark mulch finish.

Refer to Arboricultural Impact Assessment as prepared by Arborcare Ltd. for detailed reference with regard to tree/hedgerow protection and removal.

Rev.	Date	Note



General Notes

**Doyle & O'Troithigh**  
Landscape  
Architecture

Project Name: Residential Development, Ennis, Co. Clare  
Drawing Name: Open Space Plan (2 / 4)

Status: Planning  
Drawing No: LP-07-PP

Project No: 21-048  
Revision No: 00

Scale: 1:250  
Date: 12/08/2022  
Drawn By: AD  
Checked By: LD

Linda Doyle, Director  
+353 (0)87 287 4196  
linda@doyle-otroithigh.com

Dairbhí O'Troithigh, Director  
+353 (0)87 300 3459  
dairbhí@doyle-otroithigh.com

Office Address: Penbrooke House, 29-31 Upper Penbrooke St, Dublin 2  
Contact: mai@doyle-otroithigh.com  
+353 (0)1 608 7762