

Appendix C Deviations / Departures / Relaxation from Standards

Ballymun / Finglas to City Centre CBC Scheme Appendix C – Deviations from Design Standards

| DIRECTION | LOCATION | DESIGN ELEMENT | STANDARD / REQUIRED | TYPE | DESIGN | JUSTIFICATION |
|-----------------|--|----------------------|-----------------------------------|------------|--------|--|
| Southbound | A-3040 to A-3360 Eastern side | Footpath | DMURS 4.3.1 2.0m / 1.8m min. | Relaxation | 1.8m | On St. Mobhi Road to fit cycle track behind mature trees. |
| Northbound | A-3130 to A-3680 Western side | Footpath | DMURS 4.3.1 2.0m / 1.8m min | Relaxation | 1.8m | On St. Mobhi Road to fit cycle track behind mature trees. |
| Southbound | A-3040 to A-3360 Eastern side | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Departure | 1.25m | Cycle track at St. Mobhi Road behind mature trees. Width reduced to allow minimum 1.8m footpath width. |
| Northbound | A-3130 to A-3680 Western side | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Departure | 1.25m | Cycle track at St. Mobhi Road behind mature trees. Width reduced to allow minimum 1.8m footpath width. |
| Both | A-3360 to A-3690 St. Mobhi Road Eastern side | 2-way Cycle track | BCPDGB: 5.3 3.25m / 2.25m min. | Relaxation | 2.5m | Cycle track at St. Mobhi Road behind mature trees. Width reduced to allow 2.5m footpath width and to minimise encroachment into properties. There is a separate northbound Cycle track provided on the western side. Demand will be tidal associated with arrivals and departures from the schools adjoining. |
| Both directions | A-3710 to A-3800 St. Mobhi Road | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath in available space. |
| Both directions | A-3830 to A-4010 | Footpath | DMURS 4.3.1 2.0m / 1.8m min. | Relaxation | 1.9m | On St. Mobhi Road to fit cycle track behind mature trees. |
| Both directions | A-3830 to A-4010 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Departure | 1.25m | Cycle track at St. Mobhi Road at existing space behind mature trees. Width reduced to allow minimum 1.8m footpath width. |
| Both directions | A-4010 to A-4390 Botanic Road | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath in available space. |

| DIRECTION | LOCATION | DESIGN ELEMENT | STANDARD / REQUIRED | TYPE | DESIGN | JUSTIFICATION |
|-----------------|---|----------------------|--|------------|-----------------------|---|
| Both | A-4410 to A-4600 Botanic Road / Prospect Road eastern side | 2-way Cycle track | BCPDGB: 5.3 3.25m / 2.25m min. + 0.5m buffer | Relaxation | 2.5m + 0.5m buffer | To fit within the available 3m as replacement of an existing traffic lane. |
| Southbound | A-4690 to A-4750 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Departure | 1.25m | Alternative link from the main cycle route at Royal Canal along Phibsborough Road on Cross Guns Bridge over short length of 60m to connect to bus lane. |
| Northbound | A-5250 to A-5290 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Departure | 1.25m | 40m long link between bus lane sections on very narrow part of Phibsborough Road. |
| Northbound | A-5710 to A-5770 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.7m | 90m long link between bus lane sections on narrow part of Phibsborough Road between retaining walls at Royal Canal Terrace. |
| Northbound | A-5980 to A-6080 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath and retain existing street trees. |
| Both directions | A-6150 to A-6350 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Departure | 1.4m | Reduced width to allow 2m footpath in available space. |
| Southbound | A-6370 to A-6550 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath in available space. |
| Northbound | A-6510 to A-6580 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath in available space and retain existing street trees. |
| Southbound | A-6710 to A-6750 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | 40m long link between bus lane sections on very narrow part of Church Street Lower. |
| Northbound | B-770 to B-1010 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Cycle track extension over existing ramp, reduced width to avoid larger extension Oof the ramp, which would involve affecting the existing retaining wall |
| Southbound | B-1050 to B-1220 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath and retain existing street trees. |

| DIRECTION | LOCATION | DESIGN ELEMENT | STANDARD / REQUIRED | TYPE | DESIGN | JUSTIFICATION |
|------------|--|---------------------------------|---------------------------------|------------|--------|---|
| Northbound | B-1080 to B-1100 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath and retain existing street trees. |
| Southbound | B-1120 to B-1220 | Footpath | DMURS 4.3.1 2.0m / 1.8m min. | Relaxation | 1.8m | Existing footpath width retained behind mature street trees. |
| Northbound | B-1190 to B-1220 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath and retain existing street trees. |
| Southbound | B-1390 to B-1480 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath and retain existing street trees. |
| Northbound | B-1620 to B-1740 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath |
| Southbound | B-1880to B-1910 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath and retain existing street trees. |
| Northbound | B-1910 to B-2290 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Available space behind verge to allow minimum footpath width |
| Junction | B-2200 Finglas Road / Tolka Valley Road | Pedestrian crossing distance | BCPDGB: 5.6 19m maximum | Departure | 24m | Median island cannot be widened from 3m to 4m within the available road width |
| Southbound | B-2230 to B-2290 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Available space to retain existing street trees |
| Southbound | B-2290 to B-2360 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Departure | 1.4m | Reduced width to retain existing street trees |
| Northbound | B-2290 to B-2430 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Departure | 1.4m | Reduced width to allow 2m footpath |
| Southbound | B-2360 to B-2430 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath |
| Junction | B-2450 Finglas Road / Old Finglas Road | Pedestrian crossing distance | BCPDGB: 5.6 19m maximum | Departure | 21m | Median island cannot be widened from 3m to 4m within the available road width |

| DIRECTION | LOCATION | DESIGN ELEMENT | STANDARD / REQUIRED | TYPE | DESIGN | JUSTIFICATION |
|------------|--|----------------------|--|------------|------------------------|--|
| Northbound | B-2430 to B-2700 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath |
| Southbound | B-2470 to B-2800 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath |
| Southbound | B-2800 to B-2890 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Available space to retain existing street trees |
| Northbound | B-2910 to B-3050 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath |
| Southbound | B-2890 to B-3110 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath |
| Southbound | B-3120 to B-3190 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath |
| Southbound | B-3620 to B-3670 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath |
| Northbound | B-3990 to B-4070 | Cycle track | BCPDGB: 5.3 2.0m / 1.5m min. | Relaxation | 1.5m | Reduced width to allow 2m footpath |
| Southbound | B-3990 to B-4020 Finglas Road / Prospect Way | Footpath | DMURS 4.3.1 2.0m / 1.8m min. | Relaxation | 1.8m | To accommodate cycle track in limited street width |
| Both | B-4000 to B-4140 Prospect Way | 2-way Cycle track | BCPDGB: 5.3 3.25m / 2.25m min + 0.5m buffer. | Relaxation | 2.25m + 0.5m buffer | Reduced width to retain existing street trees |