



Landmark Trees (5)

- 50-55cm girth; root balled
- min. 7-8m high; min 3m clear stem

Street Trees (62no.)

- 35-40cm girth; root balled
- min. 7-8m high; min 2m clear stem

Street Trees recommended for future phase [11no.]

- Specification as per above
- Coordination required with various DCC departments

Feature Trees (32no.)

- 25-30cm girth; root balled
- min. 5-6m high; min 1.8m clear stem

Smaller-sized Plantings (Feature) (30no.)

- Multistem Tree 3-3.5m high
- Non-standard native specimen including some unusual species

Smaller-sized Plantings (Street) (125no.)

- Specimen Tree grown in 150L pot
- min 18-20cm

Domestic Fruit Trees (40no.)

- Specimen Tree 10-12cm bareroot
- Native species esp. Apple, Plum, Pear etc
- Locations not Specified on Plan

Proposed Tree List:

Landmark trees (5)

- Quercus coccoloba (3)
- Quercus rubra (1)
- Quercus cerris (1)

Street trees (62)

- Tilia platyphyllos "Rubra" (3)
- Tilia x euchlora "Pallida" (30)
- Aucubus hippocastanum (5)
- Aucubus carnea "Brickell" (3)
- Quercus robur (7)
- Quercus rubra (6)
- Liquidambar styraciflua "Worplesden" (5)
- Metasequoia glyptostroboides (3)

Street trees (Potential Future Phase) (11)

- Tilia x euchlora "Pallida" (11)

Feature trees (32)

- Liquidambar styraciflua "Worplesden" (15)
- Liriodendron tulipifera (7)
- Pinus sylvestris (9)
- Cedrus atlantica "Glaucia" (1)

Feature shrubs (30)

- Tilia henryana (3)
- Myrica luma (1)
- Betula pendula "Dulcicarpa" (9)
- Syringa vulgaris "Katherine Havemeyer" (3)
- Magnolia denudata (1)
- Toona sinensis (1)
- Celtis occidentalis (3)
- Malus tchonoskii (9)

Street shrubs (125)

- Castanea sativa (6)
- Catalpa bignonioides fargessii (5)
- Magnolia grandiflora "Ferruginea" (3)
- Maytenus boaria (3)
- Betula albo-sinensis (7)
- Quercus rubra (10)
- Quercus robur (10)
- Quercus ilex (3)
- Acer palmatum "Osakasaki" (1)
- Sorbus cadmiriana (7)
- Sorbus aucuparia "Fructo Luteo" (5)
- Sorbus sargentiana (3)
- Clerodendron trichotomum "Fargessii" (1)

Street shrubs (cont.)

- Osmanthus delavayi (1)
- Cercidiphyllum japonicum (3)
- Magnolia lilliflora "Ngra" (1)
- Magnolia lipoensis "Leonard Massie" (3)
- Magnolia lipoensis "Materii" (4)
- Zelkova carpinifolia (1)
- Prunus subhirtella "Autumnalis" (3)
- Prunus "Shirofugen" (6)
- Prunus "Tai Haku" (5)
- Davidia involucreta (2)
- Calocedrus decurrens (3)
- Cryptomeria japonica (1)
- Tetradium daniellii (1)
- Malus "Rudolph" (3)
- Malus transitoria (3)
- Cedrus atlantica "Glaucia" (1)
- Pinus sylvestris (5)
- Pinus muricata (1)
- Taxodium distichum (1)

Proposed Plant Mixes:

Mix A - Buffer planting

- 2L Pot size (unless stated otherwise)
- 40cm
- Likely mix: 10% Anemone japonica "Honome Joze" 20% Hebe x mix 10% Kerria japonica "Fire Pleni" 10% Rosa Fruittigermorgen (bare root) 10% Symplyum blue 30% Epimedium sp. 10% Verbena Bonariensis

Mix B - Suds planting

- 2L Pot size (unless stated otherwise)
- 5m2
- Likely mix: 15% Iris ensata 10% Peniculae bistorta superba 5% Osmunda regalis 5% Anemone sylvestris 5% Euphorbia griffithii dudar 10% Primula sp. (plug) 5% Mimus sp. (plug) 10% Iris pseudacorus 20% Carex Riparia 10% Matteuccia struthiopteris 5% Stipa Gigantea
- + Betula pendula whips 1/2m2

Mix C - Biodiverse planting

Mix C1 (80% of Hatched area on plan)

- Woody/Shrub: As Bare Root 1+ whips (unless stated otherwise) 1 per 3m2
- Likely mix: Syringa vulgaris Autumn Raspberry Summer Raspberry Crataegus monogyna Rosa Carina Betula pubescens Sex aquifolium JC van Tol (3L pot) Camellia sasamea (3L pot) Corylus avellana

Mix C2 (20% of Hatched area on plan)

- 2L Pot size
- 3m2 (unless stated otherwise)
- Likely mix: 10% Sasa Palmata 15% Crataegus monogyna 15% Betula pendula 15% Rosa carina 10% Rosa moyesi geranium 10% Rosa glauca 10% Dryopteris Filix mas (7m2) 10% Campanula carpatica (7m2)

Mix D - Street Underplanting

- PG Pot size (unless stated otherwise)
- Species: Galium odoratum 10 Primula veris 4 Bluebell (bubae) 12

Herbaceous

- 5 m2
- 2L pots
- Likely mix: Dryopteris filix-mas Geranium 'Brookside' Helleborus coriaceus Helleborus hybridus harvington Achillea cloth of gold Iris silberica (mixed) Rosa pimpinellifolia

Culinary Herbs

- 1 per 15m2
- 1L pots
- Likely mix: Rosmarinus officinalis Salvia officinalis Thymus sp. Origanum sp.

Legend:

- Existing Tree (outside Red Line)
- Proposed Tree (refer to planting plan)
- Proposed Tree: smaller (refer to planting plan)
- Soil mounding
- Mix A: Buffer Planting to Buildings (refer to planting schedule)
- Mix B: SUDS Planting (refer to planting schedule)
- Mix C: Biodiverse Planting (refer to planting schedule)
- Mix D: Street Underplanting (refer to planting schedule)

Project: Central Road (Local Area Development)

Client: Dublin City Council

Drawing: Planting Schedule

Date: 08/03/2024

Scale: 1:500 @ A1

Drawn by: D.M.

Checked by: H.S.

Drawn by: H.S.

Checked by: H.S.

Project No.: 010000-P-0002

Sheet: Planting

Drawn by: H.S.

Checked by: H.S.

Project No.: 4 NOVA'S ABBEY, DUBLIN 7

Phone: +353 1 8747764

Email: info@bssarch.com

Bernard Seymour Landscape Architects