



**Appendix 8.1: TII Criteria**

RECEIVED: 18/07/2023

Kildare County Council Planning Department - Viewing Purposes Only

**APPENDIX 8.1**

**CRITERIA FOR RATING SITE ATTRIBUTES – ESTIMATION OF IMPORTANCE  
OF HYDROLOGY ATTRIBUTES**

**NATIONAL ROADS AUTHORITY (NRA, 2009)**

RECEIVED: 18/07/2023

Kildare County Council Planning Department - Viewing Purposes Only

**Table 1 Criteria for rating Site Attributes - Estimation of Importance of Hydrology Attributes (NRA)**

Importance	Criteria	Typical Examples
Extremely High	Attribute has a high quality or value on an international scale	River, wetland or surface water body ecosystem protected by EU legislation e.g. 'European sites' designated under the Habitats Regulations or 'Salmonid waters' designated pursuant to the European Communities (Quality of Salmonid Waters) Regulations, 1988.
Very High	Attribute has a high quality or value on a regional or national scale	<p>River, wetland or surface water body ecosystem protected by national legislation – NHA status</p> <p>Regionally important potable water source supplying &gt;2500 homes</p> <p>Quality Class A (Biotic Index Q4, Q5)</p> <p>Flood plain protecting more than 50 residential or commercial properties from flooding</p> <p>Nationally important amenity site for wide range of leisure activities</p>
High	Attribute has a high quality or value on a local scale	<p>Salmon fishery</p> <p>Locally important potable water source supplying &gt;1000 homes</p> <p>Quality Class B (Biotic Index Q3-4)</p> <p>Flood plain protecting between 5 and 50 residential or commercial properties from flooding</p> <p>Locally important amenity site for wide range of leisure activities</p>
Medium	Attribute has a medium quality or value on a local scale	<p>Coarse fishery</p> <p>Local potable water source supplying &gt;50 homes Quality Class C (Biotic Index Q3, Q2- 3)</p> <p>Flood plain protecting between 1 and 5 residential or commercial properties from flooding</p>
Low	Attribute has a low quality or value on a local scale	<p>Locally important amenity site for small range of leisure activities</p> <p>Local potable water source supplying &lt;50 homes Quality Class D (Biotic Index Q2, Q1)</p> <p>Flood plain protecting 1 residential or commercial property from flooding</p> <p>Amenity site used by small numbers of local people</p>



**Appendix 9.1: Ambient Air Quality Standards**

RECEIVED: 18/07/2023

Kildare County Council Planning Department - Viewing Purposes Only

## APPENDIX 9.1 – AMBIENT AIR QUALITY STANDARDS

National standards for ambient air pollutants in Ireland have generally ensued from Council Directives enacted in the EU (& previously the EC & EEC) (see Table 9.1). The initial interest in ambient air pollution legislation in the EU dates from the early 1980s and was in response to the most serious pollutant problems at that time. In response to the problem of acid rain, sulphur dioxide, and later nitrogen dioxide, were both the focus of EU legislation. Linked to the acid rain problem was urban smog associated with fuel burning for space heating purposes. Also apparent at this time were the problems caused by leaded petrol and EU legislation was introduced to deal with this problem in the early 1980s.

In recent years the EU has focused on defining a basis strategy across the EU in relation to ambient air quality. In 1996, a Framework Directive, Council Directive 96/62/EC, on ambient air quality assessment and management was enacted. The aims of the Directive are fourfold. Firstly, the Directive's aim is to establish objectives for ambient air quality designed to avoid harmful effects to health. Secondly, the Directive aims to assess ambient air quality on the basis of common methods and criteria throughout the EU. Additionally, it is aimed to make information on air quality available to the public via alert thresholds and fourthly, it aims to maintain air quality where it is good and improve it in other cases.

As part of these measures to improve air quality, the European Commission has adopted proposals for daughter legislation under Directive 96/62/EC. The first of these directives to be enacted, Council Directive 1999/30/EC, has been passed into Irish Law as S.I. No 271 of 2002 (Air Quality Standards Regulations 2002), and has set limit values which came into operation on 17<sup>th</sup> June 2002. Council Directive 1999/30/EC, as relating to limit values for sulphur dioxide, nitrogen dioxide, lead and particulate matter. The Air Quality Standards Regulations 2002 detail margins of tolerance, which are trigger levels for certain types of action in the period leading to the attainment date. The margin of tolerance varies from 60% for lead, to 30% for 24-hour limit value for PM<sub>10</sub>, 40% for the hourly and annual limit value for NO<sub>2</sub> and 26% for hourly SO<sub>2</sub> limit values. The margin of tolerance commenced from June 2002. It started to reduce from 1 January 2003, continuing every 12 months thereafter by equal annual percentages to reach 0% by the respective attainment date for each pollutant. A second daughter directive, EU Council Directive 2000/69/EC, limit values for both carbon monoxide and benzene in ambient air is also included in the Air Quality Standards Regulations 2002. This has also been passed into Irish Law under the Air Quality Standards Regulations 2002.

The most recent EU Council Directive on ambient air quality was published on the 11/06/08. Council Directive 2008/50/EC combines the previous Air Quality Framework Directive and its subsequent daughter directives. This has also been passed into Irish Law under the Air Quality Standards Regulations 2011 (S.I. 180 of 2011) (see Table 9.1). Provisions were also made for the inclusion of new ambient limit values relating to PM<sub>2.5</sub>. The margin of tolerance specific to each pollutant were also slightly adjusted from previous directives. In regards to existing ambient air quality standards, it is not proposed to modify the standards but to strengthen existing provisions to ensure that non-compliances are removed. In addition,

new ambient standards for PM<sub>2.5</sub> are included in Directive 2008/50/EC. The approach for PM<sub>2.5</sub> is to establish a target value of 25 µg/m<sup>3</sup>, as an annual average (to be attained everywhere by 2010) and a limit value of 25 µg/m<sup>3</sup>, as an annual average (to be attained everywhere by 2012), coupled with a target to reduce human exposure generally to PM<sub>2.5</sub> between 2010 and 2020. This exposure reduction target will range from 0% (for PM<sub>2.5</sub> concentrations of less than 8.5 µg/m<sup>3</sup> to 20% of the average exposure indicator (AEI) for concentrations of between 18 - 22 µg/m<sup>3</sup>. Where the AEI is currently greater than 22 µg/m<sup>3</sup> all appropriate measures should be employed to reduce this level to 18 µg/m<sup>3</sup> by 2020. The AEI is based on measurements taken in urban background locations averaged over a three year period from 2008-2010 and again from 2018-2020. Additionally, an exposure concentration obligation of 20 µg/m<sup>3</sup> has been set which was to be complied with by 2012 again based on the AEI.

Although the EU Air Quality Limit Values are the basis of legislation, other thresholds outlined by the EU Directives are used which are triggers for particular actions. The Alert Threshold is defined in Council Directive 96/62/EC as “a level beyond which there is a risk to human health from brief exposure and at which immediate steps shall be taken as laid down in Directive 96/62/EC”. These steps include undertaking to ensure that the necessary steps are taken to inform the public (e.g. by means of radio, television and the press).

The Margin of Tolerance is defined in Council Directive 96/62/EC as a concentration which is higher than the limit value when legislation comes into force. It decreases to meet the limit value by the attainment date. The Upper Assessment Threshold is defined in Council Directive 96/62/EC as a concentration above which high quality measurement is mandatory. Data from measurement may be supplemented by information from other sources, including air quality modelling.

Under the terms of EU Framework Directive on Ambient Air Quality (96/62/EC), geographical areas within member states have been classified in terms of zones. The zones have been defined in order to meet the criteria for air quality monitoring, assessment and management as described in the Framework Directive and Daughter Directives. Zone A is defined as Dublin and its environs, Zone B is defined as Cork City, Zone C is defined as 21 urban areas with a population greater than 15,000 and Zone D is defined as the remainder of the country. The Zones were defined based on among other factors, population and existing ambient air quality.

EU Council Directive 96/62/EC on ambient air quality and assessment has been adopted into Irish Legislation (S.I. No. 33 of 1999). The act has designated the Environmental Protection Agency (EPA) as the competent authority responsible for the implementation of the Directive and for assessing ambient air quality in the State. Other commonly referenced ambient air quality standards include the World Health Organisation<sup>(A1)</sup>. The WHO guidelines differ from air quality standards in that they are primarily set to protect public health from the effects of air pollution. Air quality standards, however, are air quality guidelines recommended by governments, for which additional factors, such as socio-economic factors, may be considered.

- (A1) World Health Organisation (2006) Air Quality Guidelines - Global Update 2005 (and previous Air Quality Guideline Reports 1999 & 2000)

RECEIVED: 18/07/2023

Kildare County Council Planning Department - Viewing Purposes Only!



**Appendix 11.1 – 11.5: Noise Chapter Appendices**

RECEIVED: 18/07/2023

Kildare County Council Planning Department - Viewing Purposes Only



## Appendix 11.1 Glossary of Noise and Vibration Terminology

**Ambient noise** The totally encompassing sound in a given situation at a given time, usually composed of sound from many sources, near and far.

**Background noise** The steady existing noise level present without contribution from any intermittent sources. The A-weighted sound pressure level of the residual noise at the assessment position that is exceeded for 90 per cent of a given time interval, T (L<sub>AF90,T</sub>).

**dB** Decibel - The scale in which sound pressure level is expressed. It is defined as 20 times the logarithm of the ratio between the RMS pressure of the sound field and the reference pressure of 20 micro-pascals (20 µPa).

**dB(A)** An 'A-weighted decibel' - a measure of the overall noise level of sound across the audible frequency range (20 Hz – 20 kHz) with A-frequency weighting (i.e. 'A'-weighting) to compensate for the varying sensitivity of the human ear to sound at different frequencies.

**Hertz (Hz)** The unit of sound frequency in cycles per second.

**sound power level** The logarithmic measure of sound power in comparison to a referenced sound intensity level of one picowatt (1pW) where:

$$L_w = 10 \log \frac{P}{P_0} \text{ dB}$$

Where: p is the rms value of sound power in Watts; and  
P<sub>0</sub> is 1 pW.

**sound pressure level** The sound pressure level at a point is defined as:

$$L_p = 20 \log \frac{P}{P_0} \text{ dB}$$

Where: p is the rms value of sound power in Pascals; and  
P<sub>0</sub> is 2x10<sup>-5</sup> Pa.

**L<sub>Aeq,T</sub>** This is the equivalent continuous sound level. It is a type of average and is used to describe a fluctuating noise in terms of a single noise level over the sample period (T). The closer the L<sub>Aeq</sub> value is to either the L<sub>AF10</sub> or L<sub>AF90</sub> value indicates the relative impact of the intermittent sources and their contribution. The relative spread between the values determines the impact of intermittent sources such as traffic on the background.

**L<sub>AFN</sub>** The A-weighted noise level exceeded for N% of the sampling interval. Measured using the "Fast" time weighting.

**L<sub>AF90</sub>** Refers to those A-weighted noise levels in the lower 90 percentile of the sampling interval; it is the level which is exceeded for 90% of the measurement period. It will therefore exclude the intermittent features of traffic and is used to estimate a background level. Measured using the "Fast" time weighting.

LAF10	Refers to those A-weighted noise levels in the upper 10 percentile of the sampling interval; it is the level which is exceeded for 10% of the measurement period. It is typically representative of traffic noise levels. Measured using the "Fast" time weighting.
LAFmax	is the instantaneous fast time weighted maximum sound level measured during the sample period.
LAFmin	is the instantaneous fast time weighted minimum sound level measured during the sample period.

Kildare County Council Planning Department - Viewing Purposes Only

RECEIVED: 18/07/2023

## Appendix 11.2 Noise Modelling Software

### Noise Model

A 3D computer-based prediction model has been prepared in order to quantify the noise level associated with the proposed building. This section discusses the methodology behind the noise modelling process.

### DGMR iNoise

Proprietary noise calculation software has been used for the purposes of this modelling exercise. The selected software, DGMR iNoise, calculates noise levels in accordance with *ISO 9613: Acoustics – Attenuation of sound during propagation outdoors, Part 2: General method of calculation, 1996*.

DGMR iNoise is a proprietary noise calculation package for computing noise levels in the vicinity of noise sources. iNoise calculates noise levels in different ways depending on the selected prediction standard. In general, however, the resultant noise level is calculated taking into account a range of factors affecting the propagation of sound, including:

- the magnitude of the noise source in terms of A weighted sound power levels (LWA);
- the distance between the source and receiver;
- the presence of obstacles such as screens or barriers in the propagation path;
- the presence of reflecting surfaces;
- the hardness of the ground between the source and receiver;
- Attenuation due to atmospheric absorption; and
- Meteorological effects such as wind gradient, temperature gradient and humidity (these have significant impact at distances greater than approximately 400m).

### Brief Description of ISO9613-2: 1996

ISO9613-2:1996 calculates the noise level based on each of the factors discussed previously. However, the effect of meteorological conditions is significantly simplified by calculating the average downwind sound pressure level,  $L_{AT}(DW)$ , for the following conditions:

- wind direction at an angle of  $\pm 45^\circ$  to the direction connecting the centre of the dominant sound source and the centre of the specified receiver region with the wind blowing from source to receiver, and;
- wind speed between approximately  $1\text{ms}^{-1}$  and  $5\text{ms}^{-1}$ , measured at a height of 3m to 11m above the ground.

The equations and calculations also hold for average propagation under a well-developed moderate ground based temperature inversion, such as commonly occurs on clear calm nights.

The basic formula for calculating  $L_{AT}(DW)$  from any point source at any receiver location is given by:

$$L_{FT}(DW) = L_W + D_c - A \quad \text{Eqn. A}$$

Where:

$L_{FT}(DW)$  is an octave band centre frequency component of  $L_{AT}(DW)$  in dB relative to  $2 \times 10^{-5} \text{Pa}$ ;

$L_W$  is the octave band sound power of the point source;

$D_c$  is the directivity correction for the point source;

$A$  is the octave band attenuation that occurs during propagation, namely attenuation due to geometric divergence, atmospheric absorption, ground effect, barriers and miscellaneous other effects.

The estimated accuracy associated with this methodology is shown in Table A2-1 below:

Height, $h^*$	Distance, $d^\dagger$	
	$0 < d < 100\text{m}$	$100\text{m} < d < 1,000\text{m}$
$0 < h < 5\text{m}$	$\pm 3\text{dB}$	$\pm 3\text{dB}$
$5\text{m} < h < 30\text{m}$	$\pm 1\text{dB}$	$\pm 3\text{dB}$

**Table A2-1** Estimated Accuracy for Broadband Noise of  $L_{AT}(DW)$

\*  $h$  is the mean height of the source and receiver.  $\dagger d$  is the mean distance between the source and receiver.

N.B. These estimates have been made from situations where there are no effects due to reflections or attenuation due to screening.

### Other Modelling Calculation Parameters

A ground attenuation factor of 1.0 has been assumed beyond the site boundary, i.e. soft ground. No metrological corrections were assumed for the calculations. The atmospheric attenuation outlined in Table A3-2 has been assumed for all calculations.

Temp ( $^{\circ}\text{C}$ )	% Humidity	Octave Band Centre Frequencies (Hz)							
		63	125	250	500	1k	2k	4k	8k
10	70	0.12	0.41	1.04	1.92	3.66	9.70	33.06	118.4

**Table A2-2** Atmospheric Attenuation Assumed for Noise Calculations (dB per km)

Foliage regions within the Castletown House grounds have been modelled as 18 m in height, as advised by TPA.

### Input Data and Assumptions

The noise model has been constructed using data from various source as follows:

**Site Layout** The general site layout has been obtained from the drawings forwarded by the project architects.

**Local Area** The location of noise sensitive locations has been obtained from a combination of site drawings provided by the project architects and others obtained from Ordinance Survey Ireland (OSI).

**Heights** The heights of buildings on site have been obtained from site drawings forwarded by the projects. Off-site buildings have been assumed to be 8m high with the exception of industrial buildings where a default height of 15m has been assumed.

**Contours** Site ground contours/heights have been obtained from site drawings forwarded by the project architects.

## Appendix 11.3 Noise Modelling Parameters

### Energy Centre

The sound power levels for the gas-fired generators are presented in Table A3-1, based on information from a reference design supplied by the design team.

Item	Sound Power Level, L <sub>WA</sub> (dB) at Octave-band Centre Frequency, (Hz)									dB(A)
	31.5	63	125	250	500	1000	2000	4000	8000	
Booster Skid	43.6	69.6	85.1	86.6	90.9	95.1	94.3	88.1	78.1	99.4
Control Room	54.9	63.6	71.4	60.2	70.5	73.5	72.8	70	60.2	79.1
Turbine Ventilation	69.7	77.1	83.7	81.6	76.7	76.8	78.1	72.5	68.5	87.9
GLO 50 Hz	67.5	78.1	88.9	91.8	90.1	91.4	86.7	79.7	72.2	97.3
Aux 50 Hz	66.8	80.1	88.9	87.2	87.5	85	83.6	77.7	65.7	94.1
Fan Motor	66.6	77.1	87.3	88.1	91.3	92.4	90.6	82.3	70.8	97.5
Turbine 50 Hz	73.6	89.3	94.6	93.5	91.2	92.3	92.6	86.9	79.8	100.6
Air Filter OK	67.3	81.4	94.9	83.5	80.7	80.6	80.7	65.4	58.9	95.8
Coupling	58.6	73.1	87.2	74.3	79.6	85	83.3	84	81.1	92
GEN 50hz	70.9	82.6	97.2	88.7	85.3	91.5	97.5	81.9	72.8	101.4
Tempering Fan Entry	--	--	--	--	--	--	--	--	--	80
Tempering Air Fan Type B <sup>A</sup>	60	75	85	80	79	76	71	65	88	60
Exhaust Elbow 1	--	--	--	--	--	--	--	--	--	90.5
Exhaust Elbow 2	--	--	--	--	--	--	--	--	--	95
Exhaust Stage 1	--	--	--	--	--	--	--	--	--	96
Exhaust Stage 2	--	--	--	--	--	--	--	--	--	96
Exhaust Stage 3	--	--	--	--	--	--	--	--	--	90
Stack	--	--	--	--	--	--	--	--	--	84

**Table A3-1** Summary of Noise Data for Noise Model supplied by generator manufacturer.

Note A A nominal 20 dB reduction is included in the figures presented to account for the enclosure of the tempering fan motor.

The barrier around the energy compound is assumed to be 14 m high and have the following acoustic performance:

Item	Sound Reduction Index, dB at Octave Band Centre Frequency, Hz.							
	63	125	250	500	1000	2000	4000	8000
Energy Centre Louvre	9	15	20	25	39	48	50	50

**Table A3-2** Barrier Sound Reduction for energy centre.

### Data Centres

The sound power levels for the data centre buildings are presented in Table A3-2, based on information from a reference design supplied by the design team.

Source	L <sub>w</sub> (dB) per Octave Band (Hz)								L <sub>w</sub> dB(A)
	63	125	250	500	1000	2000	4000	8000	
Extract Fans <sup>Note A</sup>	85	87	85	88	86	80	76	72	94

Source	L <sub>w</sub> (dB) per Octave Band (Hz)								L <sub>w</sub> dB(A)
	63	125	250	500	1000	2000	4000	8000	
DAHU <sup>Note B</sup>	90	102	92	82	75	71	61	62	89
Condensers	--	78	75	70	71	68	60	53	75
Admin AHU – Sides and Top	67	75	69	77	77	74	70	63	80
Admin AHU – Ends	63	71	65	73	73	79	66	59	77
Admin AHU – Exhaust	68	76	69	77	77	74	70	63	82
Split Condenser	64	66	65	68	63	60	58	57	69
VRF Condenser	83	85	84	87	82	79	77	76	88
Generator – Side	79	96	92	93	93	91	86	89	101
Generator -Front	80	88	83	85	85	89	86	88	95
Generator -Rear	83	97	91	81	70	71	78	91	99
Gen. – Roof (Solid)	79	96	92	92	93	91	85	89	101
Gen. Discharge	85	98	83	64	65	67	71	94	100
Generator -Exhaust Outlet	78	87	80	80	79	78	74	68	90
House Gen – Side	70	86	79	85	85	86	80	84	93
House Gen – Front	68	76	76	76	78	79	73	68	85
House Gen – Rear	74	84	67	59	58	56	57	66	85
House Gen – Roof (Solid)	56	70	67	66	67	67	62	63	75
House Gen – Roof – Discharge	61	74	58	39	41	42	47	70	75
Exhaust Outlet	68	77	70	70	69	69	64	58	80

**Table A3-3** Noise Data for Data Centre Plant.

**Note A** In relation to the Extract Fans, it is assumed that the vertical orientation of fan output is gives a directivity pattern with a value of -4dB at 90 degrees, i.e. in the horizontal plane. In addition to this, the following reduction is assumed for night-time periods due to fans running at 90% load rather than full load. These values are based on in-situ measurements at a similar site:

Description	Sound Reduction, dB at Octave Band Centre Frequency, Hz.							
	63	125	250	500	1000	2000	4000	8000
90% load	1	5	3	4	4	5	4	4

**Note B** Note that the DAHU louvres are assumed to be contained in spaces with a reverberation time of 1.0 seconds. It is assumed that the louvres at the north facades of the B building is an acoustic louvre as are the louvres on the west sides of the 'C' buildings. The following table summarises the assumed louvre performances.

Element	Sound Reduction Index, dB at Octave Band Centre Frequency, Hz.							
	63	125	250	500	1000	2000	4000	8000
DAHU Louvre 'B' Buildings – North Facade	4	5	8	9	12	9	7	6
DAHU Louvre 'B' Buildings – South Facade	1	1	1	2	2	2	3	3
DAHU Louvre 'C' Buildings (Non-	4	5	5	5	5	5	5	5

Element	Sound Reduction Index, dB at Octave Band Centre Frequency, Hz.							
	63	125	250	500	1000	2000	4000	8000
generator sides)								
DAHU Louvre 'C' Buildings (Generator sides)	1	1	1	2	2	2	3	3

**Rinawade Substation**

The following sound power level has been assumed for each transformer at the substation

Source	L <sub>w</sub> (dB) per Octave Band (Hz)								L <sub>w</sub> dB(A)
	63	125	250	500	1000	2000	4000	8000	
Transformer	43	63	77	72	64	60	40	36	79

**Table A3-4** Noise Data for Substation

Kildare County Council Planning Department - Viewing Purposes Only

RECEIVED: 18/07/2023

## Appendix 11.4 Measured Baseline Noise Levels

Loc	Period	Time	dB L <sub>Aeq</sub>	dB L <sub>A90</sub>
A	Day	12:14 on 4 Nov 21	67	65
	Day	15:18 on 4 Nov 21	67	65
	Day	11:50 on 5 Nov 21	65	63
	Evening	21:25 on 5 Nov 21	59	56
	Night	22:40 on 5 Nov 21	57	54
	Night	23:28 on 5 Nov 21	56	50
B	Day	12:36 on 4 Nov 21	61	58
	Day	15:39 on 4 Nov 21	61	58
	Day	12:10 on 5 Nov 21	60	56
	Evening	21:52 on 5 Nov 21	51	48
	Night	23:02 on 5 Nov 21	50	46
	Night	23:50 on 5 Nov 21	49	46
C	Day	13:13 on 4 Nov 21	56	55
	Day	16:00 on 4 Nov 21	62	56
	Day	12:29 on 5 Nov 21	58	55
	Evening	22:28 on 5 Nov 21	47	46
	Night	23:36 on 4 Nov 21	47	44
	Night	00:42 on 5 Nov 21	48	46
D	Day	13:51 on 4 Nov 21	53	49
	Day	16:31 on 4 Nov 21	57	53
	Day	13:04 on 5 Nov 21	53	48
	Evening	22:51 on 5 Nov 21	38	28
	Night	01:14 on 5 Nov 21	30	27
	Night	23:59 on 5 Nov 21	38	26
E	Day	14:42 on 4 Nov 21	62	60
	Day	17:10 on 4 Nov 21	64	62
	Day	13:42 on 5 Nov 21	67	65
	Evening	22:01 on 5 Nov 21	56	51
	Night	23:17 on 5 Nov 21	55	44
	Night	00:23 on 6 Nov 21	55	45

RECEIVED: 18/07/2023

Kildare County Council Planning Department - Viewing Purposes Only



# Appendix 11.5 Noise Contours

Figure A5-1: Noise Contours for Scenario A




Figure A5-2: Noise Contours for Scenario B





Figure A5-3: Noise Contours for Scenario C





**Appendix 12.1: Resource & Waste Management Plan**

RECEIVED: 18/07/2023

Kildare County Council Planning Department - Viewing Purposes Only

# RESOURCE & WASTE MANAGEMENT PLAN FOR A PROPOSED DEVELOPMENT

## KILDARE INNOVATION CAMPUS

---

Report Prepared for

### Davy Platform ICAV

---

Report Prepared by

**Chonail Bradley**, Principal Environmental  
Consultant

---

For Reference

XXXXXXXXXXXXXXXXXXXX MXXXX

---

Date Issued

Only XXXX

---











development and implementation of a voluntary construction industry programme to meet the Government's objectives for the recovery of C&D waste.

In September 2022, the Irish Government published a policy document outlining a national action plan for Ireland to cover the period 2022-2030. This plan, 'A Waste Action Plan for a Circular Economy' or AP2022, replaces the previous national waste management plan, "A Resource Opportunity" (2012), and was prepared in response to the 'European Green Deal' which sets a roadmap for a transition to an altered economical model, where climate and environmental challenges are turned into opportunities.

The AP2022 sets the direction for waste planning and management in Ireland to 2030. This reorientates policy from a focus on managing waste to a much greater focus on creating circular patterns of production and consumption. Other policy statements from a number of public bodies already acknowledged the circular economy as a national policy priority.

The policy document contains over 100 measures across various waste areas including circular economy, municipal waste, consumer protection and citizen engagement, plastics and packaging, construction and demolition, textiles, green public procurement and waste enforcement.

One of the first actions to be taken was the development of the whole government circular economy strategy, 'Living More, Using Less' (LMUL) to set a course for Ireland to transition across all sectors and at all levels of government towards circularity and was issued in December 2022. It is anticipated that the Strategy will be updated in all every 18 months to 3 years.

The Circular Economy and Miscellaneous Provisions Act 2022 was signed into law in July 2022. The Act underpins Ireland's shift from a "take-make-waste" linear model to a more sustainable pattern of production and consumption, that retains the value of resources in our economy for as long as possible and that will to significantly reduce our greenhouse gas emissions. The Act defines circular economy for the first time in Irish law, incentivises the use of recycled and reusable alternatives to waste, single-use disposable packaging, introduces a mandatory segregation and incentivised charging regime for commercial waste, streamlines the national processes for end-of-life waste and by-products decisions, tackling the delays which can be encountered by industry, and supporting the availability of recycled secondary raw materials in the Irish market, and tackles illegal fly-tipping and littering.

The Environmental Protection Agency (EPA) of Ireland issued 'Best Practice Guidelines for the Preparation of Resource & Waste Management Plans for Construction & Demolition Projects' in December 2022. These guidelines replace the previous guidelines issued by the National Construction and Demolition Waste Council (NCDWC) and the Department of the Environment, Heritage and Local Government (DEHLG). The guidelines provide a practical approach which is informed by best practice in the prevention and management of construction wastes and resources from design to construction of a project, including consideration of the deconstruction of a project. These guidelines have been included in the preparation of this document and include the following elements:





### 2.3 Legislative Requirements

The primary legislative instruments that govern waste management in Ireland and applicable to the development are

- Waste Management Act 1996 as amended
- Environmental Protection Agency Act 1992 as amended
- Litter Pollution Act 1997 as amended
- Circular Economy and Miscellaneous Provisions Act 2018
- Planning and Development Act 2000 as amended

One of the guiding principles of European waste legislation, which has in turn been incorporated into the *Waste Management Act* as amended and subsequent Irish legislation, is the principle of "Duty of Care". This implies that the waste producer is responsible for waste from the time it is generated through until its legal recycling, recovery or disposal including its method of disposal. As it is not practical in most cases for the waste producer to physically transfer all waste from where it is produced to the final destination, waste contractors will be employed to physically transport waste to the final destination. In turn this is the concept of "Polluter Pays" whereby the waste producer is liable to be prosecuted for pollution incidents, which may arise from the incorrect management of waste produced, including the actions of any contractors engaged to collect, transport and disposal/recovery/recycle waste.

It is therefore imperative that the developer ensures that the waste contractors engaged by the demolition and construction contractors are legally compliant with respect to waste transportation, recycling, recovery and disposal. This includes the requirement that a contractor handle, transport and recycle/recover/dispose of waste in a manner that ensures that no adverse environmental impacts occur as a result of any of these activities.

A collection permit to transport waste must be held by each waste contractor which is issued by the National Waste Collection Permit Office (NWCO). Waste receiving facilities must also be appropriately permitted or licensed. Operators of such facilities cannot receive any waste, unless in possession of a certificate of registration issued under a waste permit granted by the relevant local Authority under the *Waste Management (Facility Permit & Registration) Regulations 2007 and Amendments* or a waste or industrial emissions licence granted by the EPA. The waste collection permit licence held will specify the type and quantity of waste able to be received, stored, sorted, recycled, recovered and/or disposed of at the specified site.

### 3.0 DESIGN APPROACH

The client and the design team have integrated the 'Best Practice Guidelines for the Preparation of Resource & Waste Management Plans for Construction & Demolition Projects' guidelines into the design process, to help reduce processes, identify and evaluate resource reduction measures and investigate the impact on cost, time, quality, buildability, second life and management post demolition and construction. Further details on these design principles can be found within the aforementioned guidance document.

The design team have undertaken the design process in line with the international best practice principles to firstly prevent wastes, reuse where possible and thereafter sustainably reduce and recover materials. The below sections have been the final point

00 the design 0r0cess and material sele0tions and 0ill 0ntin0e t0 be analysed and in0estigated thr00h00t the design 0r0cess and 0hen sele0tin0 material0

0he a0r0aches 0resented are based 0n international 0rin0ples 0000timisin0 res00r0es and red00in0 0aste 0n dem0liti0n and 0nstr0cti0n 0r0e0ts thr00h0

- Pre0enti0n0
- 0e0se0
- 0e0y0din00
- 0reen Pr000rement Prin0ples0
- 000Site 0nstr0cti0n0
- Materials 00timisati0n0and
- 0le00ibility and 0e0nstr0cti0n0

### 3.1 Designing For Prevention, Reuse and Recycling

0nderta0en at the 00tset and d0rin0 0r0e0t 0easibility and e0al0ati0n the 0lient and 0esi0n 0eam 00nsidered0

- 0stablishin0 the 00tential 0r any res0sable site assets 0uildin0s, str0ctres, e000ment, materials, s0ils, et0000
- 0he 00tential 0r re0rbishment and re0it 00e0stin0 str0ctres 0r 0uildin0s rather than dem0liti0n and ne0 0uild0
- Assessin0 any e0istin0 0uildin0s 0n the site that 0an be re0rbished either in 0art 0r 0h0lly t0 meet the 0lient re00irements0and
- 0nablin0 the 00tim0m re000ery 00assets 0n site0

### 3.2 Designing for Green Procurement

0aste 0re0enti0n and minimisati0n 0re0r000rement ha0e been dis00ssed and 0ill be 0rther dis00ssed in this se0ti0n00he 0esi0n 0eam 0ill dis00ss 0r00ssed design se0luti0ns, en000ra0e inn0vati0n in tenders and in0enti0se 00m0eti0ns t0 re000nise s0stainable a0r0aches00they sh00ld als0 dis00ss 00ti0ns 0r 0a0a0ain0 red0cti0n 0ith the main Contractor and subcontractors/suppliers using measures such as 'Just in Time' delivery and 0se 0rderin0 0r0e0dres that a00id e00essive 0aste00he 0reen 0r000rement e0tends 0r0m the 0lannin0 sta0e int0 the detailed design and tender sta0e and 0ill be an 0n00in0 0art 00the l0n00term design and sele0ti0n 0r0cess 0r this de0el0pment0

### 3.3 Designing for Off-Site Construction

0se 00000site man0a0cturin0 has been sh00n t0 red00e resid0al 0astes by 00 t0 000 0000metri0 0uildin0 0ers0s traditi0nal000he 0esi0n t0 0se 00site 0nstr0cti0n is ty0ically 0st led b0t there are si0nifi0cant bene0its 0r res00r0e man0ement0 Some 0rther 0nsiderati0ns 0r 0r000rement 0hich are bein0 in0estigated as 0art 00the 0lannin0 sta0e design 0r0cess are listed as 0ll00s0

- M0d0lar 0uildin0s as these 0an dis0la0e the 0se 0000n0rete and the res00r0e l0sses ass0ciated 0ith 0n0rete 0l00ks s0ch as br00en 0l00ks, m0rtars, et000
  - o M0d0lar 0uildin0s are ty0ically 0re0itted 0ith 0red 0laster0ard and installed ins0lati0n, eliminatin0 these resid0al streams 0r0m site0
- 0se 000re0e0ast str0ctural 0n0rete 0anels 0hich 0an red00e the resid0al 000mes 0000n0rete 0l00ks, m0rtars, 0lasters, et000

- The use of prefabricated composite panels for walls and roofs to reduce residual volumes insulation and plasterboards
- Using precast hollow core slabs instead of in situ ready mix concrete or timber slabs to reduce the residual volumes of concrete formwork and scaffolding, respectively and
- Designing for the differential use of composite modular units

### 3.4 Designing for Materials Optimisation During Construction

To ensure manufacturers and construction companies adopt lean production models, including maximising the reuse of materials onsite as outlined in section 3.3, structures should be designed with the intent of designing out waste. This helps to reduce the environmental impacts associated with transportation of materials and from waste management activities. This includes investigating the use of standardised sizes for certain materials to help reduce the amount of offcuts produced on site, minimising on formation and development of site infrastructure.

### 3.5 Designing for Flexibility and Deconstruction

Design flexibility has and will be investigated through the design process to ensure that where possible products including buildings only contain materials that can be recycled and are designed to be easily disassembled. Material efficiency is being considered for the duration and end of life of a building project to create flexible, adaptable spaces that enable a resource efficient, low waste future change of use of materials and how they can be recovered effectively when maintenance and refurbishment are undertaken and during disassembly/deconstruction.

## 4.0 DESCRIPTION OF THE DEVELOPMENT

### 4.1 Location, Size and Scale of the Development

The subject site is located to the south of the M0 and to the west of the M00 and the city of Deseroir in Ceidli, Kildare. The overall site extends to over 1000 ha, mainly brownfield lands.

The site consists of a 100,000m<sup>2</sup> manufacturing facility for Helett Packard (HP). The land has since been further developed for a micro-manufacturing, office and warehousing with a total area of 1,000,000m<sup>2</sup>. It is proposed to demolish three of the existing site buildings and provide an additional 100,000m<sup>2</sup> access door space across a new building as a part of the new development.

The proposed development is described as follows:

- Demolition of existing Buildings No's 7, 8 and 9 (total gfa c. 84,838sqm).
- Existing Buildings No's 1 – will be retained for deep tech and innovation related uses (total gfa 1,000,000sqm)
- Construction of a new deep tech buildings and a new data centre buildings, all including ancillary office spaces. The deep tech buildings will have an overall maximum height of 10m and vary in size from 10,000sqm – 100,000sqm with a combined total gfa of 1,000,000sqm. The data centres will be 10m in height to a parapet and 10m in height to top of roof/curtain screening. The data centres will vary in size from 10,000sqm – 100,000sqm with a combined total gfa of 1,000,000sqm.

- The new deep tech buildings (A000A000) will be provided with service yard areas, loading docks, car parking, access roads, security fences and landscaping. The deep tech buildings will include rainwater harvesting tanks and green roofs over office areas.
- Each data centre (000, 000, 000) will include data halls, admin blocks, monitoring centres, breakroom, loading dock, storage, and ancillary areas and a variety of mechanical and electrical plant areas structures including battery storage rooms and mechanical rooms car parking, access roads, security fences, gate houses and landscaping will also be provided.
- 000 will include 000 natural gas generators, 000 rooms and associated mechanical areas. 000 – 000 will each include 000 natural gas generators, 000 rooms and associated mechanical areas each including high car parking, access roads, security fences, gate houses and landscaping will also be provided.
- 000 district heating room house areas and in ground piping for district heating system.
- Construction of a replacement 000000 gas insulated Switchgear (GIS) Substation adjacent to the existing 000000 in a 000ade Substation. The current Air Insulated Switchgear (AIS) substation known as the in a 000ade 000000 sub is fed by 000000 overhead lines. The new substation will connect to these overhead lines via short runs underground cable. The replacement 000000 substation will include 000000 transformers, with client control building and a 000 storey GIS substation building within a 000m high fenced compound.
- Decommissioning and removal of the existing 000000 in a 000ade substation.
- Construction of an on-site energy centre to provide dispatchable power to the national electrical grid. The energy centre will include 000000 gas powered combustion turbine generators (CTG's) and 9no. flues with a maximum height of 000000 metres. The turbines will be enclosed by a screen wall 000000m in height. The energy compound will include all required infrastructure including 000000000000 fuel oil storage tanks, an administration building, 000000 house, fire water tank, access roads, 000000 parking bays, security fences etc.
- Provision of a gas detectors Ireland 000000 gas solid surrounded by a 000m high fence and access from Melbridge Road. The 000000 solid will replace the existing gas solid along Melbridge Road.
- Provision of a 000000A000Ab000e ground installation including 000000s building, 000000m high, surrounded by a 000m high fence.
- Ensure the existing main entrance to the campus on Melbridge Road and reinstatement of the boundary.
- Construction of a new signalled entrance exit on Melbridge Road 000000 metres north of the existing main entrance.
- Use of the existing secondary entrance exit on Barnhall Road 000000m in the south east as a principal entry exit.
- Construction of internal access roads, footpaths and cycle paths including a publicly accessible link road between Melbridge Road 000000m to the east and Barnhall Road 000000m to the west.








Figure 4.2 Proposed site layout plan

#### 4.2 Details of the Non-Hazardous Wastes to be Produced

There will be waste materials generated from the demolition (Buildings No's 7, 8 and 9 and renovation (Building No's 1 to 6) the existing buildings and hardstanding areas on site to accommodate the new development. The volume of waste generated from demolition will be more difficult to separate than waste generated from the construction phase, as many of the building materials will be bonded together or integrated in plasterboard on timber ceiling joists, steel embedded in concrete, etc.

It is predicted by the project development engineers, Clifton Scannell Partners Associates, that approximately 100,000m<sup>3</sup> of the dirt material generated during site preparation, cellin, etc., will be reused to facilitate construction of the proposed roads, car parks, buildings and landscaping berms. It is estimated that 100,000m<sup>3</sup> will be exported off the site and disposed of in accordance with relevant requirements. It will be required to be imported to the site to accommodate the development.

The facilitating works from the Gas Networks Ireland (GNI) corridors will include approximately 100,000m<sup>3</sup> of material excavated along the length of the line. It is estimated that 100,000m<sup>3</sup> may be



### 4.3.3 Invasive Plant Species

Site valuer surveys was undertaken by 000000 Ireland Wildlife Consultants Ltd 000000 Ireland

00 invasive species listed on the Third Schedule of the 0000 European Communities Birds and Natural Habitats Regulations are species of which it is an offence to disseminate, spread or otherwise cause to grow in any place where recorded within the proposed development boundary or along the proposed 000000000000 route

If any Third Schedule invasive species are detected during the demolition and construction phase of the development, then 0000 will be notified and an invasive species management plan will be produced and submitted to 000000

### 4.3.4 Asbestos

Asbestos Management Surveys were carried out at the proposed development site on the existing buildings in 0000 and 000000. Asbestos containing materials (ACMs) have been confirmed in the existing buildings along with presumed strongly presumed ACMs which requires further investigation. Please see the Asbestos Management Survey by 0000 environmental and abject saiter limited for further details

During the asbestos survey of the site, asbestos containing materials (ACM's) were identified in but not limited to 000000 and 000000. ACM's are also presumed in all original 000000, 000000 and 000000 across the development. These ACM's will be required to be identified and removed by a suitably trained and competent person prior to commencement of demolition work

Removal of asbestos or ACMs will be carried out by a suitably qualified contractor and ACMs will only be removed from site by a suitably permitted licensed waste contractor, in accordance with S.I. No. 589 of 2010 Safety, Health and Welfare at Work (Exposure to Asbestos) Regulations 2006-2010. All material will be taken to a suitably licensed or permitted facility

### 4.3.5 Other Known Hazardous Substances

Paints, 0000, adhesives and other known hazardous substances will be stored in designated areas. They will generally be present in small 000000 only and associated waste 000000 generated will be sent to a minimum 000000. Wastes will be stored in appropriate receptacles pending collection by an authorised waste contractor

In addition, 0000 containing hazardous components, printer toner cartridges, batteries, lead, acid or Mercury and other mercury containing waste may be generated from during 0000 activities or temporary site offices. These wastes, if generated, will be stored in appropriate receptacles in designated areas of the site pending collection by an authorised waste contractor

## 5.0 ROLES AND RESPONSIBILITIES

The Best Practice Guidelines on the Preparation of Resource Waste Management Plans for Construction and Demolition Projects states that a Resource Manager (RM) should be appointed. The RM may be performed by number of different individuals over the life

By the Project, however it is intended to be a reliable person chosen from within the Planning/Design/Contracting team, who is technically competent and appropriately trained, who takes the responsibility to ensure that the objectives and measures within the Project 00 MP are complied with. The 00 MP is assigned the requisite authority to meet the objective and obligations of the 00 MP. The role will include the important activities of conducting waste audits and adopting construction and demolition methodology that is designed to facilitate maximum reuse and recycling of waste.

**5.1 Role of the Client**

The client is the body establishing the aims and the performance targets for the project.

- The client has commissioned the preparation and submission of a preliminary 00 MP as part of the design and planning submission.
- The client is to commission the preparation and submission of an updated 00 MP as part of the demolition and construction tendering process.
- The client will ensure that the 00 MP is agreed on and submitted to the local authority prior to commencement of works on site.
- The client is to request the end-of-project 00 MP from the contractor.

**5.2 Role of the Client Advisory Team**

The Client Advisory Team or Design Team is formed of architects, consultants, quantity surveyors and engineers and is responsible for:

- Drafting and maintaining the 00 MP through the design, planning and procurement phases of the project.
- Appointing a 00 M to track and document the design process, inform the design team and prepare the 00 MP.
- Including details and estimated quantities of all projected waste streams with the support of environmental consultants/scientists. This should also include data on waste types, waste characterisation data, contaminated land assessments, site investigation information and prevention mechanisms such as by-products to illustrate the site circular economy principles applied by the design team.
- Managing and calling the demolition work with the support of quantity surveyors.
- Handing over the 00 MP to the selected contractor upon commencement of demolition and construction of the development, in a similar fashion to how the safety file is handed over to the contractor.
- Working with the contractor as required to meet the performance targets for the project.

**5.3 Future Role of the Contractor**

The future demolition and construction contractors have not yet been decided on for this 00 MP. However, once selected they will have major roles to fulfil. They will be responsible for:

- Preparing, implementing and reviewing the inclusion of the Pre-demolition 00 MP through the demolition and construction phases including the management of all suppliers and subcontractors as per the requirements of these guidelines.

- Identifying a designated and suitably qualified M who will be responsible for implementing the MP
- Identifying all hauliers to be engaged to transport each of the resources wastes on site
- Implementing waste management policies whereby waste materials generated on site are to be segregated as far as practicable
- Obtaining and operating a mobile crusher to crush concrete for temporary reuse on site during construction and reduce the amount of H loads required to remove material from site
- Applying for the appropriate waste permit to crush concrete on site
- Identifying all destinations for resources taken on site. As above, any resource that is legally classified as a 'waste' must only be transported to an authorised waste facility
- Conducting waste and by-product notifications addressed with the EPA where required
- Clarification of any other statutory waste management obligations, which could include on-site processing
- All records of all resources both wastes and other resources should be maintained for the duration of the project and
- Preparing a MP implementation schedule report at project handover

## 6.0 KEY MATERIALS & QUANTITIES

### 6.1 Project Resource Targets

Project specific resource and waste management targets for the site have not yet been set and this information should be updated for these targets once these targets have been confirmed by the client. However, it is expected for projects of this nature that a minimum of 10% of waste is fully reused, recycled or recovered. Target setting will inform the setting of project specific benchmarks to track target progress. Typical Key Performance Indicators (KPIs) that may be used to set targets include (as per guidelines)

- eight tonnes of volume of waste generated per construction calendar
- eight tonnes of volume of waste generated per construction floor area m<sup>2</sup>
- fraction of resource reused on site
- fraction of resource notified as by-product
- fraction of waste segregated at source before being sent on site for recycling/recovery and
- fraction of waste recovered, fraction of waste recycled, or fraction of waste disposed

### 6.2 Main Construction Waste Categories

The main non-hazardous and hazardous waste streams that could be generated by the demolition and construction activities at a typical site are shown in table 1. The list of waste codes available as per the standards referred to as the European Waste Code (EWC) for each waste stream is also shown.

**Table 6.1** Typical waste types generated and codes individual waste types may contain hazardous substances

Waste Material	Low/EWC Code
Concrete, bricks, tiles, Ceramics	17 01 01, 17 01 02, 17 01 03
Glass, glass and plastic	17 01 04, 17 01 05
Treated wood, glass, plastic, containing hazardous substances	17 01 06, 17 01 07
Bituminous mixtures, coal tar and tarred products	17 01 08, 17 01 09
Metals including their alloys and cable	17 01 10, 17 01 11
Soil and stones	17 01 12, 17 01 13
Polymers based construction material	17 01 14, 17 01 15
Paper and cardboard	17 01 16
Mixed solid waste	17 01 17
Green waste	17 01 18
Electrical and electronic components	17 01 19, 17 01 20
Batteries and accumulators	17 01 21, 17 01 22
Acid oils	17 01 23, 17 01 24
Chemicals solvents, pesticides, paints, adhesives, detergents etc	17 01 25, 17 01 26, 17 01 27
Insulation materials	17 01 28
Organic solid waste	17 01 29
Mixed Municipal waste	17 01 30

\* Individual waste type may contain hazardous substances

### 6.3 Demolition Waste Generation

There will be waste materials generated from the demolition (Buildings No's 7, 8 and 9 and renovation (Building No's 1) of the existing buildings and hardstanding areas on site to accommodate the new development and additional works on the demolition areas are identified in the planning drawings provided with the planning application. The anticipated demolition waste and rates of reuse, recycling/recovery and disposal are shown in table 6.2 below.

**Table 6.2** Estimated site reuse, recycle and disposal rates for demolition waste

Waste Type	Tonnes	Reuse		Recycle / Recovery		Disposal	
		%	Tonnes	%	Tonnes	%	Tonnes
Glass	100000	0	000	00	100000	00	000000
Concrete, bricks, tiles, Ceramics	1000000	00	100000	00	100000	0	100000
Plasterboard	100000	0	000	00	10000	00	100000
Asphalts	100000	0	000	00	10000	00	100000
Metals	100000	0	100000	00	100000	00	100000
Slate	1000	0	000	00	1000	00	1000
Timber	100000	00	100000	00	100000	00	100000
Asbestos	1000	0	000	0	1000	0	1000
<b>Total</b>	<b>23377.6</b>		<b>4383.1</b>		<b>15512.4</b>		<b>3482.1</b>

### 6.4 Construction Waste Generation

Table 6.3 shows the breakdown in waste types recorded on a typical site based on data from the EPA National Waste Reports and the Joint EPA & GMIT study and other research reports

**Table 6.3** Waste materials generated on a typical Irish construction site

Waste Types	%
Mixed	20
Timber	20
Plasterboard	20
Metals	10
Concrete	10
Other	20
<b>Total</b>	<b>100</b>

Table 6.4, below, shows the estimated construction waste generation for the proposed development and facilitation works based on the area construction and other information available to date, along with indicative targets for management of the waste streams. The estimated amounts for the main waste types with the exception of soils and stones are based on waste generation rate per m<sup>2</sup>. These have been calculated from the scheduled development areas provided by the design team.

**Table 6.4** Predicted on and offsite reuse, recycle and disposal rates for construction waste

Waste Type	Tonnes	Reuse		Recycle / Recovery		Disposal	
		%	Tonnes	%	Tonnes	%	Tonnes
Mixed	10000	20	2000	20	10000	20	2000
Timber	10000	20	2000	20	10000	0	2000
Plasterboard	10000	20	2000	20	10000	20	2000
Metals	10000	0	2000	20	10000	0	2000
Concrete	10000	20	2000	20	10000	0	2000
Other	10000	20	2000	20	10000	20	2000
<b>Total</b>	<b>5998.4</b>		<b>1361.6</b>		<b>4072.9</b>		<b>563.8</b>

In addition to the waste streams in Table 6.4, it is predicted that 100,000m<sup>3</sup> of the cut material generated during site preparation (cellin 100,000m<sup>3</sup>) will be reused to facilitate construction of the proposed roads, car parks, buildings and landscaping berms. It is estimated 100,000m<sup>3</sup> will be exported offsite and disposed of in accordance with relevant requirements. All fill will be required to be imported to the site to accommodate the development.

The facilitation works from the 100,000m<sup>3</sup> will include 100,000m<sup>3</sup> of material excavated along the length of the line. It is estimated 100,000 may be reused, leaving 100,000m<sup>3</sup> that will be removed offsite for appropriate reuse, recycling or disposal.

It should be noted that until final materials and detailed construction methodologies have been confirmed, it is difficult to predict with a high level of accuracy the construction waste



that will be generated from the proposed works as the exact materials and quantities may be subject to some degree of change and variation during the construction process.

### 6.5 Proposed Resource and Waste Management Options

Waste materials generated will be separated on-site, where it is practical. Where the on-site separation of certain waste types is not practical, off-site separation will be carried out. There will be skips and receptacles provided to facilitate separation at source, where feasible. All waste receptacles located on-site will be covered or enclosed. The appointed waste contractor will collect and transfer the wastes as receptacles are filled. There are numerous waste contractors in the Kildare region that provide this service.

All waste arising will be handled by an approved waste contractor holding a current waste collection permit. All waste arising requiring disposal on-site will be reused, recycled, recovered or disposed of at a facility holding the appropriate registration, permit or licence, as required.

During construction, some of the subcontractors on-site will generate waste in relatively low quantities. The transportation of non-hazardous waste by persons who are not directly involved with the waste business, at weights less than or equal to 10 tonnes, and in vehicles not designed for the carriage of waste, are exempt from the requirement to have a waste collection permit under Article 10 of the Waste Collection Permit Regulations 2000, as amended. Any subcontractors engaged that do not generate more than 10 tonnes of waste at any one time can transport this waste on-site in their own vehicles which are not designed for the carriage of waste. However, they are required to ensure that the receiving facility has the appropriate permit/licence.

Written records will be maintained by the contractors, detailing the waste arising throughout the phases, the classification of each waste type, waste collection permits for all waste contractors who collect waste from the site and their permit/licence for the receiving waste facility for all waste removed on-site for appropriate reuse, recycling, recovery and disposal.

Dedicated bonded storage containers will be provided for hazardous wastes which may arise, such as batteries, paints, oils, chemicals, etc.

The anticipated management of the main waste streams is outlined as follows:

#### Soils and Subsoil

The waste hierarchy states that the preferred option for waste management is prevention and minimisation of waste, followed by repairing or reuse and recycling/recovery, energy recovery/incineration and, least favoured of all, disposal. The regulations are required to facilitate construction works so the preferred option prevention and minimisation cannot be accommodated for the excavation phase.

Material removed on-site should be reused as a by-product and not as a waste. If this is done, it will be done in accordance with Regulation 10 of the Waste Regulations 2000, as amended, or the European Communities Waste Directive Regulations 2000, (Previously Article 10 of the European Communities Waste Directive), which requires that certain conditions are met and that by-product notifications are made to the EPA via their online notification form. Appropriate material should not be removed from site until





Other Hazardous Wastes

On-site storage of any hazardous wastes produced from contaminated soil encountered and other waste materials will be kept to a minimum, with removal from site organised on a regular basis. Storage of all hazardous wastes on-site will be undertaken so as to minimise exposure to on-site personnel and the public and to also minimise potential for environmental impacts. Hazardous wastes will be recovered, wherever possible, and within this, disposed appropriately.

On-Site Crushing

It is currently not envisaged that the crushing of waste materials will occur on-site. However, if the crushing of material is to be undertaken, a mobile waste facility permit will first be obtained from EPA and the destination of the aggregate waste material will be supplied to the EPA waste unit.

**6.6 Tracking and Documentation Procedures for Off-Site Waste**

All waste will be documented prior to leaving the site. Waste will be weighed by the contractor, either by a weighing mechanism on the truck or at the receiving facility. These waste records will be maintained on site by the nominated project O&M (see Section 6.6.1).

All movement of waste and the use of waste contractors will be undertaken in accordance with the *Waste Management Acts 1996* as amended, *Waste Management (Collection Permit) Regulations 2007* as amended and *Waste Management (Facility Permit & Registration) Regulations 2007* and amended. This includes the requirement for all waste contractors to have a waste collection permit issued by the EPA. The nominated project O&M (see Section 6.6.1) will maintain a copy of all waste collection permits on-site.

When the waste is being transported to another site, a copy of the local Authority waste permit or EPA waste and industrial emissions licence for that site will be provided to the nominated project O&M (see Section 6.6.1). When the waste is being shipped abroad, a copy of the Transfrontier Shipping Notification document will be obtained from Dublin City Council as the relevant authority on behalf of all local Authorities in Ireland and kept on-site along with details of the final destination, permits, licences, etc. A receipt from the final destination of the material will be kept as part of the on-site waste management records.

All information will be entered in a waste management recording system to be maintained on-site.

**7.0 ESTIMATED COST OF WASTE MANAGEMENT**

An outline of the costs associated with different aspects of waste management is outlined below. The total cost of waste management will be measured and will take into account handling costs, storage costs, transportation costs, revenue from rebates and disposal costs.

**7.1 Reuse**

By reusing materials on-site, there will be a reduction in the transport and recycle/recovery/disposal costs associated with the requirement for a waste contractor to take the material

Site clean and inert soils, gravel, stones, etc, which cannot be reused on Site may be used as access roads or backfill material for landfill sites, etc. This material is often taken free of charge or at a reduced fee for such purposes, reducing final waste disposal costs.

**7.2 Recycling**

Salvageable metals will earn a rebate, which can be offset against the costs of collection and transportation of the soils.

Clean, uncontaminated cardboard and certain hard plastics can also be recycled. Waste contractors will charge considerably less to take segregated wastes, such as recyclable waste, from a site than mixed waste.

Timber can be recycled as chipboard. Again, waste contractors will charge considerably less to take segregated wastes, such as timber, from a site than mixed waste.

**7.3 Disposal**

Landfill charges are currently at around €130 - €150 per tonne which includes a €75 per tonne landfill levy specified in the *Waste Management (Landfill Levy) Regulations 2015*. In addition to disposal costs, waste contractors will also charge a collection fee for soils.

Collection of segregated waste usually costs less than municipal waste. Segregated waste contractors take the waste to a licensed or permitted facility and, where possible, remove salvageable items from the waste stream before disposal. The remainder to landfill - clean soil, rubble, etc, is also used as fill or backfill material, wherever possible.

**8.0 DEMOLITION PROCEDURES**

There will be waste materials generated from the demolition of buildings No's 7, 8 and 9 and renovation (Building No's 1) of the existing buildings and hardstanding areas on site to accommodate the new development. A formal demolition plan including safety procedures will be prepared by the demolition contractor. However, in general, the following sequence of works should be followed during the demolition stage.

Other or Hazards

Prior to commencing works, buildings and structures to be demolished will be checked for any likely hazards including asbestos, APMs, electrical power lines or cables, gas reticulation systems, telecommunications, unsafe structures and fire explosion hazards, inflammable dust, chemical hazards, oil, fuels and contamination.

Removal of Contents

All hazardous materials will be removed first. All contents from within the buildings that can be salvaged will be removed next. This will primarily be comprised of metal. However, may also include timbers, doors, windows, pipes and metal ducting, etc.



A waste transfer note should be used to track each waste movement from the site. On exit from the site, the waste collection vehicle driver should stop at the site office and sign out as a visitor and provide the security personnel or PM with a waste document for waste transfer form to record hazardous waste or the waste load collected. At this time, the security personnel should complete and sign the waste transfer register with the following information:

- Date
- Time
- Waste contractor
- Company waste contractor appointed by, employer contractor or subcontractor name
- Collection Permit No.
- Vehicle No.
- Driver Name
- Document No.
- Waste type
- No.
- Weight/quantity

The waste vehicle will be checked by security personnel or the PM to ensure it has the waste collection permit no. displayed and a copy of the waste collection permit in the vehicle before they are allowed to remove the waste from the site.

The waste transfer documents will be transferred to the PM on a weekly basis and can be placed in the waste transfer file. This information will be recorded onto the waste collection unit when requested.

Alternatively, each subcontractor that has engaged their own waste contractor will be required to maintain a similar waste transfer note with the waste documents as maintained on file and available for inspection on site by the main contractor as required. These subcontractor files will be merged with the main waste files.

Waste receipts from the receiving waste facility will also be obtained by the site contractors and retained. A copy of the waste collection Permits, Nos., Waste Facility Permits and Waste Licences will be maintained on site at all times and will be periodically checked by the PM. Subcontractors who have engaged their own waste contractors, should provide the main contractor with a copy of the waste collection permits and waste permit licence for the receiving waste facilities and maintain a copy on file, available for inspection on site as required.

### 11.0 OUTLINE WASTE AUDIT PROCEDURE

#### 11.1 Responsibility for Waste Audit

The appointed PM will be responsible for conducting a waste audit at the site during the project phase of the proposed development. Contact details for the nominated PM will be provided to the waste collection unit after the main contractor is appointed and prior to any material being removed from site.

### 11.2 Review of Records and Identification of Corrective Actions

A review of all waste management costs and the records for the waste generated and transported on-site should be undertaken midway through the construction phase of the proposed development.

If waste movements are not accounted for, the reasons for this should be established in order to see if and why the record keeping system has not been maintained. The waste records will be compared with the established recovery reuse recycling targets for the site. Each material type will be examined, in order to see where the largest percentage of waste generation is occurring. The waste management methods for each material type will be reviewed in order to highlight how the targets can be achieved.

On completion of the construction phase, a final report will be prepared, summarising the outcomes of waste management processes adopted and the total recycling reuse recovery figures for the development.

### 11.3 Pest Management

A pest control operator will be appointed as required to manage pest on-site during the demolition and construction phase of the project. Any and all wastes generated by staff will not be stored in open sites, but in closed waste receptacles. Any waste receptacles will be carefully managed to prevent leaks, odours and pest problems.

## 12.0 C&D ENVIRONMENTAL MITIGATION MEASURES

During the demolition and construction phase the project construction Environmental Management Plan (EMP) will be utilised in regard to implementing and managing all environmental management requirements.

This EMP explains the construction techniques and methodologies which will be implemented during demolition and construction of the proposed development.

The EMP mitigation measures will be implemented to ensure that pollution and nuisances arising from site clearance and construction activities is prevented where possible and managed in accordance with best practice environmental protection.

The EMP will be implemented and adhered to by the demolition and construction contractors and will be overseen and updated as required if site conditions change by the Project Manager, Environmental Manager, O&M and Operational Clerk of Works where relevant. All personnel working on the site will be trained in the implementation of the measures.

## 13.0 CONSULTATION WITH RELEVANT BODIES

### 13.1 Local Authority

Once demolition and construction contractors have been appointed and have appointed waste contractors, and prior to removal of any on-site waste materials on-site, details of the proposed destination of each waste stream will be provided to the local waste collection unit.





Waste Management Act 1996 as amended

Environmental Protection Agency Act 1992 as amended

Litter Pollution Act 1997 (SI 1997/104) as amended

4. Eastern Midlands Region Waste Management Plan 2000 – 2005

5. Regional Waste Management Planning Rules, *Draft The National Waste Management Plan for a Circular Economy (2023)*.

Department of the Environment and Local Government, *Waste Management – Changing Our Ways, A Policy Statement*

From the Construction Industry – *Recycling of Construction and Demolition Waste*.

Department of Communications, Climate Action and Environment, *Waste Action Plan for the Circular Economy - Ireland's National Waste Policy 2020-2025* (Set 2020)

DOA, *Whole of Government Circular Economy Strategy 2022-2023 'Living More, Using Less'* (2021)

Waste Management and Miscellaneous Provisions Act 1996

Environmental Protection Agency (EPA) 'Best Practice Guidelines for the Preparation of Resource and Waste Management Plans for Construction & Demolition Projects' (2021)

Department of the Environment, Heritage and Local Government, *Best Practice Guidelines on the Preparation of Waste Management Plans for Construction and Demolition Projects*

DOA and the Construction Industry Federation (CIB), *Construction and Demolition Waste Management – a handbook for Contractors and site Managers*

DOA, *Kildare County Development Plan 2023-2029*

Planning and Development Act 2000 (SI 2000/104) as amended

EPA, *Waste Classification – List of Waste & Determining if Waste is Hazardous or Non-Hazardous*

Local Authority, establishing criteria and procedures for the acceptance of waste at landfills pursuant to Article 10 and Annex 1 of Directive

Environmental Protection Agency (EPA), *National Waste Database Reports 1998 – 2020*

EPA and Galway-Mayo Institute of Technology (GMIT), *EPA Research Report 146 – A Review of Design and Construction Waste Management Practices in Selected Case Studies – Lessons Learned*



**Appendix 16.2: Landscape Designations**

RECEIVED: 18/07/2023

Kildare County Council Planning Department - Viewing Purposes Only



RC5 Pike Bridge

Royal Canal pNHA

RC4 Deey Bridge

RC12 Rye Water Aqueduct

RC2 Cope Bridge

Rye Water Valley/ Carton SAC

Royal Canal pNHA

Liffey Valley pNHA

RC3 Louisa Bridge

RL1 Leixlip Bridge

100 m 250 m 500 m

1 km

2 km

RL2 New Bridge

RL3 Celbridge Bridge



Adelphi Plaza  
George's Street Upper  
Dun Laoghaire  
Co. Dublin  
Ireland  
T +353 (1) 238 3100  
www.aecom.com

Project Title:

LIFFEY BUSINESS CAMPUS

Client:

KILDARE INNOVATION CAMPUS

LEGEND

Proposed Development Site

Study Area

Viewpoints

Protected Viewing Corridor

Architectural Conservation Areas

Ecological Designations

Special Area of Conservation (SAC)

Proposed Natural Heritage Area (pNHA)

Scenic Routes

Castletown / Celbridge

Views of and within Carton Demesne

Scenic View Point

Walking Routes

The Royal Canal Way

Arthur's Way Heritage Trail

Sli na Sláinte - Celbridge Kildare

Sli na Sláinte - Leixlip West

Sli na Sláinte - St. Catherine's Park Sli (Leixlip)

Sli na Sláinte - Leixlip Lucan Demesne

LCA County Kildare

Northern Lowlands

River Liffey

LCA South Dublin County

Liffey Valley

Newcastle Lowlands

Urban

AECOM Internal Project No:

60663890

Drawing Title:

LANDSCAPE DESIGNATIONS

Scale at A3: 1:20,000

Drawing No:

APPENDIX 16.2

Drawn: Chk'd: App'd: Date:

TS JS MH 12/06/2023