

Elevation 7: DCC3 East

1 : 200



Elevation 9: DCC5 East

1 : 200

00-ZZ-ML-A-ElevationMaterialKey	
	*Ventilation grille positioning strategy as indicated on Facade strategy in Design statement
M1	Buff brick, stretcher bond, light mortar
M2	Red brick, stretcher bond, light mortar
M3	Red brick, stretcher bond, dark red mortar to match
M4	Red brick banding with soldier course to top and bottom
M5	Red brick banding with protruding soldier course to top and bottom and PCC sill
M6	Precast concrete parapet capping
M7	PPC metal balcony & railing; for colour strategy ref. to Design Statement
M8	Recessed PPC aluminium RWP to Tower; for colour strategy ref. to Design Statement
M10	PPC aluminium window; for colour strategy ref. to Design Statement
M11	PPC aluminium door; for colour strategy ref. to Design Statement
M13	PPC metal entrance gate / railing; for colour strategy ref. to Design Statement
M15	Red brick, hit and miss detail
M16	Alternating red/buff sawtooth brick coursing panel with precast concrete head and base course
M17	Recessed entrance w/ alternating red/buff sawtooth brick, precast concrete surround & downstand
M18	Louvred screen to mechanical plant
M19	Alternating red/buff stretcher bond coursing; flush
M20	Buff brick soldier course
M21	Recessed panel of alternating red/buff stretcher bond coursing; alternating course recessed


+83.350 m Parapet Level
+78.850 m Parapet Level
+76.150 m Parapet Level
+72.700 m Parapet Level
+72.450 m Parapet Level
M1
M21 M6 M7 M2
+67.700 m Parapet Level
D3-Overrun R 77 +72450 mm
D3-15 +67450 mm
D3-14 +64525 mm
D3-13 +61600 mm
D3-12 +58675 mm
D3-11 +54500 mm
D3-10 +51725 mm
D3-09 +48800 mm
D3-08 +45575 mm
D3-07 +42500 mm
D3-06 +39425 mm
D3-05 +36350 mm
D3-04 +33275 mm
D3-03 +30200 mm
D3-02 +27125 mm
D3-01 +24050 mm
D3-00 +20200 mm
2700
3430
3080
3080
3080
3080
3080
3080