

Kilsaran Bellewstown Access & Road Improvements

Stage 1 Road Safety Audit

Kilsaran

October 2021

Kilsaran Bellewstown Access & Road Improvements

Stage 1 Road Safety Audit

September 2021

Notice

This document and its contents have been prepared and are intended solely for Kilsaran's information and use in relation to Kilsaran Bellewstown Access & Road Improvements project.

Traffico assumes no responsibility to any other party in respect of or arising out of or in connection with this document and / or its contents.

Document History

JOB NUMBER: 210061			DOCUMENT REF: 210061RPT001_RSA1_Rev_1			
1	Final Issue	JW	MD	MD	MD	28 Oct 2021
0	Draft Issue	JW	MD	MD	MD	21 Sept 2021
Revision	Purpose Description	Originated	Checked	Reviewed	Authorised	Date

Contents

Section	Page
1. Introduction	2
1.1 Report Context	2
1.2 Details of Site Inspection	2
1.3 The Road Safety Audit Team	2
1.4 Design Drawings Examined as Part of the Audit Process	2
1.5 Road Safety Audit Compliance	2
2. Road Safety Issues Identified	4
2.1 Problem: Errant Vehicles at Embankments	4
2.2 Problem: Loss of Control at Horizontal Curve	4
2.3 Problem: Field Access on Horizontal Curve	5
2.4 Problem: Stopping Sight Distance to Right Turning Vehicle	5
2.5 Problem: Drivers Not Aware of Quarry	6
3. Audit Team Statement	7
3.1 Certification & Purpose	7
3.2 Implementation of RSA Recommendations	7
3.3 Road Safety Audit Team Sign-Off	7
4. Designers Response	8
4.1 How the Designer Should Respond to the Road Safety Audit	8
4.2 Returning the Completed Feedback Form	8

List of Tables

Table 1.1 – Site Inspection Details	2
Table 1.2 – Audit Team Details	2
Table 1.3 – Designers Drawing List	2

List of Figures

Figure 2.1 – Example Where Horizontal Curve is Combined with Embankment	4
Figure 2.2 – Straight Approaches to Horizontal Curve	4
Figure 2.3 – Field Access Proximity to Curve	5
Figure 2.4 – Stopping Sight Distance to Stationary Right Turning Vehicle	5
Figure 4.1 – Road Safety Audit Sign-Off and Completion Process	8

Appendices

Appendix A	9
A.1 Road Safety Audit Feedback Form	9

1. Introduction

1.1 Report Context

This report describes the findings of a Stage 1 Road Safety Audit associated with the Kilsaran Bellewstown Access & Road Improvements project.

The Audit has been completed by Traffico Ltd. on behalf of Kilsaran.

1.2 Details of Site Inspection

Date	Daylight / Darkness	Weather & Road Conditions
Tuesday 14 th September 2021	Daylight	Sunny with clouds, dry roads.

Table 1.1 – Site Inspection Details

1.3 The Road Safety Audit Team

The members of the Road Safety Audit Team have been listed following:

Status	Name / Qualifications	TII Auditor Reference No:
Audit Team Leader (ATL)	Martin Deegan BEng(Hons) MSc CEng MIEI	MD101312
Audit Team Member (ATM)	Jason Walsh BEng (Hons) PCert (RSA) CEng MIEI	JW3362499
Audit Trainee (AT)	-	-

Table 1.2 – Audit Team Details

1.4 Design Drawings Examined as Part of the Audit Process

The following drawing(s) were examined as part of the Road Safety Audit (RSA) process:

Drawing No.	Drawing Title	Revision
03138-20-P-00 to 03138-20-P-08 (9 sheets)	Proposed New Access Road (L56172 to L1615) and Road Improvements to L1615	-
03138-20-P-09 (1 sheet)	Proposed Link Road Vertical Profile – Long Section	-

Table 1.3 – Designers Drawing List

1.5 Road Safety Audit Compliance

Procedure and Scope

This Road Safety Audit has been carried out in accordance with the procedures and scope set out in TII publication number GE-STY-01024 - Road Safety Audit.

As part of the road safety audit process, the Audit Team have examined only those issues within the design which relate directly to road safety.

Compliance with Design Standards

The road safety audit process is not a design check, therefore verification or compliance with design standards has not formed part of the audit process.

Minimizing Risk of Collision Occurrence

All problems described in this report are considered by the Audit Team to require action in order to improve the safety of the scheme and minimise the risk of collision occurrence.

Meath County Council - Viewing Purposes Only!


2. Road Safety Issues Identified

2.1 Problem: Errant Vehicles at Embankments

Location: Where Horizontal Curves are Combined with Embankments

The risk of injury to an errant vehicle's occupants is increased at locations where horizontal curves are combined with significant earth embankments.

Figure 2.1 – Example Where Horizontal Curve is Combined with Embankment



Recommendation


Appropriate vehicle restraint systems should be specified to contain errant vehicles at the locations described.

2.2 Problem: Loss of Control at Horizontal Curve

Location: Horizontal Curve at Link Road Chainage 800.0 K to Chainage 850.0 K

The long straight approaches to the (relatively) low radius curve could result in inappropriate entry speeds, leading to loss of control type collisions.

Figure 2.2 – Straight Approaches to Horizontal Curve



Recommendation


Warning signage should be provided for drivers on both approaches to (and also around) the horizontal curve.

2.3 Problem: Field Access on Horizontal Curve

Location: Horizontal Curve at Link Road Chainage 810.0 K

The envelope of visibility could be restricted by the geometry of the horizontal curve and boundary treatments. This could lead to conflicts between farm traffic and mainline traffic.

Figure 2.3 – Field Access Proximity to Curve



Recommendation


The field access should be moved to a point where an appropriate envelope of visibility can be provided.

2.4 Problem: Stopping Sight Distance to Right Turning Vehicle

Location: New Link Road T-Junction with Local Road. Link Road Chainage 1,815.0 K

The constraints of the existing local road may impede the Stopping Sight Distance to a stationary right turning vehicle. This could lead to rear end shunt type collisions.

Figure 2.4 – Stopping Sight Distance to Stationary Right Turning Vehicle



Recommendation

Appropriate Stopping Sight Distance should be provided along the Local Road to a stationary right turning vehicle.

2.5 Problem: Drivers Not Aware of Quarry

Location: Improved Quarry Access onto Local Road. Link Road Chainage 0.070 K

Drivers may not be aware of the quarry access. This could lead to conflicts with slow moving HGV's and / or vehicles turning into the quarry access in error.

Recommendation

Suitable signage should be provided on the local road approaches to warn road users that slow moving HGV's will be crossing the local road.

Meath County Council - Viewing Purposes Only!

3. Audit Team Statement

3.1 Certification & Purpose

We certify that we have examined the drawing(s) listed in Chapter 1 of this Report.

Sole Purpose of the Road Safety Audit

The Road Safety Audit has been carried out with the sole purpose of identifying any features of the design which could be removed or modified to improve the road safety aspects of the scheme.

3.2 Implementation of RSA Recommendations

The problems identified herein have been noted in the Report together with their associated recommendations for road safety improvements.

We (the Audit Team) propose that these recommendations should be studied with a view to implementation.

Audit Team's Independence to the Design Process

No member of the Audit Team has been otherwise involved with the design of the measures audited.

3.3 Road Safety Audit Team Sign-Off

Martin Deegan

Audit Team Leader

Road Safety Engineering Team

traffico

Signed:



Date:

21st September 2021

Jason Walsh

Audit Team Member

Road Safety Engineering Team

traffico

Signed:



Date:

21st September 2021

4. Designers Response

4.1 How the Designer Should Respond to the Road Safety Audit

The Designer should prepare an Audit Response for each of the recommendations using the Road Safety Audit Feedback Form attached in Appendix A.

When completed, this form should be signed by the Designer and returned to the Audit Team for consideration. See flow-chart following for further description.




Figure 4.1 – Road Safety Audit Sign-Off and Completion Process

4.2 Returning the Completed Feedback Form

The Designer should return the completed Road Safety Audit Feedback Form attached in Appendix A of this report to the following email address:

- Email address: martin@traffico.ie

The Audit Team will consider the Designer's response and reply indicating acceptance or otherwise of the Designers response to each recommendation.

Triggering the Need for an Exception Report

Where the Designer and the Audit Team cannot agree on an appropriate means of addressing an underlying safety issue identified as part of the audit process, an Exception Report must be prepared by the Designer on each disputed item listed in the audit report.

Appendix A

A.1 Road Safety Audit Feedback Form

Meath County Council - Viewing Purposes Only!

Road Safety Audit Feedback Form


Scheme: Kilsaran Bellewstown Access & Road Improvements

Audit Stage: Stage 1 Road Safety Audit

Audit Date: 21st September 2021


Problem Reference (Section 2)	Designer Response Section			Audit Team Response Section
	Problem Accepted (yes / no)	Recommended Measure Accepted (yes / no)	Alternative Measures or Comments	Alternative Measures Accepted (yes / no)
2.1	Y	Y	Appropriate vehicle restraint systems will be specified at the detailed design stages in accordance with current guidance and best practice. Sufficient verge space is included in the road cross-section to accommodate proprietary barrier systems.	Noted with thanks
2.2	Y	Y	The current layout drawings include 'SLOW' road markings in advance of bends and at junctions. At chainage 800-850 these road markings will be complemented by appropriate signing indicating the bend ahead and the need to reduce speed. The layout and design of signs and road markings will be finalised at the detailed design stage.	Noted with thanks
2.3	Y	Y	The road design has been updated. The proposed crossing point has been relocated to Chainage 940 which is a straight section of road approximately 100m east of the bend.	Noted with thanks
2.4	Y	Y	Visibility at the proposed access accords with the national roads design standards for the Design Speed of the receiving road. Forward visibility to a right turning vehicle is one step below the desirable distance. These matters are addressed in EIAR Section 12.4.4. It is proposed to mitigate this shortfall by providing advance warning signs of turning traffic and through the provision of high friction wearing course along the 120 m section of the southbound approach lane to the proposed new junction.	Noted with thanks
2.5	Y	Y	Advance warning signing and road markings will be incorporated on the approaches to the site access on L56172 Mullagh Road and at both ends of the proposed new link road between L1615 and L56172. The layout position and design of the signing on the public road will be finalised at the detailed design stage. The detailed design of the signage and road marking works will be agreed with Meath County Council and the works will be carried out by Meath County Council or an appointed and authorised agent of Meath County Council.	Noted with thanks

Designer's Name: Julian Keenan

Designer's Signature: 

Date: 28/10/2021

Audit Team's Name: Martin Deegan

Audit Team's Signature: 

Date: 28th October 2021



traffico

t: 087 948 3535

e: hello@traffico.ie

w: www.traffico.ie



APPENDIX 12.4: BEAUMONT BRIDGE STRUCTURAL ASSESSMENT

WS Atkins Stage 1 Structural Assessment Report
WS Atkins Stage 2 Structural Assessment Report

Beaumont Bridge Structural Assessment

Stage 2 Structural Assessment Report

Kilsaran

February 2022

Meath County Council - Viewing Purposes Only!

Notice

This document and its contents have been prepared and are intended solely as information for Kilsaran and use in relation to Beaumont Bridge Structural Assessment

WS Atkins Ireland Limited assumes no responsibility to any other party in respect of or arising out of or in connection with this document and/or its contents.

Document history

Revision	Purpose description	Originated	Checked	Reviewed	Authorised	Date
Rev 1.0	Issue for Review	RMcS	MG	MJ	MJ	25/02/2022

Client signoff

Client	Kilsaran
Project	Beaumont Bridge Structural Assessment
Job number	5210920
Client signature / date	

Contents

Chapter	Page
Executive Summary	1
1. Introduction	2
2. Description of the Structure	2
3. Visual Inspection	2
4. Summary of Stage 1 Structural Assessment	3
5. Structural Investigation Results	4
6. Stage 2 Structural Assessment	4
7. Conclusions	6
8. Recommendations	6
Appendices	
Appendix A. Structure Location Map	
Appendix B. Inspection Photographs	
Appendix C. Structural Investigation Report	
Appendix D. Stage 2 Structural Assessment	
Tables	
Table 4-1 Results of Stage 1 Modified MEXE Analysis	3
Table 4-2 Results of the Stage 1 Archie-M Analysis	4
Table 5-1 Results of the Structural Investigation	4
Table 6-1 Structure dimensions used in the Stage 2 Assessment	5
Table 6-2 Condition factors used in the Stage 2 Assessment	5
Table 6-3 Results of the Stage 2 Modified MEXE Analysis	5
Table 6-4 Results of the Stage 2 Archie-M Analysis	6

Executive Summary

MH-L1615-001.00 Beaumont Bridge is a seven span masonry arch structure carrying the L1615 local road over the River Nanny in the townland of Beaumont, Co. Meath. The structure has span widths varying between 2.31m and 4.51m with a total length of 44.65m and a width out to out of 7.5m. The structure shows evidence of historical widening works using masonry construction, with varying arch profiles and open joints evident below the structure.

The structure is a protected structure and is listed in the Record of Protected Structures within the Meath County Development Plan 2021-2027.

The structure is in an overall fair condition with minor areas of masonry and pointing loss found to the arch barrels, piers and abutments. Repointing works should be undertaken in order to restore these key structural elements to a good condition.

The depression noted to the carriageway surfacing and the scour damage to the riverbed are the defects of most concern. Repairs are recommended to be undertaken to the areas of scour damage below the structure with the mainline carriageway surfacing previously only extended to arch 3 over the structure now extended to beyond the south abutment. The grass verges over the structure should be replaced by either concrete verges or the extension of the carriageway surfacing to prevent further water ingress through the arch barrels.

The Stage 1 Structural Assessment (Report reference 5210920DG0001) found the structure to have a low load capacity of <3t and 3t for the lowerbound and upperbound conditions respectively. A Stage 2 Assessment was recommended to be undertaken to the structure in order to confirm the load capacity of the structure. Structural Investigation works were subsequently undertaken to the structure to determine the exact depth of fill above each arch barrel and the thickness of each arch barrel. The investigation works also confirmed the existing arch backing to be a silty clay material with minor cobble and boulder content.

The Stage 2 Structural assessment of the structure was undertaken in accordance with TII Publication AM-STR-06057 *Stage 2 Structural Assessment of Road Structures*. The structural assessment found the existing structure to have a reduced load capacity of less than 3t due to the shallow depth of fill above the structure and the reduced arch thicknesses of certain arch barrels. Despite the assessed low load capacity of the structure Beaumont Bridge is behaving satisfactorily under current loading with no load restriction currently in place.

The results from the Archie-M analysis shows that the presence of concrete backing to the arch barrels increases the load capacity of the structure to the required 46t capacity. The installation of low strength concrete backing is therefore recommended to the areas between the piers and above the abutments of the structure. Construction details for the concrete backing and subsequent resurfacing works are to be determined at detailed design stage of the proposed repair and strengthening works.

The recommended repair and strengthening works for the structure to be agreed in liaison with Meath County Council are as follows:

- Masonry repointing to the arch barrels, piers and abutments
- Installation of low strength concrete backing to the arch barrels
- Resurfacing of the carriageway over the structure
- Repairs to areas of undermining to the north abutment and northern piers
- Infilling of scour holes at the west elevation
- Removal of debris trapped at the west elevation of arch barrel 7
- Replacement of the grass verges with new concrete verges or extension of the carriageway pavement
- Vegetation removal and repointing to the parapets, spandrel walls and wing walls
- Vegetation clearance to the embankments

1. Introduction

Kilsaran engaged Atkins to undertake the structural assessment of MH-L1615-001.00 Beaumont Bridge in accordance with TII Publication *AM-STR-06056 Stage 1 Structural Assessment of Road Structures* to determine the current condition and load capacity of the existing structure. The structural assessment of the structure was undertaken in accordance with TII Publication *AM-STR-06026 The Assessment of Road Bridges and Structures*. The Stage 1 Structural Assessment (Report reference 5210920DG0001) found the structure to have a low load capacity of <3t and 3t for the lowerbound and upperbound conditions respectively. A Stage 2 Assessment was recommended to be undertaken to the structure in accordance with *AM-STR-06057 Stage 2 Structural Assessment of Road Structures* in order to confirm the load capacity of the structure.

2. Description of the Structure

MH-L1615-001.00 Beaumont Bridge is a seven span masonry arch structure carrying the L1615 local road over the River Nanny in the townland of Beaumont, Co. Meath. The structure has span widths varying between 2.31m and 4.51m with a total length of 44.65m and a width out to out of 7.5m. The structure shows evidence of historical widening works using masonry construction, with varying arch profiles and open joints evident below the structure.

The structure is a protected structure and is listed in the Record of Protected Structures within the Meath County Development Plan 2021-2027.

The location of the structure is shown on the location map in Appendix A of this report.

3. Visual Inspection

The Principal Inspection of the structure was undertaken in December 2021. The condition of each component of the structure is outlined below with photographs from the inspection provided in Appendix C of this report. For the purposes of inspection the arch barrels and piers and have been numbered in a north to south direction.

Bridge Surface

The carriageway surfacing over the structure is split into 2no. distinct sections, the local road surfacing and the newer tie in surfacing from the mainline R150 local road.

The newer tie in surfacing is in a good condition overall, with the local road surfacing showing a loss of skid resistance throughout with areas of surfacing loss and potholes forming. There is also an area of depression noted to the carriageway surface above pier 3. See Photograph B-1 to B-3 for details of the bridge surface.

Verges

Raised grass verges are present along the base of both parapets over the structure, with areas of water ingress noted to the arch barrels below. See Photograph B-4 and B-5 for both verges.

Parapets

The masonry parapets are in a good overall condition with minor vegetation removal and repointing required. See Photograph B-4 and B-5 for both parapets.

Embankments

The embankments at both elevations are in a fair overall condition with areas of vegetation clearance required to maintain access to the structure. See Photograph B-6 to B-9. There is large debris restricting access to arch 7, see Photograph B-29.

Wing/Spandrel walls

The wing and spandrel walls are in a fair condition overall with areas of vegetation growth and minor pointing loss evident. See Photograph B-10 and B-11 for the spandrel walls.

Abutments

The abutments are in a good overall condition apart from pointing loss and undermining to the north abutment below the waterline. The south abutment is mostly hidden below the mudline, see Photograph B-12 and B-13 for both abutments.

Piers

The piers are in a fair overall condition with minor areas of pointing loss to the pier faces and vegetation growth to the cutwaters. There is also 400mm deep undermining noted to pier 1 and 200mm deep undermining noted to pier 2 with masonry and pointing loss noted below the waterline, see Photograph B-14 to B-21 for the piers.

Arch Barrels

The masonry arch barrels are in a fair condition overall with minor masonry and pointing loss evident to localised areas throughout. Water ingress is evident to all arch barrels most likely due to the soft verges over the structure with a transverse crack also evident to the arch barrel of span 1 above the north abutment.

See Photograph B-22 to B-29 for the arch barrels.

Riverbed

The riverbed below the structure is in a poor condition due the extensive scour noted at the upstream elevation of spans 1 to 4, with scour depths of up to 500mm recorded. Undermining is evident to the piers in spans 1 and 2 as a result of the scour to the adjacent riverbed. Both the upstream and downstream watercourse are impacted by overgrown vegetation with the watercourse mainly channelled through arches 3 and 4 as a result.

See Photograph B-30 and B-31 for the riverbed.

Overall Structure

The structure is in an overall fair condition with minor areas of masonry and pointing loss found to the arch barrels, piers and abutments. The depression noted to the carriageway surfacing and the scour damage to the riverbed are the defects of most concern.

See Photograph B-32 and B-33 for both elevations of the structure.

4. Summary of Stage 1 Structural Assessment

The Stage 1 Structural Assessment of the structure was undertaken in January 2021 in accordance with TII Publication AM-STR-06056 *Stage 1 Structural Assessment of Road Structures*. The structural assessment found the existing structure to have a reduced load capacity of >3t and 3t for the lowerbound and upperbound conditions respectively, mainly due to the shallow depth of fill above the structure, estimated to be less than 100mm in places. Investigation works were therefore recommended to determine the exact depth of fill above each barrel and the thickness of each arch in order to undertake a Stage 2 Structural Assessment. The results of the Stage 1 Assessment are as outlined in Table 4-1 and 4-2 below.

Table 4-1 Results of Stage 1 Modified MEXE Analysis

	Max Gross Vehicle Weight (tonnes)	
	Upper Bound	Lower Bound
Arch Barrel 1	40t	18t
Arch Barrel 2	40t	40t

	Max Gross Vehicle Weight (tonnes)	
	Upper Bound	Lower Bound
Arch Barrel 3	18t	18t
Arch Barrel 4	18t	18t
Arch Barrel 5	40t	40t
Arch Barrel 6	40t	40t
Arch Barrel 7	40t	40t

Table 4-2 Results of the Stage 1 Archie-M Analysis

		Present Condition	Good Condition	Backing Present
HA Loading	Lowerbound	Fails 3t	Fails 3t	44t
	Upperbound	3t	3t	44t
SV Loading	Lowerbound	Fails SV80	Fails SV80	SV80
	Upperbound	Fails SV80	Fails SV80	SV100

For further detail on the Stage 1 Assessment please refer to the Stage 1 Structural Assessment Report (ref. 5210920DG0001).

5. Structural Investigation Results

Jons Civil Engineering Co. Ltd. were engaged to undertake structural investigations at Beaumont Bridge in order to determine each arch barrel thickness and the depth of fill above each arch, and also to confirm the backing material behind each pier. The structural investigation works were undertaken on 10th & 11th February with the key findings outlined in Table 5-1 below.

Table 5-1 Results of the Structural Investigation

	Dimension (m)						
	Arch 1	Arch 2	Arch 3	Arch 4	Arch 5	Arch 6	Arch 7
Arch Thickness	0.380	0.270	0.350	0.370	0.500	0.400	0.250
Depth of Fill	0.080	0.200	0.110	0.050	0.400	0.450	0.290

The pier backing material was found to be a silty clay material with minor cobble and boulder content. The investigation works also identified that the exposed crowns of the northern arch barrels in the east verge are above the adjacent road surfacing, possibly due to planing of the arch barrels at this location as part of surfacing works over the structure. Any planing works would have reduced the arch barrel thicknesses which would be a cause of concern for the structure.

For further details on the investigation results refer to the factual report in Appendix C of this document.

6. Stage 2 Structural Assessment

In accordance with the recommendations of the Stage 1 Assessment Report a Stage 2 Structural Assessment was undertaken to the arch barrels of Beaumont Bridge in accordance with AM-STR-06057 Stage 2 Structural

Assessment of Road Structures in order to confirm the load carrying capacity of the structure. As the piers and abutments had passed the Stage 1 Assessment they were not considered in the Stage 2 Assessment.

Arch Barrels

A structural assessment of the masonry arch barrels was undertaken using the modified MEXE method outlined in *AM-STR-06002 The Assessment of Road Bridges and Structures*. The structure dimensions surveyed on site by Atkins and the arch dimensions confirmed by the structural investigations are listed below in Table 6-1.

Table 6-1 Structure dimensions used in the Stage 2 Assessment

	Dimension (m)						
	Arch 1	Arch 2	Arch 3	Arch 4	Arch 5	Arch 6	Arch 7
Span	2.360	2.890	4.220	4.510	2.310	2.570	2.720
Rise at Crown	1.170	1.280	1.930	2.010	1.150	1.190	1.350
Rise at Quarter Point	1.050	1.020	1.560	1.660	0.960	1.030	1.100
Ring Thickness	0.380	0.270	0.350	0.370	0.500	0.400	0.250
Depth of Fill	0.080	0.200	0.110	0.050	0.400	0.450	0.290

Based on a visual inspection and the recommendations of *AM-STR-06002* Annex D, the condition factors used in the arch assessment are summarised in Table 6-2 below.

Table 6-2 Condition factors used in the Stage 2 Assessment

Condition Factor		Reasoning
Barrel Factor, F_b	1.0	Limestone in good overall condition
Fill Factor, F_f	0.7	Well compacted material
Joint Width Factor, F_w	0.9	Joint widths between 6mm and 12.5mm
Joint Depth factor, F_d	0.8	Loss of pointing evident, average depths 20mm
Joint Mortar factor, F_{mo}	1.0	Mortar in good condition
Condition Factor, F_{CM}	0.9	Good overall condition with pointing loss evident

The Modified MEXE analysis gives a live load capacity varying between 12.5 and 46 tonnes Gross Vehicle Weight (GVW) for all arch barrels, see Table 6-3 below.

Table 6-3 Results of the Stage 2 Modified MEXE Analysis

	Max Gross Vehicle Weight (tonnes)
Arch Barrel 1	46t
Arch Barrel 2	46t
Arch Barrel 3	18t
Arch Barrel 4	12.5t
Arch Barrel 5	46t
Arch Barrel 6	46t
Arch Barrel 7	46t

As the structure is a multi-span arch structure the guidance given in *AM-STR-06026* was followed with the results from the MEXE analysis corroborated with the results of the three-hinge limit analysis method using Archie-M software. Archie-M analysis was carried out on the structure for both HA and SV assessment loading.

The Archie-M analysis carried out on the structure determined that the existing structure has a less than 3t load capacity. See Table 6-4 below for a summary of the Archie-M analysis results.

Table 6-4 Results of the Stage 2 Archie-M Analysis

	Present Condition	Good Condition	Backing Present
HA Loading	Fails 3t	Fails 3t	46t
SV Loading	Fails SV80	Fails SV80	SV100

The results from the Archie-M analysis shows that the third condition comprising the presence of backing to the arch barrels greatly increases the load capacity of the structure to 46t. The installation of a low strength concrete backing is therefore recommended to the structure.

See Appendix D of this report for the calculations and outputs from both the MEXE and Archie-M analysis.

7. Conclusions

The structure is in an overall fair condition with minor areas of masonry and pointing loss found to the arch barrels, piers and abutments. Repointing works should be undertaken in order to restore these key structural elements to a good condition.

The depression noted to the carriageway surfacing and the scour damage to the riverbed are the defects of most concern. Repairs are recommended to be undertaken to the areas of scour damage below the structure with the mainline carriageway surfacing previously only extended to arch 3 over the structure now extended to beyond the south abutment. The grass verges over the structure should be replaced by concrete verges to prevent further water ingress through the arch barrels.

The low <3t load capacity found for the existing structure is due to the shallow depths of fill over the structure, measured less than 100mm in places by the structural investigation works. Despite the assessed low load capacity of the structure Beaumont Bridge is behaving satisfactorily under current loading with no load restriction currently in place.

The results from the Archie-M analysis shows that the presence of concrete backing to the arch barrels increases the load capacity of the structure to the required 46t capacity. The installation of low strength concrete backing is therefore recommended to the areas between the piers and above the abutments of the structure. Construction details for the concrete backing and subsequent resurfacing works are to be determined at detailed design stage of the proposed repair and strengthening works.

8. Recommendations


The recommended repair and strengthening works for the structure to be agreed in liaison with Meath County Council are as follows:

- Masonry repointing to the arch barrels, piers and abutments
- Installation of low strength concrete backing to the arch barrels
- Resurfacing of the carriageway over the structure
- Repairs to areas of undermining to the north abutment and northern piers
- Infilling of scour holes at the west elevation
- Removal of debris trapped at the west elevation of arch barrel 7
- Replacement of the grass verges with new concrete verges or extension of the carriageway pavement
- Vegetation removal and repointing to the parapets, spandrel walls and wing walls
- Vegetation clearance to the embankments

Appendices

Appendix A. Structure Location Map

Meath County Council - Viewing Purposes Only!



ATKINS

Member of the SNC-Lavalin Group

Beaumont Bridge Assessment

© ORDNANCE SURVEY IRELAND LICENSE No. AR 0082521.
ORDNANCE SURVEY IRELAND & GOVERNMENT OF IRELAND

Appendix B. Inspection Photographs



Photograph B-1 – Bridge surface looking south



Photograph B-2 – Bridge surface looking north



Photograph B-3 – Area of depression to carriageway surface above pier 3. Note tie into R150 road surfacing above arch 3.



Photograph B-4 – West parapet and grass verge



Photograph B-5 – East parapet and grass verge



Photograph B-6 – NW embankment with overgrown vegetation evident



Photograph B-7 – NE embankment with overgrown vegetation evident



Photograph B-8 – SW embankment with overgrown vegetation evident



Photograph B-9 – SE embankment with overgrown vegetation evident



Photograph B-10 – West spandrel wall with minor vegetation growth evident



Photograph B-11 – East spandrel wall with minor vegetation growth evident



Photograph B-12 – North abutment with pointing loss and undermining evident below waterline



Photograph B-13 – South abutment



Photograph B-14 – North face of pier 1 with undermining evident



Photograph B-15 – West cutwater of pier 1 with vegetation growth evident



Photograph B-16 – North face of pier 2 with vegetation growth evident



Photograph B-17 – West cutwater of pier 3 with vegetation growth evident



Photograph B-18 – South face of pier 3



Photograph B-19 – West cutwater of pier 4 with vegetation growth evident



Photograph B-20 – South face of pier 4



Photograph B-21 – South face of pier 5




Photograph B-22 – Transverse crack to the bottom of arch barrel 1 above the north abutment



Photograph B-23 – Arch barrel 1 with pointing loss and water ingress evident



Photograph B-24 – Arch barrel 2 with pointing loss, minor masonry loss and water ingress evident



Photograph B-25 – Arch barrel 3 with dropped stones, minor masonry loss and pointing loss evident



Photograph B-26 – Arch barrel 4 with minor pointing loss evident and recent repointing works visible



Photograph B-27 – Arch barrel 5 with water ingress and minor pointing loss evident with a change in the arch profile evident



Photograph B-28 – Arch barrel 6 with water ingress and minor pointing loss evident



Photograph B-29 – Arch barrel 7 with water ingress and minor pointing loss evident and debris located at the west elevation with a change in the arch profile evident




Photograph B-30 – View of downstream riverbed



Photograph B-31 – View of upstream riverbed with watercourse main channel through arches 3 and 4



Photograph B-32 – View of east elevation



Photograph B-33 – View of west elevation

Appendix C. Structural Investigation Report

Jons Civil Engineering Co. Ltd.

Investigation Works at MH-L1615-001.00

Brief

- 7no. slit trenches in the west soft verge to confirm the arch thickness and depth of fill of each arch (to include presence of any services)
- 6no. trial excavations in the east soft verge above each pier to confirm the presence of any backing material, maximum expected depth of 1.5m be. low carriageway level (to include presence of any services)
- CAT scans to both verges prior to works commencing in order to determine the presence of any services

INTRODUCTION

Jons Civil Engineering Limited (JCEL) were employed by Kilsaran to carry out site investigations to facilitate a Stage 2 Structural Assessment by Atkins.

JCEL submitted a T1 License Request to Meath County Council for the works which was issued on the 10/02/2022. JCEL commenced the works on 10/02/2022 and completed on 11/02/2022.

As part of the investigation JCEL carried out the following;

- Desktop survey of services in area (see attached service drawings in Appendix A)
- Precondition photographic survey of the road and verge condition
- Temporary Traffic Management (TTM) for the works
- 7no. Slit trenches carried out in west soft verge to determine arch thickness
- 2 no. trial excavations carried out in East soft verge at main pier locations to confirm presence of any backing material
- 7no. Slit trenches carried out in East soft verge to determine arch thickness
- 6 no. trial excavations carried out in west soft verge at main pier locations to confirm presence of any backing material
- 1 no. trial excavation carried out on MH-L1615-002.00 (Beaumont Bridge) to determine depth to soffit
- De-Vegetation on East parapet wall.

Precondition Survey




West Elevation




East Elevation

East Verge







Meath County Council - Viewing Purposes Only!

West Verge





Beaumont Bridge




Service Location

JCEL requested service drawings from all the major utility providers. EIR, ESB and GNI drawings are included in appendix A.

No ESB or GNI service is located on the structure, EIR service drawings show an overhead service (visual confirmation on site) and buried service on the East Verge.


CAT scan survey was carried out on both verges and carriageway using an RD7000 and signal generator. No buried services were detected. After completing trial holes we can confirm that there are no buried services within the verge. Upon inspection of the overhead service, it appears that the cable being identified as buried is actually overhead (two cables present overhead).

Top of Arch Trail Holes



Span Ref	West	East
A	0.38	0.35
B	0.27	0.4
C	0.35	0.42
D	0.37	0.32
E	0.5	0.525
F	0.4	0.42
G	0.25	0.45

Table A 1 Arch Thickness



SPAN A	
East (Trail Hole 1)	West (Trial Hole 15)
 1.7 to bottom of key stone 1.35m to top of arch (measured from parapet)	 1.78 to bottom of key stone 1.4m to top of arch (measured from parapet) 80mm below road
SPAN B	
East (Trial Hole 2)	West (Trial Hole 14)
1.8 to bottom of key stone 1.4m to top of arch (measured from parapet)	 1.8 to bottom of key stone 1.53m to top of arch (measured from parapet) 200mm below road

SPAN C	
East (Trial Hole 3)	West (Trial Hole 13)
 1.85 to bottom of key stone 1.43m to top of arch (measured from parapet)	 1.8 to bottom of key stone 1.45m to top of arch (measured from parapet) 110mm below road
SPAN D	
East (Trial Hole 4)	West (Trial Hole 12)
1.57 to bottom of key stone 1.25m to top of arch (measured from parapet) Top of arch is above road level	 1.8 to bottom of key stone 1.43m to top of arch (measured from parapet) 50mm below road

SPAN E		
East (Trial Hole 5)		West (Trial Hole 11)
2.385 to bottom of key stone 1.86m to top of arch (measured from parapet) 100mm below road		 1.95 to bottom of key stone 1.45m to top of arch (measured from parapet) (Back of key stone) 0.4m below road. (measures 1.55m nearer to road) arch thickness taken as 0.4m.
SPAN F		
East (Trial Hole 6)		West (Trial Hole 10)
 2.35 to bottom of key stone 2.08m to top of arch (measured from parapet) 650mm below road		 1.95 to bottom of key stone 1.55m to top of arch (measured from parapet) 0.45m below road.

SPAN G		
East (Trial Hole 7)		West (Trial Hole 9)
1.9 to bottom of key stone 1.45m to top of arch (measured from parapet) 350mm below road		 1.53 to bottom of key stone 1.28m to top of arch (measured from parapet) 0.29m below road.



Beaumont Bridge (Trial Hole 8)

Concrete slab 2.35 from top of parapet to underside of deck, 2.08m to top of deck, depth of fill 850mm. Fill is a Gravely SILT with cobble content. No water proofing evident.

Pier Surveys - East Side

Pier 1



660mm depth below road, fill is a gravely SILT. Both arches meet (very narrow pier). Dip to ground level = 3.65m, refusal at 1.95m.

Pier 2



Dip to ground level from parapet 4m. Bottom of trail hole = 2.28. Refusal was stone + mortar.

Depth below road 1.03m

Pier 3



Dip to ground level = 4.35m, refusal at 2.63m. Depth below road at 1.2m.

SILT Backfill, with some cobble content (50-80mm) and some boulder content (max 200mm)

Pier 4



1.4m below road to solid. Fill is stoney, SILT cobbles and some boulders up to 200mm.

Dip from top of parapet to ground level 4.35m. Parapet to bottom of trial hole 2.7m.


Pier 5



1.2m below road to solid. Fill is brown silty sandy CLAY with small cobbles. Trial hole terminated once solid material encountered at 1.2m depth, lime mortar evident at bottom of hole.

Dip from top of parapet to ground level 4.1m. Parapet to bottom of trial hole 2.5m.

Pier 6




1.5m below road to solid. Fill is silty CLAY with small cobble content.

Dip from top of parapet to ground level 3.8m. Parapet to bottom of trial hole 2.7m.

Pier 2 (West)



Dip to ground level = 4.2m, dip to refusal = 1.93m, 600mm below road level. Fill has a high cobble content and is a GRAVELy Silt.



Pier 4 (West)

Dip to ground level = 4.48m, dip to refusal = 2.4m, 1.08m below road level. Fill has a high cobble content and is a GRAVELy Silt.

Post Condition Survey



Appendix D. Stage 2 Structural Assessment

Meath County Council - Viewing Purposes Only!

ATKINS		Project	Beaumont Bridge Stage 2 Assessment		Job ref 5210920	
		Structure No. MH-L1615-001.00	Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no.	rev 0
		Drawing Ref -	Calc By MG	Date 22-Feb-22	Check by MJ	Date 23-Feb-22
Ref	Calculations				Output	
TII	Modified MEXE Method - Span 1					
AM-STR-06002	Span	L in m				2.360
	Rise at Crown	r _c in m				1.170
	Rise at Quarter point	r _q in m				1.050
	Ring Thickness	d in m				0.380
	Depth of fill	h in m				0.080
	Barrel Factor	F _b				1.000
	Fill Factor	F _f				0.700
	Joint Width Factor	F _w				0.900
	Joint Mortar Factor	F _{mo}				1.000
	Horizontal Curve Radius	r in m				>600
	$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	$F_A = 1 + \frac{0.20 v^2}{r}$			1.000
	Joint Depth Factor	F _d				0.020
	Average depth of missing mortar, in m					
Annex G	=>	F _d				0.800
	Condition Factor	F _{cm}				0.900
		h + d in m				0.460
		L / r _c				2.017
	From Fig. 3.2 Nonogram	P.A.L.				
	Provisional Axle Loading	or $740 \times \frac{(d + h)^2}{L^{1.3}} = P.A.L.$				51.28
From Fig. 3.3	Span/Rise Factor	F _{sr}				1.000
From Fig. 3.4	Profile Factor	$F_p = 2.3 \times [(r_c - r_q)/r_c]^{0.6}$				0.587
	Material Factor	$F_m = \frac{(F_b \times d) + (F_f \times h)}{h + d}$				0.948
	Joint Factor	$F_j = F_w \times F_{mo} \times F_d$				0.720
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L)	$M.A.L = F_{sr} \times F_p \times F_m \times F_j \times F_{cm} \times P.A.L$				18.475
	AXLE FACTOR (A _f - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N)	☒			
	Single axle -	1.00 Allowable A.L				18.5
	2-Axle bogie	0.66 Allowable A.L				12.2
	3-Axle bogie	1.00 Allowable A.L				18.5
	LOAD CAPACITY	Max G.V.W in tonnes =				46

Project		Beaumont Bridge Stage 2 Assessment		Job ref 5210920	
		Structure No. MH-L1615-001.00	Assessment using TII AM-STR-06002 MEXE Method	Calc sheet no.	rev
		Drawing Ref -	Calc By MG	Date 22-Feb-22	Check by MJ Date 23-Feb-22
Ref	Calculations				Output
TII AM-STR-06002	Modified MEXE Method - Span 2				
Span	L in m				2.890
Rise at Crown	r_c in m				1.280
Rise at Quarter point	r_q in m				1.020
Ring Thickness	d in m				0.270
Depth of fill	h in m				0.200
Barrel Factor	F_b				1.000
Fill Factor	F_f				0.700
Joint Width Factor	F_w				0.900
Joint Mortar Factor	F_{mo}				1.000
Horizontal Curve Radius	r in m				>600
$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	$F_A = 1 + \frac{0.20 v^2}{r}$			1.000
Joint Depth Factor	F_d				
Average depth of missing mortar, in m					0.020
Annex G	=>	F_d			0.800
Condition Factor	F_{cm}				0.900
	h + d in m				0.470
	L / r_c				2.258
From Fig. 3.2 Nonogram	Provisional Axle Loading	P.A.L.			
		or $740 \times \frac{(d + h)^2}{L^{1.3}} = P.A.L.$			41.14
From Fig. 3.3	Span/Rise Factor	F_{sr}			1.000
From Fig. 3.4	Profile Factor	$F_p = 2.3 \times [(r_c - r_q)/r_c]^{0.6}$			0.884
	Material Factor	$F_m = \frac{(F_b \times d) + (F_f \times h)}{h + d}$			0.872
	Joint Factor	$F_j = F_w \times F_{mo} \times F_d$			0.720
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L)	$M.A.L = F_{sr} \times F_p \times F_m \times F_j \times F_{cm} \times P.A.L$			20.555
	AXLE FACTOR				
(A_r - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N)	☒			
Single axle -	1.00	Allowable A.L			20.6
2-Axle bogie	0.66	Allowable A.L			13.6
3-Axle bogie	1.00	Allowable A.L			20.6
LOAD CAPACITY	Max G.V.W in tonnes =				46

ATKINS		Project	Beaumont Bridge Stage 2 Assessment		Job ref 5210920	
		Structure No. MH-L1615-001.00		Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no. rev 0
		Drawing Ref -	Calc By MG	Date 22-Feb-22	Check by MJ	Date 23-Feb-22
Ref	Calculations				Output	
TII	Modified MEXE Method - Span 3					
AM-STR-06002	Span	L in m				4.220
	Rise at Crown	r _c in m				1.930
	Rise at Quarter point	r _q in m				1.560
	Ring Thickness	d in m				0.350
	Depth of fill	h in m				0.110
	Barrel Factor	F _b				1.000
	Fill Factor	F _f				0.700
	Joint Width Factor	F _w				0.900
	Joint Mortar Factor	F _{mo}				1.000
	Horizontal Curve Radius	r in m				>600
	$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	F _A =	1 +	$\frac{0.20 v^2}{r}$	1.000
	Joint Depth Factor	F _d				0.020
	Average depth of missing mortar, in m					0.020
Annex G	=>	F _d				0.800
	Condition Factor	F _{cm}				0.900
		h + d in m				0.460
		L / r _c				2.187
	From Fig. 3.2 Nonogram Provisional Axle Loading	P.A.L. or 740 x $\frac{(d + h)^2}{L^{1.3}} = \text{P.A.L.}$				24.09
From Fig. 3.3	Span/Rise Factor	F _{sr}				1.000
From Fig. 3.4	Profile Factor	F _p = $2.3 \times [(r_c - r_q)/r_c]^{0.6}$				0.854
	Material Factor	F _m = $\frac{(F_b \times d) + (F_f \times h)}{h + d}$				0.928
	Joint Factor	F _j = F _w x F _{mo} x F _d				0.720
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L)	M.A.L = F _{sr} x F _p x F _m x F _j x F _{cm} x P.A.L				12.371
	AXLE FACTOR (A _f - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N)	☒			
	Single axle -	1.03 Allowable A.L				12.8
	2-Axle bogie	0.66 Allowable A.L				8.2
	3-Axle bogie	1.00 Allowable A.L				12.4
	LOAD CAPACITY	Max G.V.W in tonnes =				18

ATKINS		Project	Beaumont Bridge Stage 2 Assessment		Job ref 5210920
		Structure No. MH-L1615-001.00	Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no. rev 0
		Drawing Ref -	Calc By MG	Date 22-Feb-22	Check by MJ Date 23-Feb-22
Ref	Calculations				Output
TII AM-STR-06002	Modified MEXE Method - Span 4				
Span	L in m				4.510
Rise at Crown	r_c in m				2.010
Rise at Quarter point	r_q in m				1.660
Ring Thickness	d in m				0.370
Depth of fill	h in m				0.050
Barrel Factor	F_b				1.000
Fill Factor	F_f				0.700
Joint Width Factor	F_w				0.900
Joint Mortar Factor	F_{mo}				1.000
Horizontal Curve Radius	r in m				>600
$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	$F_A = 1 + \frac{0.20 v^2}{r}$			1.000
Joint Depth Factor	F_d				0.020
Average depth of missing mortar, in m					0.020
Annex G	=>	F_d			0.800
Condition Factor	F_{cm}				0.900
	h + d in m				0.420
	L / r_c				2.244
From Fig. 3.2 Nonogram Provisional Axle Loading	P.A.L.	or $740 \times \frac{(d+h)^2}{L^{1.3}} = P.A.L.$			18.42
From Fig. 3.3	Span/Rise Factor	F_{sr}			1.000
From Fig. 3.4	Profile Factor	$F_p = 2.3 \times [(r_c - r_q)/r_c]^{0.6}$			0.806
	Material Factor	$F_m = \frac{(F_b \times d) + (F_f \times h)}{h + d}$			0.964
	Joint Factor	$F_j = F_w \times F_{mo} \times F_d$			0.720
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L.)	$M.A.L. = F_{sr} \times F_p \times F_m \times F_j \times F_{cm} \times P.A.L.$			9.275
	AXLE FACTOR (A_f - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N) ☒			
	Single axle -	1.07 Allowable A.L.			10.0
	2-Axle bogie	0.67 Allowable A.L.			6.2
	3-Axle bogie	1.00 Allowable A.L.			9.3
	LOAD CAPACITY	Max G.V.W in tonnes =			12.5

ATKINS		Project	Beaumont Bridge Stage 2 Assessment		Job ref 5210920	
		Structure No. MH-L1615-001.00	Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no.	rev 0
		Drawing Ref -	Calc By MG	Date 22-Feb-22	Check by MJ	Date 23-Feb-22
Ref	Calculations				Output	
TII	Modified MEXE Method - Span 5					
AM-STR-06002	Span	L in m				2.310
	Rise at Crown	r_c in m				1.150
	Rise at Quarter point	r_q in m				0.960
	Ring Thickness	d in m				0.500
	Depth of fill	h in m				0.400
	Barrel Factor	F_b				1.000
	Fill Factor	F_f				0.700
	Joint Width Factor	F_w				0.900
	Joint Mortar Factor	F_{mo}				1.000
	Horizontal Curve Radius	r in m				>600
	$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	$F_A = 1 + \frac{0.20 v^2}{r}$			1.000
	Joint Depth Factor	F_d				0.020
	Average depth of missing mortar, in m					
Annex G	=>	F_d				0.800
	Condition Factor	F_{cm}				0.900
		h + d in m				0.900
		L / r_c				2.009
	From Fig. 3.2 Nonogram	P.A.L.	or $740 \times \frac{(d+h)^2}{L^{1.3}} = P.A.L.$			
	Provisional Axle Loading					70.00
From Fig. 3.3	Span/Rise Factor	F_{sr}				1.000
From Fig. 3.4	Profile Factor	$F_p = 2.3 \times [(r_c - r_q)/r_c]^{0.6}$				0.781
	Material Factor	$F_m = \frac{(F_b \times d) + (F_f \times h)}{h + d}$				0.867
	Joint Factor	$F_j = F_w \times F_{mo} \times F_d$				0.720
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L)	$M.A.L = F_{sr} \times F_p \times F_m \times F_j \times F_{cm} \times P.A.L$				30.696
	AXLE FACTOR (A_f - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N)	☒ Y			
	Single axle -	1.00	Allowable A.L			30.7
	2-Axle bogie	0.66	Allowable A.L			20.3
	3-Axle bogie	1.00	Allowable A.L			30.7
	LOAD CAPACITY	Max G.V.W in tonnes =				46

ATKINS		Project	Beaumont Bridge Stage 2 Assessment		Job ref 5210920
		Structure No. MH-L1615-001.00	Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no. rev 0
		Drawing Ref -	Calc By MG	Date 22-Feb-22	Check by MJ Date 23-Feb-22
Ref	Calculations				Output
TII AM-STR-06002	Modified MEXE Method - Span 6				
Span	L in m				2.570
Rise at Crown	r _c in m				1.190
Rise at Quarter point	r _q in m				1.030
Ring Thickness	d in m				0.250
Depth of fill	h in m				0.290
Barrel Factor	F _b				1.000
Fill Factor	F _f				0.700
Joint Width Factor	F _w				0.900
Joint Mortar Factor	F _{mo}				1.000
Horizontal Curve Radius	r in m				>600
$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	$F_A = 1 + \frac{0.20 v^2}{r}$			1.000
Joint Depth Factor	F _d				0.020
Average depth of missing mortar, in m					0.020
Annex G	=>	F _d			0.800
Condition Factor	F _{cm}				0.900
	h + d in m				0.540
	L / r _c				2.160
From Fig. 3.2 Nonogram Provisional Axle Loading	P.A.L.	or	$740 \times \frac{(d + h)^2}{L^{1.3}} = \text{P.A.L.}$		63.26
From Fig. 3.3	Span/Rise Factor	F _{sr}			1.000
From Fig. 3.4	Profile Factor	F _p	$= 2.3 \times [(r_c - r_q)/r_c]^{0.6}$		0.690
	Material Factor	F _m	$= \frac{(F_b \times d) + (F_f \times h)}{h + d}$		0.839
	Joint Factor	F _j	$= F_w \times F_{mo} \times F_d$		0.720
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L.)	M.A.L.	$= F_{sr} \times F_p \times F_m \times F_j \times F_{cm} \times \text{P.A.L.}$		23.728
	AXLE FACTOR (A _r - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N)	☒ Y		
	Single axle -	1.00	Allowable A.L.		23.7
	2-Axle bogie	0.66	Allowable A.L.		15.7
	3-Axle bogie	1.00	Allowable A.L.		23.7
	LOAD CAPACITY	Max G.V.W in tonnes =			46

ATKINS		Project	Beaumont Bridge Stage 2 Assessment		Job ref 5210920	
		Structure No. MH-L1615-001.00	Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no.	rev 0
		Drawing Ref -	Calc By MG	Date 22-Feb-22	Check by MJ	Date 23-Feb-22
Ref	Calculations					Output
TII AM-STR-06002	Modified MEXE Method - Span 7					
	Span	L in m				2.720
	Rise at Crown	r _c in m				1.350
	Rise at Quarter point	r _q in m				1.100
	Ring Thickness	d in m				0.250
	Depth of fill	h in m				0.290
	Barrel Factor	F _b				1.000
	Fill Factor	F _f				0.700
	Joint Width Factor	F _w				0.900
	Joint Mortar Factor	F _{mo}				1.000
	Horizontal Curve Radius	r in m				>600
	$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	F _A	=	$1 + \frac{0.20 v^2}{r}$	1.000
	Joint Depth Factor	F _d				0.020
	Average depth of missing mortar, in m					
Annex G	=>	F _d				0.800
	Condition Factor	F _{cm}				0.900
		h + d in m				0.540
		L / r _c				2.015
	From Fig. 3.2 Nonogram Provisional Axle Loading	P.A.L. or $740 \times \frac{(d + h)^2}{L^{1.3}} = P.A.L.$				58.76
From Fig. 3.3	Span/Rise Factor	F _{sr}				1.000
From Fig. 3.4	Profile Factor	F _p = $2.3 \times [(r_c - r_q)/r_c]^{0.6}$				0.836
	Material Factor	F _m = $\frac{(F_b \times d) + (F_f \times h)}{h + d}$				0.839
	Joint Factor	F _j = F _w × F _{mo} × F _d				0.720
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L)	M.A.L = F _{sr} × F _p × F _m × F _j × F _{cm} × P.A.L				26.709
	AXLE FACTOR (A _f - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N)			☒	
	Single axle -	1.00 Allowable A.L				26.7
	2-Axle bogie	0.66 Allowable A.L				17.6
	3-Axle bogie	1.00 Allowable A.L				26.7
	LOAD CAPACITY	Max G.V.W in tonnes =				46

ATKINS

Project

Beaumont Bridge Stage 2 Assessment

Job ref

5210920

Structure No.

MH-L1615-001.00

Assessment using TII AM-STR-

06002 MEXE Method

Calc sheet no. rev

0

Drawing Ref

-

Calc By

MG

Date

22-Feb-22

Check by

MJ

Date

23-Feb-22

Ref

Calculations

Output

TII

AM-STR-06002

Modified MEXE Method - Summary**Max Gross Vehicle Weight (tonnes)**

MEXE Span 1	46
MEXE Span 2	46
MEXE Span 3	18
MEXE Span 4	12.5
MEXE Span 5	46
MEXE Span 6	46
MEXE Span 7	46

Project	Beaumont Bridge Stage 2 Assessment		Job ref 5210920	
Part of Structure MH-L1615-001.00	Archie M analysis		Calc sheet no.	rev 0
Drawing Ref -	Calc By MG	Date 22-Feb-22	Check by MJ	Date 23-Feb-22

Ref

Calculations

Output

Summary of Load Cases (Highlighted in bold) Considered in ArchieM Analysis

 Axle Lift Off: Yes/No? **Yes**
Case 1: Most onerous AWR vehicle

- 1A : In present condition
- 1B : In perfect condition
- 1C : If backing is also present

Case 2: SV Loading

- 2A : In present condition
- 2B : In perfect condition
- 2C : If backing is also present

Summary of Results

1A	1B	1C
Fails 3t	Fails 3t	46t
2A	2B	2C
Fails SV80	Fails SV80	SV100

		Project	Beaumont Bridge Stage 2 Assessment		Job ref 5210920	
		Part of Structure MH-L1615-001.00		Archie M analysis		Calc sheet no. rev 0
		Drawing Ref -	Calc By MG	Date 22-Feb-22	Check by MJ	Date 23-Feb-22
Ref	Calculations				Output	
	Arch Assessment using ArchieM				Remarks	
TII AM-STR-06026	General Archie Input					
Table 3.1	Thickness of road surfacing	=	0.1	m	road surfacing only	
Table 4.1	Unit weight of road surfacing	=	23	kN/m3		
Fig 4.3	Masonry comp. strength	=	7	N/mm2		Material: Limestone
Table 4.1	Density	=	22	kN/m3		Ashlar/Random?: Random Rubble
	Unit weight of fill	=	18	kN/m3	(default in Archie)	with lime mortar
	phi	=	30		(default in Archie)	
	Arch Dimensions					
	Refer to MEXE Analysis for dimensions of each span					
	Lane & Load details					
TII AM-STR-06026	Load assessment 40t vehicle					
	Structure loaded with		46	t vehicle		
	Load per axle	=	11.5	t		
	Lane width	=	2.5	m	(this is the most conservative lane width)	
6.22	Distributed width of wheel load	=	1.5 + h			
6.23	As per Cl.6.23 TII AM-STR-06026 Axles have 1.8m track with 0.7m minimum spacing between the track width of adjacent vehicles					
TII AM-STR-06048	Load assessment SV100 vehicle					
	Archie M does not allow load assessment of SV100 vehicle on lanes less than 3.5m					
	Use the more critical of 3.5m lanewidth or actual lane width in analysis					
	Structure loaded with		100	t vehicle		
	Load per axle	=	16.5	t		
	Lane width	=	3.5	m		
	Distributed width of wheel load	=	1.5 + h			
	Axles assumed to have 3.0m track with 0.5m minimum spacing between the track width of adjacent vehicles					

Project	Beaumont Bridge Stage 2 Assessment		Job ref 5210920	
Part of Structure MH-L1615-001.00	Archie M analysis		Calc sheet no.	rev 0
Drawing Ref -	Calc By MG	Date 22-Feb-22	Check by MJ	Date 23-Feb-22

Ref	Calculations		Output																																																																																																																
TII AM-STR- 06026	<u>Details for Archie analysis</u> <u>Condition factors, in present condition</u> <table><tr><td>CI.6.2</td><td>γ_{F3}</td><td>=</td><td>1</td><td rowspan="6">no other recorded defects which might reduce strength of masonry</td></tr><tr><td>CI.6.2</td><td>γ_m</td><td>=</td><td>1</td></tr><tr><td>Joint width factor</td><td>F_w</td><td>=</td><td>0.9</td></tr><tr><td>Mortar factor</td><td>F_{mo}</td><td>=</td><td>1</td></tr><tr><td>Average mortar loss</td><td>=</td><td>0.02</td><td>mm (conservative as hidden by gunnite layer)</td></tr><tr><td></td><td>F_d</td><td>=</td><td>1.00</td><td>taken as 1.0 as mortar loss is modelled directly in Archie</td></tr><tr><td></td><td>$F_j = (F_w * F_{mo} * F_d)$</td><td>=</td><td>0.90</td><td></td></tr><tr><td colspan="5"> - TII AM-STR-06026 CI.6.2 gives a combined gFL factor of 3.4 which is made up a load factor of 1.9 and an impact factor of 1.8. Archie includes the 1.8 impact factor in the load definitions so γ_{FL} is taken as 1.9 in the analysis - γ_{FL} factor is 2.0 for SV load assessment <table><tr><td></td><td></td><td></td><td>HA</td><td>SV</td></tr><tr><td></td><td>γ_{FL}</td><td>=</td><td>1.9</td><td>2</td></tr><tr><td>Centrifugal effect</td><td>F_A</td><td>=</td><td>1.00</td><td>1.00</td></tr><tr><td>Condition factor</td><td>F_{cm}</td><td>=</td><td>0.9</td><td>0.9</td></tr></table> <table><tr><td></td><td></td><td></td><td>HA</td><td>SV</td></tr><tr><td>Effective $\gamma_{FL} = \frac{\gamma_{FL}}{F_j * F_{cm}} * F_A$</td><td></td><td></td><td>2.35</td><td>2.47</td></tr></table></td></tr><tr><td colspan="5"> <u>Condition factors, if repair works are carried out</u> <table><tr><td></td><td>F_w</td><td>=</td><td>0.9</td><td rowspan="4">joint width does not change</td></tr><tr><td></td><td>F_{mo}</td><td>=</td><td>1</td></tr><tr><td></td><td>F_d</td><td>=</td><td>1</td></tr><tr><td></td><td>$F_j = (F_w * F_{mo} * F_d)$</td><td>=</td><td>0.9</td></tr></table> best condition γ_{FL} factor <table><tr><td></td><td></td><td></td><td>HA</td><td>SV</td></tr><tr><td></td><td>γ_{FL}</td><td>=</td><td>1.9</td><td>2</td></tr><tr><td></td><td>F_A</td><td>=</td><td>1.00</td><td>1.00</td></tr><tr><td></td><td>F_{cm}</td><td>=</td><td>1</td><td>1</td></tr><tr><td></td><td>Effective $\gamma_{FL} =$</td><td></td><td>2.11</td><td>2.22</td></tr></table></td></tr></table>		CI.6.2	γ_{F3}	=	1	no other recorded defects which might reduce strength of masonry	CI.6.2	γ_m	=	1	Joint width factor	F_w	=	0.9	Mortar factor	F_{mo}	=	1	Average mortar loss	=	0.02	mm (conservative as hidden by gunnite layer)		F_d	=	1.00	taken as 1.0 as mortar loss is modelled directly in Archie		$F_j = (F_w * F_{mo} * F_d)$	=	0.90		- TII AM-STR-06026 CI.6.2 gives a combined gFL factor of 3.4 which is made up a load factor of 1.9 and an impact factor of 1.8. Archie includes the 1.8 impact factor in the load definitions so γ_{FL} is taken as 1.9 in the analysis - γ_{FL} factor is 2.0 for SV load assessment <table><tr><td></td><td></td><td></td><td>HA</td><td>SV</td></tr><tr><td></td><td>γ_{FL}</td><td>=</td><td>1.9</td><td>2</td></tr><tr><td>Centrifugal effect</td><td>F_A</td><td>=</td><td>1.00</td><td>1.00</td></tr><tr><td>Condition factor</td><td>F_{cm}</td><td>=</td><td>0.9</td><td>0.9</td></tr></table> <table><tr><td></td><td></td><td></td><td>HA</td><td>SV</td></tr><tr><td>Effective $\gamma_{FL} = \frac{\gamma_{FL}}{F_j * F_{cm}} * F_A$</td><td></td><td></td><td>2.35</td><td>2.47</td></tr></table>								HA	SV		γ_{FL}	=	1.9	2	Centrifugal effect	F_A	=	1.00	1.00	Condition factor	F_{cm}	=	0.9	0.9				HA	SV	Effective $\gamma_{FL} = \frac{\gamma_{FL}}{F_j * F_{cm}} * F_A$			2.35	2.47	<u>Condition factors, if repair works are carried out</u> <table><tr><td></td><td>F_w</td><td>=</td><td>0.9</td><td rowspan="4">joint width does not change</td></tr><tr><td></td><td>F_{mo}</td><td>=</td><td>1</td></tr><tr><td></td><td>F_d</td><td>=</td><td>1</td></tr><tr><td></td><td>$F_j = (F_w * F_{mo} * F_d)$</td><td>=</td><td>0.9</td></tr></table> best condition γ_{FL} factor <table><tr><td></td><td></td><td></td><td>HA</td><td>SV</td></tr><tr><td></td><td>γ_{FL}</td><td>=</td><td>1.9</td><td>2</td></tr><tr><td></td><td>F_A</td><td>=</td><td>1.00</td><td>1.00</td></tr><tr><td></td><td>F_{cm}</td><td>=</td><td>1</td><td>1</td></tr><tr><td></td><td>Effective $\gamma_{FL} =$</td><td></td><td>2.11</td><td>2.22</td></tr></table>						F_w	=	0.9	joint width does not change		F_{mo}	=	1		F_d	=	1		$F_j = (F_w * F_{mo} * F_d)$	=	0.9				HA	SV		γ_{FL}	=	1.9	2		F_A	=	1.00	1.00		F_{cm}	=	1	1		Effective $\gamma_{FL} =$		2.11	2.22
CI.6.2	γ_{F3}	=	1	no other recorded defects which might reduce strength of masonry																																																																																																															
CI.6.2	γ_m	=	1																																																																																																																
Joint width factor	F_w	=	0.9																																																																																																																
Mortar factor	F_{mo}	=	1																																																																																																																
Average mortar loss	=	0.02	mm (conservative as hidden by gunnite layer)																																																																																																																
	F_d	=	1.00		taken as 1.0 as mortar loss is modelled directly in Archie																																																																																																														
	$F_j = (F_w * F_{mo} * F_d)$	=	0.90																																																																																																																
- TII AM-STR-06026 CI.6.2 gives a combined gFL factor of 3.4 which is made up a load factor of 1.9 and an impact factor of 1.8. Archie includes the 1.8 impact factor in the load definitions so γ_{FL} is taken as 1.9 in the analysis - γ_{FL} factor is 2.0 for SV load assessment <table><tr><td></td><td></td><td></td><td>HA</td><td>SV</td></tr><tr><td></td><td>γ_{FL}</td><td>=</td><td>1.9</td><td>2</td></tr><tr><td>Centrifugal effect</td><td>F_A</td><td>=</td><td>1.00</td><td>1.00</td></tr><tr><td>Condition factor</td><td>F_{cm}</td><td>=</td><td>0.9</td><td>0.9</td></tr></table> <table><tr><td></td><td></td><td></td><td>HA</td><td>SV</td></tr><tr><td>Effective $\gamma_{FL} = \frac{\gamma_{FL}}{F_j * F_{cm}} * F_A$</td><td></td><td></td><td>2.35</td><td>2.47</td></tr></table>								HA	SV		γ_{FL}	=	1.9	2	Centrifugal effect	F_A	=	1.00	1.00	Condition factor	F_{cm}	=	0.9	0.9				HA	SV	Effective $\gamma_{FL} = \frac{\gamma_{FL}}{F_j * F_{cm}} * F_A$			2.35	2.47																																																																																	
			HA	SV																																																																																																															
	γ_{FL}	=	1.9	2																																																																																																															
Centrifugal effect	F_A	=	1.00	1.00																																																																																																															
Condition factor	F_{cm}	=	0.9	0.9																																																																																																															
			HA	SV																																																																																																															
Effective $\gamma_{FL} = \frac{\gamma_{FL}}{F_j * F_{cm}} * F_A$			2.35	2.47																																																																																																															
<u>Condition factors, if repair works are carried out</u> <table><tr><td></td><td>F_w</td><td>=</td><td>0.9</td><td rowspan="4">joint width does not change</td></tr><tr><td></td><td>F_{mo}</td><td>=</td><td>1</td></tr><tr><td></td><td>F_d</td><td>=</td><td>1</td></tr><tr><td></td><td>$F_j = (F_w * F_{mo} * F_d)$</td><td>=</td><td>0.9</td></tr></table> best condition γ_{FL} factor <table><tr><td></td><td></td><td></td><td>HA</td><td>SV</td></tr><tr><td></td><td>γ_{FL}</td><td>=</td><td>1.9</td><td>2</td></tr><tr><td></td><td>F_A</td><td>=</td><td>1.00</td><td>1.00</td></tr><tr><td></td><td>F_{cm}</td><td>=</td><td>1</td><td>1</td></tr><tr><td></td><td>Effective $\gamma_{FL} =$</td><td></td><td>2.11</td><td>2.22</td></tr></table>						F_w	=	0.9	joint width does not change		F_{mo}	=	1		F_d	=	1		$F_j = (F_w * F_{mo} * F_d)$	=	0.9				HA	SV		γ_{FL}	=	1.9	2		F_A	=	1.00	1.00		F_{cm}	=	1	1		Effective $\gamma_{FL} =$		2.11	2.22																																																																					
	F_w	=	0.9	joint width does not change																																																																																																															
	F_{mo}	=	1																																																																																																																
	F_d	=	1																																																																																																																
	$F_j = (F_w * F_{mo} * F_d)$	=	0.9																																																																																																																
			HA	SV																																																																																																															
	γ_{FL}	=	1.9	2																																																																																																															
	F_A	=	1.00	1.00																																																																																																															
	F_{cm}	=	1	1																																																																																																															
	Effective $\gamma_{FL} =$		2.11	2.22																																																																																																															

Beaumont Bridge

RG (3-t 2-axle R) impact axle 2 at 8620 mm
8.88
2.12



3t HA loading in Current Condition

gammaFI dead load: 1.00 RG (3-t 2-axle R) impact axle 2 @ 8620 [mm]
gammaFI superimposed: 1.00
gammaFI live load: 2.35
gammaF3 load effect: 1.00
gammaM material: 1.00

File path: V:\5210920\7 Calcs\72 Model\Stage 2 Assessment\Beaumont Bridge.brg

NAME: Beaumont Bridge
LOCATION: Beaumont, Meath
NUMBER: MH-L1615-001.00
Atkins
DATE: 22 February 2022
Printed on: Thursday, February 24, 2022 16:00:29

Bridge Name: Beaumont Bridge Bridge Location: Beaumont, Meath
 Bridge Number: MH-L1615-001.00
 Number of spans: 7

SAFETY FACTORS

Factor for deadload: 1.00 Factor for superimposed deadload: 1.00 Factor for surfacing: 1.00
 Factor for live load: 2.35 Factor for load effect: 1.00 Factor for material strength: 1.00

APPLIED LOAD CASES

1.RG (3-t 2-axle R) impact axle 2 Total weight: 29.43 [kN] Position: 8620 [mm]
 3.00 2 1.00 0.90 2.00 3.78 0.75 1.80 2.50
 Effective lane width: 3350 [mm] Distribution length: 2418 [mm]

Applied distribution mode: Archie-M BD21/97
 Applied live load pressure: Active pressure

STRUCTURE PROPERTIES

Road shape: True shape (multi-point method)
 Road points: (-500, 1950) (1180, 2010) (5805, 2150) (11660, 2490) (19175, 2630) (29755, 2500) (33895, 2390) (43290, 1960) (45000, 1910)
 Depth of surfacing: 100Depth of overlay: 0
 Surface unit weight: 23.00 [kN/m3] Overlay unit weight: 23.00 [kN/m3]
 Lane width: 0

Fill unit weight: 18.00 [kN/m3] Fill phi: 30 degree

Left abutment Base level:-1500 [mm] Height: 380 [mm] Width: 1000 [mm]
 Right abutment Base level:-1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Right abutment Base level:-1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Shape: Circular

Span: 2360 [mm] Rise: 1170 [mm] Q-rise: 1050 [mm]

Ring thickness at crown:380 [mm] Ring thickness at springing: 380 [mm] Mortar loss: 50 [mm]

Masonry unit weight:22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment	Intrados x	Intrados z	Extrados x	Extrados z	Road z	Fx dead	Fz dead	My dead	Fx live	Fz live	My live	Fx passive	Fz total	My total	Thrust in	Thrust out	Extra-Thrust
0	0	380	-380	3831954	0.00	0.00	0.00	0.00	0.00	0.00	0.00	2.55	-29.97	-0.06	-0	4	326
1	4	472	-374	5051954	1.68	-1.05	-0.12	0.00	-0.00	0.00	0.00	0.86	-28.92	-0.16	3	8	322
2	16	563	-359	6261954	1.54	-1.28	-0.16	0.00	-0.00	0.00	0.00	-0.68	-27.64	-0.26	8	12	318
3	35	654	-334	7451955	1.39	-1.47	-0.19	0.00	-0.00	0.00	0.00	-2.07	-26.17	-0.39	13	17	313
4	60	742	-300	8621956	1.24	-1.61	-0.21	0.00	-0.00	0.00	0.00	-3.31	-24.55	-0.53	20	24	306
5	93	828	-257	9761958	1.09	-1.72	-0.22	0.00	-0.00	0.00	0.00	-4.41	-22.84	-0.69	29	32	298
6	132	912	-206	1086	1960	0.95	-1.78	-0.22	0.00	-0.00	0.00	-5.36	-21.05	-0.87	39	42	288
7	177	992	-146	1192	1962	0.81	-1.81	-0.21	0.00	-0.00	0.00	-6.17	-19.24	-1.05	52	55	275
8	229	1068	-77	1293	1965	0.68	-1.81	-0.20	0.00	-0.00	0.00	-6.85	-17.43	-1.24	67	70	260
9	286	1141	-2	1389	1967	0.56	-1.79	-0.18	0.00	-0.00	0.00	-7.41	-15.64	-1.44	85	88	242
10	349	1208	82	1478	1970	0.45	-1.74	-0.16	0.00	-0.00	0.00	-7.86	-13.91	-1.64	106	108	222
11	417	1270	171	1560	1974	0.36	-1.67	-0.14	0.00	-0.00	0.00	-8.21	-12.23	-1.83	128	130	200
12	490	1327	267	1635	1977	0.27	-1.59	-0.11	0.00	-0.00	0.00	-8.49	-10.64	-2.02	153	155	175
13	566	1378	369	1703	1981	0.20	-1.51	-0.09	0.00	-0.00	0.00	-8.69	-9.13	-2.20	180	182	148
14	647	1423	475	1762	1985	0.15	-1.43	-0.07	0.00	-0.00	0.00	-8.84	-7.70	-2.36	207	209	121
15	731	1461	586	1813	1989	0.10	-1.35	-0.05	0.00	-0.00	0.00	-8.95	-6.35	-2.52	234	236	94
16	817	1493	700	1854	1993	0.07	-1.28	-0.03	0.00	-0.00	0.00	-9.02	-5.08	-2.65	260	262	68
17	906	1518	818	1887	1998	0.05	-1.22	-0.01	0.00	-0.00	0.00	-9.06	-3.86	-2.76	284	285	45
18	996	1536	937	1911	2001	0.03	-1.17	0.01	0.00	-0.00	0.00	-9.09	-2.69	-2.86	303	305	25
19	1088	1546	1058	1925	2006	0.01	-1.14	0.03	0.00	-0.00	0.00	-9.10	-1.55	-2.93	318	319	11
20	1180	1550	1180	1930	2010	0.00	-1.13	0.04	0.00	-0.00	0.00	-9.11	-0.42	-2.98	327	328	2
21	1272	1546	1302	1925	2013	-0.00	-1.14	0.06	0.00	-0.00	0.00	-9.10	0.72	-3.01	329	330	-0

22	1364	1536	1423	1911	2017	-0.02	-1.17	0.08	-0.00	-0.00	0.00	0.00	-9.09	1.88	-3.01	3243255
23	1454	1518	1542	1887	2021	-0.03	-1.21	0.10	-0.00	-0.00	0.00	0.00	-9.06	3.09	-2.99	31331416
24	1543	1493	1660	1854	2024	-0.05	-1.27	0.12	-0.00	-0.00	0.00	0.00	-9.00	4.37	-2.94	29629832
25	1629	1461	1774	1813	2028	-0.08	-1.35	0.15	-0.00	-0.00	0.00	0.00	-8.92	5.71	-2.87	27527654
26	1713	1423	1885	1762	2031	-0.12	-1.43	0.18	-0.00	-0.00	0.00	0.00	-8.80	7.15	-2.77	25025179
27	1794	1378	1991	1703	2034	-0.17	-1.52	0.20	-0.00	-0.00	0.00	0.00	-8.62	8.67	-2.65	223224106
28	1870	1327	2093	1635	2037	-0.24	-1.61	0.23	-0.00	-0.00	0.00	0.00	-8.38	10.28	-2.51	195197133
29	1943	1270	2189	1560	2039	-0.32	-1.70	0.27	-0.00	-0.00	0.00	0.00	-8.07	11.98	-2.35	168170160
30	2011	1208	2278	1478	2041	-0.41	-1.78	0.30	-0.00	-0.00	0.00	0.00	-7.66	13.76	-2.16	142144186
31	2074	1141	2362	1389	2043	-0.51	-1.85	0.32	-0.00	-0.00	0.00	0.00	-7.15	15.61	-1.97	118120210
32	2131	1068	2437	1293	2045	-0.63	-1.89	0.35	-0.00	-0.00	0.00	0.00	-6.52	17.50	-1.76	99 231
33	2183	9922506	1192	2047	-0.76	-1.91	0.37	-0.00	-0.00	0.00	0.00	-5.77	19.42	-1.54	77 80 250	
34	2228	9122566	1086	2049	-0.89	-1.91	0.38	-0.00	-0.00	0.00	0.00	-4.87	21.33	-1.32	61 64 266	
35	2267	8282617	9762051	-1.04	-1.87	0.39	-0.00	-0.00	0.00	0.00	0.00	-3.83	23.19	-1.10	46 50 280	
36	2300	7422660	8622052	-1.19	-1.79	0.39	-0.00	-0.00	0.00	0.00	0.00	-2.64	24.98	-0.88	34 38 292	
37	2325	6542694	7452053	-1.34	-1.67	0.38	-0.00	-0.00	0.00	0.00	0.00	-1.30	26.66	-0.67	24 27 303	
38	2344	5632719	6262053	-1.50	-1.51	0.36	-0.00	-0.00	0.00	0.00	0.00	0.20	28.17	-0.46	15 19 311	
39	2356	4722734	5052054	-1.65	-1.31	0.33	-0.00	-0.00	0.00	0.00	0.00	1.85	29.48	-0.26	7 11 319	
40	2360	3802740	3832054	-1.79	-1.06	0.30	-0.00	-0.00	0.00	0.00	0.00	3.64	30.54	-0.07	0 4 326	

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 380 [mm] Thickness at top: 2000 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment	Left xRight x z	Weight	Fx	Fz	My	Thrust left	Thrust right	Stress left	Stress right	Dist. left	Dist. right
0	2360 4360 380	-109.21	-18.33	-109.21	-1.30	3340 3356	-0.06	-0.05	980.26	1004.14	
1	2360 4360 -247	-27.57	-18.33	-136.79	-12.79	3257 3276	-0.09	-0.05	896.74	1083.72	
2	2360 4360 -873	-27.57	-18.33	-164.36	-24.27	3201 3224	-0.12	-0.05	840.57	1135.95	
3	2360 4360 -1500	-27.57	-18.33	-191.93	-35.76	3160 3187	-0.15	-0.04	799.98	1172.60	

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 2890 [mm] Rise: 1280 [mm] Q-rise: 1020 [mm]

Ring thickness at crown: 270 [mm] Ring thickness at springing: 270 [mm] Mortar loss: 50 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment	Intrados.x	Intrados.z	Extrados.x	Extrados.z	Road.z	Fx dead	Fz dead	My dead	Fx live	Fz live	My live	Fx passive	Fx total	Fz total	My total	Thrust in	Thrust out	Extra-Thrust
0	4360	4004092	4332089	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-14.69	-36.46	-9.64	251257	-37 ***			
1	4377	5044112	5562090	1.80	-1.26	-0.05	0.00	-0.00	0.00	0.00	-16.49	-35.21	-8.42	220226	-6 ***			
2	4401	6074140	6782091	1.65	-1.45	-0.07	0.00	-0.00	0.00	0.00	-18.14	-33.75	-7.26	19219723				
3	4432	7084177	7972092	1.48	-1.61	-0.09	0.00	-0.00	0.00	0.00	-19.62	-32.14	-6.17	16517050				
4	4471	8064223	9142093	1.33	-1.73	-0.10	0.00	-0.00	0.00	0.00	-20.95	-30.42	-5.16	14014575				
5	4516	9014277	10262095	1.17	-1.81	-0.10	0.00	-0.00	0.00	0.00	-22.11	-28.61	-4.24	11712298				
6	4569	9934339	11352097	1.02	-1.85	-0.10	0.00	-0.00	0.00	0.00	-23.13	-26.76	-3.40	95100120				
7	4627	10804409	12392099	0.88	-1.86	-0.09	0.00	-0.00	0.00	0.00	-24.01	-24.90	-2.65	7580140				
8	4693	11634486	13372101	0.74	-1.85	-0.08	0.00	-0.00	0.00	0.00	-24.75	-23.05	-1.99	5762158				
9	4763	12414570	14302104	0.62	-1.81	-0.07	0.00	-0.00	0.00	0.00	-25.38	-21.23	-1.43	4146174				
10	4840	13144661	15162107	0.51	-1.76	-0.06	0.00	-0.00	0.00	0.00	-25.89	-19.47	-0.96	2732188				
11	4921	13814757	15962110	0.42	-1.69	-0.05	0.00	-0.00	0.00	0.00	-26.30	-17.78	-0.58	1621199				
12	5007	14424859	16682113	0.33	-1.62	-0.03	0.00	-0.00	0.00	0.00	-26.63	-16.16	-0.31	812208				
13	5098	14974966	17332117	0.26	-1.54	-0.02	0.00	-0.00	0.00	0.00	-26.89	-14.62	-0.13	27213				
14	5192	15445078	17892121	0.20	-1.46	-0.01	0.00	-0.00	0.00	0.00	-27.09	-13.17	-0.06	-04216				
15	5289	15855193	18382125	0.15	-1.38	0.00	0.00	-0.00	0.00	0.00	-27.24	-11.78	-0.10	15215				
16	5389	16195312	18782130	0.11	-1.32	0.02	0.00	-0.00	0.00	0.00	-27.34	-10.46	-0.24	610210				
17	5491	16465433	19092134	0.08	-1.26	0.03	0.00	-0.00	0.00	0.00	-27.42	-9.20	-0.49	1519201				
18	5595	16655556	19322139	0.05	-1.22	0.04	0.00	-0.00	0.00	0.00	-27.47	-7.98	-0.84	2832188				

19	5700	1676	5680	1945	2144	0.03	-1.20	0.05	0.00	-0.00	0.00	0.00	-27.50	-6.78	-1.30	44	48	172
20	5805	1680	5805	1950	2150	0.01	-1.19	0.06	0.00	-0.00	0.00	0.00	-27.51	-5.58	-1.85	65	69	151
21	5910	1676	5930	1945	2155	-0.01	-1.21	0.07	-0.00	-0.00	0.00	0.00	-27.50	-4.37	-2.51	91	95	125
22	6015	1665	6054	1932	2161	-0.03	-1.24	0.08	-0.00	-0.02	0.00	0.00	-27.47	-3.12	-3.26	120	124	96
23	6119	1646	6177	1909	2167	-0.05	-1.28	0.10	-0.03	-0.50	0.05	0.00	-27.38	-1.34	-4.09	153	157	63
24	6221	1619	6298	1878	2173	-0.09	-1.35	0.11	-0.14	-1.67	0.17	0.00	-27.15	1.69	-4.94	184	188	32
25	6321	1585	6417	1838	2179	-0.12	-1.42	0.13	-0.35	-3.07	0.32	0.00	-26.68	6.18	-5.69	208	212	19
26	6418	1544	6532	1789	2184	-0.17	-1.51	0.15	-0.58	-4.15	0.47	0.00	-25.92	11.84	-6.21	216	220	0
27	6512	1497	6644	1733	2191	-0.23	-1.60	0.17	-0.78	-4.57	0.55	0.00	-24.91	18.00	-6.41	208	212	8
28	6603	1442	6751	1668	2196	-0.30	-1.69	0.19	-0.86	-4.26	0.54	0.00	-23.75	23.94	-6.25	187	192	28
29	6689	1381	6853	1596	2201	-0.39	-1.78	0.22	-0.80	-3.40	0.46	0.00	-22.56	29.12	-5.76	159	164	56
30	6770	1314	6949	1516	2207	-0.48	-1.86	0.24	-0.64	-2.33	0.33	0.00	-21.44	33.31	-5.00	128	134	86
31	6847	1241	7040	1430	2212	-0.59	-1.93	0.26	-0.42	-1.33	0.19	0.00	-20.43	36.57	-4.11	99	104	116
32	6917	1163	7124	1337	2217	-0.72	-1.98	0.28	-0.22	-0.59	0.09	0.00	-19.50	39.14	-3.18	72	78	142
33	6983	1080	7201	1239	2222	-0.85	-2.02	0.30	-0.07	-0.17	0.03	0.00	-18.57	41.33	-2.31	49	55	165
34	7041	993	7271	1135	2225	-0.99	-2.02	0.31	-0.02	-0.04	0.01	0.00	-17.56	43.39	-1.57	31	37	183
35	7094	901	7333	1026	2229	-1.15	-2.00	0.32	-0.02	-0.04	0.01	0.00	-16.39	45.43	-0.99	17	24	196
36	7139	806	7387	914	2232	-1.31	-1.94	0.32	-0.03	-0.04	0.01	0.00	-15.05	47.41	-0.56	8	15	205
37	7178	708	7433	797	2235	-1.47	-1.84	0.32	-0.03	-0.04	0.01	0.00	-13.55	49.29	-0.30	2	9	211
38	7209	607	7470	678	2237	-1.64	-1.71	0.31	-0.04	-0.04	0.01	0.00	-11.87	51.03	-0.20	0	7	213
39	7233	504	7498	556	2239	-1.81	-1.53	0.30	-0.04	-0.03	0.01	0.00	-10.02	52.59	-0.26	1	9	211
40	7250	400	7518	433	2240	-1.97	-1.31	0.28	-0.05	-0.02	0.01	0.00	-8.00	53.92	-0.49	5	13	207

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust

Base level: -1500 [mm] Top level: 100 [mm] Thickness at top: 2300 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right																		
0	7250	9550	100	-188.90	8.97	-188.90	1.71	8396	8423	-0.08	-0.08	1145.55	1127.47					
1	7250	9550	-433	-26.99	8.97	-215.88	6.49	8415	8445	-0.09	-0.10	1164.65	1104.51					
2	7250	9550	-967	-26.99	8.97	-242.87	11.27	8429	8464	-0.09	-0.12	1179.07	1086.23					
3	7250	9550	-1500	-26.99	8.97	-269.86	16.06	8440	8479	-0.10	-0.14	1190.23	1071.22					

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 4220 [mm] Rise: 1930 [mm] Q-rise: 1560 [mm]

Ring thickness at crown: 350 [mm] Ring thickness at springing: 350 [mm] Mortar loss: 50 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment	Intrados.x	Intrados.z	Extrados.x	Extrados.z	Road.z	Fx dead	Fz dead	My dead	Fx live	Fz live	My live	Fx passive	Fx total	Fz total	My total	Thrust in	Thrust out	Extra-Thrust
0	9550	1009201	1312346	0.00	0.00	0.00	0.00	0.00	1.53	-55.11	-0.21	-0	8	292				
1	9570	2569224	3132347	3.51	-2.20	-0.07	0.15	-0.06	0.00	0.00	-2.13	-52.86	-0.88	13	20	280		
2	9601	4099261	4922350	3.18	-2.60	-0.13	0.14	-0.09	-0.00	0.00	-5.45	-50.17	-1.48	26	33	267		
3	9643	5609310	6682353	2.85	-2.91	-0.18	0.13	-0.11	-0.01	0.00	-8.44	-47.15	-2.04	40	46	254		
4	9697	7089373	8402357	2.52	-3.14	-0.21	0.12	-0.14	-0.01	0.00	-11.08	-43.88	-2.55	54	60	240		
5	9761	8519448	10062361	2.20	-3.28	-0.22	0.11	-0.15	-0.01	0.00	-13.39	-40.44	-3.02	69	75	225		
6	9836	9899535	11672367	1.89	-3.35	-0.22	0.10	-0.16	-0.02	0.00	-15.38	-36.93	-3.44	84	90	210		
7	9921	11219633	13212373	1.60	-3.36	-0.21	0.09	-0.16	-0.02	0.00	-17.06	-33.40	-3.81	100	105	195		
8	10015	12479743	14672380	1.33	-3.31	-0.19	0.07	-0.16	-0.01	0.00	-18.46	-29.94	-4.12	116	121	179		
9	10118	13659864	16052388	1.08	-3.21	-0.16	0.05	-0.14	-0.01	0.00	-19.60	-26.60	-4.40	132	136	164		
10	10230	14759994	17332396	0.87	-3.07	-0.13	0.04	-0.12	-0.01	0.00	-20.50	-23.41	-4.62	147	152	148		
11	10350	157610133	18512404	0.68	-2.90	-0.10	0.03	-0.09	-0.01	0.00	-21.21	-20.42	-4.81	162	166	134		
12	10477	166910281	19592413	0.51	-2.72	-0.07	0.01	-0.06	-0.00	0.00	-21.74	-17.64	-4.98	177	180	120		
13	10610	175110436	20552422	0.38	-2.53	-0.04	0.01	-0.03	-0.00	0.00	-22.12	-15.08	-5.12	190	194	106		
14	10749	182410599	21402432	0.27	-2.35	-0.01	0.00	-0.01	-0.00	0.00	-22.40	-12.72	-5.26	203	206	94		
15	10893	188610766	22132442	0.19	-2.18	0.02	0.00	-0.00	-0.00	0.00	-22.59	-10.54	-5.39	215	218	82		

16	11041	1938	10939	2272	2452	0.12	-2.03	0.04	-0.00	0.00	0.00	0.00	-22.71	-8.51	-5.53	22723070
17	11193	1978	11116	2319	2461	0.08	-1.91	0.06	-0.00	0.00	0.00	0.00	-22.79	-6.60	-5.68	23824159
18	11347	2007	11296	2353	2471	0.05	-1.82	0.08	-0.00	0.00	0.00	0.00	-22.84	-4.79	-5.84	24925248
19	11503	2024	11477	2373	2480	0.03	-1.77	0.10	-0.00	0.00	0.00	0.00	-22.86	-3.02	-6.02	26026337
20	11660	2030	11660	2380	2490	0.01	-1.75	0.13	-0.00	0.00	0.00	0.00	-22.87	-1.27	-6.21	27027327
21	11817	2024	11843	2373	2499	-0.01	-1.79	0.15	0.00	0.00	0.00	0.00	-22.86	0.52	-6.42	27928317
22	11973	2007	12024	2353	2507	-0.03	-1.85	0.18	0.00	0.00	0.00	0.00	-22.83	2.37	-6.63	2882919
23	12127	1978	12204	2319	2514	-0.06	-1.96	0.22	0.00	0.00	0.00	0.00	-22.77	4.33	-6.84	2932973
24	12279	1938	12381	2272	2522	-0.11	-2.10	0.26	0.00	0.00	0.00	0.00	-22.67	6.44	-7.03	297300-0 ***
25	12427	1886	12554	2213	2529	-0.17	-2.27	0.30	0.00	0.00	0.00	0.00	-22.50	8.71	-7.19	2963000
26	12571	1824	12721	2140	2536	-0.25	-2.47	0.35	0.00	0.00	0.00	0.00	-22.25	11.18	-7.31	2922955
27	12710	1751	12884	2055	2542	-0.36	-2.68	0.41	0.00	0.00	0.00	0.00	-21.89	13.85	-7.38	28328713
28	12843	1669	13039	1959	2548	-0.49	-2.89	0.47	0.00	0.00	0.00	0.00	-21.40	16.74	-7.37	27027426
29	12970	1576	13187	1851	2552	-0.65	-3.10	0.53	0.00	0.00	0.00	0.00	-20.75	19.84	-7.29	25325743
30	13090	1475	13326	1733	2557	-0.84	-3.29	0.59	0.00	0.00	0.00	0.00	-19.91	23.13	-7.12	23323763
31	13202	1365	13456	1605	2561	-1.06	-3.46	0.65	0.00	0.00	0.00	0.00	-18.84	26.59	-6.86	21021585
32	13305	1247	13577	1467	2565	-1.31	-3.59	0.71	0.00	0.00	0.00	0.00	-17.54	30.18	-6.49	186191109
33	13399	1121	13687	1321	2569	-1.58	-3.68	0.75	0.00	0.00	0.00	0.00	-15.96	33.86	-6.02	161166134
34	13484	98913785	1167	2572	-1.87	-3.71	0.79	0.00	0.00	0.00	0.00	0.00	-14.08	37.58	-5.46	135141159
35	13559	85113872	1006	2574	-2.19	-3.68	0.82	0.00	0.00	0.00	0.00	0.00	-11.89	41.26	-4.80	111117183
36	13623	70813947	8402576	-2.52	-3.57	0.83	0.00	0.00	0.00	0.00	0.00	0.00	-9.37	44.83	-4.05	87 93 207
37	13677	56014010	6682577	-2.86	-3.39	0.83	0.00	0.00	0.00	0.00	0.00	0.00	-6.51	48.22	-3.22	64 71 229
38	13719	40914059	4922578	-3.21	-3.11	0.81	0.00	0.00	0.00	0.00	0.00	0.00	-3.30	51.33	-2.30	42 49 251
39	13750	25614096	3132579	-3.56	-2.75	0.77	0.00	0.00	0.00	0.00	0.00	0.00	0.25	54.08	-1.30	21 28 272
40	13770	10014119	1312580	-3.89	-2.29	0.72	0.00	0.00	0.00	0.00	0.00	0.00	4.15	56.37	-0.22	-0 8 292

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 Base level: -1500 [mm] Top level: 100 [mm] Thickness at top: 3150 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right	0 13770 16920 100-228.03 -1.43 -228.03 4.87 15350 15383 -0.07 -0.08 1580.07 1537.35
Ring thickness at crown: 370 [mm] Ring thickness at springing: 370 [mm] Mortar loss: 50 [mm]	1 13770 16920 -433 -36.96 -1.43 -264.99 4.11 15342 15379 -0.08 -0.09 1571.58 1540.57
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]	2 13770 16920 -967 -36.96 -1.43 -301.95 3.35 15335 15378 -0.09 -0.10 1564.51 1542.35
	3 13770 16920 -1500 -36.96 -1.43 -338.91 2.58 15328 15377 -0.11 -0.11 1558.42 1543.17

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 Shape: Circular

Span: 4510 [mm] Rise: 2010 [mm] Q-rise: 1660 [mm]

Ring thickness at crown: 370 [mm] Ring thickness at springing: 370 [mm] Mortar loss: 50 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust	0 16920 20016552 2422621 0.00 0.00 0.00 0.00 0.00 0.00 2.72 -58.85 -0.24 -0 8 312
	1 16945 36316581 4322621 3.95 -2.66 -0.10 -0.00 0.00 0.00 -1.23 -56.19 -1.36 21 28 292
	2 16982 52416624 6202622 3.58 -3.08 -0.18 -0.00 0.00 0.00 -4.81 -53.11 -2.38 42 49 271
	3 17030 68216680 8032622 3.21 -3.41 -0.23 -0.00 0.00 0.00 -8.02 -49.69 -3.31 63 70 250
	4 17090 83616750 9832623 2.83 -3.65 -0.26 -0.00 0.00 0.00 -10.85 -46.04 -4.16 86 93 227
	5 17160 98616832 1156 2624 2.47 -3.80 -0.27 -0.00 0.00 0.00 -13.33 -42.25 -4.91 109 116 204
	6 17242 1130 16927 1323 2624 2.12 -3.86 -0.26 -0.00 0.00 0.00 -15.45 -38.39 -5.57 134 139 181
	7 17333 1267 17033 1483 2625 1.80 -3.85 -0.25 -0.00 0.00 0.00 -17.25 -34.54 -6.13 158 164 156
	8 17435 1397 17151 1635 2626 1.49 -3.78 -0.22 -0.00 0.00 0.00 -18.74 -30.76 -6.60 183 188 132
	9 17545 1520 17280 1778 2626 1.22 -3.65 -0.19 -0.00 0.00 0.00 -19.96 -27.12 -6.97 207 211 109
	10 17665 1635 17418 1911 2627 0.97 -3.48 -0.15 -0.00 0.00 0.00 -20.93 -23.64 -7.25 229 234 86
	11 17792 1740 17566 2033 2628 0.75 -3.27 -0.12 -0.00 0.00 0.00 -21.68 -20.37 -7.45 250 254 66
	12 17926 1836 17723 2145 2628 0.57 -3.05 -0.08 -0.00 0.00 0.00 -22.25 -17.32 -7.58 268 272 48

13	18068	1922	17887	2245	2629	0.41	-2.82	-0.04	-0.00	0.00	0.00	-22.66	-14.50	-7.64	28328634
14	18215	1997	18058	2332	2629	0.29	-2.59	-0.01	-0.00	0.00	0.00	-22.96	-11.91	-7.65	29429822
15	18367	2061	18235	2407	2629	0.19	-2.37	0.02	-0.00	0.00	0.00	-23.15	-9.54	-7.63	30330713
16	18523	2114	18417	2469	2630	0.12	-2.17	0.05	-0.00	0.00	0.00	-23.27	-7.37	-7.59	3093137
17	18683	2156	18603	2517	2630	0.07	-2.00	0.07	-0.00	0.00	0.00	-23.34	-5.36	-7.54	3133173
18	18846	2186	18792	2552	2630	0.04	-1.87	0.09	-0.00	0.00	0.00	-23.38	-3.49	-7.50	3163191
19	19010	2204	18983	2573	2630	0.02	-1.78	0.11	-0.00	0.00	0.00	-23.40	-1.71	-7.47	3173200
20	19175	2210	19175	2580	2630	0.01	-1.73	0.13	-0.00	0.00	0.00	-23.40	0.02	-7.45	3173200
21	19340	2204	19367	2573	2629	-0.01	-1.73	0.16	0.00	0.00	0.00	-23.40	1.76	-7.45	3163191
22	19504	2186	19558	2552	2629	-0.02	-1.78	0.18	0.00	0.00	0.00	-23.38	3.53	-7.47	3143182
23	19667	2156	19747	2517	2628	-0.04	-1.87	0.22	0.00	0.00	0.00	-23.34	5.40	-7.51	3123155
24	19827	2114	19933	2469	2628	-0.07	-2.00	0.26	0.00	0.00	0.00	-23.27	7.40	-7.55	3073119
25	19983	2061	20115	2407	2627	-0.12	-2.17	0.30	0.00	0.00	0.00	-23.15	9.57	-7.58	30130416
26	20135	1997	20292	2332	2626	-0.19	-2.36	0.36	0.00	0.00	0.00	-22.96	11.93	-7.59	29229525
27	20282	1922	20463	2245	2626	-0.29	-2.58	0.41	0.00	0.00	0.00	-22.67	14.50	-7.57	28028436
28	20424	1836	20627	2145	2625	-0.41	-2.81	0.48	0.00	0.00	0.00	-22.26	17.31	-7.50	26526951
29	20558	1740	20784	2033	2624	-0.57	-3.04	0.55	0.00	0.00	0.00	-21.69	20.35	-7.37	24725169
30	20685	1635	20932	1911	2623	-0.75	-3.26	0.62	0.00	0.00	0.00	-20.95	23.62	-7.17	22723189
31	20805	1520	21070	1778	2622	-0.96	-3.47	0.68	0.00	0.00	0.00	-19.98	27.08	-6.89	204209111
32	20915	1397	21199	1635	2621	-1.21	-3.64	0.75	0.00	0.00	0.00	-18.77	30.72	-6.52	181186134
33	21017	1267	21317	1483	2621	-1.49	-3.77	0.81	0.00	0.00	0.00	-17.28	34.49	-6.06	156162158
34	21108	1130	21423	1323	2620	-1.79	-3.84	0.86	0.00	0.00	0.00	-15.49	38.33	-5.50	132138182
35	21190	9862	21518	1156	2620	-2.12	-3.85	0.89	0.00	0.00	0.00	-13.37	42.18	-4.85	108114206
36	21260	8362	1600	9832	2619	-2.47	-3.79	0.92	0.00	0.00	0.00	-10.91	45.97	-4.11	85.92.228
37	21320	6822	1670	8032	2619	-2.83	-3.64	0.92	0.00	0.00	0.00	-8.08	49.61	-3.28	63.70.250
38	21368	5242	1726	6202	2618	-3.20	-3.41	0.91	0.00	0.00	0.00	-4.88	53.03	-2.36	41.49.271
39	21405	3632	1769	4322	2618	-3.57	-3.08	0.88	0.00	0.00	0.00	-1.30	56.11	-1.35	20.28.292
40	21430	2002	1798	2422	2618	-3.95	-2.66	0.83	0.00	0.00	0.00	2.64	58.76	-0.24	-0.8.312

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 200 [mm] Thickness at top: 7170 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

0	21430	28600	200	-386.20	2.56	-386.20	-50.01	24858	24913	-0.06	-0.05	3427.92	3686.91
1	21430	28600	-367	-89.39	2.56	-475.58	-48.56	24879	24947	-0.07	-0.06	3448.93	3653.13
2	21430	28600	-933	-89.39	2.56	-564.97	-47.10	24891	24972	-0.08	-0.07	3461.27	3628.02
3	21430	28600	-1500	-89.39	2.56	-654.36	-45.65	24898	24992	-0.10	-0.09	3468.50	3608.02

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 2310 [mm] Rise: 1150 [mm] Q-rise: 960 [mm]

Ring thickness at crown: 500 [mm] Ring thickness at springing: 500 [mm] Mortar loss: 50 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust

0	28600	45028	100	4522	532	0.00	0.00	0.00	0.00	0.00	0.00	5.21	-47.77	-0.16	0.7.443
1	28604	54028	106	5822	532	2.38	-1.42	-0.25	-0.00	0.00	0.00	2.83	-46.36	-0.37	5.11.439
2	28615	63028	121	7102	532	2.22	-1.75	-0.33	-0.00	0.00	0.00	0.61	-44.61	-0.61	11.17.433
3	28633	71928	147	8372	531	2.04	-2.04	-0.38	-0.00	0.00	0.00	-1.43	-42.57	-0.89	18.24.426
4	28658	80628	183	9622	530	1.86	-2.27	-0.43	-0.00	0.00	0.00	-3.29	-40.30	-1.21	28.34.416
5	28689	89028	228	1083	2530	1.68	-2.46	-0.45	-0.00	0.00	0.00	-4.97	-37.84	-1.57	40.45.405
6	28727	97228	283	1201	2529	1.50	-2.60	-0.46	-0.00	0.00	0.00	-6.47	-35.24	-1.95	55.59.391
7	28772	1051	28346	1314	2527	1.32	-2.70	-0.46	-0.00	0.00	0.00	-7.78	-32.54	-2.37	72.77.373
8	28822	1126	28419	1421	2526	1.15	-2.75	-0.44	-0.00	0.00	0.00	-8.93	-29.78	-2.79	93.97.353
9	28879	1197	28499	1523	2525	0.99	-2.78	-0.41	-0.00	0.00	0.00	-9.92	-27.01	-3.23	118.122328

10	28940	1263	28587	1618	2523	0.84	-2.77	-0.38	-0.00	0.00	0.00	0.00	-10.76	-24.24	-3.67	147150300
11	29007	1325	28683	1706	2521	0.70	-2.73	-0.34	-0.00	0.00	0.00	0.00	-11.46	-21.51	-4.09	179182268
12	29078	1381	28785	1786	2519	0.58	-2.68	-0.29	-0.00	0.00	0.00	0.00	-12.04	-18.83	-4.50	215218232
13	29153	1431	28892	1857	2516	0.47	-2.62	-0.24	-0.00	0.00	0.00	0.00	-12.51	-16.21	-4.88	254256194
14	29232	1475	29006	1921	2514	0.37	-2.54	-0.19	-0.00	0.00	0.00	0.00	-12.88	-13.67	-5.22	294297153
15	29314	1513	29123	1975	2512	0.29	-2.47	-0.14	-0.00	0.00	0.00	0.00	-13.17	-11.20	-5.52	334337113
16	29399	1544	29245	2019	2510	0.22	-2.40	-0.10	-0.00	0.00	0.00	0.00	-13.39	-8.81	-5.76	37237476
17	29486	1568	29370	2055	2508	0.16	-2.33	-0.05	-0.00	0.00	0.00	0.00	-13.55	-6.48	-5.96	40540743
18	29575	1586	29497	2080	2505	0.11	-2.28	-0.01	-0.00	0.00	0.00	0.00	-13.65	-4.20	-6.09	43043218
19	29665	1596	29626	2095	2502	0.06	-2.24	0.04	-0.00	0.00	0.00	0.00	-13.71	-1.96	-6.16	4454473
20	29755	1600	29755	2100	2499	0.02	-2.21	0.08	-0.00	0.00	0.00	0.00	-13.73	0.25	-6.17	448450-0 ***
21	29845	1596	29884	2095	2497	-0.02	-2.21	0.12	0.00	0.00	0.00	0.00	-13.71	2.46	-6.11	4404428
22	29935	1586	30013	2080	2494	-0.06	-2.22	0.17	0.00	0.00	0.00	0.00	-13.65	4.68	-5.99	42042228
23	30024	1568	30140	2055	2491	-0.10	-2.25	0.21	0.00	0.00	0.00	0.00	-13.55	6.92	-5.81	39139456
24	30111	1544	30265	2019	2489	-0.15	-2.29	0.26	0.00	0.00	0.00	0.00	-13.40	9.21	-5.57	35635892
25	30196	1513	30387	1975	2487	-0.21	-2.34	0.30	0.00	0.00	0.00	0.00	-13.19	11.56	-5.28	317319131
26	30278	1475	30504	1921	2484	-0.28	-2.41	0.35	0.00	0.00	0.00	0.00	-12.91	13.97	-4.94	276278172
27	30357	1431	30618	1857	2481	-0.35	-2.47	0.40	0.00	0.00	0.00	0.00	-12.56	16.44	-4.57	236238212
28	30432	1381	30725	1786	2479	-0.44	-2.54	0.45	0.00	0.00	0.00	0.00	-12.12	18.98	-4.17	197200250
29	30503	1325	30827	1706	2477	-0.55	-2.60	0.50	0.00	0.00	0.00	0.00	-11.57	21.58	-3.74	163166284
30	30570	1263	30923	1618	2475	-0.66	-2.65	0.55	0.00	0.00	0.00	0.00	-10.90	24.24	-3.31	131135315
31	30631	1197	31011	1523	2472	-0.80	-2.69	0.59	0.00	0.00	0.00	0.00	-10.11	26.92	-2.87	104108342
32	30688	1126	31091	1421	2470	-0.94	-2.70	0.63	0.00	0.00	0.00	0.00	-9.17	29.62	-2.44	81 85 365
33	30738	1051	31164	1314	2469	-1.09	-2.68	0.65	0.00	0.00	0.00	0.00	-8.08	32.30	-2.03	62 66 384
34	30783	97231227	1201	2467	-1.26	-2.63	0.67	0.00	0.00	0.00	0.00	0.00	-6.82	34.93	-1.64	45 50 400
35	30821	89031282	1083	2466	-1.43	-2.54	0.67	0.00	0.00	0.00	0.00	0.00	-5.39	37.47	-1.28	32 38 412
36	30852	80631327	9622465	-1.61	-2.41	0.66	0.00	0.00	0.00	0.00	0.00	0.00	-3.78	39.88	-0.97	22 27 423
37	30877	71931363	8372465	-1.79	-2.23	0.64	0.00	0.00	0.00	0.00	0.00	0.00	-1.99	42.11	-0.69	14 20 430
38	30895	63031389	7102464	-1.96	-2.01	0.60	0.00	0.00	0.00	0.00	0.00	0.00	-0.03	44.11	-0.47	8 14 436
39	30906	54031404	5822464	-2.14	-1.73	0.55	0.00	0.00	0.00	0.00	0.00	0.00	2.11	45.85	-0.29	3 10 440
40	30910	45031410	4522464	-2.30	-1.41	0.48	0.00	0.00	0.00	0.00	0.00	0.00	4.41	47.26	-0.16	0 7 443

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 350 [mm] Thickness at top: 1700 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 30910 32610 350-124.75 -2.79-124.75 -1.15 31742 31760 -0.08-0.07 831.90 850.28
1 30910 32610 -267 -23.06 -2.79-147.81 -2.87 31730 31751 -0.09-0.08 820.05 858.84
2 30910 32610 -883 -23.06 -2.79-170.87 -4.59 31721 31745 -0.11-0.09 810.95 864.64
3 30910 32610 -1500 -23.06 -2.79-193.94 -6.31 31714 31741 -0.13-0.10 803.62 868.68

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular

Span: 2570 [mm] Rise: 1190 [mm] Q-rise: 1030 [mm]

Ring thickness at crown: 400 [mm] Ring thickness at springing: 400 [mm] Mortar loss: 50 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
0 32610 35032211 3812443 0.00 0.00 0.00 0.00 0.00 0.00 1.62 -45.30 -0.14 0 6 344
1 32621 44632226 5062442 2.29 -1.50 -0.17 -0.00 0.00 0.00 0.00 -0.67 -43.80 -0.40 6 12 338
2 32639 54032249 6302442 2.12 -1.79 -0.22 -0.00 0.00 0.00 0.00 -2.79 -42.01 -0.70 14 20 330
3 32664 63332282 7522441 1.95 -2.03 -0.26 -0.00 0.00 0.00 0.00 -4.74 -39.98 -1.02 23 29 321
4 32696 72432324 8712440 1.77 -2.23 -0.28 -0.00 0.00 0.00 0.00 -6.51 -37.75 -1.38 34 40 310
5 32735 81232375 9862438 1.60 -2.38 -0.29 -0.00 0.00 0.00 0.00 -8.11 -35.37 -1.77 47 52 298
6 32780 89732434 1098 2437 1.43 -2.49 -0.30 -0.00 0.00 0.00 -9.54 -32.88 -2.17 63 68 282

7	32831	97932501	1204	2435	1.26	-2.57	-0.29	-0.00	0.00	0.00	-10.80	-30.32	-2.58	81	85	265	
8	32888	1056	32576	1306	2432	1.10	-2.61	-0.27	-0.00	0.00	0.00	-11.90	-27.71	-3.00	101	105245	
9	32951	1129	32658	1401	2430	0.95	-2.62	-0.25	-0.00	0.00	0.00	-12.85	-25.09	-3.41	124	124128222	
10	33019	1197	32748	1490	2427	0.81	-2.60	-0.23	-0.00	0.00	0.00	-13.66	-22.49	-3.81	149	152198	
11	33092	1260	32843	1572	2424	0.68	-2.57	-0.20	-0.00	0.00	0.00	-14.34	-19.93	-4.19	176	179171	
12	33170	1317	32945	1647	2421	0.57	-2.51	-0.17	-0.00	0.00	0.00	-14.91	-17.41	-4.54	204	207143	
13	33251	1368	33052	1714	2418	0.46	-2.45	-0.13	-0.00	0.00	0.00	-15.37	-14.96	-4.86	232	235115	
14	33336	1413	33163	1773	2414	0.37	-2.38	-0.10	-0.00	0.00	0.00	-15.74	-12.58	-5.14	260	263387	
15	33425	1451	33279	1824	2411	0.29	-2.31	-0.07	-0.00	0.00	0.00	-16.03	-10.26	-5.37	286	289961	
16	33516	1483	33398	1865	2407	0.22	-2.25	-0.03	-0.00	0.00	0.00	-16.26	-8.02	-5.56	309	31238	
17	33609	1508	33520	1898	2403	0.16	-2.19	-0.00	-0.00	0.00	0.00	-16.42	-5.83	-5.70	328	33119	
18	33703	1526	33644	1921	2398	0.11	-2.14	0.03	-0.00	0.00	0.00	-16.53	-3.69	-5.78	341	34337	
19	33799	1536	33769	1935	2394	0.06	-2.10	0.06	-0.00	0.00	0.00	-16.59	-1.60	-5.81	348	350-0	
20	33895	1540	33895	1940	2389	0.02	-2.07	0.09	-0.00	0.00	0.00	-16.61	0.47	-5.79	347	3500	
21	33991	1536	34021	1935	2384	-0.02	-2.06	0.12	0.00	0.00	0.00	-16.59	2.53	-5.71	340	34337	
22	34087	1526	34146	1921	2380	-0.06	-2.06	0.15	0.00	0.00	0.00	-16.53	4.60	-5.59	327	32921	
23	34181	1508	34270	1898	2375	-0.10	-2.08	0.18	0.00	0.00	0.00	-16.42	6.68	-5.41	308	31139	
24	34274	1483	34392	1865	2371	-0.15	-2.12	0.21	0.00	0.00	0.00	-16.27	8.80	-5.19	285	28763	
25	34365	1451	34511	1824	2366	-0.21	-2.16	0.24	0.00	0.00	0.00	-16.07	10.96	-4.93	259	26189	
26	34454	1413	34627	1773	2361	-0.27	-2.21	0.27	0.00	0.00	0.00	-15.80	13.17	-4.62	230	233117	
27	34539	1368	34738	1714	2356	-0.34	-2.27	0.31	0.00	0.00	0.00	-15.46	15.44	-4.29	202	205145	
28	34620	1317	34845	1647	2352	-0.42	-2.33	0.34	0.00	0.00	0.00	-15.03	17.76	-3.93	174	177173	
29	34698	1260	34947	1572	2348	-0.52	-2.38	0.38	0.00	0.00	0.00	-14.52	20.14	-3.54	147	150200	
30	34771	1197	35042	1490	2344	-0.62	-2.43	0.41	0.00	0.00	0.00	-13.89	22.57	-3.15	121	125225	
31	34839	1129	35132	1401	2340	-0.74	-2.46	0.44	0.00	0.00	0.00	-13.15	25.03	-2.75	99	103247	
32	34902	1056	35214	1306	2336	-0.87	-2.48	0.47	0.00	0.00	0.00	-12.28	27.51	-2.35	78	83	267
33	34959	97935289	1204	2332	-1.01	-2.47	0.49	0.00	0.00	0.00	0.00	-11.27	29.99	-1.96	61	65	285
34	35010	89735356	1098	2329	-1.16	-2.44	0.50	0.00	0.00	0.00	0.00	-10.11	32.42	-1.59	46	50	300
35	35055	81235415	9862327	-1.32	-2.38	0.51	0.00	0.00	0.00	0.00	0.00	-8.79	34.80	-1.25	33	38	312
36	35094	72435486	8712325	-1.48	-2.28	0.51	0.00	0.00	0.00	0.00	0.00	-7.31	37.08	-0.94	23	28	322
37	35126	63335508	7522323	-1.65	-2.14	0.50	0.00	0.00	0.00	0.00	0.00	-5.66	39.21	-0.67	14	20	330
38	35151	54035541	6302321	-1.82	-1.96	0.48	0.00	0.00	0.00	0.00	0.00	-3.84	41.17	-0.45	8	14	336
39	35169	46635564	5062320	-1.99	-1.74	0.45	0.00	0.00	0.00	0.00	0.00	-1.86	42.91	-0.27	3	9	341
40	35180	35035579	3812320	-2.15	-1.47	0.40	0.00	0.00	0.00	0.00	0.00	0.29	44.38	-0.14	0	6	344

Segment Intraados.x Intraados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 70 [mm] Thickness at top: 6750 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 35180 41930 70 -316.75 2.26 -316.75 -51.54 38370 38415 -0.05 -0.04 3189.65 3515.10
1 35180 41930 -453 -77.71 2.26 -394.46 -50.36 38399 38456 -0.07 -0.05 3219.16 3474.49
2 35180 41930 -977 -77.71 2.26 -472.18 -49.18 38417 38485 -0.08 -0.06 3237.12 3445.43
3 35180 41930 -1500 -77.71 2.26 -549.89 -48.00 38428 38507 -0.09 -0.08 3248.43 3423.01

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular
Span: 2720 [mm] Rise: 1350 [mm] Q-rise: 1100 [mm]
Ring thickness at crown: 250 [mm] Ring thickness at springing: 250 [mm] Mortar loss: 50 [mm]
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]


Segment Intraados.x Intraados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
0 41930 70 41680 72 2021 0.00 0.00 0.00 0.00 0.00 0.00 0.00 2.54 -32.39 -0.07 0 5 195
1 41935 17641686 1982021 2.17 -0.84 0.02 -0.00 0.00 0.00 0.00 0.38 -31.55 -0.30 7 12 188
2 41948 28241701 3222020 2.01 -1.14 -0.02 -0.00 0.00 0.00 0.00 -1.63 -30.41 -0.52 15 19 181
3 41970 38641727 4462019 1.84 -1.40 -0.04 -0.00 0.00 0.00 0.00 -3.47 -29.01 -0.75 24 28 172

4	41999	48841762	5672017	1.68	-1.60	-0.06	-0.00	0.00	0.00	0.00	0.00	-5.15	-27.41	-0.98	33	37	163
5	42036	58741806	6842016	1.50	-1.77	-0.07	-0.00	0.00	0.00	0.00	0.00	-6.65	-25.64	-1.21	44	48	152
6	42081	68441859	7982013	1.33	-1.89	-0.08	-0.00	0.00	0.00	0.00	0.00	-7.99	-23.75	-1.45	57	60	140
7	42134	77641921	9082011	1.17	-1.96	-0.08	-0.00	0.00	0.00	0.00	0.00	-9.16	-21.79	-1.67	70	73	127
8	42193	86441992	10122008	1.01	-2.00	-0.08	-0.00	0.00	0.00	0.00	0.00	-10.17	-19.79	-1.89	84	87	113
9	42259	94742070	11112004	0.86	-2.01	-0.07	-0.00	0.00	0.00	0.00	0.00	-11.03	-17.78	-2.09	99	102	98
10	42332	102542156	12032001	0.72	-1.99	-0.06	-0.00	0.00	0.00	0.00	0.00	-11.75	-15.79	-2.27	115	118	82
11	42410	109742248	12881998	0.60	-1.94	-0.04	-0.00	0.00	0.00	0.00	0.00	-12.35	-13.85	-2.43	131	133	67
12	42494	116342347	13651993	0.49	-1.88	-0.03	-0.00	0.00	0.00	0.00	0.00	-12.84	-11.97	-2.56	146	148	52
13	42582	122142452	14351989	0.39	-1.81	-0.02	-0.00	0.00	0.00	0.00	0.00	-13.23	-10.16	-2.67	160	162	38
14	42675	127342562	14961985	0.30	-1.72	-0.00	-0.00	0.00	0.00	0.00	0.00	-13.53	-8.44	-2.75	172	174	26
15	42772	131742677	15491981	0.23	-1.64	0.01	-0.00	0.00	0.00	0.00	0.00	-13.76	-6.80	-2.81	183	185	15
16	42872	135442795	15921976	0.17	-1.57	0.02	-0.00	0.00	0.00	0.00	0.00	-13.93	-5.23	-2.85	190	192	8
17	42974	138342916	16261972	0.12	-1.50	0.03	-0.00	0.00	0.00	0.00	0.00	-14.05	-3.74	-2.86	196	198	2
18	43078	140343039	16501968	0.08	-1.44	0.05	-0.00	0.00	0.00	0.00	0.00	-14.13	-2.30	-2.85	198	200	0
19	43184	141643164	16651964	0.04	-1.39	0.06	-0.00	0.00	0.00	0.00	0.00	-14.18	-0.91	-2.82	198	200	0
20	43290	142043290	16701960	0.01	-1.37	0.07	-0.00	0.00	0.00	0.00	0.00	-14.19	0.46	-2.78	195	197	3
21	43396	141643416	16651956	-0.01	-1.36	0.08	0.00	0.00	0.00	0.00	0.00	-14.18	1.82	-2.72	189	191	9
22	43502	140343541	16501952	-0.04	-1.37	0.09	0.00	0.00	0.00	0.00	0.00	-14.13	3.18	-2.64	182	184	16
23	43606	138343664	16261948	-0.07	-1.39	0.11	0.00	0.00	0.00	0.00	0.00	-14.06	4.58	-2.56	172	174	26
24	43708	135443785	15921944	-0.11	-1.43	0.12	0.00	0.00	0.00	0.00	0.00	-13.95	6.01	-2.45	161	163	37
25	43808	131743903	15491941	-0.16	-1.49	0.14	0.00	0.00	0.00	0.00	0.00	-13.79	7.50	-2.34	149	151	49
26	43905	127344018	14961937	-0.21	-1.55	0.15	0.00	0.00	0.00	0.00	0.00	-13.58	9.05	-2.21	135	138	62
27	43998	122144128	14351934	-0.27	-1.62	0.17	0.00	0.00	0.00	0.00	0.00	-13.31	10.68	-2.07	121	124	76
28	44086	116344233	13651932	-0.35	-1.70	0.19	0.00	0.00	0.00	0.00	0.00	-12.95	12.37	-1.92	107	109	91
29	44170	109744332	12881929	-0.44	-1.76	0.21	0.00	0.00	0.00	0.00	0.00	-12.51	14.14	-1.75	92	95	105
30	44248	102544424	12031926	-0.54	-1.82	0.23	0.00	0.00	0.00	0.00	0.00	-11.97	15.96	-1.58	79	81	119
31	44321	94744510	11111923	-0.66	-1.87	0.25	0.00	0.00	0.00	0.00	0.00	-11.31	17.82	-1.40	65	68	132
32	44387	86444588	10121921	-0.79	-1.89	0.26	0.00	0.00	0.00	0.00	0.00	-10.52	19.71	-1.22	53	57	143
33	44446	77644659	9081919	-0.93	-1.89	0.27	0.00	0.00	0.00	0.00	0.00	-9.60	21.60	-1.03	42	46	154
34	44499	68444721	7981918	-1.08	-1.86	0.28	0.00	0.00	0.00	0.00	0.00	-8.52	23.46	-0.86	33	36	164
35	44544	58744774	6841916	-1.23	-1.79	0.28	0.00	0.00	0.00	0.00	0.00	-7.28	25.25	-0.69	24	28	172
36	44581	48844818	5671915	-1.40	-1.69	0.28	0.00	0.00	0.00	0.00	0.00	-5.89	26.94	-0.53	17	21	179
37	44610	38644853	4461914	-1.56	-1.54	0.27	0.00	0.00	0.00	0.00	0.00	-4.33	28.48	-0.39	12	16	184
38	44632	28244879	3221913	-1.73	-1.35	0.26	0.00	0.00	0.00	0.00	0.00	-2.60	29.83	-0.27	7	11	189
39	44645	17644894	1981913	-1.89	-1.11	0.24	0.00	0.00	0.00	0.00	0.00	-0.71	30.94	-0.16	3	8	192
40	44650	7044900	721912	-2.04	-0.83	0.22	0.00	0.00	0.00	0.00	0.00	1.33	31.77	-0.07	0	5	195

Viewing Purposes Only!

Beaumont Bridge

10 (46t 6-axle 10.5t*) impact axle 3 at 24383 mm
17.22 17.22 17.22 39.88 10.55 12.66



46t HA loading in Good Condition with Backing

gammaFI dead load: 1.00 10 (46t 6-axle 10.5t*) impact axle 3 @ 24383 [mm]
gammaFI superimposed: 1.00
gammaFI live load: 2.11
gammaF3 load effect: 1.00
gammaM material: 1.00

File path: V:\5210920\7 Calcs\72 Model\Stage 2 Assessment\Beaumont Bridge w backing.brg

NAME: Beaumont Bridge
LOCATION: Beaumont, Meath
NUMBER: MH-L1615-001.00
Atkins
DATE: 22 February 2022
Printed on: Thursday, February 24, 2022 15:57:17

Bridge Name: Beaumont Bridge Bridge Location: Beaumont, Meath
 Bridge Number: MH-L1615-001.00
 Number of spans: 7

SAFETY FACTORS

Factor for deadload: 1.00 Factor for superimposed deadload: 1.00 Factor for surfacing: 1.00
 Factor for live load: 2.11 Factor for load effect: 1.00 Factor for material strength: 1.00

APPLIED LOAD CASES

1.10 (461.6-axle 10.5t) impact axle 3 Total weight: 451.26 [kN] Position: 24383 [mm]
 46.00 6 1.00 6.00 2.80 5.00 4.10 18.90 9.30 8.16 10.60 8.16 11.90 8.16 1.00 1.80 2.50
 Effective lane width: 3350 [mm] Distribution length: 2755 [mm]

Applied distribution mode: Archie-M, BD21/97
 Applied live load pressure: Active pressure

STRUCTURE PROPERTIES

Road shape: True shape (multi-point method)
 Road points: (-500, 1950) (1180, 2010) (5805, 2150) (11660, 2490) (19175, 2630) (29755, 2500) (33895, 2390) (43290, 1960) (45000, 1900)
 Depth of surfacing: 150Depth of overlay: 0
 Surface unit weight: 23.00 [kN/m3] Overlay unit weight: 23.00 [kN/m3]
 Lane width: 0

Fill unit weight: 18.00 [kN/m3] Fill phi: 30 degree

Left abutment Base level:-1500 [mm] Height: 380 [mm] Width: 1000 [mm]

Right abutment Base level:-1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Right abutment Base level:-1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Shape: Circular

Span: 2360 [mm] Rise: 1170 [mm] Q-rise: 1050 [mm]

Ring thickness at crown:380 [mm] Ring thickness at springing: 380 [mm] Mortar loss: 20 [mm]

Masonry unit weight:22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment	Intrados.x	Intrados.z	Extrados.x	Extrados.z	Road.z	Fx dead	Fz dead	My dead	Fx live	Fz live	My live	Fx passive	Fz total	My total	Thrust in	Thrust out	Extra-Thrust
0	0	380	-380	3831954	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-5.63	-30.87	-2.13	67	71	289
1	4	472	-374	5051954	0.00	-1.08	-0.24	0.00	-0.00	0.00	0.00	-5.63	-29.78	-1.50	47	52	308
2	16	563	-359	6261954	0.00	-1.35	-0.33	0.00	-0.00	0.00	0.00	-5.63	-28.44	-0.98	32	36	324
3	35	654	-334	7451955	0.00	-1.56	-0.39	0.00	-0.00	0.00	0.00	-5.63	-26.88	-0.58	19	23	337
4	60	742	-300	8621956	0.00	-1.72	-0.44	0.00	-0.00	0.00	0.00	-5.63	-25.15	-0.29	9	13	347
5	93	828	-257	9761958	0.00	-1.84	-0.45	0.00	-0.00	0.00	0.00	-5.63	-23.32	-0.11	3	6	354
6	132	912	-206	1086	1960	0.00	-1.90	-0.45	0.00	-0.00	0.00	-5.63	-21.41	-0.03	0	3	357
7	177	992	-146	1192	1962	0.00	-1.93	-0.43	0.00	-0.00	0.00	-5.63	-19.49	-0.04	1	4	356
8	229	1068	-77	1293	1965	0.00	-1.91	-0.40	0.00	-0.00	0.00	-5.63	-17.57	-0.12	6	8	352
9	286	1141	-2	1389	1967	0.00	-1.87	-0.36	0.00	-0.00	0.00	-5.63	-15.71	-0.27	16	18	342
10	349	1208	82	1478	1970	0.00	-1.80	-0.31	0.00	-0.00	0.00	-5.63	-13.91	-0.46	32	34	326
11	417	1270	171	1560	1974	0.00	-1.71	-0.26	0.00	-0.00	0.00	-5.63	-12.20	-0.69	56	57	303
12	490	1327	267	1635	1977	0.28	-1.62	-0.12	0.00	-0.00	0.00	-5.91	-10.58	-1.00	90	92	268
13	566	1378	369	1703	1981	0.21	-1.54	-0.10	0.00	-0.00	0.00	-6.13	-9.05	-1.29	129	131	229
14	647	1423	475	1762	1985	0.16	-1.45	-0.07	0.00	-0.00	0.00	-6.28	-7.59	-1.56	171	173	187
15	731	1461	586	1813	1989	0.11	-1.38	-0.05	0.00	-0.00	0.00	-6.39	-6.22	-1.78	215	216	144
16	817	1493	700	1854	1993	0.08	-1.30	-0.03	0.00	-0.00	0.00	-6.47	-4.91	-1.98	258	259	101
17	906	1518	818	1887	1998	0.05	-1.24	-0.01	0.00	-0.00	0.00	-6.52	-3.67	-2.14	296	297	63
18	996	1536	937	1911	2001	0.03	-1.20	0.01	0.00	-0.00	0.00	-6.55	-2.47	-2.25	328	329	31
19	1088	1546	1058	1925	2006	0.02	-1.17	0.03	0.00	-0.00	0.00	-6.56	-1.30	-2.33	350	351	9
20	1180	1550	1180	1930	2010	0.01	-1.16	0.04	0.00	-0.00	0.00	-6.57	-0.14	-2.36	359	360	0
21	1272	1546	1302	1925	2013	-0.01	-1.17	0.06	-0.00	-0.00	0.00	-6.56	1.03	-2.35	355	356	4

22	1364	1536	1423	1911	2017	-0.02	-1.20	0.08	-0.00	-0.00	0.00	0.00	-6.55	2.23	-2.30	33733822
23	1454	1518	1542	1887	2021	-0.03	-1.24	0.10	-0.00	-0.00	0.00	0.00	-6.51	3.47	-2.20	30830951
24	1543	1493	1660	1854	2024	-0.06	-1.30	0.13	-0.00	-0.00	0.00	0.00	-6.45	4.77	-2.06	27127288
25	1629	1461	1774	1813	2028	-0.09	-1.38	0.15	-0.00	-0.00	0.00	0.00	-6.37	6.15	-1.88	228229131
26	1713	1423	1885	1762	2031	-0.13	-1.46	0.18	-0.00	-0.00	0.00	0.00	-6.24	7.61	-1.66	184185175
27	1794	1378	1991	1703	2034	-0.18	-1.55	0.21	-0.00	-0.00	0.00	0.00	-6.05	9.15	-1.40	140141219
28	1870	1327	2093	1635	2037	-0.25	-1.64	0.24	-0.00	-0.00	0.00	0.00	-5.81	10.79	-1.10	99100260
29	1943	1270	2189	1560	2039	-0.33	-1.73	0.28	-0.00	-0.00	0.00	0.00	-5.48	12.52	-0.77	6263297
30	2011	1208	2278	1478	2041	0.00	-1.82	0.41	0.00	-0.00	0.00	0.00	-5.48	14.34	-0.53	3739321
31	2074	1141	2362	1389	2043	0.00	-1.91	0.46	0.00	-0.00	0.00	0.00	-5.48	16.24	-0.33	1922338
32	2131	1068	2437	1293	2045	0.00	-1.98	0.50	0.00	-0.00	0.00	0.00	-5.48	18.22	-0.17	811349
33	2183	9922506	1192	2047	0.00	-2.02	0.53	0.00	-0.00	0.00	0.00	0.00	-5.48	20.23	-0.06	25355
34	2228	9122566	1086	2049	0.00	-2.02	0.55	0.00	-0.00	0.00	0.00	0.00	-5.48	22.26	-0.04	03357
35	2267	8282617	9762051	0.00	-1.99	0.56	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	24.24	-0.09	26354
36	2300	7422660	8622052	0.00	-1.91	0.54	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	26.15	-0.25	811349
37	2325	6542694	7452053	0.00	-1.78	0.50	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	27.93	-0.52	1620340
38	2344	5632719	6262053	0.00	-1.60	0.44	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	29.54	-0.90	2832328
39	2356	4722734	5052054	0.00	-1.37	0.36	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	30.91	-1.40	4347313
40	2360	3802740	3832054	0.00	-1.09	0.25	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	32.00	-2.02	6165295

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 380 [mm] Thickness at top: 2000 [mm]

Batter: 1:0
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

0 2360 4360 380 -113.98 -3.99 -113.983.75 3385 3401 -0.05 -0.06 1024.74 958.97
1 2360 4360 -247 -27.57 -3.99 -141.55 1.25 3359 3379 -0.07 -0.07 998.71 981.06
2 2360 4360 -873 -27.57 -3.99 -169.13 -1.25 3341 3365 -0.09 -0.08 980.53 995.31
3 2360 4360 -1500 -27.57 -3.99 -196.70 -3.75 3327 3355 -0.10 -0.09 966.89 1005.01

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 2890 [mm] Rise: 1280 [mm] Q-rise: 1020 [mm]

Ring thickness at crown: 270 [mm] Ring thickness at springing: 270 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust

0 4360 4004092 4332089 0.00 0.00 0.00 0.00 0.00 0.00 0.00 -9.47 -32.87 -2.08 59 64 186
1 4377 5044112 5562090 0.00 -1.35 -0.25 0.00 -0.00 0.00 0.00 -9.47 -31.52 -1.36 39 44 206
2 4401 6074140 6782091 0.00 -1.58 -0.29 0.00 -0.00 0.00 0.00 -9.47 -29.94 -0.81 24 28 222
3 4432 7084177 7972092 0.00 -1.76 -0.32 0.00 -0.00 0.00 0.00 -9.47 -28.18 -0.42 12 16 234
4 4471 8064223 9142093 0.00 -1.89 -0.33 0.00 -0.00 0.00 0.00 -9.47 -26.29 -0.17 4 8 242
5 4516 9014277 1026 2095 0.00 -1.97 -0.33 0.00 -0.00 0.00 0.00 -9.47 -24.32 -0.05 0 4 246
6 4569 9934339 1135 2097 0.00 -2.01 -0.32 0.00 -0.00 0.00 0.00 -9.47 -22.30 -0.04 -0 3 247
7 4627 1080 4409 1239 2099 0.00 -2.02 -0.30 0.00 -0.00 0.00 0.00 -9.47 -20.28 -0.12 4 7 243
8 4693 1163 4486 1337 2101 0.00 -1.99 -0.27 0.00 -0.00 0.00 0.00 -9.47 -18.29 -0.26 11 14 236
9 4763 1241 4570 1430 2104 0.00 -1.94 -0.23 0.00 -0.00 0.00 0.00 -9.47 -16.36 -0.45 23 26 224
10 4840 1314 4661 1516 2107 0.00 -1.86 -0.20 0.00 -0.00 0.00 0.00 -9.47 -14.50 -0.68 39 42 208
11 4921 1381 4757 1596 2110 0.00 -1.76 -0.16 0.00 -0.00 0.00 0.00 -9.47 -12.73 -0.92 59 62 188
12 5007 1442 4859 1668 2113 0.00 -1.66 -0.13 0.00 -0.00 0.00 0.00 -9.47 -11.07 -1.18 83 85 165
13 5098 1497 4966 1733 2117 0.27 -1.57 -0.03 0.00 -0.00 0.00 0.00 -9.74 -9.51 -1.48 112 114 136
14 5192 1544 5078 1789 2121 0.20 -1.49 -0.01 0.00 -0.00 0.00 0.00 -9.94 -8.02 -1.75 140 142 108
15 5289 1585 5193 1838 2125 0.15 -1.41 -0.00 0.00 -0.00 0.00 0.00 -10.09 -6.61 -1.98 167 169 81
16 5389 1619 5312 1878 2130 0.11 -1.35 0.01 0.00 -0.00 0.00 0.00 -10.21 -5.26 -2.18 192 194 56
17 5491 1646 5433 1909 2134 0.08 -1.29 0.02 0.00 -0.00 0.00 0.00 -10.28 -3.97 -2.33 213 215 35
18 5595 1665 5556 1932 2139 0.05 -1.25 0.04 0.00 -0.00 0.00 0.00 -10.34 -2.71 -2.46 231 232 18

19	5700	1676	5680	1945	2144	0.03	-1.23	0.05	0.00	-0.00	0.00	0.00	-10.37	-1.48	-2.54	2422446	***
20	5805	1680	5805	1950	2150	0.01	-1.23	0.06	0.00	-0.00	0.00	0.00	-10.38	-0.25	-2.59	2492500	0
21	5910	1676	5930	1945	2155	-0.01	-1.24	0.07	-0.00	-0.00	0.00	0.00	-10.37	0.98	-2.59	2482500	0
22	6015	1665	6054	1932	2161	-0.03	-1.27	0.09	-0.00	-0.00	0.00	0.00	-10.33	2.25	-2.56	2422437	0
23	6119	1646	6177	1909	2167	-0.06	-1.31	0.10	-0.00	-0.00	0.00	0.00	-10.28	3.57	-2.48	22923119	0
24	6221	1619	6298	1878	2173	-0.09	-1.38	0.12	-0.00	-0.00	0.00	0.00	-10.19	4.94	-2.36	21121238	0
25	6321	1585	6417	1838	2179	-0.13	-1.45	0.14	-0.00	-0.00	0.00	0.00	-10.06	6.39	-2.20	18718961	0
26	6418	1544	6532	1789	2184	-0.18	-1.53	0.16	-0.00	-0.00	0.00	0.00	-9.88	7.93	-1.98	16016288	0
27	6512	1497	6644	1733	2191	-0.24	-1.62	0.18	-0.00	-0.00	0.00	0.00	-9.64	9.55	-1.72	131133117	0
28	6603	1442	6751	1668	2196	-0.31	-1.72	0.20	-0.00	-0.00	0.00	0.00	-9.33	11.27	-1.41	100102148	0
29	6689	1381	6853	1596	2201	0.00	-1.82	0.30	0.00	-0.00	0.00	0.00	-9.33	13.09	-1.15	73 76 174	0
30	6770	1314	6949	1516	2207	0.00	-1.93	0.34	0.00	-0.00	0.00	0.00	-9.33	15.02	-0.88	51 53 197	0
31	6847	1241	7040	1430	2212	0.00	-2.03	0.38	0.00	-0.00	0.00	0.00	-9.33	17.05	-0.62	32 35 215	0
32	6917	1163	7124	1337	2217	0.00	-2.10	0.41	0.00	-0.00	0.00	0.00	-9.33	19.15	-0.39	18 20 230	0
33	6983	1080	7201	1239	2222	0.00	-2.16	0.44	0.00	-0.00	0.00	0.00	-9.33	21.31	-0.21	8 11 239	0
34	7041	9937271	1135	2225	0.00	-2.18	0.45	0.00	-0.00	0.00	0.00	0.00	-9.33	23.49	-0.09	2.5 245	0
35	7094	9017333	1026	2229	0.00	-2.16	0.46	0.00	-0.00	0.00	0.00	0.00	-9.33	25.65	-0.05	0 4 246	0
36	7139	8067387	9142232	0.00	-2.11	0.45	0.00	-0.00	0.00	0.00	0.00	0.00	-9.33	27.76	-0.12	2 6 244	0
37	7178	7087433	7972235	0.00	-2.01	0.43	0.00	-0.00	0.00	0.00	0.00	0.00	-9.33	29.76	-0.32	8 13 237	0
38	7209	6077470	6782237	0.00	-1.86	0.40	0.00	-0.00	0.00	0.00	0.00	0.00	-9.33	31.62	-0.67	18 23 227	0
39	7233	5047498	5562239	0.00	-1.66	0.35	0.00	-0.00	0.00	0.00	0.00	0.00	-9.33	33.27	-1.18	32 37 213	0
40	7250	4007518	4332240	0.00	-1.41	0.28	0.00	-0.00	0.00	0.00	0.00	0.00	-9.33	34.68	-1.87	50 55 195	0

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust

Base level: -1500 [mm] Top level: 100 [mm] Thickness at top: 2300 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

0	7250	9550	100	-185.50	-42.51	-185.50	-9.73	8334	8361	-0.09	-0.07	1084.30	1189.20				
1	7250	9550	-433	-26.99	-42.51	-212.49	-32.40	8232	8263	-0.13	-0.06	982.34	1287.30				
2	7250	9550	-967	-26.99	-42.51	-239.48	-55.07	8153	8187	-0.17	-0.04	902.92	1362.86				
3	7250	9550	-1500	-26.99	-42.51	-266.46	-77.74	8089	8127	-0.20	-0.03	839.20	1422.73				

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 4220 [mm] Rise: 1930 [mm] Q-rise: 1560 [mm]

Ring thickness at crown: 350 [mm] Ring thickness at springing: 350 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust

0	9550	1009201	1312346	0.00	0.00	0.00	0.00	0.00	0.00	-51.84	-69.38	-50.26	677687	-357	***		
1	9570	2569224	3132347	0.00	-0.37	-0.56	0.00	-0.00	0.00	-51.84	-67.01	-42.89	570581	-251	***		
2	9601	4099261	4922350	0.00	-2.84	-0.68	0.00	-0.00	0.00	-51.84	-64.17	-36.18	480491	-161	***		
3	9643	5609310	6682353	0.00	-3.21	-0.76	0.00	-0.00	0.00	-51.84	-60.96	-30.13	402413	-83	***		
4	9697	7089373	8402357	0.00	-3.47	-0.80	0.00	-0.00	0.00	-51.84	-57.48	-24.72	335345	-15	***		
5	9761	8519448	1006	2361	0.00	-3.63	-0.80	0.00	-0.00	0.00	-51.84	-53.85	-19.94	27528545			
6	9836	9899535	1167	2367	0.00	-3.70	-0.76	0.00	-0.00	0.00	-51.84	-50.15	-15.74	22123199			
7	9921	1121	9633	1321	2373	0.00	-3.69	-0.70	0.00	-0.00	0.00	-51.84	-46.46	-12.10	174183147		
8	10015	1247	9743	1467	2380	0.00	-3.61	-0.63	0.00	-0.00	0.00	-51.84	-42.84	-8.99	132141189		
9	10118	1365	9864	1605	2388	0.00	-3.47	-0.54	0.00	-0.00	0.00	-51.84	-39.37	-6.38	95 104226		
10	10230	1475	9994	1733	2396	0.00	-3.29	-0.44	0.00	-0.00	0.00	-51.84	-36.08	-4.24	63 72 258		
11	10350	1576	10133	1851	2404	0.00	-3.07	-0.35	0.00	-0.00	0.00	-51.84	-33.01	-2.57	38 46 284		
12	10477	1669	10281	1959	2413	0.00	-2.83	-0.26	0.00	-0.00	0.00	-51.84	-30.18	-1.34	18 27 303		
13	10610	1751	10436	2055	2422	0.00	-2.59	-0.18	0.00	-0.00	0.00	-51.84	-27.59	-0.54	5 13 317		
14	10749	1824	10599	2140	2432	0.28	-2.39	-0.02	0.00	-0.00	0.00	-52.12	-25.20	-0.24	0 8 322		
15	10893	1886	10766	2213	2442	0.20	-2.22	0.01	0.00	-0.00	0.00	-52.32	-22.98	-0.31	1 9 321		

16	11041	1938	10939	2272	2452	0.13	-2.07	0.04	0.00	-0.00	0.00	0.00	-52.45	-20.91	-0.76	9.17	313
17	11193	1978	11116	2319	2461	0.09	-1.95	0.06	0.00	-0.00	0.00	0.00	-52.53	-18.96	-1.59	25.33	297
18	11347	2007	11296	2353	2471	0.05	-1.86	0.08	0.00	-0.00	0.00	0.00	-52.59	-17.09	-2.80	47.55	275
19	11503	2024	11477	2373	2480	0.03	-1.81	0.11	0.00	-0.00	0.00	0.00	-52.61	-15.28	-4.38	78.86	244
20	11660	2030	11660	2380	2490	0.01	-1.80	0.13	0.00	-0.00	0.00	0.00	-52.62	-13.48	-6.34	117.12	206
21	11817	2024	11843	2373	2499	-0.01	-1.83	0.16	-0.00	-0.00	0.00	0.00	-52.61	-11.65	-8.65	164.17	159
22	11973	2007	12024	2353	2507	-0.03	-1.90	0.19	-0.00	-0.02	0.00	0.00	-52.58	-9.73	-11.29	202.27	103
23	12127	1978	12204	2319	2514	-0.07	-2.01	0.22	-0.20	-3.13	0.48	0.00	-52.32	-4.59	-14.24	281.28	842
24	12279	1938	12381	2272	2522	-0.11	-2.15	0.26	-1.06	-12.02	1.76	0.00	-51.14	9.57	-16.87	323.33	0
25	12427	1886	12554	2213	2529	-0.17	-2.32	0.31	-1.99	-17.22	2.60	0.00	-48.98	29.11	-17.97	316.32	246
26	12571	1824	12721	2140	2536	-0.26	-2.51	0.36	-1.96	-13.65	2.14	0.00	-46.76	45.26	-16.83	268.27	753
27	12710	1751	12884	2055	2542	-0.37	-2.72	0.42	-1.06	-6.08	0.99	0.00	-45.33	54.06	-13.98	206.21	614
28	12843	1669	13039	1959	2548	0.00	-2.95	0.61	0.00	-2.46	0.59	0.00	-45.33	59.46	-10.96	150.16	170
29	12970	1576	13187	1851	2552	0.00	-3.21	0.72	0.00	-3.04	0.80	0.00	-45.33	65.72	-8.29	103.11	4216
30	13090	1475	13326	1733	2557	0.00	-3.46	0.82	0.00	-3.78	1.04	0.00	-45.33	72.95	-6.00	67.78	252
31	13202	1365	13456	1605	2561	0.00	-3.68	0.92	0.00	-4.28	1.24	0.00	-45.33	80.91	-4.07	39.52	278
32	13305	1247	13577	1467	2565	0.00	-3.86	1.01	0.00	-4.52	1.36	0.00	-45.33	89.29	-2.54	19.33	297
33	13399	1121	13687	1321	2569	0.00	-3.99	1.09	0.00	-4.50	1.40	0.00	-45.33	97.78	-1.46	6.21	309
34	13484	989	13785	1167	2572	0.00	-4.05	1.13	0.00	-4.28	1.37	0.00	-45.33	106.11	-0.93	0.16	314
35	13559	851	13872	1006	2574	0.00	-4.03	1.15	0.00	-3.89	1.28	0.00	-45.33	114.03	-1.07	0.17	313
36	13623	708	13947	840	2576	0.00	-3.92	1.13	0.00	-3.39	1.13	0.00	-45.33	121.35	-2.00	6.25	305
37	13677	560	14010	668	2577	0.00	-3.72	1.07	0.00	-2.83	0.95	0.00	-45.33	127.90	-3.85	19.38	292
38	13719	409	14059	492	2578	0.00	-3.41	0.97	0.00	-2.24	0.76	0.00	-45.33	133.55	-6.76	38.58	272
39	13750	256	14096	313	2579	0.00	-3.00	0.82	0.00	-1.63	0.55	0.00	-45.33	138.17	-10.82	65.86	244
40	13770	100	14119	131	2580	0.00	-2.47	0.64	0.00	-1.02	0.35	0.00	-45.33	141.66	-16.11	101.12	209

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 100 [mm] Thickness at top: 3150 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 13770 16920 100 -436.90 -46.86 -436.90 -184.53 14891 14954 -0.25 -0.03 1121.43 1966.16
1 13770 16920 -433 -36.96 -46.86 -473.86 -209.53 14869 14937 -0.28 -0.02 1098.99 1983.32
2 13770 16920 -967 -36.96 -46.86 -510.82 -234.52 14849 14922 -0.30 -0.02 1079.41 1997.61
3 13770 16920 -1500 -36.96 -46.86 -547.78 -259.51 14832 14910 -0.33 -0.02 1062.12 2009.62

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular

Span: 4510 [mm] Rise: 2010 [mm] Q-rise: 1660 [mm]

Ring thickness at crown: 370 [mm] Ring thickness at springing: 370 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
0 16920 20016552 2422621 0.00 0.00 0.00 0.00 0.00 0.00 0.00 -93.43 -81.98 -122.20 1320 1333 -983 ***
1 16945 36316581 4322621 0.00 -2.88 -0.73 0.00 -0.17 -0.06 0.00 -93.43 -78.93 -108.00 1130 1144 -794 ***
2 16982 52416624 6202622 0.00 -3.38 -0.86 0.00 -0.22 -0.07 0.00 -93.43 -75.33 -94.67 971984 -634 ***
3 17030 68216680 8032622 0.00 -3.76 -0.95 0.00 -0.26 -0.08 0.00 -93.43 -71.31 -82.22 833847 -497 ***
4 17090 83616750 9832623 0.00 -4.03 -0.98 0.00 -0.27 -0.08 0.00 -93.43 -67.01 -70.68 711725 -375 ***
5 17160 98616832 1156 2624 0.00 -4.19 -0.97 0.00 -0.24 -0.07 0.00 -93.43 -62.57 -60.03 602616 -266 ***
6 17242 1130 16927 1323 2624 0.00 -4.25 -0.92 0.00 -0.20 -0.05 0.00 -93.43 -58.13 -50.28 504518 -168 ***
7 17333 1267 17033 1483 2625 0.00 -4.22 -0.84 0.00 -0.13 -0.03 0.00 -93.43 -53.77 -41.42 415429 -79 ***
8 17435 1397 17151 1635 2626 0.00 -4.11 -0.75 0.00 -0.07 -0.02 0.00 -93.43 -49.59 -33.44 3343482
9 17545 1520 17280 1778 2626 0.00 -3.94 -0.64 0.00 -0.02 -0.00 0.00 -93.43 -45.64 -26.32 26227674
10 17665 1635 17418 1911 2627 0.00 -3.71 -0.52 0.00 -0.00 -0.00 0.00 -93.43 -41.92 -20.07 199213137
11 17792 1740 17566 2033 2628 0.00 -3.45 -0.41 0.00 -0.00 0.00 0.00 -93.43 -38.47 -14.67 143157193
12 17926 1836 17723 2145 2628 0.00 -3.17 -0.30 0.00 -0.00 0.00 0.00 -93.43 -35.30 -10.13 97 111 239

13	18068	1922	17887	2245	2629	0.00	-2.88	-0.20	0.00	-0.00	0.00	0.00	-93.43	-32.42	-6.46	59	73	277	
14	18215	1997	18058	2332	2629	0.30	-2.63	-0.02	0.00	-0.00	0.00	0.00	-93.73	-29.79	-3.74	31	45	305	
15	18367	2061	18235	2407	2629	0.20	-2.41	0.01	0.00	-0.00	0.00	0.00	-93.93	-27.38	-1.86	12	26	324	
16	18523	2114	18417	2469	2630	0.13	-2.22	0.04	0.00	-0.00	0.00	0.00	-94.06	-25.16	-0.83	2	15	335	
17	18683	2156	18603	2517	2630	0.08	-2.05	0.07	0.00	-0.00	0.00	0.00	-94.14	-23.11	-0.67	-0	14	336	
18	18846	2186	18792	2552	2630	0.04	-1.92	0.09	0.00	-0.00	0.00	0.00	-94.18	-21.19	-1.39	8	21	329	
19	19010	2204	18983	2573	2630	0.02	-1.83	0.11	0.00	-0.00	0.00	0.00	-94.21	-19.36	-3.00	25	38	312	
20	19175	2210	19175	2580	2630	0.01	-1.78	0.13	0.00	-0.00	0.00	0.00	-94.21	-17.58	-5.49	52	65	285	
21	19340	2204	19367	2573	2629	-0.01	-1.78	0.16	0.00	-0.00	0.00	0.00	-94.21	-15.80	-8.85	89	102	248	
22	19504	2186	19558	2552	2629	-0.02	-1.83	0.19	0.00	-0.00	0.00	0.00	-94.18	-13.97	-13.07	137	150	200	
23	19667	2156	19747	2517	2628	-0.04	-1.92	0.22	0.00	-0.00	0.00	0.00	-94.14	-12.06	-18.11	196	209	141	
24	19827	2114	19933	2469	2628	-0.08	-2.05	0.26	0.00	-0.25	0.47	0.00	-93.86	-7.67	-24.02	268	280	70	
25	19983	2061	20115	2407	2627	-0.13	-2.21	0.31	0.00	-0.27	0.01	3.52	0.00	-91.47	14.55	-30.45	329	342	8
26	20135	1997	20292	2332	2626	-0.20	-2.40	0.37	0.00	-0.50	0.00	6.77	0.00	-85.86	55.24	-34.69	336	350	-0
27	20282	1922	20463	2245	2626	-0.30	-2.62	0.43	0.00	-0.62	0.00	6.63	0.00	-79.34	94.31	-33.78	285	301	149
28	20424	1836	20627	2145	2625	0.00	-2.87	0.61	0.00	-1.85	0.44	0.00	-79.34	115.75	-29.21	216	234	116	
29	20558	1740	20784	2033	2624	0.00	-3.16	0.72	0.00	-3.92	0.96	0.00	-79.34	122.83	-21.89	149	169	181	
30	20685	1635	20932	1911	2623	0.00	-3.44	0.84	0.00	-1.64	0.47	0.00	-79.34	127.90	-15.22	95	116	234	
31	20805	1520	21070	1778	2622	0.00	-3.70	0.96	0.00	-1.89	0.58	0.00	-79.34	133.50	-9.85	54	76	274	
32	20915	1397	21199	1635	2621	0.00	-3.93	1.07	0.00	-2.03	0.64	0.00	-79.34	139.46	-5.83	26	48	302	
33	21017	1267	21317	1483	2621	0.00	-4.10	1.16	0.00	-2.05	0.67	0.00	-79.34	145.62	-3.21	8	31	319	
34	21108	1130	21423	1323	2620	0.00	-4.21	1.23	0.00	-1.97	0.67	0.00	-79.34	151.80	-2.07	-0	24	326	
35	21190	9862	1518	1156	2620	0.00	-4.24	1.27	0.00	-1.81	0.62	0.00	-79.34	157.86	-2.51	2	27	323	
36	21260	8362	1600	9832	2619	0.00	-4.19	1.26	0.00	-1.59	0.56	0.00	-79.34	163.63	-4.61	12	38	312	
37	21320	6822	1670	8032	2619	0.00	-4.03	1.22	0.00	-1.34	0.48	0.00	-79.34	169.00	-8.46	32	59	291	
38	21368	5242	1726	6202	2618	0.00	-3.76	1.13	0.00	-1.07	0.38	0.00	-79.34	173.83	-14.15	62	89	261	
39	21405	3632	1769	4322	2618	0.00	-3.38	0.99	0.00	-0.80	0.29	0.00	-79.34	178.01	-21.73	101	128	222	
40	21430	2002	1798	2422	2618	0.00	-2.88	0.80	0.00	-0.54	0.19	0.00	-79.34	181.43	-31.25	152	179	171	

Segment Intrados.x Intrados.z Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust

Base level: -1500 [mm] Top level: 200 [mm] Thickness at top: 7170 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment	Left x	Right x	z Weight	Fx	Fz	My Thrust left	Thrust right	Stress left	Stress right	Dist. left	Dist. right		
0	21430	28600	200	-623.12	72.67	-623.12	-388.05	24348	24437	-0.13	-0.04	2917.74	4163.24
1	21430	28600	-367	-89.39	72.67	-712.51	-346.87	24477	24579	-0.14	-0.06	3047.28	4020.94
2	21430	28600	-933	-89.39	72.67	-801.90	-305.69	24577	24691	-0.15	-0.08	3146.51	3908.93
3	21430	28600	-1500	-89.39	72.67	-891.28	-264.51	24655	24782	-0.16	-0.09	3224.56	3818.11

Segment	Left x	Right x	z Weight Fx	Fz	My Thrust left	Thrust right	Stress left	Stress right	Dist. left	Dist. right
Shape:	Circular									
Span:	2310 [mm] Rise: 1150 [mm] Q-rise: 960 [mm]									
Ring thickness at crown:	500 [mm] Ring thickness at springing: 500 [mm] Mortar loss: 20 [mm]									
Masonry unit weight:	22.00 [kN/m ³] Masonry strength: 7.00 [MPa]									

Segment	Intrados.x	Intrados.z	Extrados.x	Extrados.z	Road.z	Fx dead	Fz dead	My dead	Fx live	Fz live	My live	Fx passive	Fx total	Fz total	My total	Thrust in	Thrust out	Extra-Thrust
0	28600	45028	100	4522	532	0.00	0.00	0.00	0.00	0.00	0.00	-7.45	-49.41	-3.21	61	68	412	
1	28604	54028	106	5822	532	0.00	-1.45	-0.43	0.00	0.00	0.00	-7.45	-47.96	-2.29	44	51	429	
2	28615	63028	121	7102	532	0.00	-1.83	-0.60	0.00	0.00	0.00	-7.45	-46.14	-1.52	29	36	444	
3	28633	71928	147	8372	531	0.00	-2.14	-0.73	0.00	0.00	0.00	-7.45	-43.99	-0.92	18	24	456	
4	28658	80628	183	9622	530	0.00	-2.40	-0.83	0.00	0.00	0.00	-7.45	-41.59	-0.49	9	15	465	
5	28689	89028	228	1083	2530	0.00	-2.60	-0.89	0.00	0.00	0.00	-7.45	-38.99	-0.21	3	8	472	
6	28727	97228	283	1201	2529	0.00	-2.75	-0.91	0.00	0.00	0.00	-7.45	-36.24	-0.09	-0	5	475	
7	28772	1051	28346	1314	2527	0.00	-2.84	-0.90	0.00	0.00	0.00	-7.45	-33.40	-0.11	1	6	474	
8	28822	1126	28419	1421	2526	0.00	-2.88	-0.86	0.00	0.00	0.00	-7.45	-30.52	-0.25	6	11	469	
9	28879	1197	28499	1523	2525	0.00	-2.89	-0.80	0.00	0.00	0.00	-7.45	-27.63	-0.49	17	21	459	

10	28940	1263	28587	1618	2523	0.00	-2.85	-0.72	0.00	0.00	0.00	0.00	0.00	-7.45	-24.78	-0.81	34	37	443
11	29007	1325	28583	1706	2521	0.00	-2.79	-0.64	0.00	0.00	0.00	0.00	0.00	-7.45	-21.99	-1.20	59	62	418
12	29078	1381	28785	1786	2519	0.00	-2.72	-0.55	0.00	0.00	0.00	0.00	0.00	-7.45	-19.27	-1.62	92	95	385
13	29153	1431	28892	1857	2517	0.48	-2.64	-0.26	0.00	0.00	0.00	0.00	0.00	-7.92	-16.63	-2.23	144	146	334
14	29232	1475	29006	1921	2515	0.38	-2.57	-0.21	0.00	0.00	0.00	0.00	0.00	-8.30	-14.06	-2.79	201	203	277
15	29314	1513	29123	1975	2512	0.30	-2.50	-0.15	0.00	0.00	0.00	0.00	0.00	-8.60	-11.56	-3.27	263	265	215
16	29399	1544	29245	2019	2510	0.22	-2.43	-0.10	0.00	0.00	0.00	0.00	0.00	-8.82	-9.14	-3.67	327	328	152
17	29486	1568	29370	2055	2508	0.16	-2.36	-0.06	0.00	0.00	0.00	0.00	0.00	-8.99	-6.77	-3.99	386	387	93
18	29575	1586	29497	2080	2505	0.11	-2.31	-0.01	0.00	0.00	0.00	0.00	0.00	-9.10	-4.47	-4.22	435	437	43
19	29665	1596	29626	2095	2502	0.06	-2.27	0.04	0.00	0.00	0.00	0.00	0.00	-9.16	-2.20	-4.36	468	469	11
20	29755	1600	29755	2100	2499	0.02	-2.25	0.08	0.00	0.00	0.00	0.00	0.00	-9.18	0.05	-4.40	479	480	0
21	29845	1596	29884	2095	2497	-0.02	-2.24	0.12	0.00	0.00	0.00	0.00	0.00	-9.16	2.29	-4.35	466	468	12
22	29935	1586	30013	2080	2494	-0.06	-2.25	0.17	0.00	0.00	0.00	0.00	0.00	-9.10	4.54	-4.20	432	434	46
23	30024	1568	30140	2055	2491	-0.11	-2.28	0.22	0.00	0.00	0.00	0.00	0.00	-8.99	6.82	-3.96	383	384	96
24	30111	1544	30265	2019	2488	-0.16	-2.32	0.26	0.00	0.00	0.00	0.00	0.00	-8.83	9.14	-3.63	323	325	155
25	30196	1513	30387	1975	2486	-0.21	-2.37	0.31	0.00	0.00	0.00	0.00	0.00	-8.62	11.51	-3.23	260	262	218
26	30278	1475	30504	1921	2484	-0.28	-2.44	0.36	0.00	0.00	0.00	0.00	0.00	-8.34	13.95	-2.74	199	201	279
27	30357	1431	30618	1857	2481	-0.36	-2.50	0.42	0.00	0.00	0.00	0.00	0.00	-7.98	16.45	-2.20	142	144	336
28	30432	1381	30725	1786	2478	-0.45	-2.57	0.47	0.00	0.00	0.00	0.00	0.00	-7.53	19.02	-1.59	91	94	386
29	30503	1325	30827	1706	2476	0.00	-2.64	0.72	0.00	0.00	0.00	0.00	0.00	-7.53	21.66	-1.17	58	61	419
30	30570	1263	30923	1618	2474	0.00	-2.71	0.80	0.00	0.00	0.00	0.00	0.00	-7.53	24.37	-0.79	33	36	444
31	30631	1197	31011	1523	2472	0.00	-2.77	0.87	0.00	0.00	0.00	0.00	0.00	-7.53	27.14	-0.46	16	20	460
32	30688	1126	31091	1421	2470	0.00	-2.81	0.93	0.00	0.00	0.00	0.00	0.00	-7.53	29.95	-0.23	6	10	470
33	30738	1051	31164	1314	2469	0.00	-2.81	0.97	0.00	0.00	0.00	0.00	0.00	-7.53	32.75	-0.10	1	5	475
34	30783	972	31227	1201	2467	0.00	-2.77	0.99	0.00	0.00	0.00	0.00	0.00	-7.53	35.52	-0.09	0	5	475
35	30821	890	31282	1083	2466	0.00	-2.69	0.98	0.00	0.00	0.00	0.00	0.00	-7.53	38.21	-0.22	3	8	472
36	30852	806	31327	962	2465	0.00	-2.55	0.94	0.00	0.00	0.00	0.00	0.00	-7.53	40.76	-0.50	9	15	465
37	30877	719	31363	837	2464	0.00	-2.36	0.87	0.00	0.00	0.00	0.00	0.00	-7.53	43.12	-0.94	19	25	455
38	30895	630	31389	710	2463	0.00	-2.11	0.76	0.00	0.00	0.00	0.00	0.00	-7.53	45.23	-1.55	31	37	443
39	30906	540	31404	582	2463	0.00	-1.81	0.61	0.00	0.00	0.00	0.00	0.00	-7.53	47.04	-2.33	46	52	428
40	30910	450	31410	452	2463	0.00	-1.44	0.43	0.00	0.00	0.00	0.00	0.00	-7.53	48.48	-3.26	64	71	409

Segment Intrados x Intrados z Extrados x Extrados z Road z Fx dead Fz dead My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 350 [mm] Thickness at top: 1700 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

0 30910 32610 350-132.21 -2.73 -132.21 1.40 31761 31780 -0.07 -0.08 851.18 829.93
1 30910 32610 -267 -23.06 -2.73 -155.27 -0.28 31747 31769 -0.09 -0.09 837.12 840.69
2 30910 32610 -883 -23.06 -2.73 -178.33 -1.96 31736 31762 -0.11 -0.10 826.28 848.25
3 30910 32610 -1500 -23.06 -2.73 -201.40 -3.64 31728 31756 -0.13 -0.11 817.54 853.69

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 2570 [mm] Rise: 1190 [mm] Q-rise: 1030 [mm]

Ring thickness at crown: 400 [mm] Ring thickness at springing: 400 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Intrados x Intrados z Extrados x Extrados z Road z Fx dead Fz dead My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust

0 32610 35032211 3812442 0.00 0.00 0.00 0.00 0.00 0.00 0.00 -10.25 -47.26 -2.71 53 60 320
1 32621 44632226 5062441 0.00 -1.57 -0.42 0.00 0.00 0.00 -10.25 -45.68 -1.81 35 42 338
2 32639 54032249 6302441 0.00 -1.90 -0.53 0.00 0.00 0.00 -10.25 -43.79 -1.10 21 28 352
3 32664 63332282 7522440 0.00 -2.16 -0.60 0.00 0.00 0.00 -10.25 -41.63 -0.59 11 17 363
4 32696 72432324 8712439 0.00 -2.38 -0.66 0.00 0.00 0.00 -10.25 -39.25 -0.26 4 9 371
5 32735 81232375 9862437 0.00 -2.54 -0.68 0.00 0.00 0.00 -10.25 -36.71 -0.10 0 5 375
6 32780 89732434 1098 2436 0.00 -2.65 -0.68 0.00 0.00 0.00 -10.25 -34.06 -0.09 0 5 375

7	32831	97932501	1204	2434	0.00	-2.72	-0.66	0.00	0.00	0.00	0.00	-10.25	-31.35	-0.22	5.9	371
8	32888	1056	32576	1306	2432	0.00	-2.74	-0.62	0.00	0.00	0.00	-10.25	-28.60	-0.45	14	362
9	32951	1129	32658	1401	2430	0.00	-2.73	-0.57	0.00	0.00	0.00	-10.25	-25.87	-0.77	28	31
10	33019	1197	32748	1490	2427	0.00	-2.70	-0.51	0.00	0.00	0.00	-10.25	-23.17	-1.15	48	51
11	33092	1260	32843	1572	2424	0.00	-2.63	-0.45	0.00	0.00	0.00	-10.25	-20.54	-1.57	74	77
12	33170	1317	32945	1647	2421	0.00	-2.56	-0.38	0.00	0.00	0.00	-10.25	-17.98	-2.02	107	110
13	33251	1368	33052	1714	2418	0.47	-2.48	-0.15	-0.00	0.00	0.00	-10.72	-15.50	-2.59	151	154
14	33336	1413	33163	1773	2414	0.38	-2.41	-0.11	-0.00	0.00	0.00	-11.10	-13.09	-3.11	197	199
15	33425	1451	33279	1824	2411	0.30	-2.34	-0.08	-0.00	0.00	0.00	-11.40	-10.75	-3.55	243	245
16	33516	1483	33398	1865	2406	0.23	-2.28	-0.04	-0.00	0.00	0.00	-11.63	-8.47	-3.92	287	289
17	33609	1508	33520	1898	2402	0.17	-2.22	-0.01	-0.00	0.00	0.00	-11.79	-6.26	-4.20	325	327
18	33703	1526	33644	1921	2398	0.11	-2.17	0.02	-0.00	0.00	0.00	-11.90	-4.09	-4.40	353	356
19	33799	1536	33769	1935	2394	0.06	-2.13	0.06	-0.00	0.00	0.00	-11.97	-1.96	-4.52	373	375
20	33895	1540	33895	1940	2390	0.02	-2.10	0.09	-0.00	0.00	0.00	-11.99	0.14	-4.55	378	380
21	33991	1536	34021	1935	2385	-0.02	-2.09	0.12	0.00	0.00	0.00	-11.97	2.23	-4.49	370	372
22	34087	1526	34146	1921	2381	-0.06	-2.10	0.15	0.00	0.00	0.00	-11.90	4.33	-4.35	349	351
23	34181	1508	34270	1898	2376	-0.11	-2.12	0.18	0.00	0.00	0.00	-11.80	6.45	-4.12	318	320
24	34274	1483	34392	1865	2371	-0.16	-2.15	0.21	0.00	0.00	0.00	-11.64	8.59	-3.82	279	281
25	34365	1451	34511	1824	2366	-0.21	-2.19	0.25	0.00	0.00	0.00	-11.43	10.79	-3.44	235	237
26	34454	1413	34627	1773	2362	-0.28	-2.24	0.28	0.00	0.00	0.00	-11.15	13.03	-2.99	189	192
27	34539	1368	34738	1714	2357	-0.35	-2.30	0.32	0.00	0.00	0.00	-10.81	15.33	-2.48	144	147
28	34620	1317	34845	1647	2353	-0.43	-2.36	0.36	0.00	0.00	0.00	-10.37	17.68	-1.91	102	104
29	34698	1260	34947	1572	2349	0.00	-2.42	0.54	0.00	0.00	0.00	-10.37	20.11	-1.47	70	73
30	34771	1197	35042	1490	2345	0.00	-2.50	0.60	0.00	0.00	0.00	-10.37	22.60	-1.06	45	48
31	34839	1129	35132	1401	2341	0.00	-2.56	0.66	0.00	0.00	0.00	-10.37	25.16	-0.69	25	29
32	34902	1056	35214	1306	2338	0.00	-2.60	0.70	0.00	0.00	0.00	-10.37	27.76	-0.39	12	16
33	34959	97935289	1204	2334	0.00	-2.61	0.74	0.00	0.00	0.00	0.00	-10.37	30.38	-0.18	4	8
34	35010	89735356	1098	2331	0.00	-2.59	0.76	0.00	0.00	0.00	0.00	-10.37	32.97	-0.08	-0	5
35	35055	81235415	9862329	0.00	-2.54	0.76	0.00	0.00	0.00	0.00	0.00	-10.37	35.51	-0.11	0	6
36	35094	72435466	8712327	0.00	-2.44	0.74	0.00	0.00	0.00	0.00	0.00	-10.37	37.94	-0.30	5	10
37	35126	63335508	7522325	0.00	-2.29	0.70	0.00	0.00	0.00	0.00	0.00	-10.37	40.23	-0.65	13	19
38	35151	54035541	6302323	0.00	-2.09	0.63	0.00	0.00	0.00	0.00	0.00	-10.37	42.33	-1.18	24	30
39	35169	44635564	5062322	0.00	-1.85	0.54	0.00	0.00	0.00	0.00	0.00	-10.37	44.17	-1.91	39	45
40	35180	35035579	3812322	0.00	-1.54	0.42	0.00	0.00	0.00	0.00	0.00	-10.37	45.72	-2.83	58	64

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 Base level: -1500 [mm] Top level: 70 [mm] Thickness at top: 6750 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 0 35180 41930 70 -354.06 0.76 -354.06 -44.57 38404 38454 -0.06 -0.05 3223.82 3475.60
 1 35180 41930 -453 -77.71 0.76 -431.78 -44.17 38422 38484 -0.07 -0.06 3241.85 3446.47
 2 35180 41930 -977 -77.71 0.76 -509.49 -43.78 38433 38505 -0.08 -0.07 3252.68 3424.53
 3 35180 41930 -1500 -77.71 0.76 -587.21 -43.38 38439 38523 -0.09 -0.08 3259.18 3406.94


Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 Shape: Circular
 Span: 2720 [mm] Rise: 1350 [mm] Q-rise: 1100 [mm]
 Ring thickness at crown: 250 [mm] Ring thickness at springing: 250 [mm] Mortar loss: 20 [mm]
 Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 0 41930 70 41680 72 2026 0.00 0.00 0.00 0.00 0.00 0.00 0.00 -9.62 -34.38 -3.26 92 97 133
 1 41935 17641686 1982026 0.00 -0.87 -0.13 0.00 0.00 0.00 0.00 -9.62 -33.51 -2.26 64 69 161
 2 41948 28241701 3222025 0.00 -1.22 -0.21 0.00 0.00 0.00 0.00 -9.62 -32.29 -1.46 41 46 184
 3 41970 38641727 4462024 0.00 -1.51 -0.26 0.00 0.00 0.00 0.00 -9.62 -30.78 -0.85 24 29 201

4	41999	48841762	5672022	0.00	-1.74	-0.30	0.00	0.00	0.00	0.00	-9.62	-29.03	-0.43	12	16	214	
5	42036	58741806	6842021	0.00	-1.92	-0.32	0.00	0.00	0.00	0.00	-9.62	-27.11	-0.17	4	8	222	
6	42081	68441859	7982018	0.00	-2.05	-0.32	0.00	0.00	0.00	0.00	-9.62	-25.06	-0.05	-0	4	226	
7	42134	77641921	9082016	0.00	-2.12	-0.31	0.00	0.00	0.00	0.00	-9.62	-22.94	-0.05	0	4	226	
8	42193	86441992	10122013	0.00	-2.16	-0.29	0.00	0.00	0.00	0.00	-9.62	-20.78	-0.16	5	9	221	
9	42259	94742070	1111	2009	0.00	-2.15	-0.27	0.00	0.00	0.00	-9.62	-18.63	-0.33	15	18	212	
10	42332	102542156	12032006	0.00	-2.11	-0.23	0.00	0.00	0.00	0.00	-9.62	-16.53	-0.56	29	31	199	
11	42410	109742248	12882002	0.00	-2.04	-0.19	0.00	0.00	0.00	0.00	-9.62	-14.49	-0.81	47	50	180	
12	42494	116342347	13651997	0.00	-1.95	-0.16	0.00	0.00	0.00	0.00	-9.62	-12.54	-1.08	70	73	157	
13	42582	122142452	14351993	0.00	-1.85	-0.12	0.00	0.00	0.00	0.00	-9.62	-10.69	-1.35	97	99	131	
14	42675	127342562	14961988	0.31	-1.76	-0.01	-0.00	0.00	0.00	0.00	-9.93	-8.93	-1.66	128	130	100	
15	42772	131742677	15491984	0.24	-1.68	0.00	-0.00	0.00	0.00	0.00	-10.17	-7.26	-1.91	156	158	72	
16	42872	135442795	15921979	0.18	-1.60	0.02	-0.00	0.00	0.00	0.00	-10.34	-5.65	-2.12	182	184	46	
17	42974	138342916	16261974	0.13	-1.53	0.03	-0.00	0.00	0.00	0.00	-10.47	-4.12	-2.27	203	205	25	
18	43078	140343039	16501969	0.08	-1.47	0.04	-0.00	0.00	0.00	0.00	-10.55	-2.65	-2.37	218	220	10	
19	43184	141643164	16651964	0.05	-1.43	0.06	-0.00	0.00	0.00	0.00	-10.60	-1.23	-2.43	227	229	1	
20	43290	142043290	16701959	0.01	-1.40	0.07	-0.00	0.00	0.00	0.00	-10.61	0.17	-2.43	228	230	0	
21	43396	141643416	16651954	-0.01	-1.39	0.08	0.00	0.00	0.00	0.00	-10.60	1.56	-2.39	232	234	6	
22	43502	140343541	16501950	-0.04	-1.39	0.09	0.00	0.00	0.00	0.00	-10.55	2.95	-2.30	211	212	18	
23	43606	138343664	16261946	-0.08	-1.42	0.11	0.00	0.00	0.00	0.00	-10.48	4.37	-2.17	193	194	36	
24	43708	135443785	15921942	-0.12	-1.46	0.13	0.00	0.00	0.00	0.00	-10.36	5.83	-1.99	170	172	58	
25	43808	131743903	15491937	-0.16	-1.51	0.14	0.00	0.00	0.00	0.00	-10.20	7.34	-1.77	144	145	85	
26	43905	127344018	14961933	-0.21	-1.57	0.16	0.00	0.00	0.00	0.00	-9.99	8.92	-1.50	115	117	113	
27	43998	122144128	14351930	-0.28	-1.64	0.18	0.00	0.00	0.00	0.00	-9.71	10.56	-1.20	86	88	142	
28	44086	116344233	13651926	0.00	-1.72	0.26	0.00	0.00	0.00	0.00	-9.71	12.28	-0.94	61	63	167	
29	44170	109744332	12881923	0.00	-1.82	0.30	0.00	0.00	0.00	0.00	-9.71	14.10	-0.68	40	42	188	
30	44248	102544424	12031919	0.00	-1.90	0.33	0.00	0.00	0.00	0.00	-9.71	16.00	-0.45	23	26	204	
31	44321	94744510	1111	1916	0.00	-1.97	0.36	0.00	0.00	0.00	-9.71	17.96	-0.25	11	14	216	
32	44387	86444588	10121914	0.00	-2.01	0.38	0.00	0.00	0.00	0.00	-9.71	19.98	-0.11	3	6	224	
33	44446	77644659	9081912	0.00	-2.03	0.39	0.00	0.00	0.00	0.00	-9.71	22.00	-0.04	-0	3	227	
34	44499	68444721	7981909	0.00	-2.01	0.40	0.00	0.00	0.00	0.00	-9.71	24.01	-0.07	1	5	225	
35	44544	58744774	6841907	0.00	-1.94	0.39	0.00	0.00	0.00	0.00	-9.71	25.95	-0.23	6	10	220	
36	44581	48844818	5671906	0.00	-1.83	0.37	0.00	0.00	0.00	0.00	-9.71	27.78	-0.52	16	20	210	
37	44610	38644853	4461905	0.00	-1.67	0.33	0.00	0.00	0.00	0.00	-9.71	29.45	-0.98	29	34	196	
38	44632	28244879	3221904	0.00	-1.46	0.28	0.00	0.00	0.00	0.00	-9.71	30.91	-1.61	48	53	177	
39	44645	17644894	1981903	0.00	-1.18	0.21	0.00	0.00	0.00	0.00	-9.71	32.09	-2.43	72	77	153	
40	44650	70	44900	72	1903	0.00	-0.86	0.13	0.00	0.00	0.00	-9.71	32.95	-3.45	102	107	123

MP Council - Viewing Purposes Only!

Beaumont Bridge



SV100 loading in Good Condition with Backing

gammaFI dead load: 1.00 SV100 Impact on 1 @ 18219 [mm]
gammaFI superimposed: 1.00
gammaFI live load: 2.22
gammaF3 load effect: 1.00
gammaM material: 1.00

File path: V:\5210920\7 Calcs\72 Model\Stage 2 Assessment\Beaumont Bridge w backing.brg

NAME: Beaumont Bridge
LOCATION: Beaumont, Meath
NUMBER: MH-L1615-001.00
Atkins
DATE: 22 February 2022
Printed on: Thursday, February 24, 2022 16:19:09

Bridge Name: Beaumont Bridge Bridge Location: Beaumont, Meath
 Bridge Number: MH-L1615-001.00
 Number of spans: 7

SAFETY FACTORS

Factor for deadload: 1.00 Factor for superimposed deadload: 1.00 Factor for surfacing: 1.00
 Factor for live load: 2.22 Factor for load effect: 1.00 Factor for material strength: 1.00

APPLIED LOAD CASES

1.SV100 Impact on 1 Total weight: 1216.44 [kN] Position: 18219 [mm]
 124.00 6 1.00 22.00 1.20 20.40 2.40 20.40 3.60 20.40 4.80 20.40 6.00 20.40 1.00 2.65 3.00
 Effective lane width: 3350 [mm] Distribution length: 2743 [mm]

Applied distribution mode: Archie-M BD21/97

Applied live load pressure: Active pressure

STRUCTURE PROPERTIES

Road shape: True shape (multi-point method)
 Road points: (-500, 1950) (1180, 2010) (5805, 2150) (11660, 2490) (19175, 2630) (29755, 2500) (33895, 2390) (43290, 1960) (45000, 1900)
 Depth of surfacing: 150Depth of overlay: 0
 Surface unit weight: 23.00 [kN/m3] Overlay unit weight: 23.00 [kN/m3]
 Lane width: 0

Fill unit weight: 18.00 [kN/m3] Fill phi: 30 degree

Left abutment Base level:-1500 [mm] Height: 380 [mm] Width: 1000 [mm]

Right abutment Base level:-1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Right abutment Base level:-1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Shape: Circular

Span: 2360 [mm] Rise: 1170 [mm] Q-rise: 1050 [mm]

Ring thickness at crown:380 [mm] Ring thickness at springing: 380 [mm] Mortar loss: 20 [mm]

Masonry unit weight:22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment	Intrados.x	Intrados.z	Extrados.x	Extrados.z	Road.z	Fx dead	Fz dead	My dead	Fx live	Fz live	My live	Fx passive	Fz total	My total	Thrust in	Thrust out	Extra-Thrust	
0	0	380	-380	3831954	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-5.63	-30.87	-2.13	67	71	289	
1	4	472	-374	5051954	0.00	-1.08	-0.24	0.00	-0.00	0.00	0.00	-5.63	-29.78	-1.50	47	52	308	
2	16	563	-359	6261954	0.00	-1.35	-0.33	0.00	-0.00	0.00	0.00	-5.63	-28.44	-0.98	32	36	324	
3	35	654	-334	7451955	0.00	-1.56	-0.39	0.00	-0.00	0.00	0.00	-5.63	-26.88	-0.58	19	23	337	
4	60	742	-300	8621956	0.00	-1.72	-0.44	0.00	-0.00	0.00	0.00	-5.63	-25.15	-0.29	9	13	347	
5	93	828	-257	9761958	0.00	-1.84	-0.45	0.00	-0.00	0.00	0.00	-5.63	-23.32	-0.11	3	6	354	
6	132	912	-206	1086	1960	0.00	-1.90	-0.45	0.00	-0.00	0.00	0.00	-5.63	-21.41	-0.03	0	3	357
7	177	992	-146	1192	1962	0.00	-1.93	-0.43	0.00	-0.00	0.00	0.00	-5.63	-19.49	-0.04	1	4	356
8	229	1068	-77	1293	1965	0.00	-1.91	-0.40	0.00	-0.00	0.00	0.00	-5.63	-17.57	-0.12	6	8	352
9	286	1141	-2	1389	1967	0.00	-1.87	-0.36	0.00	-0.00	0.00	0.00	-5.63	-15.71	-0.27	16	18	342
10	349	1208	82	1478	1970	0.00	-1.80	-0.31	0.00	-0.00	0.00	0.00	-5.63	-13.91	-0.46	32	34	326
11	417	1270	171	1560	1974	0.00	-1.71	-0.26	0.00	-0.00	0.00	0.00	-5.63	-12.20	-0.69	56	57	303
12	490	1327	267	1635	1977	0.28	-1.62	-0.12	0.00	-0.00	0.00	0.00	-5.91	-10.58	-1.00	90	92	268
13	566	1378	369	1703	1981	0.21	-1.54	-0.10	0.00	-0.00	0.00	0.00	-6.13	-9.05	-1.29	129	131	229
14	647	1423	475	1762	1985	0.16	-1.45	-0.07	0.00	-0.00	0.00	0.00	-6.28	-7.59	-1.56	171	173	187
15	731	1461	586	1813	1989	0.11	-1.38	-0.05	0.00	-0.00	0.00	0.00	-6.39	-6.22	-1.78	215	216	144
16	817	1493	700	1854	1993	0.08	-1.30	-0.03	0.00	-0.00	0.00	0.00	-6.47	-4.91	-1.98	258	259	101
17	906	1518	818	1887	1998	0.05	-1.24	-0.01	0.00	-0.00	0.00	0.00	-6.52	-3.67	-2.14	296	297	63
18	996	1536	937	1911	2001	0.03	-1.20	0.01	0.00	-0.00	0.00	0.00	-6.55	-2.47	-2.25	328	329	31
19	1088	1546	1058	1925	2006	0.02	-1.17	0.03	0.00	-0.00	0.00	0.00	-6.56	-1.30	-2.33	350	351	19
20	1180	1550	1180	1930	2010	0.01	-1.16	0.04	0.00	-0.00	0.00	0.00	-6.57	-0.14	-2.36	359	360	0
21	1272	1546	1302	1925	2013	-0.01	-1.17	0.06	-0.00	-0.00	0.00	0.00	-6.56	1.03	-2.35	355	356	4

22	1364	1536	1423	1911	2017	-0.02	-1.20	0.08	-0.00	-0.00	0.00	0.00	-6.55	2.23	-2.30	33733822
23	1454	1518	1542	1887	2021	-0.03	-1.24	0.10	-0.00	-0.00	0.00	0.00	-6.51	3.47	-2.20	30830951
24	1543	1493	1660	1854	2024	-0.06	-1.30	0.13	-0.00	-0.00	0.00	0.00	-6.45	4.77	-2.06	27127288
25	1629	1461	1774	1813	2028	-0.09	-1.38	0.15	-0.00	-0.00	0.00	0.00	-6.37	6.15	-1.88	228229131
26	1713	1423	1885	1762	2031	-0.13	-1.46	0.18	-0.00	-0.00	0.00	0.00	-6.24	7.61	-1.66	184185175
27	1794	1378	1991	1703	2034	-0.18	-1.55	0.21	-0.00	-0.00	0.00	0.00	-6.05	9.15	-1.40	140141219
28	1870	1327	2093	1635	2037	-0.25	-1.64	0.24	-0.00	-0.00	0.00	0.00	-5.81	10.79	-1.10	99100260
29	1943	1270	2189	1560	2039	-0.33	-1.73	0.28	-0.00	-0.00	0.00	0.00	-5.48	12.52	-0.77	632297
30	2011	1208	2278	1478	2041	0.00	-1.82	0.41	0.00	-0.00	0.00	0.00	-5.48	14.34	-0.53	3739321
31	2074	1141	2362	1389	2043	0.00	-1.91	0.46	0.00	-0.00	0.00	0.00	-5.48	16.24	-0.33	1922338
32	2131	1068	2437	1293	2045	0.00	-1.98	0.50	0.00	-0.00	0.00	0.00	-5.48	18.22	-0.17	811349
33	2183	9922506	1192	2047	0.00	-2.02	0.53	0.00	-0.00	0.00	0.00	0.00	-5.48	20.23	-0.06	25355
34	2228	9122566	1086	2049	0.00	-2.02	0.55	0.00	-0.00	0.00	0.00	0.00	-5.48	22.26	-0.04	03357
35	2267	8282617	9762051	0.00	-1.99	0.56	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	24.24	-0.09	26354
36	2300	7422660	8622052	0.00	-1.91	0.54	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	26.15	-0.25	811349
37	2325	6542694	7452053	0.00	-1.78	0.50	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	27.93	-0.52	1620340
38	2344	5632719	6262053	0.00	-1.60	0.44	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	29.54	-0.90	2832328
39	2356	4722734	5052054	0.00	-1.37	0.36	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	30.91	-1.40	4347313
40	2360	3802740	3832054	0.00	-1.09	0.25	0.00	-0.00	0.00	0.00	0.00	0.00	-5.48	32.00	-2.02	6165295

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 Base level: -1500 [mm] Top level: 380 [mm] Thickness at top: 2000 [mm]
 Batter: 1:0
 Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 2360 4360 380 -113.98 -3.99 -113.983.75 3385 3401 -0.05 -0.06 1024.74 958.97
1 2360 4360 -247 -27.57 -3.99 -141.55 1.25 3359 3379 -0.07 -0.07 998.71 981.06
2 2360 4360 -873 -27.57 -3.99 -169.13 -1.25 3341 3365 -0.09 -0.08 980.53 995.31
3 2360 4360 -1500 -27.57 -3.99 -196.70 -3.75 3327 3355 -0.10 -0.09 966.89 1005.01

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular
Span: 2890 [mm] Rise: 1280 [mm] Q-rise: 1020 [mm]
Ring thickness at crown: 270 [mm] Ring thickness at springing: 270 [mm] Mortar loss: 20 [mm]
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
0 4360 4004092 4332089 0.00 0.00 0.00 0.00 0.00 0.00 0.00 -9.47 -32.87 -2.08 59 64 186
1 4377 5044112 5562090 0.00 -1.35 -0.25 0.00 -0.00 0.00 0.00 -9.47 -31.52 -1.36 39 44 206
2 4401 6074140 6782091 0.00 -1.58 -0.29 0.00 -0.00 0.00 0.00 -9.47 -29.94 -0.81 24 28 222
3 4432 7084177 7972092 0.00 -1.76 -0.32 0.00 -0.00 0.00 0.00 -9.47 -28.18 -0.42 12 16 234
4 4471 8064223 9142093 0.00 -1.89 -0.33 0.00 -0.00 0.00 0.00 -9.47 -26.29 -0.17 4 8 242
5 4516 9014277 1026 2095 0.00 -1.97 -0.33 0.00 -0.00 0.00 0.00 -9.47 -24.32 -0.05 0 4 246
6 4569 9934339 1135 2097 0.00 -2.01 -0.32 0.00 -0.00 0.00 0.00 -9.47 -22.30 -0.04 -0 3 247
7 4627 1080 4409 1239 2099 0.00 -2.02 -0.30 0.00 -0.00 0.00 0.00 -9.47 -20.28 -0.12 4 7 243
8 4693 1163 4486 1337 2101 0.00 -1.99 -0.27 0.00 -0.00 0.00 0.00 -9.47 -18.29 -0.26 11 14 236
9 4763 1241 4570 1430 2104 0.00 -1.94 -0.23 0.00 -0.00 0.00 0.00 -9.47 -16.36 -0.45 23 26 224
10 4840 1314 4661 1516 2107 0.00 -1.86 -0.20 0.00 -0.00 0.00 0.00 -9.47 -14.50 -0.68 39 42 208
11 4921 1381 4757 1596 2110 0.00 -1.76 -0.16 0.00 -0.00 0.00 0.00 -9.47 -12.73 -0.92 59 62 188
12 5007 1442 4859 1668 2113 0.00 -1.66 -0.13 0.00 -0.00 0.00 0.00 -9.47 -11.07 -1.18 83 85 165
13 5098 1497 4966 1733 2117 0.27 -1.57 -0.03 0.00 -0.00 0.00 0.00 -9.74 -9.51 -1.48 112 114 136
14 5192 1544 5078 1789 2121 0.20 -1.49 -0.01 0.00 -0.00 0.00 0.00 -9.94 -8.02 -1.75 140 142 108
15 5289 1585 5193 1838 2125 0.15 -1.41 -0.00 0.00 -0.00 0.00 0.00 -10.09 -6.61 -1.98 167 169 81
16 5389 1619 5312 1878 2130 0.11 -1.35 0.01 0.00 -0.00 0.00 0.00 -10.21 -5.26 -2.18 192 194 56
17 5491 1646 5433 1909 2134 0.08 -1.29 0.02 0.00 -0.00 0.00 0.00 -10.28 -3.97 -2.33 213 215 35
18 5595 1665 5556 1932 2139 0.05 -1.25 0.04 0.00 -0.00 0.00 0.00 -10.34 -2.71 -2.46 231 232 118

19	5700	1676	5680	1945	2144	0.03	-1.23	0.05	0.00	-0.00	0.00	0.00	-10.37	-1.48	-2.54	2422446	***
20	5805	1680	5805	1950	2150	0.01	-1.23	0.06	0.00	-0.00	0.00	0.00	-10.38	-0.25	-2.59	2492500	0
21	5910	1676	5930	1945	2155	-0.01	-1.24	0.07	0.00	-0.00	0.00	0.00	-10.37	0.98	-2.59	2482500	0
22	6015	1665	6054	1932	2161	-0.03	-1.27	0.09	0.00	-0.00	0.00	0.00	-10.33	2.25	-2.56	2422437	0
23	6119	1646	6177	1909	2167	-0.06	-1.31	0.10	0.00	-0.00	0.00	0.00	-10.28	3.57	-2.48	22923119	0
24	6221	1619	6298	1878	2173	-0.09	-1.38	0.12	0.00	-0.00	0.00	0.00	-10.19	4.94	-2.36	21121238	0
25	6321	1585	6417	1838	2179	-0.13	-1.45	0.14	0.00	-0.00	0.00	0.00	-10.06	6.39	-2.20	18718961	0
26	6418	1544	6532	1789	2184	-0.18	-1.53	0.16	0.00	-0.00	0.00	0.00	-9.88	7.93	-1.98	16016288	0
27	6512	1497	6644	1733	2191	-0.24	-1.62	0.18	0.00	-0.00	0.00	0.00	-9.64	9.55	-1.72	131133117	0
28	6603	1442	6751	1668	2196	-0.31	-1.72	0.20	0.00	-0.00	0.00	0.00	-9.33	11.27	-1.41	100102148	0
29	6689	1381	6853	1596	2201	0.00	-1.82	0.30	0.00	-0.00	0.00	0.00	-9.33	13.09	-1.57	76 174	0
30	6770	1314	6949	1516	2207	0.00	-1.93	0.34	0.00	-0.00	0.00	0.00	-9.33	15.02	-0.88	51 53 197	0
31	6847	1241	7040	1430	2212	0.00	-2.03	0.38	0.00	-0.00	0.00	0.00	-9.33	17.05	-0.62	32 35 215	0
32	6917	1163	7124	1337	2217	0.00	-2.10	0.41	0.00	-0.00	0.00	0.00	-9.33	19.15	-0.39	18 20 230	0
33	6983	1080	7201	1239	2222	0.00	-2.16	0.44	0.00	-0.00	0.00	0.00	-9.33	21.31	-0.21	8 11 239	0
34	7041	9937271	1135	2225	0.00	-2.18	0.45	0.00	-0.00	0.00	0.00	0.00	-9.33	23.49	-0.09	2 5 245	0
35	7094	9017333	1026	2229	0.00	-2.16	0.46	0.00	-0.00	0.00	0.00	0.00	-9.33	25.65	-0.05	-0 4 246	0
36	7139	8067387	9142232	0.00	-2.11	0.45	0.00	-0.00	0.00	0.00	0.00	0.00	-9.33	27.76	-0.12	2 6 244	0
37	7178	7087433	7972235	0.00	-2.01	0.43	0.00	-0.00	0.00	0.00	0.00	0.00	-9.33	29.76	-0.32	8 13 237	0
38	7209	6077470	6782237	0.00	-1.86	0.40	0.00	-0.00	0.00	0.00	0.00	0.00	-9.33	31.62	-0.67	18 23 227	0
39	7233	5047498	5562239	0.00	-1.66	0.35	0.00	-0.00	0.00	0.00	0.00	0.00	-9.33	33.27	-1.18	32 37 213	0
40	7250	4007518	4332240	0.00	-1.41	0.28	0.00	-0.00	0.00	0.00	0.00	0.00	-9.33	34.68	-1.87	50 55 195	0

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust

Base level: -1500 [mm] Top level: 100 [mm] Thickness at top: 2300 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 7250 9550 100-215.92 -122.04 -215.92 -78.07 8023 8054 -0.18 -0.01 773.01 1496.14
1 7250 9550 433 -26.99 -122.04 -242.90 -143.16 7793 7828 -0.27 0.06 543.29 1722.01
2 7250 9550 -967 -26.99 -122.04 -269.89 -208.25 7609 7648 -0.35 0.12 359.13 1902.32
3 7250 9550 -1500 -26.99 -122.04 -296.88 -273.34 7458 7501 -0.44 0.18 208.09 2049.50

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 4220 [mm] Rise: 1930 [mm] Q-rise: 1560 [mm]

Ring thickness at crown: 350 [mm] Ring thickness at springing: 350 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
0 9550 1009201 1312346 0.00 0.00 0.00 0.00 0.00 0.00 -131.37 -99.79 -153.57 1375 1390 -1060 ***
1 9570 2569224 3132347 0.00 -2.37 -0.56 0.00 -0.00 0.00 -131.37 -97.42 -134.31 1135 1152 -822 ***
2 9601 4099261 4922350 0.00 -2.84 -0.68 0.00 -0.00 0.00 -131.37 -94.58 -116.22938955-625 ***
3 9643 5609310 6682353 0.00 -3.21 -0.76 0.00 -0.00 0.00 -131.37 -91.37 -99.34 772790-460 ***
4 9697 7089373 8402357 0.00 -3.47 -0.80 0.00 -0.00 0.00 -131.37 -87.90 -83.74 631649-319 ***
5 9761 8519448 1006 2361 0.00 -3.63 -0.80 0.00 -0.00 0.00 -131.37 -84.26 -69.44 509529-199 ***
6 9836 9899535 1167 2367 0.00 -3.70 -0.76 0.00 -0.00 0.00 -131.37 -80.56 -56.46 405424-94 ***
7 9921 1121 9633 1321 2373 0.00 -3.69 -0.70 0.00 -0.00 0.00 -131.37 -76.87 -44.82 315334-4 ***
8 10015 1247 9743 1467 2380 0.00 -3.61 -0.63 0.00 -0.00 0.00 -131.37 -73.25 -34.53 23725773
9 10118 1365 9864 1605 2388 0.00 -3.47 -0.54 0.00 -0.00 0.00 -131.37 -69.78 -25.61 172192138
10 10230 1475 9994 1733 2396 0.00 -3.29 -0.44 0.00 -0.00 0.00 -131.37 -66.49 -18.07 117138192
11 10350 1576 10133 1851 2404 0.00 -3.07 -0.35 0.00 -0.00 0.00 -131.37 -63.42 -11.92 73 94 236
12 10477 1669 10281 1959 2413 0.00 -2.83 -0.26 0.00 -0.00 0.00 -131.37 -60.59 -7.16 40 60 270
13 10610 1751 10436 2055 2422 0.00 -2.59 -0.18 0.00 -0.00 0.00 -131.37 -58.00 -3.81 16 37 293
14 10749 1824 10599 2140 2432 0.28 -2.39 -0.02 0.00 -0.00 0.00 -131.65 -55.61 -1.94 3 24 306
15 10893 1886 10766 2213 2442 0.20 -2.22 0.01 0.00 -0.00 0.00 -131.85 -53.39 -1.44 -0 20 310

16	11041	1938	10939	2272	2452	0.13	-2.07	0.04	0.00	-0.00	0.00	0.00	-131.98	-51.32	-2.32	6.27	303
17	11193	1978	11116	2319	2461	0.09	-1.95	0.06	0.00	-0.00	0.00	0.00	-132.07	-49.37	-4.57	23	43
18	11347	2007	11296	2353	2471	0.05	-1.86	0.08	0.00	-0.00	0.00	0.00	-132.12	-47.51	-8.20	50	69
19	11503	2024	11477	2373	2480	0.03	-1.81	0.11	0.00	-0.00	0.00	0.00	-132.15	-45.69	-13.18	88	107
20	11660	2030	11660	2380	2490	0.01	-1.80	0.13	0.00	-0.00	0.00	0.00	-132.16	-43.89	-19.48	138	157
21	11817	2024	11843	2373	2499	-0.01	-1.83	0.16	-0.00	-0.12	0.02	0.00	-132.14	-41.94	-27.07	201	220
22	11973	2007	12024	2353	2507	-0.03	-1.90	0.19	-0.54	-14.51	1.98	0.00	-131.57	-25.53	-35.57	272	290
23	12127	1978	12204	2319	2514	-0.07	-2.01	0.22	-2.93	-46.99	5.99	0.00	-128.57	23.46	-41.88	311	330
24	12279	1938	12381	2272	2522	-0.11	-2.15	0.26	-4.42	-49.99	6.46	0.00	-124.04	75.60	-42.06	289	309
25	12427	1886	12554	2213	2529	-0.17	-2.32	0.31	-2.38	-20.66	2.63	0.00	-121.48	98.57	-36.55	235	256
26	12571	1824	12721	2140	2536	-0.26	-2.51	0.36	-0.63	-4.37	0.72	0.00	-120.59	105.45	-29.87	183	205
27	12710	1751	12884	2055	2542	-0.37	-2.72	0.42	-1.44	-8.27	1.56	0.00	-118.78	116.44	-24.22	139	162
28	12843	1669	13039	1959	2548	0.00	-2.95	0.61	0.00	-13.38	3.30	0.00	-118.78	132.76	-20.19	105	129
29	12970	1576	13187	1851	2552	0.00	-3.21	0.72	0.00	-17.48	4.56	0.00	-118.78	153.45	-16.91	76	103
30	13090	1475	13326	1733	2557	0.00	-3.46	0.82	0.00	-19.78	5.45	0.00	-118.78	176.69	-14.02	53	83
31	13202	1365	13456	1605	2561	0.00	-3.68	0.92	0.00	-20.15	5.81	0.00	-118.78	200.52	-11.33	34	66
32	13305	1247	13577	1467	2565	0.00	-3.86	1.01	0.00	-18.91	5.68	0.00	-118.78	223.29	-8.89	18	54
33	13399	1121	13687	1321	2569	0.00	-3.99	1.09	0.00	-16.67	5.18	0.00	-118.78	243.94	-6.98	7	45
34	13484	9891	13785	1167	2572	0.00	-4.05	1.13	0.00	-14.00	4.47	0.00	-118.78	261.99	-6.00	1	41
35	13559	8511	13872	1006	2574	0.00	-4.03	1.15	0.00	-11.32	3.70	0.00	-118.78	277.34	-6.47	0	43
36	13623	7081	13947	840	2576	0.00	-3.92	1.13	0.00	-8.88	2.95	0.00	-118.78	290.14	-8.87	6	51
37	13677	5601	14010	668	2577	0.00	-3.72	1.07	0.00	-6.77	2.28	0.00	-118.78	300.64	-13.65	19	65
38	13719	4091	14059	492	2578	0.00	-3.41	0.97	0.00	-4.99	1.69	0.00	-118.78	309.04	-21.16	41	88
39	13750	2561	14096	313	2579	0.00	-3.00	0.82	0.00	-3.46	1.17	0.00	-118.78	315.49	-31.66	72	119
40	13770	1001	14119	131	2580	0.00	-2.47	0.64	0.00	-2.10	0.71	0.00	-118.78	320.06	-45.30	114	161

Segment Intraados.x Intraados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 100 [mm] Thickness at top: 3150 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 13770 16920 100-1037.45 13.60-1037.45 -7.70 15263 15412 -0.33 -0.32 1493.47 1508.32
1 13770 16920 -433 -36.96 13.60-1074.41 -0.44 15268 15421 -0.34 -0.34 1497.84 1498.67
2 13770 16920 -967 -36.96 13.60-1111.37 6.81 15272 15431 -0.35 -0.36 1501.74 1489.49
3 13770 16920 -1500 -36.96 13.60-1148.33 14.07 15275 15439 -0.36 -0.37 1505.23 1480.73

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular

Span: 4510 [mm] Rise: 2010 [mm] Q-rise: 1660 [mm]

Ring thickness at crown: 370 [mm] Ring thickness at springing: 370 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intraados.x Intraados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
0 16920 20016552 2422621 0.00 0.00 0.00 0.00 0.00 0.00 -109.27 -316.39 -39.29 97 144206
1 16945 36316581 4322621 0.00 -2.88 -0.73 0.00 -3.54 -1.18 0.00 -109.27 -309.97 -27.15 60 107243
2 16982 52416624 6202622 0.00 -3.38 -0.86 0.00 -5.33 -1.72 0.00 -109.27 -301.25 -17.96 33 79 271
3 17030 68216680 8032622 0.00 -3.76 -0.95 0.00 -7.20 -2.23 0.00 -109.27 -290.29 -11.52 15 59 291
4 17090 83616750 9832623 0.00 -4.03 -0.98 0.00 -9.13 -2.70 0.00 -109.27 -277.12 -7.53 4 47 303
5 17160 98616832 1156 2624 0.00 -4.19 -0.97 0.00 -11.08 -3.11 0.00 -109.27 -261.85 -5.88 0 40 310
6 17242 1130 16927 1323 2624 0.00 -4.25 -0.92 0.00 -12.92 -3.40 0.00 -109.27 -244.68 -5.61 2 40 310
7 17333 1267 17033 1483 2625 0.00 -4.22 -0.84 0.00 -14.43 -3.54 0.00 -109.27 -226.03 -6.97 11 46 304
8 17435 1397 17151 1635 2626 0.00 -4.11 -0.75 0.00 -15.34 -3.46 0.00 -109.27 -206.58 -9.52 25 58 292
9 17545 1520 17280 1778 2626 0.00 -3.94 -0.64 0.00 -15.38 -3.16 0.00 -109.27 -187.27 -13.09 47 77 273
10 17665 1635 17418 1911 2627 0.00 -3.71 -0.52 0.00 -14.32 -2.63 0.00 -109.27 -169.24 -17.69 77 105245
11 17792 1740 17566 2033 2628 0.00 -3.45 -0.41 0.00 -12.12 -1.97 0.00 -109.27 -153.67 -23.43 117143207
12 17926 1836 17723 2145 2628 0.00 -3.17 -0.30 0.00 -8.99 -1.26 0.00 -109.27 -141.52 -30.52 168193157

13	18068	1922	17887	2245	2629	0.00	-2.88	-0.20	0.00	-7.31	-0.76	0.00	-109.27	-131.32	-38.80	23225595
14	18215	1997	18058	2332	2629	0.30	-2.63	-0.02	4.34	-25.44	-0.20	0.00	-113.92	-103.25	-45.25	29831832
15	18367	2061	18235	2407	2629	0.20	-2.41	0.01	7.35	-52.09	-0.25	0.00	-121.47	-48.75	-44.60	331350-0 ***
16	18523	2114	18417	2469	2630	0.13	-2.22	0.04	5.56	-49.10	-0.05	0.00	-127.16	2.58	-37.36	30031733
17	18683	2156	18603	2517	2630	0.08	-2.05	0.07	1.47	-16.93	-0.13	0.00	-128.71	21.56	-28.42	226244106
18	18846	2186	18792	2552	2630	0.04	-1.92	0.09	0.02	-0.30	-0.01	0.00	-128.77	23.78	-20.71	158176174
19	19010	2204	18983	2573	2630	0.02	-1.83	0.11	-0.00	0.00	0.00	0.00	-128.79	25.60	-14.25	103122228
20	19175	2210	19175	2580	2630	0.01	-1.78	0.13	-0.00	0.00	0.00	0.00	-128.80	27.39	-9.04	61 79 271
21	19340	2204	19367	2573	2629	-0.01	-1.78	0.16	0.00	0.00	0.00	0.00	-128.79	29.17	-5.12	30 49 301
22	19504	2186	19558	2552	2629	-0.02	-1.83	0.19	0.00	0.00	0.00	0.00	-128.77	30.99	-2.51	10 28 322
23	19667	2156	19747	2517	2628	-0.04	-1.92	0.22	0.00	0.00	0.00	0.00	-128.73	32.91	-1.23	-0 19 331
24	19827	2114	19933	2469	2628	-0.08	-2.05	0.26	0.00	0.00	0.00	0.00	-128.65	34.95	-1.26	-0 19 331
25	19983	2061	20115	2407	2627	-0.13	-2.21	0.31	0.00	0.00	0.00	0.00	-128.52	37.16	-2.60	10 29 321
26	20135	1997	20292	2332	2626	-0.20	-2.40	0.37	0.00	0.00	0.00	0.00	-128.32	39.57	-5.23	30 49 301
27	20282	1922	20463	2245	2626	-0.30	-2.62	0.43	0.00	0.00	0.00	0.00	-128.02	42.19	-9.12	59 78 272
28	20424	1836	20627	2145	2625	0.00	-2.87	0.61	0.00	0.00	0.00	0.00	-128.02	45.06	-14.39	100119231
29	20558	1740	20784	2033	2624	0.00	-3.16	0.72	0.00	0.00	0.00	0.00	-128.02	48.22	-20.94	151169181
30	20685	1635	20932	1911	2623	0.00	-3.44	0.84	0.00	0.00	0.00	0.00	-128.02	51.66	-28.77	212231119
31	20805	1520	21070	1778	2622	0.00	-3.70	0.96	0.00	0.00	0.00	0.00	-128.02	55.36	-37.84	28430347
32	20915	1397	21199	1635	2621	0.00	-3.93	1.07	0.00	0.00	0.00	0.00	-128.02	59.29	-48.14	368386-36 ***
33	21017	1267	21317	1483	2621	0.00	-4.10	1.16	0.00	0.00	0.00	0.00	-128.02	63.39	-59.66	463482-132 ***
34	21108	1130	21423	1323	2620	0.00	-4.21	1.23	0.00	0.00	0.00	0.00	-128.02	67.61	-72.40	572590-240 ***
35	21190	9862	1518	1156	2620	0.00	-4.24	1.27	0.00	0.00	0.00	0.00	-128.02	71.85	-86.33	695712-362 ***
36	21260	8362	1600	9832	619	0.00	-4.19	1.26	0.00	0.00	0.00	0.00	-128.02	76.03	-101.46	834851-501 ***
37	21320	6822	1670	8032	619	0.00	-4.03	1.22	0.00	0.00	0.00	0.00	-128.02	80.06	-117.75	9941010-660 ***
38	21368	5242	1726	6202	618	0.00	-3.76	1.13	0.00	0.00	0.00	0.00	-128.02	83.82	-135.20	1178 1195 -845 ***
39	21405	3632	1769	4322	618	0.00	-3.38	0.99	0.00	0.00	0.00	0.00	-128.02	87.20	-153.77	1396 1411 -1061 ***
40	21430	2002	1798	2422	618	0.00	-2.88	0.80	0.00	0.00	0.00	0.00	-128.02	90.08	-173.40	1657 1672 -1322 ***

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 200 [mm] Thickness at top: 7170 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 21430 28600 200-462.07 120.58 -462.07 -4.25 24973 25039 -0.06 -0.06 3542.79 3561.20
1 21430 28600 -367 -89.39 120.58 -551.46 64.0725092 25171 -0.07 -0.08 3661.80 3429.42
2 21430 28600 -933 -89.39 120.58 -640.84 132.40 25176 25267 -0.07 -0.10 3745.83 3332.62
3 21430 28600 -1500 -89.39 120.58 -730.23 200.73 25238 25342 -0.08 -0.13 3807.72 3257.96

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 2310 [mm] Rise: 1150 [mm] Q-rise: 960 [mm]

Ring thickness at crown: 500 [mm] Ring thickness at springing: 500 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
0 28600 45028100 4522532 0.00 0.00 0.00 0.00 0.00 0.00 -7.45 -49.41 -3.21 61 68 412
1 28604 54028106 5822532 0.00 -1.45 -0.43 0.00 0.00 0.00 -7.45 -47.96 -2.29 44 51 429
2 28615 63028121 7102532 0.00 -1.83 -0.60 0.00 0.00 0.00 -7.45 -46.14 -1.52 29 36 444
3 28633 71928147 8372531 0.00 -2.14 -0.73 0.00 0.00 0.00 -7.45 -43.99 -0.92 18 24 456
4 28658 80628183 9622530 0.00 -2.40 -0.83 0.00 0.00 0.00 -7.45 -41.59 -0.49 9 15 465
5 28689 89028228 1083 2530 0.00 -2.60 -0.89 0.00 0.00 0.00 -7.45 -38.99 -0.21 3 8 472
6 28727 97228283 1201 2529 0.00 -2.75 -0.91 0.00 0.00 0.00 -7.45 -36.24 -0.09 -0 5 475
7 28772 1051 28346 1314 2527 0.00 -2.84 -0.90 0.00 0.00 0.00 -7.45 -33.40 -0.11 1 6 474
8 28822 1126 28419 1421 2526 0.00 -2.88 -0.86 0.00 0.00 0.00 -7.45 -30.52 -0.25 6 11 469
9 28879 1197 28499 1523 2525 0.00 -2.89 -0.80 0.00 0.00 0.00 -7.45 -27.63 -0.49 17 21 459

10	28940	1263	28587	1618	2523	0.00	-2.85	-0.72	0.00	0.00	0.00	0.00	0.00	-7.45	-24.78	-0.81	34	37	443
11	29007	1325	28683	1706	2521	0.00	-2.79	-0.64	0.00	0.00	0.00	0.00	0.00	-7.45	-21.99	-1.20	59	62	418
12	29078	1381	28785	1786	2519	0.00	-2.72	-0.55	0.00	0.00	0.00	0.00	0.00	-7.45	-19.27	-1.62	92	95	385
13	29153	1431	28892	1857	2517	0.48	-2.64	-0.26	-0.00	0.00	0.00	0.00	0.00	-7.92	-16.63	-2.23	144	146	334
14	29232	1475	29006	1921	2515	0.38	-2.57	-0.21	-0.00	0.00	0.00	0.00	0.00	-8.30	-14.06	-2.79	201	203	277
15	29314	1513	29123	1975	2512	0.30	-2.50	-0.15	-0.00	0.00	0.00	0.00	0.00	-8.60	-11.56	-3.27	263	265	215
16	29399	1544	29245	2019	2510	0.22	-2.43	-0.10	-0.00	0.00	0.00	0.00	0.00	-8.82	-9.14	-3.67	327	328	152
17	29486	1568	29370	2055	2508	0.16	-2.36	-0.06	-0.00	0.00	0.00	0.00	0.00	-8.99	-6.77	-3.99	386	387	793
18	29575	1586	29497	2080	2505	0.11	-2.31	-0.01	-0.00	0.00	0.00	0.00	0.00	-9.10	-4.47	-4.22	435	437	743
19	29665	1596	29626	2095	2502	0.06	-2.27	0.04	-0.00	0.00	0.00	0.00	0.00	-9.16	-2.20	-4.36	468	469	111
20	29755	1600	29755	2100	2499	0.02	-2.25	0.08	-0.00	0.00	0.00	0.00	0.00	-9.18	0.05	-4.40	479	480	0
21	29845	1596	29884	2095	2497	-0.02	-2.24	0.12	0.00	0.00	0.00	0.00	0.00	-9.16	2.29	-4.35	466	468	12
22	29935	1586	30013	2080	2494	-0.06	-2.25	0.17	0.00	0.00	0.00	0.00	0.00	-9.10	4.54	-4.20	432	434	46
23	30024	1568	30140	2055	2491	-0.11	-2.28	0.22	0.00	0.00	0.00	0.00	0.00	-8.99	6.82	-3.96	383	384	96
24	30111	1544	30265	2019	2489	-0.16	-2.32	0.26	0.00	0.00	0.00	0.00	0.00	-8.83	9.14	-3.63	323	325	155
25	30196	1513	30387	1975	2486	-0.21	-2.37	0.31	0.00	0.00	0.00	0.00	0.00	-8.62	11.51	-3.23	260	262	218
26	30278	1475	30504	1921	2484	-0.28	-2.44	0.36	0.00	0.00	0.00	0.00	0.00	-8.34	13.95	-2.74	199	201	279
27	30357	1431	30618	1857	2481	-0.36	-2.50	0.42	0.00	0.00	0.00	0.00	0.00	-7.98	16.45	-2.20	142	144	336
28	30432	1381	30725	1786	2478	-0.45	-2.57	0.47	0.00	0.00	0.00	0.00	0.00	-7.53	19.02	-1.59	91	94	386
29	30503	1325	30827	1706	2476	0.00	-2.64	0.72	0.00	0.00	0.00	0.00	0.00	-7.53	21.66	-1.17	58	61	419
30	30570	1263	30923	1618	2474	0.00	-2.71	0.80	0.00	0.00	0.00	0.00	0.00	-7.53	24.37	-0.79	33	36	444
31	30631	1197	31011	1523	2472	0.00	-2.77	0.87	0.00	0.00	0.00	0.00	0.00	-7.53	27.14	-0.46	16	20	460
32	30688	1126	31091	1421	2470	0.00	-2.81	0.93	0.00	0.00	0.00	0.00	0.00	-7.53	29.95	-0.23	6	10	470
33	30738	1051	31164	1314	2469	0.00	-2.81	0.97	0.00	0.00	0.00	0.00	0.00	-7.53	32.75	-0.10	1	5	475
34	30783	972	31227	1201	2467	0.00	-2.77	0.99	0.00	0.00	0.00	0.00	0.00	-7.53	35.52	-0.09	0	5	475
35	30821	890	31282	1083	2466	0.00	-2.69	0.98	0.00	0.00	0.00	0.00	0.00	-7.53	38.21	-0.22	3	8	472
36	30852	806	31327	962	2465	0.00	-2.55	0.94	0.00	0.00	0.00	0.00	0.00	-7.53	40.76	-0.50	9	15	465
37	30877	719	31363	837	2464	0.00	-2.36	0.87	0.00	0.00	0.00	0.00	0.00	-7.53	43.12	-0.94	19	25	455
38	30895	630	31389	710	2463	0.00	-2.11	0.76	0.00	0.00	0.00	0.00	0.00	-7.53	45.23	-1.55	31	37	443
39	30906	540	31404	582	2463	0.00	-1.81	0.61	0.00	0.00	0.00	0.00	0.00	-7.53	47.04	-2.33	46	52	428
40	30910	450	31410	452	2463	0.00	-1.44	0.43	0.00	0.00	0.00	0.00	0.00	-7.53	48.48	-3.26	64	71	409

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 350 [mm] Thickness at top: 1700 [mm]

Batter: 1:0
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 30910 32610 350-132.21 -2.73 -132.21 1.40 31761 31780 -0.07 -0.08 851.18 829.93
1 30910 32610 -267 -23.06 -2.73 -155.27 -0.28 31747 31769 -0.09 -0.09 837.12 840.69
2 30910 32610 -883 -23.06 -2.73 -178.33 -1.96 31736 31762 -0.11 -0.10 826.28 848.25
3 30910 32610 -1500 -23.06 -2.73 -201.40 -3.64 31728 31756 -0.13 -0.11 817.54 853.69

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular
Span: 2570 [mm] Rise: 1190 [mm] Q-rise: 1030 [mm]
Ring thickness at crown: 400 [mm] Ring thickness at springing: 400 [mm] Mortar loss: 20 [mm]
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
0 32610 35032211 3812442 0.00 0.00 0.00 0.00 0.00 0.00 -10.25 -47.26 -2.71 53 60 320
1 32621 44532226 5062441 0.00 -1.57 -0.42 0.00 0.00 0.00 -10.25 -45.68 -1.81 35 42 338
2 32639 54032249 6302441 0.00 -1.90 -0.53 0.00 0.00 0.00 -10.25 -43.79 -1.10 21 28 352
3 32664 63332282 7522440 0.00 -2.16 -0.60 0.00 0.00 0.00 -10.25 -41.63 -0.59 11 17 363
4 32696 72432324 8712439 0.00 -2.38 -0.66 0.00 0.00 0.00 -10.25 -39.25 -0.26 4 9 371
5 32735 81232375 9862437 0.00 -2.54 -0.68 0.00 0.00 0.00 -10.25 -36.71 -0.10 -0 5 375
6 32780 89732434 1098 2436 0.00 -2.65 -0.68 0.00 0.00 0.00 -10.25 -34.06 -0.09 0 5 375

7	32831	97932501	1204	2434	0.00	-2.72	-0.66	0.00	0.00	0.00	0.00	-10.25	-31.35	-0.22	5.9	371
8	32888	1056	32576	1306	2432	0.00	-2.74	-0.82	0.00	0.00	0.00	-10.25	-28.60	-0.45	14	362
9	32951	1129	32658	1401	2430	0.00	-2.73	-0.57	0.00	0.00	0.00	-10.25	-25.87	-0.77	28	31
10	33019	1197	32748	1490	2427	0.00	-2.70	-0.51	0.00	0.00	0.00	-10.25	-23.17	-1.15	48	51
11	33092	1260	32843	1572	2424	0.00	-2.63	-0.45	0.00	0.00	0.00	-10.25	-20.54	-1.57	74	77
12	33170	1317	32945	1647	2421	0.00	-2.56	-0.38	0.00	0.00	0.00	-10.25	-17.98	-2.02	107	110
13	33251	1368	33052	1714	2418	0.07	-2.48	-0.15	-0.00	0.00	0.00	-10.72	-15.50	-2.59	151	154
14	33336	1413	33163	1773	2414	0.38	-2.41	-0.11	-0.00	0.00	0.00	-11.10	-13.09	-3.11	197	199
15	33425	1451	33279	1824	2411	0.30	-2.34	-0.08	-0.00	0.00	0.00	-11.40	-10.75	-3.55	243	245
16	33516	1483	33398	1865	2406	0.23	-2.28	-0.04	-0.00	0.00	0.00	-11.63	-8.47	-3.92	287	289
17	33609	1508	33520	1898	2402	0.17	-2.22	-0.01	-0.00	0.00	0.00	-11.79	-6.26	-4.20	325	327
18	33703	1526	33644	1921	2398	0.11	-2.17	0.02	-0.00	0.00	0.00	-11.90	-4.09	-4.40	355	356
19	33799	1536	33769	1935	2394	0.06	-2.13	0.06	-0.00	0.00	0.00	-11.97	-1.96	-4.52	373	375
20	33895	1540	33895	1940	2390	0.02	-2.10	0.09	-0.00	0.00	0.00	-11.99	0.14	-4.55	378	380
21	33991	1536	34021	1935	2385	-0.02	-2.09	0.12	0.00	0.00	0.00	-11.97	2.23	-4.49	370	372
22	34087	1526	34146	1921	2381	-0.06	-2.10	0.15	0.00	0.00	0.00	-11.90	4.33	-4.35	349	351
23	34181	1508	34270	1898	2376	-0.11	-2.12	0.18	0.00	0.00	0.00	-11.80	6.45	-4.12	318	320
24	34274	1483	34392	1865	2371	-0.16	-2.15	0.21	0.00	0.00	0.00	-11.64	8.59	-3.82	279	281
25	34365	1451	34511	1824	2366	-0.21	-2.19	0.25	0.00	0.00	0.00	-11.43	10.79	-3.44	235	237
26	34454	1413	34627	1773	2362	-0.28	-2.24	0.28	0.00	0.00	0.00	-11.15	13.03	-2.99	189	192
27	34539	1368	34738	1714	2357	-0.35	-2.30	0.32	0.00	0.00	0.00	-10.81	15.33	-2.48	144	147
28	34620	1317	34845	1647	2353	-0.43	-2.36	0.36	0.00	0.00	0.00	-10.37	17.68	-1.91	102	104
29	34698	1260	34947	1572	2349	0.00	-2.42	0.54	0.00	0.00	0.00	-10.37	20.11	-1.47	70	73
30	34771	1197	35042	1490	2345	0.00	-2.50	0.60	0.00	0.00	0.00	-10.37	22.60	-1.06	45	48
31	34839	1129	35132	1401	2341	0.00	-2.56	0.66	0.00	0.00	0.00	-10.37	25.16	-0.69	25	29
32	34902	1056	35214	1306	2338	0.00	-2.60	0.70	0.00	0.00	0.00	-10.37	27.76	-0.39	12	16
33	34959	97935289	1204	2334	0.00	-2.61	0.74	0.00	0.00	0.00	0.00	-10.37	30.38	-0.18	8	372
34	35010	89735356	1098	2331	0.00	-2.59	0.76	0.00	0.00	0.00	0.00	-10.37	32.97	-0.08	-0	5
35	35055	81235415	9862329	0.00	-2.54	0.76	0.00	0.00	0.00	0.00	0.00	-10.37	35.51	-0.11	0	6
36	35094	72435466	8712327	0.00	-2.44	0.74	0.00	0.00	0.00	0.00	0.00	-10.37	37.94	-0.30	5	10
37	35126	63335508	7522325	0.00	-2.29	0.70	0.00	0.00	0.00	0.00	0.00	-10.37	40.23	-0.65	13	19
38	35151	54035541	6302323	0.00	-2.09	0.63	0.00	0.00	0.00	0.00	0.00	-10.37	42.33	-1.18	24	30
39	35169	44635564	5062322	0.00	-1.85	0.54	0.00	0.00	0.00	0.00	0.00	-10.37	44.17	-1.91	39	45
40	35180	35035579	3812322	0.00	-1.54	0.42	0.00	0.00	0.00	0.00	0.00	-10.37	45.72	-2.83	58	64

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust

Base level:-1500 [mm] Top level: 70 [mm] Thickness at top: 6750 [mm]

Batter: 1:0

Masonry unit weight:22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 35180 41930 70 -354.06 0.76 -354.06 -44.57 38404 38454 -0.06 -0.05 3223.82 3475.60
1 35180 41930 -453 -77.71 0.76 -431.78 -44.17 38422 38484 -0.07 -0.06 3241.85 3446.47
2 35180 41930 -977 -77.71 0.76 -509.49 -43.78 38433 38505 -0.08 -0.07 3252.68 3424.53
3 35180 41930 -1500 -77.71 0.76 -587.21 -43.38 38439 38523 -0.09 -0.08 3259.18 3406.94

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 2720 [mm] Rise: 1350 [mm] Q-rise: 1100 [mm]

Ring thickness at crown:250 [mm] Ring thickness at springing: 250 [mm] Mortar loss: 20 [mm]

Masonry unit weight:22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
0 41930 70 41680 72 2026 0.00 0.00 0.00 0.00 0.00 0.00 0.00 -9.62 -34.38 -3.26
1 41935 17641686 1982026 0.00 -0.87 -0.13 0.00 0.00 0.00 0.00 -9.62 -33.51 -2.26
2 41948 28241701 3222025 0.00 -1.22 -0.21 0.00 0.00 0.00 0.00 -9.62 -32.29 -1.46
3 41970 38641727 4462024 0.00 -1.51 -0.25 0.00 0.00 0.00 0.00 -9.62 -30.78 -0.85

4	41999	48841762	5672022	0.00	-1.74	-0.30	0.00	0.00	0.00	0.00	0.00	0.00	-9.62	-29.03	-0.43	12	16	214
5	42036	58741806	6842021	0.00	-1.92	-0.32	0.00	0.00	0.00	0.00	0.00	0.00	-9.62	-27.11	-0.17	4	8	222
6	42081	68441859	7982018	0.00	-2.05	-0.32	0.00	0.00	0.00	0.00	0.00	0.00	-9.62	-25.06	-0.05	-0	4	226
7	42134	77641921	9082016	0.00	-2.12	-0.31	0.00	0.00	0.00	0.00	0.00	0.00	-9.62	-22.94	-0.05	0	4	226
8	42193	86441992	10122013	0.00	-2.16	-0.29	0.00	0.00	0.00	0.00	0.00	0.00	-9.62	-20.78	-0.16	5	9	221
9	42259	94742070	11112009	0.00	-2.15	-0.27	0.00	0.00	0.00	0.00	0.00	0.00	-9.62	-18.63	-0.33	15	18	212
10	42332	102542156	12032006	0.00	-2.11	-0.23	0.00	0.00	0.00	0.00	0.00	0.00	-9.62	-16.53	-0.56	29	31	199
11	42410	109742248	12882002	0.00	-2.04	-0.19	0.00	0.00	0.00	0.00	0.00	0.00	-9.62	-14.49	-0.81	47	50	180
12	42494	116342347	13651997	0.00	-1.95	-0.16	0.00	0.00	0.00	0.00	0.00	0.00	-9.62	-12.54	-1.08	70	73	157
13	42582	122142452	14351993	0.00	-1.85	-0.12	0.00	0.00	0.00	0.00	0.00	0.00	-9.62	-10.69	-1.35	97	99	131
14	42675	127342562	14961988	0.31	-1.76	-0.01	-0.00	0.00	0.00	0.00	0.00	0.00	-9.93	-8.93	-1.66	128	130	100
15	42772	131742677	15491984	0.24	-1.68	0.00	-0.00	0.00	0.00	0.00	0.00	0.00	-10.17	-7.26	-1.91	156	158	72
16	42872	135442795	15921979	0.18	-1.60	0.02	-0.00	0.00	0.00	0.00	0.00	0.00	-10.34	-5.65	-2.12	182	184	46
17	42974	138342916	16261974	0.13	-1.53	0.03	-0.00	0.00	0.00	0.00	0.00	0.00	-10.47	-4.12	-2.27	203	205	25
18	43078	140343039	16501969	0.08	-1.47	0.04	-0.00	0.00	0.00	0.00	0.00	0.00	-10.55	-2.65	-2.37	218	220	10
19	43184	141643164	16651964	0.05	-1.43	0.06	-0.00	0.00	0.00	0.00	0.00	0.00	-10.60	-1.23	-2.43	227	229	1
20	43290	142043290	16701959	0.01	-1.40	0.07	-0.00	0.00	0.00	0.00	0.00	0.00	-10.61	0.17	-2.43	228	230	0
21	43396	141643416	16651954	-0.01	-1.39	0.08	0.00	0.00	0.00	0.00	0.00	0.00	-10.60	1.56	-2.39	223	224	6
22	43502	140343541	16501950	-0.04	-1.39	0.09	0.00	0.00	0.00	0.00	0.00	0.00	-10.55	2.95	-2.30	211	212	18
23	43606	138343664	16261946	-0.08	-1.42	0.11	0.00	0.00	0.00	0.00	0.00	0.00	-10.48	4.37	-2.17	193	194	36
24	43708	135443785	15921942	-0.12	-1.46	0.13	0.00	0.00	0.00	0.00	0.00	0.00	-10.36	5.83	-1.99	170	172	58
25	43808	131743903	15491937	-0.16	-1.51	0.14	0.00	0.00	0.00	0.00	0.00	0.00	-10.20	7.34	-1.77	144	145	85
26	43905	127344018	14961933	-0.21	-1.57	0.16	0.00	0.00	0.00	0.00	0.00	0.00	-9.99	8.92	-1.50	115	117	113
27	43998	122144128	14351930	-0.28	-1.64	0.18	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	10.56	-1.20	86	88	142
28	44086	116344233	13651926	0.00	-1.72	0.26	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	12.28	-0.94	61	63	167
29	44170	109744332	12881923	0.00	-1.82	0.30	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	14.10	-0.68	40	42	188
30	44248	102544424	12031919	0.00	-1.90	0.33	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	16.00	-0.45	23	26	204
31	44321	94744510	11111916	0.00	-1.97	0.36	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	17.96	-0.25	11	14	216
32	44387	86444588	10121914	0.00	-2.01	0.38	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	19.98	-0.11	3	6	224
33	44446	77644659	9081912	0.00	-2.03	0.39	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	22.00	-0.04	-0	3	227
34	44499	68444721	7981909	0.00	-2.01	0.40	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	24.01	-0.07	1	5	225
35	44544	58744774	6841907	0.00	-1.94	0.39	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	25.95	-0.23	6	10	220
36	44581	48844818	5671906	0.00	-1.83	0.37	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	27.78	-0.52	16	20	210
37	44610	38644853	4461905	0.00	-1.67	0.33	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	29.45	-0.98	29	34	196
38	44632	28244879	3221904	0.00	-1.46	0.28	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	30.91	-1.61	48	53	177
39	44645	17644894	1981903	0.00	-1.18	0.21	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	32.09	-2.43	72	77	153
40	44650	7044900	721903	0.00	-0.86	0.13	0.00	0.00	0.00	0.00	0.00	0.00	-9.71	32.95	-3.45	102	107	123

Viewing Purposes Only!

WS Atkins Ireland Limited

Unit 2B
2200 Cork Airport Business Park
Cork
T12 R279

Tel: +353 21 429 0300

Meath County Council - Viewing Purposes Only!

© WS Atkins Ireland Limited except where stated otherwise

Meath County Council - Viewing Purposes Only!