



TRAFFINOMICS LIMITED

**KILSARAN BELLEWSTOWN TRAFFIC COUNTS
MANUAL CLASSIFIED JUNCTION TURNING COUNTS**

**MAY 2021
TRA/21/081**

SITE: 04

DATE: 26th May 2021

LOCATION: R150/Bellewstown Road

DAY: Wednesday

TIME	MOVEMENT 4					TOT	PCU	MOVEMENT 5					TOT	PCU	MOVEMENT 6					TOT	PCU
	CAR	LGV	OGV1	OGV2	BUS			CAR	LGV	OGV1	OGV2	BUS			CAR	LGV	OGV1	OGV2	BUS		
13:00	0	0	0	0	0	0	0	15	2	2	1	0	20	22	4	1	0	0	0	5	5
13:15	0	0	0	0	0	0	0	14	7	1	4	1	27	34	3	1	0	0	0	4	4
13:30	0	0	0	0	0	0	0	16	3	0	3	0	22	26	5	3	0	0	0	8	8
13:45	0	0	0	0	0	0	0	20	1	1	3	1	26	31	9	1	0	0	0	10	10
H/TOT	0	0	0	0	0	0	0	65	13	4	11	2	95	113	21	6	0	0	0	27	27
14:00	0	0	0	0	0	0	0	18	4	8	1	2	33	40	3	1	0	0	0	4	4
14:15	0	0	0	0	0	0	0	14	7	2	0	0	23	24	8	1	0	0	0	9	9
14:30	1	0	0	0	0	1	1	24	3	0	1	1	29	31	4	1	0	0	0	5	5
14:45	1	0	0	0	0	1	1	19	1	1	1	1	23	26	4	0	0	0	0	4	4
H/TOT	2	0	0	0	0	2	2	75	15	11	3	4	108	121	19	3	0	0	0	22	22
15:00	0	0	0	0	0	0	0	31	6	3	1	1	42	46	4	0	0	0	0	4	4
15:15	0	0	0	0	0	0	0	18	3	1	0	1	23	25	6	0	0	1	0	7	8
15:30	1	0	0	0	0	1	1	14	3	0	1	0	18	19	6	4	0	0	0	10	10
15:45	0	0	0	0	0	0	0	33	1	0	3	0	37	41	6	3	0	0	0	9	9
H/TOT	1	0	0	0	0	1	1	96	13	4	5	2	120	131	22	7	0	1	0	30	31
16:00	0	0	0	0	0	0	0	26	2	0	1	0	29	30	4	1	0	0	0	5	5
16:15	0	0	0	0	0	0	0	23	5	1	1	0	30	32	3	1	0	0	0	4	4
16:30	0	0	0	0	0	0	0	30	3	2	1	0	36	38	4	0	0	0	0	4	4
16:45	1	0	0	0	0	1	1	28	5	4	0	0	37	39	7	3	0	0	0	10	10
H/TOT	1	0	0	0	0	1	1	107	15	7	3	0	132	139	18	5	0	0	0	23	23
17:00	0	0	0	0	0	0	0	33	2	1	0	0	36	37	10	1	0	0	0	11	11
17:15	0	0	0	0	0	0	0	28	6	0	0	0	34	34	14	0	0	0	0	14	14
17:30	1	0	0	0	0	1	1	28	5	2	0	0	35	36	12	1	0	0	0	13	13
17:45	0	0	0	0	0	0	0	21	1	2	1	0	25	27	8	2	0	0	0	10	10
H/TOT	1	0	0	0	0	1	1	110	14	5	1	0	130	134	44	4	0	0	0	48	48
18:00	0	0	0	0	0	0	0	27	6	1	0	0	34	35	8	1	0	0	0	9	9
18:15	0	0	0	0	0	0	0	32	3	1	0	0	36	37	11	1	1	0	0	13	14
18:30	0	0	0	0	0	0	0	30	1	0	1	0	32	33	6	0	0	0	0	6	6
18:45	0	0	0	0	0	0	0	31	1	0	0	0	32	32	6	1	0	0	0	7	7
H/TOT	0	0	0	0	0	0	0	120	11	2	1	0	134	136	31	3	1	0	0	35	36
P/TOT	9	1	0	0	0	10	10	1092	170	64	67	14	1407	1540	254	49	7	4	1	315	325



TRAFFINOMICS LIMITED

KILSARAN BELLEWSTOWN TRAFFIC COUNTS
MANUAL CLASSIFIED JUNCTION TURNING COUNTS

MAY 2021
TRA/21/081

SITE: 04

DATE: 26th May 2021

LOCATION: R150/Bellewstown Road

DAY: Wednesday

TIME	MOVEMENT 7						PCU	MOVEMENT 8						PCU	MOVEMENT 9						PCU
	CAR	LGV	OGV1	OGV2	BUS	TOT		CAR	LGV	OGV1	OGV2	BUS	TOT		CAR	LGV	OGV1	OGV2	BUS	TOT	
13:00	2	0	0	0	0	2	2	0	0	0	0	0	0	0	2	0	0	0	0	2	2
13:15	7	0	0	0	0	7	7	0	0	0	0	0	0	0	4	0	0	0	0	4	4
13:30	5	2	0	0	0	7	7	0	0	0	0	0	0	0	4	0	0	0	0	4	4
13:45	6	0	0	0	0	6	6	0	0	0	0	0	0	0	3	2	0	0	0	5	5
H/TOT	20	2	0	0	0	22	22	0	0	0	0	0	0	0	13	2	0	0	0	15	15
14:00	5	2	0	0	0	7	7	0	0	0	0	0	0	0	4	1	0	0	0	5	5
14:15	5	2	0	0	0	7	7	0	0	0	0	0	0	0	4	1	0	0	0	5	5
14:30	6	0	0	0	0	6	6	0	0	0	0	0	0	0	3	0	0	0	0	3	3
14:45	6	0	0	0	0	6	6	0	0	0	0	0	0	0	2	0	0	1	0	3	4
H/TOT	22	4	0	0	0	26	26	0	0	0	0	0	0	0	13	2	0	1	0	16	17
15:00	5	1	0	0	0	6	6	0	0	0	0	0	0	0	2	0	0	0	0	2	2
15:15	3	3	0	0	0	6	6	0	0	0	0	0	0	0	2	1	1	0	0	4	5
15:30	7	1	0	0	0	8	8	0	0	0	0	0	0	0	3	0	0	0	0	3	3
15:45	6	2	0	1	0	9	10	0	0	0	0	0	0	0	1	0	0	0	0	1	1
H/TOT	21	7	0	1	0	29	30	0	0	0	0	0	0	0	8	1	1	0	0	10	11
16:00	5	1	0	0	0	6	6	1	0	0	0	0	1	1	3	0	0	0	0	3	3
16:15	12	1	0	0	0	13	13	1	0	0	0	0	1	1	4	0	1	0	0	5	6
16:30	8	0	0	0	0	8	8	0	0	0	0	0	0	0	4	0	0	0	0	4	4
16:45	7	2	0	0	0	9	9	0	0	0	0	0	0	0	3	1	0	0	0	4	4
H/TOT	32	4	0	0	0	36	36	2	0	0	0	0	2	2	14	1	1	0	0	16	17
17:00	3	0	0	0	0	3	3	0	0	0	0	0	0	0	6	0	0	0	0	6	6
17:15	5	1	0	0	0	6	6	0	0	0	0	0	0	0	2	1	0	0	0	3	3
17:30	6	1	0	0	0	7	7	0	0	0	0	0	0	0	5	1	0	0	0	6	6
17:45	7	3	0	0	0	10	10	0	0	0	0	0	0	0	4	1	0	0	0	5	5
H/TOT	21	5	0	0	0	26	26	0	0	0	0	0	0	0	17	3	0	0	0	20	20
18:00	6	1	0	0	0	7	7	0	0	0	0	0	0	0	4	1	0	0	0	5	5
18:15	6	0	1	0	0	7	8	0	0	0	0	0	0	0	3	0	0	0	0	3	3
18:30	5	2	0	0	0	7	7	0	0	0	0	0	0	0	5	0	1	0	0	6	7
18:45	7	1	1	0	0	9	10	0	0	0	0	0	0	0	3	1	0	0	0	4	4
H/TOT	24	4	2	0	0	30	31	0	0	0	0	0	0	0	15	2	1	0	0	18	19
P/TOT	251	45	8	2	0	306	313	2	0	0	0	0	2	2	142	19	7	4	0	172	181



TRAFFINOMICS LIMITED

**KILSARAN BELLEWSTOWN TRAFFIC COUNTS
MANUAL CLASSIFIED JUNCTION TURNING COUNTS**

**MAY 2021
TRA/21/081**

SITE: 04

DATE: 26th May 2021

LOCATION: R150/Bellewstown Road

DAY: Wednesday

TIME	MOVEMENT 10					TOT	PCU	MOVEMENT 11					TOT	PCU	MOVEMENT 12					TOT	PCU
	CAR	LGV	OGV1	OGV2	BUS			CAR	LGV	OGV1	OGV2	BUS			CAR	LGV	OGV1	OGV2	BUS		
13:00	4	0	0	0	0	4	4	13	3	2	0	1	19	21	0	0	0	0	0	0	0
13:15	2	0	1	0	0	3	4	20	3	0	2	0	25	28	1	0	0	0	0	1	1
13:30	3	0	0	0	0	3	3	22	5	2	0	0	29	30	0	0	0	0	0	0	0
13:45	7	0	0	0	0	7	7	22	2	2	1	0	27	29	0	0	0	0	0	0	0
H/TOT	16	0	1	0	0	17	18	77	13	6	3	1	100	108	1	0	0	0	0	1	1
14:00	4	0	1	0	0	5	6	27	4	2	3	0	36	41	0	0	0	0	0	0	0
14:15	1	0	0	0	0	1	1	22	5	2	1	1	31	34	0	0	0	0	0	0	0
14:30	3	1	1	0	0	5	6	18	5	1	3	0	27	31	0	0	0	0	0	0	0
14:45	4	0	0	0	0	4	4	23	5	2	1	1	32	35	0	0	0	0	0	0	0
H/TOT	12	1	2	0	0	15	16	90	19	7	8	2	126	142	0	0	0	0	0	0	0
15:00	4	0	0	0	0	4	4	23	3	2	0	1	29	31	0	0	0	0	0	0	0
15:15	1	1	0	0	0	2	2	37	7	1	1	0	46	48	0	0	0	0	0	0	0
15:30	3	0	0	0	0	3	3	33	3	3	0	1	40	43	1	0	0	0	0	1	1
15:45	4	0	0	0	0	4	4	30	6	1	1	1	39	42	0	0	0	0	0	0	0
H/TOT	12	1	0	0	0	13	13	123	19	7	2	3	154	163	1	0	0	0	0	1	1
16:00	5	0	0	0	1	6	7	29	7	6	1	1	44	49	0	0	0	0	0	0	0
16:15	5	0	0	0	0	5	5	27	8	1	2	0	38	41	0	1	0	0	0	1	1
16:30	5	0	0	0	0	5	5	39	6	4	0	0	49	51	0	0	1	0	0	1	2
16:45	7	0	0	0	0	7	7	40	14	0	0	0	54	54	0	0	0	0	0	0	0
H/TOT	22	0	0	0	1	23	24	135	35	11	3	1	185	195	0	1	1	0	0	2	3
17:00	1	0	0	0	0	1	1	43	13	0	0	0	56	56	0	0	0	0	0	0	0
17:15	3	0	0	0	0	3	3	27	3	3	1	1	35	39	2	0	0	0	0	2	2
17:30	4	0	0	0	0	4	4	51	5	0	0	0	56	56	1	0	0	0	0	1	1
17:45	4	0	0	0	0	4	4	34	10	1	0	0	45	46	0	0	0	0	0	0	0
H/TOT	12	0	0	0	0	12	12	155	31	4	1	1	192	196	3	0	0	0	0	3	3
18:00	5	0	0	0	0	5	5	23	4	0	0	0	27	27	0	0	0	0	0	0	0
18:15	3	0	0	0	0	3	3	24	3	2	0	0	29	30	0	0	0	0	0	0	0
18:30	0	0	0	0	0	0	0	31	5	1	0	0	37	38	0	0	0	0	0	0	0
18:45	1	0	0	0	0	1	1	21	7	0	0	0	28	28	0	0	0	0	0	0	0
H/TOT	9	0	0	0	0	9	9	99	19	3	0	0	121	123	0	0	0	0	0	0	0
P/TOT	132	8	6	1	1	148	153	1108	208	69	74	14	1473	1618	6	1	1	0	0	8	9



Traffic Survey Data – Automatic Traffic Counter Site L56172 Mullagh Road



TRAFFINOMICS LIMITED

KILSARAN BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS
SUMMARY
SITE 01
WEEK COMMENCING: Friday 21 May 2021
TRA/21/081

LOCATION: The Mullagh Road - Immediately North of the Kilsaran Quarry Access (Google Maps Ref: 53.803189, -6.394629)

SPEED SURVEY SUMMARY:

NORTHBOUND	85% Speed = 48.26 km/h, 95% Speed = 51.93 km/h, Median = 37.98 km/h	Maximum = 63.3 km/h, Minimum = 11.7 km/h, Mean = 36.8 km/h
SOUTHBOUND	85% Speed = 48.64 km/h, 95% Speed = 53.46 km/h, Median = 38.61 km/h	Maximum = 65.0 km/h, Minimum = 9.2 km/h, Mean = 37.5 km/h

VOLUMETRIC VEHICLE COUNTS:

Direction	Time	Friday 21 May 2021	Saturday 22 May 2021	Sunday 23 May 2021	Monday 24 May 2021	Tuesday 25 May 2021	Wednesday 26 May 2021	Thursday 27 May 2021	No. Vehicles 7 day Mean
NORTHBOUND	07-19	27	28	20	51	30	35	32	223
SOUTHBOUND	07-19	34	34	22	35	33	33	33	224
NORTHBOUND	00-00	34	30	28	60	37	42	37	268
SOUTHBOUND	00-00	39	40	29	42	44	43	40	277

PEAK FLOW SUMMARY:

Peak	AM	IP	PM
Most Frequent Peak Hour	0900	1400	1700
Average Vehicles per Peak Hour	2	5	6



TRAFFINOMICS LIMITED

**KILSARAN BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS**

**SITE 01
NORTHBOUND**

Friday 21 May 2021
TRA/21/081

WEEK COMMENCING:

TIME PERIOD	Friday 21 May 2021	Saturday 22 May 2021	Sunday 23 May 2021	Monday 24 May 2021	Tuesday 25 May 2021	Wednesday 26 May 2021	Thursday 27 May 2021	Average
0000	0	0	1	0	0	0	0	0
0100	0	0	1	0	0	0	0	0
0200	0	0	0	0	0	1	0	0
0300	1	0	0	0	0	0	0	0
0400	0	0	0	0	0	0	0	0
0500	1	0	0	0	0	0	0	0
0600	0	1	0	0	1	0	0	0
0700	0	1	0	0	1	2	0	1
0800	1	1	0	4	2	2	1	2
0900	3	1	2	2	3	1	1	2
1000	1	4	1	5	2	1	2	2
1100	2	3	3	3	0	2	4	2
1200	1	2	3	4	3	2	4	3
1300	3	2	3	6	4	4	6	4
1400	4	4	3	8	3	5	1	4
1500	3	2	1	2	1	1	4	2
1600	4	4	0	8	4	4	2	4
1700	5	3	4	5	5	9	6	5
1800	0	1	0	4	2	2	1	1
1900	1	1	1	1	1	3	0	1
2000	1	0	1	5	2	1	2	2
2100	1	0	1	1	0	1	2	1
2200	1	0	0	2	1	1	1	1
2300	1	0	3	0	2	0	0	1
07-19	27	28	20	51	30	35	32	32
06-22	30	30	23	58	34	40	36	36
06-00	32	30	26	60	37	41	37	38
00-00	34	30	28	60	37	42	37	38



TRAFFINOMICS LIMITED

Friday 21 May 2021
TRA/21/081

WEEK COMMENCING:

SITE 01
SOUTHBOUND

KILSARAN BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS

TIME PERIOD	Friday 21 May 2021	Saturday 22 May 2021	Sunday 23 May 2021	Monday 24 May 2021	Tuesday 25 May 2021	Wednesday 26 May 2021	Thursday 27 May 2021	Average
0000	1	0	0	0	0	0	0	0
0100	0	0	1	0	0	0	0	0
0200	0	0	0	0	0	0	0	0
0300	0	0	0	0	0	0	0	0
0400	0	0	0	0	0	0	0	0
0500	0	0	0	0	0	0	0	0
0600	2	1	0	2	3	3	3	2
0700	2	0	1	3	5	4	5	3
0800	2	0	0	1	3	1	2	1
0900	5	4	0	1	2	2	0	2
1000	2	1	2	1	3	2	2	2
1100	4	5	1	5	3	2	4	3
1200	3	5	7	3	6	3	6	5
1300	2	4	0	4	0	2	3	2
1400	2	4	4	5	2	3	3	3
1500	3	5	5	3	1	4	3	3
1600	3	3	1	4	1	5	1	3
1700	1	3	0	3	5	3	3	3
1800	5	0	1	2	2	2	1	2
1900	1	1	1	1	2	3	2	2
2000	0	1	4	2	2	1	0	1
2100	1	1	1	1	0	3	1	1
2200	0	1	0	0	2	0	1	1
2300	0	1	0	1	2	0	0	1
07-19	34	34	22	35	33	33	33	32
06-22	38	38	28	41	40	43	39	38
06-00	38	40	28	42	44	43	40	39
00-00	39	40	29	42	44	43	40	40



TRAFFINOMICS LIMITED

**KILSARAN BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS**

WEEK COMMENCING:
Friday 21 May 2021
TRA/21/081

**SITE 01
NORTHBOUND**

Profile:

Filter time: 00:00 21st May 2021 => 23:59 27th May 2021
Speed range: 0 - 200 km/h.
Separation: Greater than 4.00 seconds. - (Headway)
Units: Metric (meter, kilometer, m/s, km/h, kg, tonne)


Vehicles = 264

Maximum = 63.3 km/h, Minimum = 11.7 km/h, Mean = 36.8 km/h
85% Speed = 48.26 km/h, 95% Speed = 51.93 km/h, Median = 37.98 km/h
20 km/h Pace = 31 - 51, Number in Pace = 167 (63.26%)
Variance = 104.76, Standard Deviation = 10.24 km/h

Speed Bins:

Speed KPH	Bin	
	No.	%
00-10	0	0.0
10-20	12	4.5
20-30	63	23.9
30-40	75	28.4
40-50	88	33.3
50-60	25	9.5
60-70	1	0.4
70-80	0	0.0
80-90	0	0.0
90-100	0	0.0
100-110	0	0.0
110-120	0	0.0
120-130	0	0.0
130-140	0	0.0
140-150	0	0.0
150-160	0	0.0
160-170	0	0.0
170-180	0	0.0

Total Vehicles (Per Speed Bin)





TRAFFINOMICS LIMITED

Friday 21 May 2021
TRA/21/081

WEEK COMMENCING:

SITE 01
SOUTHBOUND

KILSARAN BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS


Profile:

Filter time: 00:00 21st May 2021 => 23:59 27th May 2021
Speed range: 0 - 200 km/h.
Separation: Greater than 4.00 seconds. - (Headway)
Units: Metric (meter, kilometer, m/s, km/h, kg, tonne)

Vehicles = 269
Maximum = 65.0 km/h, Minimum = 9.2 km/h, Mean = 37.5 km/h
85% Speed = 48.64 km/h, 95% Speed = 53.46 km/h, Median = 38.61 km/h
20 km/h Pace = 29 - 49, Number in Pace = 177 (65.80%)
Variance = 122.02, Standard Deviation = 11.05 km/h

Speed Bins:

Speed KPH	Bin	
	No.	%
00-10	2	0.7
10-20	24	8.9
20-30	42	15.6
30-40	73	27.1
40-50	99	36.8
50-60	26	9.7
60-70	3	1.1
70-80	0	0.0
80-90	0	0.0
90-100	0	0.0
100-110	0	0.0
110-120	0	0.0
120-130	0	0.0
130-140	0	0.0
140-150	0	0.0
150-160	0	0.0
160-170	0	0.0
170-180	0	0.0





TRAFFINOMICS LIMITED

CLASSIFICATION SCHEMES:

Scheme F Classification Scheme (Non-metric)

Scheme F is an attempt to implement the FWA's visual classification scheme as an axle-based classification scheme. This is one of several interpretations.

Vehicle Class	Class	Vehicle Type	No. of Axles	Axle spacing in feet					
				Axle 1 to 2	Axle 2 to 3	Axle 3 to 4	Axle 4 to 5	Axle 5 to 6	
PCL/MCL	1	motorcycle	2	<6.0					
CAR*	2	passenger car	2	6.0 - 10.0					
		car + 1 axle trailer	3	<10.0	10.0 - 18.0				
LGV**		car + 2 axle trailer	4	<10.0		<3.5			
		pickup	2	10.0 - 15.0					
	3	pickup + 1 axle trailer	3	10.0 - 15.0	10.0 - 18.0				
		pickup + 2 axle trailer	4	10.0 - 15.0		<3.5			
BUS		pickup + 3 axle trailer	5	9.9 - 15.0			<3.5		
	4	bus	2	>20.0					
OGV 1		bus	3	>19.0					
	5	single unit truck - dual rear axle	2	14.9 - 20.0					
	6	3 axle truck	3		<18.0				
	7	4 axle truck	4						
OGV 2		2S1	3		>18.0				
	8	2S2	4		>5.0	>3.5			
		3S1	4		<5.0	>10.0			
	9	3S2	5		<6.1		3.5 - 8.0		
		5 axle combination	5						
	10	6 axle combination	6			3.5 - 5.0			
		3S3	6						
	11	2S1-2	5		>6.0				
	12	3S1-2	6						
	13	truck	7 or more						>10.0

Car* Cars and LGV based cars

LGV** Light Goods Vehicles with the exception of LGV based on cars



Traffic Survey Data – Automatic Traffic Counter Site L1615 Hilltown Great Road



Site Locations



Site Locations



	Job number: TRA/21/223	Job Date: Week Commencing Tuesday 23 rd November 2021	Drawing No: TRA/21/223-01	traffinomics ie
	Client: Trafficwise		Author: SPW	



TRAFFINOMICS LIMITED

WEEK COMMENCING: Tuesday 23 November 2021
TRA/21/223

SUMMARY

SITE 01

**BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS**

LOCATION: L1615 North of Laburham Farm (Google Maps Ref: 53.656780, -6.355420)

SPEED SURVEY SUMMARY:

NORTHBOUND 85% Speed = 72.28 km/h, 95% Speed = 79.27 km/h, Median = 61.76 km/h
Maximum = 105.2 km/h, Minimum = 6.8 km/h, Mean = 61.7 km/h
SOUTHBOUND 85% Speed = 73.33 km/h, 95% Speed = 80.53 km/h, Median = 63.43 km/h
Maximum = 110.0 km/h, Minimum = 6.9 km/h, Mean = 63.43 km/h

VOLUMETRIC VEHICLE COUNTS:

Direction	Time	Tuesday 23 November 2021	Wednesday 24 November 2021	Thursday 25 November 2021	Friday 26 November 2021	Saturday 27 November 2021	Sunday 28 November 2021	Monday 29 November 2021	No. Vehicles	7 day Mean
NORTHBOUND	07-19	411	403	428	416	364	313	373	2708	387
SOUTHBOUND	07-19	410	415	394	399	369	313	372	2672	382
NORTHBOUND	00-00	483	479	496	483	439	369	433	3182	455
SOUTHBOUND	00-00	491	492	487	489	445	382	436	3222	460

PEAK FLOW SUMMARY:

Peak	AM	IP	PM
Most Frequent Peak Hour	0800	1200	1600
Average Vehicles per Peak Hour	39	41	39



TRAFFINOMICS LIMITED

BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS

SITE 01
NORTHBOUND

WEEK COMMENCING: Tuesday 23 November 2021
TRA/21/223

TIME PERIOD	Tuesday 23 November 2021	Wednesday 24 November 2021	Thursday 25 November 2021	Friday 26 November 2021	Saturday 27 November 2021	Sunday 28 November 2021	Monday 29 November 2021	Average
0000	1	0	0	1	2	3	2	1
0100	0	0	1	0	2	4	2	1
0200	1	1	0	0	2	2	0	1
0300	0	0	0	0	1	0	0	0
0400	0	0	2	0	0	2	1	1
0500	2	2	4	4	2	1	3	3
0600	15	11	13	10	4	1	12	9
0700	20	22	15	24	5	4	22	16
0800	53	49	50	47	21	7	41	38
0900	24	43	36	43	20	9	36	30
1000	31	32	32	39	28	30	27	31
1100	26	26	34	35	50	54	32	37
1200	38	29	36	38	44	47	37	38
1300	35	27	40	30	43	35	28	34
1400	46	36	38	31	40	25	32	35
1500	43	45	40	33	23	30	39	36
1600	39	42	42	28	40	31	32	36
1700	26	32	40	44	32	28	32	33
1800	30	20	25	24	18	13	15	21
1900	19	22	17	25	22	13	15	19
2000	10	27	15	12	22	11	11	15
2100	15	7	7	6	8	11	10	9
2200	6	5	5	9	6	7	4	6
2300	3	1	4	0	4	1	0	2
07-19	411	403	428	416	364	313	373	387
06-22	470	470	480	469	420	349	421	440
06-00	479	476	489	478	430	357	425	448
00-00	483	479	496	483	439	369	433	455



TRAFFINOMICS LIMITED

WEEK COMMENCING: Tuesday 23 November 2021
TRA/21/223

SITE 01
SOUTHBOUND

BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS

TIME PERIOD	Tuesday 23 November 2021	Wednesday 24 November 2021	Thursday 25 November 2021	Friday 26 November 2021	Saturday 27 November 2021	Sunday 28 November 2021	Monday 29 November 2021	Average
0000	0	0	1	2	6	9	3	3
0100	1	0	1	0	3	4	0	1
0200	0	0	0	0	1	1	0	0
0300	0	0	0	0	0	1	0	0
0400	1	0	0	0	0	1	0	0
0500	2	2	1	1	1	1	2	1
0600	8	7	12	12	3	0	7	7
0700	29	32	25	30	4	5	23	21
0800	44	43	40	27	18	12	40	32
0900	44	27	37	24	25	29	32	31
1000	32	24	30	23	33	16	23	26
1100	29	32	25	31	32	29	21	28
1200	34	41	35	38	43	39	43	39
1300	39	38	46	41	47	41	32	41
1400	38	32	25	37	25	36	24	31
1500	21	38	39	49	41	23	35	35
1600	39	34	32	31	38	42	40	37
1700	36	39	31	29	36	21	30	32
1800	25	35	29	39	27	20	29	29
1900	33	29	24	31	18	20	24	26
2000	14	19	30	16	14	15	11	17
2100	13	10	9	15	14	9	11	12
2200	6	7	5	10	7	5	3	6
2300	3	3	10	3	9	3	3	5
07-19	410	415	394	399	369	313	372	382
06-22	478	480	469	473	418	357	425	443
06-00	487	490	484	486	434	365	431	454
00-00	491	492	487	489	445	382	436	460



TRAFFINOMICS LIMITED

**BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS**

WEEK COMMENCING: Tuesday 23 November 2021
TRA/21/223

**SITE 01
NORTHBOUND**

Profile:


Filter time: 00:00 23rd November 2021 => 23:59 29th November 2021
Speed range: 0 - 200 km/h.
Separation: Greater than 4.00 seconds. - (Headway)
Units: Metric (meter, kilometer, m/s, km/h, kg, tonne)

Vehicles = 2945

Maximum = 105.2 km/h, Minimum = 6.8 km/h, Mean = 61.7 km/h
85% Speed = 72.28 km/h, 95% Speed = 79.27 km/h, Median = 61.76 km/h
20 km/h Pace = 57 - 77, Number in Pace = 1885 (64.01%)

Speed Bins:

Speed KPH	Bin	
	No.	%
00-10	2	0.0
10-20	5	0.2
20-30	20	0.7
30-40	106	3.6
40-50	494	16.8
50-60	993	33.7
60-70	868	29.5
70-80	368	12.5
80-90	77	2.6
90-100	9	0.3
100-110	3	0.1
110-120	0	0.0
120-130	0	0.0
130-140	0	0.0
140-150	0	0.0
150-160	0	0.0
160-170	0	0.0
170-180	0	0.0





TRAFFINOMICS LIMITED

WEEK COMMENCING: Tuesday 23 November 2021
TRA/21/223

**BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS**

**SITE 01
SOUTHBOUND**

Profile:

Filter time: 00:00 23rd November 2021 => 23:59 29th November 2021

Speed range: 0 - 200 km/h.

Separation: Greater than 4.00 seconds. - (Headway)

Units: Metric (meter, kilometer, m/s, km/h, kg, tonne)

Vehicles = 3010


Maximum = 110.0 km/h, Minimum = 6.9 km/h, Mean = 63.6 km/h

85% Speed = 73.33 km/h, 95% Speed = 80.53 km/h, Median = 63.43 km/h

20 km/h Pace = 56 - 76, Number in Pace = 2153 (71.53%)

Speed Bins:

Speed KPH	Bin	
	No.	%
00-10	1	0.0
10-20	2	0.1
20-30	3	0.1
30-40	25	0.8
40-50	123	4.1
50-60	724	22.5
60-70	1228	40.8
70-80	678	24.1
80-90	178	5.9
90-100	38	1.3
100-110	9	0.2
110-120	1	0.1
120-130	0	0.0
130-140	0	0.0
140-150	0	0.0
150-160	0	0.0
160-170	0	0.0
170-180	0	0.0





TRAFFINOMICS LIMITED

**BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS**

SUMMARY

WEEK COMMENCING: Tuesday 23 November 2021
TRA/21/223

SITE 02

LOCATION: L1615 South of Laburham Farm (Google Maps Ref: 53.656780, -6.355420)

SPEED SURVEY SUMMARY:

NORTHBOUND 85% Speed = 76.40 km/h, 95% Speed = 86.93 km/h, Median = 64.79 km/h
Maximum = 130.2 km/h, Minimum = 17.5 km/h, Mean = 64.9 km/h
SOUTHBOUND 85% Speed = 73.16 km/h, 95% Speed = 82.39 km/h, Median = 60.65 km/h
Maximum = 122.0 km/h, Minimum = 0.0 km/h, Mean = 61.1 km/h

VOLUMETRIC VEHICLE COUNTS:

Direction	Time	Tuesday 23 November 2021	Wednesday 24 November 2021	Thursday 25 November 2021	Friday 26 November 2021	Saturday 27 November 2021	Sunday 28 November 2021	Monday 29 November 2021	No. Vehicles 7 day Mean
NORTHBOUND	07-19	411	403	428	416	364	313	373	387
SOUTHBOUND	07-19	410	415	394	399	369	313	372	382
NORTHBOUND	00-00	483	479	496	483	439	369	433	455
SOUTHBOUND	00-00	491	492	487	489	445	382	436	460

PEAK FLOW SUMMARY:

Peak	AM	IP	PM
Most Frequent Peak Hour	0800	1200	1600
Average Vehicles per Peak Hour	39	41	39



TRAFFINOMICS LIMITED

WEEK COMMENCING: Tuesday 23 November 2021
TRA/21/223

**SITE 02
NORTHBOUND**

**BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS**

TIME PERIOD	Tuesday 23 November 2021	Wednesday 24 November 2021	Thursday 25 November 2021	Friday 26 November 2021	Saturday 27 November 2021	Sunday 28 November 2021	Monday 29 November 2021	Average
0000	1	0	0	1	2	3	2	1
0100	0	0	1	0	2	4	2	1
0200	1	1	0	0	2	2	0	1
0300	0	0	0	0	1	0	0	0
0400	0	0	2	0	0	2	1	1
0500	2	2	4	4	2	1	3	3
0600	15	11	13	10	4	1	12	9
0700	20	22	15	24	5	4	22	16
0800	53	49	50	47	21	7	41	38
0900	24	43	36	43	20	9	36	30
1000	31	32	32	39	28	30	27	31
1100	26	26	34	35	50	54	32	37
1200	38	29	36	38	44	47	37	38
1300	35	27	40	30	43	35	28	34
1400	46	36	38	31	40	25	32	35
1500	43	45	40	33	23	30	39	36
1600	39	42	42	28	40	31	32	36
1700	26	32	40	44	32	28	32	33
1800	30	20	25	24	18	13	15	21
1900	19	22	17	25	22	13	15	19
2000	10	27	15	12	22	11	11	15
2100	15	7	7	6	8	11	10	9
2200	6	5	5	9	6	7	4	6
2300	3	1	4	0	4	1	0	2
07-19	411	403	428	416	364	313	373	387
06-22	470	470	480	469	420	349	421	440
06-00	479	476	489	478	430	357	425	448
00-00	483	479	496	483	439	369	433	455



TRAFFINOMICS LIMITED

**BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS**

**SITE 02
SOUTHBOUND**

WEEK COMMENCING: Tuesday 23 November 2021
TRA/21/223

TIME PERIOD	Tuesday 23 November 2021	Wednesday 24 November 2021	Thursday 25 November 2021	Friday 26 November 2021	Saturday 27 November 2021	Sunday 28 November 2021	Monday 29 November 2021	Average
0000	0	0	1	2	6	9	3	3
0100	1	0	1	0	3	4	0	1
0200	0	0	0	0	1	1	0	0
0300	0	0	0	0	0	1	0	0
0400	1	0	0	0	0	1	0	0
0500	2	2	1	1	1	1	2	1
0600	8	7	12	12	3	0	7	7
0700	29	32	25	30	4	5	23	21
0800	44	43	40	27	18	12	40	32
0900	44	27	37	24	25	29	32	31
1000	32	24	30	23	33	16	23	26
1100	29	32	25	31	32	29	21	28
1200	34	41	35	38	43	39	43	39
1300	39	38	46	41	47	41	32	41
1400	38	32	25	37	25	36	24	31
1500	21	38	39	49	41	23	35	35
1600	39	34	32	31	38	42	40	37
1700	36	39	31	29	36	21	30	32
1800	25	35	29	39	27	20	29	29
1900	33	29	24	31	18	20	24	26
2000	14	19	30	16	14	15	11	17
2100	13	10	9	15	14	9	11	12
2200	6	7	5	10	7	5	3	6
2300	3	3	10	3	9	3	3	5
07-19	410	415	394	399	369	313	372	382
06-22	478	480	469	473	418	357	425	443
06-00	487	490	484	486	434	365	431	454
00-00	491	492	487	489	445	382	436	460



TRAFFINOMICS LIMITED

WEEK COMMENCING: Tuesday 23 November 2021
TRA/21/223

**BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS**

**SITE 02
NORTHBOUND**

Profile:

Filter time: 00:00 23rd November 2021 => 23:59 29th November 2021

Speed range: 0 - 200 km/h.

Separation: Greater than 4.00 seconds. - (Headway)

Units: Metric (meter, kilometer, m/s, km/h, kg, tonne)

Vehicles = 2965

Maximum = 130.2 km/h, Minimum = 17.5 km/h, Mean = 64.9 km/h

85% Speed = 76.40 km/h, 95% Speed = 86.93 km/h, Median = 64.79 km/h

20 km/h Pace = 64 - 84, Number in Pace = 1700 (57.34%)

Variance = 182.40, Standard Deviation = 13.51 km/h

Speed Bins:

Speed KPH	Bin	
	No.	%
00-10	1	0.0
10-20	2	0.1
20-30	23	0.8
30-40	68	2.3
40-50	270	9.1
50-60	671	22.6
60-70	927	31.3
70-80	636	21.5
80-90	280	9.4
90-100	68	2.3
100-110	11	0.4
110-120	5	0.2
120-130	2	0.1
130-140	1	0.0
140-150	0	0.0
150-160	0	0.0
160-170	0	0.0
170-180	0	0.0

Total Vehicles (Per Speed Bin)





TRAFFINOMICS LIMITED

**BELLEWSTOWN TRAFFIC COUNT/SPEED SURVEYS
AUTOMATIC TRAFFIC COUNTS**

WEEK COMMENCING: Tuesday 23 November 2021
TRA/21/223

**SITE 02
SOUTHBOUND**

Profile:


Filter time: 00:00 23rd November 2021 -> 23:59 29th November 2021
Speed range: 0 - 200 km/h.
Separation: Greater than 4.00 seconds. - (Headway)
Units: Metric (meter, kilometer, m/s, km/h, kg, tonne)

Vehicles = 3007

Maximum = 122.0 km/h, Minimum = 0.0 km/h, Mean = 61.1 km/h
85% Speed = 73.16 km/h, 95% Speed = 82.39 km/h, Median = 60.65 km/h
20 km/h Pace = 59 - 79, Number in Pace = 1878 (62.45%)
Variance = 162.42, Standard Deviation = 12.74 km/h

Speed Bins:

Speed KPH	Bin	
	No.	%
00-10	3	0.1
10-20	9	0.3
20-30	23	0.8
30-40	77	2.6
40-50	391	13.0
50-60	931	31.0
60-70	938	31.2
70-80	428	14.2
80-90	153	5.1
90-100	38	1.3
100-110	11	0.4
110-120	2	0.1
120-130	3	0.1
130-140	0	0.0
140-150	0	0.0
150-160	0	0.0
160-170	0	0.0
170-180	0	0.0





TRAFFINOMICS LIMITED

CLASSIFICATION SCHEMES:

Scheme F Classification Scheme (Non-metric)

Scheme F is an attempt to implement the FWHA's visual classification scheme as an axle-based classification scheme. This is one of several interpretations.


Vehicle Class	Class	Vehicle Type	No. of Axles	Axle spacing in feet					
				Axle 1 to 2	Axle 2 to 3	Axle 3 to 4	Axle 4 to 5	Axle 5 to 6	
PCL/MCL	1	motorcycle	2	<6.0					
CAR*	2	passenger car	2	6.0 - 10.0					
		car + 1 axle trailer	3	<10.0	10.0 - 18.0				
		car + 2 axle trailer	4	<10.0		<3.5			
		pickup	2	10.0 - 15.0					
LGV**	3	pickup + 1 axle trailer	3	10.0 - 15.0	10.0 - 18.0				
		pickup + 2 axle trailer	4	10.0 - 15.0		<3.5			
		pickup + 3 axle trailer	5	9.9 - 15.0			<3.5		
		bus	2	>20.0					
BUS	4	bus	3	>19.0					
OGV 1	5	single unit truck - dual rear axle	2	14.9 - 20.0					
	6	3 axle truck	3		<18.0				
	7	4 axle truck	4						
		2S1	3		>18.0				
OGV 2	8	2S2	4		>5.0	>3.5			
		3S1	4		<5.0	>10.0			
		3S2	5		<6.1		3.5 - 8.0		
	9	5 axle combination	5						
		6 axle combination	6			3.5 - 5.0			
	10	3S3	6						
	11	2S1-2	5		>6.0				
	12	3S1-2	6						
	13	truck	7 or more						
									>10.0


Car* Cars and LGV based cars

LGV** Light Goods Vehicles with the exception of LGV based on cars




APPENDIX 12.2: TRAFFIC NETWORK FLOW DIAGRAMS







Photograph B-19 – West cutwater of pier 4 with vegetation growth evident



Photograph B-20 – South face of pier 4



Photograph B-17 – West cutwater of pier 3 with vegetation growth evident



Photograph B-18 – South face of pier 3



Photograph B-15 – West cutwater of pier 1 with vegetation growth evident



Photograph B-16 – North face of pier 2 with vegetation growth evident



Photograph B-13 – South abutment



Photograph B-14 – North face of pier 1 with undermining evident



Photograph B-11 – East spandrel wall with minor vegetation growth evident



Photograph B-12 – North abutment with pointing loss and undermining evident below waterline



Photograph B-9 – SE embankment with overgrown vegetation evident



Photograph B-10 – West spandrel wall with minor vegetation growth evident



Photograph B-7 – NE embankment with overgrown vegetation evident



Photograph B-8 – SW embankment with overgrown vegetation evident




Photograph B-5 – East parapet and grass verge



Photograph B-6 – NW embankment with overgrown vegetation evident



Photograph B-3 – Area of depression to carriageway surface above pier 3. Note tie into R150 road surfacing above arch 3.



Photograph B-4 – West parapet and grass verge

Appendix B. Inspection Photographs



Photograph B-1 – Bridge surface looking south



Photograph B-2 – Bridge surface looking north

Appendix A. Structure Location Map

Meath County Council - Viewing Purposes Only!

Appendices

Abutments/Piers

A qualitative assessment was carried out for the substructure elements with the areas of undermining to north abutment and northern piers giving the substructure an overall fair condition rating. Repair works to the areas of undermining are required to restore the substructure to a good condition, with the infilling of the scour damage at the west elevation also recommended.

5. Conclusions

The structure is in an overall fair condition with minor areas of masonry and pointing loss found to the arch barrels, piers and abutments. Repointing works should be undertaken in order to restore these key structural elements to a good condition.

The depression noted to the carriageway surfacing and the scour damage to the riverbed are the defects of most concern. Repairs are recommended to be undertaken to the areas of scour damage below the structure with the mainline carriageway surfacing previously only extended to arch 3 over the structure now extended to beyond the south abutment. The grass verges over the structure should be replaced by concrete verges to prevent further water ingress through the arch barrels.

The low 3t load capacity found for the existing structure is due to the shallow depths of fill over the structure, estimated to be less than 100mm in places. Investigation works are therefore recommended to determine the exact depth of fill above each barrel and the thickness of each arch in order to undertake a Stage 2 assessment. The investigation works should also confirm if there is existing backing present to the arch barrels, with backing recommended to be installed to the structure if not present.

As Beaumont Bridge is behaving satisfactorily under current loading no load restriction is recommended at this time, with further investigation and assessment recommended to confirm the load capacity for the structure. Consideration should also be given to the use of structural health monitoring to monitor the behaviour of the structure under the current loading.

6. Recommendations

The further investigation/assessment recommended to be undertaken to Beaumont Bridge are as follows:

- Trial pit excavations to the bridge surface to confirm the depth of fill and arch thickness of each arch barrel
- Trial pit excavations to the bridge surface to confirm presence of backing to arch barrels
- Stage 2 assessment of the structure in accordance with TII AM-STR-06057 Stage 2 Structural Assessment of Sub-Standard Road Structures

The recommended repair works for the structure are as follows:

- Masonry repointing to the arch barrels, piers and abutments
- Repairs to areas of undermining to the north abutment and northern piers
- Infilling of scour holes at the west elevation
- Removal of debris trapped at the west elevation of arch barrel 7
- Replacement of the grass verges with new concrete verges
- Vegetation removal and repointing to the parapets, spandrel walls and wing walls
- Vegetation clearance to the embankments
- Installation of backing to the arch barrels
- Replacement of carriageway surfacing over the structure

Based on a visual inspection and the recommendations of AM-STR-06002 Annex D, the condition factors used in the arch assessment are summarised in Table 4-2 below.

Table 4-2 Condition factors to be used in the Assessment

Condition Factor		Reasoning
Barrel Factor, F_b	1.0	Limestone in good overall condition
Fill Factor, F_f	0.7	Well compacted material
Joint Width Factor, F_w	0.8	Joint widths greater than 12.5mm (conservative)
Joint Depth factor, F_d	0.8	Loss of pointing evident, average depths 20mm
Joint Mortar factor, F_{mo}	1.0	Mortar in good condition
Condition Factor, F_{cM}	0.9	Good overall condition with pointing loss evident

The Modified MEXE analysis gives a live load capacity varying between 18 and 40 tonnes Gross Vehicle Weight (GVW) for all arch barrels, see Table 4-3 below.

Table 4-3 Results of Modified MEXE Analysis

	Max Gross Vehicle Weight (tonnes)	
	Upper Bound	Lower Bound
Arch Barrel 1	40t	18t
Arch Barrel 2	40t	40t
Arch Barrel 3	18t	18t
Arch Barrel 4	18t	18t
Arch Barrel 5	40t	40t
Arch Barrel 6	40t	40t
Arch Barrel 7	40t	40t

As the structure is a multi-span arch structure the guidance given in AM-STR-06026 was followed with the results from the MEXE analysis corroborated with the results of the three-hinge limit analysis method using Archie-M software. Archie-M analysis was carried out on the structure for both HA and SV assessment loading. The Archie-M analysis carried out on the structure determined that the existing structure has a less than 3t load capacity for the lowerbound condition (0.6* voussoir thickness) and a 3t load capacity for the upperbound condition (full voussoir thickness). See Table 4-4 below for a summary of the Archie-M analysis results.

Table 4-4 Results of the Archie-M Analysis

		Present Condition	Good Condition	Backing Present
HA Loading	Lowerbound	Fails 3t	Fails 3t	44t
	Upperbound	3t	3t	44t
SV Loading	Lowerbound	Fails SV80	Fails SV80	SV80
	Upperbound	Fails SV80	Fails SV80	SV100

The results from the Archie-M analysis shows that the third condition comprising the presence of backing greatly increases the load capacity of the structure. Structural investigations are therefore recommended to both confirm the arch thickness dimensions and also to confirm if backing is present over the structure.

See Appendix C of this report for the calculations and outputs from both the MEXE and Archie-M analysis.

Abutments

The abutments are in a good overall condition apart from pointing loss and undermining to the north abutment below the waterline. The south abutment is mostly hidden below the mudline, see Photograph B-12 and B-13 for both abutments.

Piers

The piers are in a fair overall condition with minor areas of pointing loss to the pier faces and vegetation growth to the cutwaters. There is also 400mm deep undermining noted to pier 1 and 200mm deep undermining noted to pier 2 with masonry and pointing loss noted below the waterline, see Photograph B-14 to B-21 for the piers.

Arch Barrels

The masonry arch barrels are in a fair condition overall with minor masonry and pointing loss evident to localised areas throughout. Water ingress is evident to all arch barrels most likely due to the soft verges over the structure with a transverse crack also evident to the arch barrel of span 1 above the north abutment.

See Photograph B-22 to B-29 for the arch barrels.

Riverbed

The riverbed below the structure is in a poor condition due the extensive scour noted at the upstream elevation of spans 1 to 4, with scour depths of up to 500mm recorded. Undermining is evident to the piers in spans 1 and 2 as a result of the scour to the adjacent riverbed. Both the upstream and downstream watercourse are impacted by overgrown vegetation with the watercourse mainly channelled through arches 3 and 4 as a result.

See Photograph B-30 and B-31 for the riverbed.

Overall Structure

The structure is in an overall fair condition with minor areas of masonry and pointing loss found to the arch barrels, piers and abutments. The depression noted to the carriageway surfacing and the scour damage to the riverbed are the defects of most concern.

See Photograph B-32 and B-33 for both elevations of the structure.

4. Structural Assessment

A structural assessment in accordance with AM-STR-06056 Stage 1 Structural Assessment of Road Structures was undertaken to Beaumont Bridge in order to confirm the load carrying capacity of the structure.

Arch Barrels

A structural assessment of the masonry arch barrels was undertaken using the modified MEXE method outlined in AM-STR-06002 *The Assessment of Road Bridges and Structures*. The structure dimensions surveyed on site by Atkins and used in the assessment are listed below in Table 4-1.

Table 4-1 Structure dimensions used in the Assessment

	Dimension (m)						
	Arch 1	Arch 2	Arch 3	Arch 4	Arch 5	Arch 6	Arch 7
Span	2.360	2.890	4.220	4.510	2.310	2.570	2.720
Rise at Crown	1.170	1.280	1.930	2.010	1.150	1.190	1.350
Rise at Quarter Point	1.050	1.020	1.560	1.660	0.960	1.030	1.100
Ring Thickness*	0.350	0.370	0.420	0.440	0.370	0.370	0.450
Depth of Fill	0.100	0.150	0.100	0.100	0.400	0.380	0.200

* Lowerbound value (0.6x) of external voussoir thickness used for assessment purposes in accordance with AM-STR-06056-01 Stage 1 Structural Assessment of Road Structures.

1. Introduction

Kilsaran engaged Atkins to undertake the structural assessment of MH-L1615-001.00 Beaumont Bridge in accordance with TII Publication *AM-STR-06056 Stage 1 Structural Assessment of Road Structures* to determine the current condition and load capacity of the existing structure. The structural assessment of the structure was undertaken in accordance with TII Publication *AM-STR-06026 The Assessment of Road Bridges and Structures*.

2. Description of the Structure

MH-L1615-001.00 Beaumont Bridge is a seven span masonry arch structure carrying the L1615 local road over the River Nanny in the townland of Beaumont, Co. Meath. The structure has span widths varying between 2.31m and 4.51m with a total length of 44.65m and a width out to out of 7.5m. The structure shows evidence of historical widening works using masonry construction, with varying arch profiles and open joints evident below the structure.

The structure is a protected structure and is listed in the Record of Protected Structures within the Meath County Development Plan 2021-2027.

The location of the structure is shown on the location map in Appendix A of this report.

3. Visual Inspection

The Principal Inspection of the structure was undertaken in December 2021. The condition of each component of the structure is outlined below with photographs from the inspection provided in Appendix C of this report. For the purposes of inspection the arch barrels and piers and have been numbered in a north to south direction.

Bridge Surface

The carriageway surfacing over the structure is split into 2no. distinct sections, the local road surfacing and the newer tie in surfacing from the mainline R150 local road.

The newer tie in surfacing is in a good condition overall, with the local road surfacing showing a loss of skid resistance throughout with areas of surfacing loss and potholes forming. There is also an area of depression noted to the carriageway surface above pier 3. See Photograph B-1 to B-3 for details of the bridge surface.

Verges

Raised grass verges are present along the base of both parapets over the structure, with areas of water ingress noted to the arch barrels below. See Photograph B-4 and B-5 for both verges.

Parapets

The masonry parapets are in a good overall condition with minor vegetation removal and repointing required. See Photograph B-4 and B-5 for both parapets.

Embankments

The embankments at both elevations are in a fair overall condition with areas of vegetation clearance required to maintain access to the structure. See Photograph B-6 to B-9. There is large debris restricting access to arch 7, see Photograph B-29.

Wing/Spandrel walls

The wing and spandrel walls are in a fair condition overall with areas of vegetation growth and minor pointing loss evident. See Photograph B-10 and B-11 for the spandrel walls.

Executive Summary

MH-L1615-001.00 Beaumont Bridge is a seven span masonry arch structure carrying the L1615 local road over the River Nanny in the townland of Beaumont, Co. Meath. The structure has span widths varying between 2.31m and 4.51m with a total length of 44.65m and a width out to out of 7.5m. The structure shows evidence of historical widening works using masonry construction, with varying arch profiles and open joints evident below the structure.

The structure is a protected structure and is listed in the Record of Protected Structures within the Meath County Development Plan 2021-2027.

The structure is in an overall fair condition with minor areas of masonry and pointing loss found to the arch barrels, piers and abutments. Repointing works should be undertaken in order to restore these key structural elements to a good condition.

The depression noted to the carriageway surfacing and the scour damage to the riverbed are the defects of most concern. Repairs are recommended to be undertaken to the areas of scour damage below the structure with the mainline carriageway surfacing previously only extended to arch 3 over the structure now extended to beyond the south abutment. The grass verges over the structure should be replaced by concrete verges to prevent further water ingress through the arch barrels.

The structural assessment of the structure was undertaken in accordance with TII Publication AM-STR-06056 Stage 1 Structural Assessment of Road Structures. The structural assessment found the existing structure to have a reduced load capacity of <3t and 3t for the lowerbound and upperbound conditions respectively, mainly due to the shallow depth of fill above the structure, estimated to be less than 100mm in places. Investigation works are therefore recommended to determine the exact depth of fill above each barrel and the thickness of each arch in order to undertake a Stage 2 assessment.

The presence of backing to the arch barrels determined an increased load capacity of 44t, with site investigations recommended to be undertaken to confirm if existing backing is present to the arch barrels, with backing recommended to be installed to the structure if not present.

As Beaumont Bridge is behaving satisfactorily under current loading no load restriction is recommended at this time, with further investigation and assessment recommended to confirm the load capacity for the structure. Consideration should also be given to the use of structural health monitoring to monitor the behaviour of the structure under the current loading.

The further investigation/assessment recommended to be undertaken to Beaumont Bridge are as follows:

- Trial pit excavations to the bridge surface to confirm the depth of fill and arch thickness of each arch barrel
- Trial pit excavations to the bridge surface to confirm presence of backing to arch barrels
- Stage 2 assessment of the structure in accordance with TII AM-STR-06057 Stage 2 Structural Assessment of Sub-Standard Road Structures

The recommended repair works for the structure are as follows:

- Masonry repointing to the arch barrels, piers and abutments
- Repairs to areas of undermining to the north abutment and northern piers
- Infilling of scour holes at the west elevation
- Removal of debris trapped at the west elevation of arch barrel 7
- Replacement of the grass verges with new concrete verges
- Vegetation removal and repointing to the parapets, spandrel walls and wing walls
- Vegetation clearance to the embankments
- Installation of backing to the arch barrels
- Replacement of carriageway surfacing over the structure

Contents

Chapter	Page
Executive Summary	1
1. Introduction	2
2. Description of the Structure	2
3. Visual Inspection	3
4. Structural Assessment	5
5. Conclusions	5
6. Recommendations	6
Appendices	7
Appendix A. Structure Location Map	8
Appendix B. Inspection Photographs	25
Appendix C. Structural Assessment	
Tables	
Table 4-1 Structure dimensions used in the Assessment	3
Table 4-2 Condition factors to be used in the Assessment	4
Table 4-3 Results of Modified MEXE Analysis	4
Table 4-4 Results of the Archie-M Analysis	4

Notice

This document and its contents have been prepared and are intended solely as information for Kilsaran and use in relation to Beaumont Bridge Structural Assessment

WS Atkins Ireland Limited assumes no responsibility to any other party in respect of or arising out of or in connection with this document and/or its contents.

Document history

Revision	Purpose description	Origin- ated	Checked	Reviewed	Authorised	Date
Rev 1.0	Issue for Review	RMcS	MG	MJ	MJ	12/01/2022

Client signoff

Client	Kilsaran
Project	Beaumont Bridge Structural Assessment
Job number	5210920
Client signature / date	

ATKINS

Member of the SNC-Lavalin Group

Beaumont Bridge Structural Assessment

Stage 1 Structural Assessment Report


Kilsaran

January 2022


Meath County Council - Viewing Purposes Only!




APPENDIX 12.3: ROAD SAFETY AUDIT


















Photograph B-21 – South face of pier 5



Photograph B-22 – Transverse crack to the bottom of arch barrel 1 above the north abutment



Photograph B-23 – Arch barrel 1 with pointing loss and water ingress evident



Photograph B-24 – Arch barrel 2 with pointing loss, minor masonry loss and water ingress evident



Photograph B-25 – Arch barrel 3 with dropped stones, minor masonry loss and pointing loss evident



Photograph B-26 – Arch barrel 4 with minor pointing loss evident and recent repointing works visible



Photograph B-27 – Arch barrel 5 with water ingress and minor pointing loss evident with a change in the arch profile evident



Photograph B-28 – Arch barrel 6 with water ingress and minor pointing loss evident



Photograph B-29 – Arch barrel 7 with water ingress and minor pointing loss evident and debris located at the west elevation with a change in the arch profile evident



Photograph B-30 – View of downstream riverbed



Photograph B-31 – View of upstream riverbed with watercourse main channel through arches 3 and 4



Photograph B-32 – View of east elevation



Photograph B-33 – View of west elevation

Appendix C. Structural Assessment

Meath County Council - Viewing Purposes Only!

Project	Beaumont Bridge Assessment		Job ref 5210920	
	Structure No. MH-L1615-001.00	Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no. rev 0
	Drawing Ref -	Calc By MG	Date 20-Dec-21	Check by MJ Date 21-Dec-21

Ref	Calculations				Output	
TII AM-STR-06002	Modified MEXE Method - Span 1				Upper Bound	Lower Bound
	Span	L in m			2.360	2.360
	Rise at Crown	r _c in m			1.170	1.170
	Rise at Quarter point	r _q in m			1.050	1.050
	Ring Thickness	d in m			0.350	0.210
	Depth of fill	h in m			0.100	0.240
	Barrel Factor	F _b			1.000	1.000
	Fill Factor	F _f			0.700	0.700
	Joint Width Factor	F _w			0.800	0.800
	Joint Mortar Factor	F _{mo}			1.000	1.000
	Horizontal Curve Radius	r in m			>600	>600
	$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	$F_A = 1 + \frac{0.20 v^2}{r}$		1.000	1.000
	Joint Depth Factor	F _d			0.020	0.020
	Average depth of missing mortar, in m					
Annex G	=>	F _d			0.800	0.800
	Condition Factor	F _{cm}			0.900	0.900
		h + d in m			0.450	0.450
		L / r _c			2.017	2.017
	From Fig. 3.2 Nonogram Provisional Axle Loading	P.A.L.			49.08	49.08
		or 740 x $\frac{(d + h)^2}{L^{1.3}} = P.A.L.$				
From Fig. 3.3	Span/Rise Factor	F _{sr}			1.000	1.000
From Fig. 3.4	Profile Factor	F _p = $2.3 \times [(r_c - r_q)/r_c]^{0.6}$			0.587	0.587
	Material Factor	F _m = $\frac{(F_b \times d) + (F_f \times h)}{h + d}$			0.933	0.840
	Joint Factor	F _j = F _w x F _{mo} x F _d			0.640	0.640
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L)	M.A.L = F _{sr} x F _p x F _m x F _j x F _{cm} x P.A.L			15.476	13.928
	AXLE FACTOR (A _f - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N)	☒			
	Single axle -	1.00 Allowable A.L			15.5	13.9
	2-Axle bogie	0.66 Allowable A.L			10.2	9.2
	3-Axle bogie	1.00 Allowable A.L			15.5	13.9
	LOAD CAPACITY	Max G.V.W in tonnes =			40	18

Project	Beaumont Bridge Assessment		Job ref 5210920	
Structure No. MH-L1615-001.00	Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no.	rev 0
Drawing Ref -	Calc By MG	Date 20-Dec-21	Check by MJ	Date 21-Dec-21

Ref	Calculations				Output	
TII AM-STR-06002	Modified MEXE Method - Span 2				Upper Bound	Lower Bound
	Span	L in m			2.890	2.890
	Rise at Crown	r_c in m			1.280	1.280
	Rise at Quarter point	r_q in m			1.020	1.020
	Ring Thickness	d in m			0.370	0.222
	Depth of fill	h in m			0.150	0.298
	Barrel Factor	F_b			1.000	1.000
	Fill Factor	F_f			0.700	0.700
	Joint Width Factor	F_w			0.800	0.800
	Joint Mortar Factor	F_{mo}			1.000	1.000
	Horizontal Curve Radius	r in m			>600	>600
	$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	$F_A = 1 + \frac{0.20 v^2}{r}$		1.000	1.000
	Joint Depth Factor	F_d				
	Average depth of missing mortar, in m				0.020	0.020
Annex G	=>	F_d			0.800	0.800
	Condition Factor	F_{cM}			0.900	0.900
		h + d in m			0.520	0.520
		L / r_c			2.258	2.258
	From Fig. 3.2 Nonogram Provisional Axle Loading	P.A.L. or $740 \times \frac{(d+h)^2}{L^{1.3}} = P.A.L.$			50.36	50.36
From Fig. 3.3	Span/Rise Factor	F_{sr}			1.000	1.000
From Fig. 3.4	Profile Factor	$F_p = 2.3 \times [(r_c - r_q)/r_c]^{0.6}$			0.884	0.884
	Material Factor	$F_m = \frac{(F_b \times d) + (F_f \times h)}{h + d}$			0.913	0.828
	Joint Factor	$F_j = F_w \times F_{mo} \times F_d$			0.640	0.640
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L.)	$M.A.L. = F_{sr} \times F_p \times F_m \times F_j \times F_{cM} \times P.A.L.$			23.419	21.230
	AXLE FACTOR (A_f - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N)	☒			
	Single axle -	1.00 Allowable A.L.			23.4	21.2
	2-Axle bogie	0.66 Allowable A.L.			15.5	14.0
	3-Axle bogie	1.00 Allowable A.L.			23.4	21.2
	LOAD CAPACITY	Max G.V.W in tonnes =			40	40

Project	Beaumont Bridge Assessment		Job ref 5210920
Structure No. MH-L1615-001.00	Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no. rev 0
Drawing Ref -	Calc By MG	Date 20-Dec-21	Check by MJ Date 21-Dec-21

Ref	Calculations		Output	
TII AM-STR-06002	Modified MEXE Method - Span 3		Upper Bound	Lower Bound
	Span	L in m	4.220	4.220
	Rise at Crown	r _c in m	1.930	1.930
	Rise at Quarter point	r _q in m	1.560	1.560
	Ring Thickness	d in m	0.420	0.252
	Depth of fill	h in m	0.100	0.268
	Barrel Factor	F _b	1.000	1.000
	Fill Factor	F _f	0.700	0.700
	Joint Width Factor	F _w	0.800	0.800
	Joint Mortar Factor	F _{mo}	1.000	1.000
	Horizontal Curve Radius	r in m	>600	>600
	$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor F _A = 1 + $\frac{0.20 v^2}{r}$	1.000	1.000
	Joint Depth Factor	F _d	0.020	0.020
	Average depth of missing mortar, in m		0.800	0.800
	Annex G => F _d		0.900	0.900
Annex G	Condition Factor	F _{cm}	0.520	0.520
		h + d in m	2.187	2.187
		L / r _c	30.78	30.78
	From Fig. 3.2 Nonogram Provisional Axle Loading	P.A.L. or 740 x $\frac{(d + h)^2}{L^{1.3}} = P.A.L.$	1.000	1.000
	From Fig. 3.3 Span/Rise Factor	F _{sr}	0.854	0.854
	From Fig. 3.4 Profile Factor	F _p = $2.3 \times [(r_c - r_q)/r_c]^{0.6}$	0.942	0.845
	Material Factor	F _m = $\frac{(F_b \times d) + (F_f \times h)}{h + d}$	0.640	0.640
	Joint Factor	F _j = F _w x F _{mo} x F _d	14.265	12.797
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L)	M.A.L = F _{sr} x F _p x F _m x F _j x F _{cm} x P.A.L		
	AXLE FACTOR (A _f - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N) ☒ Y		
	Single axle -	1.03 Allowable A.L	14.7	13.2
	2-Axle bogie	0.66 Allowable A.L	9.5	8.5
	3-Axle bogie	1.00 Allowable A.L	14.3	12.8
	LOAD CAPACITY	Max G.V.W in tonnes =	18	18

ATKINS		Project	Beaumont Bridge Assessment		Job ref 5210920		
		Structure No. MH-L1615-001.00	Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no. rev 0		
		Drawing Ref -	Calc By MG	Date 20-Dec-21	Check by MJ	Date 21-Dec-21	
		Calculations					Output
Ref							
TII AM-STR-06002	Modified MEXE Method - Span 4					Upper Bound	Lower Bound
	Span	L in m			4.510	4.510	
	Rise at Crown	r _c in m			2.010	2.010	
	Rise at Quarter point	r _q in m			1.660	1.660	
	Ring Thickness	d in m			0.440	0.264	
	Depth of fill	h in m			0.100	0.276	
	Barrel Factor	F _b			1.000	1.000	
	Fill Factor	F _f			0.700	0.700	
	Joint Width Factor	F _w			0.800	0.800	
	Joint Mortar Factor	F _{mo}			1.000	1.000	
	Horizontal Curve Radius	r in m			>600	>600	
	$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	F _A =	$1 + \frac{0.20 v^2}{r}$	1.000	1.000	
	Joint Depth Factor	F _d			0.020	0.020	
	Average depth of missing mortar, in m						
Annex G	=>	F _d			0.800	0.800	
	Condition Factor	F _{cM}			0.900	0.900	
		h + d in m			0.540	0.540	
		L / r _c			2.244	2.244	
	From Fig. 3.2 Nonogram Provisional Axle Loading	P.A.L.			30.45	30.45	
		or	740 x	$\frac{(d + h)^2}{L^{1.3}} = P.A.L.$			
From Fig. 3.3	Span/Rise Factor	F _{sr}			1.000	1.000	
From Fig. 3.4	Profile Factor	F _p	=	$2.3 \times [(r_c - r_q)/r_c]^{0.6}$	0.806	0.806	
	Material Factor	F _m	=	$\frac{(F_b \times d) + (F_f \times h)}{h + d}$	0.944	0.847	
	Joint Factor	F _j	=	F _w x F _{mo} x F _d	0.640	0.640	
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L.)	M.A.L.	=	F _{sr} x F _p x F _m x F _j x F _{cM} x P.A.L.	13.349	11.967	
	AXLE FACTOR (A _r - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N)		Y			
	Single axle -	1.07	Allowable A.L.		14.3	12.8	
	2-Axle bogie	0.67	Allowable A.L.		8.9	8.0	
	3-Axle bogie	1.00	Allowable A.L.		13.3	12.0	
	LOAD CAPACITY	Max G.V.W in tonnes =			18	18	

ATKINS		Project		Beaumont Bridge Assessment		Job ref 5210920	
Ref		Structure No. MH-L1615-001.00		Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no. rev 0	
		Drawing Ref		Calc By MG		Check by MJ	
				Date 20-Dec-21		Date 21-Dec-21	
Calculations				Output			
				Upper Bound	Lower Bound		
Modified MEXE Method - Span 5							
TII	AM-STR-06002	Span	L in m	2.310	2.310		
		Rise at Crown	r _c in m	1.150	1.150		
		Rise at Quarter point	r _q in m	0.960	0.960		
		Ring Thickness	d in m	0.370	0.222		
		Depth of fill	h in m	0.400	0.548		
		Barrel Factor	F _b	1.000	1.000		
		Fill Factor	F _f	0.700	0.700		
		Joint Width Factor	F _w	0.800	0.800		
		Joint Mortar Factor	F _{mo}	1.000	1.000		
		Horizontal Curve Radius	r in m	>600	>600		
		$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor F _A = 1 + $\frac{0.20 v^2}{r}$	1.000	1.000		
		Joint Depth Factor	F _d	0.020	0.020		
		Average depth of missing mortar, in m		0.800	0.800		
Annex G		=>	F _d	0.900	0.900		
		Condition Factor	F _{cm}	0.770	0.770		
			h + d in m	2.009	2.009		
		From Fig. 3.2 Nonogram	P.A.L.	70.00	70.00		
		Provisional Axle Loading	or 740 x $\frac{(d + h)^2}{L^{1.3}} = P.A.L.$	1.000	1.000		
From Fig. 3.3		Span/Rise Factor	F _{sr}	0.781	0.781		
From Fig. 3.4		Profile Factor	F _p = 2.3 x [(r _c - r _q)/r _c] ^{0.6}	0.844	0.786		
		Material Factor	F _m = $\frac{(F_b \times d) + (F_f \times h)}{h + d}$	0.640	0.640		
		Joint Factor	F _j = F _w x F _{mo} x F _d	26.577	24.762		
		MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L)	M.A.L = F _{sr} x F _p x F _m x F _j x F _{cm} x P.A.L				
		AXLE FACTOR (A _f - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N) ☒				
		Single axle -	1.00 Allowable A.L	26.6	24.8		
		2-Axle bogie	0.66 Allowable A.L	17.5	16.3		
		3-Axle bogie	1.00 Allowable A.L	26.6	24.8		
		LOAD CAPACITY	Max G.V.W in tonnes =	40	40		

ATKINS		Project	Beaumont Bridge Assessment		Job ref 5210920		
		Structure No. MH-L1615-001.00	Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no. rev 0		
		Drawing Ref -	Calc By MG	Date 20-Dec-21	Check by MJ	Date 21-Dec-21	
		Calculations		Output			
Ref							
TII AM-STR-06002	Modified MEXE Method - Span 6					Upper Bound	Lower Bound
	Span	L in m			2.570	2.570	
	Rise at Crown	r _c in m			1.190	1.190	
	Rise at Quarter point	r _q in m			1.030	1.030	
	Ring Thickness	d in m			0.370	0.222	
	Depth of fill	h in m			0.380	0.528	
	Barrel Factor	F _b			1.000	1.000	
	Fill Factor	F _f			0.700	0.700	
	Joint Width Factor	F _w			0.800	0.800	
	Joint Mortar Factor	F _{mo}			1.000	1.000	
	Horizontal Curve Radius	r in m			>600	>600	
	$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	F _A =	$1 + \frac{0.20 v^2}{r}$	1.000	1.000	
	Joint Depth Factor	F _d			0.020	0.020	
	Average depth of missing mortar, in m				0.800	0.800	
Annex G	=>	F _d			0.900	0.900	
	Condition Factor	F _{cm}			0.750	0.750	
		h + d in m			2.160	2.160	
		L / r _c			70.00	70.00	
	From Fig. 3.2 Nonogram	P.A.L.					
	Provisional Axle Loading		or	$740 \times \frac{(d + h)^2}{L^{1.3}} = P.A.L.$			
From Fig. 3.3	Span/Rise Factor	F _{sr}			1.000	1.000	
From Fig. 3.4	Profile Factor	F _p	=	$2.3 \times [(r_c - r_q)/r_c]^{0.6}$	0.690	0.690	
	Material Factor	F _m	=	$\frac{(F_b \times d) + (F_f \times h)}{h + d}$	0.848	0.789	
	Joint Factor	F _j	=	F _w x F _{mo} x F _d	0.640	0.640	
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L.)	M.A.L. = F _{sr} x F _p x F _m x F _j x F _{cm} x P.A.L.			23.593	21.946	
	AXLE FACTOR (A _f - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N)	Y				
	Single axle -	1.00	Allowable A.L.		23.6	21.9	
	2-Axle bogie	0.66	Allowable A.L.		15.6	14.5	
	3-Axle bogie	1.00	Allowable A.L.		23.6	21.9	
	LOAD CAPACITY	Max G.V.W in tonnes =			40	40	

ATKINS		Project		Beaumont Bridge Assessment		Job ref 5210920	
		Structure No. MH-L1615-001.00		Assessment using TII AM-STR-06002 MEXE Method		Calc sheet no. rev 0	
		Drawing Ref		Calc By MG	Date 20-Dec-21	Check by MJ	Date 21-Dec-21
Ref	Calculations					Output	
TII AM-STR-06002	Modified MEXE Method - Span 7					Upper Bound	Lower Bound
	Span	L in m				2.720	2.720
	Rise at Crown	r _c in m				1.350	1.350
	Rise at Quarter point	r _q in m				1.100	1.100
	Ring Thickness	d in m				0.450	0.270
	Depth of fill	h in m				0.200	0.380
	Barrel Factor	F _b				1.000	1.000
	Fill Factor	F _f				0.700	0.700
	Joint Width Factor	F _w				0.800	0.800
	Joint Mortar Factor	F _{mo}				1.000	1.000
	Horizontal Curve Radius	r in m				>600	>600
	$v^2 = \frac{1000 r}{r + 150}$	Centrifugal Effect Factor	F _A =	1 +	$\frac{0.20 v^2}{r}$	1.000	1.000
	Joint Depth Factor	F _d				0.020	0.020
	Average depth of missing mortar, in m						
Annex G	=>	F _d				0.800	0.800
	Condition Factor	F _{cm}				0.900	0.900
		h + d in m				0.650	0.650
		L / r _c				2.015	2.015
	From Fig. 3.2 Nonogram Provisional Axle Loading	P.A.L.	or	740 x	$\frac{(d + h)^2}{L^{1.3}} = P.A.L.$	70.00	70.00
From Fig. 3.3	Span/Rise Factor	F _{sr}				1.000	1.000
From Fig. 3.4	Profile Factor	F _p	=	$2.3 \times [(r_c - r_q)/r_c]^{0.6}$		0.836	0.836
	Material Factor	F _m	=	$\frac{(F_b \times d) + (F_f \times h)}{h + d}$		0.908	0.825
	Joint Factor	F _j	=	F _w x F _{mo} x F _d		0.640	0.640
	MODIFIED AXLE LOAD FOR 2-AXLE BOGIE (M.A.L)	M.A.L	=	F _{sr} x F _p x F _m x F _j x F _{cm} x P.A.L		30.602	27.801
	AXLE FACTOR (A _f - see Fig 3.5a & 3.5b)	Axle lift-off (Y/N)		☒			
	Single axle -	1.00	Allowable A.L			30.6	27.8
	2-Axle bogie	0.66	Allowable A.L			20.2	18.3
	3-Axle bogie	1.00	Allowable A.L			30.6	27.8
	LOAD CAPACITY	Max G.V.W in tonnes =				40	40

Project	Beaumont Bridge Assessment		Job ref 5210920	
Part of Structure MH-L1615-001.00	Archie M analysis		Calc sheet no.	rev
Drawing Ref	Calc By	Date	Check by	Date
-	MG	20-Dec-21	MJ	21-Dec-21

Ref

Calculations

Output

Summary of Load Cases (Highlighted in bold) Considered in ArchieM Analysis

If $h < d$ Load Cases 1 & 2
are not required

Axle Lift Off: Yes/No?

Yes

Case 1: Lower Bound - Most onerous AWR vehicle

- 1A : In present condition
- 1B : In perfect condition
- 1C : If backing is also present

Case 2: Upper Bound - Most onerous AWR vehicle

- 2A : In present condition
- 2B : In perfect condition
- 2C : If backing is also present

Case 3: Lower Bound (SV Loading)

- 3A : In present condition
- 3B : In perfect condition
- 3C : If backing is also present

Case 4: Upper Bound (SV Loading)

- 4A : In present condition
- 4B : In perfect condition
- 4C : If backing is also present

Summary of Results

1A	1B	1C
Fails 3t	Fails 3t	44t
2A	2B	2C
3t	3t	44t
3A	3B	3C
Fails SV80	Fails SV80	SV80
4A	4B	4C
Fails SV80	Fails SV80	SV100

Project	Beaumont Bridge Assessment		Job ref 5210920	
Part of Structure MH-L1615-001.00	Archie M analysis		Calc sheet no.	rev 0
Drawing Ref -	Calc By MG	Date 20-Dec-21	Check by MJ	Date 21-Dec-21

Ref	Calculations	Output																																																						
	Arch Assessment using ArchieM <u>General Archie Input</u> <table><tr><td>Thickness of road surfacing</td><td>=</td><td>0.2</td><td>m</td><td>road surfacing only</td></tr><tr><td>Unit weight of road surfacing</td><td>=</td><td>23</td><td>kN/m3</td><td></td></tr><tr><td>Masonry comp. strength</td><td>=</td><td>7</td><td>N/mm2</td><td></td></tr><tr><td>Density</td><td>=</td><td>22</td><td>kN/m3</td><td></td></tr><tr><td>Unit weight of fill</td><td>=</td><td>18</td><td>kN/m3</td><td>(default in Archie)</td></tr><tr><td>phi</td><td>=</td><td>30</td><td></td><td>(default in Archie)</td></tr></table> <u>Arch Dimensions</u> Refer to MEXE Analysis for dimensions of each span <u>Lane & Load details</u> <u>Load assessment 40t vehicle</u> <table><tr><td>Structure loaded with</td><td>40</td><td>t vehicle</td></tr><tr><td>Load per axle</td><td>=</td><td>11.5 t</td></tr><tr><td>Lane width</td><td>=</td><td>2.5 m</td></tr><tr><td>Distributed width of wheel load</td><td>=</td><td>1.5 +h</td></tr></table> (this is the most conservative lane width) As per Cl.6.23 TII AM-STR-06026 Axles have 1.8m track with 0.7m minimum spacing between the track width of adjacent vehicles <u>Load assessment SV100 vehicle</u> Archie M does not allow load assessment of SV100 vehicle on lanes less than 3.5m Use the more critical of 3.5m lanewidth or actual lane width in analysis <table><tr><td>Structure loaded with</td><td>100</td><td>t vehicle</td></tr><tr><td>Load per axle</td><td>=</td><td>16.5 t</td></tr><tr><td>Lane width</td><td>=</td><td>3.5 m</td></tr><tr><td>Distributed width of wheel load</td><td>=</td><td>1.5 +h</td></tr></table> Axles assumed to have 3.0m track with 0.5m minimum spacing between the track width of adjacent vehicles	Thickness of road surfacing	=	0.2	m	road surfacing only	Unit weight of road surfacing	=	23	kN/m3		Masonry comp. strength	=	7	N/mm2		Density	=	22	kN/m3		Unit weight of fill	=	18	kN/m3	(default in Archie)	phi	=	30		(default in Archie)	Structure loaded with	40	t vehicle	Load per axle	=	11.5 t	Lane width	=	2.5 m	Distributed width of wheel load	=	1.5 +h	Structure loaded with	100	t vehicle	Load per axle	=	16.5 t	Lane width	=	3.5 m	Distributed width of wheel load	=	1.5 +h	Remarks Material: Limestone Ashlar/Random?: Random Rubble with lime mortar
Thickness of road surfacing	=	0.2	m	road surfacing only																																																				
Unit weight of road surfacing	=	23	kN/m3																																																					
Masonry comp. strength	=	7	N/mm2																																																					
Density	=	22	kN/m3																																																					
Unit weight of fill	=	18	kN/m3	(default in Archie)																																																				
phi	=	30		(default in Archie)																																																				
Structure loaded with	40	t vehicle																																																						
Load per axle	=	11.5 t																																																						
Lane width	=	2.5 m																																																						
Distributed width of wheel load	=	1.5 +h																																																						
Structure loaded with	100	t vehicle																																																						
Load per axle	=	16.5 t																																																						
Lane width	=	3.5 m																																																						
Distributed width of wheel load	=	1.5 +h																																																						

Project	Beaumont Bridge Assessment		Job ref 5210920	
Part of Structure MH-L1615-001.00	Archie M analysis		Calc sheet no. rev 0	
Drawing Ref -	Calc By MG	Date 20-Dec-21	Check by MJ	Date 21-Dec-21

Ref

Calculations

Output

TII
AM-STR-
06026

Details for Archie analysis

Condition factors, in present condition

CI.6.2
CI.6.2

	γ_{F3}	=	1	
	γ_m	=	1	
Joint width factor	F_w	=	0.8	
Mortar factor	F_{mo}	=	1	
Average mortar loss	=	0.02		mm (conservative as hidden by gunnite layer)
	F_d	=	1.00	
	$F_j = (F_w * F_{mo} * F_d)$	=	0.80	taken as 1.0 as mortar loss is modelled directly in Archie

- TII AM-STR-06026 CI.6.2 gives a combined gFL factor of 3.4 which is made up a load factor of 1.9 and an impact factor of 1.8. Archie includes the 1.8 impact factor in the load definitions so γ_{FL} is taken as 1.9 in the analysis

- γ_{FL} factor is 2.0 for SV load assessment

			HA	SV
	γ_{FL}	=	1.9	2
Centrifugal effect	F_A	=	1.00	1.00
Condition factor	F_{cm}	=	0.9	0.9

			HA	SV
Effective $\gamma_{FL} = \frac{\gamma_{FL}}{F_j * F_{cm}} * F_A$		=	2.64	2.78

Condition factors, if repair works are carried out


	F_w	=	0.8	
	F_{mo}	=	1	
	F_d	=	1	
	$F_j = (F_w * F_{mo} * F_d)$	=	0.8	joint width does not change

best condition γ_{FL} factor

			HA	SV
	γ_{FL}	=	1.9	2
	F_A	=	1.00	1.00
	F_{cm}	=	1	1
Effective $\gamma_{FL} =$		=	2.38	2.50

Beaumont Bridge

RF (7.5t 2-axle R) impact axle 2 at 15063 mm
25.70 3.57



Upperbound condition => <7.5t load capacity

gammaFI dead load: 1.00 RF (7.5t 2-axle R) impact axle 2 @ 15063 [mm]
gammaFI superimposed: 1.00
gammaFI live load: 2.38
gammaF3 load effect: 1.00
gammaM material: 1.00
File path: V:\521092017 Calcs\72 Model\Beaumont Bridge - UB.brg

NAME: Beaumont Bridge
LOCATION: Beaumont, Meath
NUMBER: MH-L1615-001.00
ATKINS
DATE: 20 December 2021
Printed on: Wednesday, January 12, 2022 15:35:51

Bridge Name: Beaumont Bridge Bridge Location: Beaumont, Meath
 Bridge Number: MH-L1615-001.00
 Number of spans: 7

SAFETY FACTORS

Factor for deadload: 1.00 Factor for superimposed deadload: 1.00 Factor for surfacing: 1.00
 Factor for live load: 2.38 Factor for load effect: 1.00 Factor for material strength: 1.00

APPLIED LOAD CASES

1.RF (7.5t 2-axle R) impact axle 2 Total weight: 73.58 [kN] Position: 15063 [mm]
 7.50 2 1.00 1.50 2.00 10.80 1.00 1.80 2.50
 Effective lane width: 3350 [mm] Distribution length: 2847 [mm]

Applied distribution mode: Archie-M, BD21/97
 Applied live load pressure: Active pressure

STRUCTURE PROPERTIES

Road shape: True shape (multi-point method)
 Road points: (-500, 1950) (1180, 2000) (5805, 2200) (11660, 2550) (19175, 2750) (29755, 2370) (33895, 2290) (43290, 2070) (45000, 2000)
 Depth of surfacing: 150Depth of overlay: 0
 Surface unit weight: 23.00 [kN/m³] Overlay unit weight: 23.00 [kN/m³]
 Lane width: 0

Fill unit weight: 18.00 [kN/m³] Fill phi: 30 degree

Left abutment Base level:-1500 [mm] Height: 380 [mm] Width: 1000 [mm]

Right abutment Base level:-1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Right abutment Base level:-1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Shape: Circular

Span: 2360 [mm] Rise: 1170 [mm] Q-rise: 1050 [mm]

Ring thickness at crown: 350 [mm] Ring thickness at springing: 350 [mm] Mortar loss: 50 [mm]

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust

0	0	380	-350	383	1954	0.00	0.00	0.00	0.00	0.00	0.00	2.26	-29.02	-0.06	-0	4	296
1	4	472	-344	502	1954	1.67	-0.97	-0.09	0.00	-0.00	0.00	0.60	-28.05	-0.15	4	8	292
2	16	563	-329	621	1954	1.53	-1.20	-0.13	0.00	-0.00	0.00	-0.93	-26.85	-0.26	8	12	288
3	35	654	-305	738	1955	1.39	-1.39	-0.15	0.00	-0.00	0.00	-2.32	-25.46	-0.39	13	17	283
4	60	742	-272	853	1956	1.24	-1.53	-0.17	0.00	-0.00	0.00	-3.56	-23.93	-0.53	20	24	276
5	93	828	-230	964	1957	1.10	-1.64	-0.18	0.00	-0.00	0.00	-4.66	-22.29	-0.68	29	32	268
6	132	912	-179	1073	1959	0.96	-1.71	-0.18	0.00	-0.00	0.00	-5.61	-20.58	-0.85	39	42	258
7	177	992	-120	1177	1961	0.82	-1.75	-0.18	0.00	-0.00	0.00	-6.43	-18.83	-1.03	52	54	246
8	229	1068	-53	1276	1963	0.69	-1.75	-0.17	0.00	-0.00	0.00	-7.13	-17.08	-1.21	66	69	231
9	286	1141	21	1369	1965	0.57	-1.73	-0.15	0.00	-0.00	0.00	-7.70	-15.35	-1.40	83	85	215
10	349	1208	103	1456	1968	0.47	-1.69	-0.14	0.00	-0.00	0.00	-8.17	-13.67	-1.59	102	104	196
11	417	1270	191	1537	1970	0.37	-1.63	-0.12	0.00	-0.00	0.00	-8.54	-12.04	-1.77	123	125	175
12	490	1327	285	1611	1972	0.29	-1.56	-0.10	0.00	-0.00	0.00	-8.83	-10.48	-1.95	145	147	153
13	566	1378	384	1677	1975	0.22	-1.48	-0.07	0.00	-0.00	0.00	-9.06	-9.00	-2.11	169	171	129
14	647	1423	489	1735	1978	0.16	-1.40	-0.05	0.00	-0.00	0.00	-9.22	-7.60	-2.26	193	195	105
15	731	1461	597	1785	1982	0.12	-1.33	-0.04	0.00	-0.00	0.00	-9.34	-6.27	-2.40	217	218	81
16	817	1493	710	1826	1985	0.08	-1.26	-0.02	0.00	-0.00	0.00	-9.42	-5.01	-2.52	239	241	59
17	906	1518	825	1858	1989	0.05	-1.20	-0.00	0.00	-0.00	0.00	-9.47	-3.81	-2.63	260	261	39
18	996	1536	942	1881	1992	0.03	-1.16	0.01	0.00	-0.00	0.00	-9.51	-2.66	-2.72	276	278	22
19	1088	1546	1061	1895	1996	0.02	-1.13	0.03	0.00	-0.00	0.00	-9.52	-1.53	-2.78	289	290	10
20	1180	1550	1180	1900	2000	0.01	-1.12	0.04	0.00	-0.00	0.00	-9.53	-0.41	-2.83	296	298	2
21	1272	1546	1299	1895	2003	-0.01	-1.13	0.06	-0.00	-0.00	0.00	-9.52	0.72	-2.86	299	300	-0

22	1364	1536	1418	1881	2007	-0.02	-1.15	0.08	-0.00	-0.00	0.00	0.00	-9.50	1.87	-2.86	2952973
23	1454	1518	1535	1858	2011	-0.04	-1.20	0.10	-0.00	-0.00	0.00	0.00	-9.47	3.07	-2.85	28628812
24	1543	1493	1650	1826	2015	-0.06	-1.25	0.12	-0.00	-0.00	0.00	0.00	-9.40	4.32	-2.81	27227426
25	1629	1461	1763	1785	2019	-0.09	-1.33	0.14	-0.00	-0.00	0.00	0.00	-9.31	5.65	-2.74	25425644
26	1713	1423	1871	1735	2023	-0.14	-1.41	0.16	-0.00	-0.00	0.00	0.00	-9.18	7.05	-2.66	23323565
27	1794	1378	1976	1677	2026	-0.19	-1.49	0.19	-0.00	-0.00	0.00	0.00	-8.99	8.54	-2.55	20921189
28	1870	1327	2075	1611	2030	-0.25	-1.58	0.22	-0.00	-0.00	0.00	0.00	-8.73	10.12	-2.42	185187113
29	1943	1270	2169	1537	2034	-0.33	-1.66	0.24	-0.00	-0.00	0.00	0.00	-8.40	11.78	-2.27	161163137
30	2011	1208	2257	1456	2037	-0.42	-1.73	0.27	-0.00	-0.00	0.00	0.00	-7.98	13.52	-2.10	137139161
31	2074	1141	2339	1369	2040	-0.52	-1.79	0.29	-0.00	-0.00	0.00	0.00	-7.46	15.31	-1.91	115117183
32	2131	1068	2413	1276	2043	-0.64	-1.83	0.31	-0.00	-0.00	0.00	0.00	-6.82	17.14	-1.71	95 97 203
33	2183	9922480	1177	2045	-0.77	-1.85	0.33	-0.00	-0.00	0.00	0.00	0.00	-6.05	18.99	-1.50	76 79 221
34	2228	9122539	1073	2047	-0.90	-1.84	0.34	-0.00	-0.00	0.00	0.00	0.00	-5.15	20.83	-1.29	60 63 237
35	2267	8282590	9642049	-1.04	-1.79	0.35	-0.00	-0.00	0.00	0.00	0.00	0.00	-4.11	22.62	-1.08	46 50 250
36	2300	7422632	8532051	-1.19	-1.71	0.35	-0.00	-0.00	0.00	0.00	0.00	0.00	-2.92	24.33	-0.86	34 38 262
37	2325	6542665	7382052	-1.34	-1.59	0.34	-0.00	-0.00	0.00	0.00	0.00	0.00	-1.58	25.92	-0.65	24 27 273
38	2344	5632689	6212053	-1.49	-1.43	0.32	-0.00	-0.00	0.00	0.00	0.00	0.00	-0.09	27.35	-0.45	15 19 281
39	2356	4722704	5022053	-1.64	-1.23	0.30	-0.00	-0.00	0.00	0.00	0.00	0.00	1.55	28.58	-0.25	7 11 289
40	2360	3802710	3832054	-1.77	-0.98	0.26	-0.00	-0.00	0.00	0.00	0.00	0.00	3.32	29.56	-0.06	0 4 296

Segment Intrados.x Intrados.x Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust

Base level: -1500 [mm] Top level: 380 [mm] Thickness at top: 2000 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment	Left	xRight	x z	Weight	Fx	Fz	My	Thrust left	Thrust right	Stress left	Stress right	Dist. left	Dist. right
0	2360	4360	380	-107.72	-4.00	-107.72	7.88	3425	3441	-0.04	-0.07	1065.42	919.19
1	2360	4360	-247	-27.57	-4.00	-135.29	5.37	3390	3409	-0.06	-0.08	1030.01	950.66
2	2360	4360	-873	-27.57	-4.00	-162.87	2.86	3366	3389	-0.08	-0.09	1005.92	970.81
3	2360	4360	-1500	-27.57	-4.00	-190.44	0.35	3348	3375	-0.09	-0.10	988.24	984.55

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 2890 [mm] Rise: 1280 [mm] Q-rise: 1020 [mm]

Ring thickness at crown: 370 [mm] Ring thickness at springing: 370 [mm] Mortar loss: 50 [mm]

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment	Intrados.x	Intrados.z	Extrados.x	Extrados.z	Road.z	Fx dead	Fz dead	My dead	Fx live	Fz live	My live	Fx passive	Fx total	Fz total	My total	Thrust in	Thrust out	Extra-Thrust
0	4360	4003993	4452109	0.00	0.00	0.00	0.00	0.00	0.00	-0.68	-37.41	-0.10	-0	5 315				
1	4377	5044013	5752109	1.93	-1.58	-0.16	0.00	-0.00	0.00	-2.61	-35.83	-0.27	5 10 310					
2	4401	6074044	7042111	1.75	-1.79	-0.20	0.00	-0.00	0.00	-4.36	-34.04	-0.45	11 16 304					
3	4432	7084083	8302113	1.58	-1.95	-0.22	0.00	-0.00	0.00	-5.94	-32.09	-0.66	18 23 297					
4	4471	8064131	9542115	1.40	-2.07	-0.23	0.00	-0.00	0.00	-7.34	-30.02	-0.89	27 31 289					
5	4516	9014189	1073 2118	1.23	-2.15	-0.23	0.00	-0.00	0.00	-8.57	-27.88	-1.13	37 42 278					
6	4569	9934254	1188 2121	1.07	-2.19	-0.22	0.00	-0.00	0.00	-9.63	-25.69	-1.39	50 54 266					
7	4627	1080 4328	1298 2124	0.91	-2.19	-0.21	0.00	-0.00	0.00	-10.54	-23.50	-1.65	64 67 253					
8	4693	1163 4410	1402 2128	0.77	-2.17	-0.19	0.00	-0.00	0.00	-11.31	-21.33	-1.92	80 83 237					
9	4763	1241 4499	1500 2132	0.64	-2.12	-0.17	0.00	-0.00	0.00	-11.94	-19.21	-2.20	98 101 219					
10	4840	1314 4594	1591 2137	0.52	-2.06	-0.15	0.00	-0.00	0.00	-12.46	-17.16	-2.46	117 120 200					
11	4921	1381 4697	1675 2142	0.41	-1.97	-0.13	0.00	-0.00	0.00	-12.88	-15.18	-2.72	139 141 179					
12	5007	1442 4805	1752 2147	0.33	-1.89	-0.10	0.00	-0.00	0.00	-13.20	-13.29	-2.97	161 164 156					
13	5098	1497 4918	1820 2153	0.25	-1.79	-0.08	0.00	-0.00	0.00	-13.45	-11.50	-3.21	184 186 134					
14	5192	1544 5036	1880 2159	0.19	-1.70	-0.05	0.00	-0.00	0.00	-13.64	-9.79	-3.43	207 209 111					
15	5289	1585 5158	1931 2165	0.14	-1.62	-0.03	0.00	-0.00	0.00	-13.78	-8.17	-3.64	230 232 88					
16	5389	1619 5283	1974 2172	0.10	-1.55	-0.01	0.00	-0.00	0.00	-13.88	-6.63	-3.83	251 253 67					
17	5491	1646 5411	2007 2178	0.07	-1.49	0.01	0.00	-0.00	0.00	-13.94	-5.14	-4.00	271 273 47					
18	5595	1665 5541	2031 2185	0.04	-1.45	0.03	0.00	-0.00	0.00	-13.99	-3.69	-4.15	288 290 30					

Uncinl - Viewing Purposes Only!

19	5700	1676	5673	2045	2192	0.02	-1.42	0.05	0.00	-0.00	0.00	0.00	-14.01	-2.27	-4.28	30230416
20	5805	1680	5805	2050	2199	0.01	-1.42	0.07	0.00	-0.00	0.00	0.00	-14.02	-0.85	-4.38	3123146
21	5910	1676	5937	2045	2207	-0.01	-1.44	0.09	0.00	-0.00	0.00	0.00	-14.01	0.59	-4.46	3173191
22	6015	1665	6069	2031	2214	-0.03	-1.47	0.11	0.00	-0.00	0.00	0.00	-13.98	2.06	-4.51	318320-0 ***
23	6119	1646	6199	2007	2221	-0.05	-1.53	0.13	0.00	-0.00	0.00	0.00	-13.93	3.59	-4.53	3143164
24	6221	1619	6327	1974	2229	-0.08	-1.60	0.16	0.00	-0.00	0.00	0.00	-13.85	5.20	-4.52	30530713
25	6321	1585	6452	1931	2236	-0.12	-1.69	0.19	0.00	-0.00	0.00	0.00	-13.73	6.89	-4.47	29229426
26	6418	1544	6574	1880	2243	-0.17	-1.79	0.22	0.00	-0.00	0.00	0.00	-13.55	8.68	-4.39	27427644
27	6512	1497	6692	1820	2250	-0.24	-1.90	0.25	0.00	-0.00	0.00	0.00	-13.32	10.58	-4.27	25325664
28	6603	1442	6805	1752	2257	-0.31	-2.01	0.28	0.00	-0.00	0.00	0.00	-13.00	12.58	-4.11	23023387
29	6689	1381	6913	1675	2263	-0.40	-2.11	0.32	0.00	-0.00	0.00	0.00	-12.60	14.69	-3.92	206208112
30	6770	1314	7016	1591	2269	-0.51	-2.21	0.36	0.00	-0.00	0.00	0.00	-12.09	16.90	-3.69	181184136
31	6847	1241	7111	1500	2275	-0.63	-2.29	0.39	0.00	-0.00	0.00	0.00	-11.46	19.20	-3.42	156159161
32	6917	1163	7200	1402	2280	-0.77	-2.36	0.42	0.00	-0.00	0.00	0.00	-10.69	21.55	-3.13	132135185
33	6983	1080	7282	1298	2285	-0.91	-2.40	0.45	0.00	-0.00	0.00	0.00	-9.78	23.95	-2.80	110113207
34	7041	9937356	1188	2289	-1.07	-2.41	0.47	0.00	-0.00	0.00	0.00	0.00	-8.70	26.37	-2.45	89 93 227
35	7094	9017421	1073	2293	-1.24	-2.39	0.48	0.00	-0.00	0.00	0.00	0.00	-7.46	28.75	-2.08	70 74 246
36	7139	8067479	9542297	-1.42	-2.33	0.49	0.00	-0.00	0.00	0.00	0.00	0.00	-6.04	31.09	-1.70	53 57 263
37	7178	7087527	8302300	-1.60	-2.23	0.49	0.00	-0.00	0.00	0.00	0.00	0.00	-4.43	33.31	-1.31	37 42 278
38	7209	6077566	7042302	-1.79	-2.08	0.48	0.00	-0.00	0.00	0.00	0.00	0.00	-2.64	35.40	-0.91	24 29 291
39	7233	5047597	5752304	-1.98	-1.89	0.45	0.00	-0.00	0.00	0.00	0.00	0.00	-0.67	37.29	-0.51	11 16 304
40	7250	4007617	4452306	-2.16	-1.65	0.42	0.00	-0.00	0.00	0.00	0.00	0.00	1.49	38.94	-0.11	-0 5 315

SegmentIntrados.x Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 100 [mm] Thickness at top: 2300 [mm]

Masonry unit weight:22.00 [kN/m3] Masonry strength: 7.00 [MPa]

SegmentLeft xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 7250 9550 100-175.52 -39.88 -175.52 -21.74 8264 8289 -0.10 -0.05 1013.61 1261.32
1 7250 9550 -433 -26.99 -39.88 -202.51 -43.01 8173 8202 -0.14 -0.04 923.15 1347.92
2 7250 9550 -967 -26.99 -39.88 -229.50 -64.28 8104 8136 -0.17 -0.03 853.51 1413.71
3 7250 9550 -1500 -26.99 -39.88 -256.48 -85.55 8048 8085 -0.21 -0.01 798.12 1465.24

SegmentLeft xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular

Span: 4220 [mm] Rise: 1930 [mm] Q-rise: 1560 [mm]
Ring thickness at crown:420 [mm] Ring thickness at springing: 420 [mm] Mortar loss: 50 [mm]
Masonry unit weight:22.00 [kN/m3] Masonry strength: 7.00 [MPa]

SegmentIntrados.x Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
0 9550 1009132 1372400 0.00 0.00 0.00 0.00 -38.39 -70.11 -53.34 723734-364 ***
1 9570 2569155 3242401 3.71 -2.53 -0.20 0.00 -0.00 0.00 -42.10 -67.57 -47.80 645655-285 ***
2 9601 4099193 5082403 3.36 -2.96 -0.28 0.00 -0.00 0.00 -45.46 -64.61 -42.43 572583-213 ***
3 9643 5609244 6892407 3.01 -3.29 -0.33 0.00 -0.00 0.00 -48.47 -61.33 -37.27 504514-144 ***
4 9697 7089308 8662411 2.66 -3.52 -0.37 0.00 -0.00 0.00 -51.13 -57.80 -32.35 439450-80 ***
5 9761 8519385 1037 2415 2.32 -3.68 -0.38 0.00 -0.00 0.00 -53.45 -54.13 -27.70 378389-19 ***
6 9836 9899474 1203 2421 1.99 -3.75 -0.38 0.00 -0.00 0.00 -55.45 -50.37 -23.35 32133139
7 9921 1121 9576 1361 2427 1.69 -3.76 -0.36 0.00 -0.00 0.00 -57.13 -46.62 -19.31 26727892
8 10015 1247 9689 1511 2434 1.40 -3.70 -0.32 0.00 -0.00 0.00 -58.54 -42.92 -15.62 217227143
9 10118 1365 9813 1653 2442 1.14 -3.59 -0.29 0.00 -0.00 0.00 -59.68 -39.32 -12.28 172181189
10 10230 1475 9947 1785 2450 0.91 -3.45 -0.24 0.00 -0.00 0.00 -60.59 -35.88 -9.31 130140230
11 10350 1576 10090 1906 2459 0.71 -3.27 -0.19 0.00 -0.00 0.00 -61.30 -32.61 -6.74 94 103267
12 10477 1669 10242 2017 2468 0.54 -3.08 -0.15 0.00 -0.00 0.00 -61.85 -29.53 -4.58 63 72 298
13 10610 1751 10402 2116 2478 0.40 -2.88 -0.10 0.00 -0.00 0.00 -62.24 -26.65 -2.84 37 47 323
14 10749 1824 10568 2203 2487 0.29 -2.69 -0.06 0.00 -0.00 0.00 -62.53 -23.96 -1.54 18 28 342
15 10893 1886 10741 2278 2498 0.20 -2.50 -0.02 0.00 -0.00 0.00 -62.73 -21.46 -0.69 6 15 355

16	11041	1938	10919	2339	2508	0.13	-2.35	0.02	0.00	-0.00	0.00	0.00	-62.86	-19.11	-0.31	-0	9	361
17	11193	1978	11100	2388	2518	0.08	-2.22	0.05	0.00	-0.00	0.00	0.00	-62.94	-16.89	-0.39	1	11	359
18	11347	2007	11285	2422	2529	0.05	-2.13	0.08	0.00	-0.00	0.00	0.00	-62.99	-14.77	-0.94	10	19	351
19	11503	2024	11472	2443	2539	0.03	-2.07	0.11	0.00	-0.00	0.00	0.00	-63.02	-12.69	-1.96	26	35	335
20	11660	2030	11660	2450	2549	0.01	-2.06	0.15	0.00	-0.00	0.00	0.00	-63.03	-10.63	-3.44	50	59	311
21	11817	2024	11848	2443	2560	-0.01	-2.10	0.18	-0.00	-0.00	0.00	0.00	-63.02	-8.53	-5.36	82	91	279
22	11973	2007	12035	2422	2569	-0.03	-2.18	0.22	-0.00	-0.00	0.00	0.00	-62.98	-6.35	-7.72	121	130	240
23	12127	1978	12220	2388	2579	-0.07	-2.29	0.27	-0.01	-0.00	0.00	0.00	-62.92	-4.06	-10.49	169	178	192
24	12279	1938	12401	2339	2588	-0.11	-2.45	0.32	-0.01	-0.11	0.02	0.00	-62.80	-1.51	-13.66	225	233	137
25	12427	1886	12579	2278	2597	-0.18	-2.63	0.38	-0.29	-2.52	0.47	0.00	-62.32	3.65	-17.23	286	294	76
26	12571	1824	12752	2203	2605	-0.27	-2.84	0.45	-1.13	-7.87	1.48	0.00	-60.92	14.36	-20.92	338	346	24
27	12710	1751	12918	2116	2614	-0.39	-3.07	0.52	-2.28	-13.09	2.58	0.00	-58.26	30.51	-24.01	361	370	-0
28	12843	1669	13078	2017	2621	-0.53	-3.30	0.60	-3.23	-15.60	3.25	0.00	-54.50	49.40	-25.73	348	359	11
29	12970	1576	13230	1906	2627	-0.70	-3.52	0.68	-3.55	-14.62	3.21	0.00	-50.25	67.55	-25.61	309	321	49
30	13090	1475	13373	1785	2634	-0.91	-3.73	0.76	-3.15	-11.12	2.57	0.00	-46.20	82.39	-23.64	257	270	100
31	13202	1365	13507	1653	2640	-1.14	-3.91	0.83	-2.24	-6.81	1.64	0.00	-42.82	93.11	-20.29	202	216	154
32	13305	1247	13631	1511	2646	-1.40	-4.05	0.90	-1.22	-3.19	0.79	0.00	-40.20	100.35	-16.23	150	165	205
33	13399	1121	13744	1361	2650	-1.70	-4.14	0.96	-0.45	-1.02	0.26	0.00	-38.05	105.51	-12.16	104	120	250
34	13484	989	13846	1203	2654	-2.01	-4.17	1.01	-0.13	-0.25	0.07	0.00	-35.91	109.93	-8.56	68	84	286
35	13559	851	13935	1037	2658	-2.35	-4.14	1.04	-0.12	-0.20	0.06	0.00	-33.44	114.27	-5.64	40	56	314
36	13623	708	14012	866	2661	-2.70	-4.02	1.06	-0.14	-0.19	0.06	0.00	-30.60	118.48	-3.44	20	37	333
37	13677	560	14076	689	2663	-3.06	-3.82	1.05	-0.16	-0.17	0.06	0.00	-27.38	122.47	-1.97	7	25	345
38	13719	409	14127	508	2665	-3.43	-3.52	1.02	-0.17	-0.14	0.05	0.00	-23.77	126.14	-1.23	0	19	351
39	13750	256	14165	324	2666	-3.80	-3.13	0.97	-0.18	-0.11	0.04	0.00	-19.79	129.39	-1.22	-0	19	351
40	13770	100	14188	137	2667	-4.16	-2.65	0.90	-0.19	-0.07	0.03	0.00	-15.44	132.11	-1.94	5	24	345
Segment: Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust																		
Base level: -1500 [mm] Top level: 100 [mm] Thickness at top: 3150 [mm]																		
Batter: 1:0																		
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]																		
Segment: Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right																		
Shape: Circular																		
Span: 4510 [mm] Rise: 2010 [mm] Q-rise: 1660 [mm]																		
Ring thickness at crown: 440 [mm] Ring thickness at springing: 440 [mm] Mortar loss: 50 [mm]																		
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]																		
Segment: Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust																		
0	16920	200	16483	250	2735	0.00	0.00	0.00	0.00	0.00	0.00	0.00	2.80	-69.63	-0.34	-0	10	380
1	16945	363	16513	445	2735	4.26	-3.05	-0.25	0.09	-0.04	-0.00	0.00	-1.55	-66.53	-1.51	18	28	362
2	16982	524	16556	638	2736	3.87	-3.52	-0.34	0.08	-0.06	-0.01	0.00	-5.50	-62.96	-2.62	38	47	343
3	17030	682	16614	826	2737	3.47	-3.88	-0.41	0.07	-0.07	-0.01	0.00	-9.05	-59.01	-3.66	58	66	324
4	17090	836	16685	1010	2738	3.08	-4.14	-0.44	0.06	-0.07	-0.01	0.00	-12.19	-54.80	-4.63	80	88	302
5	17160	986	16770	1189	2740	2.70	-4.31	-0.45	0.05	-0.07	-0.01	0.00	-14.94	-50.42	-5.53	103	111	279
6	17242	1130	16867	1360	2741	2.33	-4.39	-0.45	0.04	-0.06	-0.01	0.00	-17.30	-45.97	-6.35	128	135	255
7	17333	1267	16976	1524	2743	1.98	-4.39	-0.42	0.02	-0.05	-0.01	0.00	-19.31	-41.53	-7.10	155	161	229
8	17435	1397	17097	1680	2745	1.66	-4.33	-0.38	0.01	-0.03	-0.00	0.00	-20.98	-37.17	-7.77	182	188	202
9	17545	1520	17229	1827	2746	1.36	-4.21	-0.34	0.00	-0.01	-0.00	0.00	-22.35	-32.95	-8.36	210	216	174
10	17665	1635	17372	1963	2748	1.10	-4.04	-0.28	0.00	-0.00	-0.00	0.00	-23.44	-28.90	-8.86	239	244	146
11	17792	1740	17524	2089	2749	0.87	-3.84	-0.22	0.00	-0.00	-0.00	0.00	-24.31	-25.06	-9.27	266	271	119
12	17926	1836	17684	2203	2750	0.66	-3.62	-0.17	-0.00	0.00	0.00	0.00	-24.97	-21.44	-9.61	292	297	93

Viewing Purposes Only!

13	18068	1922	17853	2306	2751	0.50	-3.38	-0.11	-0.00	0.00	0.00	0.00	-25.47	-18.06	-9.87	31632070
14	18215	1997	18029	2396	2752	0.36	-3.15	-0.06	-0.00	0.00	0.00	0.00	-25.83	-14.91	-10.06	33734149
15	18367	2061	18210	2472	2753	0.25	-2.93	-0.02	-0.00	0.00	0.00	0.00	-26.08	-11.98	-10.19	35435832
16	18523	2114	18397	2536	2753	0.17	-2.73	0.03	-0.00	0.00	0.00	0.00	-26.24	-9.25	-10.27	36837218
17	18683	2156	18588	2586	2753	0.10	-2.56	0.07	-0.00	0.00	0.00	0.00	-26.35	-6.69	-10.31	3773819
18	18846	2186	18782	2621	2752	0.06	-2.42	0.10	-0.00	0.00	0.00	0.00	-26.41	-4.27	-10.31	3843873
19	19010	2204	18978	2643	2751	0.03	-2.32	0.14	-0.00	0.00	0.00	0.00	-26.44	-1.95	-10.29	38639040
20	19175	2210	19175	2650	2750	0.01	-2.27	0.17	-0.00	0.00	0.00	0.00	-26.45	0.32	-10.24	3853891
21	19340	2204	19372	2643	2747	-0.01	-2.26	0.21	0.00	0.00	0.00	0.00	-26.44	2.58	-10.18	3813855
22	19504	2186	19568	2621	2745	-0.03	-2.30	0.25	0.00	0.00	0.00	0.00	-26.41	4.89	-10.09	37437812
23	19667	2156	19762	2586	2743	-0.06	-2.39	0.29	0.00	0.00	0.00	0.00	-26.35	7.27	-9.98	36336723
24	19827	2114	19953	2536	2739	-0.10	-2.52	0.34	0.00	0.00	0.00	0.00	-26.25	9.79	-9.84	35035436
25	19983	2061	20140	2472	2736	-0.16	-2.68	0.40	0.00	0.00	0.00	0.00	-26.09	12.47	-9.67	33333753
26	20135	1997	20321	2396	2732	-0.24	-2.87	0.47	0.00	0.00	0.00	0.00	-25.86	15.34	-9.46	31431872
27	20282	1922	20497	2306	2728	-0.34	-3.09	0.55	0.00	0.00	0.00	0.00	-25.52	18.42	-9.20	29229694
28	20424	1836	20666	2203	2725	-0.47	-3.31	0.63	0.00	0.00	0.00	0.00	-25.04	21.74	-8.88	268273117
29	20558	1740	20826	2089	2721	-0.64	-3.54	0.71	0.00	0.00	0.00	0.00	-24.41	25.28	-8.50	242247143
30	20685	1635	20978	1963	2716	-0.83	-3.76	0.80	0.00	0.00	0.00	0.00	-23.58	29.04	-8.06	216221169
31	20805	1520	21121	1827	2713	-1.06	-3.96	0.88	0.00	0.00	0.00	0.00	-22.52	33.00	-7.55	189195195
32	20915	1397	21253	1680	2709	-1.32	-4.13	0.96	0.00	0.00	0.00	0.00	-21.20	37.13	-6.97	163169221
33	21017	1267	21374	1524	2706	-1.61	-4.25	1.03	0.00	0.00	0.00	0.00	-19.59	41.38	-6.32	137144246
34	21108	1130	21483	1360	2703	-1.93	-4.32	1.09	0.00	0.00	0.00	0.00	-17.67	45.70	-5.61	113120270
35	21190	9862	1580	1189	2700	-2.27	-4.32	1.13	0.00	0.00	0.00	0.00	-15.40	50.02	-4.85	9098292
36	21260	8362	1665	1010	2697	-2.63	-4.25	1.16	0.00	0.00	0.00	0.00	-12.77	54.27	-4.03	6977313
37	21320	6822	1736	8262695	-3.01	-4.09	1.16	0.00	0.00	0.00	0.00	0.00	-9.75	58.36	-3.17	5058332
38	21368	5242	1794	6382693	-3.40	-3.83	1.14	0.00	0.00	0.00	0.00	0.00	-6.35	62.19	-2.26	3241349
39	21405	3632	1837	4452691	-3.79	-3.48	1.10	0.00	0.00	0.00	0.00	0.00	-2.56	65.67	-1.32	1625365
40	21430	2002	1867	2502690	-4.18	-3.03	1.03	0.00	0.00	0.00	0.00	0.00	1.63	68.70	-0.33	010380

Segment Intraados.x Intraados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 200 [mm] Thickness at top: 7170 [mm]

Batter: 1:0
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 21430 28600 200-388.25 1.53 -388.25 -105.13 24716 24772 -0.07 -0.04 3286.49 3828.04
1 21430 28600 -367 -89.39 1.53 -477.64 -104.26 24763 24831 -0.08 -0.05 3332.60 3769.16
2 21430 28600 -933 -89.39 1.53 -567.03 -103.39 24792 24873 -0.09 -0.07 3362.16 3726.84
3 21430 28600 -1500 -89.39 1.53 -656.41 -102.52 24812 24906 -0.10 -0.08 3381.93 3694.30

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular
Span: 2310 [mm] Rise: 1150 [mm] Q-rise: 960 [mm]
Ring thickness at crown: 370 [mm] Ring thickness at springing: 370 [mm] Mortar loss: 50 [mm]
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intraados.x Intraados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
0 28600 45028230 4522422 0.00 0.00 0.00 0.00 0.00 0.00 3.16 -38.55 -0.11 0 6314
1 28604 54028235 5712422 2.10 -1.04 -0.09 -0.00 0.00 0.00 1.06 -37.52 -0.27 4 10 310
2 28615 63028250 6892421 1.96 -1.33 -0.14 -0.00 0.00 0.00 -0.89 -36.18 -0.45 10 15 305
3 28633 71928273 8062421 1.81 -1.59 -0.18 -0.00 0.00 0.00 -2.70 -34.60 -0.67 17 22 298
4 28658 80628306 9212419 1.65 -1.80 -0.21 -0.00 0.00 0.00 -4.35 -32.80 -0.92 26 31 289
5 28689 89028348 10332418 1.49 -1.97 -0.22 -0.00 0.00 0.00 -5.84 -30.83 -1.20 37 41 279
6 28727 97228398 11412416 1.34 -2.10 -0.23 -0.00 0.00 0.00 -7.18 -28.74 -1.49 50 54 266
7 28772 105128457 12452414 1.18 -2.19 -0.23 -0.00 0.00 0.00 -8.36 -26.55 -1.80 65 69 251
8 28822 112628524 13452411 1.03 -2.24 -0.22 -0.00 0.00 0.00 -9.40 -24.31 -2.12 83 86 234
9 28879 119728598 14382409 0.89 -2.27 -0.21 -0.00 0.00 0.00 -10.29 -22.04 -2.44 103106214

10	28940	1263	28679	1526	2406	0.76	-2.27	-0.19	-0.00	0.00	0.00	0.00	-11.05	-19.77	-2.76	125128192
11	29007	1325	28767	1607	2402	0.64	-2.24	-0.17	-0.00	0.00	0.00	0.00	-11.69	-17.53	-3.06	150153167
12	29078	1381	28861	1680	2399	0.53	-2.20	-0.14	-0.00	0.00	0.00	0.00	-12.22	-15.32	-3.35	176179141
13	29153	1431	28960	1746	2395	0.43	-2.15	-0.11	-0.00	0.00	0.00	0.00	-12.65	-13.17	-3.61	203205115
14	29232	1475	29064	1805	2391	0.35	-2.09	-0.09	-0.00	0.00	0.00	0.00	-13.00	-11.08	-3.84	23023288
15	29314	1513	29173	1855	2388	0.27	-2.03	-0.06	-0.00	0.00	0.00	0.00	-13.27	-9.05	-4.03	25525862
16	29399	1544	29285	1896	2384	0.21	-1.97	-0.03	-0.00	0.00	0.00	0.00	-13.47	-7.08	-4.19	27828040
17	29486	1568	29400	1928	2380	0.15	-1.91	-0.00	-0.00	0.00	0.00	0.00	-13.62	-5.17	-4.31	29729921
18	29575	1586	29517	1951	2376	0.10	-1.87	0.02	-0.00	0.00	0.00	0.00	-13.72	-3.30	-4.38	3103128
19	29665	1596	29636	1965	2373	0.06	-1.83	0.05	-0.00	0.00	0.00	0.00	-13.78	-1.47	-4.41	3183200
20	29755	1600	29755	1970	2369	0.02	-1.81	0.07	-0.00	0.00	0.00	0.00	-13.80	0.34	-4.40	318320-0
21	29845	1596	29874	1965	2366	-0.02	-1.80	0.10	0.00	0.00	0.00	0.00	-13.78	2.14	-4.35	3123146
22	29935	1586	29993	1951	2363	-0.06	-1.81	0.12	0.00	0.00	0.00	0.00	-13.72	3.95	-4.25	29930119
23	30024	1568	30110	1928	2360	-0.10	-1.83	0.15	0.00	0.00	0.00	0.00	-13.63	5.78	-4.11	28128337
24	30111	1544	30225	1896	2357	-0.14	-1.86	0.17	0.00	0.00	0.00	0.00	-13.49	7.64	-3.94	25826060
25	30196	1513	30337	1855	2354	-0.19	-1.91	0.20	0.00	0.00	0.00	0.00	-13.29	9.55	-3.73	23323585
26	30278	1475	30446	1805	2351	-0.25	-1.96	0.23	0.00	0.00	0.00	0.00	-13.04	11.50	-3.48	206208112
27	30357	1431	30550	1746	2349	-0.32	-2.01	0.26	0.00	0.00	0.00	0.00	-12.72	13.51	-3.22	178181139
28	30432	1381	30649	1680	2346	-0.40	-2.06	0.29	0.00	0.00	0.00	0.00	-12.31	15.57	-2.93	152155165
29	30503	1325	30743	1607	2344	-0.49	-2.11	0.32	0.00	0.00	0.00	0.00	-11.82	17.68	-2.62	127130190
30	30570	1263	30831	1526	2342	-0.60	-2.15	0.35	0.00	0.00	0.00	0.00	-11.22	19.83	-2.31	104107213
31	30631	1197	30912	1438	2340	-0.71	-2.17	0.37	0.00	0.00	0.00	0.00	-10.52	22.00	-1.99	83.234
32	30688	1126	30986	1345	2339	-0.83	-2.17	0.39	0.00	0.00	0.00	0.00	-9.68	24.18	-1.68	65.252
33	30738	1051	31053	1245	2337	-0.97	-2.15	0.40	0.00	0.00	0.00	0.00	-8.71	26.33	-1.38	49.53.267
34	30783	97231112	1141	2336	-1.11	-2.10	0.41	0.00	0.00	0.00	0.00	0.00	-7.60	28.44	-1.10	36.40.280
35	30821	89031162	1033	2335	-1.26	-2.02	0.41	0.00	0.00	0.00	0.00	0.00	-6.35	30.46	-0.85	26.30.290
36	30852	80631204	9212334	-1.41	-1.90	0.41	0.00	0.00	0.00	0.00	0.00	0.00	-4.94	32.36	-0.62	17.22.298
37	30877	71931237	8062333	-1.56	-1.75	0.39	0.00	0.00	0.00	0.00	0.00	0.00	-3.38	34.11	-0.44	10.15.305
38	30895	63031260	6892333	-1.71	-1.55	0.37	0.00	0.00	0.00	0.00	0.00	0.00	-1.66	35.66	-0.29	6.11.309
39	30906	54031275	5712332	-1.86	-1.31	0.33	0.00	0.00	0.00	0.00	0.00	0.00	0.20	36.97	-0.18	2.7.313
40	30910	45031280	4522332	-2.00	-1.03	0.29	0.00	0.00	0.00	0.00	0.00	0.00	2.20	37.99	-0.10	-0.5.315

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 Base level:-1500 [mm] Top level: 350 [mm] Thickness at top: 1700 [mm]

Batter: 1:0

Masonry unit weight:22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 0 30910 32610 350-115.20-1.15-115.201.95 31769 31785 -0.06-0.07 858.70 824.84
 1 30910 32610 -267 -23.06 -1.15-138.26 1.24 31759 31779 -0.08-0.08 849.08 831.17
 2 30910 32610 -883 -23.06 -1.15-161.32 0.53 31752 31775 -0.09-0.10 841.74 835.21
 3 30910 32610 -1500 -23.06 -1.15-184.39 -0.19 31746 31772 -0.11-0.11 835.83 837.83

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 Shape: Circular
 Span: 2570 [mm] Rise: 1190 [mm] Q-rise: 1030 [mm]
 Ring thickness at crown:370 [mm] Ring thickness at springing: 370 [mm] Mortar loss: 50 [mm]
 Masonry unit weight:22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 0 32610 35032241 3782315 0.00 0.00 0.00 0.00 0.00 0.00 1.04 -41.16 -0.12 0.6 314
 1 32621 44632255 5012314 2.12 -1.38-0.14-0.00 0.00 0.00 -1.08-39.78 -0.33 5.11 309
 2 32639 54032278 6232314 1.96 -1.65-0.18-0.00 0.00 0.00 -3.05-38.13 -0.57 12.18 302
 3 32664 63323211 7432313 1.80 -1.87-0.21-0.00 0.00 0.00 -4.85-36.26 -0.84 21.26 294
 4 32696 72432352 8602312 1.63 -2.04-0.23-0.00 0.00 0.00 -6.48-34.22 -1.13 31.36 284
 5 32735 81232402 9732312 1.47 -2.18-0.24-0.00 0.00 0.00 -7.95-32.04 -1.45 43.47 273
 6 32780 89732460 1083 2311 1.31 -2.28-0.24-0.00 0.00 0.00 -9.25-29.76 -1.79 57.61 259

7	32831	97932526	1187	2310	1.15	-2.34	-0.23	-0.00	0.00	0.00	-10.40	-27.41	-2.14	73	77	243
8	32888	1056	32599	1287	2309	1.00	-2.37	-0.22	-0.00	0.00	-11.40	-25.04	-2.49	91	95	225
9	32951	1129	32680	1381	2308	0.86	-2.38	-0.20	-0.00	0.00	-12.26	-22.67	-2.84	112	116	204
10	33019	1197	32768	1468	2307	0.73	-2.35	-0.18	-0.00	0.00	-12.99	-20.31	-3.18	135	138	182
11	33092	1260	32862	1549	2305	0.61	-2.31	-0.16	-0.00	0.00	-13.60	-18.00	-3.51	159	162	158
12	33170	1317	32962	1622	2303	0.50	-2.26	-0.13	-0.00	0.00	-14.10	-15.74	-3.81	184	187	133
13	33251	1368	33067	1688	2302	0.41	-2.20	-0.10	-0.00	0.00	-14.51	-13.54	-4.08	210	213	107
14	33336	1413	33176	1746	2300	0.33	-2.13	-0.07	-0.00	0.00	-14.83	-11.41	-4.33	235	238	82
15	33425	1451	33290	1796	2298	0.25	-2.06	-0.05	-0.00	0.00	-15.09	-9.35	-4.53	258	261	59
16	33516	1483	33407	1836	2297	0.19	-2.00	-0.02	-0.00	0.00	-15.28	-7.35	-4.70	279	282	38
17	33609	1508	33526	1869	2295	0.14	-1.94	0.01	-0.00	0.00	-15.42	-5.42	-4.83	297	299	21
18	33703	1526	33648	1892	2293	0.09	-1.89	0.03	-0.00	0.00	-15.51	-3.52	-4.92	309	311	9
19	33799	1536	33771	1905	2291	0.05	-1.86	0.05	-0.00	0.00	-15.57	-1.66	-4.97	316	319	1
20	33895	1540	33895	1910	2290	0.02	-1.84	0.08	-0.00	0.00	-15.58	0.18	-4.97	318	320	-0
21	33991	1536	34019	1905	2288	-0.02	-1.84	0.10	0.00	0.00	-15.57	2.02	-4.93	313	316	4
22	34087	1526	34142	1892	2286	-0.05	-1.85	0.13	0.00	0.00	-15.51	3.86	-4.85	303	306	14
23	34181	1508	34264	1869	2284	-0.09	-1.87	0.15	0.00	0.00	-15.42	5.74	-4.72	288	291	29
24	34274	1483	34383	1836	2282	-0.14	-1.91	0.18	0.00	0.00	-15.29	7.65	-4.56	269	271	49
25	34365	1451	34500	1796	2280	-0.19	-1.96	0.21	0.00	0.00	-15.10	9.61	-4.36	247	249	71
26	34454	1413	34614	1746	2279	-0.25	-2.02	0.24	0.00	0.00	-14.85	11.63	-4.12	222	225	95
27	34539	1368	34723	1688	2277	-0.31	-2.08	0.27	0.00	0.00	-14.54	13.72	-3.85	197	200	120
28	34620	1317	34828	1622	2276	-0.39	-2.15	0.30	0.00	0.00	-14.15	15.86	-3.56	171	174	146
29	34698	1260	34928	1549	2274	-0.48	-2.21	0.33	0.00	0.00	-13.66	18.07	-3.25	146	149	171
30	34771	1197	35022	1468	2273	-0.59	-2.26	0.36	0.00	0.00	-13.08	20.33	-2.92	123	126	194
31	34839	1129	35110	1381	2272	-0.70	-2.30	0.39	0.00	0.00	-12.38	22.63	-2.57	101	105	215
32	34902	1056	35191	1287	2270	-0.83	-2.32	0.41	0.00	0.00	-11.55	24.95	-2.23	82	85	235
33	34959	97935264	1187	2269	-0.96	-2.32	0.43	0.00	0.00	0.00	-10.59	27.27	-1.89	64	68	252
34	35010	89735330	1083	2268	-1.11	-2.29	0.44	0.00	0.00	0.00	-9.48	29.56	-1.56	49	54	266
35	35055	81235388	9732266	-1.26	-2.23	0.45	0.00	0.00	0.00	0.00	-8.22	31.80	-1.25	36	41	279
36	35094	72435438	8602266	-1.42	-2.14	0.45	0.00	0.00	0.00	0.00	-6.80	33.94	-0.96	26	30	290
37	35126	63335479	7432265	-1.58	-2.01	0.44	0.00	0.00	0.00	0.00	-5.21	35.95	-0.70	17	22	298
38	35151	54035512	6232265	-1.75	-1.84	0.42	0.00	0.00	0.00	0.00	-3.47	37.79	-0.47	10	15	305
39	35169	44635535	5012264	-1.91	-1.63	0.39	0.00	0.00	0.00	0.00	-1.56	39.41	-0.27	4	10	310
40	35180	35035549	3782264	-2.07	-1.37	0.36	0.00	0.00	0.00	0.00	0.51	40.78	-0.12	-0	6	314

Segment Intraados.x Intraados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 70 [mm] Thickness at top: 6750 [mm]
Batter: 1:0

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 35180 41930 70 -324.66 4.61 -324.66 -11.86 38495 38542 -0.05 -0.05 3315.28 3388.34
1 35180 41930 -453 -77.71 4.61 -402.37 -9.45 38503 38560 -0.06 -0.06 3322.78 3369.73
2 35180 41930 -977 -77.71 4.61 -480.09 -7.03 38506 38575 -0.07 -0.07 3326.06 3355.36
3 35180 41930 -1500 -77.71 4.61 -557.80 -4.62 38507 38587 -0.08 -0.08 3326.88 3343.44

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular
Span: 2720 [mm] Rise: 1350 [mm] Q-rise: 1100 [mm]
Ring thickness at crown: 450 [mm] Ring thickness at springing: 450 [mm] Mortar loss: 50 [mm]
Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Intraados.x Intraados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
0 41930 70 41480 73 2132 0.00 0.00 0.00 0.00 0.00 0.00 5.12 -45.51 -0.15 0 6 394
1 41935 17641487 2152132 2.58 -1.47 -0.19 -0.00 0.00 0.00 0.00 2.54 -44.05 -0.46 7 14 386
2 41948 28241504 3552132 2.39 -1.82 -0.26 -0.00 0.00 0.00 0.00 0.16 -42.22 -0.79 16 22 378
3 41970 38641533 4942131 2.18 -2.12 -0.32 -0.00 0.00 0.00 0.00 -2.02 -40.10 -1.14 26 32 368

4 41999 48841572 6292129 1.97 -2.36-0.36-0.00 0.00 0.00 -3.99-37.74 -1.52 38 44 356
5 42036 58741622 7622128 1.76 -2.55-0.38-0.00 0.00 0.00 -5.75-35.19 -1.91 52 57 343
6 42081 68441682 8902126 1.55 -2.67-0.39-0.00 0.00 0.00 -7.30-32.52 -2.31 69 74 326
7 42134 77641751 1013 2124 1.35 -2.75-0.38-0.00 0.00 0.00 -8.65-29.77 -2.71 89 93 307
8 42193 86441830 1130 2122 1.15 -2.78-0.36-0.00 0.00 0.00 -9.80-26.99 -3.12 111 115 285
9 42259 94741918 1241 2119 0.97 -2.77-0.33-0.00 0.00 0.00 -10.77 -24.22 -3.52 137 140 260
10 42332 1025 42015 1345 2115 0.81 -2.73-0.30-0.00 0.00 0.00 -11.58 -21.49 -3.90 165 169 231
11 42410 1097 42119 1440 2112 0.66 -2.66-0.26-0.00 0.00 0.00 -12.24 -18.83 -4.26 196 199 201
12 42494 1163 42230 1527 2108 0.52 -2.56-0.22-0.00 0.00 0.00 -12.76 -16.27 -4.58 229 232 168
13 42582 1221 42348 1606 2104 0.41 -2.46-0.17-0.00 0.00 0.00 -13.17 -13.81 -4.87 263 266 134
14 42675 1273 42472 1675 2100 0.31 -2.35-0.13-0.00 0.00 0.00 -13.48 -11.46 -5.12 296 299 101
15 42772 1317 42600 1733 2096 0.23 -2.23-0.09-0.00 0.00 0.00 -13.71 -9.23 -5.33 328 330 70
16 42872 1354 42733 1782 2091 0.17 -2.13-0.05-0.00 0.00 0.00 -13.88 -7.11 -5.48 355 357 43
17 42974 1383 42869 1820 2086 0.11 -2.03-0.02-0.00 0.00 0.00 -13.99 -5.07 -5.59 377 379 21
18 43078 1403 43008 1848 2081 0.07 -1.95-0.02-0.00 0.00 0.00 -14.06 -3.12 -5.64 391 394 6
19 43184 1416 43149 1864 2075 0.04 -1.89-0.05-0.00 0.00 0.00 -14.10 -1.23 -5.65 398 400-0 ***
20 43290 1420 43290 1870 2070 0.01 -1.85-0.08-0.00 0.00 0.00 -14.11 0.62 -5.60 396 398 2
21 43396 1416 43431 1864 2064 -0.01 -1.84-0.11 0.00 0.00 0.00 -14.10 2.46 -5.51 385 387 13
22 43502 1403 43572 1848 2059 -0.04 -1.85-0.15 0.00 0.00 0.00 -14.06 4.31 -5.36 367 369 31
23 43606 1383 43711 1820 2053 -0.07 -1.88-0.18 0.00 0.00 0.00 -14.00 6.19 -5.18 343 345 55
24 43708 1354 43847 1782 2048 -0.10 -1.94-0.22 0.00 0.00 0.00 -13.90 8.13 -4.95 313 316 84
25 43808 1317 43980 1733 2042 -0.14 -2.01-0.26 0.00 0.00 0.00 -13.76 10.14-4.68 281 283 117
26 43905 1273 44108 1675 2036 -0.20 -2.10-0.30 0.00 0.00 0.00 -13.56 12.24-4.38 247 250 150
27 43998 1221 44232 1606 2031 -0.27 -2.19-0.35 0.00 0.00 0.00 -13.29 14.43-4.05 213 216 184
28 44086 1163 44350 1527 2026 -0.35 -2.29-0.39 0.00 0.00 0.00 -12.93 16.73-3.69 181 184 216
29 44170 1097 44461 1440 2022 -0.46 -2.39-0.44 0.00 0.00 0.00 -12.47 19.12-3.32 150 153 247
30 44248 1025 44565 1345 2018 -0.58 -2.48-0.49 0.00 0.00 0.00 -11.90 21.60-2.94 123 126 274
31 44321 94744662 1241 2014 -0.71 -2.55-0.53 0.00 0.00 0.00 -11.19 24.15-2.56 98 102 298
32 44387 86444750 1130 2010 -0.86 -2.60-0.57 0.00 0.00 0.00 -10.32 26.75-2.19 77 81 319
33 44446 77644829 1013 2006 -1.03 -2.62-0.60 0.00 0.00 0.00 -9.29 29.37-1.82 59 63 337
34 44499 68444898 8902004 -1.21 -2.60-0.62 0.00 0.00 0.00 -8.08 31.97-1.48 44 48 352
35 44544 58744958 7622002 -1.41 -2.54-0.63 0.00 0.00 0.00 -6.67 34.51-1.17 31 36 364
36 44581 48845008 629-1 -1.61 -2.43-0.63 0.00 0.00 0.00 -5.07 36.94-0.89 22 27 373
37 44610 38645047 494-1 -1.81 -2.27-0.61 0.00 0.00 0.00 -3.25 39.21-0.64 14 19 381
38 44632 28245076 355-1 -2.02 -2.06-0.58 0.00 0.00 0.00 -1.23 41.27-0.44 8 14 386
39 44645 17645093 215-1 -2.22 -1.78-0.53 0.00 0.00 0.00 0.99 43.05-0.27 3 9 391
40 44650 70 45100 73 -1 -2.42 -1.45-0.47 0.00 0.00 0.00 3.41 44.50-0.14-0 6 394

Meat - Viewing Purposes Only!

Beaumont Bridge

7 (44t 6-axle A*) impact axle 3 at 16790 mm
17.85 17.85 17.35 14.28



Lowerbound condition with backing present => 44t load capacity

gammaFI dead load: 1.00
gammaFI superimposed: 1.00
gammaFI live load: 2.38
gammaF3 load effect: 1.00
gammaM material: 1.00

File path: V:\521092017 Calcs\72 Model\Beaumont Bridge - UB w backing.brg

NAME: Beaumont Bridge
LOCATION: Beaumont, Meath
NUMBER: MH-L1615-001.00
ATKINS
DATE: 20 December 2021
Printed on: Wednesday, January 12, 2022 15:19:02

Bridge Name: Beaumont Bridge Bridge Location: Beaumont, Meath
 Bridge Number: MHL1615-001.00
 Number of spans: 7

SAFETY FACTORS

Factor for deadload: 1.00 Factor for superimposed deadload: 1.00 Factor for surfacing: 1.00
 Factor for live load: 2.38 Factor for load effect: 1.00 Factor for material strength: 1.00

APPLIED LOAD CASES

1.7 (44t 6-axle A*) impact axle 3 Total weight: 431.64 [kN] Position: 16790 [mm]
 44.00 6 1.00 6.00 2.80 5.00 4.10 18.90 8.80 7.50 10.15 7.50 11.50 7.50 1.00 1.80 2.50
 Effective lane width: 3350 [mm] Distribution length: 2400 [mm]

Applied distribution mode: Archie-M, BD21/97

Applied live load pressure: Active pressure

STRUCTURE PROPERTIES

Road shape: True shape (multi-point method)
 Road points: (-500, 1950) (1180, 2000) (5805, 2200) (11660, 2550) (19175, 2750) (29755, 2370) (33895, 2290) (43290, 2070) (45000, 2000)
 Depth of surfacing: 150 Depth of overlay: 0
 Surface unit weight: 23.00 [kN/m³] Overlay unit weight: 23.00 [kN/m³]
 Lane width: 0

Fill unit weight: 18.00 [kN/m³] Fill phi: 30 degree

Left abutment Base level: -1500 [mm] Height: 380 [mm] Width: 1000 [mm]

Right abutment Base level: -1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Right abutment Base level: -1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Shape: Circular

Span: 2360 [mm] Rise: 1170 [mm] Q-rise: 1050 [mm]

Ring thickness at crown: 210 [mm] Ring thickness at springing: 210 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment: Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust

0	0	380	-210	382	1958	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-7.26	-24.30	-2.22	89	93	97
1	4	472	-205	490	1958	0.00	-0.63	-0.08	0.00	-0.00	0.00	0.00	-7.26	-23.66	-1.56	63	66	124
2	16	563	-191	598	1959	0.00	-0.87	-0.12	0.00	-0.00	0.00	0.00	-7.26	-22.79	-1.03	42	45	145
3	35	654	-169	704	1959	0.00	-1.08	-0.15	0.00	-0.00	0.00	0.00	-7.26	-21.71	-0.62	26	29	161
4	60	742	-139	808	1960	0.00	-1.24	-0.17	0.00	-0.00	0.00	0.00	-7.26	-20.48	-0.33	14	17	173
5	93	828	-101	910	1961	0.00	-1.36	-0.18	0.00	-0.00	0.00	0.00	-7.26	-19.12	-0.14	5	8	182
6	132	912	-55	1008	1963	0.00	-1.44	-0.18	0.00	-0.00	0.00	0.00	-7.26	-17.68	-0.04	1	4	186
7	177	992	-1	1103	1964	0.00	-1.49	-0.18	0.00	-0.00	0.00	0.00	-7.26	-16.20	-0.02	0	3	187
8	229	1068	60	1193	1966	0.00	-1.50	-0.17	0.00	-0.00	0.00	0.00	-7.26	-14.70	-0.06	3	5	185
9	286	1141	127	1278	1968	0.00	-1.49	-0.15	0.00	-0.00	0.00	0.00	-7.26	-13.21	-0.15	9	11	179
10	349	1208	201	1357	1970	0.00	-1.46	-0.13	0.00	-0.00	0.00	0.00	-7.26	-11.75	-0.28	20	22	168
11	417	1270	281	1430	1972	0.00	-1.41	-0.11	0.00	-0.00	0.00	0.00	-7.26	-10.35	-0.42	34	36	154
12	490	1327	367	1497	1975	0.00	-1.34	-0.09	0.00	-0.00	0.00	0.00	-7.26	-9.01	-0.58	52	53	137
13	566	1378	457	1557	1977	0.00	-1.27	-0.06	0.00	-0.00	0.00	0.00	-7.26	-7.73	-0.75	72	74	116
14	647	1423	552	1610	1980	0.21	-1.21	-0.01	0.00	-0.00	0.00	0.00	-7.47	-6.52	-0.94	97	98	92
15	731	1461	651	1655	1983	0.16	-1.16	0.00	0.00	-0.00	0.00	0.00	-7.63	-5.37	-1.10	120	121	169
16	817	1493	753	1693	1987	0.12	-1.11	0.01	0.00	-0.00	0.00	0.00	-7.75	-4.26	-1.24	142	143	47
17	906	1518	857	1722	1990	0.09	-1.07	0.02	0.00	-0.00	0.00	0.00	-7.83	-3.19	-1.34	160	161	29
18	996	1536	964	1743	1993	0.06	-1.04	0.03	0.00	-0.00	0.00	0.00	-7.89	-2.15	-1.43	175	176	14
19	1088	1546	1072	1756	1996	0.03	-1.02	0.04	0.00	-0.00	0.00	0.00	-7.92	-1.13	-1.48	185	186	4
20	1180	1550	1180	1760	2000	0.01	-1.01	0.04	0.00	-0.00	0.00	0.00	-7.94	-0.11	-1.50	189	190	0
21	1272	1546	1288	1756	2003	-0.01	-1.02	0.05	-0.00	-0.00	0.00	0.00	-7.92	0.91	-1.50	187	189	1

22	1364	1536	1396	1743	2006	-0.03	-1.04	0.06	-0.00	-0.00	0.00	0.00	-7.89	1.95	-1.47	1801828
23	1454	1518	1503	1722	2010	-0.06	-1.07	0.07	-0.00	-0.00	0.00	0.00	-7.83	3.02	-1.40	16816921
24	1543	1493	1607	1693	2014	-0.09	-1.11	0.08	-0.00	-0.00	0.00	0.00	-7.74	4.13	-1.31	15115238
25	1629	1461	1709	1655	2017	-0.13	-1.17	0.09	-0.00	-0.00	0.00	0.00	-7.61	5.30	-1.18	13013159
26	1713	1423	1808	1610	2020	-0.17	-1.22	0.11	-0.00	-0.00	0.00	0.00	-7.44	6.52	-1.02	10610783
27	1794	1378	1903	1557	2024	-0.23	-1.28	0.12	-0.00	-0.00	0.00	0.00	-7.21	7.80	-0.83	81 108
28	1870	1327	1993	1497	2027	0.00	-1.35	0.17	0.00	-0.00	0.00	0.00	-7.21	9.15	-0.66	58 60 130
29	1943	1270	2079	1430	2030	0.00	-1.43	0.20	0.00	-0.00	0.00	0.00	-7.21	10.58	-0.50	39 41 149
30	2011	1208	2159	1357	2033	0.00	-1.49	0.22	0.00	-0.00	0.00	0.00	-7.21	12.07	-0.34	24 26 164
31	2074	1141	2233	1278	2036	0.00	-1.54	0.24	0.00	-0.00	0.00	0.00	-7.21	13.62	-0.20	12 14 176
32	2131	1068	2300	1193	2038	0.00	-1.58	0.25	0.00	-0.00	0.00	0.00	-7.21	15.19	-0.09	4 7 183
33	2183	9922361	1103	2041	0.00	-1.58	0.26	0.00	-0.00	0.00	0.00	0.00	-7.21	16.77	-0.03	0 3 187
34	2228	9122415	1008	2043	0.00	-1.56	0.26	0.00	-0.00	0.00	0.00	0.00	-7.21	18.33	-0.03	-0 3 187
35	2267	8282461	9102044	0.00	-1.51	0.25	0.00	-0.00	0.00	0.00	0.00	0.00	-7.21	19.84	-0.10	3 6 184
36	2300	7422499	8082046	0.00	-1.41	0.24	0.00	-0.00	0.00	0.00	0.00	0.00	-7.21	21.25	-0.27	11 14 176
37	2325	6542529	7042047	0.00	-1.28	0.21	0.00	-0.00	0.00	0.00	0.00	0.00	-7.21	22.54	-0.55	22 25 165
38	2344	5632551	5982048	0.00	-1.11	0.18	0.00	-0.00	0.00	0.00	0.00	0.00	-7.21	23.65	-0.94	37 40 150
39	2356	4722565	4902048	0.00	-0.90	0.14	0.00	-0.00	0.00	0.00	0.00	0.00	-7.21	24.54	-1.46	56 60 130
40	2360	3802570	3822048	0.00	-0.64	0.08	0.00	-0.00	0.00	0.00	0.00	0.00	-7.21	25.18	-2.11	82 85 105

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 380 [mm] Thickness at top: 2000 [mm]
Batter: 1:0
Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 2360 4360 380 -161.91 -40.20 -161.91 36.533574 3597 -0.03 -0.14 1214.05 762.82
1 2360 4360 -247 -27.57 -40.20 -189.48 11.333406 3433 -0.08 -0.11 1046.28 926.65
2 2360 4360 -873 -27.57 -40.20 -217.05 -13.86 3281 3312 -0.13 -0.09 920.64 1048.35
3 2360 4360 -1500 -27.57 -40.20 -244.63 -39.05 3183 3218 -0.18 -0.06 822.88 1142.18

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular
Span: 2890 [mm] Rise: 1280 [mm] Q-rise: 1020 [mm]
Ring thickness at crown: 222 [mm] Ring thickness at springing: 222 [mm] Mortar loss: 20 [mm]
Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
0 4360 4004140 4272115 0.00 0.00 0.00 0.00 0.00 0.00 -47.43 -77.46 -15.83 1861984
1 4377 5044159 5472116 0.00 -1.22 -0.18 0.00 -0.00 0.00 -47.43 -76.25 -11.92 13614854
2 4401 6074186 6652118 0.00 -1.45 -0.22 0.00 -0.00 0.00 -47.43 -74.80 -8.58 95 10795
3 4432 7084223 7812119 0.00 -1.63 -0.24 0.00 -0.00 0.00 -47.43 -73.17 -5.82 63 75 127
4 4471 8064267 8952121 0.00 -1.76 -0.25 0.00 -0.00 0.00 -47.43 -71.41 -3.64 37 49 153
5 4516 9014320 1004 2124 0.00 -1.86 -0.25 0.00 -0.00 0.00 -47.43 -69.55 -2.04 18 30 172
6 4569 9934380 1110 2126 0.00 -1.91 -0.24 0.00 -0.00 0.00 -47.43 -67.64 -0.98 6 18 184
7 4627 1080 4448 1211 2130 0.00 -1.93 -0.23 0.00 -0.00 0.00 -47.43 -65.71 -0.47 -0 12 190
8 4693 1163 4523 1306 2133 0.00 -1.92 -0.20 0.00 -0.00 0.00 -47.43 -63.79 -0.48 0 12 190
9 4763 1241 4605 1396 2137 0.00 -1.88 -0.18 0.00 -0.00 0.00 -47.43 -61.92 -1.00 7 18 184
10 4840 1314 4693 1480 2142 0.00 -1.82 -0.15 0.00 -0.00 0.00 -47.43 -60.10 -2.00 21 32 170
11 4921 1381 4786 1557 2146 0.00 -1.74 -0.12 0.00 -0.02 -0.00 0.00 -47.43 -58.34 -3.47 42 53 149
12 5007 1442 4886 1628 2151 0.00 -1.66 -0.09 0.00 -0.73 -0.04 0.00 -47.43 -55.95 -5.29 70 80 122
13 5098 1497 4990 1691 2156 0.00 -1.57 -0.07 0.00 -2.85 -0.14 0.00 -47.43 -51.54 -7.17 10311389
14 5192 1544 5098 1746 2162 0.24 -1.50 0.00 1.02 -5.98 -0.02 0.00 -48.69 -44.06 -8.98 13914854
15 5289 1585 5210 1793 2168 0.19 -1.44 0.01 1.27 -9.08 0.02 0.00 -50.15 -33.55 -10.24 17017824
16 5389 1619 5325 1832 2174 0.14 -1.38 0.02 1.22 -10.84 0.11 0.00 -51.51 -21.33 -10.77 1901984
17 5491 1646 5443 1862 2180 0.10 -1.34 0.03 0.89 -10.33 0.18 0.00 -52.51 -9.66 -10.57 194202-0 ***
18 5595 1665 5563 1884 2186 0.07 -1.31 0.04 0.47 -7.63 0.18 0.00 -53.04 -0.72 -9.85 18419111

19	5700	1676	5683	1898	2192	0.04	-1.29	0.05	0.14	-3.89	0.11	0.00	-53.22	4.47	-8.93	16517329
20	5805	1680	5805	1902	2199	0.01	-1.29	0.06	0.01	-0.92	0.02	0.00	-53.25	6.68	-8.10	14815646
21	5910	1676	5927	1898	2206	-0.01	-1.31	0.07	-0.00	-0.01	0.00	0.00	-53.23	8.00	-7.52	13614458
22	6015	1665	6047	1884	2213	-0.04	-1.34	0.09	-0.01	-0.28	0.03	0.00	-53.18	9.62	-7.23	13013864
23	6119	1646	6167	1862	2219	-0.08	-1.38	0.10	-0.09	-1.49	0.13	0.00	-53.01	12.49	-7.17	12813666
24	6221	1619	6285	1832	2227	-0.11	-1.44	0.11	-0.29	-3.36	0.31	0.00	-52.61	17.29	-7.22	12613468
25	6321	1585	6400	1793	2233	-0.16	-1.51	0.13	-0.61	-5.39	0.54	0.00	-51.84	24.18	-7.21	12213171
26	6418	1544	6512	1746	2240	-0.22	-1.58	0.15	-0.99	-7.02	0.75	0.00	-50.64	32.78	-6.98	11312181
27	6512	1497	6620	1691	2246	-0.28	-1.66	0.17	-1.34	-7.91	0.90	0.00	-49.01	42.35	-6.39	96 10597
28	6603	1442	6724	1628	2252	0.00	-1.75	0.24	0.00	-7.94	1.19	0.00	-49.01	52.04	-5.77	78 88 114
29	6689	1381	6824	1557	2258	0.00	-1.85	0.27	0.00	-7.24	1.16	0.00	-49.01	61.13	-4.89	59 70 132
30	6770	1314	6917	1480	2263	0.00	-1.94	0.30	0.00	-6.08	1.02	0.00	-49.01	69.15	-3.83	41 52 150
31	6847	1241	7005	1396	2269	0.00	-2.02	0.33	0.00	-4.76	0.84	0.00	-49.01	75.93	-2.73	25 37 165
32	6917	1163	7087	1306	2274	0.00	-2.08	0.35	0.00	-3.53	0.65	0.00	-49.01	81.54	-1.75	12 25 177
33	6983	1080	7162	1211	2278	0.00	-2.11	0.37	0.00	-2.54	0.48	0.00	-49.01	86.19	-1.04	4 18 184
34	7041	9937230	1110	2282	0.00	-2.11	0.38	0.00	-1.83	0.36	0.00	-49.01	90.13	-0.75	-0 15 187	
35	7094	9017290	1004	2285	0.00	-2.08	0.38	0.00	-1.37	0.28	0.00	-49.01	93.59	-0.98	2 17 185	
36	7139	8067343	8952289	0.00	-2.01	0.37	0.00	-1.10	0.23	0.00	-49.01	96.71	-1.83	9 25 177		
37	7178	7087387	7812291	0.00	-1.90	0.35	0.00	-0.94	0.19	0.00	-49.01	99.55	-3.36	23 38 164		
38	7209	6077424	6652294	0.00	-1.74	0.32	0.00	-0.79	0.16	0.00	-49.01	102.08	-5.60	42 58 144		
39	7233	5047451	5472295	0.00	-1.54	0.27	0.00	-0.62	0.13	0.00	-49.01	104.24	-8.56	69 85 117		
40	7250	4007470	4272296	0.00	-1.28	0.22	0.00	-0.44	0.09	0.00	-49.01	105.95	-12.28	10311884		

Segment: Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 100 [mm] Thickness at top: 2300 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment	Left	xRight	x z	Weight	Fx	Fz	My	Thrust left	Thrust right	Stress left	Stress right	Dist. left	Dist. right
0	7250	9550	100	-326.18	-67.78	-326.18	-160.84	7884	7930	-0.32	0.04	633.59	1619.82
1	7250	9550	-433	-26.99	-67.78	-353.17	-197.00	7817	7867	-0.38	0.07	566.98	1682.57
2	7250	9550	-967	-26.99	-67.78	-380.15	-233.15	7760	7814	-0.43	0.10	509.55	1736.14
3	7250	9550	-1500	-26.99	-67.78	-407.14	-269.30	7709	7768	-0.48	0.13	459.48	1782.36

Segment: Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 4220 [mm] Rise: 1930 [mm] Q-rise: 1560 [mm]

Ring thickness at crown: 252 [mm] Ring thickness at springing: 252 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment	Intrados.x	Intrados.z	Extrados.x	Extrados.z	Road.z	Fx dead	Fz dead	My dead	Fx live	Fz live	My live	Fx passive	Fx total	Fz total	My total	Thrust in	Thrust out	Extra-Thrust	
0	9550	1009299	12224	10.00	0.00	0.00	0.00	0.00	-113.51	-71.13	-160.03	1971	1983	-1751	***				
1	9570	2569321	29724	11.00	-1.97	-0.34	0.00	-0.17	-0.04	0.00	-113.51	-68.99	-143.19	1649	1661	-1429	***		
2	9601	4099356	46924	14.00	-2.45	-0.43	0.00	-0.25	-0.05	0.00	-113.51	-66.29	-127.18	1389	1403	-1171	***		
3	9643	5609404	63824	16.00	-2.83	-0.48	0.00	-0.31	-0.06	0.00	-113.51	-63.15	-112.04	1174	1188	-956	***		
4	9697	7089463	80324	20.00	-3.11	-0.51	0.00	-0.34	-0.06	0.00	-113.51	-59.70	-97.80	991	1005	-773	***		
5	9761	8519535	96324	25.00	-3.30	-0.51	0.00	-0.33	-0.06	0.00	-113.51	-56.07	-84.48	833	847	-615	***		
6	9836	9899619	1117	2430	0.00	-3.40	-0.48	0.00	-0.30	-0.05	0.00	-113.51	-52.37	-72.09	694	708	-476	***	
7	9921	1121	9714	1265	2436	0.00	-3.43	-0.44	0.00	-0.23	-0.04	0.00	-113.51	-48.70	-60.64	571	586	-354	***
8	10015	1247	9819	1405	2442	0.00	-3.39	-0.39	0.00	-0.16	-0.02	0.00	-113.51	-45.16	-50.15	463	478	-246	***
9	10118	1365	9935	1537	2449	0.00	-3.29	-0.33	0.00	-0.08	-0.01	0.00	-113.51	-41.79	-40.63	368	383	-151	***
10	10230	1475	10060	1661	2457	0.00	-3.15	-0.27	0.00	-0.02	-0.00	0.00	-113.51	-38.61	-32.10	284	300	-68	***
11	10350	1576	10194	1774	2465	0.00	-2.98	-0.21	0.00	-0.00	-0.00	0.00	-113.51	-35.63	-24.56	213	229		***
12	10477	1669	10336	1878	2474	0.00	-2.79	-0.15	0.00	-0.00	0.00	0.00	-113.51	-32.85	-18.02	152	168		***
13	10610	1751	10485	1970	2482	0.00	-2.58	-0.10	0.00	-0.00	0.00	0.00	-113.51	-30.26	-12.51	102	118		***
14	10749	1824	10641	2052	2492	0.38	-2.39	0.04	0.00	-0.00	0.00	0.00	-113.90	-27.87	-8.12	62	79	153	
15	10893	1886	10802	2121	2501	0.28	-2.23	0.06	0.00	-0.00	0.00	0.00	-114.18	-25.64	-4.74	33	49	183	

16	11041	1938	10968	2179	2511	0.21	-2.11	0.08	0.00	-0.00	0.00	0.00	-114.39	-23.53	-2.41	12	29	203
17	11193	1978	11137	2254	2521	0.14	-2.01	0.09	0.00	-0.00	0.00	0.00	-114.53	-21.53	-1.14	2	18	214
18	11347	2007	11310	2256	2530	0.10	-1.94	0.11	0.00	-0.00	0.00	0.00	-114.63	-19.59	-0.96	-0	17	215
19	11503	2024	11485	2275	2540	0.05	-1.90	0.12	0.00	-0.00	0.00	0.00	-114.68	-17.69	-1.85	8	24	208
20	11660	2030	11660	2282	2549	0.02	-1.89	0.14	0.00	-0.00	0.00	0.00	-114.70	-15.80	-3.82	25	41	191
21	11817	2027	11835	2275	2559	-0.02	-1.92	0.16	0.00	-0.00	0.00	0.00	-114.68	-13.88	-6.85	52	69	163
22	11973	2007	12010	2256	2568	-0.06	-1.99	0.18	0.00	-0.05	0.01	0.00	-114.62	-11.84	-10.92	90	106	126
23	12127	1978	12183	2224	2577	-0.11	-2.08	0.21	-0.17	-2.78	0.39	0.00	-114.34	-6.97	-15.94	137	153	79
24	12279	1938	12352	2179	2586	-0.17	-2.21	0.24	-1.04	-11.73	1.55	0.00	-113.13	6.97	-21.26	185	201	131
25	12427	1886	12518	2121	2594	-0.25	-2.36	0.28	-2.57	-22.28	3.00	0.00	-110.31	31.60	-25.53	215	232	20
26	12571	1824	12679	2052	2602	-0.35	-2.53	0.32	-4.15	-28.82	4.05	0.00	-105.81	62.95	-27.38	215	232	20
27	12710	1751	12835	1970	2609	-0.47	-2.72	0.36	-4.98	-28.60	4.20	0.00	-100.36	94.28	-26.08	185	204	28
28	12843	1669	12984	1878	2617	0.00	-2.95	0.51	0.00	-22.57	4.19	0.00	-100.36	119.79	-23.05	143	164	68
29	12970	1576	13126	1774	2623	0.00	-3.17	0.58	0.00	-14.08	2.73	0.00	-100.36	137.05	-18.18	99	123	109
30	13090	1475	13260	1661	2629	0.00	-3.38	0.65	0.00	-6.70	1.35	0.00	-100.36	147.13	-12.70	61	86	146
31	13202	1365	13385	1537	2635	0.00	-3.56	0.72	0.00	-2.52	0.53	0.00	-100.36	153.20	-7.82	30	56	176
32	13305	1247	13501	1405	2640	0.00	-3.69	0.77	0.00	-1.57	0.36	0.00	-100.36	158.46	-4.38	10	37	195
33	13399	1121	13606	1265	2645	0.00	-3.78	0.81	0.00	-1.51	0.35	0.00	-100.36	163.75	-2.65	0	28	204
34	13484	989	13701	1117	2648	0.00	-3.79	0.82	0.00	-1.42	0.34	0.00	-100.36	168.96	-2.74	-0	28	204
35	13559	851	13785	963	2651	0.00	-3.74	0.82	0.00	-1.28	0.31	0.00	-100.36	173.98	-4.72	9	38	194
36	13623	708	13857	803	2654	0.00	-3.60	0.79	0.00	-1.12	0.27	0.00	-100.36	178.70	-8.68	28	57	175
37	13677	560	13916	638	2657	0.00	-3.37	0.74	0.00	-0.94	0.23	0.00	-100.36	183.02	-14.69	57	86	146
38	13719	409	13964	469	2659	0.00	-3.04	0.65	0.00	-0.75	0.18	0.00	-100.36	186.81	-22.82	97	126	106
39	13750	256	13999	297	2660	0.00	-2.61	0.54	0.00	-0.55	0.13	0.00	-100.36	189.97	-33.09	148	177	55
40	13770	100	14021	122	2661	0.00	-2.07	0.40	0.00	-0.35	0.08	0.00	-100.36	192.39	-45.51	213	241	9

Segment Intraados.x Intraados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust

Base level: -1500 [mm] Top level: 100 [mm] Thickness at top: 3150 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 13770 16920 100-482.04 79.13-482.04 -121.1115059 15128 -0.23-0.08 1289.32 1791.82
1 13770 16920 -433 -36.96 79.13-519.00 -78.91 15156 15230 -0.21-0.12 1385.89 1689.97
2 13770 16920 -967 -36.96 79.13-555.96 -36.71 15239 15319 -0.20-0.15 1469.27 1601.31
3 13770 16920 -1500 -36.96 79.13-592.92 5.50 15312 15397 -0.18-0.19 1541.92 1523.38

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 4510 [mm] Rise: 2010 [mm] Q-rise: 1660 [mm]

Ring thickness at crown: 264 [mm] Ring thickness at springing: 264 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Intraados.x Intraados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust

0	16920	2001	16658	2302	2738	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-22.02	-84.63	-5.02	52	64	180
1	16945	363	16686	4132	2738	0.00	-2.45	-0.45	0.00	-0.61	-0.14	0.00	-22.02	-81.56	-2.85	28	40	204
2	16982	524	16726	5922	2739	0.00	-2.97	-0.54	0.00	-0.90	-0.20	0.00	-22.02	-77.69	-1.40	12	23	221
3	17030	682	16780	7692	2740	0.00	-3.38	-0.60	0.00	-1.19	-0.25	0.00	-22.02	-73.11	-0.61	3	13	231
4	17090	836	16847	9412	2741	0.00	-3.69	-0.63	0.00	-1.47	-0.29	0.00	-22.02	-67.95	-0.36	-0	10	234
5	17160	986	16926	1107	2742	0.00	-3.89	-0.62	0.00	-1.74	-0.32	0.00	-22.02	-62.32	-0.55	4	13	231
6	17242	1130	17017	1268	2743	0.00	-4.00	-0.59	0.00	-1.97	-0.34	0.00	-22.02	-56.36	-1.06	14	22	222
7	17333	1267	17119	1421	2745	0.00	-4.02	-0.54	0.00	-2.15	-0.34	0.00	-22.02	-50.19	-1.77	29	37	207
8	17435	1397	17232	1567	2746	0.00	-3.97	-0.48	0.00	-2.26	-0.32	0.00	-22.02	-43.96	-2.57	50	57	187
9	17545	1520	17356	1704	2748	0.00	-3.86	-0.41	0.00	-2.28	-0.29	0.00	-22.02	-37.82	-3.37	76	82	162
10	17665	1635	17489	1832	2749	0.00	-3.70	-0.33	0.00	-2.20	-0.24	0.00	-22.02	-31.92	-4.10	106	112	132
11	17792	1740	17631	1949	2750	0.00	-3.50	-0.25	0.00	-2.02	-0.19	0.00	-22.02	-26.40	-4.71	138	143	101
12	17926	1836	17781	2056	2750	0.00	-3.27	-0.18	0.00	-1.74	-0.13	0.00	-22.02	-21.38	-5.17	169	174	70

13	18068	1922	17939	2152	2751	0.00	-3.02	-0.11	0.00	-1.38	-0.08	0.00	-22.02	-16.98	-5.48	19720143
14	18215	1997	18103	2236	2752	0.45	-2.79	0.06	0.17	-0.99	-0.00	0.00	-22.64	-13.21	-5.78	22022321
15	18367	2061	18273	2308	2753	0.34	-2.61	0.08	0.08	-0.60	0.00	0.00	-23.06	-10.00	-5.90	23323377
16	18523	2114	18447	2367	2753	0.24	-2.45	0.10	0.03	-0.27	0.00	0.00	-23.33	-7.28	-5.90	2402431
17	18683	2156	18626	2414	2752	0.17	-2.31	0.11	0.01	-0.06	0.00	0.00	-23.51	-4.91	-5.82	241244-0 ***
18	18846	2186	18807	2447	2752	0.11	-2.20	0.13	0.00	-0.00	-0.00	0.00	-23.62	-2.71	-5.68	2372413
19	19010	2204	18991	2467	2751	0.06	-2.12	0.15	-0.00	0.00	0.00	0.00	-23.68	-0.59	-5.49	23023410
20	19175	2210	19175	2474	2750	0.02	-2.08	0.16	-0.00	0.00	0.00	0.00	-23.70	1.50	-5.26	22022420
21	19340	2204	19359	2467	2748	-0.02	-2.08	0.18	0.00	0.00	0.00	0.00	-23.68	3.57	-4.99	20721133
22	19504	2186	19543	2447	2745	-0.06	-2.11	0.20	0.00	0.00	0.00	0.00	-23.62	5.68	-4.68	19219549
23	19667	2156	19724	2414	2743	-0.11	-2.18	0.23	0.00	0.00	0.00	0.00	-23.51	7.85	-4.34	17417866
24	19827	2114	19903	2367	2740	-0.16	-2.28	0.26	0.00	0.00	0.00	0.00	-23.35	10.13	-3.95	15415886
25	19983	2061	20077	2308	2737	-0.24	-2.41	0.30	0.00	0.00	0.00	0.00	-23.11	12.54	-3.50	133136108
26	20135	1997	20247	2236	2734	-0.33	-2.56	0.34	0.00	0.00	0.00	0.00	-22.78	15.10	-3.00	109113131
27	20282	1922	20411	2152	2730	-0.44	-2.73	0.38	0.00	0.00	0.00	0.00	-22.35	17.82	-2.43	88 156
28	20424	1836	20569	2056	2727	0.00	-2.95	0.53	0.00	0.00	0.00	0.00	-22.35	20.78	-1.94	62 67 177
29	20558	1740	20719	1949	2724	0.00	-3.21	0.61	0.00	0.00	0.00	0.00	-22.35	23.98	-1.45	43 47 197
30	20685	1635	20861	1832	2720	0.00	-3.43	0.69	0.00	0.00	0.00	0.00	-22.35	27.41	-1.00	26 31 213
31	20805	1520	20994	1704	2716	0.00	-3.63	0.76	0.00	0.00	0.00	0.00	-22.35	31.04	-0.60	13 19 225
32	20915	1397	21118	1567	2713	0.00	-3.79	0.82	0.00	0.00	0.00	0.00	-22.35	34.83	-0.30	4 10 234
33	21017	1267	21231	1421	2709	0.00	-3.90	0.87	0.00	0.00	0.00	0.00	-22.35	38.73	-0.14	-0 6 238
34	21108	1130	21333	1268	2707	0.00	-3.96	0.90	0.00	0.00	0.00	0.00	-22.35	42.69	-0.19	1 7 237
35	21190	98621424	1107	2704	0.00	-3.94	0.90	0.00	0.00	0.00	0.00	0.00	-22.35	46.62	-0.50	6 13 231
36	21260	83621503	9412702	0.00	-3.83	0.88	0.00	0.00	0.00	0.00	0.00	0.00	-22.35	50.46	-1.15	17 25 219
37	21320	68221570	7692700	0.00	-3.64	0.83	0.00	0.00	0.00	0.00	0.00	0.00	-22.35	54.10	-2.20	34 42 202
38	21368	52421624	5922698	0.00	-3.34	0.76	0.00	0.00	0.00	0.00	0.00	0.00	-22.35	57.44	-3.72	56 65 179
39	21405	36321664	4132697	0.00	-2.94	0.65	0.00	0.00	0.00	0.00	0.00	0.00	-22.35	60.39	-5.76	86 95 149
40	21430	20021692	2302696	0.00	-2.43	0.51	0.00	0.00	0.00	0.00	0.00	0.00	-22.35	62.82	-8.38	124134110

Segment: Intraados.x Intraados.x Extrados.x Extrados.x Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 Base level: -1500 [mm] Top level: 200 [mm] Thickness at top: 7170 [mm]

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment: Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 0 21430 28600 200-431.51 11.84-431.51 -126.17 24692 24753 -0.07 -0.05 3261.78 3846.57
 1 21430 28600 -367 -89.39 11.84-520.90 -119.4624748 24823 -0.09 -0.06 3318.46 3777.13
 2 21430 28600 -933 -89.39 11.84-610.28 -112.7524787 24874 -0.10 -0.07 3356.66 3726.16
 3 21430 28600 -1500 -89.39 11.84-699.67 -106.04 24813 24913 -0.11 -0.09 3383.47 3686.58

Segment: Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 Shape: Circular
 Span: 2310 [mm] Rise: 1150 [mm] Q-rise: 960 [mm]
 Ring thickness at crown: 222 [mm] Ring thickness at springing: 222 [mm] Mortar loss: 20 [mm]
 Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment: Intraados.x Intraados.x Extrados.x Extrados.x Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 0 28600 45028378 4512417 0.00 0.00 0.00 0.00 0.00 -10.50 -32.96 -3.20 95 99 103
 1 28604 54028383 5592417 0.00 -0.67 -0.09 0.00 0.00 0.00 -10.50 -32.29 -2.27 66 71 131
 2 28615 63028396 6662416 0.00 -0.97 -0.15 0.00 0.00 0.00 -10.50 -31.32 -1.52 44 49 153
 3 28633 71928417 7712415 0.00 -1.23 -0.19 0.00 0.00 0.00 -10.50 -30.09 -0.93 27 32 170
 4 28658 80628447 8752414 0.00 -1.45 -0.22 0.00 0.00 0.00 -10.50 -28.64 -0.50 14 19 183
 5 28689 89028485 9762413 0.00 -1.62 -0.24 0.00 0.00 0.00 -10.50 -27.02 -0.22 6 10 192
 6 28727 97228530 10742411 0.00 -1.76 -0.25 0.00 0.00 0.00 -10.50 -25.26 -0.08 1 5 197
 7 28772 105128583 11682409 0.00 -1.85 -0.25 0.00 0.00 0.00 -10.50 -23.41 -0.05 -0 4 198
 8 28822 112628643 12572407 0.00 -1.92 -0.24 0.00 0.00 0.00 -10.50 -21.49 -0.11 3 6 196
 9 28879 119728710 13422404 0.00 -1.95 -0.22 0.00 0.00 0.00 -10.50 -19.55 -0.25 10 13 189

10	28940	1263	28783	1421	2402	0.00	-1.95	-0.20	0.00	0.00	0.00	0.00	0.00	-10.50	-17.59	-0.45	21	24	178
11	29007	1325	28863	1494	2399	0.00	-1.94	-0.17	0.00	0.00	0.00	0.00	0.00	-10.50	-15.66	-0.68	36	39	163
12	29078	1381	28948	1560	2396	0.00	-1.90	-0.14	0.00	0.00	0.00	0.00	0.00	-10.50	-13.76	-0.93	55	58	144
13	29153	1431	29037	1620	2392	0.00	-1.86	-0.11	0.00	0.00	0.00	0.00	0.00	-10.50	-11.90	-1.20	78	80	122
14	29232	1475	29131	1673	2389	0.37	-1.82	-0.01	-0.00	0.00	0.00	0.00	0.00	-10.87	-10.08	-1.51	105	107	95
15	29314	1513	29229	1718	2386	0.30	-1.78	0.00	-0.00	0.00	0.00	0.00	0.00	-11.17	-8.31	-1.77	130	132	70
16	29399	1544	29331	1755	2383	0.23	-1.74	0.01	-0.00	0.00	0.00	0.00	0.00	-11.40	-6.57	-1.99	154	156	46
17	29486	1568	29434	1784	2379	0.17	-1.70	0.03	-0.00	0.00	0.00	0.00	0.00	-11.57	-4.86	-2.16	174	176	26
18	29575	1586	29540	1805	2376	0.12	-1.67	0.04	-0.00	0.00	0.00	0.00	0.00	-11.69	-3.19	-2.28	189	190	12
19	29665	1596	29647	1818	2372	0.07	-1.65	0.05	-0.00	0.00	0.00	0.00	0.00	-11.76	-1.54	-2.35	198	200	2
20	29755	1600	29755	1822	2369	0.02	-1.63	0.07	-0.00	0.00	0.00	0.00	0.00	-11.78	0.09	-2.37	200	202	-0
21	29845	1596	29863	1818	2367	-0.02	-1.63	0.08	0.00	0.00	0.00	0.00	0.00	-11.76	1.72	-2.34	196	198	4
22	29935	1586	29970	1805	2363	-0.07	-1.63	0.09	0.00	0.00	0.00	0.00	0.00	-11.69	3.35	-2.25	186	187	15
23	30024	1568	30076	1784	2360	-0.11	-1.64	0.11	0.00	0.00	0.00	0.00	0.00	-11.58	4.99	-2.12	169	171	31
24	30111	1544	30179	1755	2358	-0.17	-1.66	0.12	0.00	0.00	0.00	0.00	0.00	-11.41	6.66	-1.93	149	151	51
25	30196	1513	30281	1718	2355	-0.22	-1.69	0.14	0.00	0.00	0.00	0.00	0.00	-11.19	8.35	-1.71	125	127	75
26	30278	1475	30379	1673	2353	-0.28	-1.72	0.15	0.00	0.00	0.00	0.00	0.00	-10.91	10.06	-1.44	100	102	100
27	30357	1431	30473	1620	2351	-0.35	-1.75	0.17	0.00	0.00	0.00	0.00	0.00	-10.55	11.81	-1.13	73	75	127
28	30432	1381	30562	1560	2348	0.00	-1.78	0.24	0.00	0.00	0.00	0.00	0.00	-10.55	13.60	-0.87	51	54	148
29	30503	1325	30647	1494	2346	0.00	-1.82	0.27	0.00	0.00	0.00	0.00	0.00	-10.55	15.42	-0.62	33	36	166
30	30570	1263	30727	1421	2344	0.00	-1.86	0.29	0.00	0.00	0.00	0.00	0.00	-10.55	17.28	-0.40	19	22	180
31	30631	1197	30800	1342	2343	0.00	-1.87	0.31	0.00	0.00	0.00	0.00	0.00	-10.55	19.15	-0.21	9	12	190
32	30688	1126	30867	1257	2341	0.00	-1.87	0.32	0.00	0.00	0.00	0.00	0.00	-10.55	21.02	-0.09	2	6	196
33	30738	1051	30927	1168	2340	0.00	-1.84	0.32	0.00	0.00	0.00	0.00	0.00	-10.55	22.87	-0.04	-0	4	198
34	30783	9723	30980	1074	2339	0.00	-1.79	0.32	0.00	0.00	0.00	0.00	0.00	-10.55	24.65	-0.09	2	5	197
35	30821	8903	31025	9762	2338	0.00	-1.70	0.31	0.00	0.00	0.00	0.00	0.00	-10.55	26.35	-0.26	7	11	191
36	30852	8063	31063	8752	2337	0.00	-1.57	0.28	0.00	0.00	0.00	0.00	0.00	-10.55	27.92	-0.55	16	21	181
37	30877	7193	31093	7712	2336	0.00	-1.41	0.25	0.00	0.00	0.00	0.00	0.00	-10.55	29.33	-0.99	30	34	168
38	30895	6303	31114	6662	2336	0.00	-1.20	0.21	0.00	0.00	0.00	0.00	0.00	-10.55	30.53	-1.59	48	52	150
39	30906	5403	31127	5592	2335	0.00	-0.95	0.15	0.00	0.00	0.00	0.00	0.00	-10.55	31.48	-2.36	71	76	126
40	30910	4503	31132	4512	2335	0.00	-0.66	0.09	0.00	0.00	0.00	0.00	0.00	-10.55	32.14	-3.29	100	105	97

Segment Intraados.x Intraados.x Extrados.x Extrados.x Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust

Base level: -1500 [mm] Top level: 350 [mm] Thickness at top: 1700 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment	Left x	Right x	z	Weight	Fx	Fz	My	Thrust left	Thrust right	Stress left	Stress right	Dist. left	Dist. right
0	30910	32610	350-120.08	-1.47	-120.08	3.94	31784	31801	-0.06	-0.08	874.23	808.61	
1	30910	32610	-267	-23.06	-1.47	-143.15	3.03	31771	31791	-0.08	-0.09	860.96	818.59
2	30910	32610	-883	-23.06	-1.47	-166.21	2.12	31761	31785	-0.09	-0.10	850.91	825.35
3	30910	32610	-1500	-23.06	-1.47	-189.27	1.22	31753	31780	-0.11	-0.11	842.91	830.06

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 2570 [mm] Rise: 1190 [mm] Q-rise: 1030 [mm]

Ring thickness at crown: 222 [mm] Ring thickness at springing: 222 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment	Intraados.x	Intraados.x	Extrados.x	Extrados.x	Road.z	Fx dead	Fz dead	My dead	Fx live	Fz live	My live	Fx passive	Fx total	Fz total	My total	Thrust in	Thrust out	Extra-Thrust
0	32610	3503	2389	3672	312	0.00	0.00	0.00	0.00	0.00	0.00	-12.02	-35.69	-3.01	80	85	117	
1	32621	4463	2401	4792	312	0.00	0.00	0.00	0.00	0.00	0.00	-12.02	-34.68	-2.07	55	60	142	
2	32639	5403	2423	5902	312	0.00	-1.29	-0.20	0.00	0.00	0.00	-12.02	-33.39	-1.33	35	40	162	
3	32664	6333	2452	6992	311	0.00	-1.52	-0.23	0.00	0.00	0.00	-12.02	-31.87	-0.77	20	25	177	
4	32696	7243	2489	8052	311	0.00	-1.71	-0.26	0.00	0.00	0.00	-12.02	-30.16	-0.39	10	14	188	
5	32735	8123	2535	9092	310	0.00	-1.85	-0.27	0.00	0.00	0.00	-12.02	-28.31	-0.16	3	7	195	
6	32780	8973	2588	1008	2309	0.00	-1.96	-0.27	0.00	0.00	0.00	-12.02	-26.35	-0.06	-0	4	198	

7	32831	97932648	1104	2308	0.00	-2.03	-0.26	0.00	0.00	0.00	0.00	-12.02	-24.32	-0.08	1	5	197
8	32888	1056	32715	1195	2307	0.00	-2.06	-0.24	0.00	0.00	0.00	-12.02	-22.26	-0.19	6	9	193
9	32951	1129	32789	1280	2306	0.00	-2.07	-0.22	0.00	0.00	0.00	-12.02	-20.19	-0.37	14	18	184
10	33019	1197	32868	1360	2305	0.00	-2.06	-0.19	0.00	0.00	0.00	-12.02	-18.13	-0.60	27	30	172
11	33092	1260	32954	1433	2303	0.00	-2.02	-0.16	0.00	0.00	0.00	-12.02	-16.11	-0.86	43	46	156
12	33170	1317	33045	1500	2302	0.00	-1.97	-0.13	0.00	0.00	0.00	-12.02	-14.13	-1.15	63	65	137
13	33251	1368	33140	1560	2301	0.00	-1.92	-0.10	0.00	0.00	0.00	-12.02	-12.22	-1.43	85	88	114
14	33336	1413	33240	1613	2299	0.36	-1.87	-0.00	0.00	0.00	0.00	-12.38	-10.35	-1.75	111	113	89
15	33425	1451	33344	1658	2297	0.29	-1.82	-0.01	0.00	0.00	0.00	-12.67	-8.53	-2.03	135	138	64
16	33516	1483	33450	1695	2296	0.22	-1.78	-0.02	0.00	0.00	0.00	-12.89	-6.75	-2.26	157	159	43
17	33609	1508	33559	1724	2294	0.16	-1.74	-0.04	0.00	0.00	0.00	-13.06	-5.01	-2.44	176	178	24
18	33703	1526	33670	1745	2292	0.11	-1.71	-0.05	0.00	0.00	0.00	-13.17	-3.30	-2.57	189	191	11
19	33799	1536	33782	1758	2291	0.07	-1.68	-0.06	0.00	0.00	0.00	-13.23	-1.61	-2.64	198	200	2
20	33895	1540	33895	1762	2290	0.02	-1.67	-0.07	0.00	0.00	0.00	-13.26	0.06	-2.67	200	202	-0
21	33991	1536	34008	1758	2288	-0.02	-1.67	0.09	0.00	0.00	0.00	-13.23	1.73	-2.63	197	199	3
22	34087	1526	34120	1745	2286	-0.07	-1.68	0.10	0.00	0.00	0.00	-13.17	3.40	-2.55	187	189	13
23	34181	1508	34231	1724	2285	-0.11	-1.69	0.12	0.00	0.00	0.00	-13.06	5.09	-2.41	173	175	27
24	34274	1483	34340	1695	2283	-0.16	-1.72	0.13	0.00	0.00	0.00	-12.90	6.81	-2.22	154	156	46
25	34365	1451	34446	1658	2281	-0.22	-1.75	0.15	0.00	0.00	0.00	-12.68	8.56	-1.99	132	134	68
26	34454	1413	34550	1613	2280	-0.28	-1.79	0.16	0.00	0.00	0.00	-12.40	10.35	-1.70	108	110	92
27	34539	1368	34650	1560	2278	-0.35	-1.83	0.18	0.00	0.00	0.00	-12.05	12.18	-1.38	82	85	117
28	34620	1317	34745	1500	2277	0.00	-1.88	0.26	0.00	0.00	0.00	-12.05	14.06	-1.10	60	63	139
29	34698	1260	34836	1433	2276	0.00	-1.93	0.28	0.00	0.00	0.00	-12.05	15.99	-0.82	41	44	158
30	34771	1197	34922	1360	2274	0.00	-1.98	0.30	0.00	0.00	0.00	-12.05	17.96	-0.56	25	28	174
31	34839	1129	35001	1280	2273	0.00	-2.01	0.33	0.00	0.00	0.00	-12.05	19.97	-0.33	13	16	186
32	34902	1056	35075	1195	2272	0.00	-2.03	0.34	0.00	0.00	0.00	-12.05	22.00	-0.16	5	8	194
33	34959	97935142	1104	2271	0.00	-2.02	0.35	0.00	0.00	0.00	0.00	-12.05	24.02	-0.06	0	4	198
34	35010	89735202	1008	2270	0.00	-1.99	0.35	0.00	0.00	0.00	0.00	-12.05	26.01	-0.06	-0	4	198
35	35055	81235255	9092269	0.00	-1.92	0.35	0.00	0.00	0.00	0.00	0.00	-12.05	27.93	-0.17	3	8	194
36	35094	72435301	8052268	0.00	-1.82	0.33	0.00	0.00	0.00	0.00	0.00	-12.05	29.75	-0.41	10	15	187
37	35126	63335338	6992267	0.00	-1.69	0.30	0.00	0.00	0.00	0.00	0.00	-12.05	31.43	-0.81	22	26	176
38	35151	54035367	5902267	0.00	-1.50	0.27	0.00	0.00	0.00	0.00	0.00	-12.05	32.92	-1.37	37	42	160
39	35169	44635389	4792266	0.00	-1.27	0.22	0.00	0.00	0.00	0.00	0.00	-12.05	34.19	-2.12	57	62	140
40	35180	35035401	3672266	0.00	-1.00	0.16	0.00	0.00	0.00	0.00	0.00	-12.05	35.20	-3.06	82	88	114

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 Base level: -1500 [mm] Top level: 70 [mm] Thickness at top: 6750 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 0 35180 41930 70 -355.30 1.25 -355.30 -8.36 38506 38557 -0.05 -0.05 3326.09 3373.16
 1 35180 41930 -453 -77.71 1.25 -433.02 -7.71 38506 38568 -0.07 -0.06 3326.27 3361.87
 2 35180 41930 -977 -77.71 1.25 -510.73 -7.05 38505 38578 -0.08 -0.07 3324.71 3352.33
 3 35180 41930 -1500 -77.71 1.25 -588.45 -6.40 38502 38586 -0.09 -0.09 3322.09 3343.85

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 Shape: Circular
 Span: 2720 [mm] Rise: 1350 [mm] Q-rise: 1100 [mm]
 Ring thickness at crown: 270 [mm] Ring thickness at springing: 270 [mm] Mortar loss: 20 [mm]
 Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]


Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 0 41930 70 41660 72 2127 0.00 0.00 0.00 0.00 0.00 0.00 -10.80 -38.41 -3.74 94 100 150
 1 41935 17641666 1992127 0.00 -0.94 -0.16 0.00 0.00 0.00 0.00 -10.80 -37.47 -2.61 65 71 179
 2 41948 28241682 3262126 0.00 -1.31 -0.24 0.00 0.00 0.00 0.00 -10.80 -36.16 -1.70 43 48 202
 3 41970 38641707 4502125 0.00 -1.62 -0.30 0.00 0.00 0.00 0.00 -10.80 -34.54 -1.00 25 30 220

4	41999	48841743	5732124	0.00	-1.87	-0.35	0.00	0.00	0.00	0.00	0.00	-10.80	-32.67	-0.51	12	17	233
5	42036	58741788	6922123	0.00	-2.07	-0.37	0.00	0.00	0.00	0.00	0.00	-10.80	-30.60	-0.21	4	9	241
6	42081	68441841	8072121	0.00	-2.21	-0.38	0.00	0.00	0.00	0.00	0.00	-10.80	-28.39	-0.07	0	4	246
7	42134	77641904	9182119	0.00	-2.30	-0.37	0.00	0.00	0.00	0.00	0.00	-10.80	-26.09	-0.06	0	4	246
8	42193	86441976	10242117	0.00	-2.35	-0.35	0.00	0.00	0.00	0.00	0.00	-10.80	-23.74	-0.18	5	9	241
9	42259	94742055	11242114	0.00	-2.35	-0.32	0.00	0.00	0.00	0.00	0.00	-10.80	-21.39	-0.38	15	18	232
10	42332	102542142	12172111	0.00	-2.32	-0.28	0.00	0.00	0.00	0.00	0.00	-10.80	-19.07	-0.65	29	32	218
11	42410	109742235	13032108	0.00	-2.26	-0.24	0.00	0.00	0.00	0.00	0.00	-10.80	-16.81	-0.95	48	51	199
12	42494	116342336	13822104	0.00	-2.18	-0.20	0.00	0.00	0.00	0.00	0.00	-10.80	-14.63	-1.28	73	75	175
13	42582	122142442	14522101	0.00	-2.09	-0.15	0.00	0.00	0.00	0.00	0.00	-10.80	-12.54	-1.61	101	103	147
14	42675	127342553	15142097	0.37	-2.01	-0.02	-0.00	0.00	0.00	0.00	0.00	-11.17	-10.53	-1.99	134	136	114
15	42772	131742669	15672093	0.28	-1.94	-0.01	-0.00	0.00	0.00	0.00	0.00	-11.46	-8.60	-2.31	166	168	82
16	42872	135442789	16112089	0.21	-1.86	0.01	-0.00	0.00	0.00	0.00	0.00	-11.67	-6.73	-2.57	194	196	54
17	42974	138342911	16452084	0.15	-1.80	0.03	-0.00	0.00	0.00	0.00	0.00	-11.83	-4.94	-2.77	218	220	30
18	43078	140343036	16702080	0.10	-1.74	0.05	-0.00	0.00	0.00	0.00	0.00	-11.93	-3.19	-2.91	236	238	12
19	43184	141643163	16852075	0.06	-1.70	0.08	-0.00	0.00	0.00	0.00	0.00	-11.99	-1.50	-2.98	246	248	2
20	43290	142043290	16902070	0.02	-1.67	0.08	-0.00	0.00	0.00	0.00	0.00	-12.01	0.17	-2.99	248	250	0
21	43396	141643417	16852064	-0.02	-1.66	0.10	0.00	0.00	0.00	0.00	0.00	-11.99	1.83	-2.94	242	244	6
22	43502	140343544	16702060	-0.06	-1.66	0.11	0.00	0.00	0.00	0.00	0.00	-11.93	3.50	-2.83	229	231	19
23	43606	138343669	16452054	-0.10	-1.69	0.13	0.00	0.00	0.00	0.00	0.00	-11.83	5.18	-2.66	209	211	39
24	43708	135443791	16112050	-0.14	-1.72	0.15	0.00	0.00	0.00	0.00	0.00	-11.69	6.90	-2.44	183	185	65
25	43808	131743911	15672045	-0.20	-1.77	0.17	0.00	0.00	0.00	0.00	0.00	-11.49	8.67	-2.16	154	156	94
26	43905	127344027	15142040	-0.26	-1.83	0.20	0.00	0.00	0.00	0.00	0.00	-11.23	10.50	-1.83	123	125	125
27	43998	122144138	14522035	-0.33	-1.89	0.22	0.00	0.00	0.00	0.00	0.00	-10.90	12.39	-1.46	91	94	166
28	44086	116344244	13822031	0.00	-1.96	0.32	0.00	0.00	0.00	0.00	0.00	-10.90	14.35	-1.13	65	67	183
29	44170	109744345	13032026	0.00	-2.04	0.35	0.00	0.00	0.00	0.00	0.00	-10.90	16.38	-0.82	42	45	205
30	44248	102544438	12172023	0.00	-2.12	0.39	0.00	0.00	0.00	0.00	0.00	-10.90	18.50	-0.54	24	27	223
31	44321	94744525	11242019	0.00	-2.18	0.42	0.00	0.00	0.00	0.00	0.00	-10.90	20.68	-0.30	12	15	235
32	44387	86444604	10242016	0.00	-2.21	0.45	0.00	0.00	0.00	0.00	0.00	-10.90	22.89	-0.13	37	40	243
33	44446	77644676	9182013	0.00	-2.21	0.46	0.00	0.00	0.00	0.00	0.00	-10.90	25.10	-0.05	0	4	246
34	44499	68444739	8072010	0.00	-2.18	0.47	0.00	0.00	0.00	0.00	0.00	-10.90	27.28	-0.09	1	5	245
35	44544	58744792	6922008	0.00	-2.10	0.45	0.00	0.00	0.00	0.00	0.00	-10.90	29.38	-0.27	6	11	239
36	44581	48844837	5732006	0.00	-1.98	0.43	0.00	0.00	0.00	0.00	0.00	-10.90	31.36	-0.61	16	21	229
37	44610	38644873	4502005	0.00	-1.80	0.38	0.00	0.00	0.00	0.00	0.00	-10.90	33.15	-1.13	30	35	215
38	44632	28244898	3262004	0.00	-1.57	0.32	0.00	0.00	0.00	0.00	0.00	-10.90	34.72	-1.85	49	54	196
39	44645	17644914	1992003	0.00	-1.27	0.25	0.00	0.00	0.00	0.00	0.00	-10.90	35.99	-2.78	73	78	172
40	44650	7044920	722003	0.00	-0.93	0.16	0.00	0.00	0.00	0.00	0.00	-10.90	36.92	-3.93	104	109	141

Me... - Viewing Purposes Only!

Beaumont Bridge

SV100 Impact on 6 at 18650 mm
55.0051.0051.0051.0051.00



Upperbound condition with backing present => SV100 load capacity

gammaFI dead load: 1.00 SV100 Impact on 6 @ 18650 [mm]
gammaFI superimposed: 1.00
gammaFI live load: 2.50
gammaF3 load effect: 1.00
gammaM material: 1.00

File path: V:\5210920\7 Calcs\72 Model\Beaumont Bridge - UB w backing.brg

NAME: Beaumont Bridge
LOCATION: Beaumont, Meath
NUMBER: MH-L1615-001.00
ATKINS
DATE: 20 December 2021
Printed on: Wednesday, January 12, 2022 15:27:00

Bridge Name: Beaumont Bridge Bridge Location: Beaumont, Meath
 Bridge Number: MH-L1615-001.00
 Number of spans: 7

SAFETY FACTORS

Factor for deadload: 1.00 Factor for superimposed deadload: 1.00 Factor for surfacing: 1.00
 Factor for live load: 2.50 Factor for load effect: 1.00 Factor for material strength: 1.00

APPLIED LOAD CASES

1.SV100 Impact on 6 Total weight: 1216.44 [kN] Position: 18650 [mm]
 124.00 6 1.00 20.40 1.20 20.40 2.40 20.40 3.60 20.40 4.80 20.40 6.00 22.00 1.00 2.65 3.00
 Effective lane width: 3350 [mm] Distribution length: 2827 [mm]

Applied distribution mode: Archie-M, BD21/97
 Applied live load pressure: Active pressure

STRUCTURE PROPERTIES

Road shape: True shape (multi-point method)
 Road points: (-500, 1950) (1180, 2000) (5805, 2200) (11660, 2550) (19175, 2750) (29755, 2370) (33895, 2290) (43290, 2070) (45000, 2000)
 Depth of surfacing: 150Depth of overlay: 0
 Surface unit weight: 23.00 [kN/m³] Overlay unit weight: 23.00 [kN/m³]
 Lane width: 0

Fill unit weight: 18.00 [kN/m³] Fill phi: 30 degree

Left abutment Base level:-1500 [mm] Height: 380 [mm] Width: 1000 [mm]

Right abutment Base level:-1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Right abutment Base level:-1500 [mm] Height: 70 [mm] Width: 1000 [mm]

Shape: Circular

Span: 2360 [mm] Rise: 1170 [mm] Q-rise: 1050 [mm]

Ring thickness at crown:350 [mm] Ring thickness at springing: 350 [mm] Mortar loss: 20 [mm]

Masonry unit weight:22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment\Intrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust

0 0 380-350 3831954 0.00 0.00 0.00 0.00 0.00 0.00 -5.80 -29.56 -2.05 67 72 258
 1 4 472-344 5021954 0.00 -1.00 -0.21 0.00 -0.00 0.00 0.00 -5.80 -28.56 -1.43 47 52 278
 2 16 563-329 6211954 0.00 -1.26 -0.29 0.00 -0.00 0.00 0.00 -5.80 -27.30 -0.93 31 35 295
 3 35 654-305 7381955 0.00 -1.47 -0.34 0.00 -0.00 0.00 0.00 -5.80 -25.83 -0.54 19 22 308
 4 60 742-272 8531956 0.00 -1.63 -0.38 0.00 -0.00 0.00 0.00 -5.80 -24.19 -0.27 9 13 317
 5 93 828-230 9641957 0.00 -1.75 -0.40 0.00 -0.00 0.00 0.00 -5.80 -22.44 -0.10 3 6 324
 6 132912-179 1073 1959 0.00 -1.82 -0.40 0.00 -0.00 0.00 0.00 -5.80 -20.63 -0.03 -0 3 327
 7 177992-120 1177 1961 0.00 -1.85 -0.38 0.00 -0.00 0.00 0.00 -5.80 -18.78 -0.04 1 4 326
 8 2291068 -53 1276 1963 0.00 -1.84 -0.36 0.00 -0.00 0.00 0.00 -5.80 -16.94 -0.13 6 9 321
 9 2861141 21 1369 1965 0.00 -1.80 -0.32 0.00 -0.00 0.00 0.00 -5.80 -15.15 -0.27 16 19 311
 10 3491208 1031456 1968 0.00 -1.73 -0.28 0.00 -0.00 0.00 0.00 -5.80 -13.42 -0.45 32 34 296
 11 4171270 1911537 1970 0.00 -1.65 -0.23 0.00 -0.00 0.00 0.00 -5.80 -11.77 -0.67 55 56 274
 12 4901327 2851611 1972 0.29 -1.56 -0.10 0.00 -0.00 0.00 0.00 -6.09 -10.21 -0.97 88 89 241
 13 5661378 3841677 1975 0.22 -1.48 -0.08 0.00 -0.00 0.00 0.00 -6.31 -8.73 -1.24 124125205
 14 6471423 4891735 1978 0.16 -1.40 -0.06 0.00 -0.00 0.00 0.00 -6.48 -7.33 -1.48 163164166
 15 7311461 5971785 1982 0.12 -1.33 -0.04 0.00 -0.00 0.00 0.00 -6.59 -6.00 -1.70 202203127
 16 8171493 7101826 1985 0.08 -1.26 -0.02 0.00 -0.00 0.00 0.00 -6.68 -4.74 -1.88 24024189
 17 9061518 8251858 1989 0.05 -1.20 -0.00 0.00 -0.00 0.00 0.00 -6.73 -3.54 -2.02 27427555
 18 9961536 9421881 1992 0.03 -1.16 0.01 0.00 -0.00 0.00 0.00 -6.76 -2.38 -2.13 30230327
 19 1088 1546 1061 1895 1996 0.02 -1.13 0.03 0.00 -0.00 0.00 0.00 -6.78 -1.26 -2.20 3213228
 20 1180 1550 1180 1900 2000 0.01 -1.12 0.04 0.00 -0.00 0.00 0.00 -6.79 -0.14 -2.24 329330-0
 21 1272 1546 1299 1895 2003 -0.01 -1.13 0.06 -0.00 -0.00 0.00 0.00 -6.78 0.99 -2.23 3253264

22	1364	1536	1418	1881	2007	-0.02	-1.15	0.08	-0.00	-0.00	0.00	0.00	-6.76	2.14	-2.18	3103	1119
23	1454	1518	1535	1858	2011	-0.04	-1.20	0.10	-0.00	-0.00	0.00	0.00	-6.72	3.34	-2.09	2852	8743
24	1543	1493	1650	1826	2015	-0.06	-1.25	0.12	-0.00	-0.00	0.00	0.00	-6.66	4.59	-1.96	2532	5476
25	1629	1461	1763	1785	2019	-0.09	-1.33	0.14	-0.00	-0.00	0.00	0.00	-6.57	5.92	-1.79	2152	16114
26	1713	1423	1871	1735	2023	-0.14	-1.41	0.17	-0.00	-0.00	0.00	0.00	-6.43	7.33	-1.59	1751	76154
27	1794	1378	1976	1677	2026	-0.19	-1.49	0.19	-0.00	-0.00	0.00	0.00	-6.24	8.82	-1.34	1351	136194
28	1870	1327	2075	1611	2030	-0.25	-1.58	0.22	-0.00	-0.00	0.00	0.00	-5.99	10.39	-1.06	96	98
29	1943	1270	2169	1537	2034	-0.33	-1.66	0.25	-0.00	-0.00	0.00	0.00	-5.66	12.06	-0.75	61	63
30	2011	1208	2257	1456	2037	0.00	-1.75	0.37	0.00	-0.00	0.00	0.00	-5.66	13.81	-0.52	37	39
31	2074	1141	2339	1369	2040	0.00	-1.84	0.41	0.00	-0.00	0.00	0.00	-5.66	15.65	-0.33	20	22
32	2131	1068	2413	1276	2043	0.00	-1.90	0.45	0.00	-0.00	0.00	0.00	-5.66	17.55	-0.17	8	11
33	2183	9922	2480	1177	2045	0.00	-1.94	0.48	0.00	-0.00	0.00	0.00	-5.66	19.48	-0.07	2	5
34	2228	9122	2539	1073	2047	0.00	-1.94	0.50	0.00	-0.00	0.00	0.00	-5.66	21.42	-0.03	0	3
35	2267	8282	2590	9642	2049	0.00	-1.90	0.50	0.00	-0.00	0.00	0.00	-5.66	23.32	-0.08	2	5
36	2300	7422	2632	8532	2051	0.00	-1.82	0.48	0.00	-0.00	0.00	0.00	-5.66	25.14	-0.23	7	11
37	2325	6542	2665	7382	2052	0.00	-1.69	0.44	0.00	-0.00	0.00	0.00	-5.66	26.83	-0.48	16	20
38	2344	5632	2689	6212	2053	0.00	-1.51	0.39	0.00	-0.00	0.00	0.00	-5.66	28.34	-0.85	27	31
39	2356	4722	2704	5022	2053	0.00	-1.29	0.31	0.00	-0.00	0.00	0.00	-5.66	29.63	-1.34	42	47
40	2360	3802	2710	3832	2054	0.00	-1.01	0.21	0.00	-0.00	0.00	0.00	-5.66	30.64	-1.94	61	66

Segment Intrados.x Intrados.x Extrados.x Extrados.x Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 Base level: -1500 [mm] Top level: 380 [mm] Thickness at top: 2000 [mm]

Batter: 1:0

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 0 2360 4360 380 -115.65 -3.36 -115.657.15 3414 3430 -0.05 -0.07 1053.57 929.91
 1 2360 4360 -247 -27.57 -3.36 -143.22 5.05 3385 3405 -0.06 -0.08 1025.00 954.54
 2 2360 4360 -873 -27.57 -3.36 -170.79 2.94 3365 3389 -0.08 -0.09 1005.02 970.58
 3 2360 4360 -1500 -27.57 -3.36 -198.37 0.84 3350 3378 -0.10 -0.10 990.05 981.61

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right

Shape: Circular

Span: 2890 [mm] Rise: 1280 [mm] Q-rise: 1020 [mm]

Ring thickness at crown: 370 [mm] Ring thickness at springing: 370 [mm] Mortar loss: 20 [mm]

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.x Extrados.x Extrados.x Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 0 4360 4003993 4452109 0.00 0.00 0.00 0.00 0.00 0.00 -9.02 -38.10 -2.17 53 59 291
 1 4377 5044013 5752109 0.00 -1.68 -0.41 0.00 -0.00 0.00 0.00 -9.02 -36.42 -1.42 35 40 310
 2 4401 6074044 7042111 0.00 -1.91 -0.48 0.00 -0.00 0.00 0.00 -9.02 -34.51 -0.84 21 26 324
 3 4432 7084083 8302113 0.00 -2.09 -0.52 0.00 -0.00 0.00 0.00 -9.02 -32.42 -0.43 10 15 335
 4 4471 8064131 9542115 0.00 -2.22 -0.54 0.00 -0.00 0.00 0.00 -9.02 -30.20 -0.17 3 8 342
 5 4516 9014189 1073 2118 0.00 -2.30 -0.54 0.00 -0.00 0.00 0.00 -9.02 -27.90 -0.06 -0 4 346
 6 4569 9934254 1188 2121 0.00 -2.33 -0.51 0.00 -0.00 0.00 0.00 -9.02 -25.57 -0.07 1 4 346
 7 4627 1080 4328 1298 2124 0.00 -2.32 -0.48 0.00 -0.00 0.00 0.00 -9.02 -23.25 -0.17 6 9 341
 8 4693 1163 4410 1402 2128 0.00 -2.28 -0.43 0.00 -0.00 0.00 0.00 -9.02 -20.97 -0.37 15 18 332
 9 4763 1241 4499 1500 2132 0.00 -2.20 -0.38 0.00 -0.00 0.00 0.00 -9.02 -18.77 -0.62 30 33 317
 10 4840 1314 4594 1591 2137 0.00 -2.11 -0.32 0.00 -0.00 0.00 0.00 -9.02 -16.66 -0.92 51 53 297
 11 4921 1381 4697 1675 2142 0.00 -1.99 -0.27 0.00 -0.00 0.00 0.00 -9.02 -14.67 -1.25 77 79 271
 12 5007 1442 4805 1752 2147 0.33 -1.89 -0.11 0.00 -0.00 0.00 0.00 -9.34 -12.78 -1.68 112 115 235
 13 5098 1497 4918 1820 2153 0.25 -1.79 -0.08 0.00 -0.00 0.00 0.00 -9.59 -10.98 -2.07 150 152 198
 14 5192 1544 5036 1880 2159 0.19 -1.70 -0.06 0.00 -0.00 0.00 0.00 -9.78 -9.28 -2.42 189 191 159
 15 5289 1585 5158 1931 2165 0.14 -1.62 -0.04 0.00 -0.00 0.00 0.00 -9.92 -7.66 -2.73 227 229 121
 16 5389 1619 5283 1974 2172 0.10 -1.55 -0.01 0.00 -0.00 0.00 0.00 -10.02 -6.11 -2.99 263 265 85
 17 5491 1646 5411 2007 2178 0.07 -1.49 0.01 0.00 -0.00 0.00 0.00 -10.08 -4.62 -3.21 295 297 53
 18 5595 1665 5541 2031 2185 0.04 -1.45 0.03 0.00 -0.00 0.00 0.00 -10.13 -3.17 -3.37 321 323 27

19	5700	1676	5673	2045	2192	0.02	-1.42	0.05	0.00	-0.00	0.00	0.00	-10.15	-1.75	-3.49	3393419	***
20	5805	1680	5805	2050	2199	0.01	-1.42	0.07	0.00	-0.00	0.00	0.00	-10.16	-0.33	-3.55	349350-0	
21	5910	1676	5937	2045	2207	-0.01	-1.44	0.09	-0.00	-0.00	0.00	0.00	-10.15	1.10	-3.56	3483491	
22	6015	1665	6069	2031	2214	-0.03	-1.47	0.11	-0.00	-0.00	0.00	0.00	-10.13	2.58	-3.51	33733812	
23	6119	1646	6199	2007	2221	-0.05	-1.53	0.13	-0.00	-0.00	0.00	0.00	-10.07	4.11	-3.40	31731832	
24	6221	1619	6327	1974	2229	-0.08	-1.60	0.16	-0.00	-0.00	0.00	0.00	-9.99	5.71	-3.24	28829060	
25	6321	1585	6452	1931	2236	-0.12	-1.69	0.19	-0.00	-0.00	0.00	0.00	-9.87	7.40	-3.02	25425595	
26	6418	1544	6574	1880	2243	-0.17	-1.79	0.22	-0.00	-0.00	0.00	0.00	-9.69	9.20	-2.73	215217133	
27	6512	1497	6692	1820	2250	-0.24	-1.90	0.26	-0.00	-0.00	0.00	0.00	-9.46	11.09	-2.39	174176174	
28	6603	1442	6805	1752	2257	-0.31	-2.01	0.29	-0.00	-0.00	0.00	0.00	-9.14	13.10	-1.99	133135215	
29	6689	1381	6913	1675	2263	-0.41	-2.11	0.33	-0.00	-0.00	0.00	0.00	-8.74	15.21	-1.53	93 96 254	
30	6770	1314	7016	1591	2269	0.00	-2.23	0.49	0.00	-0.00	0.00	0.00	-8.74	17.44	-1.17	64 66 284	
31	6847	1241	7111	1500	2275	0.00	-2.34	0.55	0.00	-0.00	0.00	0.00	-8.74	19.78	-0.84	40 43 307	
32	6917	1163	7200	1402	2280	0.00	-2.44	0.61	0.00	-0.00	0.00	0.00	-8.74	22.22	-0.54	22 26 324	
33	6983	1080	7282	1298	2285	0.00	-2.51	0.65	0.00	-0.00	0.00	0.00	-8.74	24.73	-0.30	10 14 336	
34	7041	9937356	1188	2289	0.00	-2.54	0.69	0.00	-0.00	0.00	0.00	0.00	-8.74	27.27	-0.13	7 343	
35	7094	9017421	1073	2293	0.00	-2.53	0.70	0.00	-0.00	0.00	0.00	0.00	-8.74	29.81	-0.07	-0 4 346	
36	7139	8067479	9542297	0.00	-2.48	0.70	0.00	-0.00	0.00	0.00	0.00	0.00	-8.74	32.29	-0.12	1 6 344	
37	7178	7087527	8302300	0.00	-2.38	0.68	0.00	-0.00	0.00	0.00	0.00	0.00	-8.74	34.67	-0.31	6 11 339	
38	7209	6077566	7042302	0.00	-2.23	0.63	0.00	-0.00	0.00	0.00	0.00	0.00	-8.74	36.90	-0.66	15 20 330	
39	7233	5047597	5752304	0.00	-2.02	0.56	0.00	-0.00	0.00	0.00	0.00	0.00	-8.74	38.92	-1.19	27 33 317	
40	7250	4007617	4452306	0.00	-1.75	0.47	0.00	-0.00	0.00	0.00	0.00	0.00	-8.74	40.66	-1.90	43 49 301	

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 100 [mm] Thickness at top: 2300 [mm]

Batter: 1:0
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 7250 9550 100-211.35-118.12-211.35-96.68 7927 7958 -0.20 0.02 677.44 1592.37
1 7250 9550 -433 -26.99 -118.12-238.34 -159.68 7713 7747 -0.28 0.08 462.98 1802.98
2 7250 9550 -967 -26.99 -118.12-265.32 -222.68 7542 7580 -0.37 0.14 291.75 1970.35
3 7250 9550 -1500 -26.99 -118.12-292.31 -285.68 7402 7444 -0.45 0.20 151.78 2106.46

Segment Left xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular

Span: 4220 [mm] Rise: 1930 [mm] Q-rise: 1560 [mm]
Ring thickness at crown: 420 [mm] Ring thickness at springing: 420 [mm] Mortar loss: 20 [mm]
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
0 9550 1009132 1372400 0.00 0.00 0.00 0.00 0.00 0.00 -126.86 -94.77 -159.93 1506 1521 -1121 ***
1 9570 2569155 3242401 0.00 -2.70 -0.76 0.00 -0.00 0.00 -126.86 -92.07 -141.07 1258 1274 -874 ***
2 9601 4099193 5082403 0.00 -3.20 -0.92 0.00 -0.00 0.00 -126.86 -88.87 -123.26 1053 1069 -669 ***
3 9643 5609244 6892407 0.00 -3.58 -1.02 0.00 -0.00 0.00 -126.86 -85.29 -106.56 879896-496 ***
4 9697 7089308 8662411 0.00 -3.85 -1.07 0.00 -0.00 0.00 -126.86 -81.44 -91.01 730748-348 ***
5 9761 8519385 1037 2415 0.00 -4.01 -1.07 0.00 -0.00 0.00 -126.86 -77.43 -76.64 601619-219 ***
6 9836 9899474 1203 2421 0.00 -4.08 -1.03 0.00 -0.00 0.00 -126.86 -73.35 -63.48 488506-106 ***
7 9921 1121 9576 1361 2427 0.00 -4.06 -0.95 0.00 -0.00 0.00 -126.86 -69.29 -51.55 389408-8 ***
8 10015 1247 9689 1511 2434 0.00 -3.97 -0.85 0.00 -0.00 0.00 -126.86 -65.32 -40.86 30332278
9 10118 1365 9813 1653 2442 0.00 -3.81 -0.73 0.00 -0.00 0.00 -126.86 -61.51 -31.42 229248152
10 10230 1475 9947 1785 2450 0.00 -3.61 -0.61 0.00 -0.00 0.00 -126.86 -57.90 -23.24 166185215
11 10350 1576 10090 1906 2459 0.00 -3.38 -0.49 0.00 -0.00 0.00 -126.86 -54.52 -16.33 113132268
12 10477 1669 10242 2017 2488 0.00 -3.12 -0.37 0.00 -0.00 0.00 -126.86 -51.40 -10.71 70 90 310
13 10610 1751 10402 2116 2478 0.40 -2.88 -0.11 0.00 -0.00 0.00 -127.26 -48.52 -6.49 39 58 342
14 10749 1824 10568 2203 2487 0.29 -2.69 -0.07 0.00 -0.00 0.00 -127.55 -45.83 -3.50 16 36 364
15 10893 1886 10741 2278 2498 0.20 -2.50 -0.02 0.00 -0.00 0.00 -127.75 -43.33 -1.76 3 23 377

16	11041	1938	10919	2339	2508	0.13	-2.35	0.01	0.00	-0.00	0.00	0.00	-127.88	-40.98	-1.28	-0	19	381
17	11193	1978	11100	2388	2518	0.08	-2.22	0.05	0.00	-0.00	0.00	0.00	-127.96	-38.76	-2.06	6	25	375
18	11347	2007	11285	2422	2529	0.05	-2.13	0.08	0.00	-0.00	0.00	0.00	-128.01	-36.64	-4.11	22	41	359
19	11503	2024	11472	2443	2539	0.03	-2.07	0.11	0.00	-0.00	0.00	0.00	-128.04	-34.56	-7.42	48	66	334
20	11660	2030	11660	2450	2549	0.01	-2.06	0.15	0.00	-0.00	0.00	0.00	-128.05	-32.50	-11.96	84	103	297
21	11817	2024	11848	2443	2560	-0.01	-2.10	0.18	-0.00	-0.00	0.00	0.00	-128.04	-30.40	-17.70	132	150	250
22	11973	2007	12035	2422	2569	-0.03	-2.18	0.22	-0.00	-0.00	0.00	0.00	-128.00	-28.22	-24.62	192	210	190
23	12127	1978	12220	2388	2579	-0.07	-2.29	0.27	-0.08	-1.31	0.25	0.00	-127.86	-24.62	-32.70	266	283	117
24	12279	1938	12401	2339	2588	-0.11	-2.45	0.32	-1.54	-17.41	2.94	0.00	-126.20	-4.76	-41.82	342	359	41
25	12427	1886	12579	2278	2597	-0.18	-2.63	0.38	-4.80	-41.60	7.19	0.00	-121.22	39.48	-49.77	382	400	-0
26	12571	1824	12752	2203	2605	-0.27	-2.84	0.45	-7.37	-51.20	9.36	0.00	-113.58	93.52	-53.11	362	382	18
27	12710	1751	12918	2116	2614	-0.39	-3.07	0.53	-6.96	-39.93	7.73	0.00	-106.24	136.52	-50.00	301	324	76
28	12843	1669	13078	2017	2621	-0.53	-3.30	0.61	-4.32	-20.89	4.28	0.00	-101.39	160.71	-41.74	228	252	148
29	12970	1576	13230	1906	2627	0.00	-3.56	0.90	0.00	-10.78	3.20	0.00	-101.39	175.05	-32.89	162	188	212
30	13090	1475	13373	1785	2634	0.00	-3.83	1.04	0.00	-11.62	3.74	0.00	-101.39	190.50	-25.05	109	138	262
31	13202	1365	13507	1653	2640	0.00	-4.07	1.17	0.00	-13.15	4.45	0.00	-101.39	207.72	-18.51	68	100	300
32	13305	1247	13631	1511	2646	0.00	-4.27	1.29	0.00	-13.88	4.91	0.00	-101.39	225.87	-13.24	38	72	328
33	13399	1121	13744	1361	2650	0.00	-4.41	1.39	0.00	-13.83	5.09	0.00	-101.39	244.11	-9.32	18	55	345
34	13484	989	13846	1203	2654	0.00	-4.48	1.45	0.00	-13.14	4.99	0.00	-101.39	261.73	-6.88	5	45	355
35	13559	851	13935	1037	2658	0.00	-4.46	1.48	0.00	-11.96	4.66	0.00	-101.39	278.16	-6.15	-0	42	358
36	13623	708	14012	866	2661	0.00	-4.35	1.46	0.00	-10.48	4.16	0.00	-101.39	292.99	-7.40	2	46	354
37	13677	560	14076	689	2663	0.00	-4.14	1.39	0.00	-8.79	3.54	0.00	-101.39	305.91	-10.88	11	57	343
38	13719	409	14127	508	2665	0.00	-3.82	1.27	0.00	-6.98	2.84	0.00	-101.39	316.71	-16.86	27	75	325
39	13750	256	14165	324	2666	0.00	-3.38	1.09	0.00	-5.12	2.08	0.00	-101.39	325.20	-25.53	52	100	300
40	13770	100	14188	137	2667	0.00	-2.82	0.86	0.00	-3.23	1.31	0.00	-101.39	331.24	-37.03	85	133	267

SegmentIntrados.x Intrados.x Extrados.x Extrados.x Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
Base level:-1500 [mm] Top level: 100 [mm] Thickness at top: 3150 [mm]

Batter: 1.0
Masonry unit weight:22.00 [kN/m3] Masonry strength: 7.00 [MPa]

SegmentLeft xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
0 13770 16920 100-1123.17 -27.31 -1123.17 54.9815314 15474 -0.32-0.39 1543.72 1445.83
1 13770 16920 -433 -36.96 -27.31 -1160.13 40.4115297 15463 -0.34-0.39 1526.97 1457.30
2 13770 16920 -967 -36.96 -27.31 -1197.09 25.8515281 15452 -0.36-0.40 1511.09 1467.90
3 13770 16920 -1500 -36.96 -27.31 -1234.05 11.2915286 15442 -0.38-0.40 1496.00 1477.71

SegmentLeft xRight x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
Shape: Circular
Span: 4510 [mm] Rise: 2010 [mm] Q-rise: 1660 [mm]

Ring thickness at crown:440 [mm] Ring thickness at springing: 440 [mm] Mortar loss: 20 [mm]
Masonry unit weight:22.00 [kN/m3] Masonry strength: 7.00 [MPa]

SegmentIntrados.x Intrados.x Extrados.x Extrados.x Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx totalFz totalMy total Thrust in Thrust out Extra-Thrust
0 16920 20016483 2502735 0.00 0.00 0.00 0.00 0.00 0.00 -133.38 -377.52 -45.14 88 144276
1 16945 36316513 4452735 0.00 -3.27 -0.98 0.00 -2.44 -0.98 0.00 -133.38 -371.81 -30.53 50 106314
2 16982 52416556 6382736 0.00 -3.81 -1.16 0.00 -3.50 -1.37 0.00 -133.38 -364.50 -19.82 24 79 341
3 17030 68216614 8262737 0.00 -4.22 -1.27 0.00 -4.45 -1.68 0.00 -133.38 -355.83 -12.96 7 61 359
4 17090 83616685 1010 2738 0.00 -4.51 -1.31 0.00 -5.38 -1.94 0.00 -133.38 -345.94 -9.80 -0 53 367
5 17160 98616770 1189 2740 0.00 -4.68 -1.31 0.00 -6.72 -2.31 0.00 -133.38 -334.53 -9.96 2 53 367
6 17242 1130 16867 1360 2741 0.00 -4.75 -1.25 0.00 -8.94 -2.88 0.00 -133.38 -320.84 -12.83 13 62 358
7 17333 1267 16976 1524 2743 0.00 -4.73 -1.16 0.00 -12.43 -3.74 0.00 -133.38 -303.68 -17.51 31 77 343
8 17435 1397 17097 1680 2745 0.00 -4.63 -1.03 0.00 -17.28 -4.80 0.00 -133.38 -281.77 -22.95 55 98 322
9 17545 1520 17229 1827 2746 0.00 -4.45 -0.89 0.00 -22.96 -5.83 0.00 -133.38 -254.36 -28.09 82 122298
10 17665 1635 17372 1963 2748 0.00 -4.22 -0.74 0.00 -28.14 -6.45 0.00 -133.38 -222.00 -32.21 113148272
11 17792 1740 17524 2089 2749 0.00 -3.95 -0.59 0.00 -30.94 -6.31 0.00 -133.38 -187.10 -35.15 144176244
12 17926 1836 17684 2203 2750 0.00 -3.66 -0.45 0.00 -29.50 -5.25 0.00 -133.38 -153.95 -37.45 177205215

13	18068	1922	17853	2306	2751	0.50	-3.39	-0.13	4.72	-23.29	-1.67	0.00	-138.59	-127.27	-41.79	215241179
14	18215	1997	18029	2396	2752	0.36	-3.15	-0.07	2.37	-13.90	-0.82	0.00	-141.32	-110.21	-46.51	254279141
15	18367	2061	18210	2472	2753	0.25	-2.93	-0.02	0.70	-4.96	-0.26	0.00	-142.27	-102.32	-52.70	29932397
16	18523	2114	18397	2536	2753	0.17	-2.73	0.02	0.58	-5.12	0.22	0.00	-143.02	-94.47	-60.18	35537842
17	18683	2156	18588	2586	2753	0.10	-2.56	0.06	4.04	-46.48	1.41	0.00	-147.16	-45.44	-62.79	398420-0
18	18846	2186	18782	2621	2752	0.06	-2.42	0.10	4.32	-70.48	2.01	0.00	-151.54	27.46	-55.83	37239327
19	19010	2204	18978	2643	2751	0.03	-2.32	0.13	1.01	-27.60	0.55	0.00	-152.58	57.38	-44.24	288309111
20	19175	2210	19175	2650	2750	0.01	-2.27	0.17	0.00	-0.35	-0.00	0.00	-152.60	60.00	-33.48	209230190
21	19340	2204	19372	2643	2747	-0.01	-2.26	0.21	0.00	0.00	0.00	0.00	-152.59	62.27	-24.24	144166254
22	19504	2186	19568	2621	2745	-0.03	-2.30	0.25	0.00	0.00	0.00	0.00	-152.56	64.57	-16.56	92 115305
23	19667	2156	19762	2586	2743	-0.06	-2.39	0.29	0.00	0.00	0.00	0.00	-152.50	66.96	-10.48	52 76 344
24	19827	2114	19953	2536	2739	-0.10	-2.52	0.35	0.00	0.00	0.00	0.00	-152.40	69.48	-6.03	24 48 372
25	19983	2061	20140	2472	2736	-0.16	-2.68	0.41	0.00	0.00	0.00	0.00	-152.24	72.15	-3.21	7 31 389
26	20135	1997	20321	2396	2732	-0.24	-2.87	0.48	0.00	0.00	0.00	0.00	-152.01	75.02	-2.05	-0 24 396
27	20282	1922	20497	2306	2728	-0.34	-3.09	0.55	0.00	0.00	0.00	0.00	-151.66	78.11	-2.53	3 27 393
28	20424	1836	20666	2203	2725	-0.47	-3.31	0.64	0.00	0.00	0.00	0.00	-151.19	81.42	-4.66	15 39 381
29	20558	1740	20826	2089	2721	0.00	-3.58	0.92	0.00	0.00	0.00	0.00	-151.19	85.01	-8.66	38 63 357
30	20685	1635	20978	1963	2716	0.00	-3.87	1.07	0.00	0.00	0.00	0.00	-151.19	88.88	-14.39	71 96 324
31	20805	1520	21121	1827	2713	0.00	-4.14	1.22	0.00	0.00	0.00	0.00	-151.19	93.02	-21.86	115139281
32	20915	1397	21253	1680	2709	0.00	-4.37	1.36	0.00	0.00	0.00	0.00	-151.19	97.39	-31.07	169193227
33	21017	1267	21374	1524	2706	0.00	-4.55	1.47	0.00	0.00	0.00	0.00	-151.19	101.94	-42.01	233258162
34	21108	1130	21483	1360	2703	0.00	-4.66	1.56	0.00	0.00	0.00	0.00	-151.19	106.59	-54.69	31033486
35	21190	9862	1580	1189	2700	0.00	-4.69	1.61	0.00	0.00	0.00	0.00	-151.19	111.28	-69.09	398422-2 ***
36	21260	8362	1665	1010	2697	0.00	-4.62	1.61	0.00	0.00	0.00	0.00	-151.19	115.90	-85.21	501525-105 ***
37	21320	6822	1736	8262	2695	0.00	-4.45	1.56	0.00	0.00	0.00	0.00	-151.19	120.35	-103.02	620643-223 ***
38	21368	5242	1794	6382	2693	0.00	-4.17	1.45	0.00	0.00	0.00	0.00	-151.19	124.53	-122.51	758781-361 ***
39	21405	3632	1837	4452	2691	0.00	-3.77	1.28	0.00	0.00	0.00	0.00	-151.19	128.30	-143.61	920942-522 ***
40	21430	2002	1867	2502	2690	0.00	-3.25	1.05	0.00	0.00	0.00	0.00	-151.19	131.55	-166.27	1113 1134 -714 ***

Segment: Intrados.x Intrados.x Extrados.x Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
Base level: -1500 [mm] Top level: 200 [mm] Thickness at top: 7170 [mm]

Batter: 1:0
Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment	Left x	Right x	z	Weight	Fx	Fz	My	Thrust left	Thrust right	Stress left	Stress right	Dist. left	Dist. right
0	21430	28600	200	-491.56	143.16	-491.56	-180.08	24614	24684	-0.09	-0.05	3183.55	3916.22
1	21430	28600	-367	-89.39	143.16	-580.95	-98.95	24803	24886	-0.09	-0.07	3373.18	3713.83
2	21430	28600	-933	-89.39	143.16	-670.33	-17.82	24941	25036	-0.10	-0.09	3510.53	3563.71
3	21430	28600	-1500	-89.39	143.16	-759.72	63.3025044	25153	-0.10	-0.11	3614.06	3447.41	

Segment: Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist left Dist right
Shape: Circular
Span: 2310 [mm] Rise: 1150 [mm] Q-rise: 960 [mm]
Ring thickness at crown: 370 [mm] Ring thickness at springing: 370 [mm] Mortar loss: 20 [mm]
Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment	Intrados.x	Intrados.x	Extrados.x	Extrados.x	Road.z	Fx dead	Fz dead	My dead	Fx live	Fz live	My live	Fx passive	Fx total	Fz total	My total	Thrust in	Thrust out	Extra-Thrust
0	28600	45028230	4522422	0.00	0.00	0.00	0.00	0.00	0.00	-8.03	-39.54	-2.66	64	70	280			
1	28604	54028235	5712422	0.00	-1.06	-0.23	0.00	0.00	0.00	-8.03	-38.48	-1.84	44	50	300			
2	28615	63028250	6892421	0.00	-1.39	-0.34	0.00	0.00	0.00	-8.03	-37.09	-1.18	29	34	316			
3	28633	71928273	8062421	0.00	-1.67	-0.43	0.00	0.00	0.00	-8.03	-35.42	-0.68	16	21	329			
4	28658	80628306	9212419	0.00	-1.89	-0.49	0.00	0.00	0.00	-8.03	-33.53	-0.33	7	12	338			
5	28689	89028348	10332418	0.00	-2.07	-0.52	0.00	0.00	0.00	-8.03	-31.46	-0.13	2	6	344			
6	28727	97228398	11412416	0.00	-2.20	-0.53	0.00	0.00	0.00	-8.03	-29.26	-0.06	-0	4	346			
7	28772	105128457	12452414	0.00	-2.28	-0.53	0.00	0.00	0.00	-8.03	-26.97	-0.11	2	6	344			
8	28822	112628524	13452411	0.00	-2.32	-0.51	0.00	0.00	0.00	-8.03	-24.65	-0.26	9	12	338			
9	28879	119728598	14382409	0.00	-2.33	-0.47	0.00	0.00	0.00	-8.03	-22.32	-0.48	20	23	327			

10	28940	1263	28679	1526	2406	0.00	-2.31	-0.42	0.00	0.00	0.00	0.00	-8.03	-20.01	-0.77	38	40	310
11	29007	1325	28767	1607	2402	0.00	-2.26	-0.37	0.00	0.00	0.00	0.00	-8.03	-17.76	-1.11	62	64	286
12	29078	1381	28861	1680	2399	0.53	-2.20	-0.15	-0.00	0.00	0.00	0.00	-8.56	-15.55	-1.59	98	100	250
13	29153	1431	28960	1746	2395	0.43	-2.15	-0.13	-0.00	0.00	0.00	0.00	-8.99	-13.40	-2.03	138	140	210
14	29232	1475	29064	1805	2391	0.35	-2.09	-0.10	-0.00	0.00	0.00	0.00	-9.33	-11.31	-2.43	180	181	169
15	29314	1513	29173	1855	2388	0.27	-2.03	-0.07	-0.00	0.00	0.00	0.00	-9.60	-9.28	-2.77	222	224	126
16	29399	1544	29285	1896	2384	0.21	-1.97	-0.04	-0.00	0.00	0.00	0.00	-9.81	-7.31	-3.05	262	264	86
17	29486	1568	29400	1928	2380	0.15	-1.91	-0.01	-0.00	0.00	0.00	0.00	-9.96	-5.40	-3.27	298	300	50
18	29575	1586	29517	1951	2376	0.10	-1.87	0.02	-0.00	0.00	0.00	0.00	-10.06	-3.53	-3.43	326	328	22
19	29665	1596	29636	1965	2373	0.06	-1.83	0.04	-0.00	0.00	0.00	0.00	-10.12	-1.70	-3.52	343	345	55
20	29755	1600	29755	1970	2369	0.02	-1.81	0.07	-0.00	0.00	0.00	0.00	-10.13	0.11	-3.54	349	350	-0
21	29845	1596	29874	1965	2366	-0.02	-1.80	0.10	0.00	0.00	0.00	0.00	-10.12	1.91	-3.50	341	342	8
22	29935	1586	29993	1951	2363	-0.06	-1.81	0.12	0.00	0.00	0.00	0.00	-10.06	3.72	-3.39	321	323	27
23	30024	1568	30110	1928	2360	-0.10	-1.83	0.15	0.00	0.00	0.00	0.00	-9.96	5.55	-3.21	292	293	57
24	30111	1544	30225	1896	2357	-0.14	-1.86	0.18	0.00	0.00	0.00	0.00	-9.82	7.41	-2.98	255	257	93
25	30196	1513	30337	1855	2354	-0.19	-1.91	0.21	0.00	0.00	0.00	0.00	-9.63	9.32	-2.68	215	216	134
26	30278	1475	30446	1805	2351	-0.25	-1.96	0.24	0.00	0.00	0.00	0.00	-9.37	11.27	-2.34	173	175	175
27	30357	1431	30550	1746	2349	-0.32	-2.01	0.27	0.00	0.00	0.00	0.00	-9.05	13.28	-1.95	132	134	216
28	30432	1381	30649	1680	2346	-0.40	-2.06	0.30	0.00	0.00	0.00	0.00	-8.65	15.34	-1.51	93	95	255
29	30503	1325	30743	1607	2344	-0.49	-2.11	0.33	0.00	0.00	0.00	0.00	-8.16	17.45	-1.04	58	61	289
30	30570	1263	30831	1526	2342	0.00	-2.16	0.50	0.00	0.00	0.00	0.00	-8.16	19.62	-0.71	35	38	312
31	30631	1197	30912	1438	2340	0.00	-2.21	0.54	0.00	0.00	0.00	0.00	-8.16	21.82	-0.44	18	21	329
32	30688	1126	30986	1345	2339	0.00	-2.24	0.57	0.00	0.00	0.00	0.00	-8.16	24.06	-0.22	7	11	339
33	30738	1051	31053	1245	2337	0.00	-2.24	0.60	0.00	0.00	0.00	0.00	-8.16	26.30	-0.09	1	5	345
34	30783	9723	1112	1141	2336	0.00	-2.20	0.60	0.00	0.00	0.00	0.00	-8.16	28.50	-0.06	-0	4	346
35	30821	8903	1162	1033	2335	0.00	-2.13	0.59	0.00	0.00	0.00	0.00	-8.16	30.62	-0.15	2	7	343
36	30852	8063	1204	921	2334	0.00	-2.01	0.57	0.00	0.00	0.00	0.00	-8.16	32.63	-0.37	9	13	337
37	30877	7193	1237	806	2333	0.00	-1.84	0.51	0.00	0.00	0.00	0.00	-8.16	34.47	-0.73	18	23	327
38	30895	6303	1260	689	2333	0.00	-1.63	0.44	0.00	0.00	0.00	0.00	-8.16	36.10	-1.25	31	36	314
39	30906	5403	1275	571	2332	0.00	-1.37	0.35	0.00	0.00	0.00	0.00	-8.16	37.47	-1.92	48	53	297
40	30910	4503	1280	452	2332	0.00	-1.05	0.24	0.00	0.00	0.00	0.00	-8.16	38.52	-2.76	69	74	276
Segment Intradados.x Intradados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust																		
Base level: -1500 [mm] Top level: 350 [mm] Thickness at top: 1700 [mm]																		
Batter: 1:0																		
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]																		
Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right																		
0	30910	32610	350	-121.22	-1.39	-121.22	3.76	31782	31800	-0.06	-0.08	872.37	810.31					
1	30910	32610	-267	-23.06	-1.39	-144.29	2.91	31770	31790	-0.08	-0.09	859.84	819.55					
2	30910	32610	-883	-23.06	-1.39	-167.35	2.05	31760	31784	-0.09	-0.10	850.31	825.79					
3	30910	32610	-1500	-23.06	-1.39	-190.41	1.20	31753	31780	-0.11	-0.11	842.68	830.12					
Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right																		
Shape: Circular																		
Span: 2570 [mm] Rise: 1190 [mm] Q-rise: 1030 [mm]																		
Ring thickness at crown: 370 [mm] Ring thickness at springing: 370 [mm] Mortar loss: 20 [mm]																		
Masonry unit weight: 22.00 [kN/m3] Masonry strength: 7.00 [MPa]																		
Segment Intradados.x Intradados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust																		
0	32610	3503	2241	378	2315	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-9.54	-42.22	-2.45	54	60	290
1	32621	446	32255	501	2314	0.00	-1.44	-0.35	0.00	0.00	0.00	0.00	-9.54	-40.78	-1.62	36	42	308
2	32639	540	32278	623	2314	0.00	-1.74	-0.44	0.00	0.00	0.00	0.00	-9.54	-39.04	-0.98	22	27	323
3	32664	633	32311	743	2313	0.00	-1.98	-0.51	0.00	0.00	0.00	0.00	-9.54	-37.06	-0.52	11	16	334
4	32696	724	32352	860	2313	0.00	-2.17	-0.55	0.00	0.00	0.00	0.00	-9.54	-34.90	-0.22	4	9	341
5	32735	812	32402	973	2312	0.00	-2.31	-0.57	0.00	0.00	0.00	0.00	-9.54	-32.59	-0.08	-0	5	345
6	32780	897	32460	1083	2311	0.00	-2.40	-0.56	0.00	0.00	0.00	0.00	-9.54	-30.19	-0.08	0	5	345

7	32831	97932526	1187	2310	0.00	-2.45	-0.54	0.00	0.00	0.00	0.00	-9.54	-27.74	-0.19	5.9	341
8	32888	1056	32599	1287	2309	0.00	-2.46	-0.51	0.00	0.00	0.00	-9.54	-25.28	-0.40	14	17
9	32951	1129	32680	1381	2308	0.00	-2.44	-0.46	0.00	0.00	0.00	-9.54	-22.84	-0.69	28	31
10	33019	1197	32768	1468	2307	0.00	-2.39	-0.41	0.00	0.00	0.00	-9.54	-20.44	-1.03	48	51
11	33092	1260	32862	1549	2305	0.00	-2.33	-0.35	0.00	0.00	0.00	-9.54	-18.11	-1.41	74	77
12	33170	1317	32962	1622	2303	0.50	-2.26	-0.14	0.00	0.00	0.00	-10.04	-15.85	-1.94	111	114
13	33251	1368	33067	1688	2302	0.41	-2.20	-0.11	0.00	0.00	0.00	-10.45	-13.66	-2.41	151	153
14	33336	1413	33176	1746	2300	0.33	-2.13	-0.08	0.00	0.00	0.00	-10.78	-11.53	-2.83	192	194
15	33425	1451	33290	1796	2298	0.25	-2.06	-0.05	0.00	0.00	0.00	-11.03	-9.47	-3.20	232	234
16	33516	1483	33407	1836	2297	0.19	-2.00	-0.03	0.00	0.00	0.00	-11.22	-7.47	-3.50	270	271
17	33609	1508	33526	1869	2295	0.14	-1.94	0.00	0.00	0.00	0.00	-11.36	-5.53	-3.73	302	304
18	33703	1526	33648	1892	2293	0.09	-1.89	0.03	0.00	0.00	0.00	-11.46	-3.64	-3.90	328	329
19	33799	1536	33771	1905	2291	0.05	-1.86	0.05	0.00	0.00	0.00	-11.51	-1.78	-4.00	343	345
20	33895	1540	33895	1910	2290	0.02	-1.84	0.08	0.00	0.00	0.00	-11.53	0.06	-4.03	348	350
21	33991	1536	34019	1905	2288	-0.02	-1.84	0.10	0.00	0.00	0.00	-11.51	1.90	-3.98	342	344
22	34087	1526	34142	1892	2286	-0.05	-1.85	0.13	0.00	0.00	0.00	-11.46	3.75	-3.87	325	327
23	34181	1508	34264	1869	2284	-0.09	-1.87	0.15	0.00	0.00	0.00	-11.37	5.62	-3.69	299	300
24	34274	1483	34383	1836	2282	-0.14	-1.91	0.18	0.00	0.00	0.00	-11.23	7.53	-3.45	265	267
25	34365	1451	34500	1796	2280	-0.19	-1.96	0.21	0.00	0.00	0.00	-11.04	9.50	-3.14	227	229
26	34454	1413	34614	1746	2279	-0.25	-2.02	0.24	0.00	0.00	0.00	-10.80	11.52	-2.77	187	189
27	34539	1368	34723	1688	2277	-0.31	-2.08	0.28	0.00	0.00	0.00	-10.49	13.60	-2.35	147	149
28	34620	1317	34828	1622	2276	-0.39	-2.15	0.31	0.00	0.00	0.00	-10.09	15.75	-1.88	108	110
29	34698	1260	34928	1549	2274	-0.48	-2.21	0.34	0.00	0.00	0.00	-9.61	17.96	-1.36	72	74
30	34771	1197	35022	1468	2273	0.00	-2.27	0.51	0.00	0.00	0.00	-9.61	20.23	-0.99	46	49
31	34839	1129	35110	1381	2272	0.00	-2.34	0.56	0.00	0.00	0.00	-9.61	22.57	-0.65	27	30
32	34902	1056	35191	1287	2270	0.00	-2.39	0.60	0.00	0.00	0.00	-9.61	24.96	-0.37	13	16
33	34959	97935264	1187	2269	0.00	-2.41	0.63	0.00	0.00	0.00	0.00	-9.61	27.36	-0.17	4	342
34	35010	89735330	1083	2268	0.00	-2.40	0.65	0.00	0.00	0.00	0.00	-9.61	29.76	-0.07	-0	4
35	35055	81235388	9732266	0.00	-2.35	0.66	0.00	0.00	0.00	0.00	0.00	-9.61	32.12	-0.08	0	5
36	35094	72435438	8602266	0.00	-2.26	0.64	0.00	0.00	0.00	0.00	0.00	-9.61	34.38	-0.24	4	9
37	35126	63335479	7432265	0.00	-2.13	0.61	0.00	0.00	0.00	0.00	0.00	-9.61	36.51	-0.54	12	17
38	35151	54035512	6232265	0.00	-1.95	0.55	0.00	0.00	0.00	0.00	0.00	-9.61	38.46	-1.02	23	29
39	35169	44635535	5012264	0.00	-1.72	0.47	0.00	0.00	0.00	0.00	0.00	-9.61	40.18	-1.67	38	44
40	35180	35035549	3782264	0.00	-1.43	0.37	0.00	0.00	0.00	0.00	0.00	-9.61	41.61	-2.51	56	62

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 Base level: -1500 [mm] Top level: 70 [mm] Thickness at top: 6750 [mm]
 Batter: 1:0

Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 0 35180 41930 70 -356.72 1.40 -356.72 -7.57 38508 38559 -0.05 -0.05 3328.31 3370.73
 1 35180 41930 -453 -77.71 1.40 -434.44 -6.83 38508 38570 -0.07 -0.06 3328.24 3359.70
 2 35180 41930 -977 -77.71 1.40 -512.15 -6.10 38507 38580 -0.08 -0.08 3326.51 3350.33
 3 35180 41930 -1500 -77.71 1.40 -589.87 -5.37 38504 38588 -0.09 -0.09 3323.77 3341.96

Segment Left x Right x z Weight Fx Fz My Thrust left Thrust right Stress left Stress right Dist. left Dist. right
 Shape: Circular
 Span: 2720 [mm] Rise: 1350 [mm] Q-rise: 1100 [mm]
 Ring thickness at crown: 450 [mm] Ring thickness at springing: 450 [mm] Mortar loss: 20 [mm]
 Masonry unit weight: 22.00 [kN/m³] Masonry strength: 7.00 [MPa]

Segment Intrados.x Intrados.z Extrados.x Extrados.z Road.z Fx dead Fz dead My dead Fx live Fz live My live Fx passive Fx total Fz total My total Thrust in Thrust out Extra-Thrust
 0 41930 70 41480 73 2132 0.00 0.00 0.00 0.00 0.00 0.00 0.00 -8.21 -46.97 -3.47 70 77 353
 1 41935 17641487 2152132 0.00 -1.50 -0.40 0.00 0.00 0.00 0.00 -8.21 -45.47 -2.41 49 56 374
 2 41948 28241504 3552132 0.00 -1.90 -0.56 0.00 0.00 0.00 0.00 -8.21 -43.57 -1.55 32 38 392
 3 41970 38641533 4942131 0.00 -2.24 -0.68 0.00 0.00 0.00 0.00 -8.21 -41.33 -0.90 18 24 406

4	41999	48841572	6292129	0.00	-2.50	-0.77	0.00	0.00	0.00	0.00	0.00	-8.21	-38.84	-0.44	8.14	416	
5	42036	58741622	7622128	0.00	-2.69	-0.81	0.00	0.00	0.00	0.00	0.00	-8.21	-36.15	-0.18	2.7	423	
6	42081	68441682	8902126	0.00	-2.82	-0.82	0.00	0.00	0.00	0.00	0.00	-8.21	-33.33	-0.08	0	5425	
7	42134	77641751	10132124	0.00	-2.88	-0.80	0.00	0.00	0.00	0.00	0.00	-8.21	-30.45	-0.13	2.7	423	
8	42193	86441830	11302122	0.00	-2.89	-0.75	0.00	0.00	0.00	0.00	0.00	-8.21	-27.56	-0.31	10	14	416
9	42259	94741918	12412119	0.00	-2.85	-0.68	0.00	0.00	0.00	0.00	0.00	-8.21	-24.70	-0.60	23	27	403
10	42332	102542015	13452115	0.00	-2.78	-0.60	0.00	0.00	0.00	0.00	0.00	-8.21	-21.93	-0.97	44	47	383
11	42410	109742119	14402112	0.00	-2.67	-0.51	0.00	0.00	0.00	0.00	0.00	-8.21	-19.26	-1.38	73	75	355
12	42494	116342230	15272108	0.52	-2.56	-0.23	0.00	0.00	0.00	0.00	0.00	-8.73	-16.69	-1.99	117	119	311
13	42582	122142348	16062104	0.41	-2.46	-0.19	0.00	0.00	0.00	0.00	0.00	-9.14	-14.23	-2.54	166	168	262
14	42675	127342472	16752100	0.31	-2.35	-0.14	0.00	0.00	0.00	0.00	0.00	-9.45	-11.89	-3.02	218	220	210
15	42772	131742600	17332096	0.23	-2.23	-0.10	0.00	0.00	0.00	0.00	0.00	-9.68	-9.66	-3.43	271	273	157
16	42872	135442733	17822091	0.17	-2.13	-0.06	0.00	0.00	0.00	0.00	0.00	-9.85	-7.53	-3.77	322	323	107
17	42974	138342869	18202086	0.11	-2.03	-0.02	0.00	0.00	0.00	0.00	0.00	-9.96	-5.50	-4.03	367	368	62
18	43078	140343008	18482081	0.07	-1.95	0.02	0.00	0.00	0.00	0.00	0.00	-10.03	-3.55	-4.21	402	403	27
19	43184	141643149	18642075	0.04	-1.89	0.05	0.00	0.00	0.00	0.00	0.00	-10.07	-1.66	-4.31	423	424	255
20	43290	142043290	18702070	0.01	-1.85	0.08	0.00	0.00	0.00	0.00	0.00	-10.09	0.20	-4.33	429	430	0
21	43396	141643431	18642064	-0.01	-1.84	0.11	0.00	0.00	0.00	0.00	0.00	-10.07	2.04	-4.27	418	419	11
22	43502	140343572	18482059	-0.04	-1.85	0.15	0.00	0.00	0.00	0.00	0.00	-10.04	3.89	-4.13	391	393	37
23	43606	138343711	18202053	-0.07	-1.88	0.18	0.00	0.00	0.00	0.00	0.00	-9.97	5.77	-3.91	353	355	75
24	43708	135443847	17822048	-0.10	-1.94	0.22	0.00	0.00	0.00	0.00	0.00	-9.87	7.71	-3.62	307	308	122
25	43808	131743980	17332042	-0.14	-2.01	0.26	0.00	0.00	0.00	0.00	0.00	-9.73	9.72	-3.26	256	257	173
26	43905	127344108	16752036	-0.20	-2.20	0.10	0.31	0.00	0.00	0.00	0.00	-9.53	11.81	-2.83	204	206	224
27	43998	122144232	16062031	-0.27	-2.19	0.35	0.00	0.00	0.00	0.00	0.00	-9.26	14.01	-2.35	154	156	274
28	44086	116344350	15272026	-0.35	-2.29	0.40	0.00	0.00	0.00	0.00	0.00	-8.90	16.30	-1.82	107	110	320
29	44170	109744461	14402022	-0.46	-2.39	0.45	0.00	0.00	0.00	0.00	0.00	-8.45	18.69	-1.24	66	68	362
30	44248	102544565	13452018	0.00	-2.50	0.66	0.00	0.00	0.00	0.00	0.00	-8.45	21.19	-0.84	39	42	388
31	44321	94744662	12412014	0.00	-2.60	0.74	0.00	0.00	0.00	0.00	0.00	-8.45	23.79	-0.50	20	23	407
32	44387	86444750	11302010	0.00	-2.68	0.81	0.00	0.00	0.00	0.00	0.00	-8.45	26.47	-0.24	7	11	419
33	44446	77644829	10132006	0.00	-2.73	0.86	0.00	0.00	0.00	0.00	0.00	-8.45	29.20	-0.09	1	5	425
34	44499	68444898	8902004	0.00	-2.73	0.89	0.00	0.00	0.00	0.00	0.00	-8.45	31.93	-0.07	-0	5	425
35	44544	58744958	7622002	0.00	-2.68	0.89	0.00	0.00	0.00	0.00	0.00	-8.45	34.62	-0.21	3	8	422
36	44581	48845008	629-1	0.00	-2.57	0.86	0.00	0.00	0.00	0.00	0.00	-8.45	37.19	-0.51	11	16	414
37	44610	38645047	494-1	0.00	-2.41	0.80	0.00	0.00	0.00	0.00	0.00	-8.45	39.60	-1.01	22	28	402
38	44632	28245076	355-1	0.00	-2.17	0.70	0.00	0.00	0.00	0.00	0.00	-8.45	41.77	-1.69	37	43	387
39	44645	17645093	215-1	0.00	-1.86	0.57	0.00	0.00	0.00	0.00	0.00	-8.45	43.63	-2.58	55	62	368
40	44650	7045100	73-1	0.00	-1.48	0.40	0.00	0.00	0.00	0.00	0.00	-8.45	45.11	-3.67	78	84	346

McGraw Hill - Viewing Purposes Only!

WS Atkins Ireland Limited
Unit 2B
2200 Cork Airport Business Park
Cork
T12 R279

Tel: +353 21 429 0300

Meath County Council - Viewing Purposes Only!

© WS Atkins Ireland Limited except where stated otherwise