

\mathbf{O}

APPENDIX 8-1

HES BOREHOLE LOG

HYDRO-ENVIRONMENTAL SERVICES

Monitoring Well Log

Well No.: MW21-01

Project No: P1574-0

Client: MKO

Date started: 15/12/2023

Easting: 538162.5 Northing: 743701.7

Site: Laurclavagh WF, Co. Galway

Date finished: 15/12/2023

Elevation: 42.86mOD

SUBSURFACE PROFILE Water Level Depth/Elev. Comments Description Well Completion Details Symbol Depth **Ground Surface** 42.9 0 GL 0.0 Firm brown TOPSOIL -ŕ Ť т Medium dense very silty SAND & GRAVEL w/ LS cobbles & boulders Gravel drainage area Medium strong weathered grey LIMESTONE w/ weathered clay Drill cuttings damp at joints 10-Р 9mbgl, keeping dust 30.9 down 12.0 Strong to very strong LIMESTONE Plain pipe 0-37mbgl 20 200 30 30mbgl Bentonite Top seal 35mbgl 37bgl 40 ¥ Minor water strike at 41mbgl Filter Material(Sand / Gravel) $eqref{eq: started}$ Slotted pipe 37-55mbgl 50 -12.1 55mbgl 55.0 60 **Remarks:** Drilling Contractor: Petersen Drilling Services Ltd. Drilling type: Scale as shown Logged by: AK Sheet: 1 of 1 HYDRO-ENVIRONMENTAL SERVICES 22 Lower Main Street Dungarvan Co. Waterford Tel: 058-44122 Email: info@hydroenvironmental.ie

Monitoring Well Log

Date started: 13/12/2023

Well No.: MW21-02

Easting: 535264.3

Northing: 743746.5

Elevation: 32.7mOD

Project No: P1574-0 YDRO-ENVIRONMENTAL SERVICES Client: MKO Symbol Depth 0 clay

Site: Laurclavagh WF, Co. Galway

Date finished: 13/12/2023

SUBSURFACE PROFILE Water Level Depth/Elev. Comments Description **Well Completion Details Ground Surface** 32.7 0.0 GL Firm brown TOPSOIL Firm to stiff brown silty gravelly 29.9 2.8 Firm to stiff light brown gravelly Gravel drainage area clay. Very frequent limestone fragments Plain pipe 0-21.5mbgl Drill cuttings damp at 7mbgl, keeping dust down 10 19.5 13.2 Firm to stiff greyish brown sandy gravelly clay, highly weathered limestone 16mbgl 16.2 16.5 Very weak highly weathered Bentonite Top seal grey limestone 13.9 19mbgl 18.8 Medium strong dark grey ∇ Major water strike fast limestone with some fractures 20 flowing at 19.5m Filter Material (Sand / Gravel) 21.5bgl • Slotted pipe 21.5-24mbgl 8.7 - 24mbgl 24.0 **Remarks**: Drilling Contractor: Petersen Drilling Services Ltd. Drilling type: Scale as shown Logged by: AK Sheet: 1 of 1 HYDRO-ENVIRONMENTAL SERVICES 22 Lower Main Street Dungarvan Co. Waterford Tel: 058-44122 Email: info@hydroenvironmental.ie

Monitoring Well Log

Well No.: MW21-03

Project No: P1574-0

Site: Laurclavagh WF, Co. Galway

Date started: 14/12/2023

Easting: 535587.4

Northing: 743205.6

Client: MKO

YDRO-ENVIRONMENTAL SERVICES

Date finished: 14/12/2023

Elevation: 35.558mOD

