

East Meath - North Dublin Grid Upgrade Environmental Impact Assessment Report (EIAR): Volume 3

Appendix A13.1 - Inventory of Archaeology, Architectural Heritage, and Cultural Heritage

EirGrid

March 2024



Contents

Appendix A13.1 Inventory of Archaeology, Architectural Heritage, and Cultural Heritage	1
1. Inventory of Archaeological Assets	2
2. Inventory of Architectural Heritage Assets.....	14
3. Inventory of Gardens and Designed Landscapes	17
4. Inventory of Cultural Heritage Assets	25
5. Inventory of LiDAR Assets.....	45
6. Inventory of Townland Boundaries.....	77

Appendix A13.1 Inventory of Archaeology, Architectural Heritage, and Cultural Heritage

1. Inventory of Archaeological Assets

Unique Reference Number	AY_07	Reference Number(s)	ME050-030
Figure Number	Figure 13.1 in Volume 4	Legal Status	-
Townland	Dunboyne	Site Type	Field system
Easting / Northing	700971 / 743204	Distance from Proposed Development	0m
Significance	Low		
Description	<p>Situated on a fairly level landscape. Aerial photographs by L. Swan (LS_AS_67BWN_00132) from the early 1970s record elements of a rectangular field system covering an extensive area (dims c. 220m NW-SE; c. 220m NE-SW) between the large enclosure (ME050-027----) to the SE and the possible church site (ME050-029----) to the NW, but not connected directly with either and different in character to both. The fields are large and rectangular (dims c. 60-120m (metres) x c. 30-50m), and appear to be defined by single ditches that correspond closely to features represented on the Down Survey (1656-8) barony and parish maps. They also run generally parallel with the current boundaries but are probably medieval in date.</p> <p>The area was subject to a partial magnetic gradiometer and earth resistance survey (00R0014) by I. Elliot (2000) where the features recorded in the aerial photographs are confirmed. Elliott's results suggest that the enclosing elements consisted primarily of hedges. The NE-SW by-pass road (R157) for Dunboyne cut through the area, and centre-line testing (04E0487) by R. O'Hara (2004, 10-11) noted four of these ditches of uniform character (Wth c. 1.2m; D 0.5m) with homogenous fills from which nothing was recovered except some snail shells (excavations.ie 2004:1229). Further excavation (E003024) by R. Elliott (excavations.ie 2004:1554) of Dunboyne 4 recorded the drain features in detail and recovered post-medieval and modern ceramics from them. The long structure (ME050-062001-) and its associated possible kiln (ME050-062002-) were also identified and excavated but they are unrelated to the fields (Elliott 2008).^[1]</p> <p><u>GoogleEarth</u></p> <p>05/2013 - large circular enclosure (ME050-029) to north of field (outside study area), with linear features, interpreted as former field boundaries forming a field system.</p> <p>07/2013 - Possible former field boundaries visible across field (also in field to the south-west; LI_67).</p> <p>05/2017 - enclosure and former field boundaries visible.</p> <p>03/2022 - Circular enclosure vaguely perceptible in northern portion of field.^[2]</p> <p>Also visible on Digital Globe Aerial Imagery as straight sided fields.^[3]</p> <p>Single fill ditches and drains containing post-medieval and modern ceramics.^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. Archaeological Survey of Ireland SMR 2. GoogleEarth, various 3. Digital Globe Aerial Imagery 4. Elliott, R. and V. Ginn (2008). M3 Clonee-North of Kells Contract 1 Clonee – Dunshaughlin Report on the Archaeological Excavation of Dunboyne 4, Co. Meath. Ministerial Directions No. A017/002 E3024. 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	AY_08	Reference Number(s)	ME050-062001
Figure Number	Figure 13.1 in Volume 4	Legal Status	-
Townland	Dunboyne	Site Type	Structure (site of)
Easting / Northing	701066 / 743342	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<p>Situated on a slight rise in a generally level landscape. Archaeological testing (04E0487) by R. O'Hara on the link-road (R157) for Dunboyne set aside this area for resolution as Dunboyne 4 (excavations. ie 2004:1229). Archaeological excavation (E003024) by R. Elliott (excavations.ie 2004:1554) recorded elements of the field system (ME050-030----) as well as this prehistoric structure and the possible kiln (ME050-062002-). Nineteenth century quarrying, the importation of soils and subsequent ploughing severely truncated most of the archaeological features.</p> <p>Thirty one stake and post-holes were recorded in one area, and twenty three of these create a long narrow structure (dims 13m plus ENE-WSW; 3.5m NNW-SSE) extending outside the road-take to the WSW. A strictly regular pattern is not discernible but two post-holes just outside the S line towards the E end have ramps from the S, and a C14 date of 2117-1779 cal. BC was returned from one of these. A large post-hole at the E edge also has a ramp at the E edge. This produced two sherds of Middle-Late Bronze Age pottery together with cremated bone, from which a C14 date of 971-804 cal. BC was returned. A sample of charcoal from another post-hole yielded a date of 1115-853 cal. BC. The nature of this structure is uncertain, but it has neither slot-trenches nor a hearth, and the fairly even distribution of the post-holes suggests that it could be a post-alignment, except that its scale is reduced. ^{[1] [2]}</p>		
Sources	<ol style="list-style-type: none"> 1. Archaeological Survey of Ireland SMR 2. https://excavations.ie/report/2004/Meath/0012351/ [Accessed April 2023] 		

Unique Reference Number	AY_09	Reference Number(s)	ME050-062002
Figure Number	Figure 13.1 in Volume 4	Legal Status	-
Townland	Dunboyne	Site Type	Kiln (site of)
Easting / Northing	701098 / 743314	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<p>Situated on a slight rise in a generally level landscape. Archaeological testing (04E0487) by R. O'Hara on the link-road (R157) for Dunboyne set aside this area for resolution as Dunboyne 4 (excavations. ie 2004:1229). Archaeological excavation (E003024) by R. Elliott (excavations.ie 2004:1554) recorded elements of the field system (ME050-030----) as well as this structure that is interpreted as a kiln and the prehistoric structure (ME050-062001-). This consists of a large sub-oval pit (max. dims 3.35m N-S; 1.3m E-W; D 0.43m) with a clay lining. It has two bowls with a connecting flue but many of the fills contained burnt stone. Some uncharred grain was recovered, but a sample of hazel charcoal from a basal fill yielded a C14 determination of 2117-1779 cal. BC. This sample must have been contaminated somehow. A subrectangular cut (dims 1.9m x 1.35m; D 0.17m) for a bellows was connected to the S bowl by a narrow channel, but much of the bellows pit was damaged by a large modern quarry to its S. (Elliott 2008, 3-4). ^{[1] [2]}</p> <p>While this site provides an indication of possible activity in this location, given it has been removed and developed, it is no longer an asset. ^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Archaeological Survey of Ireland SMR 2. https://excavations.ie/report/2004/Meath/0012351/ [Accessed April 2023]. 3. Jacobs July 2023 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	AY_11	Reference Number(s)	ME050-057
Figure Number	Figure 13.1 in Volume 4	Legal Status	-
Townland	Bennetstown	Site Type	Excavation – miscellaneous
Easting / Northing	701490 / 743915	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<p>Situated on the E-facing slope of a rise in a fairly level landscape. Centre-line testing (04E0488) by R. O'Hara on the Dunboyne link road (R157) to the M3 (excavations.ie 2004:1183) identified archaeological features that were fully excavated (E003027) by R. Elliott in February and March 2006 as Bennetstown 3 (excavations.ie 2006:1509). A group of eight post-holes (diam. 0.2-0.6m; D 0.2-0.66m) from which most of the posts had been removed rather than being burnt or left to rot form a rough rectangular structure (max. int. dims 4.3m NE-SW; 2.6m NW-SE) that might have been open (Wth c. 1.1m) on the NW side. Two small pits (dims 0.67m x 0.32m; D 0.16m; diam. 0.37-0.39m; D 0.13m) were just to the W and two patches of burnt clay (dims 1.2m x 0.7m; T 0.1m: 0.63m x 0.24m; T 0.07m) 11m to the NW may be the remains of hearths. There were four other pits (dims 0.69m x 0.41m; D 0.3m to 1.15m x 1.04m; D 0.17m) c. 20m to the W, some with charcoal and burnt bone inclusions, and a curving trench (dims 2m x 0.5m; D 0.09m) could represent a slot-trench for a hut-site but there is no further evidence of it. A charcoal sample from its fill produced a C14 date of 1490-1310 cal. BC, which accords well with a sherd of coarse pottery from the same context. (Elliott and Ginn 2008).^[1]</p> <p>^[2]</p> <p>While this site provides an indication of possible activity in this locations, given it has been removed and developed, it is no longer an asset.^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Archaeological Survey of Ireland SMR 2. https://excavations.ie/report/2004/Meath/0012305/ [Accessed April 2023] 3. Jacobs July 2023 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	AY_12	Reference Number(s)	ME050-058
Figure Number	Figure 13.1 in Volume 4	Legal Status	-
Townland	Bennetstown	Site Type	Burnt mound (site of)
Easting / Northing	701594 / 743995	Distance from Proposed Development	14m to the south-east of the Proposed Development
Significance	Very Low / Negligible		
Description	<p>Situated in the valley of the N-S Tolka or Tullaghanoge River, with a canalised NW-SE section of the stream just to the NE, although the original meandering stream is c. 50m to the NE. Centre-line testing (04E0488) by R. O'Hara on the Dunboyne link road (R157) to the M3 (excavations.ie 2004:1183) identified a spread of dark soil that was partially excavated (E003026) by R. Elliott in January 2006 as Bennetstown 2 (excavations.ie 2006:1508). It consisted of a spread (dims 11.5m N-S; 4.5m E-W; T 0.2m plus) of black silty clay with burnt and broken stones that extended outside the excavated area to the NW. It was over a black/brown clay peat, into which a small pit (dims 0.4m x 0.34m; D 0.12m) had been cut, and it was covered by alluvial layers of silt. A rectangular pit (dims c. 1.7m x c. 0.5m plus; D 0.23) that cut into the top of the burnt mound was modern, and a sample of charcoal from the mound produced a C14 date of 2460-2200 cal. BC. No trough was recognised but much of the monument lies outside the excavated area to the NW. (Elliott and Ginn 2008) ^{[1] [2]}</p> <p>While this site provides an indication of possible activity in this location, given it has been removed and developed, it is no longer an asset. ^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Archaeological Survey of Ireland SMR 2. https://excavations.ie/report/2004/Meath/0012305/ [Accessed April 2023]. 3. Jacobs July 2023 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	AY_18	Reference Number(s)	ME051-002
Figure Number	Figure 13.1 in Volume 4	Legal Status	Recorded Monument
Townland	Ballintry	Site Type	Enclosure
Easting / Northing	704748 / 744981	Distance from Proposed Development	28m to the south of the Proposed Development
Significance	Medium		
Description	<p>Located on a fairly level landscape with an E-W road just to the N. The faint cropmark of a circular enclosure (diam. c. 50m) defined by a single fosse is visible on oblique aerial photographs (CUCAP: BDK006-007) from 1970. A gradiometer survey (18R01789) by J. Leigh proved inconclusive, and archaeological testing (18E0445) by F. O'Carroll in a trench parallel with the road bank and probably just N of the enclosure produced no evidence of it, although an area of burning did come to light and is preserved in situ. (O'Carroll 2019).^[1]</p> <p>Not depicted on historic mapping.^{[2][3]}</p> <p>Likely construction of a modern house has truncated the enclosure; however, the south-eastern portion may remain in the pasture field to the east of the house and garden. [1995]^[4]</p> <p>Actual location of the enclosure is in the pasture field to the south of Belgree Lane^[5]</p> <p>Adjacent to a field named 'Raheens' meaning 'The Little Rath'.^[6]</p> <p>Archaeological investigations to the north of the enclosure identified deposits that were preserved in situ.^[7]</p>		
Sources	<ol style="list-style-type: none"> 1. NMS, 1996, Record of Monuments and Places (County Meath) 2. Ordnance Survey 6" (1837) MH051 3. Ordnance Survey 25" (1911) MH051-01 4. OSi Aerial Imagery, 1995 5. https://www.cambridgeairphotos.com/location/bdk006/ and https://www.cambridgeairphotos.com/location/bdk007/ [Accessed August 2022] 6. Meath Field Names Project (n.d.). Meath Field Names Project. [Online] Available from: https://meathfieldnames.com/ [Accessed April 2023]. 7. O'Carroll, F. 2019 Final Report on Archaeological Pre-Development Testing at Ballintry, Kilbride, Co. Meath. Licence: 18E0445 		

Unique Reference Number	AY_21	Reference Number(s)	DU011-091
Figure Number	Figure 13.1 in Volume 4	Legal Status	-
Townland	Ward Upper	Site Type	Habitation site (site of)
Easting / Northing	709410 / 744364	Distance from Proposed Development	17m to the south-east of the Proposed Development
Significance	Very Low / Negligible		
Description	<p>Excavations in advance of the N2 Finglas-Ashbourne Road Scheme in 2004 revealed a random grouping of features including a small burnt pit, a linear feature and a small pit or cremation (03E1358). The pit (diam 1.65m, D 0.65m) produced 280 pieces of prehistoric pottery of Late date (NRA).^[1]</p> <p>While this site provides an indication of possible activity in this location, given it has been removed and developed, it is no longer an asset.^[2]</p>		
Sources	<ol style="list-style-type: none"> 1. Archaeological Survey of Ireland SMR 2. Jacobs July 2023 		

Unique Reference Number	AY_23	Reference Number(s)	DU011-039001
Figure Number	Figure 13.1 in Volume 4	Legal Status	Recorded Monument (also AH_06; a Protected Structure)
Townland	Ward Lower	Site Type	Church
Easting / Northing	709652 / 744834	Distance from Proposed Development	23m to the north-west of the Proposed Development
Significance	High		
Description	<p>Dedicated to St Brigid the church fell into ruin between 1630 and 1650 (Fingal Historic Graves Project 2008). This site was described as the walls of an old church in the Civil survey (1654-6) (Simington 1945, 235). The foundations of the medieval parish church can be traced within a raised, walled graveyard. In the 1992 report they appeared as a low rectangular mound, aligned WNW-ESE (dims. L 14m, Wth 8-9m, H.1m). The church has since undergone 'improvement'. It is defined by a rectilinear stone wall with a grass ramp built into south wall and return in north wall with a stone built concrete roofed alcove in east wall. The alcove contains a statute of the Blessed Virgin Mary. Wall stands to 0.75m-1m in height and is extensively ribbon pointed. Presumed enclosure of original mound remains. A fragment of a limestone window jamb of late medieval date has been re-used as a headstone east of the church. ^[1]</p> <p>Depicted on Rocque 1860 as 'the old church'. ^[2]</p> <p>LI_43:</p> <ul style="list-style-type: none"> - A sub-circular area, truncated by the R121 to the south-east, measuring approximately 60m by 45m across. Includes a church building (in ruins) and monuments laid out in rows across the church yard. - Depicted on historic Ordnance Survey mapping as 'Church' and 'Grave Yd.', with the church identified as 'in ruins' on later editions. - Visible on aerial imagery. ^[3] <p>Slightly elevated position, enclosed in an oval walled graveyard. Wall roughly coursed, rubblestone with a dressed cope. Modern roadside shrine, and shrine installed at the footings of the medieval parish church. Views are across flat agricultural fields to the north, west and south and across the busy road (R121) towards houses to the east. ^[4]</p> <p>13km from Dublin at the side of the road which runs from Mulhuddart to the road between Finglas and Ashbain. 'Pleasant rural setting' surrounded on three sides by fields of barley and to the east by the road. Limestone wall encloses the entire site. Higher than surrounding land indicating use as a graveyard for a very long period of time. At the centre there are the foundations on an ancient church which, although in 'good repair' do not extend higher than 1m at any point. At the eastern end of the ruins a small 'grotto' has been 'tastefully' erected by Dublin County Council. Few old headstones on the south side of the church ruins. The oldest date - Lacy #59 - 15 May 1720 (oldest stone recorded), a limestone Maltese Cross on IHS in narrow starburst. Presently in use and well kept by Dublin County Council. ^[5]</p>		
Sources	<ol style="list-style-type: none"> 1. NMS, 1998, Record of Monuments and Places (County of Fingal) 2. https://www.lbrowncollection.com/dublin-parishes-composite-maps-1865/ [Accessed April 2023] 3. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 4. Jacobs site inspection and walkover survey, June 2023 5. Egan, M. J. S. (1991). Dublin City and County Graveyards. Ireland Branch of the Irish Genealogical Research Society. Dublin. 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	AY_24	Reference Number(s)	DU011-039002
Figure Number	Figure 13.1 in Volume 4	Legal Status	Recorded Monument (also AH_06; a Protected Structure)
Townland	Ward Lower	Site Type	Graveyard
Easting / Northing	709652 / 744825	Distance from Proposed Development	3m to the north-west of the Proposed Development
Significance	High		
Description	<p>A raised, roughly oval, walled graveyard (L 70m, Wth 50m) which encloses the foundations of the medieval parish church (DU011-039001-). Fragment of a limestone window jamb of late medieval date is used as gravemarker in the graveyard E of church. The memorials are 19th/20th century in date. The site was formerly surveyed (Egan 1992). Still in use. ^[1]</p> <p>Depicted on Rocque 1960 as 'the old church'. ^[2]</p> <p>LI_43:</p> <ul style="list-style-type: none"> - A sub-circular area, truncated by the R121 to the south-east, measuring approximately 60m by 45m across. Includes a church building (in ruins) and monuments laid out in rows across the church yard. - Depicted on historic Ordnance Survey mapping as 'Church' and 'Grave Yd.', with the church identified as 'in ruins' on later editions. - Visible on aerial imagery. ^[3] <p>Slightly elevated position, enclosed in an oval walled graveyard. Wall roughly coursed, rubblestone with a dressed cope. Modern roadside shrine, and shrine installed at the footings of the medieval parish church. Views are across flat agricultural fields to the north, west and south and across the busy road (R121) towards houses to the east. ^[4]</p> <p>13km from Dublin at the side of the road which runs from Mulhuddart to the road between Finglas and Ashbain. 'Pleasant rural setting' surrounded on three sides by fields of barley and to the east by the road. Limestone wall encloses the entire site. Higher than surrounding land indicating use as a graveyard for a very long period of time. At the centre there are the foundations on an ancient church which, although in 'good repair' do not extend higher than 1m at any point. At the eastern end of the ruins a small 'grotto' has been 'tastefully' erected by Dublin County Council. Few old headstones on the south side of the church ruins. The oldest date - Lacy #59 - 15 May 1720 (oldest stone recorded), a limestone Maltese Cross on IHS in narrow starburst. Presently in use and well kept by Dublin County Council. ^[5]</p>		
Sources	<ol style="list-style-type: none"> 1. NMS, 1998, Record of Monuments and Places (County of Fingal) 2. https://www.lbrowncollection.com/dublin-parishes-composite-maps-1865/ [Accessed April 2023] 3. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 4. Jacobs site inspection and walkover survey, June 2023 5. Egan, M. J. S. (1991). Dublin City and County Graveyards. Ireland Branch of the Irish Genealogical Research Society. Dublin. 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	AY_25	Reference Number(s)	DU011-068
Figure Number	Figure 13.1 in Volume 4	Legal Status	Recorded Monument
Townland	Ward Upper	Site Type	Castle - unclassified
Easting / Northing	710002 / 745096	Distance from Proposed Development	36m to the north of the Proposed Development
Significance	Medium		
Description	<p>The Civil survey (1654-6) describes the walls of an old castle at the Ward, held by Sir James Ware (Simington 1945, 235). This may have been formerly located where Ward House is situated just NE of the medieval parish church (DU011-039----). Austin Cooper's in 1779 describes the remains of an 'old castle. It is nothing more than the lower storey....built of small flat stones and is in a ruinous condition. The door is at one end opposite a window and the left corner as you enter a Gothic door which leads to the Orchard where there are pieces of other stone walls'. There are remains of an orchard to the rear of the present Ward House but no visible remains of a castle. ^[1]</p> <p>A ruined church is depicted on historic mapping, no castle is depicted. ^{[2][3][4]}</p> <p>Described as 'the walls of an olde castle'. Part of a holding with other buildings including the ruins of an old church [AY_23]. ^[5]</p> <p>The first proprietor of the Ward after the English invasion caused to be here constructed a large fosse called "Halfpenny Trench... At the close of the sixteenth century a castle was garrisoned here". ^[6]</p> <p>Not visible from the road. High stone boundary wall. ^[7]</p>		
Sources	<ol style="list-style-type: none"> 1. NMS, 1998, Record of Monuments and Places (County of Fingal) 2. https://www.lbrowncollection.com/dublin-parishes-composite-maps-1865/ [Accessed April 2023] 3. http://www.dublinhistoricmaps.ie/maps/1600-1799/index.html [Accessed August 2022] 4. https://iiif.lib.harvard.edu/manifests/view/ids:10653105 [Accessed August 2022] 5. https://www.irishmanuscripts.ie/digital/The_Civil_Survey_AD_1654-56_Vol_VII_County_of_Dublin/The_Civil_Survey_AD_1654-56_Vol_VII_County_of_Dublin.pdf [Accessed August 2022] 6. D'Alton, J. (1838). The History of the County of Dublin. Hodges and Smith, College-Green. Dublin. 7. Jacobs site inspection and walkover survey, June 2023 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	AY_29	Reference Number(s)	DU011-023001
Figure Number	Figure 13.1 in Volume 4	Legal Status	Recorded Monument
Townland	Common	Site Type	Ringfort - unclassified
Easting / Northing	712321 / 745846	Distance from Proposed Development	50m to the north of the Proposed Development
Significance	Medium		
Description	<p>Located in a field of low-lying pasture. The 1837 OS 6-inch map shows an oval enclosure (50m N-S; 30m E-W). The depiction of the site on the current OS 6-inch map suggests that it was a ringfort. An archaeological assessment of the site in the winter of 1999 revealed no archaeological evidence for the monument. A dwelling had been constructed on the site (Conway, 2000, 57-8).^[1]</p> <p>An oval enclosure is depicted nearby on historic mapping but is not depicted on later mapping.^{[2][3]}</p> <p>This location has been developed. Archaeological testing in advance of proposed residential development in this location did not identify any features of archaeological significance or relating to this asset.^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. NMS, 1998, Record of Monuments and Places (County of Fingal) 2. Ordnance Survey 6" (1837) MH051 3. Ordnance Survey 25" (1908) DN011-10 4. https://excavations.ie/report/1999/Dublin/0004056/ [Accessed August 2022] 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	AY_41	Reference Number(s)	DU011-043
Figure Number	Figure 13.1 in Volume 4	Legal Status	Recorded Monument
Townland	Forrest Great	Site Type	Ringfort - unclassified
Easting / Northing	715314 / 744668	Distance from Proposed Development	10m to the north-west of the Proposed Development
Significance	Medium		
Description	<p>Situated on level grassland. This site was formerly a platform type ringfort (diam. c. 50m) with a waterlogged external fosse (Healy 1975, 23). It's southeastern quadrant has been truncated by works associated with Dublin Airport but the majority of the ringfort is visible as a crop mark on the Bird's Eye viewer of Bing.^[1]</p> <p>Depicted on First Edition Ordnance Survey mapping.^[2]</p> <p>LI_52:</p> <ul style="list-style-type: none"> - A circular feature measuring approximately 80m in diameter, truncated by a roundabout on the R108. - Corresponds with a ringfort identified on the RMP (AY_41; DU011-043). - The 'fort' is depicted on historic Ordnance Survey mapping (1843, 1908). - This feature is also visible on aerial imagery (GoogleEarth, various; https://ncap.org.uk/frame/11-1-2-76-41, https://ncap.org.uk/frame/11-1-2-76-42).^[3] <p>Located within an arable field to the north of the R108. The site has been interpreted as a platform-type ringfort with a waterlogged external fosse (ditch). Modern infrastructure, including airport lighting, form part of this asset's setting, along with traffic / plane noise. Visible as a very low rise to the south-east of the field, a ditch is vaguely perceptible in sections in the grass.^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. NMS, 1998, Record of Monuments and Places (County of Fingal) 2. Ordnance Survey 6" (1843) DN011 3. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 4. Jacobs site inspection and walkover survey, June 2023 		

Unique Reference Number	AY_43	Reference Number(s)	DU011-046
Figure Number	Figure 13.1 in Volume 4	Legal Status	Recorded Monument
Townland	Cloghran	Site Type	Ringfort - unclassified
Easting / Northing	717244 / 744290	Distance from Proposed Development	14m to the south of the Proposed Development
Significance	Medium		
Description	<p>Named 'fort' on the 1837 OS 6-inch map. It was partly demolished in 1822 and cleared away in 1873 (Healy 1975, 24). The area has been incorporated into an extension to the recently constructed runway at Dublin Airport. Not visible at ground level.^[1]</p> <p>Comprises a 'fort' depicted on First Edition Ordnance Survey mapping (1837 – 1842) and has since been redeveloped as part of Dublin Airport.^[2]</p>		
Sources	<ol style="list-style-type: none"> 1. NMS, 1998, Record of Monuments and Places (County of Fingal) 2. Ordnance Survey 6" (1843) DN011 		

Unique Reference Number	AY_47	Reference Number(s)	DU015-001
Figure Number	Figure 13.1 in Volume 4	Legal Status	Recorded Monument
Townland	Cloghran	Site Type	Mound
Easting / Northing	718868 / 743533	Distance from Proposed Development	0m
Significance	Medium		
Description	<p>In field of pasture N of farm house. An aerial photograph (FSI 453/2) taken in 1971 shows evidence for an earthen mound (diam. c. 15m). Not visible at ground level. ^[1]</p> <p>Not depicted on historic mapping. ^{[2][3]}</p> <p>Not visible on aerial imagery, including 1970s aerial photographs or available GoogleEarth epochs. ^{[4][5]}</p> <p>Not visible on the ground (located within an arable field). ^[6]</p> <p>The RMP file for the site states that an aerial photograph from the Fairey Survey of Ireland, 453/2 in 1971 shows evidence for an earthen mound c.15m in diameter. The copy of the photograph from the Fairey Survey which is in the RMP file clearly shows the circular site, located c.50m north-west of the existing farmhouse, and c.30m west of the eastern hedgerow of the field. The file notes, which were compiled in 1993, state that this is no longer visible. The condition of the monument is recorded in the file as "no visible trace". A field inspection of this field failed to find any evidence of the monument. ^{[7][8]}</p>		
Sources	<ol style="list-style-type: none"> 1. NMS, 1998, Record of Monuments and Places (County of Fingal) 2. Ordnance Survey 6" (1843) DN015 3. Ordnance Survey 25" (1909) DN015-01 4. https://ncap.org.uk/frame/11-1-2-76-8?pos=0 [Accessed April 2023] 5. Google Earth, various 6. Jacobs site inspection and walkover survey, June 2023 7. Duffy, C., 2008, Archaeological Assessment including Test Trenching of a Site at Stockhole Lane, Cloghran, Co. Dublin. https://heritagemaps.ie/documents/Therefore_ArchaeologyReports/08E0333.pdf [Accessed October 2023]. 8. National Monuments Service Archive, ASI Record [provided November 2023] 		

2. Inventory of Architectural Heritage Assets

Unique Reference Number	AH_06	Reference Number(s)	RPS 660
Figure Number	Figure 13.2 in Volume 4	Legal Status	Protected Structure (Also AY_23 and AY_24; Recorded Monuments)
Townland	Ward Lower	Site Type	Church in ruins
Easting / Northing	709654 / 744837	Distance from Proposed Development	3 - 23m to the north-west of the Proposed Development
Significance	High		
Description	<p>St. Brigid's Church & Graveyard (in ruins) Remains of foundations of medieval parish church within raised, walled graveyard. ^[1] A ruined church is depicted on Rocque's map (1760) and a map of the environs of Dublin (1853). ^{[2][3]} A church and graveyard are depicted on historic Ordnance Survey mapping, with a 'Church Well' to the south, opposite an 'Old Quarry'. Later mapping depicts the church 'in ruins'. ^{[4][5]} Graveyard remains in use. ^[6] A modern roadside shrine and a "grotto" to the east of the church have been installed. The elevated interior of the site suggests the graveyard has been in use for a long period of time and the oldest headstone recorded dates to 1720. ^[7] Located immediately adjacent to the R121. Views to the west are open over the surrounding fields; however, are limited to the east and north by buildings and to the south by established trees. Views east are across the busy R121 towards a house. ^[8]</p>		
Sources	<ol style="list-style-type: none"> 1. https://www.fingal.ie/sites/default/files/2019-04/2017-2023_dev_plan_record_of_protected_structures.pdf [Accessed August 2022] 2. http://www.dublinhistoricmaps.ie/maps/1600-1799/index.html [Accessed August 2022] 3. https://iiif.lib.harvard.edu/manifests/view/ids:10653105 [Accessed August 2022] 4. Ordnance Survey 6" (18137) MH051 5. Ordnance Survey 25" (1908) DN011-13 6. https://buried.fingal.ie/burial-ground-locations/the-ward/ [Accessed April 2023] 7. Egan, M. J. S. (1991). Dublin City and County Graveyards. Ireland Branch of the Irish Genealogical Research Society. Dublin. 8. Jacobs site inspection and walkover survey, June 2023 		

Unique Reference Number	AH_10	Reference Number(s)	RPS 608
Figure Number	Figure 13.2 in Volume 4	Legal Status	Protected Structure
Townland	Swords Glebe (part of)	Site Type	Enclosed stone well at base of steps under tree in field
Easting / Northing	718010 / 744000	Distance from Proposed Development	14m to the north of the Proposed Development
Significance	Medium		
Description	<p>Enclosed stone well at base of steps under tree in field. Identified as a holy well in Development Plan. ^[1]</p> <p>The well is not depicted on First Edition Ordnance Survey mapping (1837 – 1842); however, is shown on later mapping (Ordnance Survey 25", 1888-1913) at the end of a trackway at the corner of a pair of field boundaries. ^{[2][3]}</p> <p>The well is located north of Stockhole Lane, within an area of established vegetation. Very overgrown. A course of stones were visible in the undergrowth, likely forming part of this asset. Located within an established field boundary beneath a mature tree to the north of Stockhole Lane. ^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. https://www.fingal.ie/sites/default/files/2019-04/2017-2023_dev_plan_record_of_protected_structures.pdf [Accessed August 2022] 2. Ordnance Survey 6" (1843) DN014 3. Ordnance Survey 25" (1909) DN014-04 4. Jacobs site inspection and walkover survey, June 2023 		

Unique Reference Number	AH_13	Reference Number(s)	NIAH 11349005
Figure Number	Figure 13.2 in Volume 4	Legal Status	NIAH - Regional
Townland	Belcamp	Site Type	Country house
Easting / Northing	719398 / 741439	Distance from Proposed Development	14m to the north of the Proposed Development
Significance	Low		
Description	<p>Detached three-bay two-storey house, c.1840, with central portico. ROOF: M-profile double pitched slate roof; rendered chimney stacks; terracotta pots. WALLS: Pebble dashed; nap rendered plinth course. OPENINGS: Ionic columns to portico; square headed openings; stone cills; uPVC casements.</p> <p>The house has been demolished. ^[1]</p> <p>'Belcamp' is depicted on First Edition Ordnance Survey mapping (1837 – 1842) in its demesne (DL_17), with ancilliary buildings depicted to the north and a formal garden laid out to the north-west of the house. Later mapping shows the same layout. ^{[2][3]}</p>		
Sources	<ol style="list-style-type: none"> 1. https://www.fingal.ie/sites/default/files/2019-04/2017-2023_dev_plan_record_of_protected_structures.pdf [Accessed August 2022] 2. Ordnance Survey 6" (1843) DN015 3. Ordnance Survey 25" (1909) DN015-05 		

3. Inventory of Gardens and Designed Landscapes

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	DL_04	Reference Number(s)	NIAH 5156
Figure Number	Figure 13.3 in Volume 4	Legal Status	-
Townland	Priest Town	Site Type	GDL
Easting / Northing	705834 / 745825	Distance from Proposed Development	0m
Significance	Medium		
Description	<p>Priest Town House - Building indicated, area labelled Priest Town. ^[1] House and ancillary buildings depicted on historic Ordnance Survey mapping. Parkland woodland, and original driveways and entrances remain extant. Boundary along Belgree Lane formed of hedgerows and 'Crockanee' woodland. ^[2] Crockanee Wood and the established hedgerows form a dense screen adjacent to the road. ^[3] Extant landscape features: external boundary, areas of woodland, internal boundaries, entrances, driveway, principal building, parkland; some modern development / some features vaguely perceptible - driveway, garden areas. ^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. https://www.buildingsofireland.ie/buildings-search/site/5156/priest-town-house-kilbride-co-meath [Accessed August 2022] 2. Ordnance Survey 6" (1837) MH051 3. Google StreetView 4. Jacobs July 2023 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	DL_05	Reference Number(s)	NIAH 2267
Figure Number	Figure 13.3 in Volume 4	Legal Status	-
Townland	Hollystown; Hollywood; Hollywoodrath; Spricklestown	Site Type	GDL
Easting / Northing	708289 / 743285	Distance from Proposed Development	0m
Significance	Medium		
Description	<p>Hollywoodrath - Buildings indicated, area labelled Hollywood. ^[1] House, garden and ancillary buildings depicted on historic Ordnance Survey mapping. ^{[2][3]} Some development within the footprint of the site, including the golf course to the west. A section of roadside rubblestone boundary wall remains extant to the south of the site along the road that bisects the demesne. ^[4] Established hedgerow (including trees) and a ditch along north boundary of the demesne. Extant roadside wall to south, roughly coursed, squared stones with alternate horizontal and vertical cope stones (continue south of entrance and round onto R121). Large Entrance, with low rendered walls, cast iron railings on top, with large gatepiers (with modern lights on top) and pair of cast iron gates. Single storey lodge located inside the entrance, adjacent to drive, with views across entrance and road. ^[5] Extant landscape features: partial external / internal boundaries, principal house, gate lodge and entrance (Golf course and housing in parkland area to the west); drive (although altered).^[6]</p>		
Sources	<ol style="list-style-type: none"> 1. https://www.buildingsofireland.ie/buildings-search/site/2267/hollywoodrath-mulhuddart-co-dublin [Accessed August 2022] 2. Ordnance Survey 6" (1837) MH051 3. Ordnance Survey 25" (1909) DN013-04 4. Google StreetView 5. Jacobs site inspection and walkover survey, June 2023 6. Jacobs July 2023 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	DL_07	Reference Number(s)	-
Figure Number	Figure 13.3 in Volume 4	Legal Status	-
Townland	Ward Lower	Site Type	GDL
Easting / Northing	710057 / 745171	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<p>Ward House - Identified from historic Ordnance Survey mapping as 'Ward House'. [1]</p> <p>Located on the crossroads between the R135 and R121. The area has been redeveloped, including a new high roadside boundary wall. The house and two adjoining agricultural ranges remain extant. Alignment of one driveway also perceptible; however, majority of other demesne features have been removed. A complex of modern agricultural buildings are located on the western boundary and a new bungalow to the north-east. Two storey house with views across gardens and fields to the north-east (and the road beyond) and towards the farm to the west. High stone roadside boundary wall, some sections have been replaced adjacent to the R121. Northern boundary to the demesne has been removed. [2]</p> <p>Modern development includes farm buildings, a bungalow, the R121, and 'The Ward Cross' roundabout. [3]</p> <p>Extant landscape features: driveway and house / agricultural ranges (footprint no longer legible). This demesne is no longer legible in the landscape given the removal of the boundaries and replacement with modern roadside walls. Modern development has also encroached on the site and, while the house and original agricultural ranges remain extant, the features of the demesne have largely been removed. [4]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1837) MH051 2. Google StreetView 3. Jacobs site inspection and walkover survey, June 2023 4. Jacobs July 2023 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	DL_08	Reference Number(s)	-
Figure Number	Figure 13.3 in Volume 4	Legal Status	-
Townland	Newpark	Site Type	GDL
Easting / Northing	711071 / 745492	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<p>Newpark House - Identified from historic Ordnance Survey mapping as 'Newpark House'.^[1] Located to the south of the R121. Redeveloped as a commercial complex, including a concrete block boundary wall. Original buildings as depicted on 6" OS mapping appear to have been removed and the area redeveloped as a commercial premises.^{[2][3]} Extant landscape features: pond, some external boundaries, largely developed.^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1837) MH051 2. Google StreetView 3. Jacobs site inspection and walkover survey, June 2023 4. Jacobs July 2023 		

Unique Reference Number	DL_09	Reference Number(s)	-
Figure Number	Figure 13.3 in Volume 4	Legal Status	-
Townland	Kingstown	Site Type	GDL
Easting / Northing	713279 / 744623	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<p>Kingstown House - Identified from historic Ordnance Survey mapping as 'Kingstown House'. Roadside boundaries reflect those depicted. House and associated buildings have been removed and the entrance replaced.^[1] Boundary features along Kilreesk Road include a ditch and established boundary (trees and hedgerow), as well as a modern post and rail fence. Established boundary with overgrown driveway to cleared area (former location of house).^{[2][3]} Extant landscape features: exterior boundary, driveway (overgrown), site of buildings. While legible, this demesne retains limited original landscape features.^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1843) DN011 2. Google StreetView 3. Jacobs site inspection and walkover survey, June 2023 4. Jacobs July 2023 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	DL_11	Reference Number(s)	NIAH 5726
Figure Number	Figure 13.3 in Volume 4	Legal Status	-
Townland	Cloghran	Site Type	GDL
Easting / Northing	717559 / 743989	Distance from Proposed Development	30m to the south-west of the Proposed Development
Significance	Low		
Description	<p>Castle Mount - Identified from historic Ordnance Survey mapping as 'Castle Mount'.^[1] The principal building remains extant (RPS 611); however, the area has been developed. The boundary depicted on historic mapping (Ordnance Survey 6", 1837 – 1842) is vaguely perceptible in places as hedgerows. The boundary on the R132 appears to have been replaced with a new wall.^[2] Extant landscape features: some boundaries, driveway. Remains partially perceptible in the landscape.^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1843) DN014 2. Google StreetView 3. Jacobs July 2023 		

Unique Reference Number	DL_13	Reference Number(s)	-
Figure Number	Figure 13.3 in Volume 4	Legal Status	-
Townland	Cloghran	Site Type	GDL
Easting / Northing	718057 / 743892	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<p>Limepark - Identified from historic Ordnance Survey mapping as 'Limepark'.^[1] House appears to have been demolished and the majority of the boundaries are no longer present apart from some sections of hedgerow. Bisected by Stockhole Lane. Part of the northern boundary, driveway and Glebe House to the south-east remain extant; however, this demesne has been bisected by a local access road from Stockhole lane to Old Stockhole Lane, as well as Stockhole Lane.^{[2][3]} Extant landscape features: Glebe House, some boundaries, driveway. Remains partially perceptible in the landscape; however, has been bisected by Stockhole Lane.^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1843) DN014 2. Google StreetView 3. Jacobs site inspection and walkover survey, June 2023 4. Jacobs July 2023 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	DL_15	Reference Number(s)	-
Figure Number	Figure 13.3 in Volume 4	Legal Status	-
Townland	Middletown	Site Type	GDL
Easting / Northing	718864 / 742282	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<p>Upper Middletown - Identified from historic Ordnance Survey mapping as 'Upper Middletown'.^[1]</p> <p>The house, driveway and 'Turret' are no longer extant. The gate lodge to the east of Stockhole Lane has been redeveloped as modern dwellings. The site boundary remains extant as established hedgerows with former sub-divisions visible as cropmarks on aerial imagery.^[2]</p> <p>The footings of a roadside range, or boundary wall, were identified during the site inspection and walkover survey and are visible as an area of disturbance on aerial imagery and LiDAR data (CH_34).^{[3] [4]}</p> <p>Extant landscape features: Partial external boundary, one internal boundary, footings / walls of Upper Middleton to north.^[5]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1843) DN014 & DN015 2. Google StreetView 3. Jacobs site inspection and walkover survey, June 2023 4. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 5. Jacobs July 2023 		

Unique Reference Number	DL_16	Reference Number(s)	-
Figure Number	Figure 13.3 in Volume 4 of this EIAR	Legal Status	-
Townland	Glebe	Site Type	GDL
Easting / Northing	718945 / 743380	Distance from Proposed Development	0m
Significance	Low		
Description	<p>Glebe House - Identified from historic Ordnance Survey mapping as 'Glebe House'.^[1]</p> <p>House has been replaced with modern dwellings; however, the boundary and sub-divisions reflect those depicted on historic Ordnance Survey mapping. The site boundary comprises established hedgerows, including trees, some of which have modern fence running parallel.^[2]</p> <p>Extant landscape features: external boundary and some internal, house and drive no longer extant.^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1843) DN014 & DN015 2. Google StreetView 3. Jacobs July 2023 		

Unique Reference Number	DL_17	Reference Number(s)	NIAH 2455
Figure Number	Figure 13.3 in Volume 4 of this EIAR	Legal Status	-
Townland	Belcamp	Site Type	GDL
Easting / Northing	719160 / 741169	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<p>Belcamp - Identified from historic Ordnance Survey mapping as 'Belcamp'.^[1] House has been demolished (AH_13); however, the boundary and internal divisions reflect those depicted on historic Ordnance Survey mapping.^[2] Extant landscape features: external boundary and some internal divisions including the formal garden, the bridge and weir are also perceptible. House and ancillary buildings no longer extant. The access track to Belcamp substation bisects the demsene.^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1843) DN014 & DN015 2. MapGenie, 2013 - 2018 3. Jacobs July 2023 		

4. Inventory of Cultural Heritage Assets

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_01	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Blackhall Big	Site Type	Roadside house
Easting / Northing	694847 / 744987	Distance from Proposed Development	10m to the south of the Proposed Development
Significance	Low		
Description	<p>An 'L'-shaped, single storey roadside cottage depicted on historic Ordnance Survey mapping. Rendered with central stack. ^[1]</p> <p>Located within a walled (low coursed, squared stone) plot, set at an angle with the road (R156), with an unenclosed drive to the north. Views are over the R156 towards the fields to the north. Single storey rendered house, with slate roof. Plot bounded by a low squared, rubblestone wall. Views across R156 towards established hedgerows and pasture field beyond. Appears to have later additions / some modernisation. ^[2]</p> <p>Large gravel driveway between road and boundary wall. Established roadside boundaries to east and west; however, view largely across road immediately to the north towards fields. ^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 25" (1911) MH050-01 2. Google StreetView 3. Jacobs site inspection and walkover survey, June 2023 		

Unique Reference Number	CH_04	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Staffordstown Little	Site Type	Roadside house
Easting / Northing	696345 / 744282	Distance from Proposed Development	7m to the south-west of the Proposed Development
Significance	Very Low / Negligible		
Description	<p>A house depicted on historic Ordnance Survey mapping. ^[1]</p> <p>The house is positioned perpendicular to the R156, and comprises a single storey rendered structure with tile roof and central stack, with a high walled garden / yard to the south. Appears abandoned and plot is overgrown. A single storey house, with tile roof and central stack. Roof appears to have collapsed and the house is no longer in use. ^[2]</p> <p>Within a small overgrown plot in a large agricultural field. ^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 25" (1911) MH050-06 2. Google StreetView, June 2021 3. Jacobs site inspection and walkover survey, June 2023 		

Unique Reference Number	CH_12	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Ballymagillin	Site Type	Courtyard farm
Easting / Northing	702502 / 744660	Distance from Proposed Development	3m to the north of the Proposed Development
Significance	Low		
Description	<p>A group of farm buildings arranged in a courtyard plan depicted on historic Ordnance Survey mapping. Single and two-storey rendered stone ranges remain extant with some modern additions forming part of the farm complex. ^{[1][2]}</p> <p>Views are internal across the farmyard with views out limited by a high stone wall. The farm is positioned immediately to the north of the L5026. ^[3]</p> <p>Rendered and painted roadside (L5026) agricultural ranges, arranged in a courtyard plan. Some modern replacement, including concrete block buildings, corrugated sheet roofing and modern hay barn. An entrance to modern housing to the north is also located adjacent to the farm (to the west). Remnants of a rubblestone wall was also noted to the east of the roadside range. Views are internal, across the yard. Pasture fields surround the farm on three sides, with modern bungalows located to the north. ^{[3][4]}</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1837) MH050 2. Ordnance Survey 25" (1911) MH050-08 3. Google StreetView 4. Jacobs site inspection and walkover survey, June 2023 		

Unique Reference Number	CH_13	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Whitesland	Site Type	House
Easting / Northing	702660 / 744657	Distance from Proposed Development	4m to the north of the Proposed Development
Significance	Low		
Description	<p>A house depicted on historic Ordnance Survey mapping comprising a roughly coursed rubble stone construction. ^[1]</p> <p>Appears to have been altered and includes modern extensions. The house is located within a low stone walled garden and is positioned perpendicular to the L5026. Views outward are filtered by the surrounding established grounds. ^[2]</p> <p>A two storey roadside house, positioned at an angle with the carriageway within a walled private garden. Views are orientated east, across the garden towards neighbouring properties, and west across the garden to fields beyond. While the house is located close to the road, views are filtered by established trees lining the verge. ^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 25" (1911) MH050-08 2. Google StreetView 3. Jacobs site inspection and walkover survey, June 2023 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_15	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Belgree	Site Type	Road bridge
Easting / Northing	705608 / 745439	Distance from Proposed Development	0m
Significance	Low		
Description	<p>A stone road bridge depicted on historic Ordnance Survey mapping. ^[1]</p> <p>The bridge includes a pair of low coursed rubblestone parapets with squared ends and horizontal copes. A footway is present inside both parapets. The bridge appears to have been refurbished. The bridge carries Belgree Lane across the Ward River. ^[2]</p> <p>Squared roughly hewn rubblestone parapets, located either side of Belgree Lane, forming part of the bridge crossing the Ward River. Large squared copes with smaller squared roughly coursed masonry below, and a modern footway added either side. ^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1837) MH051 2. Google StreetView, June 2021 3. Jacobs site inspection and walkover survey, June 2023 		

Unique Reference Number	CH_24	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Ward Upper	Site Type	House
Easting / Northing	710160 / 745108	Distance from Proposed Development	16m to the south-east of the Proposed Development
Significance	Low		
Description	<p>'Six Mile House' depicted on historic Ordnance Survey mapping. ^[1]</p> <p>The house comprises a single storey, brick and rendered building with a slate roof and gable stack. Original house appears to have been extended. ^[2]</p> <p>The house is located on the roadside on the junction between the R121 and the R135. Views out are limited by hedges, a wall, and outbuildings; however, to the north and east views are across the roundabout and roads. ^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1837) MH051 2. Google StreetView, July 2021 3. Jacobs site inspection and walkover survey, June 2023 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_25	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Newpark	Site Type	Agricultural ranges
Easting / Northing	710338 / 745269	Distance from Proposed Development	0m
Significance	Low		
Description	<p>A group of roadside agricultural buildings, forming a courtyard, depicted on historic Ordnance Survey mapping. ^{[1][2]}</p> <p>The buildings comprise one and two-storey structures, constructed with stone and brick. Views are across the farmyard with views out limited by a wall. The farm is positioned immediately to the north of the R121. ^[3]</p> <p>Yard expanded by 1940 to include a house and further ranges (OS). ^[4]</p> <p>Roadside farm, as described. Views are internal across a yard. With a range and boundary wall lining the R121. ^[5]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1837) MH051 2. Ordnance Survey 25" (1908) DN011-13 3. Google StreetView 4. Ordnance Survey 6" (1941) DN011 5. Jacobs site inspection and walkover survey, June 2023 		

Unique Reference Number	CH_29	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Ballystrahan	Site Type	House
Easting / Northing	712626 / 745191	Distance from Proposed Development	7m to the south-west of the Proposed Development
Significance	Low		
Description	<p>A roadside house depicted on historic Ordnance Survey mapping. ^{[1][2]}</p> <p>The house comprises a single storey rendered five-bay structure with an off-centre stack and tile roof. Farm buildings, some of which are depicted on later mapping are located to the south and west. The house is located adjacent to R122 within a plot enclosed by a low rendered boundary wall. ^[3]</p> <p>A single storey, white rendered house with tile roof and later projecting porch. Set back from road, at an angle, with a low rendered stone boundary wall and set of gates / gate piers. Views are across the drive adjacent to the house, across the busy R122, towards a pasture field beyond. ^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1836) DN011 2. Ordnance Survey 25" (1908) DN011-14 3. Google StreetView 4. Jacobs site inspection and walkover survey, June 2023 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_32	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Clonshaugh	Site Type	Field system
Easting / Northing	719193 / 741776	Distance from Proposed Development	0m
Significance	Low		
Description	A network of linear cropmarks visible on aerial imagery. ^[1] These cropmarks correspond with former field boundaries depicted on historic Ordnance Survey mapping that have since been removed. ^[2]		
Sources	1. Digital Globe 2. Ordnance Survey 6" (1843) DN015		

Unique Reference Number	CH_33	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Cloghran	Site Type	Farm
Easting / Northing	718928 / 743480	Distance from Proposed Development	15m to the south of the Proposed Development
Significance	Low		
Description	A courtyard farm depicted on historic Ordnance Survey mapping. ^[1] The farm comprises an 'L'-shaped range and farmhouse on Stockhole Lane. The farm is positioned at the end of a drive within large rectangular fields. Modern agricultural buildings form part of the yard. Views are internal across the farmyard with views out limited by buildings and established field boundaries. ^[2] Set back from Stockhole Lane. Internal facing, courtyard plan. Set within agricultural fields. Car park to rear. ^[3]		
Sources	1. Ordnance Survey 6" (1843) DN015 2. Google StreetView 3. Jacobs site inspection and walkover survey, June 2023		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_34	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Middletown	Site Type	House (site of)
Easting / Northing	718996 / 742340	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<p>Upper Middletown', a farm/house, depicted on historic Ordnance Survey mapping. ^[1] The buildings have been demolished. However, earthworks are visible in this location on aerial imagery and may indicate the site of the footings of the buildings. ^{[2][3]} LI_59: - An irregular area of disturbance to the south of the road measuring approximately 45m by 33m. - Visible as an overgrown area adjacent to the road on aerial imagery. - 'Upper Middleton' (CH_34) is depicted in this location on historic Ordnance Survey mapping (1843); however, is reduced to one building (1909) on later editions. - Interpreted as the location of Upper Middle farm buildings. ^[4] Extant rubblestone walls noted adjacent to the lane. Could be the remains of a laneside building or boundary wall. ^[5]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1843) DN015 2. Google StreetView 3. Digital Globe 4. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 5. Jacobs site inspection and walkover survey, June 2023 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_53	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Gallanstown	Site Type	Quarry
Easting / Northing	708417 / 743907	Distance from Proposed Development	3m to the north-east of the Proposed Development
Significance	Very Low / Negligible		
Description	<p>A 'Quarry' depicted on historic Ordnance Survey mapping. Located in an arable field to the west of a local road. ^{[1][2]} LI_39: - A small rectangular area measuring approximately 16m by 12m to the east of a local road. - Not depicted on historic Ordnance Survey mapping; however, located opposite a quarry identified on earlier editions (1843). - Vaguely perceptible on aerial imagery as a small area of disturbance in the corner of a pasture field. - Tentatively interpreted as a possible quarry of unknown date; however, could equally be modern disturbance. ^[3] No remains visible above ground. ^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1843) DN013 2. Ordnance Survey 25" (1909) DN013-04 3. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 4. Jacobs site inspection and walkover survey, June 2023 		

Unique Reference Number	CH_58	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Spicklestown	Site Type	Enclosure
Easting / Northing	708604 / 743762	Distance from Proposed Development	10m to the south of the Proposed Development
Significance	Medium		
Description	<p>An ephemeral circular enclosure, comprising a single narrow ditch measuring approximately 42m in diameter, visible as a cropmark on aerial imagery (GoogleEarth, 07/2013) in a small arable field. ^[1] This asset comprises a previously unrecorded possible univallate enclosure of unknown date, and may contribute to the understanding of rural settlement, the pattern and relationship between enclosures, and the local pastoral economy. ^[2]</p>		
Sources	<ol style="list-style-type: none"> 1. GoogleEarth, 07/2013 2. Jacobs July 2023 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_59	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Culcommon; Barstown	Site Type	Field system
Easting / Northing	694219 / 745068	Distance from Proposed Development	0m
Significance	Low		
Description	Linear features visible on aerial imagery (GoogleEarth, various) comprising a sinuous linear orientated approximately east-west and a perpendicular linear orientated north-south. ^[1] Reflects two field boundaries depicted on historic Ordnance Survey mapping. ^{[2][3]}		
Sources	<ol style="list-style-type: none"> 1. GoogleEarth, various 2. Ordnance Survey 6" (1837) MH050 3. Ordnance Survey 25" (1911) MH050-01 		

Unique Reference Number	CH_60	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Forrest Great	Site Type	Building
Easting / Northing	715563 / 744793	Distance from Proposed Development	30m to the north of the Proposed Development
Significance	Very Low / Negligible		
Description	<p>A roadside building depicted on historic mapping. ^{[1][2]}</p> <p>Possibly associated with Forrest House which is identified as 'in ruins' on later mapping. ^[3]</p> <p>Depicted on Ordnance Survey mapping (1843), with additional ranges depicted on later additions, including a roadside range (1908; 1941). ^{[4][5]}</p> <p>Buildings are in poor condition, roofless and overgrown. Two gables of the single storey roadside range were identified, comprising rubblestone construction with some areas of render noted. A roadside cast iron gate with stone gate pier and dressed cope, was also identified. ^[6]</p>		
Sources	<ol style="list-style-type: none"> 1. Rocque, 1760, Dublin County 2. Taylor & Skinner Dublin to Swords, 1778 3. Taylor's Environs of Dublin, 1816 4. Ordnance Survey 6" (1843) DN011 5. Ordnance Survey 25" (1908) DN011-15 6. Jacobs site inspection and walkover survey, June 2023 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_61	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Woodland	Site Type	Ring ditches
Easting / Northing	694544 / 747983	Distance from Proposed Development	0m
Significance	Medium		
Description	A group of small circular cropmarks measuring between approximately 3m and 9m in diameter. Interpreted as a group of ring-ditches - possibly the remains of a barrow cemetery or group of roundhouses of prehistoric date. ^[1]		
Sources	1. BlueSky, 2022		

Unique Reference Number	CH_62	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Woodland	Site Type	Ring ditches
Easting / Northing	694774 / 747813	Distance from Proposed Development	0m
Significance	Medium		
Description	A group of approximately 14 circular cropmarks measuring between approximately 4m and 20m in diameter. Interpreted as a group of ring-ditches - possibly the remains of a barrow cemetery or group of roundhouses of prehistoric date. ^[1] Locally undulating / tussock-y pasture field, irregular in shape with established hedgerow boundaries (including mature trees, scrub & ditches). Existing substation(s) visible from field, low humming from substation also perceptible. No remains of the ring-ditches were visible above ground. Some variation in grass; however, not discernible with any confidence as cropmarks identified from aerial imagery. ^[2]		
Sources	1. BlueSky, 2022 2. Walkover and site inspection, January 2023 [CP966]		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_63	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Piercetown	Site Type	Pump
Easting / Northing	702008 / 744698	Distance from Proposed Development	1m to the north of the Proposed Development
Significance	Low		
Description	<p>A cast-iron pump in a concrete roadside recess. Set slightly back from the road (L5026) adjacent to a private driveway and modern telephone pole. A large covered plastic crate (on concrete blocks) is positioned in front of the pump. ^[1]</p> <p>Not depicted on historic Ordnance Survey mapping; however a pump is depicted further to the east outside a roadside farm (CH_12). The pump may not be in its original location. ^{[2][3][4]}</p>		
Sources	<ol style="list-style-type: none"> 1. Jacobs site inspection and walkover survey, June 2023 2. Ordnance Survey 6" (1837) MH050 3. Ordnance Survey 25" (1911) MH050-08 4. Ordnance Survey 6" (1912) MH050 		

Unique Reference Number	CH_64	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Cullendragh	Site Type	Building misc.
Easting / Northing	694115 / 745455	Distance from Proposed Development	9m to the north of the Proposed Development
Significance	Very Low / Negligible		
Description	<p>The site of a small roofless rectangular building depicted on historic Ordnance Survey mapping in an irregular field. Not depicted on later mapping. ^{[1][2]}</p> <p>Not visible on aerial imagery; however, a parchmark in this approximate location is visible (GoogleEarth, 2013). However, this could be the result of modern agricultural activity in this location. ^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1837) MH050 2. Ordnance Survey 25" (1911) MH050-01 3. GoogleEarth Jul' 2022 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_65	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Woodland	Site Type	Ring ditches
Easting / Northing	694697 / 747437	Distance from Proposed Development	0m
Significance	Medium		
Description	A group of small circular cropmarks measuring up to approximately 7m in diameter. Interpreted as a group of ring-ditches - possibly the remains of a barrow cemetery or group of roundhouses of prehistoric date. ^[1]		
Sources	1. BlueSky, 2022		

Unique Reference Number	CH_66	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Cullendragh	Site Type	Enclosure
Easting / Northing	694419 / 746515	Distance from Proposed Development	0m
Significance	Medium		
Description	A faint circular enclosure visible as a cropmark on aerial imagery. Measuring approximately 6m in diameter. Tentatively interpreted as a possible enclosure of unknown date. ^[1]		
Sources	1. BlueSky, 2022		

Unique Reference Number	CH_67	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Cullendragh	Site Type	Ring-ditches
Easting / Northing	694195 / 745582	Distance from Proposed Development	0m
Significance	Medium		
Description	A group of five ephemeral curvi-linear cropmarks visible on aerial imagery. Interpreted as a group of ring-ditches - possibly the remains of a barrow cemetery or group of roundhouses of prehistoric date. ^[1]		
Sources	1. BlueSky, 2022		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_68	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Cullendragh	Site Type	Field boundary
Easting / Northing	694111 / 745336	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	A linear feature measuring approximately 74m in length, orientation east-west visible on aerial imagery. A field boundary is depicted on historic OS mapping (25") in this location. ^{[1][2]}		
Sources	<ol style="list-style-type: none"> 1. BlueSky, 2022 2. Ordnance Survey 25" (1911) MH050-01 		

Unique Reference Number	CH_69	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Woodland	Site Type	Field boundaries
Easting / Northing	694632 / 748157	Distance from Proposed Development	0m
Significance	Low		
Description	Linear features in a field to the west of Woodland substation identified from aerial imagery. ^{[1][2]} Corresponds with field boundaries depicted on historic OS mapping. ^{[3][4]}		
Sources	<ol style="list-style-type: none"> 1. Digital Globe Aerial Imagery 2. GoogleEarth, various dates 3. Ordnance Survey 6" (1837) MH044 4. Ordnance Survey 25" (1911) MH044-09 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_70	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Creemore	Site Type	Field boundaries
Easting / Northing	694994 / 748574	Distance from Proposed Development	0m
Significance	Low		
Description	Linear features in a field to the north of Woodland substation, as well as a circular feature measuring approximately 40m in diameter, identified from aerial imagery. ^{[1][2]} Some correspond with field boundaries depicted on historic OS mapping; however, the field system and circular feature could be earlier in date. A ringfort (ME044-017; outwith the study area) is located approximately 100m to the west of the circular feature. ^{[3][4]}		
Sources	<ol style="list-style-type: none"> 1. Digital Globe Aerial Imagery 2. GoogleEarth, various dates 3. Ordnance Survey 6" (1837) MH044 4. Ordnance Survey 25" (1911) MH044-09 		

Unique Reference Number	CH_71	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Dunboyne	Site Type	House
Easting / Northing	700273 / 742738	Distance from Proposed Development	5m to the south of the Proposed Development
Significance	Low		
Description	Two roadside buildings depicted on historic Ordnance Survey mapping as 'Dispy.' ^[1] The house is located adjacent to R156 Regional Road within a plot enclosed by a low rendered boundary wall. Views from the house are limited by established vegetation and mature trees along the boundaries. ^[2]		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 25" (1911) MH050-12 2. Google StreetView 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_72	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Dunboyne	Site Type	Palaeochannel
Easting / Northing	700313 / 742839	Distance from Proposed Development	0m
Significance	Medium		
Description	An ephemeral sinuous meandering channel visible on aerial imagery. ^[1] Not depicted on historic mapping; however, located to the west of a straight watercourse. ^{[2][3]}		
Sources	1. MapGenie Imagery, various dates 2. Ordnance Survey 6" (1837) MH050 3. Ordnance Survey 25" (1911) MH050-12		

Unique Reference Number	CH_73	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Pace	Site Type	Railway
Easting / Northing	701674 / 744212	Distance from Proposed Development	0m
Significance	Low		
Description	The Dublin & Navan Branch of the Midland Great Western Railway depicted on historic Ordnance Survey mapping. ^[1] The railway corridor remains perceptible in the landscape on aerial imagery, and a section remains in operation. ^{[2][3]} The railway was closed to passengers in 1947; however, a section was reopened (terminating at the M3 Parkway) in 2010. ^[4]		
Sources	1. Ordnance Survey 25" (1911) MH050-08 2. MapGenie, 1995 3. MapGenie, 2013 – 2018 4. https://www.railscot.co.uk/companies/D/Dublin_and_Meath_Railway/ [Accessed October 2023]		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_74	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Priest Town	Site Type	Road bridge
Easting / Northing	705579 / 745531	Distance from Proposed Development	25m to the north of the Proposed Development
Significance	Low		
Description	<p>A stone road bridge depicted on historic Ordnance Survey mapping.^{[1] [2]}</p> <p>The bridge includes a pair of parallel unmatching rubblestone parapets with squared ends. One includes curved concrete copes, the other horizontal stone copes. The bridge carries a local road across the Ward River.^[3]</p>		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1837) MH051 2. Ordnance Survey 25" (1911) MH051-02 3. Google StreetView, April 2023 		

Unique Reference Number	CH_75	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Shallon	Site Type	Enclosure
Easting / Northing	712232 / 745693	Distance from Proposed Development	0m
Significance	Medium		
Description	<p>A faint circular enclosure visible as a cropmark on aerial imagery. Measuring approximately 70m in diameter (external) with linear features to the west; tentatively interpreted as a possible enclosure of unknown date.^[1]</p> <p>Not depicted on historic Ordnance Survey mapping; however, one of the linear features corresponds with a former field boundary.^{[2] [3]}</p>		
Sources	<ol style="list-style-type: none"> 1. DigitalGlobe, 2011 – 2013 2. Ordnance Survey 6" (1843) DN011 3. Ordnance Survey 25" (1908) DN011-10 		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_76	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Forrest Great	Site Type	Enclosure
Easting / Northing	715450 / 744655	Distance from Proposed Development	4.1m to the south-east of the Proposed Development
Significance	Medium		
Description	<p>A sub-circular area of rough ground and overgrown with vegetation. Measuring approximately 30m in diameter, with a field boundary to the east. Interpreted as a possible enclosure. ^[1] No depicted on historic Ordnance Survey mapping. ^{[2][3]} LI_53: - A sub-circular area of rough ground measuring approximately 30m across south of Naul Road. A possible section of bank is located to the north and west. Appears to have been truncated to the south. - Not depicted on historic Ordnance Survey mapping. - Visible on aerial imagery (and Google Street View) as a slightly raised area of rough ground. Tentatively interpreted as a possible enclosure of unknown date and function. ^[4]</p>		
Sources	<ol style="list-style-type: none"> 1. DigitalGlobe, 2011 – 2013 2. Ordnance Survey 6" (1843) DNO11 3. Ordnance Survey 25" (1908) DNO11-15 4. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 		

Unique Reference Number	CH_77	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Cloghran	Site Type	Enclosure
Easting / Northing	718811 / 744000	Distance from Proposed Development	18m to the north of the Proposed Development
Significance	Medium		
Description	<p>A sub-circular area of rough ground. Measuring approximately 55m in diameter. Interpreted as a possible enclosure. ^[1] Not depicted on historic Ordnance Survey mapping. ^{[2][3]}</p>		
Sources	<ol style="list-style-type: none"> 1. DigitalGlobe, 2011 – 2013 2. Ordnance Survey 6" (1843) DNO14 3. Ordnance Survey 25" (1909) DNO14-04 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_78	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Stockhole	Site Type	Ring ditches
Easting / Northing	718875 / 742865	Distance from Proposed Development	0m
Significance	Medium		
Description	Three small circular cropmarks measuring up to approximately 10m in diameter. Interpreted as a group of ring-ditches - possibly the remains of a barrow cemetery or group of roundhouses of prehistoric date. ^[1]		
Sources	1. MapGenie, 2013 - 2018		

Unique Reference Number	CH_79	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Stockhole	Site Type	Enclosure
Easting / Northing	718813 / 742566	Distance from Proposed Development	18m to the east of the Proposed Development
Significance	Medium		
Description	Two ephemeral curvi-linear features, interpreted as a possible sub-circular enclosure measuring approximately 40m in diameter. ^[1] Not depicted on historic Ordnance Survey mapping. ^{[2][3]}		
Sources	1. DigitalGlobe, 2011 – 2013 2. Ordnance Survey 6" (1843) DN014 3. Ordnance Survey 25" (1909) DN014-08		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	CH_80	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Stockhole	Site Type	House (site of)
Easting / Northing	718861 / 742416	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	'Stockhole House', a farm/house, depicted on historic Ordnance Survey mapping. ^{[1][2]} The footprint of the building plot remains perceptible on aerial imagery. ^[3]		
Sources	<ol style="list-style-type: none"> 1. Ordnance Survey 6" (1843) DN014 2. Ordnance Survey 25" (1909) DN014-08, DN015-05 3. MapGenie, 2013 - 2018 		

Unique Reference Number	CH_81	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Woodland	Site Type	Ditch
Easting / Northing	694685 / 747933	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - Shallow, negative linear feature, c.197m in length, orientated approximately north-south running between two extant field boundaries. - No corresponding features on historic Ordnance Survey mapping. - Vaguely perceptible on aerial imagery. - No modern utilities noted; however, south-west of Woodland 400kV Converter Substation and parallel to overhead service (identified from DSM). Interpreted as a possible modern utility or drainage ditch.^[1] Ditch appears to be overlain by circular cropmarks visible on aerial imagery (BlueSky Aerial, 2022) which may indicate an earlier date.^[2] Locally undulating / tussock-y pasture field, irregular in shape with established hedgerow boundaries (including mature trees, scrub & ditches). Existing substation(s) visible from field, low humming from substation also perceptible. Very faint negative linear feature visible running roughly north-south parallel to the field boundary to the west of the field.^[3] 		
Sources	<ol style="list-style-type: none"> 1. Appendix 13.1 (Inventory of Archaeology, Architectural Heritage and Cultural Heritage) for the Kildare-Meath Grid Upgrade (CP966). 		

Unique Reference Number	CH_82	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Gaulstown	Site Type	Ditch
Easting / Northing	694270 / 746590	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A negative linear feature, orientated west-east, measuring c. 250m in length (extends beyond 100m Study Area). - No corresponding features on historic Ordnance Survey mapping. Possibly modern drainage. - Visible on aerial imagery. - Located parallel to a minor watercourse. Interpreted as a ditch of unknown date, possibly modern drainage. ^[1]		
Sources	1. Appendix 13.1 (Inventory of Archaeology, Architectural Heritage and Cultural Heritage) for the Kildare-Meath Grid Upgrade (CP966).		

Unique Reference Number	CH_83	Reference Number(s)	-
Figure Number	Figure 13.4 in Volume 4	Legal Status	-
Townland	Cullendragh	Site Type	Ditch
Easting / Northing	694304 / 746431	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A negative 'L'-shaped linear feature, measuring c.53m x c.168m. - No corresponding features on historic Ordnance Survey mapping. - To the south of a minor watercourse. Interpreted as a ditch of unknown date. Section orientated roughly east-west perceptible running across the field. Located within a large tussock-y pasture field, south of a watercourse. ^[1]		
Sources	1. Appendix 13.1 (Inventory of Archaeology, Architectural Heritage and Cultural Heritage) for the Kildare-Meath Grid Upgrade (CP966).		

5. Inventory of LiDAR Assets

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_01	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Woodland	Site Type	Boundary
Easting / Northing	694807 / 747856	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - Negative linear features forming a rectilinear area, c.80m x 48m, abutting a field boundary to the north-east. Area within boundary disturbed. - Corresponds with a farmstead including a 'U'-shaped cluster of buildings within a sub-rectangular plot, depicted on historic Ordnance Survey mapping (1837, 1911). - Faintly perceptible on aerial imagery. - Interpreted as the boundary of a post-medieval farmstead. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_02	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Woodland	Site Type	Field boundary(ies)
Easting / Northing	694585 / 747832	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - Shallow negative linear feature, c.73m in length, orientated approximately north-south abutting townland boundary (to south) and an extant field boundary to the north. - Perceptible on aerial imagery. - Corresponds with a field boundary on historic Ordnance Survey mapping (1837, 1911). - Interpreted as a post-medieval field boundary. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_03	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Woodland	Site Type	Field boundary(ies)
Easting / Northing	694814 / 747782	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - An ephemeral negative linear feature, c.107m in length, orientated approximately north-south abutting extant field boundaries (to north and south). - Corresponds with a field boundary on historic Ordnance Survey mapping (1837, 1911). - Associated with (LI_02). - Interpreted as a post-medieval field boundary. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_05	Reference Number(s)	-
Figure Number	Figure 13. in Volume 4	Legal Status	-
Townland	Gaulstown; Culcommon	Site Type	Field system
Easting / Northing	694445 / 747206	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A network of negative linear features and cultivation patterns. - Some linear features correspond with field boundaries on historic Ordnance Survey mapping (1837, 1911). - Some field boundaries remain extant as hedgerows and others are visible as cropmarks on aerial imagery. - Interpreted as a post-medieval field system. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_06	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Culcommon	Site Type	Field boundary(ies)
Easting / Northing	694531 / 746903	Distance from Proposed Development	8m to the east of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - An ephemeral linear feature orientated approximately east-west, measuring c.140m in length. Runs between an extant field boundary and townland boundary. - Corresponds with a field boundary on historic Ordnance Survey mapping (1837, 1911). - Interpreted as a post-medieval field boundary. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_07	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Culcommon	Site Type	Field system
Easting / Northing	694570 / 746304	Distance from Proposed Development	3m to the east of the Proposed Development
Significance	Low		
Description	<ul style="list-style-type: none"> - A network of ephemeral negative linear features, located between two townland boundaries, including a pair of north-south orientated linear features, a triangular area, and irregular southern boundary. Appear to be overlain by later uniform cultivation patterns. A number of circular features were also noted (likely the result of the wear pattern around modern animal feeding stations). - Some features correspond with historic Ordnance Survey mapping (1911). - Northern boundary is a minor watercourse. - The location of a large circular enclosure (ME050-001), identified as a 'Fort' on historic Ordnance Survey mapping, is c.600m to the south-east. - Tentatively interpreted as field boundaries and field drains forming part of a field system of pre-19th century date. Later agricultural activity is also noted. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_08	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Cullendragh	Site Type	Buildings
Easting / Northing	694329 / 746085	Distance from Proposed Development	0m
Significance	Low		
Description	<ul style="list-style-type: none"> - Three positive rectangular features: 1) c.8mx6m, 2) c.9mx4m, and 3) c.12mx6m between a negative linear feature and townland boundary. - North of a possible field system (LI_09). - No corresponding features on historic Ordnance Survey mapping and not visible on aerial imagery. - Interpreted as the site of a group of buildings (likely agricultural) of unknown date. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_09	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Cullendragh	Site Type	Field system
Easting / Northing	694186 / 746004	Distance from Proposed Development	0m
Significance	Low		
Description	<ul style="list-style-type: none"> - A network of negative linear features between two existing field boundaries and a townland boundary. Majority orientated approximately north-south (including one parallel to townland boundary); however, some run perpendicular forming small irregular enclosures. - Possible associated buildings to the north (LI_08). - No corresponding features on historic Ordnance Survey mapping, although the area outline is depicted on historic Ordnance Survey mapping (1911). - Interpreted as a field system of unknown date. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_10	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Culcommon	Site Type	Field system
Easting / Northing	694403 / 745767	Distance from Proposed Development	0m
Significance	Low		
Description	<ul style="list-style-type: none"> - A network of negative linear features, forming irregular fields within a larger area. - Linear features to the south correspond with field boundaries depicted on historic Ordnance Survey mapping (1837). Only triangular area of trees depicted on later Ordnance Survey mapping (1911). - Some linear features perceptible on aerial imagery as well as triangular area of trees. - Interpreted as part of a field system of unknown date. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_11	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Cullendragh	Site Type	Field system
Easting / Northing	694096 / 745609	Distance from Proposed Development	0m
Significance	Low		
Description	<ul style="list-style-type: none"> - A network of negative linear features and cultivation patterns. Some parallel and evenly spaced straight features. - Some linear features correspond with field boundaries on historic Ordnance Survey mapping. - Vaguely perceptible on aerial imagery. - Minor watercourse runs through the centre. - Interpreted as a field system of unknown date, including field drainage. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_13	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Culcommon	Site Type	Boundary
Easting / Northing	694123 / 745200	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	-A linear feature measuring approximately 39m in length, running roughly east-west. - Vaguely perceptible on aerial imagery (GoogleEarth, 03/2022) in a private garden to the north of the R156. - Possibly the remains of a former boundary feature depicted on historic Ordnance Survey mapping (1837, 1911) surrounding a small group of roadside buildings. ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_14	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Culcommon	Site Type	Police station
Easting / Northing	694356 / 745131	Distance from Proposed Development	0m
Significance	Low		
Description	- A rectangular feature measuring approximately 12m by 6m set back from the R156, with a larger former boundary feature also noted. - Visible on aerial imagery (GoogleEarth, various) as an overgrown rectangular area at the junction between the R156 and a local road. - Corresponds with the location of a building set back from the road on historic Ordnance Survey mapping, including First Edition 6" (1837) which identifies the building as a 'Police Station'. ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_15	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Blackhall Big	Site Type	Boundary
Easting / Northing	695643 / 744416	Distance from Proposed Development	3m to the south of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - An ephemeral sub-rectangular feature measuring approximately 32m in with to the south of the R156. Other linear features were noted adjacent to the feature. - Not visible on aerial imagery. - A small group of roadside buildings and a boundary feature are depicted on historic Ordnance Survey mapping in this location (1837). The buildings and boundaries are not depicted on later mapping (1911). - Interpreted as a post-medieval boundary. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_16	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Staffordstown Little	Site Type	Field system
Easting / Northing	696120 / 744277	Distance from Proposed Development	0m
Significance	Low		
Description	<ul style="list-style-type: none"> - A network of linear features, defining a large area, with some ephemeral linear features within. - Visible on aerial imagery (GoogleEarth 03/2022) to the south of the R156. - Correspond with field boundaries depicted on historic Ordnance Survey mapping (1837, 1911). - Interpreted as former field boundaries forming part of a post-medieval field system. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_17	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Staffordstown Little	Site Type	Driveway
Easting / Northing	696294 / 744156	Distance from Proposed Development	6m to the south of the Proposed Development
Significance	Very Low / Negligible		
Description	- A pair of ephemeral parallel linear features, orientated roughly north-south running from a roadside building (CH_04) to the south. - Visible on aerial imagery (GoogleEarth, 03/2022). - Corresponds with a driveway leading to a pair of rectangular buildings (located outside the Study Area; no longer extant) depicted on historic Ordnance Survey mapping (1837), and later mapping depicts the driveway connected to the roadside building plot (1911). ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_18	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Harlockstown	Site Type	Field system / palaeochannel
Easting / Northing	696942 / 744183	Distance from Proposed Development	0m
Significance	Medium		
Description	- A network of linear features, including two orientated north-south (extending outside the Study Area) with cultivation patterns and possible drainage. A wide (approximately 12m) channel, orientated north-south was also identified as a possible palaeochannel. - Not depicted on historic Ordnance Survey mapping. - Visible on aerial imagery. - Interpreted as a possible field boundaries forming a field system of unknown date. ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_19	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Harlockstown	Site Type	Field boundary(ies)
Easting / Northing	697281 / 744100	Distance from Proposed Development	7m to the north of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - Five negative linear features orientated north-south, running between a local road to the R156. - Visible on aerial imagery (GoogleEarth, various). - Some of the linear features correspond with field boundaries depicted on historic Ordnance Survey mapping (1837, 1911). - Interpreted as post-medieval former field boundaries. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_20	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Baytownpark	Site Type	Pit
Easting / Northing	698650 / 743467	Distance from Proposed Development	11m to the south of the Proposed Development
Significance	Medium		
Description	<ul style="list-style-type: none"> - A circular feature measuring approximately 7m in diameter, with two small circular features adjacent (c.3m in diameter each). - Visible on aerial imagery (GoogleEarth, 10/2009, 06/2020, 04/2021). - No corresponding features on historic Ordnance Survey mapping. - Tentatively interpreted as a possible pits of unknown date; however, equally could be the location of a modern animal feeder. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_21	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Baytownpark	Site Type	Field system
Easting / Northing	698953 / 743499	Distance from Proposed Development	0m
Significance	Low		
Description	<ul style="list-style-type: none"> - A network of linear features forming a series of possible fields, including cultivation patterns. Drainage (likely later in date) was also noted. - No corresponding features are depicted on historic Ordnance Survey mapping. - Visible on aerial imagery (GoogleEarth, 03/2022). - Interpreted as a possible field system of unknown date. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_23	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Colliersland North	Site Type	Field boundary(ies)
Easting / Northing	699979 / 742741	Distance from Proposed Development	48m to the south-west of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A series of linear features, oriented east-west, and one roughly north-south, within an agricultural field. - Not depicted on historic Ordnance Survey mapping. - Visible on aerial imagery. - Interpreted as former field boundaries of unknown date (possibly modern). ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_24	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Dunboyne	Site Type	Palaeochannel
Easting / Northing	700255 / 742872	Distance from Proposed Development	0m
Significance	Medium		
Description	<ul style="list-style-type: none"> - A series of linear features forming fields, with cultivation patterning, and a wide (approximately 23m) channel. - Not depicted on historic Ordnance Survey mapping. - Visible on aerial imagery. - Interpreted as possible field system of unknown date and possible palaeochannel. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_25	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Dunboyne	Site Type	Ditch
Easting / Northing	701300 / 743510	Distance from Proposed Development	0m
Significance	Low		
Description	<ul style="list-style-type: none"> - A curvi-linear feature measuring approximately 118m in length, extends from south-north before turning west - possibly truncated by the R157 (may continue in fields to the north). - Vaguely perceptible on aerial imagery (GoogleEarth, 01/2017, 03/2021). - No corresponding features are depicted on historic Ordnance Survey mapping (1837, 1911). - Tentatively interpreted as a possible ditch of unknown date and function. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_26	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Bennettstown	Site Type	Field boundary(ies)
Easting / Northing	701312 / 743773	Distance from Proposed Development	2m to the west of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A linear feature measuring approximately 276m in length and orientated routh north-south between two extant field boundaries. - A field boundary is depicted on historic Ordnance Survey mapping in this location. - Visible on aerial imagery. - Interpreted as a post-medieval former field boundary. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_27	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Pace	Site Type	Palaeochannel
Easting / Northing	701933 / 744352	Distance from Proposed Development	10m to the east of the Proposed Development
Significance	Medium		
Description	<ul style="list-style-type: none"> - A curvilinear channel measuring up to approximately 50m in width. Cultivation patterns noted overlying the feature. - Located near a late bronze age site (http://excavations.ie/report/2005/Meath/0014235/) and a circular feature is located outside Study Area on a more elevated location near channel which may evidence early human activity. - Visible on aerial imagery. - Not depicted on historic Ordnance Survey mapping. - Field known as 'Slang' and 'Big Field'. Three Archaeological sites (one minor, second thought to be a site for butchering and skinning near the stream, third - old farmhouse brick, cobbled yard, small sheds mid 1700's). Pace - pass or route between soft ground via glacial ridges, long before field ditches were dug. See field 20 for notes on laneway. The lake here is more of a pond. (Meath Field Names Project, 2019). - Located near a channel of alluvium (Geological Survey of Ireland, n.d.) - Tentatively interpreted as a possible palaeochannel (possibly a former tributary of the River Tolka). ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_28	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Pace	Site Type	Field boundary(ies)
Easting / Northing	702086 / 744592	Distance from Proposed Development	12m to the south of the Proposed Development
Significance	Very Low / Negligible		
Description	- A linear feature measuring approximately 157m (extending outside the Study Area) and orientated north-south in an agricultural field to the south of the L5026. - Field known as 'Burns Field' (Meath Field Names Project, 2019). Visible on aerial imagery. - Corresponds with a field boundary depicted on historic Ordnance Survey mapping (1837). - Interpreted as a section of former field boundary. ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_29	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Stokestown	Site Type	Field boundary(ies)
Easting / Northing	703060 / 744617	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	- A linear feature measuring approximately 198m in length (extends outside the Study Area), orientated north-south, extending from the road to an extant field boundary. - Visible on aerial imagery (GoogleEarth, 01/2017). - Field known as 'Daisy Field' (Meath Field Names Project, 2019). - Corresponds with a former field boundary depicted on later historic Ordnance Survey mapping (1911). ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_30	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Stokestown	Site Type	Gravel pit
Easting / Northing	703082 / 744602	Distance from Proposed Development	30m to the north of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - An irregular area measuring approximately 32m across, with narrow linear features running from it. Located in a pasture field to the north of the road through Stokestown. - Not depicted on historic Ordnance Survey mapping. - Field known as 'Daisy Field' (Meath Field Names Project, 2019). - Visible on aerial imagery. - Tentatively interpreted as a possible gravel pit of unknown date; however, could equally be the result of modern disturbance or drainage. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_31	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Kinoristown	Site Type	Enclosure
Easting / Northing	703318 / 744520	Distance from Proposed Development	46m to the south-east of the Proposed Development
Significance	Medium		
Description	<ul style="list-style-type: none"> - An ephemeral circular area approximately 30m in diameter. - Not depicted on historic mapping (1837, 1911). - Field known as 'Pillar Field' (Meath Field Names Project, 2019). - Visible on aerial imagery as a circular feature within a pasture field adjacent to the road (e.g. GoogleEarth, 06/2020). - Tentatively interpreted as a possible enclosure of unknown date. ^[1] <p>This asset comprises a previously unrecorded possible univallate enclosure, and may contribute to the understanding of rural settlement, the pattern and relationship between enclosures, and the local pastoral economy. ^[2]</p>		
Sources	<ol style="list-style-type: none"> 1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 2. Jacobs July 2023 		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_32	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Kinoristown	Site Type	Field boundary(ies)
Easting / Northing	703386 / 744557	Distance from Proposed Development	6m to the south-east of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A linear feature measuring approximately 147m in length orientated roughly north-west to south-east. - Visible on aerial imagery (GoogleEarth, various). - Field known as 'Pillar Field' (Meath Field Names Project, 2019). - Corresponds with a former field boundary depicted on historic Ordnance Survey mapping (1837), with later mapping showing the feature as a drainage ditch. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_33	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Kinoristown	Site Type	Gravel pit
Easting / Northing	703648 / 744879	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A large irregular area measuring approximately 90m across located in an agricultural field adjacent to an extant field boundary. - Vaguely perceptible on aerial imagery. - Extractive activity is depicted in this location on historic Ordnance Survey mapping (1911). ^[1] - Not visible during site inspection and walkover (June 2023). ^[2] 		
Sources	<ol style="list-style-type: none"> 1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 2. Jacobs site inspection and walkover survey, June 2023 		

Unique Reference Number	LI_34	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Stokestown	Site Type	Enclosure
Easting / Northing	703612 / 745032	Distance from Proposed Development	17m to the west of the Proposed Development
Significance	Medium		
Description	<ul style="list-style-type: none"> - A curvi-linear feature measuring approximately 41m in diameter. Truncated by a later drainage ditch. - Vaguely perceptible on aerial imagery. - Not depicted on historic Ordnance Survey mapping. - Tentatively interpreted as part of a circular enclosure; however, could equally be modern disturbance. ^[1] <p>This asset comprises a previously unrecorded possible univallate enclosure, and may contribute to the understanding of rural settlement, the pattern and relationship between enclosures, and the local pastoral economy. ^[2]</p>		
Sources	<ol style="list-style-type: none"> 1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 2. Jacobs July 2023 		

Unique Reference Number	LI_35	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Stokestown	Site Type	Field boundary(ies)
Easting / Northing	703570 / 745029	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A curvi-linear feature measuring approximately 164m in length (extends beyond the Study Area). Cultivation patterns and ephemeral linear features running parallel interpreted as drainage were also noted. - Visible on aerial imagery (GoogleEarth, various). - Corresponds with a field boundary depicted on historic Ordnance Survey mapping (1837, 1911). ^[1] 		
Sources	<ol style="list-style-type: none"> 1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 		

Unique Reference Number	LI_36	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Nuttstown	Site Type	Palaeochannel
Easting / Northing	704173 / 745029	Distance from Proposed Development	0m
Significance	Medium		
Description	<ul style="list-style-type: none"> - A meandering linear feature located in a pasture field to the north of an extant watercourse (Pinkeen River). - Not depicted on historic Ordnance Survey mapping; however located in an area adjacent to the current channel of the Pinkeen River. - Located near a channel of alluvium (Geological Survey of Ireland, n.d.). - Visible on aerial imagery. - Tentatively interpreted as a possible palaeochannel, or river terrace, associated with the Pinkeen River. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_37	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Preist Town	Site Type	Gravel pit
Easting / Northing	705675 / 745507	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - An irregular area on a localised mound within an area of established woodland. - The area is depicted as woodland, 'Crockanee', on historic Ordnance Survey mapping on the southern boundary of the Priest Town House demesne (DL_04). A track is shown into the woodland from the road to the south. To the north-east, an area of woodland is the location of a gravel pit. Later mapping shows this area as mixed woodland. - Not visible on aerial imagery. - Located adjacent to the Ward River, in an area of till derived from limestones. - Interpreted as a possible post-medieval gravel pit. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_38	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Court	Site Type	Field boundary(ies)
Easting / Northing	707407 / 744527	Distance from Proposed Development	12m to the east of the Proposed Development
Significance	Very Low / Negligible		
Description	- A linear feature measuring approximately 134m in length and orientated roughly north-west to south-east. - Visible on aerial imagery located within a small irregular field between a watercourse and an extant field boundary. - Corresponds with a former field boundary depicted on historic Ordnance Survey mapping (1843, 1908). ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_40	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Irishtown	Site Type	Enclosure
Easting / Northing	708484 / 743851	Distance from Proposed Development	0m
Significance	Medium		
Description	- A curved feature measuring approximately 88m in diameter, located in an agricultural field with an extant field boundary running across it from west-east and track. Comprises a raised interior with a circular enclosing ditch (continuing into the field to the north) and very ephemeral interior bank. A circular wear pattern around a modern animal feeder is also visible within the enclosure. - Not depicted on historic Ordnance Survey mapping. - Vaguely perceptible on aerial imagery (GoogleEarth, 01/2017, 02/2021). - Tentatively interpreted as a possible large enclosure of unknown date; however could equally be a natural rise or modern disturbance. ^[1] This asset comprises a previously unrecorded possible univallate enclosure, and may contribute to the understanding of rural settlement, the pattern and relationship between enclosures, and the local pastoral economy. ^[2]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 2. Jacobs July 2023		

Unique Reference Number	LI_41	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Irishtown	Site Type	Designed landscape feature
Easting / Northing	708541 / 743797	Distance from Proposed Development	15m to the south of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - An irregular area measuring approximately 15m across. - Not visible on aerial imagery. - Corresponds with the location of a 'pond' within the Hollywoodrath demesne (DL_05) depicted on historic Ordnance Survey mapping (1843, 1909). - Interpreted as an infilled pond; however, could equally be modern disturbance.^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_42	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Spicklestown	Site Type	Ditch
Easting / Northing	708615 / 743823	Distance from Proposed Development	0m
Significance	Low		
Description	<ul style="list-style-type: none"> - A linear feature measuring approximately 60m in length orientated roughly east-west within an area of trees. A number of extant drainage ditches are located in this area. - No corresponding feature is depicted on historic Ordnance Survey mapping; however, an area of woodland is depicted on later editions. - Not visible on aerial imagery. - Tentatively interpreted as a ditch of unknown date.^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_44	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Ward Lower	Site Type	Building
Easting / Northing	710297 / 745265	Distance from Proposed Development	14m to the north-west of the Proposed Development
Significance	Low		
Description	<ul style="list-style-type: none"> - A rectangular feature measuring approximately 14m by 18m located in the corner of an agricultural field adjacent to the R121. - Two buildings and a number of boundary features are depicted in this location on historic Ordnance Survey mapping (1843); however, these are no longer shown on later editions (1908). - Vaguely perceptible on aerial imagery. - Tentatively interpreted as the site of two demolished post-medieval buildings; however, could equally likely be modern disturbance.^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_45	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Newpark	Site Type	Field boundary(ies)
Easting / Northing	710545 / 745302	Distance from Proposed Development	37m to the south-east of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - An irregular linear feature orientated roughly north-south, measuring approximately 110m (extends outside the Study Area). - Visible on aerial imagery. - Corresponds with a field boundary depicted on historic Ordnance Survey mapping.^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_46	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Newpark	Site Type	Field boundary(ies)
Easting / Northing	710680 / 745350	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - An irregular linear feature orientated roughly north-south, measuring approximately >195m (extends outside the Study Area and extent of LiDAR data coverage). - Visible on aerial imagery. - Corresponds with a field boundary depicted on historic Ordnance Survey mapping. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_47	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Newpark	Site Type	Gravel pit
Easting / Northing	711033 / 745741	Distance from Proposed Development	15m to the north of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - An irregular area measuring approximately 60m across located in an agricultural field to the north of the R121. - No corresponding features on historic Ordnance Survey mapping; however, areas of extraction are depicted on later editions (1908) to the north-east. - Located in an area identified as 'gravels' (Geological Survey of Ireland, n.d.). - Interpreted as a possible gravel pit of unknown date. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_48	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Shallon	Site Type	Field boundary(ies)
Easting / Northing	711649 / 745855	Distance from Proposed Development	30m to the north-east of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A curvi-linear feature measuring approximately 70m in length, extending from the Ward River (to the north) before curving to the east. - Depicted on historic Ordnance Survey mapping bounding an area of trees. - Visible on aerial imagery. - Interpreted as a former post-medieval field boundary. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_49	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Corrstown	Site Type	Ditch
Easting / Northing	711925 / 745900	Distance from Proposed Development	8m to the north of the Proposed Development
Significance	Low		
Description	<ul style="list-style-type: none"> - A very ephemeral negative linear feature with possible bank, measuring approximately 46m in length, and orientated roughly north-south. - No corresponding features are depicted on historic Ordnance Survey mapping. - Faintly perceptible on aerial photography. - Tentatively interpreted as a possible bank and ditch of unknown date. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_50	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Corrstown	Site Type	Field boundary(ies)
Easting / Northing	712144 / 745847	Distance from Proposed Development	6m to the north of the Proposed Development
Significance	Very Low / Negligible		
Description	- A linear feature that extends outside the Study Area, measuring approximately 122m before turning east and north. - Visible on aerial imagery (GoogleEarth, 05/2017). - Corresponds with a field boundary depicted on historic Ordnance Survey mapping (1843; 1908). ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_51	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Skephubble	Site Type	Field boundary(ies)
Easting / Northing	712584 / 745451	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	- A curvi-linear feature measuring approximately 78m in length extending between two extant field boundaries. - Visible on aerial imagery. - Corresponds with a field boundary on historic Ordnance Survey mapping (1843), and later editions depicted the feature as a ditch (1908). The boundary has been removed by the last edition (1941). ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_54	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Cloghran	Site Type	Enclosure
Easting / Northing	718228 / 743875	Distance from Proposed Development	0m
Significance	Medium		
Description	<p>- A group of features including a large sub-circular enclosing feature measuring approximately 76m by 64m and a circular feature measuring approximately 10m in diameter, in a pasture field to the south of Stockhole Lane. A more recent circular feature is also located to the south-east overlying the enclosing feature.</p> <p>- Visible on aerial imagery.</p> <p>- Not depicted on historic Ordnance Survey mapping.</p> <p>- Tentatively interpreted as a possible large enclosure with internal feature; however, could equally be a modern animal exercising arena and associated disturbance. ^[1]</p>		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_55	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Cloghran	Site Type	Road
Easting / Northing	718232 / 743855	Distance from Proposed Development	31m to the south of the Proposed Development
Significance	Very Low / Negligible		
Description	<p>- A linear feature measuring approximately 80m in length running through an agricultural field from an extant driveway to an area of rough ground.</p> <p>- The alignment of the road is depicted in this location on historic Ordnance Survey mapping (1843) in this location through Glebe House and farm. The alignment of the road is depicted as straightened on later mapping (1909).</p> <p>- Visible on aerial imagery.</p> <p>- Interpreted as the former alignment of the road. ^[1]</p>		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_56	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Cloghran	Site Type	Field boundary(ies)
Easting / Northing	718467 / 743815	Distance from Proposed Development	28m to the south of the Proposed Development
Significance	Very Low / Negligible		
Description	- A linear feature measuring approximately 230m located within an agricultural field to the south of Stockhole Lane and west of the M1 motorway. Cultivation patterns and possible disturbance was also noted. - Visible on aerial imagery. - Corresponds with a former field drain depicted on historic Ordnance Survey mapping (1843). ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_57	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Cloghran	Site Type	Field boundary(ies)
Easting / Northing	718741 / 743816	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	- A linear feature measuring approximately 40m located within an area of rough ground to the east of the M1 motorway. Appears to be a continuation of LI_084. - Visible on aerial imagery. - Corresponds with a former field drain depicted on historic Ordnance Survey mapping (1843). ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_58	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Cloghran	Site Type	Palaeochannel
Easting / Northing	719099 / 743483	Distance from Proposed Development	0m
Significance	Medium		
Description	<ul style="list-style-type: none"> - A 43m wide channel located within a narrow pasture field north of a watercourse. - Visible on aerial imagery. - Not depicted on historic Ordnance Survey mapping; however, a stream is depicted on later editions (1909) as a field boundary. - Tentatively interpreted as a possible palaeochannel or river terraces. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_60	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Clonshaugh	Site Type	Field boundary(ies)
Easting / Northing	719034 / 742029	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A narrow linear feature measuring approximately 150m in length and orientated north-south located within an agricultural field, running between two extant field boundaries. - Visible on aerial imagery (GoogleEarth, 06/2018). - Corresponds with a field boundary depicted on historic Ordnance Survey mapping (1837; 1911). ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_61	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Lynaghstown	Site Type	Field boundary(ies)
Easting / Northing	694594 / 744981	Distance from Proposed Development	4m to the south of the Proposed Development
Significance	Very Low / Negligible		
Description	- A linear feature measuring approximately 118m in length and orientated north-south located within a field currently in use for plantation, south of the R156. - Visible on aerial imagery. - Corresponds with a field boundary depicted on historic Ordnance Survey mapping (1837; 1911). ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_62	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Blackhall Big	Site Type	Boundary
Easting / Northing	695757 / 744397	Distance from Proposed Development	3m to the south of the Proposed Development
Significance	Very Low / Negligible		
Description	- A negative rectangular feature measuring approximately 31m by 28m located within a field, south of the R156. - Faintly perceptible on aerial imagery (GoogleEarth, 10/2009, 05/2017). - Corresponds with a boundary depicted on historic Ordnance Survey mapping (1837; 1911). ^[1]		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Unique Reference Number	LI_63	Reference Number(s)	
Figure Number	Figure 13.5 in Volume 4	Legal Status	
Townland	Harlockstown	Site Type	Enclosure
Easting / Northing	696778 / 744130	Distance from Proposed Development	2m to the north of the Proposed Development
Significance	Low		
Description	<ul style="list-style-type: none"> - A negative rectangular feature measuring approximately 18m by 10m located within a field, north of the R156. Two adjoining linear features are visible extending from the corners of the enclosure suggesting it may be part of a larger complex. - Visible on aerial imagery. - No corresponding features on historic Ordnance Survey mapping. - Tentatively interpreted as a small rectangular enclosure of unknown date. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_65	Reference Number(s)	
Figure Number	Figure 13.5 in Volume 4	Legal Status	
Townland	Vesingtown	Site Type	Enclosure
Easting / Northing	697728 / 744108	Distance from Proposed Development	48m to the north of the Proposed Development
Significance	Medium		
Description	<ul style="list-style-type: none"> - An ephemeral circular feature measuring approximately 17m in diameter, located within an agricultural field to the north of the R156. - Not visible on aerial imagery. - No corresponding features on historic Ordnance Survey mapping. - Tentatively interpreted as a possible enclosure of unknown date. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_66	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Cushinstown	Site Type	Track
Easting / Northing	699779 / 743165	Distance from Proposed Development	3m to the north-east of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A pair of parallel linear features measuring approximately 180m in length, orientated roughly north-south located within an agricultural field. - Visible on aerial imagery. - No corresponding features on historic Ordnance Survey mapping. - Interpreted as a possible track of unknown date. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_67	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Dunboyne	Site Type	Boundary
Easting / Northing	700710 / 743081	Distance from Proposed Development	0m
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - A pair of parallel linear features measuring approximately >185m in length (extending outside the Study Area), orientated roughly north-west to south-east located within an agricultural field. - Field known as 'Weld Fields / Wild Fields' (Meath Field Names Project, 2019). - Visible on aerial imagery. - Correspond with a boundary feature on historic Ordnance Survey mapping (1837), with later mapping showing the boundary as a belt of trees (1911). ^[1] <p>Possibly continues into fields to the south of the road (DigitalGlobe). Former field boundaries are also visible in the fields in this area. ^[2]</p>		
Sources	<ol style="list-style-type: none"> 1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 2. Digital Globe Aerial Imagery 		

Unique Reference Number	LI_68	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Dunboyne	Site Type	Gravel pit
Easting / Northing	701057 / 743391	Distance from Proposed Development	19m to the west of the Proposed Development
Significance	Very Low / Negligible		
Description	<ul style="list-style-type: none"> - An irregular area measuring approximately 16m across located in an area of rough ground south of Kennedy Road. - A possible gravel pit is depicted on historic Ordnance Survey mapping (1837, 1911). - Interpreted as a possible post-medieval gravel pit. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

Unique Reference Number	LI_69	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Pace	Site Type	Palaeochannel
Easting / Northing	701568 / 744101	Distance from Proposed Development	15m to the north of the Proposed Development
Significance	Medium		
Description	<ul style="list-style-type: none"> - A narrow sinuous curvi-linear feature within an area of rough ground north-east of the River Tolka. - Not visible on aerial imagery. - Located within an area of alluvium (Geological Survey of Ireland, n.d.). - The meandering course of the river is depicted on historic Ordnance Survey mapping (1837), then later shown as straightened (1911) with the former channel still depicted. - Interpreted as the former channel of the River Tolka. ^[1] <p>Channel not visible at ground level; however, pasture field with some wetland-type grasses noted (walkover and site inspection, June 2023). ^[2]</p>		
Sources	<ol style="list-style-type: none"> 1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR 2. Jacobs site inspection and walkover survey, June 2023 		

Unique Reference Number	LI_70	Reference Number(s)	-
Figure Number	Figure 13.5 in Volume 4	Legal Status	-
Townland	Spicklestown	Site Type	Ditch
Easting / Northing	708628 / 743753	Distance from Proposed Development	28m to the south of the Proposed Development
Significance	Low		
Description	<ul style="list-style-type: none"> - A negative curvi-linear feature measuring approximately 103m in length, within an agricultural field in DL_05. - Visible on aerial imagery. - No corresponding features on historic Ordnance Survey mapping. - Tentatively interpreted as a possible ditch of unknown date. ^[1] 		
Sources	1. Appendix A13.2 (LiDAR Review for CP1021: East Meath to North Dublin Grid Upgrade) in Volume 3 of this EIAR		

6. Inventory of Townland Boundaries

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Townland Boundary Reference Number	Townland Names	Description	Significance
TB_01	Woodland - Gaulstown	Field boundary - an established hedgerow and ditch (drainage) within an area of agricultural fields	Medium
TB_02	Woodland - Culcommon	Field boundary - an established hedgerow and ditch (drainage) within an area of agricultural fields	Low
TB_03	Gaulstown - Culcommon	Field boundary - an established hedgerow and ditch within an area of agricultural fields	Low
TB_04	Gaulstown - Cullendraugh	Field boundary - an established hedgerow and ditch (drainage) within an area of agricultural fields	Medium
TB_05	Culcommon - Cullendraugh	Field boundary - an established hedgerow within an area of agricultural fields	Low
TB_06	Culcommon - Barstown	Visible as a cropmark in the large irregular field to the south of the R156 (former field boundary; CH_59)	Low
TB_07	Barstown - Lynaghstown	Field boundary - an established hedgerow	Low
TB_08	Culcommon - Ballymaglassan	Field boundary - an established hedgerow	Low
TB_09	Lynaghstown - Blackhall Big	The alignment of the R156 and a property boundary	Very Low / Negligible
TB_10	Blackhall Big - Staffordstown Little	The alignment of the R156 and a local lane	Very Low / Negligible
TB_11	Blackhall Big - Harlockstown	Alignment of a former field boundary (now removed); modern replacement north of the R156	Very Low / Negligible
TB_12	Staffordstown Little - Harlockstown	Alignment of the R156 Regional Road	Very Low / Negligible
TB_13	Staffordstown Little - Waynestown	Field boundary - an established hedgerow	Low
TB_14	Harlockstown - Waynestown	Alignment of the R156 Regional Road and a section of extant field boundary, to the south of the road	Low
TB_15	Harlockstown - Vesington	Field boundary - an established hedgerow (bisected by the R156 Regional Road)	Low
TB_16	Vesington - Baytownpark	Lane / local road crossed by the R156 Regional Road	Very Low / Negligible
TB_17	Baytownpark - Sarney	Alignment of the R156 Regional Road and an extant field boundary running south, perpendicular from the road	Low
TB_18	Baytownpark - Cushingtown	Field boundary - an established hedgerow	Low
TB_19	Sarney - Cushinstown	Alignment of the R156 Regional Road, modern garden boundaries and an established field boundary	Low
TB_20	Cushinstown - Colliersland North	Alignment of the R156 Regional Road and local access road	Very Low / Negligible
TB_21	Cushinstown - Dunboyne	Property boundary	Very Low / Negligible
TB_22	Colliersland North - Dunboyne	Alignment of the R156 Regional Road and a property boundary	Very Low / Negligible
TB_23	Dunboyne - Bennetstown	Established field boundary (bisected by the R157 Regional Road)	Low
TB_24	Bennetstown - Pace	Established field boundary (partially removed by the R157 Regional Road)	Very Low / Negligible

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Townland Boundary Reference Number	Townland Names	Description	Significance
TB_25	Woodpark - Pace	Removed by M3 Motorway	Very Low / Negligible
TB_26	Woodpark - Piercetown	Removed by M3 Motorway	Very Low / Negligible
TB_27	Piercetown - Pace	Sections of established field boundary / property boundaries, alignment of the L5026 Local Road	Very Low / Negligible
TB_28	Piercetown - Ballymagillin	Local commercial access track north of the L5026 Local Road	Very Low / Negligible
TB_29	Ballymagillin - Pace	Alignment of the L5026 Local Road	Very Low / Negligible
TB_30	Whitesland - Ballymagillin	An established hedgerow and ditch (drainage) adjacent to a farm complex (CH_12)	Low
TB_31	Pace - Whitesland	Field boundary - an established hedgerow within an area of agricultural fields	Low
TB_32	Whitesland - Pace	Field boundary - an established hedgerow within an area of agricultural fields and the alignment of the L5026 Local Road	Low
TB_33	Whitesland - Stokestown	Established field boundary	Low
TB_34	Pace - Stokestown	Alignment of the L5026 Local Road	Very Low / Negligible
TB_35	Pace - Normansgrove	Visible as a cropmark in the large agricultural field to the south of the L5026 Local Road	Low
TB_36	Normansgrove - Stokestown	Alignment of the L5026 Local Road and local lane	Very Low / Negligible
TB_37	Kinoristown - Stokestown	Alignment of the L5026 Local Road and extant field boundaries	Low
TB_38	Stokestown - Rowan	Established field boundary and section of watercourse (Pinkeen River)	Medium
TB_39	Rowan - Nuttstown	Pinkeen River	Medium
TB_40	Nuttstown - Ballintry	Alignment of Belgree Lane	Very Low / Negligible
TB_41	Ballintry - Belgree	Modern property boundary	Very Low / Negligible
TB_42	Nuttstown - Belgree	Alignment of Belgree Lane	Very Low / Negligible
TB_43	Nuttstown - Priest Town	Established field boundary	Low
TB_44	Priest Town - Belgree	River Ward	Medium
TB_45	Ballymacarney - Belgree	Alignment of a local lane and extant field boundary (bisected by Kilbride Road)	Low
TB_46	Belgree - Ballymacarney	Extant field boundary	Low
TB_47	Belgree - Court	Extant field boundary (ditch)	Low
TB_48	Ballymacarney - Court	Extant field boundary (bisected by Kilbride Road)	Low
TB_49	Court - Court	Established field boundary (bisected by Kilbride Road)	Low
TB_50	Court - Gallanstown	Extant field boundary (bisected by Kilbride Road)	Low

East Meath - North Dublin Grid Upgrade
Environmental Impact Assessment Report (EIAR): Volume 3

Townland Boundary Reference Number	Townland Names	Description	Significance
TB_51	Gallanstown - Yellow Walls	Extant field boundary (modern residential development has removed some)	Low
TB_52	Yellow Walls - Hollystown	Established field boundary (hedgerow)	Low
TB_53	Gallanstown - Hollystown	Extant field boundary	Low
TB_54	Hollystown - Irishtown	Local lane (Hollywood)	Very Low / Negligible
TB_55	Gallanstown - Irishtown	Local lane (Hollywood)	Very Low / Negligible
TB_56	Hollywood - Irishtown	Extant field boundary	Low
TB_57	Irishtown - Spicklestown	Extant field boundary (some sections missing)	Low
TB_58	Spicklestown - Killamonan	Alignment of the R121 Regional Road and a property boundary	Very Low / Negligible
TB_59	Spicklestown - Ward Lower	Property access and boundary	Very Low / Negligible
TB_60	Spicklestown - Cherryhound	Property boundary (disturbed)	Very Low / Negligible
TB_61	Ward Lower - Cherryhound	Alignment of the R121 Regional Road	Very Low / Negligible
TB_62	Cherryhound - Ward Upper	Property boundary / access track	Very Low / Negligible
TB_63	Ward Lower - Ward Upper	Alignment of the R121 Regional Road	Very Low / Negligible
TB_64	Ward Lower - Newpark	Alignment of a local road (Newpark) adjacent to a farm complex (CH_25)	Very Low / Negligible
TB_65	Ward Upper - Newpark	Alignment of a local road (Newpark)	Very Low / Negligible
TB_66	Newpark - Shallon	Property boundary, road (R121 Regional Road), field boundary	Very Low / Negligible
TB_67	Shallon - Shallon	Watercourse (crossed by the R121 Regional Road)	Medium
TB_68	Newpark - Shallon	Watercourse	Medium
TB_69	Corrstown - Shallon	Alignment of the R121 Regional Road. Boundary not visible in fields to the north of the road	Very Low / Negligible
TB_70	Corrstown - Shallon	Alignment of the R121 Regional Road. Boundary not visible in fields to the north of the road	Very Low / Negligible
TB_71	Shallon - Ballystrahan	Alignment of a local lane south of the R121 Regional Road	Very Low / Negligible
TB_72	Corrstown - Ballystrahan	Alignment of the R121 Regional Road	Very Low / Negligible
TB_73	Corrstown - Skephubble	Alignment of the R122 Regional Road	Very Low / Negligible
TB_74	Ballystrahan - Skephubble	Alignment of the R122 Regional Road	Very Low / Negligible
TB_75	Kilreesk - Ballystrahan	Alignment of the R122 Regional Road with and extant field boundary running perpendicular to the road to the east and a property boundary to the west	Very Low / Negligible
TB_76	Kilreesk - Kingstown	Extant field boundary, bisected by road (Kilreesk Lane)	Low

East Meath - North Dublin Grid Upgrade
 Environmental Impact Assessment Report (EIAR): Volume 3

Townland Boundary Reference Number	Townland Names	Description	Significance
TB_77	Kingstown - Barberstown	Extant field boundary (bisected by road; R108 Regional Road)	Low
TB_78	Barberstown - Pickardstown	Extant field boundary (bisected by road; R108 Regional Road)	Low
TB_79	Pickardstown - Forrest Great	Extant field boundary (bisected by road; R108 Regional Road)	Low
TB_80	Forrest Great - Forrest Little	Extant field boundary (bisected by road; Naul Road)	Very Low / Negligible
TB_81	Forrest Little - Cloghran	Extant field boundary (bisected by road; Naul Road)	Low
TB_82	Cloghran - Glebe	Extant field boundary (hedgerow)	Low
TB_83	Glebe - Baskin	Extant Field boundary	Low
TB_85	Stockhole - Middleton	Local lane	Low
TB_86	Middleton - Clonshaugh	Extant field boundary and section of R122 Regional Road	Low
TB_87	Clonshaugh - Belcamp	Extant field boundary	Low
TB_88	Creemore - Woodland	Watercourse	Medium
TB_89	Creemore - Portan	Watercourse	Medium
TB_90	Woodland - Portan	Extant field boundary (some removed)	Low
TB_91	Stokestown - Nuttstown	Pinkeen River	Medium
TB_92	Hollystown - Yellow Walls	No longer extant	Very Low / Negligible
TB_93	Hollystown - Hollywood	Property boundary	Very Low / Negligible
TB_94	Nevinstown East - Cloghran	Field boundary - an established hedgerow within an area of agricultural fields	Low
TB_95	Stockhole - Glebe	Field boundary - an established hedgerow within an area of agricultural fields	Low
TB_96	Glebe - Baskin	Field boundary - an established hedgerow within an area of agricultural fields	Low
TB_97	Stockhole - Baskin	Field boundary - an established hedgerow	Low
TB_98	Stockhole - Clonshagh	Alignment of the R122 Regional Road	Very Low / Negligible
TB_99	Belcamp	Watercourse	Medium