

APPENDIX 14.1

Description of recorded archaeological monuments located within 2km of the proposed development site. And 100m from the proposed grid connection route.

RECEIVED 19/01/2024

Please note that the following descriptions are derived from 'The Archaeological Inventory of County Leitrim' compiled by Michael J. Moore (Dublin: Stationery Office, 2003). In certain instances, the entries have been revised and updated by the Archaeological Survey of Ireland in the light of recent research.

RMP No. LE017-012----

Townland: Corralustia

Monument type: Burnt mound

This site is located c. 1.3km from the proposed development site. Situated in the S bank of a small WNW-ENE stream or drain on a gentle north-facing slope. An area of burnt stone in a black soil matrix (Length 5m; width 1m) lies exposed along the bank of the stream.

RMP No. LE017-004001-

Townland: Lugmeeltan

Monument type: Ringfort

Located c. 1.3km from the proposed development site and 80m from the proposed grid connection route. Situated on a north-facing slope with a small SSW-NNE stream immediately to the west. This is a grass and rush-covered D-shaped area (33m by 24m; internal dimensions 28m by 23.3m) defined by a grass-covered earthen bank (Width 4-6m; internal height 0.3-0.7m) and an external rounded fosse with a scarp (Height 4m) down to the stream on the straight west side. There is an entrance (Width c. 4m), probably not original, at north-east. A rectangular house site (7m x 2.8m) at the centre is defined by a grass-covered stone spread (Width 1m; Height 0.3m) with a doorway (Width 1m) in the east wall.

RMP No. LE017-004002-

Townland: Lugmeeltan

Monument type: House

Located c. 1.3km from the proposed development site and 80m from the proposed grid connection route. Situated on a north facing slope with a small stream just to the west. A rectangular house-site (7m x 2.8m) at the centre of rath (LE017-004001-) is defined by a grass-covered stone spread (Width 1m; Height 0.3m) with a doorway (Width 1m) at east.