PROPOSED WORKS & MEASURES

NEW APPLICATION BOUNDARY OUTLINED IN RED

BOUNDARY OUTLINED IN RED
TOTAL AREA: 8.708 Hectares

Figure 3.1

Road Sign to indicate quarry ahead, sign erect approx 150m from quarry entrance.

120m Sight Lines to inner roadway verge.

Applicants Home House.

QUARRY SITE ENTRANCE

Site Notice erected on Existing Site Access Gate.

Photo 1-F
Access Road
Haul Road

120m Sight Lines to inner roadway verge.

Photo 1-G
Quarry Entrance

RUNN-OFF INTERCEPTOR DRAIN

EXISTING STONE WALL WITH ERECTED GATE

225mm DISCHARGE PIPE FROM QUARRY BOTTOM TO NORTHERN PART OF SITE VIA PUMP STATION, WATER NATURALLY FINDS ITS COURSE BACK TOWARDS QUARRY.

Access Gate.

Photo 1-E
Water Discharge Pipe from quarry floor.

SAFETY BARRIER AROUND QUARRY

EXISTING RIVER FLOWING WEST

MAIN QUARRIED SECTION TO DATE HIGHLIGHTED.

EXISTING QUARRY FACE HIGHLIGHTED IN GREEN, SEE ATTACHED SITE SECTION FOR GREATER DETAIL.

SAFETY BARRIER AROUND QUARRY

EXISTING RIVER FLOWING WEST

Fencing 1.2m in height with a terram screening 0.6m in height following the perimeter of the Quarry Boundary. 2no fences

EXISTING RIVER FLOWING WEST

Photo 1-A
Terram Fencing

Fencing 1.2m in height with a terram screening 0.6m in height following the perimeter of the Quarry Boundary.2 no fences

Existing Site Office(Portacabin)(See Supporting Photos)

Photo 1-C,D
Site Office

Photo 1-B
Work Area

Concrete Hardstand Area where the Stone cutting machinery is mounted.(See supporting Photos)

10m x 3m x 1m SILT TRAPS TO COLLECT ANY EXCESS SILT ARISING FROM THE POLISHED WATER BEING PUMPED FROM THE QUARRY.

225mm DISCHARGE PIPE

VEGATATION FILTER

RUNN-OFF INTERCEPTOR DRAIN

Fencing 1.2m in height with a terram screening 0.6m in height following the perimeter of the Quarry Boundary.2 no fences

SITE SECTION A - A

SITE SECTION B - B

DRAWING NOTES:

APPENDIX (1)

Photo 1-F
Access Road
Haul Road

Photo 1-G
Quarry Entrance

DRAWING NOTES:

APPENDIX (1)

Photo 1-A
Terram Fencing

Photo 1-B
Work Area

Photo 1-C,D
Site Office

Photo 1-C,D
Site Office

Photo 1-E
Water Discharge Pipe from quarry floor.

1. ALL STRUCTURAL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH BONDED STRUCTURAL ENGINEER'S DESIGN.
2. ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH 1997 BUILDING REGULATIONS AND ANY SUBSEQUENT REVISIONS THEREAFTER.
3. THIS DRAWING IS FOR PLANNING PERMISSION PURPOSES ONLY.
4. DO NOT SCALE FROM THIS DRAWING.
5. ALL DIMENSIONS TO BE CHECKED ON SITE.

SCALE:	1:500 A0	TITLE:	SITE LAYOUT
DATE:	01.05.2013	DWG NO:	08-13 DWG.
PREPARED BY:	P O RAGHALLAIGH	CHECKED BY:	P. O RAGHALLAIGH

PROJECT:

QUARRY AT SHANNAPHEASTEEN REIA
APPLICANT MR. STIOFÁN O LORCÁIN

CLIENT: STIOFÁN O LORCÁIN

PROFE
ARCHITECTURAL DESIGN & PLANNING CONSULTANTS
PROFESSIONAL DESIGN SERVICES
BALE CARRIGIN, AN SPIDAL, CO NA GALLIMHE
TEL: 087-6882547 WEBSITE: WWW.PROFEDESIGNS.COM
EMAIL: INFO@PROFEDESIGNS.COM