

Appendix 14-1- List of all SMR's and Brief Description



14.1 LIST OF ALL SMR'S AND BRIEF DESCRIPTION

LIST OF RECORDED MONUMENTS WITH DESCRIPTIONS - DERRYAROGUE BOG

AGHAMORE (Ardagh By.), COMMONS NORTH, KNOCK, LANESBOROUGH

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF017-031-	BURNT PIT	604100,771554	204150,271535	YES
DESCRIPTION An irregularly shaped pit (2.5m x 1.55m; D 0.13m) was discovered during monitoring, c. 200m N of Lanesborough, at the site of the ESB power station. It was subsequently excavated in 2003 and three layers of fill were identified. The uppermost fill contained charcoal-rich, silty clay in which a fragment of bone and a piece of burnt chert were found. Below this was a deposit of mottled, silty clay with charcoal flecks containing six sherds of pottery that are likely to be prehistoric in date. The base comprised a compact band of oxidised, heat-reddened clay (Powell 2003, 6-7).				

SMR	CLASS	INCLUSION IN NEXT SMR
LF017-003	Historic town	YES
DESCRIPTION At a crossing point on the river Shannon where it enters Lough Ree. Lanesborough was formerly known as Athleague or Ballyleague (AFM vol. 1, 1063, 1109; vol. 3, 200) and Joyce (1871, 343) translates Béal Átha Liag as the mouth of the ford of the stones. It occupied a strategic border location on the river Shannon between the early medieval kingdoms of Connacht and Midhe and the modern counties of Longford and Roscommon. Records indicate that a causeway (LF017-003003-) was constructed across the river in 1000 (AFM, sub 1000; Ann. Clon., sub 994), while bridges (cliathdroichid) (LF017-003001-) were built in the mid-12th century (AFM, sub 1140 and 1154; Ann. Clon., sub 1132). In 1172 Walter de Lacy began to build a castle but it was not completed because Cathal Crobderg O Connobair, King of Connacht, forced him to abandon it (AFM; ALC; Ann. Clon., sub 1220). The castle (LF017-003002-) built in 1227 by the Irish Justiciar Geoffrey de Marisco (Ann. Conn.; AFM) may have been built on or close to its site. The latter castle appears to have been the spur to the development of a vill, for a charter of borough status was granted before 1235 (MacNiocaill 1977, 55). Upon Walter de Lacy's death in 1241, Lanesborough was inherited by John de Verdon (Otway-Ruthven 1968b, 411-13). Its situation made it vulnerable and in 1271 Aedh O Connobair attacked and destroyed the castle (Ann. Conn.; AFM; AU). In 1284 Theobald de Verdon was granted a charter to hold a weekly market (Cal. doc. Ire. vol. ii, 532). Whatever urban developments occurred probably fell victim to the political and economic difficulties of the early 14th century. The failure of the Anglo-Norman settlement is recorded in the 1332 partition of the lands of Theobald de Verdon. After		

his death Henry Ferrers, husband of Isabella de Verdon, was granted '18 carucates of land in the town of Ballilegge alias Beallalegge, now extended at no value because the land is waste and uncultivated for lack of tenants' (Othway-Ruthven 1968, 435).

The next references date to the late 16th and early 17th centuries: in 1572 Athleague was attacked by a rebellious faction of the Clanrickard Burkes, suggesting that the area was under the control of the English (Bradley et al. 1985, 26). Sir Patrick Barnewell, who built a 'fair and strong fort [LF017-003011-] and house' in the late 16th or early 17th century (Cal. S.P. Ire., 1611-14, 51), probably on the site of the levelled castle, was granted a licence in 1616 to hold a market and two fairs (Cal. pat. rolls Ire., Jas I, 304). In 1617/8 Thomas Rotherham was granted the 'castle and fort of Ballyleigg otherwise Bealaleig, and 300a ... lying about said castle, and next adjoining to the river Shannon' (ibid., 360). Gerald Murtagh received a grant of the lands of Ballyleague in 1620 as part of the plantation of Longford and he was also granted a licence to hold a market and a fair (ibid., 482). In 1664 the lands of Ballyleague, then held by Sir George Lane, were erected into the manor of Lanesborough and the town was constituted a free borough (Bradley et al., 1985, 26). The Down Survey (1655-6) map of Rathcline barony (NLI MS 716) depicts a small clustered settlement around the 'Fort of Ballyleague' and a church (LF017-003004-) on the E side of the Shannon and 'Ballyleag Castle' (RO037-004----), in county Roscommon, on the W bank. In 1682 Nicholas Dowdall noted that the town had 'fine stonehouses and very fair Church stately beautified within and with a Tall Steeple and Church Yard walled about' (Gillespie and Moran 1991, 208). A late-17th-century map of the town (NLI MS 8646/8) depicts the church, annotated 'old church', castle, an enclosed orchard and a cluster of low houses with centrally placed chimneystacks on the S side of a road leading down to a bridge (LF017-003001-). A large stone building on the SE side of the town is named the 'Lime house' and there is a mill to the NE of the bridge.

The extent of the 13th-century Anglo-Norman borough and its exact whereabouts are unknown. The 17th-century plantation settlement may overlies it but there is also a possibility that a formal medieval settlement was never established at this location. It may have been on the W bank of the Shannon, in the vicinity of Ballyleague castle (RO037-004----) in county Roscommon (Bradley et al. 1985, 29). The 17th-century borough appears to have been quite small, it consisted of one main street aligned NNW-SSE with long property plots extending off both sides of it. It may have functioned as a garrison town controlling the bridge (ibid., 26, 29). No traces of any 17th-century buildings are evident in the modern streetscape, and the castle (LF017-003002-) and fort (LF017-003011-) have been levelled.

LANESBOROUGH

SMR	CLASS	INCLUSION IN NEXT SMR
LF017-003001	Bridge	YES
DESCRIPTION Spanning the river Shannon at the NW end of Lanesborough (LF017-003----). Bridges built by Toirrdelbach Ua Conchobhair, King of Connacht, in 1140 (AFM, Ann. Clon. sub 1132) and again in 1154 (AFM) were probably built on or close to earlier fording points (see LF017-003003-). The term used in the annals to describe the bridges is 'cliathdroichet', which may be translated as wicker-bridge (Bradley et al. 1985, 25). In 1663, an Act was passed for 'the building of a bridge at Ballilegue [Ballyleague/Lanesborough] over the River Shannon between the counties of Longford and Roscommon' (Cal. S.P. Ire. 1663-5, 228). The bridge, built by Sir George Lane in 1667, was described in 1682 as 'a fair stone bridge ... built by the Contribution of several of the Adjacent Counties and is in length and breadth at this day the largest in the Kingdome' (Gillespie and Moran 1991, 208). The present bridge, dating to the c. 1835-43, was probably built on the site of the 17th-century structure, which in turn undoubtedly replaced the earlier medieval bridges and fords. (www.buildingsofireland.ie, Reg. 13310001, last accessed 26 March 2012)		

LANESBOROUGH

SMR	CLASS	INCLUSION IN NEXT SMR
LF017-003003	Ford	NO
DESCRIPTION At the NW end of Lanesborough (LF017-003----), which was known as Béal Átha Liag (Ballyleague) or Áth Liag (the mouth of the ford of the flagstones) before 1664 (Cal. S.P. Ire. 1663-5, 442; Bradley et al. 1985, 26; Gillespie and Moran 1991, 208). This was a major crossing point on the river Shannon at the NE end of Lough Ree, on a strategic boundary separating the early medieval kingdoms of Connacht and Meath and the modern counties of Longford and Roscommon. Causeways were constructed in AD 1000 by Mael Sechnaill, King of Midhe, and also by Cathal Ua Conchobhair (AFM; A. Clon. sub 994; Bradley et al. 1985, 25). Their exact location is unknown, although they were probably replaced by later bridges (see LF017-003001-).		

BALLYNAKILL

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF017-002001-	Road - gravel/stone trackway peatland	604100,771554	204150,271535	YES
DESCRIPTION This road, orientated NE-SW, was found at a depth of 0.09m below the bog surface. It was an extension of LF017-001---- and was recorded by Rynne in 1957 and excavated in 1958 (NMI I.A. 32/57; 4/58- Rynne).				

DERRYAROGUE

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF012-005001-	Road - class 3 togher	603650,771499	203700,271480	NO
DESCRIPTION A togher (L 12.9m min.; D 0.6m), orientated NW-SE, with a compact superstructure of longitudinal hazel and oak brushwood (diam. 0.02-0.03m), six pieces deep, supported by a transverse substructure of large roundwood (diam. 0.23m max.). In one section, a brushwood hurdle was used as the substructure. Toolmarks visible were quite degraded but may have been made by a stone tool.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF012-005002-	Road - class 3 togher	603730,771499	203780,271480	YES
DESCRIPTION A togher (Wth 1.26m; D 0.04m), orientated ESE-WNW, consisting of longitudinal hazel brushwood (diam. 0.02-0.035m) one piece deep and in a poor condition. Toolmarks may have been made by a stone implement.				

Derryadd Wind Farm - EIAR

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF017-002005-	Road - class 3 togher	603730,771119	,203780,271100	YES
DESCRIPTION A single oak plank (L 0.64m; Wth 0.41m; D 0.16m), orientated NNE-SSW.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF017-002002-	Road - class 2 togher	603840,771094	203890,271075	
DESCRIPTION A togher (L 124m; Wth 2.8m; D 0.3m), orientated ENE-WSW, consisting of a single layer of longitudinal ash roundwood (diam. 0.065-0.085m) with some hazel brushwood (av. diam. 0.025m). At its W end it was overlain by a layer of fine sand.				

DERRYAROGUE, MOUNT DAVYS

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF017-001----	Road - Gravel. Stone Trackway - peatland	603380, 770649		YES
DESCRIPTION Found at a depth of 0.7m below the bog surface, this road (Wth 3m; T 0.2m max.) was recorded by Rynne in 1957 and excavated, along with an extension (LF017-002001-), in 1958; it was orientated NE-SW (NMI I.A. 32/57; 4/58- Rynne).				

DERRYAROGGE

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF017-002004-	Road - class 3 togher	603930,771079	203980,271060	YES
DESCRIPTION A togher (Wth 1.58m; D 0.22m), orientated E-W, consisting of longitudinal roundwood (diam. 0.08-0.1m) and brushwood (av. diam. 0.03m) of ash, hazel and birch.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF017-002006-	Road - class 3 togher	603970,771044	204020,271025	YES
DESCRIPTION Reported in 1957 by Bord na Móna as a possible togher, at a depth in excess of 1m in the bog, orientated E-W (NMI I.A. 32/57).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF017-0027----	Structure	604130,770919	204180,270900	YES
DESCRIPTION This structure (L 1.81m; D 0.1m) was composed of a number of birch roundwoods, which may have been worked with stone implements. One piece (L 1.18m; diam. 0.1m) had been worked from 0.4m to a point with facets of 0.03-0.05m in width. There were wood chips in the vicinity.				

Derryadd Wind Farm - EIAR

CLOONBROCK

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF017-029----	Redundant record	604220,770879	204270,270860	NO
DESCRIPTION A single worked roundwood (L 1.6m; diam. 0.07m). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

LIST OF RECORDED MONUMENTS WITH DESCRIPTIONS - DERRYADD BOG

CLOONFIUGH

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-091----	Road - class 3 togher	606729,768220		NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (pers. comm. B. Raftery).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-090----	Road - class 3 togher	606739,768200		NO
DESCRIPTION Noted during field survey in 1988, orientated NW-SE (pers. comm. B. Raftery).				

DERRYADD (MOYDOW BY.)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-078----	Road - class 3 togher	606969,768230	207020,268210	YES
DESCRIPTION A togher (Wth 1.4m; D 0.15m), composed of longitudinal birch and hazel roundwood (diam. 0.05-0.08m).				

CLOONFORE

Derryadd Wind Farm - EIAR

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-076----	Road - class 3 togher	606969,768230	207020,268210	YES
DESCRIPTION A togher (Wth 1.4m; D 0.15m), composed of longitudinal birch and hazel roundwood (diam. 0.05-0.08m).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-076001-	Road - class 3 togher	605230,768649	205280,268630	YES
DESCRIPTION A togher (Wth 0.2m; D 0.08m), orientated NW-SE, consisting of longitudinal oak and hazel roundwood and brushwood.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-076006-	Road - class 3 togher	605260,768499	205310,268480	YES
DESCRIPTION A togher (Wth 1.13m; D 0.12m), orientated E-W, consisting of transverse and longitudinal brushwood of hazel and alder which may possibly form a hurdle.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-106	Platform - peatland	605148,768463	205198,268444	YES
DESCRIPTION Originally recorded as a number of patches of tightly packed brushwood (diam. 0.01-0.03m) exposed over quite a large area of one field (exposed area 11m N-S; 6m E-W). The remains were on the field surface and were being milled but may have survived intact under the central dome of the field (Dunne 1999, 41, 99DD0005A-D). During				

excavation a cutting (1m x 1m) was opened, which uncovered a possible hurdle, the elements of which ranged in diameter from 0.007 to 0.032m and were orientated NW-SE. The rest of the remains were very badly degraded (Dunne 2002c, 204).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-107	Road - class 23togher	605200,768552	205250,268533	YES
DESCRIPTION Originally recorded as a band of small and large brushwood, along with twigs, that was exposed on the field surface and was being milled (Dunne 1999, 43, 99DD0009A). All of the pieces of brushwood were aligned WNW-ESE except one transverse example, which seemed to overlie the longitudinal elements. It was best preserved at WNW, where approximately 30 tightly packed pieces of brushwood (diam. 0.015-0.05m) were present. Excavation revealed the remains (exposed L 5.6m; Wth 2.9m) as being composed of two layers. The upper layer (Wth 0.5-0.73m) consisted of a band of longitudinal small brushwood, which was supported by transverse brushwood (L 2.9m). The lower layer (Wth 1.08m) consisted of longitudinal brushwood and twigs (Dunne 2002d, 204).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-108	Road - class togher	605197,768399	205247,268380	YES
DESCRIPTION This togher (L 420m; Wth 2.2m), generally orientated E-W, was visible across 28 fields. The remains were largely on the field surface and had been milled. They were mostly evident as a band of wood chips and degraded timbers with some displaced timbers in the drains. At one point they were visible in the drain face at a depth of 0.28m (Dunne 1999, 40, 99DD0001A-Y). The togher may still be intact under the milled surface in other areas but this was not clear. It was constructed of quite thin oak planks and split timbers (L 1.9m max.; Wth 0.10-0.30m; T 0.02-0.10m), roundwood (diam. 0.07-0.08m), brushwood (diam. 0.01-0.055m) and twigs. Most of the elements were aligned longitudinally but many split timbers, roundwood and brushwood transverses were also in evidence. Longitudinal planks were laid side-by-side and covered by a dense brushwood layer. Occasional pegs, including a squared example, were present. Excavation revealed the remains to be composed of oak-split planks laid longitudinally and supported by transverse split planks and roundwood held in place by pegs (Dunne 2002a, 203).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-109	Platform peatland -	605187,768553	205237,268534	YES
DESCRIPTION Four roundwoods (diam. 0.075-0.08m; L 0.76m max.), orientated WNW-ESE, were located on the field surface and were being milled (exposed area 1.5m x 1.3m). A single degraded wedge-point end was noted. A small concentration of twigs (0.2m x 0.2m), with varying orientations occurred S of the roundwood with some brushwood on the opposite side. The evidence suggested that this was likely to be the remains of a platform. (Dunne 1999, 46, 99DD0018A)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-110	Road - class 1 togher	605071,768405	205121,268386	YES
DESCRIPTION This togher (L 173m; Wth 1.2m), orientated ENE-WSW, extended across eleven fields (Dunne 1999, 41, 99DD0003A-J). The remains were on the field surface and were being milled. They were largely visible as a band of degraded brushwood and wood chips, however, there was evidence to show that the togher survived intact in places beneath ground level, particularly under the central dome of the fields. Two parallel lines of brushwood (diam. 0.05cm) formed the edges with a third, similar, line extending along the centre. The body of the togher consisted of tightly packed longitudinal small brushwood (diam. 0.01-0.02m and 0.04m max.), along with some twigs. The longitudinal elements rested on a substructure of transverse large brushwood. Excavation revealed the togher to be composed of longitudinal small brushwood and twigs on the upper surface. This layer was supported by larger brushwood also laid longitudinally or at a slight angle to the upper surface. This lower surface was further supported by longitudinal small brushwood and twigs (Dunne 2002b, 203-4).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-111	Platform peatland -	605129,768467	205179,268448	YES
DESCRIPTION A small area of exposed brushwood (1.5m NW-SE; 0.30m NE-SW) was located on the field surface and was being milled. Two long but degraded pieces of brushwood (diam.				

0.01m and 0.02m) extended NW-SE along the length of the exposure. A short brushwood (diam. 0.015m) extended N-S across both of these. Other short fragments of brushwood present were orientated both NW-SE and NE-SW. The larger longitudinal brushwood had a possible coppiced heel at its NW end. The evidence suggested that this was likely to be the remains of a platform. (Dunne 1999, 42, 99DD0007A)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-112	Platform peatland	- 605118,768448	205168,268429	YES
<p>DESCRIPTION</p> <p>Three pieces of brushwood (diam. 0.04m) extended diagonally into the bog at varying angles (exposed area 0.5 x 0.5m). Two were orientated NE-SW, with the third aligned at right angles. No toolmarks were visible though the pieces of brushwood were likely to have worked ends that were driven into the bog. The evidence suggested that this may well have been the last remnants of a possible platform. (Dunne 1999, 42, 99DD0006A)</p>				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-113	Platform peatland	- 605205,768522	205255,268503	YES
<p>DESCRIPTION</p> <p>A band of tightly packed brushwood, along with some twigs, was located on the field surface was being milled (exposed area 1.3m NE-SW; 0.6m NW-SE). Approximately ten pieces of brushwood (diam. 0.02-0.03m) were present and all were aligned NE-SW. The band appeared to extend into the bog at the SW end and may have been intact under ground level beyond that point. The evidence suggested that this was likely to be the remains of a platform. (Dunne 1999, 42, 99DD0008A)</p>				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-114	Platform peatland,	- 605171,768627	205221,268608	YES
<p>DESCRIPTION</p> <p>A band of parallel, longitudinal brushwood (overall exposed L 3m; Wth 0.7m) was exposed on the field surface and was being milled. The principle exposed area measured 1.5m ENE-WSW by 0.7m NNW-SSE but there were occasional pieces of brushwood</p>				

visible for a further 1.5m. Of eight pieces of closely spaced brushwood (diam. 0.02-0.04m), the longest measured 1.1m. The evidence suggested that this was likely to be the remains of a platform. (Dunne 1999, 44, 99DD0013A)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-115	Road - class 2 togher	605222,768446	205272,268427	YES
DESCRIPTION A togher (exposed L 23m; Wth 1.1-1.25m), aligned WNW-ESE, was located on the field surface and was being milled (Dunne 1999, 45, 99DD0015A-C; 2002f, 205). Two adjoining fields were at a higher level than the fields on either side, which accounted for the survival of the togher at this location. The remains, noted at three points (15A-C) across two fields, comprised densely packed brushwood (diam. 0.01-0.025m) and twigs; some brushwood and twig pegs were also uncovered. Most elements were longitudinal with occasional transverses. A hurdle panel was also uncovered, lying over one section of the togher. A large transverse roundwood (L 3.9m; diam. 0.075m) (at 15B), orientated N-S, had a degraded chisel point at its S end. This end appears to have been split in antiquity before being placed in position.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-116	Platform - peatland,	605140,768397	205190,268378	YES
DESCRIPTION A small platform (exposed area 0.46m ENE-WSW; 0.42m NNW-SSE) was located on the field surface and was being milled. The remains consisted of tightly packed, longitudinal brushwood and twigs (diam. 0.005-0.02m), which extended under the milled surface. There was no visible evidence of woodworking. (Dunne 1999, 41, 99DD0004A)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-117	Platform - peatland,	605229,768490	205279,268471	YES
DESCRIPTION A small area of exposed roundwood and brushwood (overall exposed L 1.2m; Wth 0.6m) was located on the field surface and was being milled. Four principle rods (diam. 0.03-				

0.06m; exposed L 0.45-1.1m) were parallel, closely set or adjoining, and extended under the milled surface. A further roundwood (exposed L 0.1m) extended diagonally into the bog. Other smaller fragments of brushwood and twigs were also present. The evidence suggested that this was likely to be the remains of a platform. (Dunne 1999, 45, 99DD0016A)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-118	Platform peatland	605223,768530	205273,268511	YES
DESCRIPTION A small platform located on the field surface was largely degraded and milled out (exposed area 1.1m x 1m). The remains comprised tightly packed longitudinal brushwood, orientated WSW-ENE, with a small number of transverse pieces of brushwood, one of which overlay the longitudinals. (Dunne 1999, 46, 99DD0017A)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-119	Road - class 2 togher	605156,768654	205206,268635	YES
DESCRIPTION Fragmentary remains of a brushwood togher (overall L 15.3m; original Wth 1.2m) were located on the field surface, in the centre of two adjacent fields, largely milled out. 20A: exposed area (1m x 0.7m) E of a drain. Longitudinal brushwood (diam. 0.015-0.03m), orientated E-W to WNW-ESE. 20B: W of drain. Longitudinal brushwood (diam. 0.01-0.05m) with larger pieces (0.045-0.05m) forming the sides of the togher (original Wth 1.2m; overall Wth 1.3m) oriented E-W to WNW-ESE. The presence of old bamboo in the drain indicated that this monument was included in the original Irish Archaeological Wetland Unit (UCD) survey. (Dunne 1999, 47, 99DD0020A-B)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-120	Road - class 2 togher	605180,768557	205230,268538	YES
DESCRIPTION This togher (exposed L 11.5m; Wth 1.1m) was composed of closely set longitudinal small and large brushwood and twigs, and was orientated NW-SE (Dunne 2002g, 205). There				

were also occasional small brushwood transverses. Adjacent fields had been milled to a lower level. Originally recorded as 19A and 19B (Dunne 1999, 46, 99DD0019A-B). 19A: was located to the W of a drain, on the field surface, and was being milled. It consisted of tightly packed brushwood (diam. 0.01-0.03m) at least two layers thick; it was orientated E-W but turned to NNW-SSE at W. Some of the brushwood pieces were larger and may have been part of a substructure. 19B: 10.5m to the W consisted of three to four pieces of brushwood (diam. 0.02-0.04m; L 0.5m max.; Wth of exposure 0.5m) oriented NW-SE.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-121	Road - class 2 togher	605172,768577	205222,268558	YES
<p>DESCRIPTION</p> <p>This togher (exposed L 10m, Wth 1.1m, T 0.32m) was composed of mainly small and occasional large brushwood and twigs, and was orientated WSW-ENE (Dunne 2002e, 204-5). A number of pegs were recorded along the centre. Originally recorded as 12A and 12B (Dunne 1999, 44, 99DD0012A-B). 12A was located on the field surface and was being milled (exposed L 0.7m, Wth 1.7m). Two parallel, longitudinal, large pieces of brushwood (diam. 0.045-0.05m) formed the sides and centre. The body of the togher comprised more than 50 tightly packed, small pieces of brushwood (diam. 0.015-0.02m and 0.03m max.) along with some twigs, all aligned longitudinally. The pieces of brushwood had fractures in such a way as to suggest the presence of transverse elements underneath. There was no visible evidence of woodworking. 12B, 8m E on the same field surface, consisted of a small exposure of similar form, suggesting a continuation of the togher.</p>				

ANNAGHBEG

SMR	CLASS	ITM Easting, ITM Northing	Irish Easting, Grid Irish Grid Northing	Inclusion in next SMR
LF018-077----	REDUNDANT RECORD	605259.768499		NO
<p>DESCRIPTION</p> <p>This record was formerly classed as 'Archaeological Complex'. This is an obsolete broad or group term and is not currently used by the Archaeological Survey of Ireland.</p>				

Derryadd Wind Farm - EIAR

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077001	Road - class 3 togher	606150,768220	206200,268200	NO
DESCRIPTION A togher (Wth 0.8m; D 0.11m), orientated E-W, composed of longitudinal ash roundwood (diam. 0.085-0.111m).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077002	Road - class 3 togher	606160,768200	206210,268180	NO
DESCRIPTION A togher (Wth 1m; D 0.14m), orientated E-W, composed of longitudinal birch roundwood (av. diam. 0.11m).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077003	Road - class 3 togher	606235,768040	206285,268020	YES
DESCRIPTION A togher (Wth 0.9m; D 0.08m), orientated ENE-WSW, consisting of longitudinal brushwood with occasional roundwood of hazel. May possibly be a hurdle.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077004	Road - class 3 togher			YES
DESCRIPTION A togher (Wth 1.1m; D 0.12m), orientated ENE-WSW, consisting of regularly laid roundwood of hazel and ash with some hazel brushwood.				

Derryadd Wind Farm - EIAR

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077005	Road - class 3 togher	606240,768070	206290,268050	YES
DESCRIPTION A togher (Wth 1.3m; D 0.15m), orientated ENE-WSW, consisting of longitudinal roundwood and brushwood of birch and hazel.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077006	Road - class 3 togher	606303,768033	206353,268013	YES
DESCRIPTION A togher (L 20m; Wth 1.5m; D 0.06m), orientated ENE-WSW, consisting of longitudinal brushwood of hazel. May possibly be a hurdle.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077007	Road - class 3 togher	606310,768075	206360,268055	NO
DESCRIPTION A togher (Wth 0.8m; D 0.11m), orientated E-W, composed of longitudinal ash roundwood (diam. 0.085-0.111m).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
-----	-------	---------------------------	---	-----------------------

Derryadd Wind Farm - EIAR

LF018-077008	Road - class 3 togher	606305,768110,	206355,268090	YES
DESCRIPTION A togher (Wth 0.8m; D 0.4m) consisting of a superstructure of regularly laid roundwood and brushwood of ash and hazel with a substructure of the latter. There is possible evidence for coppicing.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077009	Road - class 3 togher	606242,768045	206292,268025	NO
DESCRIPTION A togher (Wth 0.8m; D 0.11m), orientated E-W, composed of longitudinal ash roundwood (diam. 0.085-0.111m).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077010	Road - class 3 togher	606243,768042	206293,268022	YES
DESCRIPTION A substantial togher (L 16m min.; Wth 1.8m min.; D 1.5m), found in 1989, 1.5m below the bog surface, consisted of three overlapping panels of woven hazel rods overlain by large roundwood, which damaged the hurdles beneath. The largest panel (L 5.2m; Wth 1.1-1.2m) remained intact and was constructed of twelve or thirteen sails with 84 rods interwoven around them. The togher ended with a small scatter of brushwood and was orientated ESE-WNW. Radiocarbon dated to 2298-2038 BC (3770±40 BP, GrN-18360). (Raftery 1990, AG2, 21-2, 28-9; 1996, Annaghbeg 2, 173-8) References: 1. Adams, B.W. 1881 Antiquarian notes, etc., of the parishes of Santry and Cloghran, Co. Dublin. Journal of the Royal Society of Antiquaries of Ireland 15, 482-98.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
-----	-------	---------------------------	---	-----------------------

Derryadd Wind Farm - EIAR

LF018-0770011	Road - class 3 togher			NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-0770012	Road - class 3 togher	606354,768137	206404,268117	NO
DESCRIPTION Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-0770013	Road - class 3 togher	606321,768140	206371,268120	YES
DESCRIPTION A togher (L 2.7m min.; Wth 0.8m; D 0.1m), noted in 1989, consisted of an extensively damaged hurdle which was partially excavated. The orientation was E-W. The sails (diam. 0.04-0.045m) and rods (diam. 0.02-0.03m) were unusually thick. Radiocarbon dated to 2400-2155 BC (3830±25 BP, GrN-18373). (Raftery 1990, AG3, 73; 1996, Annaghbeg 3, 178-9)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077014-	Road - class 3 togher	606337,768202	206387,268182	YES
DESCRIPTION Noted during field survey in 1988, orientated NW-SE (Raftery 1990, 73, Fig. 81).				

Derryadd Wind Farm - EIAR

SMR	CLASS,	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077015	Road - class 3 togher	606318,768190	206368,268170	NO
DESCRIPTION Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077016	Road - class 3 togher	606330,768185	206380,268165	NO
DESCRIPTION Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077018	Road - class 3 togher	606319,768175	206369,268155	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077019	Road - class 3 togher			NO

Derryadd Wind Farm - EIAR

DESCRIPTION

Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077020	Road - class 3 togher	606316,768168	206366,268148	NO

DESCRIPTION

Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077021	Road - class 3 togher	606321,768168	206371,268148	NO

DESCRIPTION

Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077022	Road - class 3 togher	606316,768166	206366,268146	NO

DESCRIPTION

Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077023	Road - class 3 togher	606317,768162	206367,268142	NO

DESCRIPTION

Derryadd Wind Farm - EIAR

Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077024	Road - class 3 togher	606306,768159	206356,268139	NO

DESCRIPTION

Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077025	Road - class 3 togher	606317,768160	206367,268140	NO

DESCRIPTION

Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077026	REDUNDANT RECORD	606317,768158	206367,268138	NO

DESCRIPTION

Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077027	Road - class 3 togher	606343,768160	206393,268140	NO

DESCRIPTION

Derryadd Wind Farm - EIAR

Noted during field survey in 1988, orientated ENE-WSW (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077028	Redundant Record	606334,768157	206384,268137	NO
DESCRIPTION Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077029	Road - class 3 togher	606334,768155	206384,268135	NO
DESCRIPTION Noted during field survey in 1988, orientated ENE-WSW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077030	Road - class 3 togher	606360,768157	206410,268137	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077031	Redundant record	606307,768149	206357,268129	NO
DESCRIPTION				

Derryadd Wind Farm - EIAR

Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077032	Redundant Record	606308,768140	206358,268120	NO

DESCRIPTION

Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077033	Road - class 3 togher	606336,768144	206386,268124	NO

DESCRIPTION

Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077034	Redundant Record	606322,768142	206372,268122	NO

DESCRIPTION

Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077035	Road - class 3 togher	606342,768135	206392,268115	NO

DESCRIPTION

Derryadd Wind Farm - EIAR

Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077036	Redundant Record	606342,768133	206392,268113	NO
DESCRIPTION Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077037	Road - class 3 togher	606326,768132	206376,268112	NO
DESCRIPTION Noted during field survey in 1988, orientated WNW-ESE (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077038	Road - class 3 togher	606337,768133	206387,268113	NO
DESCRIPTION Noted during field survey in 1988, orientated ENE-WSW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077039	Road - class 3 togher	606322,768128	206372,268108	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

Derryadd Wind Farm - EIAR

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077040	Road - class 3 togher	606323,768126	206373,268106	NO
DESCRIPTION Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077041	Redundant Record	606327,768124	206377,268104	NO
DESCRIPTION Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077042	Road - class 3 togher	606348,768129	206398,268109	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077043	Redundant Record	606323,768121	206373,268101	NO
DESCRIPTION Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

Derryadd Wind Farm - EIAR

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077044	Road - class 3 togher	606328,768120	206378,268100	NO
DESCRIPTION Noted during field survey in 1988, orientated NNE-SSW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077045	Road - class 3 togher	606325,768116	206375,268096	NO
DESCRIPTION Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077046	Road - class 3 togher	606312,768113	206362,268093	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077047	Road - class 3 togher	606340,768113	206390,268093	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
-----	-------	---------------------------	---	-----------------------

Derryadd Wind Farm - EIAR

LF018-077048	Road - class 3 togher	606325,768107	206375,268087	NO
DESCRIPTION Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077049	Redundant Record	606314,768104	206364,268084	NO
DESCRIPTION Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077050	Road - class 3 togher	606330,768102	206380,268082	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077051	Road - class 3 togher	606314,768097	206364,268077	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
-----	-------	---------------------------	---	-----------------------

Derryadd Wind Farm - EIAR

LF018-077052	Road - class 3 togher	606326,768098	206376,268078	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077053	Road - class 3 togher	606315,768094	206365,268074	NO
DESCRIPTION Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077054	Road - class 3 togher	606352,767996	206402,267976	NO
DESCRIPTION Noted during field survey in 1988, orientated NW-SE (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077055	Road - class 3 togher	606352,767994	206402,267974	NO
DESCRIPTION Noted during field survey in 1988, orientated NW-SE (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077056	Redundant Record	606266,768065	206316,268045	NO

Derryadd Wind Farm - EIAR

DESCRIPTION

Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077057	Redundant Record	606265,768069	206315,268049	NO

DESCRIPTION

Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077058	Road - class 3 togher	606297,768077	206347,268057	NO

DESCRIPTION

Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077059	Road - class 3 togher	606273,768082	206323,268062	NO

DESCRIPTION

Noted during field survey in 1988, orientated N-S (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077060	Redundant Record	606288,768095	206338,268075	NO

DESCRIPTION

Derryadd Wind Farm - EIAR

Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077061	Redundant Record	606271,768093	206321,268073	NO
DESCRIPTION Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077063	Road - class 3 together	606247,768119	206297,268099	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077064	Road - class 3 together	606246,768125	206296,268105	NO
DESCRIPTION Noted during field survey in 1988, orientated NNE-SSW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077065	Redundant Record	606267,768130	206317,268110	NO
DESCRIPTION Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077066	Road - class 3 together	606295,768135	206345,268115	NO

Derryadd Wind Farm - EIAR

DESCRIPTION
Noted during field survey in 1988, orientated NNE-SSW (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077067	Road - class 3 togher	606296,768137	206346,268117	NO

DESCRIPTION
Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077068	Road - class 3 togher	606294,768138	206344,268118	NO

DESCRIPTION
Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077069	Road - class 3 togher	606266,768138	206316,268118	NO

DESCRIPTION
Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077070	Redundant Record	606265,768140	206315,268120	NO

DESCRIPTION
Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077071	Road - class 3 togher	606282,768141	206332,268121	NO

DESCRIPTION
Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077072	Road - class 3 togher	606283,768143	206333,268123	NO

DESCRIPTION
Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077073	Road - class 3 togher	606248,768144	206298,268124	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077074	Road - class 3 togher	606248,768149	206298,268129	NO
DESCRIPTION Noted during field survey in 1988, orientated E-W (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077075	Redundant Record	606263,768154	206313,268134	NO
DESCRIPTION Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077076	Redundant Record	606262,768159	206312,268139	NO
DESCRIPTION Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077077	Road - class 3 togher	606261,768168,	206311,268148	NO
DESCRIPTION Noted during field survey in 1988, orientated N-S (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077078	Redundant Record	606260,768174	206310,268154	NO
DESCRIPTION Worked wood noted during field survey in 1988 (Raftery 1990, 73). The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-077079	Road - class 3 togher	606246,768170	206296,268150	NO
DESCRIPTION Noted during field survey in 1988, orientated NE-SW (Raftery 1990, 73, Fig. 81).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-105	Road - class 3 togher,	606273,768054	206323,268034	yes
DESCRIPTION A band of parallel, longitudinal roundwood and brushwood (exposed Wth 1.47m, T 0.32m) was exposed towards the top of an NEE drain face. No remains were visible on the field surface, the level of which was higher than the adjacent fields on either side. Five roundwoods (diam. 0.06-0.095m) were present and two or three pieces of brushwood (diam. 0.03-0.04m). Two possible split timber pegs, one with a worked end, were positioned WNW of the roundwood. A split timber transverse, aligned NW-SE, extended under the roundwood on this side. A rusty 6-inch nail recovered from under one of the roundwoods indicated that these remains probably formed part of the Irish Archaeological Wetland Unit (UCD) survey. (Dunne 1999, 51, 99DD0011A)				

ANNAGHMORE/CORRALOUGH

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-080--	Road - class 1 togher	605749, 766555		YES
DESCRIPTION A togher (L 500m; Wth 2.6m; D 0.15m), orientated E-W, consisting of longitudinal brushwood of alder and hazel with twigs compacted between them.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-035--	Ringfort - rath,	606360,766709	206411,266689	YES
DESCRIPTION In pasture surrounded by bog. Depicted as a circular enclosure with the designation 'Fort' on the 1837 ed. of the OS 6-inch map and on the OS 25-inch plan (surveyed 1911) as an enclosed area defined by a bank and fosse. A field boundary overlay the bank from N-NE and another curved around it from NE to SSW. On inspection in 1976 (SMR file) a curving stretch of a substantial earthen bank, incorporated into modern field fences, was visible at S and W. A ditch on the S side of the bank may have marked the line of the fosse. On an OSI				

aerial photograph (SMR file) the outline of the E half of the rath is now visible as a curving field boundary, while the W half is visible as a cropmark.

LIST OF RECORDED MONUMENTS WITH DESCRIPTIONS - LOUGH BANNOW BOG

DERRYNASKEA

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-084071	Burnt spread	607971,764935	208022,264915	YES
DESCRIPTION In bogland. A spread (L 4.4m; Wth 5m; D 0.08m) of yellow/orange peat ash was noted along the face of a drain and on the field surface. In many places the ash was covered by stratified peat and may be evidence of an episode of burning in the bog.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-084012	Road - class 2 togher	608019,765017	208070,264997	YES
DESCRIPTION A togher (L 45m; Wth 1.4m; D 0.26m), orientated NW-SE, composed of longitudinal ash roundwood.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-084073	Road - class 3 togher	608089,765020	208140,265000	NO
DESCRIPTION Noted during field survey in 1988 (pers. comm. B. Raftery)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-084076	Road - class 3 togher	608109,765020	208160,265000	NO
DESCRIPTION Noted during field survey in 1988 (pers. comm. B. Raftery).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-084074	Road - class 3 togher	608099,765040	208150,265020	NO
DESCRIPTION Noted during field survey (pers. comm. B. Raftery).				

Derryadd Wind Farm - EIAR

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-070----	Road - class 3 togher	608039,764610	208090,264590	NO
DESCRIPTION Noted during field survey in 1988 (pers. comm. B. Raftery).				

CORLEA

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057029-	Road - class 3 togher	609759,763725	209810,263705	YES
DESCRIPTION A togher (Wth 1.62m; D 0.2m), orientated NW-SE, composed of transverse roundwood with occasional brushwood, mostly birch but there was also some oak present.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057030-	Road - class 3 togher	609759,763745	209810,263725	YES
DESCRIPTION A togher (Wth 2.6m; D 0.26m) composed of regularly laid roundwood with occasional clusters of brushwood. The species present included birch, ash and some alder.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057031-	Road - class 3 togher	609754,763735	209805,263715	YES
DESCRIPTION A togher (Wth 1.85m; D 0.18m), orientated NW-SE, composed of transverse roundwood and brushwood of ash, oak and hazel.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057032-	Road - class 3 togher	609749,763775	209800,263755	YES
DESCRIPTION A togher (Wth 1.5m; D 0.15m), orientated E-W, constructed of predominantly hazel brushwood.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057033-	Road - class 3 togher	609754,763750	209805,263730	YES
DESCRIPTION A togher (Wth 1.4m; D 0.18m), orientated E-W, composed of longitudinal brushwood flanked by roundwood, predominantly birch and hazel.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057034-	Road – class 3 togher	609754,763760	209805,263740	YES
DESCRIPTION A togher (Wth 2.19m; D 0.17m), orientated NE-SW, composed of scattered brushwood with occasional roundwood. Predominant species were hazel and birch.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-086----	Platform peatland	609778,763700	209829,263680	YES
DESCRIPTION A small platform (exposed L 1.3m; Wth 0.9m) on the field surface consisted of longitudinal brushwood and roundwood extending E-W. A single isolated transverse brushwood immediately to the S of the spread extended the exposed width to 1.55m. The remains were badly degraded and milled and there was no evidence of woodworking. (Dunne 1999, 7, 99LBW0015A)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057001-	Road – class 1 togher	609595,763557	209646,263536	YES
DESCRIPTION A togher (L 750m; Wth 2.5m; D 0.23m), noted in 1988, orientated ENE-WSW, consisted of a superstructure of transverse roundwood and split stems, which had been laid on a substructure of longitudinal runners and transverse roundwood. There was evidence that a metal tool had been used. Dendrochronological dating revealed a date range of 2259±9 BC (Q7918). When inspected in 1999 the togher extended over the milled surface of twelve fields for an overall distance of 225m. It comprised longitudinal parallel roundwood (diam. 0.06-0.10m), brushwood (diam. 0.02-0.06m) and twigs. A small number of transverse pieces of brushwood of similar diameter were also visible and one worked chisel-point end was noted (Dunne 1999, 99LBW0008A-I). (Raftery 1990, 11-14; 1996, Corlea 6, 71-8)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057002-	Road – class 3 togher	609614,763635	209665,263615	YES
DESCRIPTION A togher (L 5.9m min.; Wth 3m; D 0.2m), noted in 1989, consisting of longitudinal brushwood and roundwood overlying a small deposit of transverse brushwood. The orientation was NE-SW. Radiocarbon dated to 3654-3371 BC (4760±60 BP, GrN-16830). (Raftery 1990, 11; 1996, Corlea 8, 79-81)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057003-	Road – class 1 togher	609744,763530	209795,263509	YES
DESCRIPTION				

Derryadd Wind Farm - EIAR

A togher (L 435m; Wth 2.1m; D 0.24m), noted in 1989, consisted of a superstructure of longitudinal roundwood and brushwood, supported by a substructure of transverse roundwood and longitudinal brushwood and roundwood. The orientation was NE-SW. Some pegs were apparent and a chert flake was found on the surface. Radiocarbon dating revealed a date range of 3362-3369 BC (4680±125 BP, GrN-16831). When inspected in 1999 a transverse superstructure (L 480m; Wth 2.5m) extended across 31 fields. The upper surface was generally constructed of closely laid transverse planks (L 1.2-2.4m; Wth 0.13-0.3m; T 0.06-0.1m) and roundwood (diam. 0.06-0.14m) but also included transverse brushwood (diam. 0.01-0.05m). These elements were orientated NW-SE to NNW-SSE and rested on a substructure of longitudinal roundwood runners (diam. 0.06-0.18m) that extended NE-SW to ENE-WSW. Almost the entire remains were located on the field surface and most of the structure was badly degraded due to milling. It was, however, evident in section in the drain face at a number of locations. In places the surface of the transverse planks was milled, while the original woodworking on the ends was still largely intact. Some of the brushwood had worked chisel-point ends. A flat stone (0.19 x 0.15 x 0.04m) was incorporated into the surface of the track at one point. Quantities of hazelnut shells were present in places between the elements. (Raftery 1990, 11-12; 1996, Corlea 9, 81-91; Dunne 1999, 9, 99LBW0022A-W)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057028-	Road – class 3 togher	609694,763675	209745,263655	YES
DESCRIPTION A togher (Wth 1.95m; D 0.2m), orientated NE-SW, composed of longitudinal roundwood of alder and hazel with some birch also present.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-085----	Road – class 3 togher	609705,763653	209756,263633	YES
DESCRIPTION Originally recorded as being exposed on the field surface (exposed L 5.7m; Wth 0.8m) and being milled immediately W of a drain (Dunne 1999, 13, 99LBW0034A). However, it appeared to extend under the bog surface that rose away from the drain towards the centre of the field. Excavation revealed longitudinal twigs and small brushwood, arranged in a band (Wth 0.5-0.8m) orientated NE-SW (Dunne 2002o, 207).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-078----	Road unclassified togher	609677,763639	209728,263619	YES
DESCRIPTION A small patch of a togher (exposed Wth 0.75m) was located on the field surface immediately to the E of a drain. It may have been truncated at W by the drain and it was not evident in the opposite section face or field surface. It was composed of converging brushwood and roundwood, which generally extended NW-SE to NNW-SSE. Two roundwoods (diam. 0.06m and 0.07m) extended across the brushwood (av. diam. 0.02m) holding the general orientation. There were also two to three roundwoods extending in an E-W direction. (Dunne 1999, 13, 99LBW0035A)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-095----	Platform peatland	609661,763619	209712,263599	YES
DESCRIPTION A small patch (exposed L 1.3m, Wth 0.4m) of brushwood and twigs (diam. c. 0.01-0.04m) was located on the field surface was being milled. There was no visible evidence of woodworking. The evidence suggested that this was likely to be the remains of a platform. (Dunne 1999, 5, 99LBW0009A)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-077----	Road - class 2 togher	609664,763607	209715,263586	YES
DESCRIPTION Originally recorded as a substantial structure (exposed L 27.5m; Wth 1.2m) located immediately to the WSW of a drain shoulder. The remains were being milled close to the drain but extended under the milled surface, which rose towards the centre of the field. The surface consisted of a superstructure of longitudinal, densely packed, small and large brushwood. This was underlain by a substructure of four longitudinal planks (Wth 0.12-0.3m), two of which were closely set in the middle, while the other two formed both edges. The gap between the S and central planks was 0.5cm, while the corresponding gap on the N side was 0.35m. The gaps were filled with brushwood. Some of the brushwood extended into the bog surface at an angle of c. 45° (Dunne 1999, 10, 99LBW0026A). Excavation revealed that there may be two toghers here. Longitudinal small brushwood with three larger pieces of brushwood, orientated NE-SW forming boundaries and an internal spine of the togher, were uncovered (Dunne 2002l, 206). This may be part of another togher (LF022-085----) located 50m away.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057004-	Road - class 3 togher	609599,763715	209650,263695	YES
DESCRIPTION A togher (L 2m; Wth 1.6m; D 0.08m), orientated NE-SW, constructed of longitudinal thin hazel rods tightly packed together with some foliage. (Raftery 1996, Corlea 12, 92-3)				

Derryadd Wind Farm - EIAR

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057005-	Road – class 3 togher	609619,763620	209670,263600	YES
DESCRIPTION A loose collection of almost exclusively hazel brushwood and occasional roundwood (L 3.4m min.; Wth 1.6m min.; D 0.07m) all placed more or less in a longitudinal position and orientated E-W. (Raftery, 1990; 1996, Corlea 13, 93)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057006-	Road – class 3 togher	609619,763611	209670,263590	YES
DESCRIPTION A thin layer (L 4.9m; Wth 1.6m max.; D 0.02m) of tightly packed hazel brushwood (diam. 0.01-0.02m). The togher narrowed from SW to NE along its orientation. (Raftery, 1990; 1996, Corlea 14, 93-4)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-067----	Road – class 2 togher	609585,763581	209636,263560	YES
DESCRIPTION A togher (L 82m; Wth 0.75m; D 0.1m), orientated NE-SW, composed of longitudinal, tightly packed small pieces of brushwood, predominantly of hazel.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057038-	Road – class 2 togher	609572,763547	209623,263526	YES
DESCRIPTION A togher (L 4.15m min.; Wth 0.8m; D 0.06m), noted in 1989, consisted of longitudinal brushwood secured with occasional diagonals. The orientation was ENE-WSW. Radiocarbon dated to 3329-2910 BC (4410±45 BP, GrN-18376). When inspected in 1999 the togher (L 180m; Wth 0.7-1.7m) extended across the surface of nine fields. Its orientation ranged from ENE-WSW at 16A to NE-SW at 16E, however, at 16D the brushwood ran E-W. The remains consisted of tightly packed, longitudinal, parallel brushwood (diam. 0.01-0.03m), fine twigs and roundwood, no more than one to two layers in thickness. Some pegs (diam. 0.03-0.035m) were evident. The original form of the feature was visible at 18E. Two parallel, longitudinal roundwoods (1.2m apart; diam. 0.08m) formed the edges of the track. A transverse piece of brushwood (diam. 0.03m) was visible here (Dunne 1999, 7, 99LBW0016A-E). (Raftery 1996, Corlea 11, 91-2)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
-----	-------	------------------------------	--	--------------------------

Derryadd Wind Farm - EIAR

LF022-057039-	Road – class 3 togher	609522,763516	209573,263495	YES
DESCRIPTION A togher (L 1.9m min.; Wth 1.2m; D 0.1-0.15m), noted in 1989, consisted of closely spaced longitudinal roundwood and brushwood. Pegs were set at irregular intervals along both sides of it. The orientation was ENE-WSW. Radiocarbon dated to 3368-3097 BC (4540±40 BP, GrN-18375). (Raftery 1990, 11; 1996, Corlea 10, 91)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057041-	Road – class 3 togher	609774,763426	209825,263405	NO
DESCRIPTION This togher, orientated NE-SW, was destroyed before it could be recorded.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-084----	Road unclassified togher	609793,763419	209844,263398	YES
DESCRIPTION A small exposed patch of a togher (1.7m NNW-SSE; 1.6m ENE-WSW) was located on the field surface and was being milled. It was composed of a combination of roundwood (diam. 0.07-0.09m) with small and large brushwood (diam. 0.01-0.04m). There was no visible evidence of woodworking. (Dunne 1999, 12, 99LBW0031A)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057027-	Road – class 3 togher	609804,763426	209855,263405	YES
DESCRIPTION A togher (Wth 1.34m; D 0.12m), orientated NW-SE, composed of transverse roundwood and brushwood of birch and hazel.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-096----	Platform peatland	609794,763413	209845,263392	YES
DESCRIPTION Originally recorded as a small area of a hurdle (exposed L 2.9m; Wth 2m) on the field surface which was being milled (Dunne 1999, 12, 99LBW0032A). Excavation revealed the hurdle to be aligned WSW-ENE and constructed of five sails with woven rods. It rested on an oak roundwood				

(L 2m), orientated ENE-WSW (Dunne 2002m, 206-7). The evidence suggested that this was most likely to be the remains of a platform.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057035-	Road - class 3 togher	609804,763406	209855,263385	YES
DESCRIPTION A togher (Wth 2.3m; D 0.35m), orientated NE-SW, consisting of a dense concentration of hazel brushwood with some small roundwoods.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057021-	Road - class 3 togher	609804,763396	209855,263375	YES
DESCRIPTION A togher (Wth 1.5m; D 0.09m), orientated NW-SE, composed of seven to eight transverse roundwoods in close proximity.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-090----	Platform peatland	-609794,763394	209845,263373	YES
DESCRIPTION A compact band (exposed Wth 2.2m; T 0.2m) of brushwood was visible in opposing drain faces. The majority of the elements were small (diam. c. 0.02m), with five or six larger pieces (diam. 0.04 to 0.05m) at the N end of the section. Most of the brushwood extended into the drain face while one or two pieces ran transversely underneath them at the S end. There was no visible evidence of woodworking. The evidence suggested that this was likely to be the remains of a platform. (Dunne 1999, 6, 99LBW0011A)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-083----	Platform peatland	-609796,763392	209847,263371	YES
DESCRIPTION A very narrow, compact band (exposed Wth 0.38m; T 0.11m) of small brushwood (av. diam. 0.015m) was visible in the E face of a drain but was not visible on opposite side. There was no evidence of woodworking. Most likely to have been the remains of a platform. (Dunne 1999, 12, 99LBW0030A)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-079----	Road - class 3 togher	609797,763387	209848,263366	YES
DESCRIPTION				

Derryadd Wind Farm - EIAR

A band (exposed Wth 2.58m) of thin brushwood (av. diam. 0.03m) was exposed in an E drain face. It was not visible in the opposite drain face and there was no sign of woodworking. The orientation of the togher was difficult to determine as the brushwood formed a jumbled arrangement, however, the two principle directions noted were N-S and E-W. (Dunne 1999, 11, 99LBW0029A)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-073----	Platform peatland	-609798,763385	209849,263364	YES

DESCRIPTION

A band (exposed Wth 3.1m; T 0.12m) of 200 to 300 densely packed twigs was visible in the E face of a drain. The band also included ten to twelve irregularly spaced pieces of brushwood (diam. 0.04-0.05m). The remains were also visible in the W section face, though the elements there were less compacted. No woodworking was visible. The evidence suggested that this was likely to be the remains of a platform. (Dunne 1999, 11, 99LBW0028A).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057020-	Road - class 3 togher	609809,763386	209860,263365	YES

DESCRIPTION

A togher (Wth 1.3m; D 0.2m) composed of regularly laid roundwood and brushwood.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057042-	Road - class 3 togher	609809,763386	209860,263365	NO

DESCRIPTION

This togher was destroyed before it could be recorded.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057019-	Road - class 3 togher	609809,763381	209860,263360	YES

DESCRIPTION

A number of regularly laid roundwoods (Wth 0.45m; D 0.08m).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057016-	Road - class 2 togher	609802,763366	209853,263345	YES

DESCRIPTION

A togher (L 100m min.; Wth 2m; D 0.14m), orientated NE-SW, composed of roundwood and brushwood.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057017-	Road - class 3 togher	609824,763346	209875,263325	YES

Derryadd Wind Farm - EIAR

DESCRIPTION
A togher, orientated NE-SW, composed of transverse roundwood of ash and oak.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-088----	Road unclassified togher	-609851,763336	209902,263315	YES

DESCRIPTION
A compact assortment of small and large brushwood (diam. 0.03-0.055m) and roundwood (diam. 0.07m) was visible in both faces of a drain (exposed Wth 2.9m, T 0.2m). The band extended below the water level at the base of the drain. There was no visible evidence of woodworking. (Dunne 1999, 6, 99LBW0013A)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-080----	Road - class 2 togher	609852,763331	209903,263310	YES

DESCRIPTION
Originally recorded as a loose band (exposed L 35.5m; Wth 2.5m; T 0.3m) of small and large brushwood, along with at least two roundwoods, extending roughly at right angles into both the E and W drain faces (Dunne 1999, 13, 99LBW0033A). It was orientated ENE-WSW. Two cuttings were excavated along its length revealing that the togher was constructed with longitudinal roundwood, brushwood and twigs (Wth 0.95-2.5m; T 0.3m); the roundwoods were sometimes arranged in pairs. A large number of pegs and posts were used and these displayed a variety of worked ends. Many of the tips were blunted and buckled from impinging on lower elements of the structure. (Dunne 2000n, 207)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-076----	Road unclassified togher	-609798,763370	209849,263349	YES

DESCRIPTION
Up to five parallel roundwoods (exposed L 1.5m; Wth 0.7m) located on the field surface were badly degraded due to milling. There was no visible evidence of woodworking. The remains were also visible in the E face of a nearby drain. (Dunne 1999, 10, 99LBW0024A)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057018-	Road - class 3 togher	609839,763411	209890,263390	YES

DESCRIPTION
A togher (Wth 2.25m; D 0.1m), orientated NW-SE, composed of transverse roundwood.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-087----	Road - class 3 togher	609838,763401	209889,263380	YES

DESCRIPTION

Derryadd Wind Farm - EIAR

Originally recorded as a small patch of a togher (L 10m min.) exposed on the field surface and visible in a drain section face (Dunne 1999, 7, 99LBW0014A). Excavation revealed an upper walking surface (original Wth 1.6-1.75m) of loosely laid, longitudinal small brushwood, with roundwood placed along the edges extending E-W. A substructure consisted of transverse, diagonal and longitudinal roundwood and brushwood, which in turn rested on diagonal and longitudinal small brushwood. Pegs were used to contain the edges of the togher and the substructure. There was no evidence of woodworking. The remains were quite degraded and milled. (Dunne 2000i, 205-6)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-089----	Road unclassified togher	609629, 763399	209680, 263378	YES

DESCRIPTION

A tightly packed band (exposed Wth 1.6m; T 0.18m) comprising seven roundwoods, and also incorporating c. 30 small and large pieces of brushwood, was exposed in a drain face. It extended into the section and was not evident in the opposing drain face. There was no visible evidence of woodworking. (Dunne 1999, 6, 99LBW0012A)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057008-	Road - class 3 togher	609689, 763366	209740, 263345	YES

DESCRIPTION

A togher (Wth 0.94m; D 0.22m) composed of a superstructure of longitudinal birch and ash roundwood with a substructure of longitudinal roundwood and brushwood, including some hazel.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057009-	Road - class 3 togher	609684, 763376	209735, 263355	YES

DESCRIPTION

A togher (Wth 1.85m; D 0.08m), orientated NE-SW, composed of longitudinal roundwood and brushwood of hazel, alder and birch.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057010-	Road - class 3 togher	609684, 763391	209735, 263370	YES

DESCRIPTION

A togher (Wth 0.9m; D 0.23m), orientated E-W, composed of longitudinal roundwood and brushwood, predominantly of ash and hazel.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
-----	-------	------------------------------	--	--------------------------

Derryadd Wind Farm - EIAR

LF022-057011-	Road – class 3 togher	609679,763401	209730,263380	YES
---------------	--------------------------	---------------	---------------	-----

DESCRIPTION
A togher (Wth 0.95m; D 0.16m), orientated NE-SW, composed of longitudinal roundwood and brushwood, predominantly of ash and hazel.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057012-	Road – class 3 togher	609674,763416	209725,263395	YES

DESCRIPTION
Small pieces of brushwood, orientated NE-SW.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-075----	Platform peatland	609692,763352	209743,263331	YES

DESCRIPTION
A compact horizontal band (Wth 0.8m; T 0.08m) of uniform small brushwood (diam. 0.015-0.045m) was evident in both section faces; possibly a hurdle. The remains extended roughly at right angles to the line of the drain. Approximately twenty pieces were visible and there was no visible evidence of woodworking. The evidence suggested that was likely to have been the remains of a platform. (Dunne 1999, 10, 99LBW0023A)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-093----	Road – class 3 togher	609707,763356	209758,263335	YES

DESCRIPTION
A substantial togher (exposed Wth 5.6m; T 0.4m min.) consisting of at least two split timbers, more than 30 roundwoods and over 100 pieces of brushwood was visible in both the E and W faces of a drain. It appeared to be orientated E-W, extending roughly at right angles to the line of the drain. A superstructure consisted of the two split timbers and numerous roundwoods (diam. 0.1-0.15m). The underlying substructure was composed of small brushwood (diam. c. 0.03m). (Dunne 1999, 4, 99LBW0006A)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057023-	Road – class 3 togher	609739,763356	209790,263335	YES

DESCRIPTION
A double layer of very fine ash brushwood and split-oak timbers, orientated NE-SW.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057024-	Road – class 3 togher	609719,763406	209770,263385	YES

DESCRIPTION
A togher (Wth 1.5m; D 0.26m), orientated NE-SW, consisting of longitudinal roundwood and brushwood with possible stone toolmarks.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057025-	Road – class 3 togher	609729,763396	209780,263375	YES
DESCRIPTION A scatter of alder wood (Wth 1.4m), with metal toolmarks and some damaged transverse hazel rods, was located on the field surface. It was orientated ENE-WSW.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057026-	Road – class 3 togher	609673,763308	209724,263287	NO
DESCRIPTION A badly preserved hurdle panel (L 0.9m min.; Wth 0.9m min.) noted in 1989. Radiocarbon dated to AD 43-617 (1535±30 BP, GrN-16829). (Raftery 1996, Corlea 7, 79)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057036-	Road – class 2 togher	609654,763331	209705,263310	YES
DESCRIPTION A togher (L 105m), orientated NE-SW, consisting of a superstructure of hazel twigs and leaves with a substructure of transverse hazel and ash brushwood.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-058006-	Road – class 3 togher	609665,763332	209716,263311	YES
DESCRIPTION This togher was located at the base of a drain and was partially exposed following investigation. It was orientated E-W (Information provided by B. Raftery).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057013-	Road – class 3 togher	609704,763291	209755,263270	YES
DESCRIPTION An irregular arrangement of brushwood, orientated NE-SW.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-074----	Road – class 1 togher	609733,763280	209784,263259	YES
DESCRIPTION				

A togher (L 159m) orientated ENE-WSW. Excavation revealed an upper walking surface (Wth 0.4-0.7m), which consisted of a core of closely spaced roundwood and brushwood longitudinal, with longitudinal outliers placed parallel to these central elements (Dunne 2002, 206). This superstructure rested on transverse, diagonal and longitudinal roundwood and brushwood. The largest transverse was a curving oak roundwood (L 3.5m). The wood was very soft and decayed and no well-preserved worked ends were recovered. A small number of timbers possessed worked ends that were in a degraded and decayed condition. The largest of the upper longitudinal was a half-split, roundwood trunk that was hollowed through decay and which may have been in that rotted condition when it was originally put in place. (Dunne 1999, 9, 99LBW0021A)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-094----	Platform peatland	-609720,763275	209771,263254	YES

DESCRIPTION

A compact band (exposed Wth 4.5m; T up to 0.3m) of two to three roundwoods and numerous pieces of brushwood and twigs was exposed in a drain. One of the roundwoods displayed a possible worked end. Beneath the platform were concentrations of natural wood and roots. (Dunne 1999, 4, 99LBW0007A)

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057015-	Road – class 3 togher	609759,763276	209810,263255	YES

DESCRIPTION

A togher (Wth 1.35m; D 0.22m), orientated NE-SW, constructed of roundwood and brushwood predominantly of oak, hazel and birch.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-057014-	Road – class 3 togher	609744,763266	209795,263245	YES

DESCRIPTION

A togher (Wth 1.2m; D 0.22m), orientated E-W, composed of transverse roundwood and brushwood of birch and hazel.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-081----	Road unclassified togher	-609783,763270	209834,263249	YES

DESCRIPTION

Originally recorded as a compact band (exposed L 3.7m; Wth 2.3m) of small and large brushwood (diam. 0.01-0.15m) located on the field surface and aligned NNW-SSE (Dunne 1999, 8, 99LBW0019A). Excavation revealed that the elements appeared to have been transverses for a roundwood and brushwood togher that originally ran ENE-WSW. A number of posts and pegs held the structure in place (Dunne 2002j, 206).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-082----	Road – class 2 togher	609616,763239	209667,263218	YES
DESCRIPTION A platform or togher complex (exposed L 28m; T 0.28m) composed of small and large brushwood, and roundwood was exposed in both faces of a drain. (Dunne 1999, 3, 99LBW0004A)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-092----	Road – class 3 togher	609631,763220	209682,263199	YES
DESCRIPTION Originally recorded as consisting of eight to ten roundwoods lying on top of smaller brushwood in a WSW drain face (Dunne 1999, 4, 99LBW0005A). Excavation revealed the togher (L 1.7m min.; exposed Wth 1.2m; T 0.45m) to be orientated NNE-SSE and constructed of longitudinal roundwood and brushwood (diam. 0.12m). These were probably originally underlain by transverse elements (Dunne 2002h, 205).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-066007-	Redundant record	610034,764800	210085,264780	NO
DESCRIPTION Four pieces of birch roundwood and brushwood on the field surface, two with metal-cut chisel points. This is possibly an area of modern scrub clearance. The evidence is insufficient to warrant acceptance as the remains of an archaeological monument				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-066008-	Redundant record	610034,764770	210085,264750	NO
Eight pieces of worked brushwood with metal toolmarks. This is possible an area of modern scrub clearance. The evidence is insufficient to warrant acceptance as the remains of an archaeological monument.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-066001-	Road – class 2 togher	610032,764683	210083,264663	YES
DESCRIPTION A togher (Wth 1.5m; D 0.15m), orientated ENE-WSW, composed of transverse and longitudinal roundwood and brushwood of hazel, ash and birch. Metal-cut toolmarks were evident.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
-----	-------	------------------------------	--	--------------------------

Derryadd Wind Farm - EIAR

LF022-066002-	Road – class 3 togher	610169,764450	210220,264430	YES
DESCRIPTION A togher (Wth 1.5m; D 0.15m), orientated E-W, consisting of hazel and birch brushwood and roundwood, with no apparent structure, overlying a possible hurdle.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-066003-	Road – class 3 togher	610154,764485	210205,264465	YES
DESCRIPTION A togher (Wth 2.5m; D 0.07m), orientated ENE-WSW, composed of transverse and longitudinal roundwood and brushwood of ash, birch and oak.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-066004-	Road – class 3 togher	610064,764500	210115,264480	YES
DESCRIPTION A togher (Wth 2.5m; D 0.07m), orientated ENE-WSW, composed of transverse and longitudinal roundwood and brushwood of ash, birch and oak.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-066005-	Road – class 3 togher	610159,764480	210210,264460	YES
DESCRIPTION A togher (Wth 2.5m; D 0.07m), orientated ENE-WSW, composed of transverse and longitudinal roundwood and brushwood of ash, birch and oak.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF022-066006-	Road – class 3 togher	610149,764490	210200,264470	YES
DESCRIPTION A togher (Wth 1.5mm; D 0.12m) composed of an irregular series of transverse ash, hazel and birch roundwood, orientated NW-SE.				

DERROGHIL

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-81001-	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION This togher (L 4.3m min.; Wth 0.7m; D 0.1m), noted in 1988, was orientated E-W and consisted of a narrow, dense bed of straight, longitudinal brushwood with occasional short diagonal pieces. Radiocarbon dated to 1524-1401 BC (3195±40 BP, GrN-16632). (Raftery 1990, 24; 1996, Derryoghil 28, 155-6)				

--

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081002-	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION This togher (L 2.8m min.; Wth 1.2m; D 0.12m), noted in 1988, was orientated NNE-SSW and consisted of poorly preserved longitudinal brushwood and roundwood. Radiocarbon dated to 1489-1309 BC (3120±35 BP, GrN-16638). (Raftery 1996, Derryoghil 35, 162-3)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081003	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION This togher (L 2.6m min.; Wth 1.1m min.; D 0.1m), noted in 1988, was orientated NE-SW and consisted of longitudinal brushwood and roundwood. Radiocarbon dated to 1519-1323 BC (3170±35 BP, GrN-16639). (Raftery 1996, Derryoghil 36, 163)				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081004-	Road - class 2 togher	605187,768553	205237,268534	YES
DESCRIPTION A togher (L 20m; Wth 2.23m; D 0.3m), orientated ESE-WNW, composed of a longitudinal hurdle panel overlying a roundwood substructure. The weave of the hurdle was a simple under-over pattern alternating with every second sail. Small worked pegs were inserted through it to prevent lateral movement. The togher survived across two fields.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081005	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION A togher (Wth 2.15m; D 0.06m), orientated ESE-WNW, composed of longitudinal hazel brushwood. One large peg was visible at one edge of the section.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
-----	-------	---------------------------	---	-----------------------

Derryadd Wind Farm - EIAR

LF018-081006	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION A togher (Wth 1.05m; D 0.14m), orientated NW-SE, composed of longitudinal small brushwood; there was also a large volume of twigs in the area.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081007	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION A togher (Wth 1.85m; D 0.44m) consisting of longitudinal roundwood with brushwood around the periphery. It was orientated WNW-ESE and the wood included ash, oak, alder and hazel.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081008	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: A togher (Wth 0.9m; D 0.08m), orientated E-W, composed of longitudinal brushwood of alder, hazel and ash.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081009	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description A togher (Wth 1m; D 0.14m), orientated E-W, composed of longitudinal roundwood and some hazel brushwood supported by large, transverse roundwood.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081010	Road - class 3 togher	605187,768553	205237,268534	YES

Derryadd Wind Farm - EIAR

DESCRIPTION
Yes
Description: A togher (Wth 1.35m; D 0.06m), orientated E-W, composed of a possible hurdle panel of longitudinal ash and hazel brushwood.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081011	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A togher (Wth 1.1m; D 0.11m), orientated E-W, consisting of mixed brushwood and roundwood of ash and hazel.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081012	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A togher (Wth 1m; D 0.08m), orientated E-W, composed of longitudinal roundwood (av. diam. 0.05m), most of which was hazel. A single worked peg was exposed in the drain face.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081013	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A togher (Wth 1.2m; D 0.2m), orientated NW-SE, consisting of longitudinal roundwood and brushwood of ash and hazel.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081015	Road - class 3 togher	605187,768553	205237,268534	YES

Derryadd Wind Farm - EIAR

DESCRIPTION Yes Description: A togher (Wth 2.7m; D 0.2m), orientated E-W, composed of longitudinal brushwood, which was predominantly hazel, with a scattering of smaller twigs. There was good evidence of woodworking.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081017	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION Yes Description: A togher (Wth 2.45m; D 0.12m), orientated ENE-WSW, consisting of longitudinal roundwood and brushwood of hazel and birch. One peg (L 0.54m; diam. 0.065m) was found in the exposed section in the drain face.				
---	--	--	--	--

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081018	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION Yes Description: A togher (Wth 2.15m; D 0.32m), orientated E-W, consisting of longitudinal brushwood of hazel and birch. There was good evidence of woodworking.				
---	--	--	--	--

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081019	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION Yes Description: A togher (Wth 0.6m; D 0.07m), orientated E-W, consisting of longitudinal hazel brushwood that was secured by pegs. The pegs were bent, presumably from being driven into place.				
---	--	--	--	--

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081020	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION				
-------------	--	--	--	--

Derryadd Wind Farm - EIAR

Yes
Description : A togher (Wth 0.85m; D 0.04m), orientated E-W, composed of longitudinal roundwood and brushwood mainly of hazel.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081021	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description : A togher (Wth 1.35m; D 0.07m), orientated E-W, consisting of longitudinal roundwood and brushwood, mostly of hazel.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081022	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description : A togher (D 0.13m), orientated E-W, consisting of worked roundwood and brushwood of ash, hazel and birch.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081023	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description : A togher (Wth 1.8m; D 0.2m), orientated E-W, composed of longitudinal brushwood of hazel and birch.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081024	Road - class 2 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes

Derryadd Wind Farm - EIAR

Description :A togher (L 39m; Wth 2m; D 0.2m), orientated E-W, composed of longitudinal and occasional transverse roundwood of ash, birch and oak.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081025	Road - class 2 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : A togher (L 45m; Wth 2.9m; D 0.2m), orientated ENE-WSW, composed of longitudinal roundwood of ash, hazel and oak.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081026	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : A well-constructed togher (L 6m min.; Wth 1.8m; D 0.25m), orientated E-W, consisting of a substructure of longitudinal and transverse roundwood, above and below which were thick deposits of irregular brushwood, and a superstructure of very regular transverse roundwood and brushwood. Pegs were irregularly positioned along its sides. Toolmarks were very clear and showed good signatures. At its E end the togher veered to the NE. Radiocarbon dated to 1685 1459 BC (3295±40 BP, GrN 16566) (Raftery 1990, 19; 1996, Derryoghil 10, 132-6). When inspected in 1999, it (exposed L 2.2m; Wth 2.5m) consisted of large parallel roundwoods (diam. 0.10-0.11m) with parallel brushwood (diam. 0.03-0.06m) between and one transverse roundwood (0.13 x 0.6m) (Dunne 1999).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081027	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 8m min.; Wth 1.5m; D 0.4m), noted in 1988, was orientated E-W and consisted of longitudinal brushwood (diam. 0.03-0.06m) with occasional roundwood (diam. 0.09m). Poor woodworking was evident. Radiocarbon dated to 1680-1451 BC (3275±35 BP, GrN-16569) (Raftery 1996, Derryoghil 13, 139-42).

Derryadd Wind Farm - EIAR

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081028	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: This largely obliterated togher (L 4.4m min.; Wth 1m; D 0.07m), noted in 1988, consisted of tightly packed longitudinal brushwood and roundwood, with the latter concentrated at the edges. It was orientated E-W. Radiocarbon dated to 1603-1428 BC (3235±35 BP, GrN-16570) (Raftery 1996, Derryoghil 14, 142).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081029	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: This togher (L 8.4m min.; Wth 2.2m; D 0.3m), noted in 1988, was orientated ENE-WSW. It consisted of a superstructure of tightly packed longitudinal roundwood and brushwood, beneath which was a substructure of longitudinal brushwood, a transverse oak plank, a half-split ash timber and a small concentration of wood-chips. Seven pegs were noted along its edges. Radiocarbon dated to 1680-1451 BC (3275±35 BP, GrN-16571) (Raftery 1996, Derryoghil 15, 142-3).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081030	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: This substantial togher (L 5m; Wth 2.2m; D 0.3m), noted in 1988, was orientated NE-SW and consisted of longitudinal hazel and birch brushwood, occasional roundwood and a radially split-oak plank. Two pegs were encountered within the body of this material. A half-split birch log lay parallel to it, c. 1.7m to the NW. Radiocarbon dated to 1767-1614 BC (3395±35 BP, GrN-16847) (Raftery 1996, Derryoghil 16, 143-4).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081031	Road - class 3 togher	605187,768553	205237,268534	YES

Derryadd Wind Farm - EIAR

DESCRIPTION Yes Description This togher (L 4.5m; Wth 1.1m; D 0.1m), noted in 1988, was orientated NW-SE and consisted of longitudinal brushwood (diam. 0.03-0.05m) laid on a bed of longitudinal roundwood. Radiocarbon dated to 1521-1400 BC (3185±35 BP, GrN-16573) (Raftery 1996, Derryoghil 17, 145).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081032	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : This togher (L 2.3m; Wth 0.3m; D 0.05m), noted in 1988, was orientated NE-SW and consisted of a number of broken longitudinal brushwood pieces of hazel and birch. Radiocarbon dated to 1013-834 BC (2795±35 BP, GrN-16574) (Raftery 1996, Derryoghil 18, 145).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081033	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : This togher (L 7m min.; Wth 0.5-0.8m) noted in 1988, was orientated N-S and was composed mostly of longitudinal brushwood (diam. 0.03-0.05m); there was good evidence of worked wood. It was not substantial and had noticeable gaps between the brushwood. Another togher (LF018-081052-) underlay it, at a right angle to it (Raftery 1996, Derryoghil 19a, 148).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081034	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes				

Description : This togher (L 6m min.; Wth 0.5m; D 0.06m), noted in 1988, was orientated NW-SE and consisted of loosely arranged longitudinal brushwood. Radiocarbon dated to 1210-922 BC (2880±40 BP, GrN-16624) (Raftery 1996, Derryoghil 20, 149).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081035	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 3.1m min.; Wth 0.7m; D 0.06m), noted in 1988, was orientated NW-SE and consisted of a damaged hurdle panel with seven intact sails. Radiocarbon dated to 1366-1010 BC (2950±40 BP, GrN-16625) (Raftery 1996, Derryoghil 21, 149-50).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081036	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 1.7m min.; Wth 0.9m; D 0.12m), noted in 1988, was orientated N-S and consisted of tightly packed longitudinal and occasional transverse hazel rods. Radiocarbon dated to 1258-898 BC (2870±60 BP, GrN-16626) (Raftery 1996, Derryoghil 22, 150).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081037	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 3.2m min.; Wth 0.9m; D 0.07m), noted in 1988, was orientated E-W and consisted of longitudinal roundwood and brushwood. Radiocarbon dated to

1209-926 BC (2880±35 BP, GrN-16627) (Raftery 1996, Derryoghil 23, 150). It was similar to another togher (LF018-081038-).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081038	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : This togher (L 4.9m min.; Wth 2m; D 0.08m), noted in 1988, was orientated NE-SW and was of similar construction to another togher (LF018-081037-) but it contained a significantly larger amount of roundwood. Radiocarbon dated to 1008-833 BC (2790±35 BP, GrN-16628) (Raftery 1996, Derryoghil 24, 150).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081039	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : This togher (L 5.2m min.; Wth 2.25m; D 0.2m), noted in 1988, was orientated NW-SE and was composed of large roundwoods (diam. 0.10-0.18m) in the W half of the excavated area. This gave way to much-thinner brushwood towards the E. Radiocarbon dated to 1375-1126 BC (2995±35 BP, GrN-16629) (Raftery 1996, Derryoghil 25, 153-4).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081040	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : This togher (L 4.3m min.; Wth 4m; D 0.5m), noted in 1988, was orientated NE-SW and consisted of a wide band of very irregularly laid brushwood and roundwood. Occasional pegs were randomly inserted throughout the structure for stability.				

Derryadd Wind Farm - EIAR

Radiocarbon dated to 1260-1004 BC (2930±35 BP, GrN-16630) (Raftery 1996, Derryoghil 26, 154).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081041	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
 Yes
Description : This togher (L 4.3m min.; Wth 4m; D 0.5m), noted in 1988, was orientated NE-SW and consisted of longitudinal brushwood upon which occasional roundwood stems were laid. A small number of pegs were scattered within it. Radiocarbon dated to 1256-979 BC (2905±35 BP, GrN-16631) (Raftery 1996, Derryoghil 27, 155).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081042	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
 Yes
Description: This togher (L 3.2m; Wth 2.5m; D 0.04m), noted in 1988, consisted of short irregularly laid brushwood (av. diam. 0.05m) in poor condition. Radiocarbon dated to 1013-834 BC (2795±35 BP, GrN-16565) (Raftery 1996, Derryoghil 9, 130-32).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081043	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
 Yes
Description : This togher (L 2m; Wth 1.8m; D 0.05m), noted in 1988, was orientated E-W and survived only as splinters and shavings on the field surface. There were several worked ends present. Radiocarbon dated to 1490-1263 BC (3115±40 BP, GrN-16567) (Raftery 1996, Derryoghil 11, 137).

Derryadd Wind Farm - EIAR

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081044	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : This extensively damaged togher (L 2.4m; Wth 2m; D 0.05m) of brushwood, noted in 1988, was radiocarbon dated to 1523-1321 BC (3180±45 BP, GrN-16568) (Raftery 1996, Derryoghil 12, 137-9).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081045	Road - class 2 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description This togher (L 5m min.; Wth 1.2m; D 0.12m), orientated E-W, consisted of longitudinal roundwood and occasional pegs and was radiocarbon dated to 1617-1433 BC (3250±35 BP, GrN-16633) (Raftery 1990, 24; 1996, Derryoghil 29, 157-8). When inspected in 1999 (Dunne) it comprised longitudinal roundwood and large brushwood overlying a brushwood substructure (overall L 18m; Wth 2m; T 0.4m).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081046	Road - class 2 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : This togher (L 5.1m min.; Wth 1.4m; D 0.3m), orientated NW-SE, consisted of a dense layer of brushwood (diam. 0.02-0.05m) upon which two hurdle panels had been placed. It was radiocarbon dated to 1258-941 BC (2905±40 BP, GrN-16007) (Raftery 1990, 24-5; 1996, Derryoghil 30, 158-9). When inspected in 1999 (Dunne) it comprised a densely packed longitudinal brushwood platform (exposed L 1.6m; Wth 1.07m) with elements (diam. 0.015-0.06m) aligned ENE-WSW.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081047	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : This togher (L 3.6m min.; Wth 1.3m; D 0.1m), orientated NNE-SSW, consisted of longitudinal hazel rods overlain by a poorly preserved hurdle panel. It was				

radiocarbon dated to 1208-923 BC (2875±35 BP, GrN-16634) (Raftery 1990, 24; 1996, Derryoghil 31, 159-60). When inspected in 1999 (Dunne) it comprised quite densely packed longitudinal small and large brushwood (diam. 0.02-0.04m) with roundwood (one is 0.11m in diameter), aligned E-W (overall L 15m; Wth 1.2m). Two longitudinal roundwoods extended along the centre of the togher.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081048	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 3.6m min.; Wth 1.3m; D 0.1m), noted in 1988, was orientated NNE-SSW and consisted of poorly preserved longitudinal brushwood (diam. 0.01-0.02m) and roundwood (diam. 0.06m). Radiocarbon dated to 1678-1443 BC (3265±35 BP, GrN-16635) (Raftery 1996, Derryoghil 32, 160-61).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081049	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 2.95m; Wth 0.4m; D 0.05m), noted in 1988, was orientated NW-SE, and consisted of a hurdle panel of hazel brushwood with a single stake inserted through the NE corner. Radiocarbon dated to 1209-926 BC (2880±35 BP, GrN-16636).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081050	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 3.5m min.; Wth 2.2m; D 0.09m), noted in 1988, was orientated NE-SW and consisted of degraded longitudinal brushwood overlain by transverse brushwood and roundwood. Radiocarbon dated to 794-541 BC (2525±25 BP, GrN-16637) (Raftery 1996, Derryoghil 34, 161).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
-----	-------	---------------------------	---	-----------------------

Derryadd Wind Farm - EIAR

LF018-081051	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : This togher (L 4.75m min.; Wth 2.2m; D 0.13m), orientated NW-SE, consisted of extensively damaged brushwood and roundwood. The NW end of the excavated portion was constructed of longitudinal brushwood (diam. 0.02-0.05m) which, towards the E, gave way to a substructure of transversely laid brushwood. It was radiocarbon dated to 1207-922 BC (2870±35 BP, GrN-16642) (Raftery 1996, Derryoghil 39, 164-5). When inspected in 1999 (Dunne) it comprised longitudinal brushwood (overall L 15m; Wth 2.2m) in very bad condition. The brushwood (diam. 0.02-0.04m) was densely packed and no woodworking was visible.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-081052	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : This togher (L 7.2m min., Wth 4.9m min., D 0.44m), noted in 1988, was orientated E-W and consisted of tightly packed parallel roundwoods (diam. 0.02-0.05m) and one very large ash plank (surviving L 2.1m, Wth 0.45m, T 0.09m) that was used as a foundation. The plank had a double mortice at its E end. Another togher (LF018-081033-) overlay it, at a right angle to it. Radiocarbon dated to 1680-1451 BC (3275±35 BP, GrN-16623) (Raftery 1996, Derryoghil 19, 145-8).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082001	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : A togher (Wth 1m; D 0.07m), orientated E-W, consisting of longitudinal brushwood of hazel and birch. There was good evidence of woodworking.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082002	Road - class 2 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description : A togher (L 30m; Wth 1.1m; D 0.23m), orientated ENE-WSW, composed of longitudinal roundwood and brushwood of hazel, alder and birch.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082003	Structure peatland	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description: An irregular spread (L 10m) consisting of a large number of oak planks with ash and hazel roundwood, orientated NNE-SSW, was exposed in a drain face, and on and near the field surface. The timbers were well spaced with no direct contact between them but their general proximity and similarity in form suggested that they were functionally associated. A single mortice and abundant toolmarks were evident.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082004	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description: A togher (Wth 1.5m; D 0.1m), orientated ESE-WNW, composed of longitudinal roundwood of ash and hazel.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082005	Road - class 2 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description: A togher (L 53m; Wth 1.2m; D 0.2m), orientated ESE-WNW, composed of transverse and longitudinal brushwood of hazel, alder and birch.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082006	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Derryadd Wind Farm - EIAR

Yes
Description: A togher (Wth 0.9m; D 0.08m), orientated E-W, composed of four roundwoods of ash and hazel and a half-split oak timber.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082007	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A togher (Wth 1.2m; D 0.25m), orientated E-W, composed of transverse and longitudinal roundwood and brushwood. The species present included hazel and ash and some of the wood was worked.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082009	Road - class 2 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: This togher (L 30m min.; Wth 0.55m; D 0.1m), noted in 1988, was orientated E-W and was composed of longitudinal roundwood of birch, ash and oak placed end to end, with up to four laid parallel. The togher was recognized in two other fields and probably extended from the dry land to the E to that to the W. Radiocarbon dating revealed a date range of 1684-1440 BC (3280±45 BP, GrN-16564) (Raftery 1990, 19; 1996, Derryoghil 8, 129-30). When inspected in 1999 (Dunne) it was visible in the headland section face, which was much higher than the adjacent milled surface. A superstructure of roundwood (diam. 0.10-0.13m) overlay densely packed brushwood (diam. 0.02-0.025m).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082010	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: This togher (L 11.5m min.; Wth 0.65m; D 0.1m), noted in 1988, was orientated E-W and consisted of several long straight longitudinal roundwoods of oak and ash (diam. 0.08-0.1m). These were laid on occasional well-spaced transverses of oak secured by pegs. Radiocarbon dated to 2559-2294 BC (3930±40 BP, GrN-16006) (Raftery 1990, 18-19, 63; 1996, Derryoghil 7, 127-9).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082011	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 11m min.; Wth 1.6m; D 0.15m), noted in 1987, was oriented E-W and consisted of a superstructure of longitudinal small brushwood (av. diam. 0.08m; av. L 1.8m) on a substructure of transverse rods and larger roundwood (av. diam 0.15m; av. L 3m). Short pegs (av. diam. 0.11m; av. L 0.45m) were used in its construction. The evidence for worked wood was extremely good. Presuming the togher crossed the bog, its original length would have been c. 650m. Radiocarbon dated to 1286-1000 BC (2925±40 BP, GrN-16559) (Raftery 1990, 63; 1996, Derryoghil 2, 115-20).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082012	Road - class 2 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 16m; Wth 1m; D 0.13m), noted in 1987, was orientated E-W and consisted of longitudinal brushwood and roundwood (diam. 0.06-0.13m; L 0.66-2.3m). Radiocarbon dated to 1003-900 BC (2805±20 BP, GrN-15487) (Raftery 1996, Derryoghil 3, 121-2).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082013	Road - class 2 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 17m min.; Wth 1.5m; D 0.1m), noted in 1987, was orientated E-W and consisted of longitudinal roundwood (av. diam. 0.08m), large twigs (diam. 0.18-0.25m) and pegs (av. diam. 0.07m; L 0.2-0.55m). There was limited evidence for woodworking. Radiocarbon dated to 1410-1131 BC (3045±40 BP, GrN-15488) and 916-801 BC (2700±35 BP, GrN-16561) (Raftery 1996, Derryoghil 4, 122-4).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082014	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 17m min.; Wth 1.5m; D 0.1m), noted in 1987, was orientated E-W and consisted of a brushwood hurdle of hazel and occasional birch (av. diam. 0.035m). It had a simple under-over weave and three remaining sails, each with toolmarks at the ends. Radiocarbon dated to 1109-900 BC (2830±35 BP, GrN-15489) (Raftery 1990, 21, 27-8; 1996, Derryoghil 5, 125-6).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082015	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 7.3m; Wth 0.6m; D 0.05m), noted in 1988, was orientated ESE-WNW and consisted of three woven hurdles laid end to end. They were made of a simple under-over weave of hazel and ash. Birch and ash roundwood was used as the sails, most of which had fine toolmarks. Radiocarbon dated to 1369-1023 BC (2965±40 BP, GrN-16563) (Raftery 1990, 6; 1996, Derryoghil 6, 126-7).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082016	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This togher (L 2.8m; Wth 0.9m; D 0.15m), noted in 1988, was orientated E-W and consisted of seven birch roundwoods. Radiocarbon dated to 1384-1054 BC (2995±40 BP, GrN-16640) (Raftery 1996, Derryoghil 37, 163).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082017	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: This togher (L 2.85m; Wth 0.55m; D 0.1m), noted in 1988, was orientated E-W and consisted of hazel roundwood and brushwood. Radiocarbon dated to 760-406 BC (2440±20 BP, GrN-16641) (Raftery 1996, Derryoghil 38, 163-4).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082029	Road - class 2 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: A togher (L 60m; Wth 1.4m; D 0.17m), orientated NE-SW, consisting of longitudinal brushwood of birch and ash with evidence of woodworking.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082030	Road - class 2 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: A togher (L 85m; Wth 1m; D 0.25m), orientated NE-SW, consisting of longitudinal birch, ash, hazel and some split-oak timbers. Toolmarks were present.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082031	Road - class 2 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: A togher (L 33m; Wth 2.35m; D 0.1m), orientated NE-SW, consisting of longitudinal roundwood and brushwood of ash and birch. There was evidence of woodworking.				

Derryadd Wind Farm - EIAR

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082032	Road - class 2 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: A togher (L 33m; Wth 1.6m; D 0.11m), orientated NE-SW, consisting of transverse and longitudinal roundwood and brushwood of birch, oak and ash.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082033	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: This two-layered togher (L 1m; Wth 4.1m; D 0.4m), orientated E-W, consisted of a superstructure of transverse and longitudinal roundwood and brushwood of ash, birch and occasional hazel and a substructure of longitudinal brushwood. A peg had been driven through both structures.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082034	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: A togher (Wth 1.5m; D 0.18m), orientated NE-SW, consisting of longitudinal roundwood of birch and ash.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-082035	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: A togher (Wth 1.2m; D 0.12m), orientated NW-SE, consisting of longitudinal brushwood and roundwood of hazel and ash (diam. 0.028-0.08m).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
-----	-------	---------------------------	---	-----------------------

Derryadd Wind Farm - EIAR

LF018-087	Road - class 3 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: Noted during field survey in 1988, orientated NE-SW (pers. comm. B. Raftery).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-122	Platform peatland	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: Small longitudinal brushwood (diam. 0.01-0.04m) with some roundwood (diam. 0.06-0.09m) appeared to be aligned ENE-WSW. No woodworking was visible. The evidence suggested that this was likely to be the remains of a platform (exposed Wth 1.2m; T 0.16m).				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-123	Platform peatland	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: Roundwood, brushwood and twigs (exposed Wth 2.5m; T 0.3m) were exposed in both faces of a drain. A substructure of roundwood, orientated E-W, overlain by a layer of brushwood, orientated N-S, and a superstructure of brushwood, orientated E-W, with twigs throughout, were evident. It most likely was the remains of a platform.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-124	Road - class 2 togher	605187,768553	205237,268534	YES
DESCRIPTION Yes Description: A togher (overall L 35m; Wth 3.1m; T 0.35m), orientated ENE-WSW, consisting of longitudinal small and large brushwood (av. diam. 0.04m), roundwood (diam 0.065-0.09m) and twigs, with some transverse elements.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-125	Platform peatland	605187,768553	205237,268534	YES

Derryadd Wind Farm - EIAR

DESCRIPTION Yes Description : Closely set longitudinal twigs and brushwood (diam. 0.007-0.05m) appeared to be the remains of a platform (exposed Wth 0.25m; T 0.15m) orientated NNE-SSW. The smaller elements were located more towards the centre with the larger elements forming the edges.				

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-126	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION Yes Description : A wide band (overall L 7.5m, T 0.15m) of mainly small brushwood (diam. 0.02-0.03m) , orientated N-S, was visible in both faces of a drain. No woodworking was visible. Originally recorded as 27A and 28A but believed to be one monument. The evidence suggested that this was most likely to be the remains of a platform				
--	--	--	--	--

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-127	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION Yes Description : A loosely arranged longitudinal band (exposed Wth 1.6m, T 0.15m) of brushwood (av. diam. 0.04m), orientated NE-SW, was exposed in a drain face. One transverse was visible. There was no evidence of woodworking. It most likely was the remains of a platform.				
--	--	--	--	--

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-128	Road - class 2 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A togher (overall L 17m; Wth 2.4m; T 0.4m) consisting of longitudinal roundwood, tightly packed in the centre and loose to the sides. Two roundwoods formed the edges. The structure also incorporated small brushwood and twigs. The two outer roundwoods were orientated WNW-ESE.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-129	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A substantial structure (overall exposed Wth 6.2m; T 0.35m), orientated NE-SW, composed of closely set longitudinal roundwood (diam. 0.2m max.) flanked by brushwood (diam. 0.045-0.06m). Pegs were also evident. The evidence suggested that this was likely to be the remains of a platform.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-130	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A superstructure of lightly packed small brushwood (diam. 0.02-0.03m) rested on a substructure of large brushwood (diam. 0.04-0.06m). All the brushwood (exposed L 2m; Wth 0.7m; T 0.2m) was laid longitudinally in a NNE-SSW alignment. The evidence suggested that this was likely to be the remains of a platform.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-131	Road - class 2 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A togher (exposed L 23m; Wth 1.1m; T 0.4m) consisting of a narrow band of closely set parallel roundwood and brushwood, orientated NW-SE. A single peg was also evident.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-132	Road - class 1 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A togher (overall L 60m; Wth 2.2m; T 0.5m), orientated E-W, consisting longitudinal brushwood (diam. 0.02-0.05m) and roundwood (diam. 0.06-0.08m) was exposed over four milled fields. Two possible planks were evident.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-133	Road - class 2 togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: Three areas of longitudinal brushwood (diam. 0.015-0.05m) and small roundwood (diam. 0.09m max.), aligned ENE-WSW, exposed on the milled surface may have been part of the same togher (overall L 20m; Wth 1.7m). The three exposed sections were slightly offset but were of the same construction type.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-134	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: Tightly packed parallel brushwood (diam. 0.023-0.04m) with twigs, possibly aligned NE-SW, appeared to be the remains of a platform (exposed Wth 1m, T 0.07m).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-135	Road unclassified togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A togher (exposed Wth 2.85m; T 0.5m min.) exposed in a drain face, aligned NE-SW, was composed of roundwood (diam. 0.06m) and split large roundwood (diam. 0.3m) lying upon a substructure of roundwood and brushwood (0.02-0.05m). One roundwood peg was evident. It was also visible in the opposite drain face and field.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-136	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION

Derryadd Wind Farm - EIAR

Yes
Description: A platform (exposed L 0.7m; Wth 1.5m) consisting of longitudinal roundwood (diam. 0.1-0.13m) and brushwood (diam. 0.04-0.05m).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-137	Road - class 2 together	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A togher (L 22m, Wth 2.8m, T 0.2m) consisting of up to eleven roundwoods (diam. 0.07-0.09m) and fifteen pieces of brushwood (diam. 0.02-0.05m) all laid longitudinally in a NE-SW orientation. At least one possible peg was evident.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-138	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: An extensive band (exposed Wth 1.9m; T 0.47m) of brushwood (diam. c. 0.02-0.05m) with two roundwoods (diam. 0.07-0.08m), aligned NE-SW, appeared to be the remains of a platform.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-139	Road unclassified togher	605187,768553	205237,268534	YES

DESCRIPTION
Yes
Description: A togher (exposed Wth 1.4m, T 0.15m), exposed in a drain face, consisting of longitudinal roundwood, split roundwood, planks and brushwood. The split roundwood (diam. 0.2m) formed the outer edges.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-140	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION
Yes

Description : A hurdle panel (exposed L 1.9m, Wth 1.3m) exposed on the field surface was orientated ENE-WSW. It was composed of rods (diam. 0.02-0.03m) and sails (diam. 0.04-0.05m). Some toolmarks were visible at the ends of the rods. The evidence suggested that this was most likely to be the remains of a platform.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-141	Road unclassified togher	-605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : A togher (original Wth 0.8m; T 0.2m) consisting of four closely set, longitudinal roundwoods aligned NE-SW.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-142	Platform peatland	-605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : Brushwood and roundwood (av. diam. 0.12m) exposed on the field surface and aligned NE-SW, appeared to be the remains of platform (exposed L 5.5m; Wth 1.4m). No toolmarks were evident.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-143	Platform peatland	-605187,768553	205237,268534	YES

DESCRIPTION

Description : Longitudinal large brushwood was laid upon small brushwood, which in turn was supported by transverse brushwood orientated NE-SW. The evidence suggested that it most likely was the remains of a platform (exposed L 2.3m; Wth 1.8m).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-144	Platform peatland	-605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This platform (exposed L 1.8m; Wth 1m) was composed of several layers of densely packed twigs (diam. 0.01m), small and large brushwood (diam. 0.03-0.04m) and

Derryadd Wind Farm - EIAR

one roundwood (diam. 0.1m). It was orientated roughly E-W. The twigs may have been sandwiched between two layers of brushwood.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-145	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION
 Yes
Description: Longitudinal brushwood (diam. 0.05m max.) and twigs appeared to be orientated WNW-ESE. The material was closely set in the centre becoming less dense towards edges though this may have been due to milling. The evidence suggested that this was likely to have been the remains of a platform (exposed L 0.6m, Wth 0.9m).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-146	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION
 Yes
Description: This togher (exposed L 11.6m, T 0.45m), orientated ENE-WSE, consisted of small and large brushwood with occasional roundwood. Both longitudinal and transverse elements were evident.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-147	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION
 Yes
Description: Two longitudinal roundwoods (diam. 0.08m and 0.14m) and nine pieces of brushwood (diam. 0.03-0.05m), orientated ESE-WNW, appeared to be the remains of a platform (exposed L 5m; Wth 0.8m).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-148	Road - class 2 togher	605187,768553	205237,268534	YES

DESCRIPTION
 Yes

Derryadd Wind Farm - EIAR

Description: A togher (overall L 27m, Wth 3.2m, T 0.5m), orientated ENE-WSW, consisting of longitudinal, transverse and diagonal large brushwood and roundwood with occasional small brushwood.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-149	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description: A band (exposed Wth 0.83m; T 0.11m) of brushwood (av. diam. 0.03m), aligned NW-SE, exposed in a headland section face that was much higher than the adjacent milled field surface, appeared to be the remains of a platform.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-150	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description: A togher (overall L 8m; Wth 0.35m), aligned NE-SW, comprising two transverse roundwoods (diam. 0.06-0.07m) overlying brushwood and twigs (diam. 0.02-0.05m).

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-151	Road - class 2 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description: A togher (overall L 17m; Wth 3m; T 0.35m), aligned NE-SW, constructed of roundwood (diam. 0.07-0.1m), planks (one measures 0.19 x 0.03m), split rectangular timbers (av. 0.08 x 0.04m) and brushwood.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-152	Road unclassified togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description: A togher (exposed Wth 0.8m; T 0.12m), aligned roughly E-W, consisting of closely set roundwood (av. diam. 0.07m) and brushwood, with an associated bed of twigs and small brushwood c. 0.2m to the S. Also present in the opposite drain face.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-153	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description: A togher (overall L 12m; Wth 1.2m) identified as 48A and 48B. The former was composed of tightly packed brushwood (diam. 0.025m) with some roundwood, while the latter consisted of a looser arrangement of roundwood, brushwood (diam. 0.02-0.05m) and twigs. It is possible that both were unconnected.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-154	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description: A band (exposed Wth 1.54m; T 0.26m) of brushwood (diam. 0.025-0.055m), aligned NE-SW, exposed in a headland section face that was much higher than the adjacent milled field surface, appeared to be the remains of a platform.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-155	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description: A large brushwood substructure with a superstructure of two large pieces of brushwood at right angles to it appeared to be the remains of a platform (exposed L 2m; Wth 1.5m) aligned NNW-SSE. Some pegs were also visible.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-159	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This site is located in the industrial peatlands of Lough Bannow Bog. It was recorded in the 2013 Re-assessment Peatland Survey as a togher exposed in the drain face. The roundwoods were cut by the drain, but where they ran under the peat, they survived in good condition, with bark remaining. While the elements predominately ran parallel, the western one ran over the central one at one point (Whitaker 2014).

A single cutting was opened and excavated under licence 15E0205. The site was dated cal. 2870-2498 BC (UBA 26639). It was situated in Sphagnum peat with Phragmites inclusions. The excavated site consisted of three NW-SE orientated heavy hazel roundwood elements (L1.75-3.55m, Diam. 0.1-0.14m) with three associated light hazel and blackthorn brushwoods (L0.71-1.65m, Diam. 0.02-0.03m). The elements were closely placed, side-by-side, creating a total width ranging from 0.46-1.25m. A toolmarked end was noted.

The roundwoods were truncated by the drain, but there was no evidence for the site in the opposing drain face. The excavated elements either represent the remains of a small platform or short length of togher.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-160	Road - class 2 togher	2605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This site is located in the industrial peatlands of Lough Bannow Bog. The three sites mentioned below were originally recorded as separate structures but following excavation were subsequently interpreted as being part of the same togher structure, roughly orientated E-W. The site was situated in raised bog peats. It was dated to the Neolithic, specifically to cal. 2863-2501 BC (UBA).

LF-LBW014 (Photo 1) was recorded in the 2013 Re-assessment survey as a single roundwood exposed in section in the drain face 0.47m below the field surface, with a small root beside it (Whitaker 2014). It was excavated under licence 15E2013. The site consisted of predominantly ENE-WSW orientated, closely placed roundwood and brushwood elements, 1.6-2.3m in width. These were supported by a substructure composed of closely placed SSE-NNW orientated brushwood, secured by pegs. Eleven of the elements had toolmarked ends. Most elements were in poor condition. Three sondages were excavated to the W of the cutting, revealing possible hurdle panels and a roundwood and brushwood deposit.

The other sighting was recorded as a togher, visible in section in the drain face 0.18m below the drain surface (Whitaker 2014). It was excavated under licence 15E0208. Here, the upper surface of the togher (W1.5-4.03m) was composed of closely placed, transversely laid, roundwood and brushwood elements (Photo 2). The majority of the elements were soft and spongy in texture although most had intact bark. Underlying the superstructure were E-W orientated, densely placed roundwood and brushwood longitudinals, with lighter brushwood used as packing (Photo 3). The elements were in moderate condition with many elements retaining their bark. Pegs delineated the site. Several toolmarked ends were noted in both structures. The elements were species identified as alder and birch with lesser amounts of ash, holly, hazel, elm, and pomoideae.

Derryadd Wind Farm - EIAR

A possible separate structure (LBW017, see Photo), oriented NE-SW, was uncovered at the W extent of the site, 1.5m to the N in the drain face (Photo 4). It was composed of longitudinally-laid brushwood and roundwood elements, secured by pegs. The elements were closely placed, laid two to three elements deep and were in moderate to poor condition. They were species identified as alder, ash, with lesser amounts of hazel, holly and willow.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-161	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This site was located in the industrial peatlands of Lough Bannow Bog. It was recorded in the 2013 Re-assessment Peatland Survey as a togher exposed in the drain face. The elements were two to three layers deep (Whitaker 2014). A single cutting was opened and excavated under licence 15E0207. The site was situated in poorly decomposed Sphagnum peat with Phragmites and Menyanthes inclusions. It was dated to cal. 2859-2497 BC (UBA 26641).

The site (L3.7m, W0.9-3m) was composed mainly of longitudinally-laid, roughly-shaped alder, ash and holly roundwood and heavy brushwood elements oriented E-W. Towards the centre of the cutting a light hazel brushwood hurdle panel (L1.25m, W0.65m) was located between two longitudinal roundwoods . There were six E-W orientated hazel and alder brushwood sails arranged in pairs, with tightly placed N-S orientated rods. The majority of the elements had intact bark present. A single E-W orientated roundwood continued into the W baulk. Three sondages were excavated 1m to the W of the cutting, and revealed several roundwood and brushwood elements.

Most elements were in fairly poor condition and included some forked branch pieces. Several elements had toolmarked ends with mainly concave facets.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-162	Platform peatland	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This site was located in the industrial peatlands of Lough Bannow Bog. It was recorded in the 2013 Re-assessment Peatland Survey as a togher exposed in section in the drain face 0.28m below the field surface. The elements were closely placed (Whitaker 2014).

A single cutting was opened and excavated under licence 15E0211. The site was situated in Sphagnum peat with Phragmites and Menyanthes inclusions. It was dated to 2857-2492 BC (UBA 26647). The excavation revealed a collection of NE-SW orientated hazel brushwood elements (L0.09-1.54m), with a single alder roundwood and single hazel peg. Within the cutting the deposit was 1.65 x 0.7m in size, although it was also visible in section in the opposing drain face which gives a minimum length of 3m.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-163	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description : This site was located in the industrial peatlands of Lough Bannow Bog. It was recorded in the 2013 Re-assessment Peatland Survey as a togher visible in the drain face 0.13m below the field surface. The elements were sparsely laid over an area 2.08m in width. There were no additional sightings in the drains to the east or west (Whitaker 2014).

A single cutting was opened and excavated under licence 15E0208. The site was overlain by moderately decomposed Sphagnum peat and underlain by fen peat. It was dated cal. 2618-2469 BC (UBA 26643). The excavated structure was composed of a series of longitudinally laid roundwoods (L3.05-6.03m). The composition of the site varied along its length. At the E extent of the cutting were six sparsely placed E-W orientated roundwoods. The central part of the site consisted of five shorter longitudinal roundwoods, whose W extent was supported by two parallel transverse roundwoods. To the E of the transverses, the site consisted of a single longitudinal roundwood that stopped 0.9m short of the western drain edge. Five of the elements had toolmarked ends, three wedge and two chisel points. All had multiple concave or dished facets. The roundwoods were species identified as alder, ash, elm and hazel.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-164	Road - class 3 togher	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Derryadd Wind Farm - EIAR

Description : This site was located in the industrial peatlands of Lough Bannow Bog. It was recorded in the 2013 Re-assessment Peatland Survey as a roundwood and brushwood togher, located on the field surface near the drain edge, and was traced for a length of 2.9m(Whitaker 2014).

A single cutting was opened and excavated under licence 15E0210. The site was situated in poorly humified Sphagnum peat with sedge and root inclusions. It was dated cal. 2456-2137 BC (UBA 26645). The excavated site (W0.81-1.9m) was orientated ENE-WSW. It was composed of machine-damaged longitudinally-laid ash, alder and willow roundwood and birch brushwood elements with transverse supports and two shallow pegs. All elements were fractured along their lengths and were in poor condition. Only three elements had toolmarked ends consisting of two wedge and a chisel point. The facets were flat to slightly concave. There were several root bowls within the cutting along the margins of the site.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-165	Redundant record	605187,768553	205237,268534	YES

DESCRIPTION

Description This site was located in the industrial peatlands of Lough Bannow Bog. It was recorded in the 2013 Re-assessment Peatland Survey as a togher. The site consisted of longitudinal brushwood, oriented NE-SW, and was exposed on the field surface. The elements were tightly packed to the NE of the sighting, and less densely packed to the W. The elements were moderately preserved with the smaller elements frequently broken (Whitaker 2014). The site was dated to cal. 1495-1304 BC (UBA 26642).

The original sighting was relocated by GPS and an area measuring 3m x 4m was cleaned by hand (licence 15E0206), but no remains of the site were noted during the course of the 2015 excavation season.

SMR	CLASS	ITM Easting, ITM Northing	Irish Grid Easting, Irish Grid Northing	Inclusion in next SMR
LF018-166	Redundant record	605187,768553	205237,268534	YES

DESCRIPTION

Yes

Description This site is located in the industrial peatlands of Lough Bannow Bog. The 2013 Reassessment Peatland Survey recorded it as a SW-NE oriented brushwood and roundwood togher, located on the surface of two fields (Whitaker 2014). A date of cal. 1195-997 BC was returned from a piece of hazel brushwood. Further excavation was not deemed needed.